

Plan of:	Metford Rehabilitation Domain Areas	Location:	Metford Clay Mine Metford Rd, Metford NSW 2320	Source:	Contours updated by GPS 22/5/07 Boundaries Monteath & Powys	Our Ref:	V:\Jobs_MT\2013\ClosurePlan\Figs\ CPMOPMT.cdr
Figure:	Nine (MT13A)	Council:	Maitland City Council	Survey:	AAM Hatch 27/2/06	Plan By:	LGT
Sheet:	1 of 1	Tenures:	ML 1523, 4589, 875, 2843, 5848, 4865, 5090	Projection:	MGA	Project Manager:	GVT
Version/Date:	A 26/03/2014	Client:	CSR Building Products Ltd	Contour Interval:	1m	Office:	Thornton



Legend							
Domain A 	Disturbed floor and stockpiles. <u>Action:</u> Fill in low lying areas with stockpile materials, shape to self-drain and apply grasses.	Domain C 	Natural steep face with good vegetation. <u>Action:</u> Risk assess to potentially leave	Domain E 	The Hill- mix of natural and carbonaceous shale stockpiles, vegetated. <u>Action:</u> None	Domain G 	Mixed revegetated land and shallow water bodies. <u>Action:</u> Build access tracks for potential pedestrian use.
Domain B 	Construction & Demolition batter with some vegetation and some steep slopes. <u>Action:</u> Survey, batter back slopes to 3:1 with available material, apply grasses to disturbed faces.	Domain D 	Vegetated bund wall atop steep natural slope. <u>Action:</u> Use existing stockpiles, batter face to 3:1, apply grasses.	Domain F 	Mostly revegetated with some aggregate stockpiles. <u>Action:</u> Pick out aggregates and apply grasses to disturbed areas	Domain H 	Natural <u>Action:</u> None
						Lime 	Lime stockpile <u>Action:</u> Lime will be mixed with soil to assist with revegetation.