

Appendix A

DRAWINGS BY COSTIN ROE CONSULTING

GENERAL NOTES:

- 1. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS' DRAWINGS AND SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK.
2. ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE RELEVANT AND CURRENT STANDARDS AUSTRALIA CODES AND WITH THE BY-LAWS AND ORDINANCES OF THE RELEVANT BUILDING AUTHORITIES EXCEPT WHERE VARIED BY THE PROJECT SPECIFICATION.
3. ALL DIMENSIONS SHOWN SHALL BE VERIFIED BY THE BUILDER ON SITE. ENGINEER'S DRAWINGS SHALL NOT BE SCALED FOR DIMENSIONS. ENGINEER'S DRAWINGS ISSUED IN ANY ELECTRONIC FORMAT MUST NOT BE USED FOR DIMENSIONAL SETOUT. REFER TO THE ARCHITECT'S DRAWINGS FOR ALL DIMENSIONAL SETOUT INFORMATION. DURING CONSTRUCTION THE STRUCTURE SHALL BE MAINTAINED IN A STABLE CONDITION AND NO PART SHALL BE OVERSTRESSED. TEMPORARY BRACING SHALL BE PROVIDED BY THE BUILDER TO KEEP THE WORKS AND EXCAVATIONS STABLE AT ALL TIMES. UNLESS NOTED OTHERWISE ALL LEVELS ARE IN METRES AND ALL DIMENSIONS ARE IN MILLIMETRES.
4. ALL WORKS SHALL BE UNDERTAKEN IN ACCORDANCE WITH ACCEPTABLE SAFETY STANDARDS & APPROPRIATE SAFETY SIGNS SHALL BE INSTALLED AT ALL TIMES DURING THE PROGRESS OF THE JOB.

SURVEY NOTE:

- 1. EXISTING SITE LEVELS AND DETAILS BASED ON A PLAN OF SURVEY '11019-001' BY 'BOXALL SURVEYORS PTY. LTD.' DATED 23.07.2020.

SITE PREPARATION NOTES:

- 1. ALL EARTHWORKS SHALL BE COMPLETED GENERALLY IN ACCORDANCE WITH THE GUIDELINES SPECIFIED BY THE GEOTECHNICAL REPORT 'PSM3959-004L' PROVIDED BY PSM DATED 17.10.2019.
2. EXISTING LEVELS ARE BASED ON INFORMATION PROVIDED BY BOXALL SURVEYORS TITLED 11019-001 DATED 23.07.2020.
3. STRIP ANY TOP SOIL OR DELETERIOUS MATERIAL AND DISPOSE OF FROM SITE OR STORE AS DIRECTED.
4. COMPLETE CUT TO FILL EARTHWORKS TO ACHIEVE THE REQUIRED LEVELS AS INDICATED ON THE DRAWINGS WITHIN A TOLERANCE OF +0mm/-10mm THROUGH BUILDING PADS/PAVEMENTS AND +0mm/-20mm ELSEWHERE.
5. PREPARE STEEP BATTERS TO RECEIVE FILL BY CONSTRUCTING BENCHING TO FACILITATE FILL PLACEMENT AND COMPACTION.
6. AREAS TO RECEIVE FILL (THAT ARE NOT ON BENCHED BATTERS) AND AREAS IN CUT SHALL BE PROFF ROLLED TO IDENTIFY ANY SOFT HEAVING MATERIAL. SOFT MATERIAL SHALL BE BOXED OUT AND REMOVED PRIOR TO FILL PLACEMENT. PROFF ROLLING TO BE INSPECTED BY A GEOTECHNICAL ENGINEER OR THE EARTHWORKS DESIGNER.
7. SITE WON FILL SHALL BE COMPACTED IN MAXIMUM 300mm LAYERS AND TO DRY OR HALF DENSITY RATIOS (STANDARD COMPACTION) OF BETWEEN 98% AND 103%. THE PLACEMENT MOISTURE VARIATION OR HALF MOISTURE VARIATION SHALL BE CONTROLLED TO BE BETWEEN 2% DRY AND 2% WET.
8. IMPORTED FILL SHALL BE COMPACTED IN MAXIMUM 300mm LAYERS AND TO DRY OR HALF DENSITY RATIOS (STANDARD COMPACTION) OF BETWEEN 98% AND 103%. THE PLACEMENT MOISTURE VARIATION OR HALF MOISTURE VARIATION SHALL BE CONTROLLED TO BE BETWEEN 2% DRY AND 2% WET.
9. ALL ENGINEERED FILL PARTICLES SHALL BE ABLE TO BE INCORPORATED WITHIN A SINGLE LAYER. FURTHER, LESS THAN 30% OF PARTICLES SHALL BE RETAINED ON THE 37.5 mm SIEVE. ENGINEERED FILL SHALL BE ABLE TO BE TESTED IN ACCORDANCE WITH THE STANDARD COMPACTION METHOD (AS1289.5.4.1) OR HALF TEST METHOD (AS1289.5.7.1). THESE METHODS REQUIRE LESS THAN 20% RETAINED ON THE 37.5 mm SIEVE. WHERE BETWEEN 20% AND 30% OF PARTICLES ARE RETAINED ON THE 37.5 mm SIEVE THE ABOVE TEST METHODS SHALL STILL BE ADOPTED AND TEST REPORTS ANNOTATED APPROPRIATELY. THESE REQUIREMENTS SHOULD BE MET BY THE MATERIAL AFTER PLACEMENT AND COMPACTION.
10. ALL THE EARTHWORKS UNDERTAKEN AND THE SUBGRADE CONDITION IN THE CUT AREAS (IN THE STATED PERIOD) ARE DOCUMENTED IN THE REPORTS AND HAVE BEEN UNDERTAKEN IN ACCORDANCE WITH THE SPECIFICATION (EG. COSTIN ROE SITE PREPARATION NOTES IN DWG C01402100-DA100)
11. PRIOR TO ANY EARTHWORKS, EROSION CONTROL AS OUTLINED IN THE EROSION AND SEDIMENTATION CONTROL PLAN SHALL BE COMPLETED.
12. EXISTING ROCK, IF ANY, SHALL BE REMOVED BY HEAVY ROCK BREAKING OR RIPPING. MATCH EXISTING LEVELS AT BATTER INTERFACE.
13. CONTRACTOR TO MATCH EXISTING LEVELS AT THE INTERFACE OF EARTHWORKS AND EXISTING SURFACE AT BATTER LOCATIONS OR WHERE NO RETAINING WALLS ARE PRESENT. ANY DISCREPANCY BETWEEN DESIGN AND EXISTING LEVELS TO BE REFERRED TO THE ENGINEER FOR DIRECTION OR ADJUSTMENTS TO DESIGN LEVELS.
14. DURING EARTHWORKS THE CONTRACTOR IS TO ENSURE ALL AREAS ARE FREE DRAINING & WILL NOT RETAIN WATER DURING RAINFALL. PROVIDE TEMPORARY MEASURES AS REQUIRED TO ENSURE FREE FLOWING RUNOFF THROUGH MANAGED DRAINAGE PATHS, DIVERSION DRAINS OR OTHER SUITABLE DISPOSAL METHOD AS AGREED DURING THE WORKS. REFER ANY CONCERNS TO THE ENGINEER. REFER TO EROSION AND SEDIMENT CONTROL DRAWINGS AND NOTES.

ELECTRONIC INFORMATION NOTES:

- 1. THE ISSUED DRAWINGS IN HARD COPY OR PDF FORMAT TAKE PRECEDENCE OVER ANY ELECTRONICALLY ISSUED INFORMATION, LAYOUTS OR DESIGN MODELS.
2. THE CONTRACTOR'S DIRECT AMENDMENT OR MANIPULATION OF THE DATA OR INFORMATION THAT MIGHT BE CONTAINED WITHIN AN ENGINEER-SUPPLIED DIGITAL TERRAIN MODEL AND ITS SUBSEQUENT USE TO UNDERTAKE THE WORKS WILL BE SOLELY AT THE DISCRETION OF AND THE RISK OF THE CONTRACTOR.
3. THE CONTRACTOR IS REQUIRED TO HIGHLIGHT ANY DISCREPANCIES BETWEEN THE DIGITAL TERRAIN MODEL AND INFORMATION PROVIDED IN THE CONTRACT AND/OR DRAWINGS AND IS REQUIRED TO SEEK CLARIFICATION FROM THE SUPERINTENDENT.
4. THE ENGINEER WILL NOT BE LIABLE OR RESPONSIBLE FOR THE POSSIBLE ON-GOING NEED TO UPDATE THE DIGITAL TERRAIN MODEL, SHOULD THERE BE ANY AMENDMENTS OR CHANGES TO THE DRAWINGS OR CONTRACT INITIATED BY THE CONTRACTOR.

EROSION CONTROL NOTES:

ALL CONTROL WORK INCLUDING DIVERSION BANKS AND CATCH DRAINS, V-DRAINS AND SILT FENCES SHALL BE COMPLETED DIRECTLY FOLLOWING THE COMPLETION OF THE EARTHWORKS.

- 1. SILT FENCES AND SILT FENCE RETURNS SHALL BE ERECTED CONVEX TO THE CONTOUR TO POND WATER.
2. HAY BALE BARRIERS AND GEOTEXTILE FENCES ARE TO BE CONSTRUCTED TO TOE OF BATTER, PRIOR TO COMMENCEMENT OF EARTHWORKS, IMMEDIATELY AFTER CLEARING OF VEGETATION AND BEFORE REMOVAL OF TOP SOIL.
3. ALL TEMPORARY EARTH BERMS, DIVERSION AND SILT DAM EMBANKMENTS ARE TO BE MACHINE COMPACTED, SEEDED AND MULCHED FOR TEMPORARY VEGETATION COVER AS SOON AS THEY HAVE BEEN FORMED.
4. CLEAR WATER IS TO BE DIVERTED AWAY FROM DISTURBED GROUND AND INTO THE DRAINAGE SYSTEM.
5. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND PROVIDING ON GOING ADJUSTMENT TO EROSION CONTROL MEASURES AS REQUIRED DURING CONSTRUCTION. ALL SEDIMENT TRAPPING STRUCTURES AND DEVICES ARE TO BE INSPECTED AFTER STORMS FOR STRUCTURAL DAMAGE OR CLOGGING, TRAPPED MATERIAL IS TO BE REMOVED TO A SAFE, APPROVED LOCATION.
7. ALL FINAL EROSION PREVENTION MEASURES INCLUDING THE ESTABLISHMENT OF GRASSING ARE TO BE MAINTAINED UNTIL THE END OF THE DEFECTS LIABILITY PERIOD.
8. ALL EARTHWORKS AREAS SHALL BE ROLLED ON A REGULAR BASIS TO SEAL THE EARTHWORKS.
9. ALL FILL AREAS ARE TO BE LEFT WITH A BUND AT THE TOP OF THE SLOPE AT THE END OF EACH DAY'S EARTHWORKS. THE HEIGHT OF THE BUND SHALL BE A MINIMUM OF 200mm. ALL CUT AND FILL SLOPES ARE TO BE SEEDED AND HYDROMULCHED WITHIN 10 DAYS OF COMPLETION OF FORMATION.
11. AFTER REVEGETATION OF THE SITE IS COMPLETE AND THE SITE IS STABLE IN THE OPINION OF A SUITABLY QUALIFIED PERSON ALL TEMPORARY WORK SUCH AS SILT FENCE, DIVERSION DRAINS ETC SHALL BE REMOVED.
12. ALL TOPSOIL STOCKPILES ARE TO BE SUITABLY COVERED TO THE SATISFACTION OF THE SITE MANAGER TO PREVENT WIND AND WATER EROSION.
13. ANY AREA THAT IS NOT APPROVED BY THE CONTRACT ADMINISTRATOR FOR CLEARING OR DISTURBANCE BY THE CONTRACTOR'S ACTIVITIES SHALL BE CLEARLY MARKED AND SIGN POSTED, FENCED OFF OR OTHERWISE APPROPRIATELY PROTECTED AGAINST ANY SUCH DISTURBANCE.
14. ALL STOCKPILE SITES SHALL BE SITUATED IN AREAS APPROVED FOR SUCH USE BY THE SITE MANAGER. A 6m BUFFER ZONE SHALL EXIST BETWEEN STOCKPILE SITES AND ANY STREAM OR FLOW PATH. ALL STOCKPILES SHALL BE ADEQUATELY PROTECTED FROM EROSION AND CONTAMINATION OF THE SURROUNDING AREA BY USE OF THE MEASURES APPROVED IN THE EROSION AND SEDIMENTATION CONTROL PLAN. ACCESS AND EXIT AREAS SHALL INCLUDE SHAKE-DOWN OR OTHER METHODS APPROVED BY THE SITE MANAGER FOR THE REMOVAL OF SOIL MATERIALS FROM MOTOR VEHICLES.
16. THE CONTRACTOR IS TO ENSURE RUNOFF FROM ALL AREAS WHERE THE NATURAL SURFACE IS DISTURBED BY CONSTRUCTION, INCLUDING ACCESS ROADS, DEPOT AND STOCKPILE SITES, SHALL BE FREE OF POLLUTANTS BEFORE IT IS EITHER DISPERSED TO STABLE AREAS OR DIRECTED TO NATURAL WATERCOURSES.
17. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN SLOPES, CROWNS AND DRAINS ON ALL EXCAVATIONS AND EMBANKMENTS TO ENSURE SATISFACTORY DRAINAGE AT ALL TIMES WATER SHALL NOT BE ALLOWED TO POND ON THE WORKS UNLESS SUCH PONDING IS PART OF AN APPROVED ESCP / SWMP.

EXISTING SERVICES NOTES:

- 1. DURING THE EXECUTION OF WORKS, THE CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF EXISTING SERVICES. THE CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED TO THE EXISTING SERVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE RELEVANT SERVICE AUTHORITY, AT NO COST TO THE PRINCIPAL.
2. WHERE IT IS NECESSARY TO REMOVE, DIVERT OR CUT INTO ANY EXISTING SERVICE, THE CONTRACTOR SHALL GIVE AT LEAST THREE (3) DAYS NOTICE OF ITS REQUIREMENTS TO THE SUPERINTENDENT, WHO WILL ADVISE WHAT ARRANGEMENTS SHOULD BE MADE FOR THE ALTERATION OF SUCH EXISTING SERVICES. EXISTING SERVICES HAVE BEEN PLOTTED FROM SUPPLIED DATA. THE ACCURACY IS NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ESTABLISH THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO COMMENCING WORK. ALL CLEARANCES AND APPROVALS SHALL ALSO BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY PRIOR TO THE COMMENCEMENT OF WORK.
4. ALL NEW AND EXHUMED SERVICES THAT CROSS EXISTING AND FUTURE ROADS/PAVEMENTS WITHIN THE SITE SHALL BE BACKFILLED WITH DGB20 MATERIAL TO SUBGRADE LEVEL AND COMPACTED TO 98% STANDARD DENSITY RATIO. SUBJECT TO PRIOR APPROVAL FROM RELEVANT AUTHORITY.
5. ON COMPLETION OF SERVICES INSTALLATION, ALL DISTURBED AREAS SHALL BE RESTORED TO ORIGINAL, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AREAS, GRASSED AREAS AND ROAD PAVEMENTS.
6. CARE TO BE TAKEN WHEN EXCAVATING NEAR UTILITY SERVICES. NO MECHANICAL EXCAVATION TO BE UNDERTAKEN OVER SERVICES. LIAISE WITH RELEVANT AUTHORITY.
7. THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION AND REMOVAL IF REQUIRED OF ALL EXISTING SERVICES IN AREAS AFFECTED BY THE WORKS WITHIN THE CONTRACT AREA AS SHOWN ON THE DRAWINGS UNLESS DIRECTED OTHERWISE BY THE SUPERINTENDENT. ALL TO REGULATORY AUTHORITY STANDARDS AND APPROVAL.
8. THE CONTRACTOR IS TO MAINTAIN EXISTING STORMWATER DRAINAGE FLOWS THROUGH THE ROADS AT ALL TIMES. MAKE DUE ALLOWANCE FOR ALL SUCH FLOWS AT ALL TIMES. PRIOR TO COMMENCEMENT OF ANY WORKS THE CONTRACTOR SHALL OBTAIN THE SUPERINTENDENT'S APPROVAL OF THE PROGRAM FOR THE RELOCATION/CONSTRUCTION OF TEMPORARY SERVICES.
10. CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES AS REQUIRED TO MAINTAIN EXISTING SUPPLY TO BUILDINGS REMAINING IN OPERATION DURING WORKS TO THE SATISFACTION AND APPROVAL OF THE SUPERINTENDENT. ONCE DIVERSION IS COMPLETE AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND MAKE GOOD TO THE SATISFACTION OF THE SUPERINTENDENT.
11. INTERRUPTION TO SUPPLY OF EXISTING SERVICES SHALL BE DONE SO AS NOT TO CAUSE ANY INCONVENIENCE OR DAMAGE TO THE ADJACENT RESIDENCES. CONTRACTOR TO GAIN APPROVAL OF THE SUPERINTENDENT FOR TIME OF INTERRUPTION.
12. THE CONTRACTOR SHALL UNDERTAKE A DIAL BEFORE YOU DIG (DBYD 1100) SERVICES SEARCH BEFORE THE COMMENCEMENT OF ANY WORKS.

TRAFFIC CONTROL NOTES:

- 1. TRAFFIC CONTROLS TO COMPLY WITH AS 1742.3-2002
2. TRAFFIC CONTROL PLANS TO BE SUBMITTED AND CERTIFIED BY AN ACCREDITED WORK SITE OPERATIVE.
3. AS PART OF THE TRAFFIC CONTROL PLAN ENSURE THAT PEDESTRIANS ARE CATERED FOR.
4. AFTER-HOURS TRAFFIC CONTROL THROUGH THE WORKSITE HAVE TO BE CATERED FOR.

PCC NOTES:

ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH PENRITH CITY COUNCIL STANDARDS AND SPECIFICATIONS.

STORMWATER DRAINAGE NOTES:

- 1. ALL STORMWATER WORKS TO BE COMPLETED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS3500.3:2003 PLUMBING AND DRAINAGE, PART 3: STORMWATER DRAINAGE.
2. THE MINOR (PIPED) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 20 YEAR ARI STORM EVENT AND THE MAJOR (OVERLAND) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 100 YEAR ARI STORM EVENT.
3. PIT SIZES SHALL BE AS INDICATED IN THE SCHEDULE WHILE PIPE SIZES AND DETAILS ARE PROVIDED ON PLAN.
4. EXISTING STORMWATER PIT LOCATIONS AND INVERT LEVELS TO BE CONFIRMED BY SURVEY PRIOR TO COMMENCING WORKS ON SITE.
5. ALL STORMWATER PIPES Ø375 OR GREATER SHALL BE CLASS 2 (WITH HS2 SUPPORT) REINFORCED CONCRETE WITH RUBBER RING JOINTS UNLESS NOTED OTHERWISE.
6. ALL PIPES UP TO AND INCLUDING Ø300 TO BE uPVC GRADE S88 UNO.
7. PIPE CLASS NOMINATED ARE FOR IN-SERVICE LOADING CONDITIONS ONLY. CONTRACTOR IS TO MAKE ANY NECESSARY ADJUSTMENTS REQUIRED FOR CONSTRUCTION CONDITIONS.
8. ALL CONCRETE PITS GREATER THAN 1000mm DEEP SHALL BE REINFORCED USING N12-200 EACH WAY CENTERED IN WALL AND BASE. LAP MINIMUM 300mm WHERE REQUIRED. ALL CONCRETE FOR PITS SHALL BE F'c=25 MPa. PRECAST PITS MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
9. IN ADDITION TO ITEM 9 ABOVE, ALL CONCRETE PITS GREATER THAN 3000mm DEEP SHALL HAVE WALLS AND BASE THICKNESS INCREASED TO 200mm. PIPES SHALL BE LAID AS PER PIPE LAYING DETAILS. PARTICULAR CARE SHALL BE TAKEN TO ENSURE THAT THE PIPE IS FULLY AND EVENLY SUPPORTED. RAM AND PACK FILLING AROUND AND UNDER BACK OF PIPES AND PIPE FAUCETS, WITH NARROW EDGED RAMMERS OR OTHER SUITABLE TAMPING DETAILS.
11. CONCRETE PIPES UNDER, OR WITHIN THE ZONE OF INFLUENCE OF PAVED AREAS SHALL BE LAID USING HS2 TYPE SUPPORT, AS A MINIMUM, IN ACCORDANCE WITH AS 3725. AGGREGATE BACKFILL SHALL NOT BE USED FOR PIPE BEDDING AND OR HAUNCH/SIDE SUPPORT.
12. WHERE PIPE LINES ENTER PITS, PROVIDE 2m LENGTH OF STOCKING WRAPPED SLOTTED Ø100 uPVC TO EACH SIDE OF PIPE.
13. ALL SUBSOIL DRAINAGE LINES SHALL BE Ø100 SLOTTED uPVC WITH APPROVED FILTER WRAP LAID IN 300mm WIDE GRANULAR FILTER UNLESS NOTED OTHERWISE. LAY SUBSOIL LINES TO MATCH FALLS OF LAND AND/OR 1 IN 200 MINIMUM. PROVIDE CAPPED CLEANING EYE (RODDING POINT) AT UPSTREAM END OF LINE AND AT 30m MAX. CTS. PROVIDE SUBSOIL LINES TO ALL PAVEMENT/ LANDSCAPED INTERFACES, TO REAR OF RETAINING WALLS (AS NOMINATED BY STRUCTURAL ENGINEER) AND AS SHOWN ON PLAN.
14. ALL PIPE GRADES 1 IN 200 MINIMUM UNO.
15. PROVIDE STEP IRONS IN PITS DEEPER THAN 1000mm.
16. MIN. 600 COVER TO PIPE OVERT BENEATH ROADS & MIN. 400 COVER BENEATH LANDSCAPED AND PEDESTRIAN AREAS.
17. PIT COVERS IN TRAFFICABLE PAVEMENT SHALL BE CLASS D 'HEAVY DUTY', THOSE LOCATED IN NON-TRAFFICABLE AREAS SHALL BE CLASS B 'MEDIUM DUTY' U.N.O. PROVIDE CLEANING EYES (RODDING POINTS) TO PIPES AT ALL CORNERS AND T-JUNCTIONS WHERE NO PITS ARE PRESENT.
18. DOWN PIPES (DP) TO BE AS PER HYDRAULIC ENGINEERS DETAILS WITH CONNECTOR TO MATCH DP SIZE U.N.O. ON PLAN. PROVIDE CLEANING EYE AT GROUND LEVEL. PIPE LENGTHS NOMINATED ON PLAN OR LONGSECTIONS ARE MEASURED FROM CENTER OF PITS TO THE NEAREST 0.5m AND DO NOT REPRESENT ACTUAL LENGTH. THE CONTRACTOR IS TO ALLOW FOR THIS.

FINISHED LEVELS PLAN NOTES:

- 1. LEVELS DATUM IS AUSTRALIAN HEIGHT DATUM (A.H.D.).
2. GRADING REQUIREMENTS TO BE COMPLETED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS2890.1, AS2890.2 AND AS2890.6.
3. ALL CONTOUR LINES & SPOT LEVELS INDICATE FINISHED PAVEMENT LEVELS U.N.O. ON PLAN. CONTOUR INTERVALS
• THE MINOR CONTOUR INTERVAL IS 0.1m.
• THE MAJOR CONTOUR INTERVAL IS 0.5m.
5. HARDSTAND GRADING
• MINIMUM PAVEMENT GRADE IS TO BE 1:100 (1%).
• GRADING OF ON-GRADE DOCKS TO BE 1:100 (1%) FALL AWAY FROM THE DOCK FACE FOR A LENGTH OF 15m U.N.O.
• GRADING OF TRUCK CIRCULATION ZONES TO BE MINIMUM AS NOTED ABOVE, 3-4% NOMINAL AND MAX. 5%.
6. CAR PARKING AREA GRADES
• MINIMUM PAVEMENT GRADE IS TO BE 1:100 (1%), DESIRABLE MINIMUM GRADE 1:50 (2%).
• MAXIMUM PAVEMENT GRADE IS TO BE 1:20 (5%) IN CARPARKING AREAS AND 1:25 (4%) ELSEWHERE.
• DISABLED ACCESS PARKING ZONES AND SHARED SPACE TO BE MAXIMUM OF 1:33 (3%) IN ASPHALT PAVEMENT AND MAXIMUM OF 1:40 (2.5%) IN CONCRETE PAVEMENT.
• CARPARK RAMP GRADES TO BE MAX 1:5 WITH 2.5m SMOOTH TRANSITION AT TOP AND BOTTOM U.N.O.
7. TRUCK RAMP GRADES
• MAXIMUM B-DOUBLE OR 19.0m AV RAMP GRADES ARE TO BE 1:8.3 (12%) U.N.O. ON PLAN
• PROVIDE MINIMUM 4.0m LONG TRANSITION WHERE CHANGES OF GRADE EXCEED 1:20 (5%) AT A CREST U.N.O.
• PROVIDE MINIMUM 3.0m LONG TRANSITION WHERE CHANGE OF GRADE EXCEED 1:20 (5%) AT A SAC U.N.O.
• TRANSITIONS ARE TO PROVIDE A SMOOTH CONTINUOUS CIRCULAR AND TANGENTIAL CHANGE IN GRADE TO ENSURE NO SHARP OR ACUTE CHANGES IN GRADE ARE PRESENT.
8. WHERE FIRE BRIGADE ACCESS IS REQUIRED, MAXIMUM RAMP GRADIENTS ARE TO BE 1:6 (16.6%). DESIRABLE RAMP GRADIENTS ARE TO BE 1:8 (12.5%) WITH 7m TRANSITION TOP AND BOTTOM U.N.O. ON PLAN.
9. PERMANENT BATTER SLOPES ARE TO HAVE A MAXIMUM GRADE OF 1V:3H U.N.O. BASED ON GEOTECHNICAL ASSESSMENT. PROVIDE MINIMUM 0.5m BERM BETWEEN THE BACK OF KERB OR PAVEMENT EDGES AND THE TOP OR TOE OF A BATTER.
10. ALL BATTER SLOPE WITH GRADES AT OR EXCEEDING 1V:6H ARE TO BE TURFED IMMEDIATELY OR APPROPRIATE EROSION CONTROL IS TO BE PROVIDED TO THE SATISFACTION OF THE ENGINEER.
11. ALL FOOTPATHS ARE TO FALL AWAY FROM THE BUILDING AT 2.5% NOMINAL GRADE.
12. ALL PAVEMENTS ARE TO BE SET AT 30mm BELOW THE FINISHED FLOOR LEVEL OF THE WAREHOUSE AND OFFICE AREAS. PROVIDE LOCAL FEATHERING AT DOORWAYS OR ROLLER SHUTTERS TO PROVIDE FLUSH FINISH AS REQUIRED.
13. WHERE NEW AND EXISTING INTERFACING IS REQUIRED, MATCH EXISTING LEVELS AND PROVIDE SMOOTH INTERFACE BETWEEN NEW AND EXISTING GRADIENTS. REFER ANY CONCERNS TO THE ENGINEER.

REINFORCED EARTH RETAINING WALL NOTES:


- 1. ALL COMPONENTS AND INSTALLATION SHALL COMPLY WITH AS4678 AND THE STANDARDS REFERRED TO THEREIN.
2. MINIMUM HEIGHT (H) TO GEOGRID REINFORCEMENT LENGTH (L) TO BE 1:0.
3. MINIMUM BEARING CAPACITY OF FOUNDATION (BASED ON MINIMUM H/L RATIO OF 1:0) TO BE AS FOLLOWS:
a. H MAX. 2.0m = 100 kPa
b. H MAX. 3.5m = 150 kPa
c. H MAX. 5.0m = 200 kPa
BEFORE COMMENCEMENT OF CONSTRUCTION THE FOUNDATION SHALL BE INSPECTED AND VERIFIED BY A QUALIFIED GEOTECHNICAL ENGINEER.
4. WHERE MINIMUM BEARING IS NOT ACHIEVABLE OR NOT MEETING DESIGN REQUIREMENT, THE FOUNDATION MATERIAL IS TO BE EXCAVATED AND REPLACED WITH APPROVED MATERIAL PLACED IN ACCORDANCE WITH THE FILLING SPECIFICATION TO A MINIMUM COMPACTION OF 100% SMD AND PLACED WITHIN 2% OF OMC.
5. MINIMUM SURCHARGE LOADS TO BE APPLIED AS FOLLOWS U.N.O. ON PLAN:
a. LIVE LOAD = 20 kPa
b. DEAD LOAD = 5 kPa
c. CONSTRUCTION TRAFFIC LIVE LOAD = 10 kPa
6. THE GEOGRIDS SHALL BE OF THE TYPE AND INDEX STRENGTH NOMINATED ON THE DRAWINGS. THE MINIMUM GEOGRIDS SHALL BE A SINGLE LENGTH IN THE DIRECTION OF DESIGN TENSION, NOT LAPPED, MAKING PROVISION FOR CONNECTION TO THE FACING ACROSS THE WHOLE WIDTH OF THE FACING AND PROVIDING FOR THE SPECIFIED ANCHORAGE WITHIN THE DESIGNATED ANCHORAGE ZONE. GEOGRIDS SHALL COVER THE WHOLE OF THE PLAN AREA BEHIND THE WALL FOR THE SPECIFIED ANCHORAGE LENGTH AND SHALL BE LAPPED WITH ADJACENT SECTIONS IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
7. MINIMUM WALL EMBEDMENT AT THE TOE OF THE WALL TO BE 300mm.
8. DESIGN LIFE OF STRUCTURE IS TO BE 100 YEARS.
9. SELECT BACKFILL MATERIAL WITHIN THE REINFORCED SOIL BLOCK SHALL BE SOUND GRANULAR MATERIAL OF NATURAL OR INDUSTRIAL ORIGIN, NON-EXPANSIVE, FREE FROM ORGANIC OR OTHER DELETERIOUS MATERIAL CONFORMING TO THE PHYSICAL, CHEMICAL AND ELECTROCHEMICAL LIMITS AS SPECIFIED AND SHALL NOT BE SUBJECT TO BREAKDOWN UNDER COMPACTION. THE SELECT BACKFILL MATERIAL IS TO HAVE THE FOLLOWING PARAMETERS:
a. MINIMUM INTERNAL FRICTION, Ø = 34°
b. EFFECTIVE COHESION, C' = 0 kPa
c. UNIT WEIGHT = 21 kN/m³
d. PH BETWEEN 4 AND 9.
10. SELECT BACKFILL IS TO BE PLACED AND COMPACTED IN LAYERS NOT MORE THAN 300mm (LOOSE) COMPACTION TO NOT LESS THAN 100% SMD WILL BE ACHIEVED AND MATERIAL PLACED WITHIN 2% OF OMC. DENSITY TESTING SHALL BE PERFORMED IN EACH COMPACTED LIFT IN ACCORDANCE WITH AS3198.
11. PROVIDE A DRAINAGE LAYER DIRECTLY BEHIND THE FACING UNITS IN A MINIMUM 300mm WIDE 12-20mm AGGREGATE LAYER. FACING UNIT VOIDS TO BE FILLED WITH AGGREGATE. PROVIDE 100mm MINIMUM AG. DRAIN IN GEOTEXTILE SOCK AT TOE OF WALL FACING AND CONNECT TO DRAINAGE SYSTEM AT 30m MAX. SPACING.
12. THE NEED FOR A CHIMNEY DRAIN OR DRAINAGE AT THE REAR OF THE MASS SOIL BLOCK IS TO BE CONFIRMED ON SITE BY THE GEOTECHNICAL ENGINEER AND DESIGNER FOLLOWING PREPARATION OF THE FOUNDATION AND PRIOR TO CONSTRUCTION OF THE MASS SOIL BLOCK.
13. CONSTRUCTION EQUIPMENT WEIGHING MORE THAN 500KG STATIC WEIGHT IS TO BE KEPT BACK 15m FROM THE REAR FACE OF THE WALL FACING UNITS. COMPACTION OF THE SELECT FILL MATERIAL WITHIN THE 15m STRIP ADJACENT TO THE WALL SHALL BE ACHIEVED BY LIGHT MECHANICAL TAMPERS (VIBRATING PLATE, TRENCH COMPACTOR OR SIMILAR) TO GIVE THE SAME DENSITY AS IN THE REMAINDER OF THE SELECT FILL.
14. ALL DESIGN AND CONSTRUCT WALL SYSTEM TO BE COMPLETED IN ACCORDANCE WITH THESE NOTES.
15. TOP OF WALL HEIGHTS ARE NOTED TO ALIGN WITH FINISHED PAVEMENT HEIGHTS. THE CONTRACTOR AND THEIR DESIGN AND CONSTRUCT WALLING CONTRACTORS ARE TO ENSURE THAT ALL WALL STRAPS ARE INSTALLED BELOW THE DESIGN EARTHWORKS SUBGRADE. CONTRACTOR TO ALLOW FOR WALL STRAPS TO BE GRADED AWAY FROM THE FACE OF THE WALL OR OTHERWISE INSTALLED TO SUIT EARTHWORKS DESIGN LEVELS AND GRADES.

DIFFERENTIAL SETTLEMENT NOTE:

FUTURE BUILDING AND SERVICE DESIGNERS TO CONSIDER DIFFERENTIAL SETTLEMENT OF REINFORCED EARTH WALL BLOCK AND GENERAL FILL AREAS. PARTICULAR ATTENTION TO BE DRAWN TO HEAVILY LOADED AREAS, OR DIFFERING LOADED AREAS (INCLUDING SPRINKLER TANK AND TRUCK PAVEMENT AREAS) AND WHERE SIGNIFICANT CHANGES IN OVERALL WALL HEIGHT OR FILL AMOUNTS ARE EXPERIENCED. IT IS THE RESPONSIBILITY OF THE FUTURE DESIGNERS TO ENSURE APPROPRIATE DESIGN CONSIDERATION TO DIFFERENTIAL SETTLEMENT ARE MADE DEPENDING ON THE DESIGN ELEMENT AND INTERACTION WITH RETAINED ELEMENTS AND GENERAL FILL MATERIAL.

RETAINING WALL NOTES:

- 1. ALL COMPONENTS AND INSTALLATION SHALL COMPLY WITH AS4678 AND THE STANDARDS REFERRED TO THEREIN.
2. MINIMUM BEARING CAPACITY OF FOUNDATION TO BE AS FOLLOWS:
a. H MAX. 2.0m = 100 kPa
b. H MAX. 3.5m = 150 kPa
c. H MAX. 5.0m = 200 kPa
BEFORE COMMENCEMENT OF CONSTRUCTION THE FOUNDATION SHALL BE INSPECTED AND VERIFIED BY A QUALIFIED GEOTECHNICAL ENGINEER.
3. WHERE MINIMUM BEARING IS NOT ACHIEVABLE OR NOT MEETING DESIGN REQUIREMENT, THE FOUNDATION MATERIAL IS TO BE EXCAVATED AND REPLACED WITH APPROVED MATERIAL PLACED IN ACCORDANCE WITH THE FILLING SPECIFICATION TO A MINIMUM COMPACTION OF 100% SMD AND PLACED WITHIN 2% OF OMC.
4. MINIMUM SURCHARGE LOADS TO BE APPLIED AS FOLLOWS U.N.O.
5. ON PLAN:
a. LIVE LOAD = 20 kPa
b. DEAD LOAD = 5 kPa
c. CONSTRUCTION TRAFFIC LIVE LOAD = 10 kPa
6. MINIMUM WALL EMBEDMENT AT THE TOE OF THE WALL TO BE 300mm MINIMUM UNLESS NOTED OTHERWISE.
7. DESIGN LIFE OF STRUCTURE IS TO BE 100 YEARS.
8. TIED WALLS ARE TO BE TEMPORARILY PROPPED AT TOP UNTIL SUCH TIME THE TOP OF WALL IS TIED TO THE SLAB AND 28-DAY CONCRETE STRENGTH HAS BEEN ACHIEVED.
9. CONSTRUCTION EQUIPMENT WEIGHING MORE THAN 500KG STATIC WEIGHT IS TO BE KEPT BACK 15m FROM THE REAR FACE OF THE WALL FACING UNITS. COMPACTION OF THE SELECT FILL MATERIAL WITHIN THE 15m STRIP ADJACENT TO THE WALL SHALL BE ACHIEVED BY LIGHT MECHANICAL TAMPERS (VIBRATING PLATE, TRENCH COMPACTOR OR SIMILAR) TO GIVE THE SAME DENSITY AS IN THE REMAINDER OF THE SELECT FILL.
10. ALL DESIGN AND CONSTRUCT WALL SYSTEMS TO BE COMPLETED IN ACCORDANCE WITH THESE NOTES.



POND DEWATERING NOTES:

- DRAIN PONDS OF WATER & DISCHARGE CLEAN WATER TO STORMWATER DRAINAGE SYSTEM (AS PER NOTES 2 & 3) - REFER TO STORMWATER PLAN FOR LOCATIONS.
- DEWATERING TO BE PERFORMED IN SUCH A MANNER AS TO REMOVE CLEAN WATER WITHOUT REMOVING OR DISTURBING SILT, SEDIMENT OR OTHER ORGANIC MATERIAL FROM THE BASE OF THE PONDS.
- DISCHARGE OF WATER FROM PONDS TO HAVE A PH RANGE OF 6.5-8.5 AND TSS < 50mg/L. PONDS TO BE DOSED WITH GYPSUM (APPROX. 30mg PER CUBIC METRE) TO ACCELERATE SETTLEMENT OF SUSPENDED SOLIDS.
- REMOVE ALL SILT, ORGANIC AND WATER LOGGED MATERIAL FROM BASE OF POND (NOM. DEPTH 0.5-1.0m) AND DISPOSE OF IN ACCORDANCE WITH THE ACCEPTABLE PRACTICE.
- EXPOSE NATURAL SITE SOILS AND COMPACT SUBGRADE IN ACCORDANCE WITH THE SITE PREPARATION NOTES (REFER DRG. DA10) REMOVING ANY SOFT ZONES AS REQ'D.
- PLACE AND COMPACT FILL AS PER SITE PREPARATION NOTES ON DRAWING C110.
- INFORMATION PROVIDED ON THIS DRAWING SHALL BE USED TO GUIDE THE DEVELOPMENT OF THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN THAT SHALL BE IMPLEMENTED DURING CONSTRUCTION.

STAGED CONSTRUCTION NOTE:

STAGE 1 - INITIAL SITE ESTABLISHMENT AND INSTALLATION OF SEDIMENT & EROSION CONTROL MEASURES AS NOTED ON PLAN. REFER TO DRAWING C013874.06-SSDA200

STAGE 2 - MAJORITY OF STORMWATER INFRASTRUCTURE COMPLETED, PADS BENCHED & RETAINING WALLS CONSTRUCTED. STORMWATER FROM DEVELOPED LOTS DIVERTED TO RETENTION BASIN. STORMWATER FROM UNDEVELOPED PADS DIVERTED TO SEDIMENT BASINS. REFER TO DRAWING C013874.06-SSDA201

NOTE:

REFER TO DRAWING DA10 FOR ALL EROSION AND SEDIMENT CONTROL NOTES.

SEDIMENTATION BASIN NOTE:

FOR SEDIMENT & EROSION CONTROL DETAILS REFER TO DRAWING C013874.06-SSDA250.

SEDIMENTATION BASIN SIZING BASED ON RECOMMENDATIONS OF 'SOILS AND CONSTRUCTION, MANAGING URBAN STORMWATER-THE BLUE BOOK'. CAPACITY BASED UPON 5 DAY RAINFALL DEPTH AT 80th PERCENTILE INTENSITY (32.2mm).

APPROXIMATE AREA OF DISTURBED SITE = 19.88ha


SEDIMENTATION BASINS TO COLLECT RUN-OFF IN EXTREME RAINFALL EVENTS. COLLECTED RUN-OFF TO BE ASSESSED BY A QUALIFIED LABORATORY FOR DOUSING RATES OF ALUM OR GYPSUM TO ENSURE COAGULATION OF SEDIMENTS PRIOR TO WATER BEING DISCHARGED TO COUNCIL STORMWATER SYSTEM.

EACH BASIN IS TO HAVE A MARKER PLACED AS PER THE DETAIL TO INDICATE WHEN SEDIMENT IS TO BE REMOVED. REMOVED SEDIMENT IS TO BE CLASSED AND DEWATERED PRIOR TO REMOVAL FROM SITE.

ALLOWANCE TO BE MADE DURING BENCHING OF SITE TO ENSURE RUN-OFF IS DIRECTED TO SEDIMENTATION BASINS.


NOTES:

- ASSUME TYPE D SOIL (CLAY/SILTY CLAY)
- ASSUME GROUP D SOIL (HIGH PLASTICITY AND SHRINK/SWELL PROPERTIES)




SEDIMENT BASIN DIMENSIONS

Basin	Catchment Area	Required Basin Volume	Base Dimension (LxB)	Top Dimension (LxB)	Max Side Slope	Depth	Provided Basin Volume
Sediment Basin 1	15.0ha	5040m ³	76.0m x 38.0m	85.0m x 37.0m	1V:3H	1.5m	5140m ³
Sediment Basin 2	8.72ha	2930m ³	69.0m x 23.0m	78.0m x 32.0m	1V:3H	1.5m	3037m ³
Sediment Basin 3	7.74ha	2601m ³	54.0m x 27.0m	63.0m x 36.0m	1V:3H	1.5m	2772m ³



BASIN 1

OVERFLOW TO EXISTING FLOW PATH SUBJECT TO WORKS ON MIRVAC SITE. NOTE STAGE 2 EROSION AND SEDIMENT CONTROL FOR FINAL OVERFLOW LOCATION.



SEDIMENT BASIN DIMENSIONS

<p>SEDIMENT BASIN 1: CATCHMENT AREA = 4.00ha REQUIRED BASIN VOLUME = 859m³ BASE DIMENSION (LxB) = 20.0m x 11.0m TOP DIMENSION (LxB) = 32.0m x 23.0m MAX SIDE SLOPE = 1V:3H DEPTH = 2.0m PROVIDED BASIN VOLUME = 906m³</p>	<p>SEDIMENT BASIN 2: CATCHMENT AREA = 4.45ha REQUIRED BASIN VOLUME = 956m³ BASE DIMENSION (LxB) = 20.0m x 12.5m TOP DIMENSION (LxB) = 32.0m x 24.5m MAX SIDE SLOPE = 1V:3H DEPTH = 2.0m PROVIDED BASIN VOLUME = 985m³</p>	<p>SEDIMENT BASIN 3: CATCHMENT AREA = 7.19ha REQUIRED BASIN VOLUME = 1545m³ BASE DIMENSION (LxB) = 30.0m x 16.0m TOP DIMENSION (LxB) = 42.0m x 28.0m MAX SIDE SLOPE = 1V:3H DEPTH = 2.0m PROVIDED BASIN VOLUME = 1605m³</p>	<p>SEDIMENT BASIN 4: CATCHMENT AREA = 7.60ha REQUIRED BASIN VOLUME = 1635m³ BASE DIMENSION (LxB) = 32.5m x 15.0m TOP DIMENSION (LxB) = 44.5m x 27.0m MAX SIDE SLOPE = 1V:3H DEPTH = 2.0m PROVIDED BASIN VOLUME = 1635m³</p>	<p>SEDIMENT BASIN 5: CATCHMENT AREA = 6.04ha REQUIRED BASIN VOLUME = 1297m³ BASE DIMENSION (LxB) = 25.0m x 15.0m TOP DIMENSION (LxB) = 37.0m x 27.0m MAX SIDE SLOPE = 1V:3H DEPTH = 2.0m PROVIDED BASIN VOLUME = 1325m³</p>	<p>SEDIMENT BASIN 6: CATCHMENT AREA = 155ha REQUIRED BASIN VOLUME = 375m³ BASE DIMENSION (LxB) = 10.0m x 5.0m TOP DIMENSION (LxB) = 22.0m x 17.0m MAX SIDE SLOPE = 1V:3H DEPTH = 2.0m PROVIDED BASIN VOLUME = 375m³</p>	<p>SEDIMENT BASIN 7: CATCHMENT AREA = 2.57ha REQUIRED BASIN VOLUME = 550m³ BASE DIMENSION (LxB) = 15.0m x 7.0m TOP DIMENSION (LxB) = 27.0m x 19.0m MAX SIDE SLOPE = 1V:3H DEPTH = 2.0m PROVIDED BASIN VOLUME = 565m³</p>
---	---	---	---	---	---	--

SEDIMENTATION BASIN NOTE:

FOR SEDIMENT & EROSION CONTROL DETAILS REFER TO DRAWING C013874.06-SSDA250.

SEDIMENTATION BASIN SIZING BASED ON RECOMMENDATIONS OF 'SOILS AND CONSTRUCTION, MANAGING URBAN STORMWATER - THE BLUE BOOK'. CAPACITY BASED UPON 5 DAY RAINFALL DEPTH AT 80TH PERCENTILE INTENSITY (32.2mm).

APPROXIMATE AREA OF DISTURBED SITE = 19.88ha

SEDIMENTATION BASINS TO COLLECT RUN-OFF IN EXTREME RAINFALL EVENTS. COLLECTED RUN-OFF TO BE ASSESSED BY A QUALIFIED LABORATORY FOR DOUSING RATES OF ALUM OR GYPSUM TO ENSURE COAGULATION OF SEDIMENTS PRIOR TO WATER BEING DISCHARGED TO COUNCIL STORMWATER SYSTEM.

EACH BASIN IS TO HAVE A MARKER PLACED AS PER THE DETAIL TO INDICATE WHEN SEDIMENT IS TO BE REMOVED. REMOVED SEDIMENT IS TO BE CLASSED AND DEWATERED PRIOR TO REMOVAL FROM SITE.

ALLOWANCE TO BE MADE DURING BENCHING OF SITE TO ENSURE RUN-OFF IS DIRECTED TO SEDIMENTATION BASINS.

NOTES:

1. ASSUME TYPE D SOIL (CLAY/SILTY CLAY)
2. ASSUME GROUP D SOIL (HIGH PLASTICITY AND SHRINK/SWELL PROPERTIES)

NOTE:

REFER TO DRAWING DA110 FOR ALL EROSION AND SEDIMENT CONTROL NOTES

LEGEND:


- - - DENOTES SITE BOUNDARY
- - - DENOTES DIVERSION DRAIN
- - - DENOTES CATCHMENT BOUNDARY
- - - DENOTES SILT FENCE WITH CATCH DRAIN
- - - DENOTES SILT FENCE ONLY
- ▣ DENOTES CONSTRUCTION ENTRY

STAGED CONSTRUCTION NOTE:

STAGE 1 - INITIAL SITE ESTABLISHMENT AND INSTALLATION OF SEDIMENT & EROSION CONTROL MEASURES AS NOTED ON PLAN. REFER TO DRAWING C013874.06-SSDA200


STAGE 2 - MAJORITY OF STORMWATER INFRASTRUCTURE COMPLETED, PADS BENCHED & RETAINING WALLS CONSTRUCTED. STORMWATER FROM DEVELOPED LOTS DIVERTED TO RETENTION BASIN. STORMWATER FROM UNDEVELOPED PADS DIVERTED TO SEDIMENT BASINS. REFER TO DRAWING C013874.06-SSDA201

EROSION AND SEDIMENT CONTROL PLAN - STAGE 2
 SCALE 1:1000




FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION


<p>REVISOR</p> <p>ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION</p> <p>ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION</p>	<p>07.04.22</p> <p>06.04.22</p> <p>21.06.21</p> <p>24.05.21</p>	<p>D</p> <p>C</p> <p>B</p> <p>A</p>	<p>ARCHITECT</p> <p>SBA ARCHITECTS</p> <p>112-118/2000 STAMFORD STREET, NORTH SYDNEY NSW 2060</p> <p>PH: (02) 9550-8888 FAX: (02) 9550-8889</p> <p>www.sba.com.au</p>	<p>CLIENT</p> <p>GPT The GPT Group</p>	<p>PROJECT</p> <p>YIRIBANA LOGISTICS ESTATE</p> <p>754-770 & 784-786 MAMRE ROAD</p> <p>KEMPS CREEK NSW</p>	<p>CONSULTANT</p> <p>Costin Roe Consulting Pty Ltd.</p> <p>Consulting Engineers</p> <p>Level 1, 8 Windmill Street</p> <p>Wahbi Bay, Sydney NSW 2000</p> <p>Tel: (02) 9551-7999 Fax: (02) 9541-3721</p> <p>email: mail@costinroe.com.au</p>	<p>PRECISION COMMUNICATION ACCOUNTABILITY</p>	<p>DRAWING TITLE</p> <p>EROSION AND SEDIMENT CONTROL PLAN</p> <p>STAGE 2</p> <p>DRAWING No. C013874.06-SSDA201</p> <p>ISSUE D</p>
--	---	-------------------------------------	--	---	--	--	---	---



SILT FENCE WITH STRAW BALE DETAIL
N.T.S.




TYPICAL SILT FENCE DETAIL
N.T.S.
PROVIDE 1m RETURNS AT 30m INTERVALS.
TYPICAL




TYPICAL STOCKPILE DETAIL
N.T.S.

- STOCKPILE NOTES**
1. PLACE ALL STOCKPILES IN LOCATIONS MORE THAN 5m FROM EXISTING VEGETATION, ROADS & HAZARD AREAS.
 2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT ELONGATED MOUNDS. SIDE SLOPE TO BE 1 V : 2 H MAX.
 3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT.
 4. WHERE STOCKPILES ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE USING WOOD CHIP MULCH - 16 TONNE/Ha
 5. CONSTRUCT SILT FENCE WITH CATCH DRAIN ON UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES & SILT FENCE ONLY 1 TO 2m DOWNSLOPE AS SHOWN.




SEDIMENT STORAGE MARKER
SCALE 1:20


- NOTES:**
- ALL EROSION & SEDIMENT CONTROL MEASURES TO BE INSPECTED & MAINTAINED DAILY BY SITE MANAGER.
- MINIMISE DISTURBED AREAS.
- ROADS & FOOTPATHS TO BE SWEEP DAILY.
- 12m TURF TO BE PLACED BEHIND KERBS.
- DUST MINIMISATION CONTROL BY WATERING TO BE IMPLEMENTED BY SITE MANAGER AS REQUIRED OR AS DIRECTED BY THE EPA.




TYPE 1 DIVERSION DRAIN SECTION
SCALE 1:20




TYPE 2 DIVERSION DRAIN SECTION
SCALE 1:20




TYPE 3 DIVERSION DRAIN SECTION
SCALE 1:20



TYPE 4 DIVERSION DRAIN SECTION
SCALE 1:20




SECTION 1:20
1
SSDA20




TYPICAL SEDIMENT CONTROL POND PLAN
SCALE 1:250

SPILLWAY DETAIL & SCHEDULE

CATCHMENT (Ha)	FLOW (m ³ /s)	WIDTH (mm)	FLOW DEPTH (mm)	ROCK SIZE (mm)	BUND HEIGHT ABOVE SPILLWAY (mm)
0.20	0.14	1000	200	-	600
0.5	0.2	2000	200	-	600
1	0.3	2000	200	-	700
2	0.6	4000	200	-	700
5	1.4	5000	300	200	800
10	2.8	8000	350	200	850
20	5.5	14000	400	250	900
40	11.0	20000	500	250	1000



TYPICAL SEDIMENT CONTROL BASIN SECTION
SCALE 1:50



FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION

REVISION	DATE	ISSUE
REVISED FOR RIS SUBMISSION	06.04.22	D
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	01.04.21	C
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	21.05.21	B
ISSUED FOR PRELIMINARY ONLY	09.04.21	A

AMENDMENTS	DATE	ISSUE

ARCHITECT

SBA
ARCHITECTS

112-1000 BIRRO
112-1000 BIRRO
112-1000 BIRRO

CLIENT

GPT
The GPT Group

PROJECT

YIRIBANA LOGISTICS ESTATE
754-770 & 784-786 MAMRE ROAD
KEMPS CREEK NSW

DESIGNED: DS
DRAWN: JB
DATE: APRIL '21
CHECKED: DS
SCALE: AS SHOWN

CONSULTANT

Costin Roe Consulting Pty Ltd.
Consulting Engineers

Level 1, 8 Widdowall Street
Wahia Bay, Sydney NSW 2000
Tel: (02) 8551-7899 Fax: (02) 8541-3721
email: mail@costinroe.com.au

Costin Roe Consulting


PRECISION | COMMUNICATION | ACCOUNTABILITY

DRAWING TITLE

EROSION AND SEDIMENT CONTROL DETAILS

DRAWING No. C013874.06-SSDA250

ISSUE D



LEGEND

NOTE:
LEVELS DATUM IS AHD.
ALL LEVELS ARE ±1000 mm

- - - - - EXISTING CONTOUR
- - - - - B.E.L. CONTOUR (MAJOR 10m)
- - - - - B.E.L. CONTOUR (MINOR 0.25m)

PAVEMENT FFL
BASE/SUBBASE COURSES
SUBGRADE

DEPTH OF PAVEMENT. REFER TO STRUCTURAL PLANS FOR DETAILS.

NOMINATED B.E. LEVEL

NOMINATED B.E.L. DETAIL
N.T.S.

ADJACENT PROPERTY LEVELS NOTE:

FUTURE DEVELOPMENT LEVELS FOR NEIGHBOURING PROPERTIES TO NORTH AND EAST NOT CURRENTLY KNOWN. INTERFACING CURRENTLY SHOWN ON PLAN IS TO EXISTING LEVELS. FINAL INTERFACING ARRANGEMENT SUBJECT TO FURTHER DISCUSSION & COORDINATION WITH ADJOINING LANDOWNERS/DEVELOPERS.

LEVELS NOTE:

LEVELS SHOWN TO BE ±1000mm FROM THOSE SHOWN FINAL LEVELS SUBJECT TO FINAL GEOTECHNICAL INVESTIGATIONS, ARCHITECTURAL LAYOUT AND ACHIEVING A CUT TO FILL EARTHWORKS BALANCE OVER THE PROPERTY.

MIRVAC SITE
ANTICIPATED PAD LEVELS AS SHOWN
SITE LAYOUT PER MIRVAC SSDA_10448 EIS

DEPTH RANGE			
No.	FROM DEPTH	TO DEPTH	DEPTH RANGE VOLUME
1	-18.000	-16.000	44m
2	-16.000	-14.000	2222m
3	-14.000	-12.000	7802m
4	-12.000	-10.000	15344m
5	-10.000	-8.000	25120m
6	-8.000	-6.000	38872m
7	-6.000	-4.000	60199m
8	-4.000	-2.000	101518m
9	-2.000	0.000	176985m
10	0.000	2.000	342971m
11	2.000	4.000	167543m
12	4.000	6.000	53626m
13	6.000	8.000	15454m
14	8.000	10.000	1426m

EARTHWORKS VOLUMES
SITE AREA = 33.1 Ha


TOPSOIL STRIP (200 mm) = (- 66,200 m³)
CUT MATERIAL = - 432,100 m³
FILL MATERIAL = + 542,500 m³

DETAILED EXCAVATION (2,000m³/Ha OVER 33.1 Ha) = - 66,200 m³

BALANCE = + 44,200 m³

NOTE:
EARTHWORKS VALUES ARE APPROXIMATE ONLY.
NO ALLOWANCE HAS BEEN MADE IN THE ABOVE VOLUMES FOR EROSION & SEDIMENT CONTROL BACKFILLING, BULKING OR COMPACTION OF FILLED SOILS, THE REMOVAL OF UNCONTROLLED OR CONTAMINATED MATERIAL, TEMPORARY DRAINAGE SWALES WITHIN BUILDING PADS, OR ANY OTHER UNSPECIFIED EXCAVATION RELATED TO WAREHOUSE CONSTRUCTION.

BULK EARTHWORKS PLAN
SCALE 1:1000



FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION

ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	DATE	ISSUE	AMENDMENTS
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	07.04.22	F	
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	06.04.22	E	
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	01.06.21	D	
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	21.05.21	C	
ISSUED FOR PRELIMINARY ONLY	15.04.21	B	
ISSUED FOR PRELIMINARY ONLY	09.04.21	A	

ARCHITECT

120-122 North Street, North Sydney NSW 2060
Tel: (02) 9550-8888 Fax: (02) 9550-8889
www.sba.com.au

CLIENT

PROJECT

YIRIBANA LOGISTICS ESTATE
754-770 & 784-786 MAMRE ROAD
KEMPS CREEK NSW

CONSULTANT

Costin Roe Consulting Pty Ltd.
Consulting Engineers
Level 1, 8 Widdowall Street
Wahia Bay, Sydney NSW 2000
Tel: (02) 8551-7889 Fax: (02) 8541-3728
email: mail@costinroec.com.au

PRECISION | COMMUNICATION | ACCOUNTABILITY





DRAWING TITLE

BULK EARTHWORKS PLAN


DRAWING NO: C013874.06-SSDA300

LEGEND:

- DENOTES BULK EARTHWORKS PROFILE
- DENOTES EXISTING PROFILE
- DENOTES AREA IN CUT
- DENOTES AREA IN FILL




FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION




PROJECT: YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW			ARCHITECT: SBA ARCHITECTS CLIENT: GPT The GPT Group			CONSULTING ENGINEERS: Costin Roe Consulting Pty Ltd. Level 1, 8 Widdowall Street, Walsh Bay, Sydney NSW 2000 Tel: (02) 8551-7899 Fax: (02) 8541-3728 email: mail@costinroe.com.au			DRAWING TITLE: BULK EARTHWORKS SECTIONS SHEET 1		
DESIGNED: [Name] DATE: APRIL '21 CHECKED: [Name] SCALE: AS SHOWN CAD REF: 018746-SSD4350			PRECISION COMMUNICATION ACCOUNTABILITY			DRAWING NO: C013874.06-SSD4350 ISSUE: C					

LEGEND:


- DENOTES BULK EARTHWORKS PROFILE
- - - DENOTES EXISTING PROFILE
- ▨ DENOTES AREA IN CUT
- ▩ DENOTES AREA IN FILL



SECTION 5
HORIZONTAL SCALE 1:1000
VERTICAL SCALE 1:200




SECTION 6
HORIZONTAL SCALE 1:1000
VERTICAL SCALE 1:200



FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION

REVISIONS ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION ISSUED FOR PRELIMINARY ONLY AMENDMENTS	06.04.22 01.04.21 21.05.21 09.04.21 DATE ISSUE AMENDMENTS DATE ISSUE AMENDMENTS	ARCHITECT 	CLIENT 	PROJECT YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	 Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Woodmill Street Walsh Bay, Sydney NSW 2000 Tel: (02) 9551-7899 Fax: (02) 9541-3721 email: mail@costinroe.com.au	DRAWING TITLE BULK EARTHWORKS SECTIONS SHEET 2	DRAWING No. C013874.06-SSDA351	ISSUE D
--	--	---------------	------------	---	---	--	-----------------------------------	------------



LEVELS NOTE:
 LEVELS SHOWN TO BE +/-1000mm FROM THOSE SHOWN.
 FINAL LEVELS SUBJECT TO FINAL GEOTECHNICAL INVESTIGATIONS, ARCHITECTURAL LAYOUT AND ACHIEVING A CUT TO FILL EARTHWORKS BALANCE OVER THE PROPERTY.


LEGEND:
 LEVELS DATUM IS AHD.

EXISTING SITE LEVELS AND DETAILS BASED ON A PLAN OF SURVEY 2019 DE-01 BY STATIKER 26/09/20.

---	50.00	FINISHED PAVEMENT CONTOUR (MAJOR) 0.5m INTERVALS
---	50.10	FINISHED PAVEMENT CONTOUR (MINOR) 0.1m INTERVALS
---	50.10	EXISTING ESTATE CONTOUR
---	SW	INFRASTRUCTURE DRAINAGE
---	FW	FUTURE SITE DRAINAGE
---	---	POST-DEVELOPMENT CATCHMENT
⊕		KIP, KERB INLET PIT
⊕		SGGP, SINGLE GRATED GULLY PIT
⊕		SJP, SEALED JUNCTION PIT

FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION

STORMWATER DRAINAGE MASTER PLAN
 SCALE 1:1000



REVISED FOR RIS SUBMISSION	06.04.22	F			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	01.06.21	E			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	26.05.21	D			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	24.05.21	C			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	21.05.21	B			
ISSUED FOR PRELIMINARY ONLY	09.04.21	A			
AMENDMENTS	DATE	ISSUE	AMENDMENTS	DATE	ISSUE
	07.04.22	G			

ARCHITECT **SBA ARCHITECTS**

CLIENT **GPT The GPT Group**


PROJECT **YIRIBANA LOGISTICS ESTATE**
 754-770 & 784-786 MAMRE ROAD
 KEMPS CREEK NSW

DESIGNED: [Signature] DATE: APRIL '21
 CHECKED: [Signature] DATE: []
 SIZE: A0 SCALE: AS SHOWN
 CAD REF: 018174-SSDA400

Costin Roe Consulting Pty Ltd.
 Consulting Engineers
 Level 1, 8 Widdowall Street
 Walsh Bay, Sydney NSW 2000
 Tel: (02) 9251-7889 Fax: (02) 9241-3721
 email: mail@costinroe.com.au

Costin Roe Consulting
 PRECISION | COMMUNICATION | ACCOUNTABILITY

DRAWING TITLE: **STORMWATER DRAINAGE MASTERPLAN**
 DRAWING No: **C013874.06-SSDA400** ISSUE: **G**




ROADWORKS STORMWATER DRAINAGE PLAN - ROAD 1
SCALE 1:250

LEGEND:
LEVELS DATUM IS AHD.

EXISTING SITE LEVELS AND DETAILS BASED ON A PLAN OF SURVEY 2019 DE-01 BY STATIKER 26/09/20.


---	50.00	FINISHED PAVEMENT CONTOUR (MAJOR) 0.5m INTERVALS	---	3m	INFRASTRUCTURE DRAINAGE
---	50.10	FINISHED PAVEMENT CONTOUR (MINOR) 0.1m INTERVALS	---	3m	FUTURE SITE DRAINAGE
---	50.10	EXISTING ESTATE CONTOUR	☐		KIP, KERB INLET PIT
			☐		SGGP, SINGLE GRATED GULLY PIT
			☐		SJP, SEALED JUNCTION PIT

LEVELS NOTE:
LEVELS SHOWN TO BE +/-1000mm FROM THOSE SHOWN. FINAL LEVELS SUBJECT TO FINAL GEOTECHNICAL INVESTIGATIONS, ARCHITECTURAL LAYOUT AND ACHIEVING A CUT TO FILL EARTHWORKS BALANCE OVER THE PROPERTY.



ROADWORKS STORMWATER DRAINAGE PLAN - ROAD 1
SCALE 1:250


FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION




<table border="1"> <tr> <td>REVISIONS</td> <td>DATE</td> <td>ISSUE</td> <td>AMENDMENTS</td> </tr> <tr> <td>REVISED FOR RIS SUBMISSION</td> <td>07.04.22</td> <td>B</td> <td></td> </tr> <tr> <td>REVISED FOR RIS SUBMISSION</td> <td>06.04.22</td> <td>A</td> <td></td> </tr> </table>	REVISIONS	DATE	ISSUE	AMENDMENTS	REVISED FOR RIS SUBMISSION	07.04.22	B		REVISED FOR RIS SUBMISSION	06.04.22	A		<table border="1"> <tr> <td>ARCHITECT</td> <td>CLIENT</td> <td>PROJECT</td> <td>DESIGNED</td> <td>CHECKED</td> <td>DATE</td> <td>SIZE</td> <td>SCALE</td> <td>CAD REF:</td> </tr> <tr> <td>SBA ARCHITECTS</td> <td>GPT The GPT Group</td> <td>YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW</td> <td>DS</td> <td>DS</td> <td>APRIL '21</td> <td>A0</td> <td>A5 SHOWN</td> <td>01874-NL-SSDA410</td> </tr> </table>	ARCHITECT	CLIENT	PROJECT	DESIGNED	CHECKED	DATE	SIZE	SCALE	CAD REF:	SBA ARCHITECTS	GPT The GPT Group	YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	DS	DS	APRIL '21	A0	A5 SHOWN	01874-NL-SSDA410	<table border="1"> <tr> <td>CONSULTING ENGINEERS</td> <td>PROJECT</td> <td>CLIENT</td> </tr> <tr> <td>Level 1, 8 Windmill Street Wahia Bay, Sydney NSW 2000 Tel: (02) 9551-7899 Fax: (02) 9541-3721 email: mail@costinroe.com.au</td> <td>YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW</td> <td>GPT The GPT Group</td> </tr> </table>	CONSULTING ENGINEERS	PROJECT	CLIENT	Level 1, 8 Windmill Street Wahia Bay, Sydney NSW 2000 Tel: (02) 9551-7899 Fax: (02) 9541-3721 email: mail@costinroe.com.au	YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	GPT The GPT Group	<table border="1"> <tr> <td>DRAWING TITLE</td> <td>ISSUE</td> </tr> <tr> <td>ROADWORKS STORMWATER DRAINAGE PLAN - SHEET 1</td> <td>B</td> </tr> </table>	DRAWING TITLE	ISSUE	ROADWORKS STORMWATER DRAINAGE PLAN - SHEET 1	B
REVISIONS	DATE	ISSUE	AMENDMENTS																																								
REVISED FOR RIS SUBMISSION	07.04.22	B																																									
REVISED FOR RIS SUBMISSION	06.04.22	A																																									
ARCHITECT	CLIENT	PROJECT	DESIGNED	CHECKED	DATE	SIZE	SCALE	CAD REF:																																			
SBA ARCHITECTS	GPT The GPT Group	YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	DS	DS	APRIL '21	A0	A5 SHOWN	01874-NL-SSDA410																																			
CONSULTING ENGINEERS	PROJECT	CLIENT																																									
Level 1, 8 Windmill Street Wahia Bay, Sydney NSW 2000 Tel: (02) 9551-7899 Fax: (02) 9541-3721 email: mail@costinroe.com.au	YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	GPT The GPT Group																																									
DRAWING TITLE	ISSUE																																										
ROADWORKS STORMWATER DRAINAGE PLAN - SHEET 1	B																																										

Costin Roe Consulting
PRECISION | COMMUNICATION | ACCOUNTABILITY

DRAWING TITLE: ROADWORKS STORMWATER DRAINAGE PLAN - SHEET 1
ISSUE: B
DRAWING NO: C013874.06-SSDA410



ROADWORKS STORMWATER DRAINAGE PLAN - ROAD 2
SCALE 1:250




ROADWORKS STORMWATER DRAINAGE PLAN - ROAD 2
SCALE 1:250

LEGEND:
LEVELS DATUM IS AHD.

EXISTING SITE LEVELS AND DETAILS BASED ON A PLAN OF SURVEY 20119 DE-01 BY STATIKER 26/09/20.

- 50.00 — FINISHED PAVEMENT CONTOUR (MAJOR) 0.5m INTERVALS
- 50.10 — FINISHED PAVEMENT CONTOUR (MINOR) 0.1m INTERVALS
- 50.10 — EXISTING ESTATE CONTOUR
- SW+ — INFRASTRUCTURE DRAINAGE
- SW+ — FUTURE SITE DRAINAGE
- ⊕ KIP, KERB INLET PIT
- ⊞ SGGP, SINGLE GRATED GULLY PIT
- ⊞ SJP, SEALED JUNCTION PIT

LEVELS NOTE:
LEVELS SHOWN TO BE +/-1000mm FROM THOSE SHOWN. FINAL LEVELS SUBJECT TO FINAL GEOTECHNICAL INVESTIGATIONS, ARCHITECTURAL LAYOUT AND ACHIEVING A CUT TO FILL EARTHWORKS BALANCE OVER THE PROPERTY.



FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION

AMENDMENTS	DATE	ISSUE	AMENDMENTS	DATE	ISSUE
REVISED FOR RIS SUBMISSION	07.04.22	D			
ISSUED FOR RIS SUBMISSION	06.04.22	C			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	21.05.21	B			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	21.05.21	A			

ARCHITECT	CLIENT	PROJECT
SBA ARCHITECTS Suite 102, 83 Mount Street, North Sydney NSW 2060 T: (02) 9550 5888 F: (02) 9550 8800 E: info@sba.com.au W: www.sba.com.au	GPT The GPT Group	YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW




DESIGNED	DRAWN	CHECKED	DATE	SCALE	CAD REF:
DS	DS	DS	APRIL '21	A0	01187L-N-SSDA411

PROJECT	CLIENT
YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Windmill Street Wahia Bay, Sydney NSW 2000 Tel: (02) 8551-7800 Fax: (02) 8541-3721 email: mail@costinroe.com.au


Costin Roe Consulting

PRECISION | COMMUNICATION | ACCOUNTABILITY




DRAWING TITLE	DRAWING No	ISSUE
ROADWORKS STORMWATER DRAINAGE PLAN - SHEET 2	C013874.06-SSDA411	D



FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION




REVISED FOR RIS SUBMISSION	07.04.22	E	ARCHITECT	SBA ARCHITECTS	CLIENT	GPT The GPT Group	PROJECT	YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	CONSULTANT	Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Windmill Street Wahia Bay, Sydney NSW 2000 Tel: (02) 8551-7899 Fax: (02) 8541-3728 email: mail@costinroe.com.au	DRAWING TITLE	ESTATE BASIN 1 PLAN	
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	06.04.22	D	DATE	ISSUE	DATE	ISSUE	DESIGNED	DRW/DS	CHECKED	DS	DATE	APRIL '21	
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	26.05.21	B	DATE	ISSUE	DATE	ISSUE	SIZE	A0	SCALE	AS SHOWN	CAD REF:	010817L-RL-SSDA431	
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	24.05.21	A	DATE	ISSUE	DATE	ISSUE	PRECISION	COMMUNICATION	ACCOUNTABILITY	DRAWING No	C013874.06-SSDA431	ISSUE	E



BASIN LOCATION ZONE
BASIN LOCATED WITH TEMPORARY OSD STORAGE WITHIN E2 CORRIDOR & WATERCOURSE IN ACCORDANCE WITH THE FINAL MAMRE ROAD PRECINCT DCP, SECTION 2.4, CONTROL 12-14.

- LEGEND:**
LEVELS DATUM IS AHD.
- EXISTING SITE LEVELS AND DETAILS BASED ON SURVEY INFORMATION PROVIDED BY BOXALL SURVEYORS (REF: 11017-001, DATED 23.07.2020)
- SGGP, SINGLE GRATED GULLY PIT
 - SJP, SEALED JUNCTION PIT
 - KIP, KERB INLET PIT
 - PROPOSED DRAINAGE LINE
 - FUTURE WAREHOUSE DRAINAGE LINE
 - LONG-TERM STORAGE TOP WATER LEVEL
 - 2 YEAR ARI TOP WATER LEVEL
 - 20 YEAR ARI TOP WATER LEVEL
 - 100 YEAR ARI TOP WATER LEVEL
 - OVERLAND FLOW DIRECTION
 - FINISHED PAVEMENT CONTOUR (MAJOR) 0.5m INTERVALS
 - FINISHED PAVEMENT CONTOUR (MINOR) 0.10m INTERVALS



AMENDMENTS	DATE	ISSUE	AMENDMENTS	DATE	ISSUE
REVISED FOR RIS SUBMISSION	07.04.22	D			
REVISED FOR RIS SUBMISSION	06.04.22	C			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	01.06.21	B			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION	24.05.21	A			

ARCHITECT	CLIENT	PROJECT	DRAWN	CHECKED	DATE	SCALE	SIZE	SCALE	DATE	SCALE
SBA ARCHITECTS	GPT The GPT Group	YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW	DS	DS	APRIL '21	A0	AS SHOWN	1:250	01/04/21	1:250

ESTATE BASIN 2 PLAN
SCALE 1:250

FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION

PROJECT: YIRIBANA LOGISTICS ESTATE
754-770 & 784-786 MAMRE ROAD
KEMPS CREEK NSW

DESIGNED: DS
DRAWN: DS
DATE: APRIL '21
CHECKED: DS
DATE: 01/04/21

SCALE: A0
SIZE: AS SHOWN

CAD REF: 010874-RL-SSDA432

Costin Roe Consulting Pty Ltd.
Consulting Engineers
Level 1, 8 Widdowall Street
Wahia Bay, Sydney NSW 2000
Tel: (02) 8551-7999 Fax: (02) 8541-3721
email: mail@costinroe.com.au

Costin Roe Consulting

PRECISION | COMMUNICATION | ACCOUNTABILITY

ESTATE BASIN 2 PLAN

DRAWING NO: C013874.06-SSDA432

ISSUE: D