
From: Fogerty, Benjamin <Benjamin.Fogerty@arcadis.com>
Sent: Wednesday, 9 October 2019 1:10 PM
To: Vinay Moorthy
Cc: Brian Mariotti; Stephen O'Hora; Matt Brindley; Das, Kakoli
Subject: RE: 18029_Wee Hur Gibbons St Floor plans_ Mech Coordination

Categories: 18029 Weehur Gibbons St

Hi Vinay,

Based on the question only asks about rooms, but see below expanded description to cover all rooms and corridors.

Mechanical Ventilation to each room:

Each room will be provided with mechanical ventilation through roof mounted fans, the fans will connect to ductwork risers which will reticulate down the building in the riser shaft located between each SOU bathroom. Each individual riser will provide outside air to two (2) SOU per level. The fans on the roof will be arranged to achieve separation clearances to all discharges. Rooms located on Mezzanine Ground and basement will be provided with outside air ducted from various locations on the façade, including rooms like the cinema, gym and basement rooms, where rooms are provided with exhaust, make-up air will be drawn from the adjacent corridors. The main corridors in the tower will be provided with ventilation from the façade located at the end of each corridor.

Kind Regards

Benjamin Fogerty

DJV Mechanical Engineer – Victoria Cross ISD

D. + 61 2 8907 9010 | M. + 61 435 526 993

E. Benjamin.fogerty@arcadis.com



The information contained in this e-mail is intended only for the person or entity to which it is addressed and may contain confidential and/or privileged material. If you are not the intended recipient of this e-mail, the use of this information or any disclosure, copying or distribution is prohibited and may be unlawful. If you received this in error, please contact the sender and delete the material from any computer.