

13-23 GIBBONS STREET, REDFERN

Environmental Wind Tunnel Test Re-Test of Modified Building Geometry

Prepared for:

The Trust Company (Australia) Ltd ATF WH Gibbons Trust
c/o Allen Jack + Cottier
79 Myrtle Street
CHIPPENDALE NSW 2008

SLR Ref: 610.18313-R08
Version No: -v2.0
November 2019



PREPARED BY

SLR Consulting Australia Pty Ltd
ABN 29 001 584 612
Grd Floor, 2 Lincoln Street
Lane Cove NSW 2066 Australia
(PO Box 176 Lane Cove NSW 1595 Australia)
T: +61 2 9427 8100
E: sydney@slrconsulting.com www.slrconsulting.com

BASIS OF REPORT

This report has been prepared by SLR Consulting Australia Pty Ltd with all reasonable skill, care and diligence, and taking account of the timescale and resources allocated to it by agreement with The Trust Company (Australia) Ltd ATF WH Gibbons Trust (the Client). Information reported herein is based on the interpretation of data collected, which has been accepted in good faith as being accurate and valid.

This report is for the exclusive use of the Client. No warranties or guarantees are expressed or should be inferred by any third parties. This report may not be relied upon by other parties without written consent from SLR

SLR disclaims any responsibility to the Client and others in respect of any matters outside the agreed scope of the work.

DOCUMENT CONTROL

Reference	Date	Prepared	Checked	Authorised
610.18313-R08-v2.0	19 November 2019	Dr Peter Georgiou	Dr Neihad Al-Khalidy	Dr Neihad Al-Khalidy
610.18313-R08-v1.0	4 November 2019	Dr Peter Georgiou	Dr Neihad Al-Khalidy	Dr Neihad Al-Khalidy

EXECUTIVE SUMMARY

SLR Consulting Pty Ltd (SLR) has been commissioned by Allen, Jack + Cottier, on behalf of The Trust Company (Australia) Ltd ATF WH Gibbons Trust, to assess the ground level wind environment around a proposed student village located at 13-23 Gibbons Street, Redfern.

In late 2018, an initial assessment was made via a Discrete Sensor Environmental Wind Tunnel Study whereby wind tunnel measurements were made to investigate wind conditions within and around the proposed development (simulated via a 1:400 scale model) at areas to be used by visitors and occupants of the development itself. The study was documented in:

- SLR Report 610.18313-R06-v1.0, *“13-23 Gibbons Street, Redfern – Environmental Wind Tunnel Test”*, December 2018.

Since that time, and following design changes to the bulk envelope of the building, a second Environmental Wind Study has been undertaken, again via wind tunnel testing, using architectural drawings dated September 2019. This second study included the following additional aspects:

- The second round of testing has included new assessment points on the nearest residential building to the south of the site, No.1 Margaret Street, Redfern, including its roof level terrace areas; and
- The re-testing has also included additional testing of a City of Sydney “DCP-Compliant” bulk envelope building form.

The proposed development is bounded by Gibbons Street to the west, Margaret Street to the south and William Lane to the east. It will comprise a basement level, a four-storey podium with external common areas at Levels 2, 3 and Level 4 (overlooking Gibbons Street), and a 14-storey upper component, providing for 419 student units on Levels 1 to 18.

Buildings surrounding site are a mix of low and medium-rise, including commercial, retail and residential buildings (several of similar height to the proposed development). Gibbons Street Reserve lies immediately to the west with Redfern train station to the north-northwest. There are a number of planned and approved future residential developments of similar height located immediately to the north of the proposed development, running between Gibbons Street and Regent Street. Sydney’s CBD area lies to the north and the proposed SSD Waterloo Precinct development to the south-southeast.

Redfern Wind Climate

The study has developed a site-specific statistical wind climate model based on long-term wind records obtained from nearby Bureau of Meteorology stations at Sydney Kingsford Smith Airport and Bankstown Airport. For Redfern, SLR has determined that local winds have characteristics very close to Sydney (KS) Airport compared to Bankstown Airport, given Redfern’s proximity to Sydney (KS) Airport and similar distance inland from the coastline. Key prevailing wind directions of interest are the northeast, southeast and south for summer and mainly west quadrant winds for winter.

Wind Acceptability Criteria

The present study has again adopted the so-called “Melbourne” criteria for assessment, currently referenced by many Australian Local Government Development Control Plans in relation to wind impact.

EXECUTIVE SUMMARY

In addition the present study has assessed the impact of the development with respect to the City of Sydney's understanding of the intent of RWUDP (Redfern-Waterloo Design Principles) with respect to wind conditions.

Built Environment Scenarios Assessed

The present study involved the testing of three built environment "scenarios":

- "Baseline" scenario: simulating the existing built environment (as of October 2019); and
- "Future-R" scenario: with the addition of the future proposed development.
- "Future-C" scenario: with the addition of a City of Sydney "Bulk Envelope Compliant" design.

All of the above scenarios included the proposed and approved future developments lying to the immediate north of the site.

"Baseline" (Existing) Wind Environment

With the existing built environment, a number of pedestrian areas in surrounding thoroughfares were found to lie above the adopted 16 m/s walking comfort criterion (but below the 23 m/s safety criterion). The testing showed some channelling of northerly and southerly winds along Gibbons Street and channelling of easterly and westerly winds along Margaret Street.

- Wind conditions predicted in the wind tunnel testing did not have the advantage of the mature and extensive vegetation and trees along some of the footpath areas of interest (in particular Gibbons Street) – refer **Figure 17**. These would have an ameliorating (ie sheltering) effect, in some cases significant, on local wind speeds; and throughout the year, provided they comprise evergreen species.

"Future" Wind Environment – Surrounding Pedestrian Footpath Areas

Ground level locations surrounding the site continue to have the potential to experience wind speeds above the adopted 16 m/s walking comfort criterion (but below the 23 m/s safety criterion).

- Again, the absence of the mature and extensive vegetation and trees along the footpath areas of interest in the testing is noted – refer **Figure 17**, with their associated ameliorating (ie sheltering) effect on Gibbons Street winds in particular.

Future-Revised & Future-Compliant Compared to 16 m/sec Walking Comfort

- For most of the locations where the Future-Revised Design peak annual gust was above 16 m/s, the peak annual gust remained above 16 m/s for the Future-Compliant Design
- There was one instance (Location 14) where the Future-Revised Design peak annual gust was above 16 m/s, and the peak annual gust was below 16 m/s for the Future-Compliant Design
- There were four instances (Locations 11, 12, 13 and 20) where the Future-Revised Design peak annual gust was below 16 m/s, and the peak annual gust was above 16 m/s for the Future-Compliant Design

On the basis of the above, it is concluded that the "Future-Revised" Design performs comparably, wind-wise, to the "Future-Compliant" Design and overall slightly better.

EXECUTIVE SUMMARY

Through Site Link

- Peak annual gusts within the Through Site Link for the “Future-Revised” Design are all below the 13 m/sec level.
- Peak annual gusts within the Through Site Link for the “Future-Compliant” Design are also below the 13 m/sec level except at Location 22 (14 m/s).

Observation:

- It is noted that wind conditions within the new Through Site Link were tested in the wind tunnel without the benefit of any of the landscaping, or the “Public Artwork Canopy” proposed for this area.

Podium Areas

The Level 2 Podium is significantly sheltered by the proposed development itself and the adjacent similar height building to the immediate north.

The proposed development’s Level 4 Podium has the potential to experience elevated wind conditions as windflow accelerates past the western façade of the proposed development’s high-rise component and is directed downwards as downwash and accelerated shear flow.

In the original (2018) tested model, this was most apparent at both the northwest and southwest corners of the Podium, especially at the southwest corner (peak predicted annual gust of 21 m/s). In the “Future-Revised (2019) model, considerable improvement has been achieved at the southwest corner where the peak predicted annual gust is now 15.5 m/s. Winds at the northwest corner remain the same as the original (2018) tested model.

Observation:

- Wind conditions on the new Podium were tested in the wind tunnel without the benefit of any of the landscaping already proposed for the Podium.
- It is also important to appreciate that, while the Podium has the potential to attract elevated winds from building floors above (downwash, etc), especially at the northwest corner, these winds are thereby prevented from generating the same impact at ground level locations immediately below. The Podium therefore plays a potentially important role in ameliorating ground level wind conditions in surrounding pedestrian areas.

No.1 Margaret Street Terrace Areas

Predicted peak annual gusts for the No.1 Margaret Street roof terrace test Locations 31-33 are (respectively):

- 11.5 m/s, 11.5 m/s and 15 m/s for the “Future-Revised” Design
- 10 m/s, 14 m/s and 17 m/s for the “Future-Compliant” Design

As for the ground level locations surrounding the site, it is concluded that the “Future-Revised” Design performs comparably, wind-wise, to the “Future-Compliant” Design and overall slightly better.

EXECUTIVE SUMMARY

Already Planned and Existing Wind Mitigation

The current round of wind tunnel testing did not include the following features, all of which would have had an ameliorating impact on local wind speeds:

- Vegetation and trees along Gibbons Street and the Gibbons Street Reserve - refer **Figure 17**;
- Extensive landscaping and pergolas planned for the Through Site Link – refer **Figure 2**;
- Additional trees for Margaret Street - refer **Figure 2**; and
- Extensive landscaping planned for the Level 4 Podium – refer **Figure 2**.

Current plans for the proposed development retain the existing landscaping along Gibbons Street and included a full perimeter awning along the development's western façade – refer **Figure 2**. It is also noted that the main Gibbons Street entry into the development comprises a recessed, double-door (ie "airlock") design. This feature and the western façade awning will ensure acceptable wind conditions at this location.

The wind tunnel testing showed that potentially high localised winds occur at selected ground level locations along both Gibbons Street and Margaret Street ("Baseline" and "Future" scenarios).

- It has been noted that these results were obtained in the absence of existing trees and landscaping
- Further, the "Future" results did not include the planned additional trees along Margaret Street.

We recommend retention of the existing awnings protecting ground level footpaths and all of the trees and landscaping, existing and planned.

Given the relatively low wind speeds predicted for the Through Site Link in the "Future-Revised" Design and the observation that this was in the absence of planned landscaping and the Public Artwork Canopy, no additional mitigation is recommended beyond that already planned.

Podium – Level 4

The wind tunnel testing showed that high localised winds occur at the northwest corner of the Level 4 Podium area facing west – refer **Figure 18**. This corner will be exposed to winds with both a horizontal and vertical component. As a result, wind mitigation here should include both horizontal protection (eg awnings, canopies, etc) and vertical protection (balustrades, vertical screens, landscaping, etc). Since the recent round of wind tunnel testing, the design of the Level 4 Podium external space has progressed with the addition of 1.8 m high balustrades and an extended pergola (3 m high), also shown **Figure 18**. These most recent design changes, along with the previously planned landscaping, would adequately address the wind issue identified for this northwest corner area of Level 4.

Addition Wind Mitigation Recommendations – Roof Level

It is almost certain, given the absence of nearby similar height buildings in some wind directions, that the Roof Level will experience elevated wind conditions, especially for stronger southerly and westerly winds, potentially requiring wind treatment beyond standard height (ie code-compliant) balustrades, if this area is to be used for public access usage (eg a Roof Garden).

EXECUTIVE SUMMARY

Such treatments might include a combination of both vertical screening (eg increased height solid balustrades, balustrades combined with planter boxes, etc) and horizontal screening to ensure all-year-round amenity, particularly for southerly and westerly winds.

The development drawings do not currently show any public access areas at Roof Level. Accordingly, no wind mitigation is recommended for these areas.

“Future-Revised” versus “Future-Compliant” Design

On the basis of the test results at all ground level locations and the new No.1 Margaret Street roof terrace test locations it has been concluded that

- On average, the “Future-Revised” Design performs comparably, wind-wise, to the “Future-Compliant” Design; and
- Taking into account predicted wind speed increases and decreases, the “Future-Revised” Design performs overall slightly better than the “Future-Compliant” Design.

Taking into account all of the above, it is believed that the proposed development
will comply with the adopted wind acceptability criteria
at all pedestrian and public access locations within and around the development.

CONTENTS

1	INTRODUCTION.....	10
1.1	Structure of the Report.....	10
2	DESCRIPTION OF THE PROPOSED DEVELOPMENT	11
2.1	Location of Development Site	11
2.2	Proposed Development Description.....	12
2.3	The Surrounding Built Environment	14
3	SYDNEY’S REGIONAL WIND CLIMATE	16
3.1	Seasonal Variations.....	16
3.2	Wind Exposure at the Site – the “Local” Wind Environment	16
4	WIND ACCEPTABILITY CRITERIA	17
4.1	The “Melbourne” Wind Criteria.....	17
5	DESIGN WIND SPEEDS	18
5.1	Methodology	18
5.2	Reference Height Wind Speeds	18
6	WIND TUNNEL TEST METHODOLOGY	19
6.1	Simulation of Natural Wind	19
6.2	Development Models and Proximity Model.....	20
6.3	Data Processing.....	23
6.4	Test Method – Sensor Locations.....	23
6.5	Sample Test Result.....	25
7	TEST RESULTS.....	26
7.1	Sensor Locations: Gibbons Street (west side) – (representative locations Fig.11).....	26
7.2	Sensor Locations: Gibbons Street (east side) - (representative locations Fig.12)	27
7.3	Sensor Locations: Margaret Street - (representative locations Fig.13)	28
7.4	Sensor Locations: Through Site Link - (representative locations Fig.14)	29
7.5	“Future” Locations - Podium Locations - (representative locations Fig.15)	30
7.6	Sensor Locations – No.1 Margaret Street Roof Terraces	31
8	OVERALL WIND IMPACT.....	32
8.1	Wind Impact Relative to Intended Usage.....	33
9	MITIGATION TREATMENT RECOMMENDATIONS	37

CONTENTS

9.1	Existing and Planned Wind Amelioration	37
9.2	Additional Wind Mitigation Recommendations	37
9.3	“Future-Revised” versus “Future-Compliant” Design.....	39
9.4	Areas Not Assessed Via Wind Tunnel Testing.....	39
10	CLOSURE	40

DOCUMENT REFERENCES

TABLES

Table 1	Melbourne-Derived Wind Acceptability Criteria.....	17
Table 2	Predicted Peak Annual Gust Wind Speeds at all Sensor Locations	32

FIGURES

Figure 1	Satellite Image of the Proposed Development Site	11
Figure 2	Key Architectural Floor Plans of Interest and Representative Elevations.....	12
Figure 3	City of Sydney “Bulk Envelope Compliant” Design	14
Figure 4	Annual Wind Roses for Sydney (KS) Airport and Bankstown Airport (BoM Data)	16
Figure 5	Reference Height (200 m) Annual Recurrence Mean Wind Speed at Liverpool.....	18
Figure 6	Wind Tunnel Test Profiles for Mean Wind and Turbulence Intensity.....	19
Figure 7	1:400 Scale Model of the Proposed Development	20
Figure 8	Proximity Models Used in the Wind Tunnel Testing.....	21
Figure 9	Wind Tunnel Test Sensor Locations	24
Figure 10	Sample Polar Plot Test Result – Location 15 – “Baseline” & “Future” Scenarios	25
Figure 11	Peak Annual Gusts V/Vref: “Baseline” versus “Future” Scenarios Representative Location	26
Figure 12	Peak Annual Gusts V/Vref: “Baseline” versus “Future” Scenarios Representative Locations	27
Figure 13	Peak Annual Gusts V/Vref: “Baseline” versus “Future” Scenarios Representative Locations	28
Figure 14	Peak Annual Gusts V/Vref: “Baseline” versus “Future” Scenarios Representative Locations	29
Figure 15	Peak Annual Gusts V/Vref: “Future” Scenario Representative Locations.....	30
Figure 16	Peak Annual Gusts V/Vref: “Future” Scenarios Representative Locations	31
Figure 17	Vegetation and Trees along Surrounding Footpath Areas.....	34
Figure 18	Recently Proposed Level 4 Mitigation.....	38

PHOTOS

Photo 1	Representative Project Surrounds (Views towards Site, East and West of Site)	15
---------	--	----

APPENDICES

Appendix A	Seasonal Wind Roses for Sydney Airport and Bankstown Airport
Appendix B	Wind Speed Polar Plots for BASELINE Wind Tunnel Tests
Appendix C	Wind Speed Polar Plots for FUTURE Wind Tunnel Tests

1 INTRODUCTION

SLR Consulting Pty Ltd (SLR) has been commissioned by Allen, Jack + Cottier, on behalf of The Trust Company (Australia) Ltd ATF WH Gibbons Trust, to assess the ground level wind environment around a proposed student village located at 13-23 Gibbons Street, Redfern.

In late 2018, an initial assessment was made via a Discrete Sensor Environmental Wind Tunnel Study whereby wind tunnel measurements were made to investigate wind conditions within and around the then-proposed development (simulated via a 1:400 scale model) at areas to be used by visitors and occupants of the development itself. The study was documented in:

- SLR Report 610.18313-R06-v1.0, *“13-23 Gibbons Street, Redfern – Environmental Wind Tunnel Test”*, December 2018.

Since that time, and following design changes to the bulk envelope of the building, a second Environmental Wind Study has been undertaken, again via wind tunnel testing, using architectural drawings dated September 2019. This second study included the following additional aspects:

- The second round of testing has included new assessment points on the nearest residential building to the south of the site, No.1 Margaret Street, Redfern, including its roof level terrace areas; and
- The re-testing has also included additional testing of a City of Sydney “DCP-Compliant” bulk envelope building form.

Since that time, and following design changes to the bulk envelope of the building, a second Environmental Wind Study has been undertaken, again via wind tunnel testing, using architectural drawings dated September 2019. In addition to assessing the wind environment at all of the previously monitored locations the second round of testing has included new assessment points on the nearest residential building to the south of the site, No.1 Margaret Street, Redfern, including its roof level terrace areas.

1.1 Structure of the Report

The remainder of this report is structured as follows:

Section 2 ...	describes the proposed development and surrounds
Section 3 ...	describes Sydney’s regional wind climate
Section 4 ...	presents the wind comfort and safety criteria used in the study
Section 5 ...	describes the local wind climate characteristics expected at the site
Section 6 ...	discusses the wind tunnel test methodology used in the study
Section 7 ...	presents the results of the testing
Section 8 ...	presents a summary of the results compared to the adopted acceptability criteria
Section 9 ...	discusses the wind mitigation recommendations for the development

2 DESCRIPTION OF THE PROPOSED DEVELOPMENT

2.1 Location of Development Site

The proposed development is bounded by Gibbons Street to the west, Margaret Street to the south and William Lane to the east - refer **Figure 1**.

Figure 1 Satellite Image of the Proposed Development Site



Image Courtesy: GoogleEarth, October 2019

2.2 Proposed Development Description

The proposal comprises (refer **Figure 2**):

- One level of basement car parking;
- Level 1 (Ground Floor) with building entry, common areas, retail unit;
- Level 4 (Podium) with external common areas, student units;
- Levels 2-3 and 5-18 for student units; and
- Roof Level (Plant and Equipment)

Figure 2 Key Architectural Floor Plans of Interest and Representative Elevations




Fig.2 (cont'd)

Level 4



West (Gibbons Street) Elevation




South (Margaret Street) Elevation



The revised assessment of the proposed development included testing of a City of Sydney “Bulk Envelope Compliant” design conforming to standard CoS set-back and building podium/height requirements. This is shown in **Figure 3**.

Figure 3 City of Sydney “Bulk Envelope Compliant” Design



2.3 The Surrounding Built Environment

In terms of surrounding buildings:

- Buildings surrounding site are generally low and mid-rise, comprising a mix of commercial, retail and residential buildings (several of similar height to the proposed development).
- Gibbons Street Reserve lies immediately to the west with Redfern train station to the north-northwest.
- There are a number of planned and approved future residential developments of similar height located immediately to the north of the proposed development, running between Gibbons Street and Regent Street.
- Sydney’s CBD area lies to the north and the proposed SSD Waterloo Precinct development to the south-southeast.

The terrain is undulating in the surrounding built environment, with no particularly significant topographical variations (ie hills, escarpments, etc) influencing local wind speeds.

These aspects are shown in representative views in **Photo 1**.

Photo 1 Representative Project Surrounds (Views towards Site, East and West of Site)



3 SYDNEY'S REGIONAL WIND CLIMATE


The data of interest in this study are the mean hourly wind speeds and largest gusts experienced throughout the year (especially higher, less frequent winds), how these winds vary with azimuth, and the seasonal break-up of winds into the primary Sydney Region wind seasons.

3.1 Seasonal Variations

Key characteristics of Sydney's Regional Wind Climate are illustrated in two representative wind roses shown in **Figure 4**, taken from Bureau of Meteorology (BoM) data recorded during the period 1999-2017 at Sydney (Kingsford Smith) Airport and Bankstown Airport. The associated seasonal wind roses (refer **Appendix A**) show that Sydney is affected by two primary wind seasons with short (1-2 month) transition periods in between:

- Summer winds occur mainly from the northeast, southeast and south. While northeast winds are the more common prevailing wind direction (occurring typically as offshore land-sea breezes), southeast and southerly winds generally provide the strongest gusts during summer. Northeast sea breeze winds and stronger southerly winds associated with "Southerly Busters" and "East Coast Lows" typically have a significantly greater impact along the coastline. Inland, these systems lose strength and have altered wind direction characteristics.
- Winter/Early Spring winds occur mainly from west quadrants and to a lesser extent from the south. West quadrant winds provide the strongest winds during winter and in fact for the whole year, particularly at locations away from the coast.

Figure 4 Annual Wind Roses for Sydney (KS) Airport and Bankstown Airport (BoM Data)



3.2 Wind Exposure at the Site – the “Local” Wind Environment

Close to the ground, the “regional” wind patterns described above are affected by the local terrain, topography and built environment, all of which influence the “local” wind environment.

- As noted in **Section 1.3**, the site is currently surrounded by a mix of low to mid-rise retail, commercial and residential buildings, with a number of these of similar height to the proposed development. The site will therefore receive moderate wind shielding depending upon oncoming wind direction at lower levels with upper levels exposed to higher winds from most wind directions.

4 WIND ACCEPTABILITY CRITERIA

The choice of suitable criteria for evaluating the acceptability of particular ground level conditions has been the subject of international research over recent decades.

4.1 The “Melbourne” Wind Criteria

One of the acceptability criteria developed from this research, and currently referenced by many Australian Local Government Development Control Plans, are the so-called “Melbourne” criteria, summarised in **Table 1**.

Table 1 Melbourne-Derived Wind Acceptability Criteria

Type of Criteria	Gust Wind Speed Occurring Once Per Year	Activity Concerned
Safety	24 m/s	Knockdown in Isolated Areas
	23 m/s	Knockdown in Public Access Areas
Comfort	16 m/s	Comfortable Walking
	13 m/s	Standing, Waiting, Window Shopping
	10 m/s	Dining in Outdoor Restaurant

The following objectives relate to the above wind impact criteria:

- The general objective for pedestrian areas is for annual 3-second gust wind speeds to remain at or below the 16 m/s “walking comfort” criterion. Whilst this magnitude may appear somewhat arbitrary, its value represents a level of wind intensity above which the majority of the population would find unacceptable for comfortable walking on a regular basis.
- In many urban locations, either because of exposure to open coastal conditions or because of street “channelling” effects, etc, the 16 m/s criterion may already be currently exceeded. In such instances a new development should ideally not exacerbate existing adverse wind conditions and, wherever feasible and reasonable, ameliorate such conditions.
- The recommended criteria for spaces designed for activities such as seating, outdoor dining, etc, are lower (ie more stringent) than for “walking comfort”.

The **Table 1** criteria should not be viewed as “hard” numbers as the limiting values were generally derived from subjective assessments of wind acceptability. Such assessments have been found to vary with the height, strength, age, etc, of the pedestrian concerned.

A further factor for consideration is the extent of windy conditions, and some relaxation of the above criteria may be acceptable for small areas under investigation provided the general site satisfies the relevant criteria.

Finally, it is noted that the wind speed criteria in **Table 1** are based on the maximum wind gust occurring (on average) once per year. Winds occurring more frequently, eg monthly winds, weekly winds, etc, would be of lesser magnitude. So for example, a location with a maximum annual gust of 10 m/s would experience winds throughout the year of a much lower and hence generally mild nature, conducive to stationary activities (seating, dining, etc).

5 DESIGN WIND SPEEDS

5.1 Methodology

SLR has carried out a detailed study of Sydney Basin wind speeds using continuous records of wind speed and direction measured at the Bureau of Meteorology's (BoM) Sydney weather stations. The objective of this study was to develop statistical wind information for locations not situated in close proximity (ie within say approximately a kilometre) of BoM weather stations.

Wind records given particular emphasis were from weather stations with a "clean" surrounding exposure, eg stations such as Sydney (Kingsford Smith) Airport and Bankstown Airport, ie locations relatively free of immediately surrounding obstacles such as buildings, vegetation, trees, etc, which would otherwise distort the winds seen by the weather station anemometer.

For Redfern, SLR has determined that local winds have characteristics very close to Sydney (KS) Airport compared to Bankstown Airport, given Redfern's proximity to Sydney (KS) Airport and similar distance inland from the coastline. Key prevailing wind directions of interest are the northeast, southeast and south for summer and mainly west quadrant winds for winter.


The above analysis is described in detail in ...

- SLR Technical Note: "9300-TN-CW&E-v2.0 Sydney Region Design Winds", March 2018.

5.2 Reference Height Wind Speeds

In the wind tunnel testing, the reference dynamic pressure used to record all wind speed data was measured at an equivalent (full-scale) height of 200 m above ground level (500 mm in the wind tunnel). Accordingly, conversion from wind tunnel speeds to full-scale speeds requires the determination of reference height design mean wind speeds for the site. These are shown in **Figure 5** and have been based on the adopted Liverpool wind model as described above. The winds shown in **Figure 5** have a once-per-year exceedance probability.

Figure 5 Reference Height (200 m) Annual Recurrence Mean Wind Speed at Liverpool



6 WIND TUNNEL TEST METHODOLOGY

6.1 Simulation of Natural Wind


Similarity requirements between the wind tunnel model and prototype (ie full-scale) need to be fulfilled so that similitude in the flow conditions is satisfied. Usually all requirements cannot be satisfied and compromises need to be made. In this type of wind tunnel test it is possible to waive strict adherence to the full range of similarity parameters.

The wind tunnel test has been carried out using a geometric length scale of 1:400 for all dimensions (standard wind tunnel test scaling) and by scaling the boundary layer approach wind in the wind tunnel to the same scale as in the atmosphere.

The approach wind was modelled by matching terrain category conditions for all wind directions. In the wind tunnel, this is achieved by an almost 20-metre fetch of appropriate roughness elements.

The upstream profile conditions simulated in the present study is Terrain Category 3 associated with medium density suburban surroundings. The variation of mean wind speed (blue curve) and turbulence intensity (green curve) is shown in **Figure 6**.

Figure 6 Wind Tunnel Test Profiles for Mean Wind and Turbulence Intensity





6.2 Development Models and Proximity Model

Development Models: September 2019 Revised Design & “Compliant” Design



Two 1:400 scale models of the proposed development were built (using 3D printing) for the testing – refer **Figure 7** - for the latest (September 2019) design and City of Sydney “Bulk Envelope Compliant” design.

Figure 7 1:400 Scale Model of the Proposed Development

September 2019 Design



CoS “Bulk Compliant” Design



Proximity Model

To take into account the influence of the immediate surrounding physical environment, all neighbouring buildings and local topography within a diameter of almost 900 m around the site were included in the purpose-built 1:400 scale “proximity model” used for the test as shown in **Figure 7**.

The proximity models simulate the following built environment “scenarios”:

- “Baseline” scenario: simulating the existing built environment (as of October 2019); and
- “Future-R” scenario: with the addition of the future proposed development.
- “Future-C” scenario: with the addition of a City of Sydney “Bulk Envelope Compliant” design.

All of the above included the proposed and approved future developments lying to the immediate north of the site – refer **Figure 8**.

Figure 8 Proximity Models Used in the Wind Tunnel Testing

“Baseline”
Scenario
(Existing)

View from
South






Fig.8 (cont'd)

“Future-R”
Scenario
(with Revised
Design Proposal)



“Future-C”
Scenario
(with Cos
“Compliant Design”)



6.3 Data Processing

The wind speeds at the locations of interest are measured in the wind tunnel using Irwin sensors. The reader is referred to the publication referenced below for a full description of this technique and validation of Irwin sensor data using hot-wire anemometry.

- LTR-LA-242 *"A Simple Omni-Directional Sensor for Wind Tunnel Studies of Pedestrian Level Winds"* (Irwin, National Aeronautical Establishment, Ottawa, Canada, May 1980)

Wind speeds in the wind tunnel ...

- were measured at a height corresponding to approximately chest height (1.5 m) in full scale;
- were measured at 10° intervals (north is at 0°, east at 90°, south at 180°, etc).

The 90-second sampling duration velocities are recorded as dimensionless ratios of the mean and gust ground level velocity to a mean reference wind speed at a height of 200 m above ground level. The data is then processed using the directional wind speed information derived from the Redfern wind climate model to yield ground level wind speeds as a function of annual return period and directional mean reference wind speed – refer **Figure 5**.

The ground level wind speeds thus incorporate both the building and terrain/topographical aspects of the location as well as the directional probability of wind speed for the site.

The results have been computed on an annual exceedance basis, to compare to the adopted wind acceptability criteria, using the local Project-Site statistical wind data – refer **Figure 5**.


6.4 Test Method – Sensor Locations

In the wind tunnel testing, Irwin wind sensors were positioned at the locations shown in **Figure 8**.

These locations were chosen as potentially susceptible to adverse wind conditions, eg near building corners, or represent locations of interest throughout the development, eg near primary building entrances and along footpaths.

- The 25 Ground level sensors are shown in yellow;
- Locations 1 to 23 were measured both the "Baseline" and the two "Future" scenarios;
- Locations 24-25 were only measured for the two "Future" scenarios;
- The 5 Podium level sensors, Locations 26 to 30 are shown separately (purple circles); these positions are located on the newly proposed development Podium and were measured only for the "Future-R" scenario; and
- Locations 31-33 were measured on the roof terraces of No.1 Margaret Street and were assessed for all three scenarios.

Figure 9 Wind Tunnel Test Sensor Locations



6.5 Sample Test Result


An example of the test results and interpretation of these results is shown in **Figure 10**, illustrating the peak annual mean and gust wind speeds at:

Sensor: **Location 15**
Location: Margaret Street – close to Gibbons Street intersection

The polar diagram shows the output of the wind tunnel test results in terms of the ratio of mean wind speed and gust wind speed to reference height mean wind speed ($H_t=200\text{m}$):

Mean wind speed: “navy blue” data points
Gust wind speed: “red” data points.

Figure 10 Sample Polar Plot Test Result – Location 15 – “Baseline” & “Future” Scenarios



For the “Baseline” scenario ...

- Winds at Location 15 are strongest from the east, northwest and west, where winds from these directions can approach the site over low height buildings or open areas like Gibbons Street Reserve and then can channel along Margaret Street.

For the two “Future” scenarios ...

- With the addition of the proposed (revised design) development, winds at Location 15 decrease slightly from the northeast, thanks to shielding from the development itself, and increase from the west-northwest, where winds can accelerate around the development’s southwest corner.
- At Location 15, wind responses for the City of Sydney “Bulk Envelope Compliant” design are virtually identical to the revised design.

7 TEST RESULTS


Appendices B, C & D shows the relevant wind tunnel test result polar plots respectively for all locations for the “Baseline” (existing built environment), “Future-R” (with the proposal) and “Future-C” (“compliant”) scenarios.

It should be noted that no landscaping was incorporated in the “Baseline” and two “Future” proximity models. This is done to provide a clear insight as to the approach angles resulting in potential adverse wind conditions and the magnitude of such adverse conditions. This information can then be used to develop effective additional windbreak mitigation options such as increased landscaping, additional canopies, awnings, etc.

7.1 Sensor Locations: Gibbons Street (west side) – (representative locations Fig.11)

- Winds along the western footpath of Gibbons Street and within Gibbons Street Reserve are currently highest for directions where winds approach the relevant locations within minimal or modest upstream shielding, eg from the northwest.
- The addition of the proposed development produces only modest changes in existing winds
- With the proposed development downstream for northwest winds, these remain unaffected.
- There is a modest decrease in easterly winds at locations opposite and south of the site, reflecting increased sheltering from the proposed development – this occurs for both of the “Future” scenarios.


Figure 11 Peak Annual Gusts V/Vref: “Baseline” versus “Future” Scenarios Representative Location



7.2 Sensor Locations: Gibbons Street (east side) - (representative locations Fig.12)

- Winds along the eastern footpath of Gibbons Street and within Gibbons Street Reserve are currently highest for directions where winds approach the relevant locations within minimal or modest upstream shielding, eg from the northwest and south.
- With the addition of the proposed Revised Design development, winds from the northwest remain unaffected away from the development and increase right in front of the development reflecting downwash off the development's western facade.
- Winds from the south increase with the proposed development at and north of the site, reflecting increased downwash and accelerated flow of the development's western façade.
- Winds for the two future scenarios ("Revised Design" and "Compliant Design") are essentially the same for most of these locations, with the exception of Location 13, where winds are higher for both easterly and southerly winds.


Figure 12 Peak Annual Gusts V/Vref: "Baseline" versus "Future" Scenarios Representative Locations



7.3 Sensor Locations: Margaret Street - (representative locations Fig.13)

- Winds along Margaret Street in the vicinity of the development site are currently highest from the east and west, reflecting channelling of winds along this thoroughfare. Winds from northerly and southerly quadrants are shielded by adjacent buildings. Margaret Street winds close to Regent Street are modest and do not exhibit strong wind channelling characteristics.
- With the addition of the proposed Revised Design development, Margaret Street winds close to Gibbons Street are predicted to increase from the west, reflecting the acceleration and downward influence of the proposed development's southern façade. Margaret Street winds close to Regent Street remain the same or reduce from the northeast.
- Winds for the two future scenarios ("Revised Design" and "Compliant Design") are similar for most of these locations, with slightly higher winds for easterly winds for the Compliant Design.


Figure 13 Peak Annual Gusts V/Vref: "Baseline" versus "Future" Scenarios Representative Locations



7.4 Sensor Locations: Through Site Link - (representative locations Fig.14)

- Winds within the Through Site Link are generally mild from all directions, reflecting the sheltering at these locations from buildings in all directions except from the east.
- With the addition of the proposed Revised Design development, winds remain the same from the east and increase from the northeast and southwest.
- Winds for the two future scenarios (“Revised Design” and “Compliant Design”) vary somewhat with winds increasing for the Compliant Design at Location 23 and decreasing modestly at Location 24.


Figure 14 Peak Annual Gusts V/Vref: “Baseline” versus “Future” Scenarios Representative Locations



7.5 “Future” Locations - Podium Locations - (representative locations Fig.15)

- These are all “Future” scenario Podium locations (they do not exist in the “Baseline” scenario).
- Winds on the Podium are highest from the west where they occur as downwash winds off the development’s Gibbons Street façade.
- In the previous (2018) testing, winds at Location 30 were significantly higher than with the Revised Design, which has benefitted from a more extensive canopy protecting this Podium area (southwest corner of building).

Figure 15 Peak Annual Gusts V/Vref: “Future” Scenario Representative Locations




7.6 Sensor Locations – No.1 Margaret Street Roof Terraces


- In the current built environment, No.1 Margaret Street roof terrace wind conditions range from moderate winds in the centre to higher winds close to the eastern end of the building.
- Winds increase slightly in both of the Future scenarios in the central area and in the eastern area as well, especially for the Future-Compliant scenario.

Figure 16 Peak Annual Gusts V/Vref: “Future” Scenarios Representative Locations


“Existing” Scenario



“Future-Revised” Scenario



“Future-Compliant” Scenario



8 OVERALL WIND IMPACT

Table 2 gives the peak annual gust wind speeds predicted to occur at the test sensor locations for the “Baseline” and “Future” built environment scenarios, relevant to assessment of the Melbourne Criteria.

Table 2 Predicted Peak Annual Gust Wind Speeds at all Sensor Locations

Sensor No and Location Description (ref Fig.9)		Peak Annual Gust (m/s)		
		BASELINE	FUTURE REVISED	FUTURE COMPLIANT
1	Gibbons Street – west footpath, north of site	17.5	16.5	17.0
2	Gibbons Street – west footpath, opposite NW corner of development	18.5	17.0	19.0
3	Gibbons Street Reserve – opposite development	18	20.0	19.0
4	Gibbons Street – west footpath, opposite SW corner of development	19.5	19.5	19.5
5	Gibbons Street – west footpath, south of site	17	17.0	16.5
6	Gibbons Street – east footpath, north of site	13.5	15.5	15.5
7	Gibbons Street – east footpath, north of site	16	15.5	14.0
8	Gibbons Street – east footpath, NW corner of development	17	14.5	14.0
9	Gibbons Street – east footpath, midway between Locs. 8 & 10	15.5	16.0	16.5
10	Gibbons Street – east footpath, midway along development west facade	15	15.5	15.5
11	Gibbons Street – east footpath, midway between Locs. 10 & 12	18	15.0	18.5
12	Gibbons Street – east footpath, SW corner of development	14	15.5	16.5
13	Gibbons Street – east footpath, southern side of Margaret Street	15.5	15.5	18.5
14	Gibbons Street – east footpath, south of site	16	17.0	13.5
15	Margaret Street – along development southern facade	17	21.0	21.0
16	Margaret Street – along development southern facade	15	20.0	21.5
17	Margaret Street – along development southern facade	13	19.0	21.0
18	Margaret Street & Through Site Link – SE corner of development	15	19.0	19.5
19	Margaret Street & William Lane	15.5	19.0	19.0
20	Margaret Street – east of development site	14	15.5	17.0
21	Margaret Street – east of development site (close to Regent Street)	11.5	12.0	11.5
22	Through Site Link – along eastern façade of development	7	11.5	14.0
23	Through Site Link – NE corner of development (close to William Lane)	7.5	10.0	13.0
24	Through Site Link – along eastern façade of development		11.5	11.5
25	Through Site Link – along eastern façade of development		12.5	11.0
26	Level 2 Podium – facing north, midway along façade	Refer Note 2	13.5	
27	Level 4 Podium – near NW corner of development		18.0	Refer Note 3
28	Level 4 Podium – midway along western façade		13.0	
29	Level 4 Podium – near SW corner of development		14.0	

Sensor No and Location Description (ref Fig.9)	Peak Annual Gust (m/s)		
	BASELINE	FUTURE REVISED	FUTURE COMPLIANT
30 Level 4 Podium – near SW corner of development		15.5	
31 No.1 Margaret Street Roof Terrace (central)		11.5	10.0
32 No.1 Margaret Street Roof Terrace (northeast)		11.5	14.0
33 No.1 Margaret Street Roof Terrace (southeast)		15.0	17.0

Note 1: Peak Gust Values rounded off to the nearest 0.5 m/s (the experimental error in results is ± 0.5 m/s)

Note 2: Locations 24-29 are Ground Level (24-25) and Podium (26-30) locations which only exist in the “Future” scenario

Note 3: Podium locations 26-30 were not tested for the “Revised-Compliant” model due to space constraints with the Podium width

8.1 Wind Impact Relative to Intended Usage

Feedback received from the City of Sydney (CoS) regarding the original 2018 Wind Report included the following:

- So as to comply with the intent of the Redfern-Waterloo Urban Design Principles (RWUDP), an ‘active frontage’ criteria is to be adopted for Gibbons Street of maximum 13m/s. This must not be exceeded;*
- A maximum of 16m/s is to be adopted for Margaret Street. This must not be exceeded; and*
- For sitting areas in the through site link, the more stringent criteria of 10m/s maximum is to be adopted. The analysis must take into account that an awning capable of deflecting wind is currently proposed in this location.*

There is no mention in the project SEARs of compliance with RWUDP. There is reference in SEARs: Section 1 - “Key Issues” to consideration of the relevant provisions, goals and objectives in ... “Redfern Centre Urban Design Principles”. There is also a direct reference to wind effects in SEARs: Section 5 - “Amenity Issues” as follows:

5. Amenity

- Detail the impacts of the development on view loss, sunlight/overshadowing, wind impacts, reflectivity, visual and acoustic privacy to achieve a high level of environmental amenity.

With regarding to Gibbons Street, SLR notes that Gibbons Street is a highly trafficked thoroughfare.

Furthermore, from SLR’s Wind Studies (2018 and 2019), the following has been established:

- In terms of its existing (current) wind environment: (a) peak annual gusts along the western footpath of Gibbons Street range from 17 m/sec to 19.5 m/sec (north of the site to south of the site), and (b) peak annual gusts along the eastern footpath of Gibbons Street range from 14 m/sec to 16.5 m/sec (north of the site to south of the site);
- With the addition of the proposed development ... (a) peak annual gusts along the western footpath of Gibbons Street generally decrease, and (b) peak annual gusts along the eastern footpath of Gibbons Street experience both modest increases and decreases.

Given the above, SLR feels that the standard “Walking Comfort” criterion of 16 m/sec (peak annual gust) should be retained for Gibbons Street, particularly in view of the existing conditions prevailing at the site.

For the above same reasons, SLR does not concur with the recommendation that the suggested criteria for Gibbons Street and Margaret Street ... *“must not be exceeded”*, particularly in view of the fact that the suggested criteria are almost certainly already being exceeded in the existing conditions.

It has been standard practice with all regulatory bodies (including CoS) that, in urban locations where the walking comfort 16 m/s criterion is already being exceeded, a new development should ideally not exacerbate existing adverse wind conditions and, wherever feasible and reasonable, ameliorate such conditions.

Pedestrian Footpath Areas Surrounding the Site

Wind category objective: 16 m/s Walking Comfort criterion (recommended by SLR)

Ground level locations surrounding the site (Gibbons Street, Margaret Street, Through Site Link) are predicted to experience both modest increases and decreases in wind speed for key prevailing wind directions (northeast, southeast, south and west).

- In terms of the Melbourne Criteria, a number of these locations currently experience peak annual gusts which lie above the 16 m/s walking comfort criterion, but well below the 23 m/s safety criterion.
- In the “Future” scenario, most of these locations remain above the 16 m/s walking comfort criterion, and continue to remain below the 23 m/s safety criterion.

Observation:

- Wind conditions predicted in the wind tunnel testing did not have the advantage of the mature and extensive vegetation and trees along some of the footpath areas of interest, in particular Gibbons Street and the Gibbons Street Reserve – refer **Figure 17**. These would have a significant ameliorating (ie sheltering) effect on local wind speeds (throughout the year if of evergreen species) for ALL of the test scenarios – “Baseline”, “Future-Revised” and “Future-Compliant”.

Figure 17 Vegetation and Trees along Surrounding Footpath Areas



Future-Revised versus Future-Compliant

- There were 8 ground level locations where the Future-Compliant Design peak annual gust was lower than the Future-Revised Design (differences typically around 1 m/s)
- There were 6 ground level locations where the Future-Compliant Design peak annual gust was the same as the Future-Revised Design
- There were 11 ground level locations where the Future-Compliant Design peak annual gust was higher than the Future-Revised Design (differences typically around 1 m/s)

Future-Revised & Future-Compliant Compared to 16 m/sec Walking Comfort

- For most of the locations where the Future-Revised Design peak annual gust was above 16 m/s, the peak annual gust remained above 16 m/s for the Future-Compliant Design
- There was one instance (Location 14) where the Future-Revised Design peak annual gust was above 16 m/s, and the peak annual gust was below 16 m/s for the Future-Compliant Design
- There were four instances (Locations 11, 12, 13 and 20) where the Future-Revised Design peak annual gust was below 16 m/s, and the peak annual gust was above 16 m/s for the Future-Compliant Design

On the basis of the above, it is concluded that the “Future-Revised” Design performs comparably, wind-wise, to the “Future-Compliant” Design and overall slightly better.

Through Site Link

Wind category objective: 16 m/Walking Comfort criterion
Ideally 13 m/s Standing-Waiting-Window Shopping criterion, and
The 10 m/s Outdoor Dining criterion for seating areas intended for dining

- Peak annual gusts within the Through Site Link for the “Future-Revised” Design are all below the 13 m/sec level.
- Peak annual gusts within the Through Site Link for the “Future-Compliant” Design are also below the 13 m/sec level except at Location 22 (14 m/s).

Observation:

- It is noted that wind conditions within the new Through Site Link were tested in the wind tunnel without the benefit of any of the landscaping, or the “Public Artwork Canopy” proposed for this area.

Podium Areas

Wind category objective: 13 m/s Standing-Waiting-Window Shopping criterion
Ideally 10 m/s Outdoor Dining criterion for seating areas intended for dining

The Level 2 Podium is significantly sheltered by the proposed development itself and the adjacent similar height building to the immediate north.

The proposed development’s Level 4 Podium has the potential to experience elevated wind conditions as windflow accelerates past the western façade of the proposed development’s high-rise component and is directed downwards as downwash and accelerated shear flow.

In the original (2018) tested model, this was most apparent at both the northwest and southwest corners of the Podium, especially at the southwest corner (peak predicted annual gust of 21 m/s).

In the "Future-Revised (2019) model, considerable improvement has been achieved at the southwest corner where the peak predicted annual gust is now 15.5 m/s. Winds at the northwest corner remain the same as the original (2018) tested model.

Observation:

- Wind conditions on the new Podium were tested in the wind tunnel without the benefit of any of the landscaping already proposed for the Podium.
- It is also important to appreciate that, while the Podium has the potential to attract elevated winds from building floors above (downwash, etc), especially at the northwest corner, these winds are thereby prevented from generating the same impact at ground level locations immediately below. The Podium therefore plays a potentially important role in ameliorating ground level wind conditions in surrounding pedestrian areas.

No.1 Margaret Street Terrace Areas

Predicted peak annual gusts for the No.1 Margaret Street roof terrace test Locations 31-33 are (respectively):

- 11.5 m/s, 11.5 m/s and 15 m/s for the "Future-Revised" Design
- 10 m/s, 14 m/s and 17 m/s for the "Future-Compliant" Design

As for the ground level locations surrounding the site, it is concluded that the "Future-Revised" Design performs comparably, wind-wise, to the "Future-Compliant" Design and overall slightly better.

9 MITIGATION TREATMENT RECOMMENDATIONS

Sections 7 and 8 provided guidance as to the areas where the adopted wind acceptability criteria had the potential to be exceeded and an indication as to the likely local optimum wind treatment strategy, eg whether the wind condition of interest is likely to arise from accelerating winds which require vertical windbreaks (such as landscaping) or downwash winds which require horizontal windbreaks (such as awnings, canopies).

The wind conditions of potential concern in relation to the proposed development revealed by the wind tunnel study are:

- Selected footpath areas along Margaret Street; and
- The NW corner of the Level 4 Podium.

9.1 Existing and Planned Wind Amelioration

It has been noted that the current round of wind tunnel testing did not include the following features, all of which would have had an ameliorating impact on local wind speeds:

- Vegetation and trees along Gibbons Street and the Gibbons Street Reserve - refer **Figure 17**;
- Extensive landscaping and pergolas planned for the Through Site Link – refer **Figure 2**;
- Additional trees for Margaret Street - refer **Figure 2**; and
- Extensive landscaping planned for the Level 4 Podium – refer **Figure 2**.

9.2 Additional Wind Mitigation Recommendations

Pedestrian Areas Surrounding the Site

Current plans for the proposed development retain the existing landscaping along Gibbons Street and included a full perimeter awning along the development's western façade. Refer **Figure 2**.

It is also noted that the main Gibbons Street entry into the development comprises a recessed, double-door (ie "airlock") design. This feature and the western façade awning will ensure acceptable wind conditions at this location.

The wind tunnel testing showed that potentially high localised winds occur at selected ground level locations along both Gibbons Street and Margaret Street ("Baseline" and "Future" scenarios).

- It has been noted that these results were obtained in the absence of existing trees and landscaping
- Further, the "Future" results did not include the planned additional trees along Margaret Street.


We recommend retention of the existing awnings protecting ground level footpaths and all of the trees and landscaping, existing and planned.

Given the relatively low wind speeds predicted for the Through Site Link in the "Future-Revised" Design and the observation that this was in the absence of planned landscaping and the Public Artwork Canopy, no additional mitigation is recommended beyond that already planned.

Podium – Level 4

The wind tunnel testing showed that high localised winds occur at the northwest corner of the Level 4 Podium area facing west – refer **Figure 18**. This corner will be exposed to winds with both a horizontal and vertical component. As a result, wind mitigation here should include both horizontal protection (eg awnings, canopies, etc) and vertical protection (balustrades, vertical screens, landscaping, etc). Since the recent round of wind tunnel testing, the design of the Level 4 Podium external space has progressed with the addition of 1.8 m high balustrades and an extended pergola (3 m high), also shown **Figure 18**. These most recent design changes, along with the previously planned landscaping, would adequately address the wind issue identified for this northwest corner area of Level 4.

Figure 18 Recently Proposed Level 4 Mitigation



9.3 “Future-Revised” versus “Future-Compliant” Design

On the basis of the test results at all ground level locations and the new No.1 Margaret Street roof terrace locations it has been concluded that

- On average, the “Future-Revised” Design performs comparably, wind-wise, to the “Future-Compliant” Design; and
- Taking into account predicted wind speed increases and decreases, the “Future-Revised” Design performs overall slightly better than the “Future-Compliant” Design.

9.4 Areas Not Assessed Via Wind Tunnel Testing

Due to currently intended usages (or rather absence of public access usage) and the physical constraints associated with the scale used in the testing, a number of areas were not tested in the present DA-phase assessment, including:

- The proposed development’s Roof Level which currently shows no areas of public access on the development drawings.

It is almost certain, given the absence of nearby similar height buildings in some wind directions, that the Roof Level will experience elevated wind conditions, especially for stronger southerly and westerly winds, potentially requiring wind treatment beyond standard height (ie code-compliant) balustrades, if this area is to be used for public access usage (eg a Roof Garden).

Such treatments might include a combination of both vertical screening (eg increased height solid balustrades, balustrades combined with planter boxes, etc) and horizontal screening to ensure all-year-round amenity, particularly for southerly and westerly winds.

The development drawings do not currently show any public access areas at Roof Level. Accordingly, no wind mitigation is recommended for these areas.

Taking into account all of the above, it is believed that the proposed development
will comply with the adopted wind acceptability criteria
at all pedestrian and public access locations within and around the development.

10 CLOSURE


This report has been prepared by SLR Consulting Australia Pty Ltd with all reasonable skill, care and diligence, and taking account of the manpower and resources devoted to it by agreement with the client. Information reported herein is based on the interpretation of data collected and has been accepted in good faith as being accurate and valid.

This report is for the exclusive use of The Trust Company (Australia) Ltd ATF WH Gibbons Trust. No warranties or guarantees are expressed or should be inferred by any third parties. This report may not be relied upon by other parties without written consent from SLR Consulting.

APPENDIX A

Seasonal Wind Roses for Bureau of Meteorology Met Stations at Sydney (Kingsford Smith) Airport and Bankstown Airport


Sydney Airport AWS
(Observations)
1999-2017
600.09300



APPENDIX A

Seasonal Wind Roses for Bureau of Meteorology Met Stations at Sydney (Kingsford Smith) Airport and Bankstown Airport

Bankstown Airport AWS
(Observations)
1999-2017
600.09300




APPENDIX B

Wind Tunnel Test Results: BASELINE Scenario Polar Plots: Ratio of Ground Level Wind Speed to Reference Wind Speed




Wind Tunnel Test Results: BASELINE Scenario

Polar Plots: Ratio of Ground Level Wind Speed to Reference Wind Speed



Wind Tunnel Test Results: FUTURE Scenario Polar Plots: Ratio of Ground Level Wind Speed to Reference Wind Speed

Future-REVISED Design




Wind Tunnel Test Results: FUTURE Scenario Polar Plots: Ratio of Ground Level Wind Speed to Reference Wind Speed

Future-REVISED Design



Wind Tunnel Test Results: FUTURE Scenario Polar Plots: Ratio of Ground Level Wind Speed to Reference Wind Speed


Future-COMPLIANT Design




Wind Tunnel Test Results: FUTURE Scenario Polar Plots: Ratio of Ground Level Wind Speed to Reference Wind Speed

Future-COMPLIANT Design


LOCATION 17




LOCATION 18




LOCATION 19




LOCATION 20




LOCATION 21




LOCATION 22




LOCATION 23




LOCATION 24




LOCATION 25




LOCATION 31



LOCATION 30



LOCATION 31



ASIA PACIFIC OFFICES

BRISBANE

Level 2, 15 Astor Terrace
Spring Hill QLD 4000
Australia
T: +61 7 3858 4800
F: +61 7 3858 4801

CANBERRA

GPO 410
Canberra ACT 2600
Australia
T: +61 2 6287 0800
F: +61 2 9427 8200

DARWIN

5 Foelsche Street
Darwin NT 0800
Australia
T: +61 8 8998 0100
F: +61 2 9427 8200

GOLD COAST

Ground Floor, 194 Varsity Parade
Varsity Lakes QLD 4227
Australia
M: +61 438 763 516

MACKAY

21 River Street
Mackay QLD 4740
Australia
T: +61 7 3181 3300

MELBOURNE

Suite 2, 2 Domville Avenue
Hawthorn VIC 3122
Australia
T: +61 3 9249 9400
F: +61 3 9249 9499

NEWCASTLE

10 Kings Road
New Lambton NSW 2305
Australia
T: +61 2 4037 3200
F: +61 2 4037 3201

PERTH

Ground Floor, 503 Murray Street
Perth WA 6000
Australia
T: +61 8 9422 5900
F: +61 8 9422 5901

ROCKHAMPTON

rockhampton@slrconsulting.com
M: +61 407 810 417

SYDNEY

2 Lincoln Street
Lane Cove NSW 2066
Australia
T: +61 2 9427 8100
F: +61 2 9427 8200

TAMWORTH

PO Box 11034
Tamworth NSW 2340
Australia
M: +61 408 474 248
F: +61 2 9427 8200

TOWNSVILLE

Level 1, 514 Sturt Street
Townsville QLD 4810
Australia
T: +61 7 4722 8000
F: +61 7 4722 8001

AUCKLAND

68 Beach Road
Auckland 1010
New Zealand
T: +64 27 441 7849

NELSON

5 Duncan Street
Port Nelson 7010
New Zealand
T: +64 274 898 628

NEW PLYMOUTH

Level 2, 10 Devon Street East
New Plymouth 4310
New Zealand
T: +64 0800 757 695