

BASIX[®]Certificate

Building Sustainability Index www.basix.nsw.gov.au

Multi Dwelling

Certificate number: 943081M_05

This certificate confirms that the proposed development will meet the NSW government's requirements for sustainability, if it is built in accordance with the commitments set out below. Terms used in this certificate, or in the commitments, have the meaning given by the document entitled "BASIX Definitions" dated 06/10/2017 published by the Department. This document is available at www.basix.nsw.gov.au

This certificate is a revision of certificate number 943081M_03 lodged with the consent authority or certifier on 28 September 2018 with application SSD7749.

It is the responsibility of the applicant to verify with the consent authority that the original, or any revised certificate, complies with the requirements of Schedule 1 Clause 2A, 4A or 6A of the Environmental Planning and Assessment Regulation 2000

Secretary

Date of issue: Friday, 15 February 2019

To be valid, this certificate must be lodged within 3 months of the date of issue.



Project summary

Project name	SGCH Gibbons Street_05
Street address	11 Gibbons Street Redfern 2016
Local Government Area	Sydney City Council
Plan type and plan number	deposited 4209
Lot no.	1-11
Section no.	-
No. of residential flat buildings	1
No. of units in residential flat buildings	160
No. of multi-dwelling houses	0
No. of single dwelling houses	0

Project score

Water	✓ 41	Target 40
Thermal Comfort	✓ Pass	Target Pass
Energy	✓ 44	Target 25

Certificate Prepared by

Name / Company Name: Northrop Consulting Engineers Pty Ltd

ABN (if applicable): 81094433100

Description of project

Project address

Project name	SGCH Gibbons Street_05
Street address	11 Gibbons Street Redfern 2016
Local Government Area	Sydney City Council
Plan type and plan number	deposited 4209
Lot no.	1-11
Section no.	-

Project type

No. of residential flat buildings	1
No. of units in residential flat buildings	160
No. of multi-dwelling houses	0
No. of single dwelling houses	0

Site details

Site area (m²)	1578
Roof area (m²)	753
Non-residential floor area (m²)	587.0
Residential car spaces	0
Non-residential car spaces	0

Common area landscape

Common area lawn (m²)	0.0
Common area garden (m²)	125.0
Area of indigenous or low water use species (m²)	0.0

Assessor details

Assessor number	20579
Certificate number	0003616650
Climate zone	56

Project score

Water	✓ 41	Target 40
Thermal Comfort	✓ Pass	Target Pass
Energy	✓ 44	Target 25

Description of project

The tables below describe the dwellings and common areas within the project

Residential flat buildings - Building1, 160 dwellings, 18 storeys above ground

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
101	2	71.0	7.0	0.0	0.0
105	2	68.4	6.9	0.0	0.0
109	2	68.2	6.9	0.0	0.0
203	2	70.3	6.9	0.0	0.0
207	3	116.8	7.5	0.0	0.0
301	1	53.0	7.0	0.0	0.0
305	2	76.5	6.7	0.0	0.0
403	2	65.8	8.0	0.0	0.0
501	2	66.9	7.2	0.0	0.0
505	2	67.1	7.0	0.0	0.0
509	2	76.5	6.7	0.0	0.0
603	2	67.1	7.0	0.0	0.0
607	2	64.7	8.0	0.0	0.0
701	2	66.9	7.2	0.0	0.0
705	2	67.1	7.0	0.0	0.0
709	2	72.4	6.7	0.0	0.0
803	2	67.1	7.0	0.0	0.0
807	2	64.7	8.0	0.0	0.0

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
102	1	47.6	6.9	0.0	0.0
106	2	67.0	7.3	0.0	0.0
110	3	92.3	6.8	0.0	0.0
204	1	47.8	6.75	0.0	0.0
208	3	94.5	7.58	0.0	0.0
302	1	45.3	7.0	0.0	0.0
306	2	63.1	10.2	0.0	0.0
404	1	46.6	7.3	0.0	0.0
502	1	45.3	7.0	0.0	0.0
506	1	54.2	8.5	0.0	0.0
510	2	63.1	10.2	0.0	0.0
604	1	44.3	6.6	0.0	0.0
608	1	48.1	7.1	0.0	0.0
702	1	44.3	7.0	0.0	0.0
706	1	54.2	8.5	0.0	0.0
710	2	64.0	10.2	0.0	0.0
804	1	44.3	6.6	0.0	0.0
808	1	48.1	7.1	0.0	0.0

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
103	2	70.3	6.9	0.0	0.0
107	3	119.4	7.6	0.0	0.0
201	2	71.1	7.3	0.0	0.0
205	2	68.4	6.9	0.0	0.0
209	2	68.2	6.8	0.0	0.0
303	2	65.8	8.0	0.0	0.0
401	2	66.9	7.2	0.0	0.0
405	2	76.5	6.7	0.0	0.0
503	2	67.1	7.0	0.0	0.0
507	2	64.7	8.0	0.0	0.0
601	2	66.9	7.2	0.0	0.0
605	2	67.1	7.0	0.0	0.0
609	2	72.4	6.7	0.0	0.0
703	2	67.1	7.0	0.0	0.0
707	2	64.7	8.0	0.0	0.0
801	2	66.9	7.2	0.0	0.0
805	2	67.1	7.0	0.0	0.0
809	2	72.4	6.7	0.0	0.0

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
104	1	47.6	6.9	0.0	0.0
108	3	98.8	7.8	0.0	0.0
202	1	47.6	6.7	0.0	0.0
206	2	66.8	7.1	0.0	0.0
210	3	91.9	7.5	0.0	0.0
304	1	46.6	7.3	0.0	0.0
402	1	45.3	7.0	0.0	0.0
406	2	63.1	10.2	0.0	0.0
504	1	44.3	6.6	0.0	0.0
508	1	46.6	7.3	0.0	0.0
602	1	44.3	7.0	0.0	0.0
606	1	54.2	8.5	0.0	0.0
610	2	64.0	10.2	0.0	0.0
704	1	44.3	6.6	0.0	0.0
708	1	48.1	7.1	0.0	0.0
802	1	44.3	7.0	0.0	0.0
806	1	54.2	8.5	0.0	0.0
810	2	64.0	10.2	0.0	0.0

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
901	2	66.9	7.2	0.0	0.0
905	2	67.1	7.0	0.0	0.0
909	2	72.4	6.7	0.0	0.0
1003	2	67.1	7.0	0.0	0.0
1007	2	64.7	8.0	0.0	0.0
1101	2	66.9	7.2	0.0	0.0
1105	2	67.1	7.0	0.0	0.0
1109	2	72.4	6.7	0.0	0.0
1203	2	67.1	7.0	0.0	0.0
1207	2	64.7	8.0	0.0	0.0
1301	2	66.9	7.2	0.0	0.0
1305	2	67.1	7.0	0.0	0.0
1309	2	72.4	6.7	0.0	0.0
1403	2	67.1	7.0	0.0	0.0
1407	2	64.7	8.0	0.0	0.0
1501	2	66.9	7.2	0.0	0.0
1505	2	67.1	7.0	0.0	0.0
1509	2	72.4	6.7	0.0	0.0
1603	2	67.1	7.0	0.0	0.0
1607	2	64.7	8.0	0.0	0.0
1701	2	66.9	7.2	0.0	0.0
1705	2	65.8	8.0	0.0	0.0

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
902	1	44.3	7.0	0.0	0.0
906	1	54.2	8.5	0.0	0.0
910	2	64.0	10.2	0.0	0.0
1004	1	44.3	6.6	0.0	0.0
1008	1	48.1	7.1	0.0	0.0
1102	1	44.3	7.0	0.0	0.0
1106	1	54.2	8.5	0.0	0.0
1110	2	64.0	10.2	0.0	0.0
1204	1	44.3	6.6	0.0	0.0
1208	1	48.1	7.1	0.0	0.0
1302	1	44.3	7.0	0.0	0.0
1306	1	54.2	8.5	0.0	0.0
1310	2	64.0	10.2	0.0	0.0
1404	1	44.3	6.6	0.0	0.0
1408	1	48.1	7.1	0.0	0.0
1502	1	44.3	7.0	0.0	0.0
1506	1	54.2	8.5	0.0	0.0
1510	2	64.0	10.2	0.0	0.0
1604	1	44.3	6.6	0.0	0.0
1608	1	48.1	7.1	0.0	0.0
1702	1	44.3	6.6	0.0	0.0
1706	1	48.1	7.1	0.0	0.0

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
903	2	67.1	7.0	0.0	0.0
907	2	64.7	8.0	0.0	0.0
1001	2	66.9	7.2	0.0	0.0
1005	2	67.1	7.0	0.0	0.0
1009	2	72.4	6.7	0.0	0.0
1103	2	67.1	7.0	0.0	0.0
1107	2	64.7	8.0	0.0	0.0
1201	2	66.9	7.2	0.0	0.0
1205	2	67.1	7.0	0.0	0.0
1209	2	72.4	6.7	0.0	0.0
1303	2	67.1	7.0	0.0	0.0
1307	2	64.7	8.0	0.0	0.0
1401	2	66.9	7.2	0.0	0.0
1405	2	67.1	7.0	0.0	0.0
1409	2	72.4	6.7	0.0	0.0
1503	2	67.1	7.0	0.0	0.0
1507	2	64.7	8.0	0.0	0.0
1601	2	66.9	7.2	0.0	0.0
1605	2	67.1	7.0	0.0	0.0
1609	2	72.4	6.7	0.0	0.0
1703	2	67.1	7.0	0.0	0.0
1707	2	72.4	6.7	0.0	0.0

Dwelling no.	No. of bedrooms	Conditioned floor area (m ²)	Unconditioned floor area (m ²)	Area of garden & lawn (m ²)	Indigenous species (min area m ²)
904	1	44.3	6.6	0.0	0.0
908	1	48.1	7.1	0.0	0.0
1002	1	44.3	7.0	0.0	0.0
1006	1	54.2	8.5	0.0	0.0
1010	2	64.0	10.2	0.0	0.0
1104	1	44.3	6.6	0.0	0.0
1108	1	48.1	7.1	0.0	0.0
1202	1	44.3	7.0	0.0	0.0
1206	1	54.2	8.5	0.0	0.0
1210	2	64.0	10.2	0.0	0.0
1304	1	44.3	6.6	0.0	0.0
1308	1	48.1	7.1	0.0	0.0
1402	1	44.3	7.0	0.0	0.0
1406	1	54.2	8.5	0.0	0.0
1410	2	64.0	10.2	0.0	0.0
1504	1	44.3	6.6	0.0	0.0
1508	1	48.1	7.1	0.0	0.0
1602	1	44.3	7.0	0.0	0.0
1606	1	54.2	8.5	0.0	0.0
1610	2	64.0	10.2	0.0	0.0
1704	1	52.3	8.2	0.0	0.0
1708	2	64.0	10.2	0.0	0.0

Description of project

The tables below describe the dwellings and common areas within the project

Common areas of unit building - Building1

Common area	Floor area (m²)
Lift car (No.1)	-
Residential Bin Room	51.0
Bike Workshop	8.2
Fire Control Room	11.3
RW Re-Use Tank	9.0
Pump Room	26.0
Store	6.1
LV1-17 Hallway	1015.0

Common area	Floor area (m²)
Lift car (No.2)	-
Community Hub	63.0
Comms Room	5.0
Gas Cupboard	6.9
RWT	10.0
Bicycle Storage	67.2
Lift Lobby	82.0

Common area	Floor area (m²)
Main Switch Room	11.0
Community Room	48.0
Chamber Substation	26.0
RWT/CW Pump	11.2
OSD	10.0
Fire Stair	572.4
Corridors	49.0

Schedule of BASIX commitments

1. Commitments for Residential flat buildings - Building1

(a) Dwellings

- (i) Water
- (ii) Energy
- (iii) Thermal Comfort

(b) Common areas and central systems/facilities

- (i) Water
- (ii) Energy

2. Commitments for multi-dwelling houses

3. Commitments for single dwelling houses

4. Commitments for common areas and central systems/facilities for the development (non-building specific)

- (i) Water
- (ii) Energy

Schedule of BASIX commitments

The commitments set out below regulate how the proposed development is to be carried out. It is a condition of any development consent granted, or complying development certificate issued, for the proposed development, that BASIX commitments be complied with.

1. Commitments for Residential flat buildings - Building1

(a) Dwellings

(i) Water	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must comply with the commitments listed below in carrying out the development of a dwelling listed in a table below.			
(b) The applicant must plant indigenous or low water use species of vegetation throughout the area of land specified for the dwelling in the "Indigenous species" column of the table below, as private landscaping for that dwelling. (This area of indigenous vegetation is to be contained within the "Area of garden and lawn" for the dwelling specified in the "Description of Project" table).	✓	✓	
(c) If a rating is specified in the table below for a fixture or appliance to be installed in the dwelling, the applicant must ensure that each such fixture and appliance meets the rating specified for it.		✓	✓
(d) The applicant must install an on demand hot water recirculation system which regulates all hot water use throughout the dwelling, where indicated for a dwelling in the "HW recirculation or diversion" column of the table below.		✓	✓
(e) The applicant must install:			
(aa) a hot water diversion system to all showers, kitchen sinks and all basins in the dwelling, where indicated for a dwelling in the "HW recirculation or diversion" column of the table below; and		✓	✓
(bb) a separate diversion tank (or tanks) connected to the hot water diversion systems of at least 100 litres. The applicant must connect the hot water diversion tank to all toilets in the dwelling.		✓	✓
(e) The applicant must not install a private swimming pool or spa for the dwelling, with a volume exceeding that specified for it in the table below.	✓	✓	
(f) If specified in the table, that pool or spa (or both) must have a pool cover or shading (or both).		✓	
(g) The pool or spa must be located as specified in the table.	✓	✓	
(h) The applicant must install, for the dwelling, each alternative water supply system, with the specified size, listed for that dwelling in the table below. Each system must be configured to collect run-off from the areas specified (excluding any area which supplies any other alternative water supply system), and to divert overflow as specified. Each system must be connected as specified.	✓	✓	✓

	Fixtures					Appliances		Individual pool				Individual spa		
Dwelling no.	All shower-heads	All toilet flushing systems	All kitchen taps	All bathroom taps	HW recirculation or diversion	All clothes washers	All dish-washers	Volume (max volume)	Pool cover	Pool location	Pool shaded	Volume (max volume)	Spa cover	Spa shaded
All dwellings	3 star (> 4.5 but <= 6 L/min)	4 star	4 star	4 star	no	-	-	-	-	-	-	-	-	-

	Alternative water source							
Dwelling no.	Alternative water supply systems	Size	Configuration	Landscape connection	Toilet connection (s)	Laundry connection	Pool top-up	Spa top-up
None	-	-	-	-	-	-	-	-

(ii) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must comply with the commitments listed below in carrying out the development of a dwelling listed in a table below.			
(b) The applicant must install each hot water system specified for the dwelling in the table below, so that the dwelling's hot water is supplied by that system. If the table specifies a central hot water system for the dwelling, then the applicant must connect that central system to the dwelling, so that the dwelling's hot water is supplied by that central system.	✓	✓	✓
(c) The applicant must install, in each bathroom, kitchen and laundry of the dwelling, the ventilation system specified for that room in the table below. Each such ventilation system must have the operation control specified for it in the table.		✓	✓
(d) The applicant must install the cooling and heating system/s specified for the dwelling under the "Living areas" and "Bedroom areas" headings of the "Cooling" and "Heating" columns in the table below, in/for at least 1 living/bedroom area of the dwelling. If no cooling or heating system is specified in the table for "Living areas" or "Bedroom areas", then no systems may be installed in any such areas. If the term "zoned" is specified beside an air conditioning system, then the system must provide for day/night zoning between living areas and bedrooms.		✓	✓
(e) This commitment applies to each room or area of the dwelling which is referred to in a heading to the "Artificial lighting" column of the table below (but only to the extent specified for that room or area). The applicant must ensure that the "primary type of artificial lighting" for each such room in the dwelling is fluorescent lighting or light emitting diode (LED) lighting. If the term "dedicated" is specified for a particular room or area, then the light fittings in that room or area must only be capable of being used for fluorescent lighting or light emitting diode (LED) lighting.		✓	✓

(ii) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(f) This commitment applies to each room or area of the dwelling which is referred to in a heading to the "Natural lighting" column of the table below (but only to the extent specified for that room or area). The applicant must ensure that each such room or area is fitted with a window and/or skylight.	✓	✓	✓
(g) This commitment applies if the applicant installs a water heating system for the dwelling's pool or spa. The applicant must: (aa) install the system specified for the pool in the "Individual Pool" column of the table below (or alternatively must not install any system for the pool). If specified, the applicant must install a timer, to control the pool's pump; and (bb) install the system specified for the spa in the "Individual Spa" column of the table below (or alternatively must not install any system for the spa). If specified, the applicant must install a timer to control the spa's pump.		✓ ✓	
(h) The applicant must install in the dwelling: (aa) the kitchen cook-top and oven specified for that dwelling in the "Appliances & other efficiency measures" column of the table below; (bb) each appliance for which a rating is specified for that dwelling in the "Appliances & other efficiency measures" column of the table, and ensure that the appliance has that minimum rating; and (cc) any clothes drying line specified for the dwelling in the "Appliances & other efficiency measures" column of the table.		✓ ✓ ✓	✓
(i) If specified in the table, the applicant must carry out the development so that each refrigerator space in the dwelling is "well ventilated".		✓	

	Hot water	Bathroom ventilation system		Kitchen ventilation system		Laundry ventilation system	
Dwelling no.	Hot water system	Each bathroom	Operation control	Each kitchen	Operation control	Each laundry	Operation control
All dwellings	gas instantaneous 4.5 star	individual fan, ducted to façade or roof	manual on / timer off	individual fan, ducted to façade or roof	manual on / timer off	individual fan, ducted to façade or roof	manual on / timer off

Dwelling no.	Cooling		Heating		Artificial lighting						Natural lighting	
	living areas	bedroom areas	living areas	bedroom areas	No. of bedrooms &/or study	No. of living &/or dining rooms	Each kitchen	All bathrooms/toilets	Each laundry	All hallways	No. of bathrooms &/or toilets	Main kitchen
101, 104, 105, 106, 107, 108, 110, 201, 202, 203, 205, 208, 209, 210, 302, 303, 404, 405, 502, 503, 510, 601, 602, 603, 604, 605, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 801, 802, 803,	ceiling fans	ceiling fans	-	-	1	1	yes	yes	yes	yes	0	no

Dwelling no.	Cooling		Heating		Artificial lighting						Natural lighting	
	living areas	bedroom areas	living areas	bedroom areas	No. of bedrooms &/or study	No. of living &/or dining rooms	Each kitchen	All bathrooms/toilets	Each laundry	All hallways	No. of bathrooms &/or toilets	Main kitchen
804, 805, 806, 807, 808, 809, 810, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 1001, 1002, 1003, 1004, 1005, 1006, 1007												
All other dwellings	ceiling fans	ceiling fans	-	-	2	1	yes	yes	yes	yes	0	no

	Individual pool		Individual spa		Appliances & other efficiency measures							
Dwelling no.	Pool heating system	Timer	Spa heating system	Timer	Kitchen cooktop/oven	Refrigerator	Well ventilated fridge space	Dishwasher	Clothes washer	Clothes dryer	Indoor or sheltered clothes drying line	Private outdoor or unsheltered clothes drying line
All dwellings	-	-	-	-	gas cooktop & electric oven	-	yes	-	-	-	yes	-

(iii) Thermal Comfort	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must attach the certificate referred to under "Assessor details" on the front page of this BASIX certificate (the "Assessor Certificate") to the development application and construction certificate application for the proposed development (or, if the applicant is applying for a complying development certificate for the proposed development, to that application). The applicant must also attach the Assessor Certificate to the application for a final occupation certificate for the proposed development.			
(b) The Assessor Certificate must have been issued by an Accredited Assessor in accordance with the Thermal Comfort Protocol.			
(c) The details of the proposed development on the Assessor Certificate must be consistent with the details shown in this BASIX Certificate, including the details shown in the "Thermal Loads" table below.			
(d) The applicant must show on the plans accompanying the development application for the proposed development, all matters which the Thermal Comfort Protocol requires to be shown on those plans. Those plans must bear a stamp of endorsement from the Accredited Assessor, to certify that this is the case.	✓		
(e) The applicant must show on the plans accompanying the application for a construction certificate (or complying development certificate, if applicable), all thermal performance specifications set out in the Assessor Certificate, and all aspects of the proposed development which were used to calculate those specifications.		✓	
(f) The applicant must construct the development in accordance with all thermal performance specifications set out in the Assessor Certificate, and in accordance with those aspects of the development application or application for a complying development certificate which were used to calculate those specifications.		✓	✓
(g) Where there is an in-slab heating or cooling system, the applicant must: (aa) Install insulation with an R-value of not less than 1.0 around the vertical edges of the perimeter of the slab; or (bb) On a suspended floor, install insulation with an R-value of not less than 1.0 underneath the slab and around the vertical edges of the perimeter of the slab.	✓	✓	✓
(h) The applicant must construct the floors and walls of the development in accordance with the specifications listed in the table below.	✓	✓	✓

	Thermal loads	
Dwelling no.	Area adjusted heating load (in mJ/m²/yr)	Area adjusted cooling load (in mJ/m²/yr)
101	15.3	11.4
102	12.5	14.0
103	15.4	9.9
104	6.7	13.7
105	14.0	9.1
106	20.4	11.8
107	15.8	9.8
108	13.0	7.1
109	20.9	11.0
110	24.2	9.7
201	21.2	11.2
202	8.6	11.4
203	18.0	8.8
204	15.0	14.4
205	14.1	9.3
206	17.0	7.6
207	25.4	10.4
208	15.9	7.3
209	22.6	11.4
301	14.4	9.2
302	6.4	10.0
303	20.5	10.0
304	17.0	8.8
305	13.3	12.3
306	26.5	9.0
401	15.5	7.3
402	9.7	10.0

	Thermal loads	
Dwelling no.	Area adjusted heating load (in mJ/m²/yr)	Area adjusted cooling load (in mJ/m²/yr)
404	15.6	8.7
405	10.2	8.7
406	27.2	9.1
501	15.8	7.3
502	6.8	10.3
503	17.2	7.2
504	9.7	8.9
505	17.6	7.1
506	20.6	8.2
507	20.6	9.5
508	16.1	8.9
509	10.6	8.7
510	27.3	8.6
601	16.2	7.3
602	6.9	10.0
603	12.6	8.0
604	6.8	10.1
605	17.9	7.0
606	19.7	9.4
607	20.9	8.9
608	16.5	8.9
609	10.9	8.4
610	27.7	8.5
701	16.5	7.2
702	7.2	10.0
703	12.9	7.9
704	7.1	10.0

	Thermal loads	
Dwelling no.	Area adjusted heating load (in mJ/m²/yr)	Area adjusted cooling load (in mJ/m²/yr)
705	18.1	7.1
706	20.1	9.2
707	21.3	8.7
708	16.8	8.6
709	11.1	8.3
710	28.1	8.7
801	16.6	7.4
803	13.1	7.8
805	18.3	7.1
806	20.4	9.4
807	21.5	8.7
808	17.1	9.0
810	28.4	8.4
901	16.9	7.3
902	7.5	9.7
903	13.3	7.8
904	7.4	9.8
905	18.5	7.1
906	20.7	9.4
907	21.8	9.1
908	17.3	8.9
910	28.6	8.1
1001	17.1	7.3
1002	7.6	9.6
1003	14.6	7.2
1004	8.6	8.8
1005	19.8	6.3

	Thermal loads	
Dwelling no.	Area adjusted heating load (in mJ/m²/yr)	Area adjusted cooling load (in mJ/m²/yr)
1006	22.6	9.5
1007	23.4	9.5
1008	18.9	9.1
1009	12.7	7.5
1010	30.3	8.0
1101	17.3	7.1
1102	7.8	9.6
1103	14.8	7.0
1104	8.7	8.7
1105	20.0	6.3
1106	22.8	9.9
1107	23.6	9.2
1108	19.1	8.8
1109	12.9	7.5
1110	30.5	8.2
1201	17.5	7.0
1202	8.0	9.5
1203	14.9	7.0
1204	8.7	8.3
1205	20.1	6.3
1206	22.8	10.2
1207	23.7	9.2
1208	19.2	8.9
1209	13.0	7.6
1210	30.7	8.1
1301	17.7	7.0
1302	8.1	9.6

	Thermal loads	
Dwelling no.	Area adjusted heating load (in mJ/m²/yr)	Area adjusted cooling load (in mJ/m²/yr)
1303	15.0	7.0
1304	8.7	8.2
1305	20.2	6.3
1306	22.9	10.2
1307	23.8	9.1
1308	19.3	8.9
1310	30.8	8.1
1401	17.8	7.0
1402	8.2	9.7
1403	15.2	6.9
1404	8.9	8.1
1405	20.3	6.4
1406	22.9	10.3
1408	19.5	8.9
1409	13.1	7.5
1410	31.0	7.9
1501	18.0	6.7
1502	8.4	9.7
1503	15.3	7.0
1504	9.0	8.3
1505	20.4	6.3
1506	22.8	10.4
1508	19.6	8.9
1510	31.1	7.9
1601	18.1	6.8
1602	8.5	9.7
1603	24.7	8.5

	Thermal loads	
Dwelling no.	Area adjusted heating load (in mJ/m ² /yr)	Area adjusted cooling load (in mJ/m ² /yr)
1604	17.3	8.5
1605	28.2	7.2
1606	21.5	10.2
1608	19.7	8.9
1609	13.1	7.6
1610	31.3	7.9
1701	27.3	7.0
1702	17.7	8.5
1703	25.2	8.4
1704	24.8	10.3
1705	28.7	8.2
1706	28.6	7.6
1707	22.8	8.0
1708	38.8	7.3
210, 403	20.3	9.8
802, 804	7.3	9.8
809, 909	11.3	8.5
1309, 1509	13.0	7.4
All other dwellings	23.9	9.0

(b) Common areas and central systems/facilities

(i) Water	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a showerhead, toilet, tap or clothes washer into a common area, then that item must meet the specifications listed for it in the table.		✓	✓
(b) The applicant must install (or ensure that the development is serviced by) the alternative water supply system(s) specified in the "Central systems" column of the table below. In each case, the system must be sized, be configured, and be connected, as specified in the table.	✓	✓	✓
(c) A swimming pool or spa listed in the table must not have a volume (in kLs) greater than that specified for the pool or spa in the table.	✓	✓	
(d) A pool or spa listed in the table must have a cover or shading if specified for the pool or spa in the table.		✓	
(e) The applicant must install each fire sprinkler system listed in the table so that the system is configured as specified in the table.		✓	✓
(f) The applicant must ensure that the central cooling system for a cooling tower is configured as specified in the table.		✓	✓

Common area	Showerheads rating	Toilets rating	Taps rating	Clothes washers rating
All common areas	no common facility	4 star	4 star	no common laundry facility

Central systems	Size	Configuration	Connection (to allow for...)
Central water tank - rainwater or stormwater (No. 1)	25000.0	To collect run-off from at least: - 500.0 square metres of roof area of buildings in the development - 0.0 square metres of impervious area in the development - 0.0 square metres of garden/lawn area in the development - 0.0 square metres of planter box area in the development (excluding, in each case, any area which drains to, or supplies, any other alternative water supply system).	- irrigation of 125.0 square metres of common landscaped area on the site

(ii) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a ventilation system to service a common area specified in the table below, then that ventilation system must be of the type specified for that common area, and must meet the efficiency measure specified.		✓	✓
(b) In carrying out the development, the applicant must install, as the "primary type of artificial lighting" for each common area specified in the table below, the lighting specified for that common area. This lighting must meet the efficiency measure specified. The applicant must also install a centralised lighting control system or Building Management System (BMS) for the common area, where specified.		✓	✓
(c) The applicant must install the systems and fixtures specified in the "Central energy systems" column of the table below. In each case, the system or fixture must be of the type, and meet the specifications, listed for it in the table.	✓	✓	✓

Common area	Common area ventilation system		Common area lighting		
	Ventilation system type	Ventilation efficiency measure	Primary type of artificial lighting	Lighting efficiency measure	Lighting control system/BMS
Lift car (No.1)	-	-	light-emitting diode	connected to lift call button	No
Lift car (No.2)	-	-	light-emitting diode	connected to lift call button	No
Main Switch Room	ventilation exhaust only	interlocked to light	light-emitting diode	manual on / manual off	No
Residential Bin Room	ventilation exhaust only	-	light-emitting diode	motion sensors	No
Community Hub	ventilation (supply + exhaust)	time clock or BMS controlled	light-emitting diode	daylight sensor and motion sensor	No
Community Room	no mechanical ventilation	-	light-emitting diode	daylight sensor and motion sensor	No
Bike Workshop	no mechanical ventilation	-	light-emitting diode	motion sensors	No
Comms Room	ventilation exhaust only	interlocked to light	light-emitting diode	manual on / manual off	No
Chamber Substation	ventilation exhaust only	interlocked to light	light-emitting diode	manual on / manual off	No
Fire Control Room	no mechanical ventilation	-	light-emitting diode	manual on / manual off	No
Gas Cupboard	ventilation exhaust only	interlocked to light	light-emitting diode	manual on / manual off	No
RWT/CW Pump	ventilation exhaust only	interlocked to light	light-emitting diode	manual on / manual off	No
RW Re-Use Tank	no mechanical ventilation	-	light-emitting diode	motion sensors	No
RWT	no mechanical ventilation	-	light-emitting diode	motion sensors	No
OSD	no mechanical ventilation	-	light-emitting diode	motion sensors	No

	Common area ventilation system		Common area lighting		
Common area	Ventilation system type	Ventilation efficiency measure	Primary type of artificial lighting	Lighting efficiency measure	Lighting control system/BMS
Pump Room	ventilation exhaust only	interlocked to light	light-emitting diode	manual on / manual off	No
Bicycle Storage	no mechanical ventilation	-	light-emitting diode	motion sensors	No
Fire Stair	ventilation exhaust only	time clock or BMS controlled	light-emitting diode	motion sensors	No
Store	no mechanical ventilation	-	light-emitting diode	motion sensors	No
Lift Lobby	no mechanical ventilation	-	light-emitting diode	daylight sensor and motion sensor	No
Corridors	no mechanical ventilation	-	light-emitting diode	daylight sensor and motion sensor	No
LV1-17 Hallway	no mechanical ventilation	-	light-emitting diode	daylight sensor and motion sensor	No

Central energy systems	Type	Specification
Lift (No. 1)	gearless traction with V V V F motor	Number of levels (including basement): 18
Lift (No. 2)	gearless traction with V V V F motor	Number of levels (including basement): 18

4. Commitments for common areas and central systems/facilities for the development (non-building specific)

(b) Common areas and central systems/facilities

(i) Water	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a showerhead, toilet, tap or clothes washer into a common area, then that item must meet the specifications listed for it in the table.		✓	✓
(b) The applicant must install (or ensure that the development is serviced by) the alternative water supply system(s) specified in the "Central systems" column of the table below. In each case, the system must be sized, be configured, and be connected, as specified in the table.	✓	✓	✓
(c) A swimming pool or spa listed in the table must not have a volume (in kLs) greater than that specified for the pool or spa in the table.	✓	✓	
(d) A pool or spa listed in the table must have a cover or shading if specified for the pool or spa in the table.		✓	
(e) The applicant must install each fire sprinkler system listed in the table so that the system is configured as specified in the table.		✓	✓
(f) The applicant must ensure that the central cooling system for a cooling tower is configured as specified in the table.		✓	✓

Common area	Showerheads rating	Toilets rating	Taps rating	Clothes washers rating
All common areas	no common facility	4 star	4 star	no common laundry facility

(ii) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a ventilation system to service a common area specified in the table below, then that ventilation system must be of the type specified for that common area, and must meet the efficiency measure specified.		✓	✓
(b) In carrying out the development, the applicant must install, as the "primary type of artificial lighting" for each common area specified in the table below, the lighting specified for that common area. This lighting must meet the efficiency measure specified. The applicant must also install a centralised lighting control system or Building Management System (BMS) for the common area, where specified.		✓	✓
(c) The applicant must install the systems and fixtures specified in the "Central energy systems" column of the table below. In each case, the system or fixture must be of the type, and meet the specifications, listed for it in the table.	✓	✓	✓

Central energy systems	Type	Specification
Alternative energy supply	Photovoltaic system	Rated electrical output (min): 50.0 peak kW

Notes

1. In these commitments, "applicant" means the person carrying out the development.
2. The applicant must identify each dwelling, building and common area listed in this certificate, on the plans accompanying any development application, and on the plans and specifications accompanying the application for a construction certificate / complying development certificate, for the proposed development, using the same identifying letter or reference as is given to that dwelling, building or common area in this certificate.
3. This note applies if the proposed development involves the erection of a building for both residential and non-residential purposes (or the change of use of a building for both residential and non-residential purposes). Commitments in this certificate which are specified to apply to a "common area" of a building or the development, apply only to that part of the building or development to be used for residential purposes.
4. If this certificate lists a central system as a commitment for a dwelling or building, and that system will also service any other dwelling or building within the development, then that system need only be installed once (even if it is separately listed as a commitment for that other dwelling or building).
5. If a star or other rating is specified in a commitment, this is a minimum rating.
6. All alternative water systems to be installed under these commitments (if any), must be installed in accordance with the requirements of all applicable regulatory authorities. NOTE: NSW Health does not recommend that stormwater, recycled water or private dam water be used to irrigate edible plants which are consumed raw, or that rainwater be used for human consumption in areas with potable water supply.

Legend

1. Commitments identified with a "✔" in the "Show on DA plans" column must be shown on the plans accompanying the development application for the proposed development (if a development application is to be lodged for the proposed development).
2. Commitments identified with a "✔" in the "Show on CC/CDC plans and specs" column must be shown in the plans and specifications accompanying the application for a construction certificate / complying development certificate for the proposed development.
3. Commitments identified with a "✔" in the "Certifier check" column must be certified by a certifying authority as having been fulfilled. (Note: a certifying authority must not issue an occupation certificate (either interim or final) for a building listed in this certificate, or for any part of such a building, unless it is satisfied that each of the commitments whose fulfilment it is required to monitor in relation to the building or part, has been fulfilled).