



(10/10/25)

TO WHO IT MAY CONCERN

The Five at Heart Arc bike racks are designed to comply with the Australian Standard for bicycle parking (AS2890.3–2015).

Key design features and recommended spacings ensure that the racks meet the requirements outlined by AS2890.3–2015 and in particular Section 3.3 for dynamic parking...

- Each unit is offset by 300mm so the adjacent bike handlebars are not in alignment.
- Units are movable which creates the minimum bicycle footprint of 500mm.
- Movable lock bars so cyclists can access and lock their bicycle.
- A 2000mm aisle is to be provided in front of the bike rack.
- As per the dynamic spacing requirements, each unit is to be spaced at 400mm.
- 2700mm clearance height required.

Five at Heart prioritises quality over quantity and emphasises adherence to Australian Standards as best practice, ensuring the highest level of user experience. This statement confirms that the Five at Heart Arc product will comply with Australian Standards, provided it is laid out and installed in as per the requirements.

Please note that this does not constitute a sign-off confirming that the overall bike room design complies with the Standards.

Kind regards,

A handwritten signature in black ink that reads 'Josh Kimberley'.

Josh Kimberley
Design Manager