

REPORT:

ARBORICULTURAL ASSESSMENT

**Sydney Olympic Park
Site 13**

**Cnr Olympic Boulevard & Sarah Durack Avenue
Homebush NSW**

Prepared 10 June 2008
Reference 10261

Contents

	page
Summary	3
1.0 Introduction	4
2.0 Aims & Objectives	5
3.0 Methodology	6
4.0 Pruning Standards	7
5.0 Tree Assessments	8
• Assessment of tree/s or stand/s of trees	
• Observations	
• Discussions	
6.0 Conclusion	15
7.0 Recommendations	15
References	16
Disclaimer	16
<u>Tables</u>	
1.0 General description of trees.	3
2.0 Schedule of works and trees effected.	3
3.0 Tree Protection Zone fencing locations	12

Appendices

Appendix A	UTM Rating System for Tree Significance
Appendix B	Modified extract from British Standard BS 5837: 1991 Guide for “Trees in relation to construction.” Minimum distances for protective fencing around trees
Appendix C	Matrix - Sustainable Retention Index Value (S.R.I.V.), (IACA) 2005 ©
Appendix D	Tree Protection Zones - Standard Procedure
Appendix E	Tree Protection on Construction Sites
Appendix F	Extract from British Standard BS 5837: 1991 Guide for “Trees in relation to construction.” Scaffolding within a protected area
Appendix G	Glossary of terminology
Appendix H	Site Plan A - Survey of Subject Trees
Appendix I	Site Plan B - UTM Tree Protection Plan

SUMMARY

This report considers a total of twenty (20) trees, which were assessed as part of the proposed development. The trees are a monoculture stand of *Araucaria cunninghamii* - Hoop Pine.

The trees form part of an avenue planting along the Olympic Boulevard and are considered highly significant due to the prominence by their canopy when viewed from various directions and their cultural associations with the Sydney Olympics.

All trees are proposed to be retained in situ; Trees 1 -11 may be directly impacted by the proposed development, however the trees can be protected and the impact ameliorated by special construction works, Tree 12 -20 have suitable set backs provided and will not be impacted by the proposed works.

The general condition of each tree/s is listed in Table 1.0 a summary of works in Table 2.0 and minimum setbacks for protective fencing from development works per tree to be retained is summarized in Table 3.0.

Table 1.0 General condition of trees. Trees are described in greater detail in section 5.0.

UTM Tree No.	Genus and species	Common name	Condition G = Good F = Fair P = Poor D = Dead
1	<i>Araucaria cunninghamii</i>	Hoop Pine	G
2	<i>Araucaria cunninghamii</i>	Hoop Pine	G
3	<i>Araucaria cunninghamii</i>	Hoop Pine	G
4	<i>Araucaria cunninghamii</i>	Hoop Pine	G
5	<i>Araucaria cunninghamii</i>	Hoop Pine	G
6	<i>Araucaria cunninghamii</i>	Hoop Pine	G
7	<i>Araucaria cunninghamii</i>	Hoop Pine	G
8	<i>Araucaria cunninghamii</i>	Hoop Pine	G
9	<i>Araucaria cunninghamii</i>	Hoop Pine	G
10	<i>Araucaria cunninghamii</i>	Hoop Pine	G
11	<i>Araucaria cunninghamii</i>	Hoop Pine	G
12	<i>Araucaria cunninghamii</i>	Hoop Pine	G
13	<i>Araucaria cunninghamii</i>	Hoop Pine	G
14	<i>Araucaria cunninghamii</i>	Hoop Pine	G
15	<i>Araucaria cunninghamii</i>	Hoop Pine	G
16	<i>Araucaria cunninghamii</i>	Hoop Pine	G
17	<i>Araucaria cunninghamii</i>	Hoop Pine	G
18	<i>Araucaria cunninghamii</i>	Hoop Pine	G
19	<i>Araucaria cunninghamii</i>	Hoop Pine	G
20	<i>Araucaria cunninghamii</i>	Hoop Pine	G

Table 2.0 Schedule of works and trees affected. Trees are described in greater detail in section 5.0.

UTM Tree No.	Common name	Description of work to be done
1-11	Hoop Pine	Retain and protect within a Tree Protection Zone. See Tree Protection Plan for additional protection.
12-20	Hoop Pine	Retain and protect within a Tree Protection Zone, suitable set backs provided.

1.0 INTRODUCTION

URBAN TREE MANAGEMENT © has prepared this report for Mr Mark Collison of AV Jennings, on behalf of OD Partnership Pty Limited (*the applicant*).

The site is subject to the *Sydney Regional Environmental Plan No 24 – Homebush Bay Area (SREP 24)* in accordance with the Sydney Olympic Park Master Plan and this report and any works recommended herein, that require approval from the consenting authority, is provided for as part of that consideration.

The subject site, known as Lot 201, D.P. 1041756 - Site 13, Cnr Olympic Parade and Sarah Durack Avenue, Homebush (*the site*) currently consists of a bus stop and parking area surrounded by planted landscapes. The proposed development consists of a five (5) storey commercial office building with a basement carpark.

Mr Laurie Dorfer (*the author*) attended *the site* on Tuesday 10 June 2008 and the trees and their growing environment were examined.

The proposed building design and its configuration and infrastructure were arrived at prior to the undertaking of an arboricultural assessment of the trees on the site to determine their significance by URBAN TREE MANAGEMENT ©.

The trees are indicated in Appendix H & I – Survey of Subject Trees & Tree Protection Plan. This report has relied upon the following plan/s/reports:

- Survey Plan, by Craig & Rhodes, Ref: 233-06, Sheet 1 Of 2, dated Dec 2006.
- Architectural Design Report, by Batessmart, Project No. S10649, dated 5 March 2008.

2.0 AIMS & OBJECTIVES

Aims

Detail the condition of the tree/s on the site or on adjoining properties where such trees may be affected by the proposed works. This will be undertaken by assessment of individual specimens or stands, and indicate remedial works or protection measures for their retention in a safe and healthy condition, or a condition not less than that at the time of initial inspection for this report, or in a reduced but sustainable condition due to the impact of the development. Where possible expected impacts will be ameliorated through tree protection measures able to be applied, and will consider the location and condition of the trees in relation to the proposed building works, or recommend removal and replacement where appropriate.

Provide as an outcome of the assessment, the following: a description of the trees, observations made, discussion of the effects the location of the proposed building works may have on the trees, and make recommendations required for remedial or other works to the trees, if and where appropriate.

Determine from the assessment a description of the works or measures required to ameliorate the impact upon the trees to be retained, by the proposed building works or future impacts the trees may have upon the new building works if and where appropriate, or the benefits of removal and replacement if appropriate for the medium to long term safety and amenity of the site.

Objectives

Assess the condition of the subject tree/s.

Determine impact of development on the subject tree/s.

Provide recommendations for retention or removal of the subject tree/s.

Provide specifications for protection of tree/s to be retained.

Provide recommendations for replacement tree/s where appropriate.

3.0 METHODOLOGY

Note: Individual methodologies applied as applicable.

- 3.1 The method of assessment of tree/s applied is adapted from the principles of visual tree assessment undertaken from the ground, which considers:
 1. Tree health and subsequent stability, both long and short term
 2. Sustainable Retention Index Value (SRIV) (IACA 2005)©
 3. Hazard potential to people and property
 4. Amenity values
 5. Habitat values
 6. Significance
- 3.2 This assessment is undertaken using standard tree assessment criteria for each tree based on the values above and is implemented as a result of at least one comprehensive and detailed site inspection to undertake a visual tree assessment of each individual tree, or stand of trees, or a representative population sample.
- 3.3 Any dimensions recorded as averages, or by approximation are noted accordingly.
- 3.4 In the absence of an appropriate Australian Standard for the protection of trees on development sites, the British Standard BS 5837 – 1991 Guide for “Trees in relation to construction” is applied by UTMA P/L and was used in this report to provide tree protection setback methodology because its methodology is similar to that proposed by the draft Australian Standard AS4837 “Guide for the planning and protection of trees on development sites” as a point of reference and guide for the recommended minimum clearances from the centre of tree’s trunk to development works and is applied as a generalized benchmark and the distances may be increased or decreased by the author as a result of other factors providing mitigating circumstances or constraints as indicated by but not restricted to the following:
 1. Condition of individual trees,
 2. Tolerance of individual species to disturbance,
 3. Geology e.g. physical barriers in soil, rock floaters, bedrock to surface
 4. Topography e.g. slope, drainage,
 5. Soil e.g. depth, drainage, fertility, structure,
 6. Microclimate e.g. due to landform, exposure to dominant wind,
 7. Engineering e.g. techniques to ameliorate impact on trees such as structural soil, gap graded fill, lateral boring,
 8. Construction e.g. techniques to ameliorate impact on trees such as pier and beam, bridge footings, suspended slabs,
 9. Root mapping,
 10. Physical limitations - existing modifications to the environment and any impact to tree/s by development e.g. property boundaries, built structures, houses, swimming pools, road reserves, utility services easements, previous impact by excavation, or construction in other directions, soil level changes by cutting or filling, existing landscaping works within close proximity, modified drainage patterns,
 11. Extraneous factors e.g. potential future impacts from development on adjoining land when the tree is located on or near to a property boundary.

- 3.5 Trees in groups may be referred to as stands and a stand may exclusively contain specimens to be either retained or removed or a combination of both. A stand may be used to discuss all the trees on a given site to expedite their assessment, or refer to trees growing proximate to one another or within a defined space. Stands may be comprised by mass boundary or screen plantings, to form a group of the same or a mixture of taxa. Each stand is considered as a single unit with each component tree assessed and expressed in tabular form, or indicated by a given percentage as a population sample of each stand. Where it is appropriate for a stand of trees to be retained in full or part, the location and setback of Tree Protection Zone fences or works, are prescribed to provide for the preservation of the stand or selected component trees, in a condition not less than that at the time of initial inspection for its incorporation into the landscape works for the site, or in a reduced but sustainable condition due to the impact of the development but ameliorated through tree protection measures.
- 3.6 The trees/s have been allocated a significance rating as determined by the UTM Rating Systems for Tree Significance – Appendix A which allows the retention value to be determined.

4.0 TREE PRUNING STANDARDS

- 4.1 Any pruning recommended in this report is to be to the Australian Standard® AS4373 'Pruning of amenity trees', and conducted in accordance with the NSW Work Cover Authority Code of Practice for the Amenity Tree Industry, 1998.
- 4.2 All pruning or removal works are to be in accordance with the appropriate Tree Management Policy where applicable, or Tree Management Order (TMO), or Tree Preservation Order (TPO).
- 4.3 Tree maintenance work is specialised and in order to be undertaken safely to ensure the works carried out are not detrimental to the survival of a tree being retained, and to assist in the safe removal of any tree, should be undertaken by a qualified arboriculturist with appropriate competencies recognised within the Australian Qualification Framework, with a minimum of 5 years of continual experience within the industry of operational amenity arboriculture, and covered by appropriate and current types of insurance to undertake such works.

5.0 TREE ASSESSMENT

5.1 Assessment of tree/s or stand/s of trees.

Tree No	Genus & species / Common Name	Age Y = Young M = Mature O = Over-mature	Condition G = Good F = Fair P = Poor D = Dead	Crown Form D = Dominant C = Co-dominant I = Intermediate S = Suppressed F = Forest E = Emergent	Ht. Approx. metres	Crown spread approx. metres / Orientation R = Radial, or other	Crown Symmetry 1 = symmetrical 2 = asymmetrical / Orientation	Crown cover / Crown density % / D = dormant	DBH in mm @ 1.4m, or other, as indicated / trunk orientation other than R = radial, e.g. N/S	Trunk Lean 1. = Upright-Slight 2. = Moderate 3. = Severe 4. = Critical. 5. = Acaulescent / Orientation / ST = Static P = Progressive Sc = self-correcting	Roots evident @ root crown 1. = None 2. = Adventitious 3. = Basal Flare 4. = Buttresses 5. = First Order Roots (FOR), No. & distribution e.g. R = radial, or one each to N, S, E, NE and W	Pests & diseases 1 = No or 2 = Yes (If 2. see comments)	Branch Bark included 1 = No or 2 = Yes or 3 = N/A	Vigour 1 = Normal Vigour 2 = Low Vigour	Form 1 = Good form 2 = Poor form	SRIV Age, Vigour, Condition/ Index Rating Estimated Life Expectancy 1. Long 2. Medium 3. Short	
1	Araucaria cunninghamii Hoop Pine	Y	G	D	10	4x4	1	90	200	1.		1.	1.	1.	1.	1.	YNVG-9
						R		90	R								1
2	Araucaria cunninghamii Hoop Pine	Y	G	D	8	4x4	1	90	200	1.		1.	1.	1.	1.	1.	YNVG-9
						R		90	R								1
3	Araucaria cunninghamii Hoop Pine	Y	G	D	11	4x4	1	90	210	1.		1.	1.	1.	1.	1.	YNVG-9
						R		90	R								1
4	Araucaria cunninghamii Hoop Pine	Y	G	D	11	4x4	1	90	220	1.		1.	1.	1.	1.	1.	YNVG-9
						R		90	R								1
5	Araucaria cunninghamii Hoop Pine	Y	G	D	10	4x4	1	90	220	1.		1.	1.	1.	1.	1.	YNVG-9
						R		90	R								1
Tree No.	Comments																
1	-																
2	Apical meristem removed at 8m																
3	-																
4	-																
5	-																

5.1 Assessment of tree/s or stand/s of trees. Continues

[illegible]

5.1 Assessment of tree/s or stand/s of trees. Continues

Tree No	Genus & species / Common Name	Age Y = Young M = Mature O = Over-mature	Condition G = Good F = Fair P = Poor D = Dead	Crown Form D = Dominant C = Co-dominant I = Intermediate S = Suppressed F = Forest E = Emergent	Ht. Approx. metres	Crown spread approx. metres / Orientation R = Radial, or other	Crown Symmetry 1 = symmetrical 2 = asymmetrical / Orientation	Crown cover / Crown density % / D = dormant	DBH in mm @ 1.4m, or other, as indicated / trunk orientation other than R = radial, e.g. N/S	Trunk Lean 1. = Upright-Slight 2. = Moderate 3. = Severe 4. = Critical. 5. = Acaulescent / Orientation / ST = Static P = Progressive Sc = self-correcting	Roots evident @ root crown 1. = None 2. = Adventitious 3. = Basal Flare 4. = Buttresses 5. = First Order Roots (FOR), No. & distribution e.g. R = radial, or one each to N, S, E, NE and W	Pests & diseases 1 = No or 2 = Yes (If 2. see comments)	Branch Bark included 1 = No or 2 = Yes or 3 = N/A	Vigour 1 = Normal Vigour 2 = Low Vigour	Form 1 = Good form 2 = Poor form	SRIV Age, Vigour, Condition/ Index Rating Estimated Life Expectancy 1. Long 2. Medium 3. Short	
11	<i>Araucaria cunninghamii</i> Hoop Pine	Y	G	D	11	4x4	1	90	220	1.	1.	1.	1.	1.	1.	1.	YNVG-9
						R		90	R	1							
12	<i>Araucaria cunninghamii</i> Hoop Pine	Y	G	D	10	4x4	1	90	220	1.	1.	1.	1.	1.	1.	1.	YNVG-9
						R		90	R	1							
13	<i>Araucaria cunninghamii</i> Hoop Pine	Y	G	D	10	4x4	1	90	230	1.	1.	1.	1.	1.	1.	1.	YNVG-9
						R		90	R	1							
14	<i>Araucaria cunninghamii</i> Hoop Pine	Y	G	D	10	4x4	1	90	230	1.	1.	1.	1.	1.	1.	1.	YNVG-9
						R		90	R	1							
15	<i>Araucaria cunninghamii</i> Hoop Pine	Y	G	D	11	4x4	1	90	220	1.	1.	1.	1.	1.	1.	1.	YNVG-9
						R		90	R	1							
Tree No.	Comments																
11	-																
12	-																
13	-																
14	-																
15	-																

5.1 Assessment of tree/s or stand/s of trees. Continues

[illegible]

Observations

- 5.2 Two linear, monoculture planted stands, indigenous and evergreen specimens which form part of the broader streetscape. The trees line the road and a pedestrian path which runs parallel with Olympic Boulevard.
- 5.3 The trees are all young specimens, approximately 10-12 years old, planted during the lead up to the Sydney Olympics.
- 5.4 The trees are situated within allocated planted areas immediately surrounded by mulch and intercepted by turf crossings.
- 5.5 Additional trees were observed at the centre of *the site* which were identified as young *Corymbia citriodora* – Lemon Scented Gums. These trees will be required to be removed to accommodate the proposed development. They did not form part the brief for this report and were therefore not assessed.
- 5.6 The stands of *Corymbia citriodora* – Lemon Scented Gum, *Casuarina cunninghamiana* – River She-Oak and *Platanus x hispanica* – London Plane Tree which form part of the landscaping within the adjacent sports centre (See Appendix G - Survey of Subject Tree/s) have suitable set backs and will not be impacted by the proposed works. They also did not form part the brief for this report and were therefore not assessed.

Tree Significance

- 5.7 See Appendix A for Tree Significance - Assessment Criteria. The trees are considered high significance due mainly for their prominence within the stand and cultural associations with the Sydney Olympics.

Significant Trees for *the site (the trees)* as established by URBAN TREE MANAGEMENT © using the **UTM Ratings System**.

Significant Scale

1 – High

2 – Medium

3 – Low

4 – Environmental Pest/Noxious Weed

5 – Hazardous

Significance Scale	1	2	3	4	5
UTM Tree No.	1-20				

Tree Retention Value

- 5.7 See Appendix A for Retention Value – Priority Matrix.

Retention Value

High – Priority for Retention

Medium – Consider for Retention

Low – Consider for Removal

Remove - Priority for Removal

Retention Value	High Priority for Retention	Medium Consider for Retention	Low Consider for Removal	Remove Priority for Removal
UTM Tree No.	1-20			

Discussion

- 5.8 Trees 1-20 are proposed to be retained in situ and all incorporated into the construction works for the site. The proposed design and its configuration may directly impact on trees 1-11; however this can be ameliorated by implementing special construction techniques. Trees 12-20 have suitable set backs provided with no adverse impact expected. All trees to be retained are to be incorporated into the construction works for the site with Tree Protection Zones provided as shown in Table 3.0 below.

Table 3.0 This table applies only to trees being retained. Tree Protection Zone fencing locations are measured from the centre of each tree with the actual distances for the side closest to the building/ construction works e.g. excavation shown (see explanatory notes below). Tree Protection Zone fences and setbacks where applicable are indicated in Appendix A.

1. Tree No.	2. Trunk Diameter (See Section 5) (mm)	3. Age of tree Y = Young M = Mature O = Over- mature (Senescent)	4. Tree Vigour Normal Vigour = 1 or Low Vigour = 2	5. British Standard BS 5837:1991 Recommended distance per DBH in metres (see Appendix C) (m)	6. Reduced distance by British Standard (one third on one side only) (m)	7. Actual Distance from tree to proposed construction works. (m)
1-11	200-240	Y	1	3	2	2.8
12-20	200-240	Y	1	3	2	11.5

Explanatory notes for Table 3.0.

This table is based upon British Standard BS 5837: 1991 Guide for "Trees in relation to construction" (Appendix B) for suitable set backs (**British Standard - Column 5**). However, these set backs can be reduced by up to one third on one side only while retaining suitable set backs in other directions (**Reduced - Column 6**). The final column (**Actual - Column 7**) provides the set backs as provided by the proposed construction works.

- 5.9 Trees 1 & 11 –The basement car park is situated at 2.8m from the centre of the trees. An expected set back by excavation should be no less than 2.5m, which would accommodate minor over excavation and the drying affect of the soil profile. With the species medium tolerance to development and a set back greater then the reduced set back on one side (Table 3-Column 6), the trees should not be adversely affected.
- 5.10 The deep excavation proposed for the carpark should be piled by shord excavation. Attempts should be made to maintain a 2.8m set back, with a 2.5m being a minimum set back due to their medium tolerance. No batter slope or benching should be undertaken during excavation.
- 5.11 The Tree Protection Zone fencing set back adjacent to Trees 1-11, closest to the works should be maintained at 2.5m during the basement construction. At commencement of above ground construction, the TPZ fencing should be reduced to 1.5m to allow for construction access and scaffolding to be undertaken (See Appendix E & F). However, the ground surface is to be covered with metal or timber sheeting within the TPZ to displace loads whereby compaction is minimised. Sand is to be used to level undulations in grade with geotextile fabric placed on top.

- 5.12 The trees current crown overhang reaches approximately 2m-2.5m at the lower crowns, and taper off as the height increases due to their typical conical shape. During scaffold construction, the distal section of the branches in conflict should be tie back to prevent mechanical or abrasion wounds. Pruning should be avoided as the tree shape can easily be adversely altered. The flexibility in the branch should allow enough clearance, however if pruning becomes unavoidable, this should be undertaken in consultation with the Consulting Arboriculturist.
- 5.13 Branches may be secured back using 50mm hessian tie, in a figure eight arrangement between the branch and/or trunk. The distal and proximal ends of the ties are to be secured around a junction or if this is not feasible, rapped around the branch/trunk above and below the bracing point three times providing a cross formation to prevent the tie from slipping.
- 5.14 As the trees mature, conflict will occur with the building. Ongoing pruning will be required as the branches encroach the vertical fins. The reduced branching structure limits the pruning methods employed; all foliage is situated distally. Generally, only selective pruning of entire branches back to the collar region at the trunk can be carried out. Condition and vigour should not be affected; however, the crown shape towards the building will be altered.
- 5.15 Pruning should be undertaken regularly and only in small percentages at any one time.
- 5.16 Trees 12 & 20 - No direct impact is expected by the proposed development works. All works proposed are outside the recommended Tree protection Zones.

Tree Protection Works – Specific

Prior to excavation

- 5.17 Tree Protection Zones (TPZ) including fencing, are to be installed with set backs as detailed in Table 3 and Appendix I -Tree Protection Plan. A 2.5m set back should be provided for Trees 1-11 on the side closet to works.
- 5.18 All trees at the centre of the site within or proximate to the proposed building envelope should be removed.

During excavation

- 5.19 Excavation adjacent to Trees 1-11 should be piled by shord excavation. No batter slope or benching should be undertaken during excavation.
- 5.20 Where structural woody roots (roots >20 mm diameter) are encountered, these are to be cut cleanly by hand to undamaged woody tissue. This will promote continued root growth and minimise infestation by decay pathogens.

During Construction

- 5.21 Tree Protection Zone fencing adjacent to Trees 1-11 may be reduced to 1.5m to allow for construction access and scaffolding to be undertaken.
- 5.22 The ground surface between the TPZ fencing and excavation works is to be protected by covering with metal or timber sheeting to displace loads whereby minimising compaction. Sand is to be used to level undulations in grade with geotextile fabric placed on top.
- 5.23 For adequate scaffold clearance, some branches at the lower crowns may be required to be tie back using 50mm hessian tie. Pruning should be avoided, however if it becomes unavoidable, this should be undertaken in consultation with the Consulting Arboriculturist.
- 5.24 No utility services are to be located within the TPZ's (above and below ground). Where locating of such services is unavoidable it should only be undertaken in consultation with a Consulting Arboriculturist. Alternatively, for underground services within the TPZ, installation can be carried out by horizontal direction drilling beneath the root plate at a minimum depth of 800mm (See Part 1.2.1 of Appendix E). No open excavation should occur within the TPZ of any tree to be retained. Reason: Prevent impact on trees by the removal of roots during open excavation.

Post construction

- 5.25 Tree Protection Zone fencing should be removed to allow for landscaping to be undertaken.
- 5.26 All hessian ties should be removed, with all branches secured back allowed to regain their original positioning.

Tree Protection Works - General

- 5.27 The Tree Protection Zone for each tree is to be incorporated into the construction works for the site and the protection fencing to be located as indicated in Appendix I – Tree Protection Plan.
- 5.28 Tree Protection Zones are to be constructed as described here and detailed in Appendix D, and in Appendix I. The trees will be sustained within the constraints of the modifications to the site by development works. Attention is drawn specifically to Appendix E for the protection of all trees to be retained and particular parts as indicated being 1.0, 1.2.1, 1.2.2, 1.3.2, and 1.4.1.1.
- 5.29 Trees 1-20 are to be retained and protected and incorporated into landscape works for the site, and their Tree Protection Zone fencing and works to be marked accordingly on the Landscape Plan, where appropriate.

6.0 CONCLUSION

This report has examined twenty (20) trees adjacent to *the site* and considers the retention of all.

The trees to be retained are to be protected through the implementation of adequate measures for their integration into the development by the application of appropriate technology as detailed in the recommendations of this report.

If all the recommendations and procedures detailed herein are adhered to the tree/s subject of this report will remain stable and viable, continuing to develop as important landscape component/s providing elements of long term amenity for the property and its owners or occupants, and the local community.

The recommendations made in this report are subject to approval by the consent authority.

7.0 RECOMMENDATIONS

- 7.1 Trees 1-20 are to be retained in situ and protected as detailed in 5.8-5.29, and section 4.0, and Appendices D and E. Tree protection fences and/or works are to be located in accordance with Appendix I – Tree Protection Plan.
- 7.2 Where Tree Protection Zone fences are to be moved or relocated, additional to the this report, this must be undertaken in consultation with the Consulting Arboriculturist to ensure that tree protection is maintained.
- 7.4 Where structural woody roots with a diameter of 20mm or greater are to be pruned, these are to be cut cleanly to undamaged woody tissue.
- 7.5 Deep excavation adjacent to Trees 1-11 should be piled by shord excavation as detailed in 5.10. No batter slope or benching should be undertaken.
- 7.6 Scaffolding is to undertaken as detailed in 5.11.
- 7.7 Branches should be secured back as detailed in 5.13 for scaffold clearance.
- 7.8 No utility services are to be located within the TPZ's (above and below ground). Where locating of such services is unavoidable it should only be undertaken in consultation with a Consulting Arboriculturist.



Laurie Dorfer
Senior Consultant
Urban Tree Management Australia P/L

REFERENCES

1. British Standards Institution 1991, *British Standard 5837 Guide for Trees in relation to construction*, British Standards Institution, London, UK.
2. IACA 2005, Sustainable Retention Index Value, *Institute of Australian Consulting Arboriculturists*, Australia, www.iaca.org.au .
3. Matheny N & Clark JR 1998, *Trees and Development - a Technical guide to Preservation of Trees during Land Development*, International Society of Arboriculture, IL 61826-3129 USA.
4. Standards Australia 2007, *Australian Standard 4373 Pruning of amenity trees*, Standards Australia, Sydney, Australia.
5. Work Cover NSW 1998, *Code of Practice for the Amenity Tree Industry*, New South Wales Government, Australia.

DISCLAIMER

The author and Urban Tree Management take no responsibility for actions taken and their consequences, contrary to those expert and professional instructions given as recommendations pertaining to safety by way of exercising our responsibility to our client and the public as our duty of care commitment, to mitigate or prevent hazards from arising, from a failure moment in full or part, from a structurally deficient or unsound tree or a tree likely to be rendered thus by its retention and subsequent deterioration from modification/s to its growing environment either existing or proposed, either above or below ground, contrary to our advice.

Appendix A

UTM Rating System for Tree Significance

The significance of a tree is highly subjective and difficult to ascertain in a consistent and repetitive fashion. However, it is necessary to determine a rating to assist in determining the retention value for each tree. URBAN TREE MANAGEMENT © has developed a significance rating whereby the retention values can be determined.

Many variables can be taken into consideration by individuals undertaking assessments which include but are not limited to; exposure of location, contribution as a component of the overall landscape for amenity or aesthetic qualities, importance due to uniqueness of taxa for species, subspecies, variety, form, or as an historical or cultural planting, or for age, or substantial dimensions, or habit, or as remnant vegetation, or habitat potential, or a rare or threatened species, or uncommon in cultivation, or of Aboriginal cultural importance, or is a commemorative planting. *Note: Where a tree is considered significant this must be expressed clearly and defined by a methodology and balanced against diminishing factors such as nuisance, as any tree will be of some significance but not every tree can be significant.*

Once the actual significance of an individual tree has been defined by the criteria, the retention value can then be determined (Table 1.0 in this Appendix).

Tree Significance - Assessment criteria

1. High Significance in landscape

- The tree is in good condition, or normal vigour and form typical of the species,
- The tree is a remnant or is a planted locally indigenous specimen and/or is rare or uncommon in the local area or of botanical interest or of grand age.
- The tree is listed as a Heritage Item, Threatened Species or part of a Threatened Community or listed on Councils significant Tree Register.
- The tree is visually prominent and visible from a considerable distance when viewed from most directions within the landscape by bulk and scale and makes a positive contribution to the local amenity.
- The tree has been influenced by historic figures, events or part of the heritage development of the place.
- The tree supports social and cultural sentiments or spiritual associations, reflected by the broader population or community group or has commemorative values.
- The growing environment supports the tree to its full dimensions above and below ground without conflict or constraint.

2. Medium Significance in landscape

- The tree is in fair-good condition, or normal or low vigour and form typical or atypical of the species,
- The tree is a planted locally indigenous or a common species with its taxa readily planted in the local area,
- The tree is visible from surrounding properties, although not visually prominent as partially obstructed by other vegetation or buildings when viewed from the street,
- The tree provides a fair contribution to the visual character and amenity of the area,
- The tree is moderately constrained by above or below ground influences of the built environment to reach full dimensions.

3. Low Significance in landscape

- The tree is in fair-poor condition, or normal or low vigour and form typical or atypical of the species,
- The tree is not visible or is partly from surrounding properties as obstructed by other vegetation or buildings.
- The tree provides a minor contribution or has a negative impact on the visual character and amenity of the area.
- The tree is severely constrained by above or below ground by influences of the built environment and therefore will not reach full dimensions; tree is inappropriate to the site conditions.
- The tree is listed as exempt under the provisions of the local Council Tree Preservation Order.
- The tree has a wound or defect that has potential to become structurally unsound.

4. Environmental Pest/Noxious Weed Species

- The tree is an Environmental Pest Species due to its invasiveness or poisonous/ allergenic properties.
- The tree is a declared noxious weed by legislation.

5. Hazardous/Irreversible Decline

- The tree is structurally unsound and/or unstable and is considered potentially dangerous.
- The tree is dead, or is in irreversible decline, or has the potential to fail or collapse in full or part in the immediate to short term.

The tree is to correspond with at least three (3) of the criteria in categories 1, 2 and 3, and one (1) criteria only is required in categories 4 and 5 to be classified in that group.

Note: The assessment criteria are for individual trees only and are not to be applied to stands of trees.

Table 1.0 Tree Retention Value - Priority Matrix.

	Tree Significance				
Estimated Life Expectancy	1. High Significance in Landscape	2. Medium Significance in Landscape	3. Low Significance in Landscape	4. Environmental Pest / Noxious Weed Species	5. Hazardous / Irreversible Decline
Long > 40 years	Priority for Retention (High)				
Medium 15 to 40 Years					
Short <1-15 Years		Consider for Retention (Medium)	Consider for Removal (Low)	Priority for Removal (Remove)	
Dead					

Legend for Matrix Assessment

	Priority for Retention (High) - These trees are considered important for retention and should be retained and protected. Design modification or re-location of building/s should be considered to accommodate the set backs as detailed in Table 3. Special construction works must be implemented e.g. pier and beam etc if works are to proceed within the Tree Protection Zone.
	Consider for Retention (Medium) - These trees may be retained and protected. These are considered less critical; however their retention should remain priority with removal considered only if adversely affecting the proposed building/works and all other alternatives have been considered and exhausted.
	Consider for Removal (Low) – These trees are not considered important for retention, nor require special works or design modification to be implemented for their retention.
	Priority for Removal – These trees are considered hazardous, or in irreversible decline, or weeds and should be removed irrespective of development.

Appendix B

Modified extract from British Standard BS 5837: 1991 Guide for “Trees in relation to construction.”

Table 1. Protection of trees: minimum distances for protective fencing around trees			
Tree age	Tree vigour	Trunk diameter	Minimum distance
Young trees	Normal vigour	mm	m
		< 200	2.0
		200 to 400	3.0
		> 400	4.0
Young trees	Low vigour	< 200	3.0
		200 to 400	4.5
		> 400	6.0
Mature trees	Normal vigour	< 350	4.0
		350 to 750	6.0
		> 750	8.0
Mature trees and overmature trees	Low vigour	< 350	6.0
		350 to 750	9.0
		> 750	12.0

Note 1. It should be emphasized that this table relates to distances from centre of tree to protective fencing. Other considerations particularly the need to provide adequate space around the tree including allowances for future growth (see 6.3), and also working space (see 6.7), will usually indicate that structures should be further away.

Note 2. With appropriate precautions, temporary site works can occur within the protected area, e.g. for access or scaffolding (see 8.3).

Appendix C

Matrix - Sustainable Retention Index Value (S.R.I.V.)©

Developed by IACA – Institute of Australian Consulting Arboriculturists www.iaca.org.au

To be used with the values defined in the Glossary.
An Index value as indicated where ten (10) is the highest value.


Age Class	Vigour Class and Condition Class					
	Normal Vigour & Good Condition (NVG)	Normal Vigour & Fair Condition (NVF)	Normal Vigour & Poor Condition (NVP)	Low Vigour & Good Condition (LVG)	Low Vigour & Fair Condition (LVF)	Low Vigour & Poor Condition (LVP)
	Able to be retained if sufficient space available above and below ground for future growth. No remedial work or improvement to growing environment required. May be subject to abnormal vigour. Retention potential - Medium – Long Term.	Able to be retained if sufficient space available above and below ground for future growth. Remedial work may be required or improvement to growing environment may assist. Retention potential - Medium Term. Potential for longer with remediation or favourable environmental conditions.	Able to be retained if sufficient space available above and below ground for future growth. Remedial work unlikely to assist condition, improvement to growing environment may assist. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	May be able to be retained if sufficient space available above and below ground for future growth. No remedial work required, but improvement to growing environment may assist vigour. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	May be able to be retained if sufficient space available above and below ground for future growth. Remedial work or improvement to growing environment may assist condition and vigour. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	Unlikely to be able to be retained if sufficient space available above and below ground for future growth. Remedial work or improvement to growing environment unlikely to assist condition or vigour. Retention potential - Likely to be removed immediately or retained for Short Term. Potential for longer with remediation or favourable environmental conditions.
Young (Y)	Index Value 9 Retention potential - Long Term. Likely to provide minimal contribution to local amenity if height <5m. High potential for future growth and adaptability. Retain, move or replace.	Index Value 8 Retention potential - Short – Medium Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5m. High-moderate potential for future growth and adaptability. Retain, move or replace.	Index Value 5 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5m. Moderate-low potential for future growth and adaptability. Retain, move or replace.	Index Value 4 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5m. Moderate potential for future growth and adaptability. Retain, move or replace.	Index Value 3 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5m. Moderate-low potential for future growth and adaptability. Retain, move or replace.	Index Value 1 Retention potential - Likely to be removed immediately or retained for Short Term. Likely to provide minimal contribution to local amenity if height <5m. Low potential for future growth and adaptability.
Mature (M)	Index Value 10 Retention potential - Medium - Long Term.	Index Value 9 Retention potential - Medium Term. Potential for longer with improved growing conditions.	Index Value 6 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 5 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 4 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 2 Retention potential - Likely to be removed immediately or retained for Short Term.
Over-mature (O)	Index Value 6 Retention potential - Medium - Long Term.	Index Value 5 Retention potential - Medium Term.	Index Value 4 Retention potential - Short Term.	Index Value 3 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 2 Retention potential - Short Term.	Index Value 0 Retention potential - Likely to be removed immediately or retained for Short Term.

Appendix D

1.0 TREE PROTECTION ZONES - STANDARD PROCEDURE

- 1.1 Each tree to be retained is to have its dripline fenced off, except where otherwise indicated, to create a **Tree Protection Zone**, and this may include one enclosure to protect a single or multiple tree/s, or multiple enclosures separated over the site. The area contained is the **Tree Protection Zone**, and is to exclude any activity, except where otherwise stated. **Tree Protection Zone** works may extend beyond the fenced area or replace a fence if appropriate. The **Tree Protection Zone** is to exclude: modification of existing soil levels, storage of materials including waste, site sheds and machinery; preparation of building materials e.g. concrete, or chemical treatments; the movement of pedestrian or vehicular traffic; or the temporary, or permanent location of services, or the works required for their installation, e.g. trenches, holes or canals. The above list is not meant to be exhaustive, and is intended as a guide to the types of activities that are excluded from within the **Tree Protection Zone**, except where otherwise stated.
- 1.2 The Tree Protection Fence that defines the **Tree Protection Zone** is to be 1.8m high steel chain link with galvanised steel pipes, or approved similar, located around the dripline of the tree except where otherwise stated, as a minimum distance from the tree for its protection and should be made larger where possible. The perimeter of the **Tree Protection Zone** to be further delineated by the attachment of shade cloth material to the outside surface area of the fence facing the inside of the site to reduce the movement of dust and other air borne residue from building activities that may be phytotoxic to plants or plant parts. The fence is to be installed prior to the commencement of any works on site, (except weed removal and tree maintenance, e.g. pruning, irrigation and mulching), and is to be maintained for the duration of the project. The fence must have a lockable opening for access to, and the security of the enclosed area. A temporary TPZ fence or fence section may be required to be established initially, where demolition of existing structures is required to provide an area of sufficient space for the full extent of the Tree Protection Zone to be installed.
- 1.3 Tree Protection signage is to be attached to each **Tree Protection Zone** and displayed in a prominent position and the sign repeated at 10m intervals or closer where the fence changes direction. The lettering for each sign to be a minimum of 72 point and printed in Arial font. The signs to be a minimum size of 600mm x 500mm. Each sign to advise as minimum details, the following:
1. **Tree Protection Zone** (title)
 2. (TEXT) "This fence has been installed to prevent damage to the trees and their growing environment both above and below ground, and access is restricted."
 3. (TEXT) "If encroachment or incursion into this Tree Protection Zone is deemed to be essential the Consulting Arboriculturist should be informed prior to the undertaking of such works."
 4. (TEXT) **Name, Address and Telephone number** of the *developer* (to enable enquiries concerning the trees to be directed to the developer).

- 1.4 Where a tree is to be retained and a **Tree Protection Zone** can not be adequately established due to restricted access e.g. tree located along side an access way, the trunk will be protected by wrapping 2 layers of hessian or carpet underfelt around the trunk for a minimum of 2m or as lower branches permit, then wire or rope secures 75x50x2000mm hardwood planks to the trunk (do not nail to the trunk). The number of planks to be used is as required to encircle the trunk and the planks are to extend to the base of the tree. (Diagram courtesy G. Cluble)



- 1.5 If a tree is growing down slope from an excavation, a silt fence located along the contours of the site in the area immediately above the **Tree Protection Zone** fencing may need to be installed and regularly maintained to prevent burial and asphyxiation of the roots of the tree. To allow for the maintenance of both fences, the silt fence must be constructed separately to the tree protection fence and the 2 fences must be constructed independently of each other and standalone. To reduce competition with the tree the area within the **Tree Protection Zone** is to be kept free of weeds. These are best removed by the application of foliar herbicide with Glyphosate as the active constituent. This is the preferred method rather than removal by cultivation of the soil within the dripline, to minimise root disturbance to the tree. The removal of woody weeds such as Privet should use the cut and paint method of herbicide application. Weeds to be controlled within the **Tree Protection Zone**, for the duration of the project.
- 1.6 The area of the Tree Protection Zone to be mulched to a depth of 100 millimetres with organic material being 75% leaf litter and 25% wood, and this being composted material preferably from the same genus and species of tree as that to where the mulch is to be applied, i.e. species specific mulch. The depth of mulch and type as indicated, to be maintained for the duration of the project. Where deep excavation will expose the soil profile to drying out the root plate is to be protected by pegging jute matting across the ground surface 2m back from the edge of the profile and 2m down the face of the profile and is to be in one continuous sheet or layers up to 5mm thick and overlapped 300mm and pegged. Pegs are to be a minimum length of 200mm and spaced at 500mm increments in a grid pattern. Once installed mulch is to be placed on top of the jute matting previously described.
- 1.7 No services either temporary or permanent are to be located within the **Tree Protection Zone**. If services are to be located within the **Tree Protection Zone**, special details will need to be provided by a qualified Consulting Arboriculturist for the protection of the tree regarding the location of the service/s.

- 1.8 A tree will not be fertilised during its protection within the ***Tree Protection Zone***, as this may hasten its decline if it were to decline. If a tree is to be fertilised this should be in consultation with a qualified Consulting Arboriculturist.
- 1.9 In the event of prolonged dry periods, or where a tree has been transplanted, or where excavation nearby, especially up slope, leads to drying out of a soil profile, or modification to ground water flow, or flows across an existing ground surface to the tree and its growing environment; deep root watering thoroughly at least twice a week is to be undertaken to irrigate the tree. The need for such watering is determined readily by observing the dryness of the soil surface within the dripline of the tree by scraping back some mulch. Mulch to be reinstated afterwards. In the event of disrupted ground or surface water flows to the tree due to excavation, filling or construction, a reticulated irrigation system may be required to be installed within the ***Tree Protection Zone***. If an irrigation system is to be installed, consideration must be given to volume, frequency, and drainage of water delivered, and this should be in consultation with a qualified Consulting Arboriculturist.

Appendix E

1.0 TREE PROTECTION ON CONSTRUCTION SITES

Note: Individual protection measures to be applied where stated as applicable.

- 1.1.0 General notes
- 1.2.0 Cautionary notes for the protection of retained trees
- 1.3.0 Demolition of built structures - precautions to protect trees
- 1.4.0 Excavation and construction close to Tree Protection Zones

1.1.0 General notes

- 1.1.1 The application of any measures for the protection of trees on development sites is determined by the species characteristics of the subject tree, and the existing physical constraints of the growing environment on site both above and below ground.
- 1.1.2 This report considers where applicable, British Standard BS 5837 : 1991 Guide for “Trees in relation to construction.” as no Australian Standard currently exists for the protection of trees on development sites.
- 1.1.3 This report applies the **Tree Protection Zone - Standard Procedure** as developed and continually improved over time by URBAN TREE MANAGEMENT ® © for the effective protection of trees on development sites (see Appendix F). However, this does not restrict the author from applying additional or alternative conditions where it is deemed appropriate by the author for the protection of trees on development sites. Such additional or alternative conditions may be founded upon professional judgement based on:
 - the experience of the Consulting Arboriculturist
 - scientific research
 - new technology
 - industry best practice
 - consideration of the individual tree species and its relative tolerance to development impacts
 - the individual or cumulative factors present or proposed to impact upon the growing environment essential for the trees’ survival
- 1.1.4 Where this report makes reference to the retention of subject trees it is for their incorporation into the landscaping works for the site, and they are to be documented on a Landscape Plan for the site (*the Landscape Plan*).

1.2.0 Cautionary notes for the protection of retained trees

1.2.1 Location of services

If a utility service is to be located within the area of the dripline of a protected tree or within the Tree Protection Zone, the British Standard BS 5837 : 1991 Guide for “Trees in relation to construction.” provides the following: “7.5.8 An alternative solution is to excavate a narrow trench passing directly towards the tree along a radius to not closer than 1m from the trunk, tunnel straight beneath the tree, preferably not less than 750mm deep, and exit on the opposite side along another radius (see figure 3, see Appendix F in this report). Provided the trench is kept as narrow as possible, the amount of root severance will be minimal, and will be far less than if a trench passes close beside the tree. It may be necessary to sleeve a service where it passes beneath a tree in order to reduce the risk of damage to the service and facilitate future servicing and repair.” The tunneling could be achieved by the use of horizontal directional drilling to link the two trenches, being a horizontal steerable drilling system. Such a system has capabilities of installing pipeline ranging from 100mm, up to 1100mm diameters for lengths of just over 1000m and has little to no disruption to tree roots. Such tunneling is usually undertaken beneath structural woody roots radiating away from the trunk and not just under the center of the tree.

1.2.1.1

Location of services Option B (Driveway Construction)

If a service is to be located within the area of the dripline of a protected tree or within the Tree Protection Zone, and site conditions such as shallow bed rock or if mass rooting has occurred from multiple trees growing in close proximity to each other, the service trench is to be elevated and positioned above natural ground level within the new driveway structure. The existing driveway surface is to be scabbled and a reinforced concrete topping is to be provided with down turned thickened edges constructed under the kerb edging to prevent lateral movement. A suitable subgrade material to manufacturers’ recommendations is to be utilised if and where appropriate. Construction is to occur in a manner so as not to cause damage to the subject trees root system. All works to be in accordance with engineers’ details.

1.2.2 Precautions in respect of temporary work

For Precautions in respect of temporary work, British Standard BS 5837 Guide for “Trees in relation to construction.” provides the following:

“8.3.1 if temporary vehicle access is required through the protected area, a reinforced concrete slab should be laid over the existing soil surface, with appropriate protection along the road edge.

8.3.2 If it is essential for scaffolding to be erected within a protected area, fencing in accordance with 8.2.2 or 8.2.3 should be erected to provide just sufficient space for scaffolding. The ground between this fence and the building should be protected by boarding (e.g. scaffold boards) as shown in figure 6. (see Appendix E in this report) A single thickness of boarding laid on the soil surface will provide sufficient protection for pedestrian loads, but more substantial boarding sufficient to spread the load should be used for heavier traffic. The ground beneath the boarding should be left undisturbed and should be protected with a porous geotextile fabric. If necessary, sand should be laid on the fabric to level the ground. When required, the building scaffolding should be erected. The boarding should be left in place until the building works are finished.”

1.3.0 Demolition of built structures - precautions to protect trees

1.3.1 Demolition of existing Buildings

The demolition of the buildings should be undertaken with access restricted to the driveway and the building platform for each of the existing buildings, or to areas of the land where no trees are growing within 6m of any tree to be retained. Where access or space for a safe working environment is restricted, or where the area of the 6m set back must be compromised, a 100mm layer of Eucalyptus wood mulch must be laid over the area of encroachment. Where vehicular access is required across the mulch layer further root protection should be provided by laying a temporary pathway over the mulch. The temporary pathway should be constructed of a grated steel material capable of supporting the vehicles used during demolition e.g. similar to ramps used to load vehicles onto the backs of trucks. Trunks of trees are to be protected from vehicular damage as per section 6.4 of this report.

1.3.2 Demolition of landscape structures

The demolition of walls, driveways retaining walls, paths and pools etc. within 6m of a tree to be retained should be undertaken manually using hand tools. Where a driveway is to be demolished being of concrete strip or slab type construction, it should be undertaken by working from the end of the driveway closest to the building back towards the street by utilising the driveway as a stable platform to prevent soil compaction. Where a concrete slab driveway passes less than 1m from the base of a tree and the area beneath the driveway is to be undisturbed and incorporated into the landscape works for the site, the volume of space previously occupied by the driveway must be replaced with local top soil from the site or otherwise a loamy sand, to replace the mass of the concrete on the root plate which may be critical to the ballast and centre of mass for the stability of the tree. If the tree becomes unstable immediately contact the Consultant Arboriculturist.

1.3.3 Removal of existing trees near trees to be retained

Removal of a tree within 6m of a tree to be retained should be undertaken only by cutting down such a tree without damaging the trees to be retained, and by grinding out its stump. Where possible the structural roots of 20mm diameter or greater of the tree to be cut down should not be removed, to minimise soil disturbance and to reduce the impact on the roots of any tree to be retained nearby. Where structural roots are to be removed this should be undertaken manually by the use of non-motorized hand tools after the stump has been ground out when such roots are often easier to locate from the site of the stump from which they have been severed.

1.4.0 Excavation and construction close to Tree Protection Zones

1.4.1 Excavation close to Tree Protection Zones

1.4.1.1

Where structural woody roots with a diameter of 20mm or greater are to be pruned outside the area of the Tree Protection Zone, they are to be excavated manually first by using hand tools to determine their location. A Waterknife or Airknife can be used as a mechanised alternative to locate such structural woody roots. Once located those roots to be severed are to be cut cleanly with a final cut to undamaged woody tissue and this will prevent tearing damage to the roots from excavation equipment which can extend beyond the point of excavation back towards the tree.

1.4.1.2

Where a large vigorous tree is to be retained near to built structure, and dependent upon its taxa, age class and propensity for its roots system to regenerate, it may be prudent to install a root barrier immediately adjacent to the footing of the new building, or to deepen and strengthen the footings themselves to act as a root barrier, but for such structural advice an appropriately qualified chartered structural engineer should be consulted.

1.4.2 Root location and protection where structures are to be positioned near a retained tree

1.4.2.1

If walls or a driveway or other structures are to be constructed near a protected tree, careful excavation is to be undertaken manually by using non-motorized hand tools to determine the location of first order and lower order structural roots with a diameter of 20mm (*structural woody roots*) or greater, without damaging them. Boundary walls or fences should use columns or posts with in fill panels, or a wall to be constructed with suspended sections 100mm clear above or beside any structural woody root or further as required, or any new wall to be built only to the depth of that existing. Structural woody roots to be further protected by utilising the construction techniques of pier or bridge footings, or screw piles between or over them with a minimum clearance above or beside of 100mm, or further as required to allow for future and ongoing growth.

1.4.2.2


Where a driveway or footpath is to pass by the tree a suspended slab is to be constructed or approved similar, to protect the roots that may be encountered at, near, or above ground, and may be constructed on gap graded fill. Where such a driveway or footpath is to be constructed the edge of the structure closest to the tree is to terminate no closer than 0.5m from the closest edge of trunk, or further depending on the species and its likely further growth to allow for future development and expansion of the trunk, buttresses, and first order and lower order roots as may be advised by a Consultant Arboriculturist. The side of the driveway closest to a tree is to be edged with a concrete kerb of minimum dimensions of 150 x 150mm, to prevent vehicular collision with the trunk. Here a *Waterknife* or an *Airknife* can be used as a mechanised alternative to locate first order and lower order structural woody roots.

1.4.2.3

Alternatively a footpath or driveway may be constructed at ground level without any excavation, removing turf by raking, having sprayed with herbicide first if time permits. Here the path or driveway section is to extend for a distance past the tree equivalent to the lateral spread of the crown of that tree alongside the footpath, or driveway.

1.4.2.4

Watering / Gaseous exchange vents are to be installed in the area of the driveway that passes within the dripline of the tree or the prescribed **Tree Protection Zone** area and the number and location are to be determined by a Consultant Arboriculturist and the driveway design approved by a Certified Engineer. Exposed edges of the path are to be concealed with the finished level beside the path equivalent to the top of the path by minimal filling with a sandy soil and turf, or mulch, or a garden bed with minimal cultivation, or other landscape treatments as appropriate.



1.4.3 *Root protection where a driveway close to a tree is to be demolished and a new driveway constructed in a similar location to a previous driveway.*

After demolition of an existing driveway as per 5.3.2, the level of the base for the new driveway should be located at the same existing level as that of the base of the previous driveway, and should extend for a distance past the tree equivalent to the lateral spread of the crown of that tree alongside the driveway. To prevent excavation from damaging the existing roots which may be located at, near or above the surface of the soil beneath the base of the previous driveway, the new driveway may need to be raised by constructing it on pier or bridge footings between or over them (see 5.4.2 for minimum clearances), or based on a gap graded fill and the driveway constructed with any exposed edges concealed to the top of the driveway by minimal filling with a sandy soil and turf, or mulch, or a garden bed with minimal cultivation, or other landscape treatments as appropriate. Where roots have grown to occupy the soil between the concrete strips of a concrete, stone or brick strip driveway, they and the soil may be excavated to the level of the base of the concrete strips, but where such roots have a diameter of 20mm or greater, a Consulting Arboriculturist should be contacted prior to such works being undertaken. Where roots are to be severed, they are to be cut cleanly with a final cut to undamaged woody tissue.

1.4.4 *Root protection where a footpath is to be constructed close to a tree.*

1.4.4.1

A footpath may be constructed at ground level without any excavation, by first killing with herbicide the plants to be removed from the pathway area, and then removing that plant material by cutting the trunks of woody shrubs to ground level and by raking all other plant material to expose the top soil surface without organic matter. This will remove the need for physically disturbing the soil and the roots of the tree. The path section is to extend for a distance past each tree equivalent to the lateral spread of the crown of that tree where it extends alongside the footpath.

1.4.4.2

To prevent excavation from damaging the existing roots which may be located at, near, or above the surface of the soil, a gap graded fill as a fill material of a media as appropriate, to a depth of 100mm above the soil surface, or above the top of the root of any tree to be retained, or above the soil surface may be utilised as a base treatment to construct the foot path. Any exposed edges to be concealed to the top of the edges of the footpath and tapering back to the base of the trunk of each tree by minimal filling at each trunk of no greater than 100mm with a sandy soil and turf, or mulch, or a garden bed with minimal cultivation with ground covers, or other landscape treatments as appropriate. A Consultant Arboriculturist should be contacted prior to such works being undertaken or if any structural roots are considered appropriate to be severed being those roots of 20mm diameter or greater.

1.4.5 *Structural Soil to accommodate load bearing conditions*

A structural soil should only be considered as a new media into which the trees could be planted if the planting was into a new area where the area surrounding was to be load bearing such as a footpath, driveway or road.

1.4.6 *Gap graded fill to accommodate compacted sub grade and root growth*

To further protect woody roots with a diameter of 20mm or greater, a gap graded fill with no fines such as gravel 40mm diameter should only be considered as a fill media above existing grade when soil levels are to be increased near existing trees and the roots can utilise the new media to develop ongoing and future root growth and provide for gaseous exchange between the soil and the atmosphere.

Appendix F

Extract from British Standard BS 5837: 1991 Guide for “Trees in relation to construction.”

Scaffolding within a protected area




Figure 6. Scaffolding within a protected area (see 8.3.2)

Appendix G

Glossary

Vigour

Vigour / Vigor Ability of a tree to sustain its life processes. This is independent of the *condition* of a tree but may impact upon it. Vigour can appear to alter rapidly with change of seasons (seasonality) e.g. *dormant*, deciduous or semi-deciduous trees.

Normal Vigour Ability of a tree to maintain and sustain its life processes. This may be evident by the *typical* growth of leaves, *crown cover* and *crown density*, branches, roots and trunk and *resistance to predation*. This is independent of the *condition* of a tree but may impact upon it, and especially the ability of a tree to sustain itself against predation.

Low Vigour Reduced ability of a tree to sustain its life processes. This may be evident by the *atypical* growth of leaves, reduced *crown cover* and reduced *crown density*, branches, roots and trunk, and a deterioration of their functions with reduced *resistance to predation*. This is independent of the *condition* of a tree but may impact upon it, and especially the ability of a tree to sustain itself against predation.

Dormant Tree Vigour Determined by existing turgidity in lowest order branches in the outer extremity of the crown, with good bud set and formation, and where the last extension growth is distinct from those most recently preceding it, evident by bud scale scars. Normal vigour during dormancy is achieved when such growth is evident on a majority of branches throughout the crown.

Abnormal Vigour *Accelerated growth* of a tree due to incidental or deliberate artificial changes to its growing *environment* that are seemingly beneficial, but may result in *premature aging* or failure if the favourable conditions cease, or promote *prolonged senescence* if the favourable conditions remain, e.g. water from a leaking pipe; water and nutrients from a leaking or disrupted sewer pipe; nutrients from animal waste, a tree growing next to a chicken coop, or a stock feed lot, or a regularly used stockyard; a tree subject to a stringent watering and fertilising program; or some trees may achieve an extended lifespan from continuous *pollarding* practices over the life of the tree.

Age

Age Most trees have a stable biomass for the major proportion of their life. The estimation of the age of a tree is based on the knowledge of the expected lifespan of the taxa *in situ* divided into three distinct stages of measurable biomass, when the exact age of the tree from its date of cultivation or planting is unknown and can be categorized as *Young*, *Mature* and *Over-mature*.

Young Tree aged less than <20% of life expectancy, *in situ*.

Mature Tree aged 20-80% of life expectancy, *in situ*.

Over-mature Tree aged greater than >80% of life expectancy, *in situ*, or *senescent* with or without reduced *vigour*, and declining gradually or rapidly but irreversibly to death.

Periods of Time

Periods of Time The life span of a tree in the urban environment may often be reduced by the influences of encroachment and the dynamics of the environment and can be categorized as *Immediate*, *Short Term*, *Medium Term* and *Long Term*.

Immediate An *episode* or occurrence, likely to happen within a twenty-four (24) hour period, e.g. tree failure or collapse in full or part posing an imminent danger.

Short Term A period of time less than <1 – 15 years.

Medium Term A period of time 15 – 40 years.

Long Term A period of time greater than >40 years.

Trunk

Trunk A single stem extending from the *root crown* to support or elevate the *foliage crown*, terminating where it divides into separate *stems* forming *first order branches*. A trunk may be evident at or near ground or be absent in *acaulescent* trees of *deliquescent* habit, or may be continuous in trees of *excurrent* habit. The trunk of any *caulescent* tree can be divided vertically into three (3) sections and can be categorized as *Lower Trunk*, *Mid Trunk* and *Upper Trunk*. For a *leaning* tree these may be divided evenly into sections of one third along the trunk.

Acaulescent A *trunkless* tree or tree growth forming a very short *trunk*.

Caulescent Tree grows to form a *trunk*.

Condition

Good Condition Tree is of good habit, with *crown form* not severely restricted for space and light, physically free from the adverse effects of *predation* by pests and diseases, obvious instability or structural weaknesses, fungal, bacterial or insect infestation and is expected to continue to live in much the same condition as at the time of inspection provided conditions around it for its basic survival do not alter greatly. This may be independent from, or contributed to by vigour.

Fair Condition Tree is of good habit or *misshapen*, a form not severely restricted for space and light, has some physical indication of *decline* due to the early effects of *predation* by pests and diseases, fungal, bacterial, or insect infestation, or has suffered physical injury to itself that may be contributing to instability or structural weaknesses, or is faltering due to the modification of the *environment* essential for its basic survival. Such a tree may recover with remedial works where appropriate, or without intervention may stabilise or improve over time, or in response to the implementation of beneficial changes to its local environment. This may be independent from, or contributed to by vigour.

Poor Condition Tree is of good habit or *misshapen*, a form that may be severely restricted for space and light, exhibits symptoms of advanced and *irreversible decline* such as fungal, or bacterial infestation, major die-back in the branch and *foliage crown*, *structural deterioration* from insect damage e.g. termite infestation, or storm damage or lightning strike, ring barking from borer activity in the trunk, root damage or instability of the tree, or damage from physical wounding impacts or abrasion, or from altered local environmental conditions and has been unable to adapt to such changes and may decline further to death regardless of remedial works or other modifications to the local *environment* that would normally be sufficient to provide for its basic survival if in *good to fair* condition. Deterioration physically, often characterised by a gradual and continuous reduction in vigour but may be independent of a change in vigour, but characterised by a proportionate increase in susceptibility to, and *predation* by pests and diseases against which the tree cannot be sustained. Such conditions may also be evident in trees of advanced senescence due to normal phenological processes, without modifications to the growing environment or physical damage having been inflicted upon the tree. This may be independent from, or contributed to by vigour.

Dead Tree is no longer capable of performing any of the following processes or is exhibiting any of the following symptoms:

Processes

Photosynthesis via its foliage crown (as indicated by the presence of moist, green or other coloured leaves);

Osmosis (the ability of the root system to take up water);

Turgidity (the ability of the plant to sustain moisture pressure in its cells);

Epicormic shoots or *epicormic strands* in Eucalypts (the production of new shoots as a response to stress, generated from latent or adventitious buds or from a *lignotuber*);

Symptoms

Permanent leaf loss;

Permanent wilting (the loss of turgidity which is marked by desiccation of stems leaves and roots);

Abscission of the *epidermis* (bark desiccates and peels off to the beginning of the sapwood).

Leaning Trees

Leaning A tree where the *trunk* grows or moves away from upright. A lean may occur anywhere along the *trunk* influenced by a number of contributing factors e.g. genetically predetermined characteristics, competition for space or light, prevailing winds, aspect, slope, or other factors. A *leaning* tree may maintain a *static lean* or display an increasingly *progressive lean* over time and may be hazardous and prone to *failure* and *collapse*. The degrees of leaning can be categorized as *Slight Lean*, *Moderate Lean*, *Severe Lean* and *Critical Lean*.

Slight Lean A leaning tree where the trunk is growing at an angle within 0°-15° from upright.

Moderate Lean A leaning tree where the trunk is growing at an angle within 15°-30° from upright.

Severe Lean A leaning tree where the trunk is growing at an angle within 30°-45° from upright.

Critical Lean A leaning tree where the trunk is growing at an angle greater than >45° from upright.

Progressive Lean A tree where the degree of *leaning* appears to be increasing over time.

Static Lean A tree where the degree of *leaning* appears to have stabilized over time.

Self-correcting *Atypical* stem growth subsequently influenced and modified by *tropisms*, e.g. *gravitropism* and *phototropism*, where *reaction wood* attempts to return it to a more *typical* habit or *form*, e.g. a trunk with a *butt sweep* where it is returning to upright.

Form of Trees

Crown Form The shape of the crown of a tree as influenced by the availability or restriction of space and light, or other contributing factors within its growing environment. Crown Form may be determined for tree shape and habit generally as *Dominant*, *Codominant*, *Intermediate*, *Emergent*, *Forest* and *Suppressed*. The habit and shape of a *crown* may also be considered qualitatively and can be categorized as *Good Form* or *Poor Form*.

Good Form Tree of *typical* crown shape and habit with proportions representative of the taxa considering constraints such as origin e.g. indigenous or exotic, but does not appear to have been adversely influenced in its development by environmental factors in situ such as *soil water* availability, prevailing wind, or cultural practices such as lopping and competition for space and light.

Poor Form Tree of *atypical* crown shape and habit with proportions not representative of the species considering constraints and appears to have been adversely influenced in its development by environmental factors in situ such as *soil water* availability, prevailing wind, cultural practices such as lopping and competition for space and light; causing it to be *misshapen* or disfigured by disease or vandalism.

Crown Form Codominant Crowns of trees restricted for space and light on one or more sides and receiving light primarily from above e.g. constrained by another tree/s or a building.


Crown Form Dominant Crowns of trees generally not restricted for space and light receiving light from above and all sides.

Crown Form Emergent Crowns of trees restricted for space on most sides receiving most light from above until the *upper crown* grows to protrude above the canopy in a stand or forest environment. Such trees may be *crown form dominant* or transitional from *crown form intermediate* to *crown form forest* asserting both *apical dominance* and *axillary dominance* once free of constraints for space and light.

Crown Form Forest Crowns of trees restricted for space and light except from above forming tall trees with narrow spreading crowns with foliage restricted generally to the top of the tree. The trunk is usually erect, straight and continuous, tapering gradually, crown often excurrent, with first order branches becoming structural, supporting the live crown concentrated towards the top of the tree, and below this point other first order branches arising radially with each *inferior* and usually temporary, divergent and ranging from horizontal to ascending, often with internodes exaggerated due to competition for space and light in the *lower crown*.

Crown Form Intermediate Crowns of trees restricted for space on most sides with light primarily from above and on some sides only.

Crown Form Suppressed Crowns of trees generally not restricted for space but restricted for light by being *overtopped* by other trees and occupying an understorey position in the canopy and growing slowly.



Symmetry

Symmetry Balance within a *crown*, or *root plate*, above or below the *axis* of the trunk of branch and foliage, and root distribution respectively.

Asymmetrical Imbalance within a crown, where there is an uneven distribution of branches and the foliage *crown* or *root plate* around the vertical *axis* of the trunk. This may be due to *Crown Form Codominant* or *Crown Form Suppressed* as a result of natural restrictions e.g. from buildings, or from competition for space and light with other trees, or from exposure to wind, or artificially caused by pruning for clearance of roads, buildings or power lines. An example of an expression of this may be, crown asymmetrical, bias to west.

Symmetrical Balance within a crown, where there is an even distribution of branches and the *foliage crown* around the vertical *axis* of the trunk. This usually applies to trees of *Crown Form Dominant* or *Crown Form Forest*. An example of an expression of this may be crown symmetrical.

Crown Spread Orientation Direction of the *axis* of *crown spread* which can be categorized as *Orientation Radial* and *Orientation Non-radial*.

Crown Spread Orientation Radial Where the *crown spread* is generally an even distance in all directions from the trunk and often where a tree has *Crown Form Dominant* and is *symmetrical*.

Crown Spread Orientation Non-radial Where the crown extent is longer than it is wide, e.g. east/west or E/W.

Significant Important, weighty or more than ordinary.

Significant Tree A tree considered important, weighty or more than ordinary. Example: due to prominence of location, or in situ, or contribution as a component of the overall landscape for *amenity* or aesthetic qualities, or *curtilage* to structures, or importance due to uniqueness of taxa for species, subspecies, variety, *crown form*, or as an historical or cultural planting, or for age, or substantial dimensions, or habit, or as *remnant vegetation*, or habitat potential, or a rare or threatened species, or uncommon in cultivation, or of aboriginal cultural importance, or is a commemorative planting.

Substantial A tree with large dimensions or proportions in relation to its place in the landscape.

Sustainable Retention Index Value (SRIV) A visual tree assessment method to determine a qualitative and numerical rating for the viability of urban trees for development sites and management purposes, based on general tree and landscape assessment criteria using classes of *age*, *condition* and *vigour*. SRIV is for the professional manager of urban trees to consider the tree *in situ* with an assumed knowledge of the *taxon* and its growing environment. It is based on the physical attributes of the tree and its response to its environment considering its position in a matrix for age class, vigour class, condition class and its sustainable retention with regard to the safety of people or damage to property. This also factors the ability to retain the tree with remedial work or beneficial modifications to its growing environment or removal and replacement. SRIV is supplementary to the decision made by a tree management professional as to whether a tree is retained or removed (IACA - Institute of Australian Consulting Arboriculturists 2005).

Diameter at Breast Height (DBH) Measurement of trunk width calculated at a given distance above ground from the base of the tree often measured at 1.4 m. The trunk of a tree is usually not a circle when viewed in cross section, due to the presence of *reaction wood* or *adaptive wood*, therefore an average diameter is determined with a *diameter tape* or by recording the trunk along its narrowest and widest axes, adding the two dimensions together and dividing them by 2 to record an average and allowing the orientation of the longest axis of the trunk to also be recorded. Where a tree is growing on a lean the distance along the top of the trunk is measured to 1.4m and the diameter then recorded from that point perpendicular to the edge of the trunk. Where a *leaning* trunk is *crooked* a vertical distance of 1.4m is measured from the ground. Where a tree branches from a trunk that is less than 1.4m above ground, the trunk diameter is recorded perpendicular to the length of the *trunk* from the point immediately below the base of the flange of the *branch collar* extending the furthest down the trunk, and the distance of this point above ground recorded as *trunk* length. Where a tree is located on sloping ground the DBH should be measured at half way along the side of the tree to average out the angle of slope. Where a tree is *acaulescent* or *trunkless* branching at or near ground such as a mallee or *sprout mass* as regrowth, an average diameter is determined by recording the radial extent of the trunk at or near ground.

Deadwood

Deadwooding Removing of dead branches by *pruning*. Such pruning may assist in the prevention of the spread of *decay* from *dieback* or for reasons of safety near an identifiable target.

Deadwood Dead branches within a tree's crown and considered quantitatively as separate to *crown cover* and can be categorised as *Small Deadwood* and *Large Deadwood* according to diameter, length and subsequent *risk* potential. The amount of dead branches on a tree can be categorized as Low Volume Deadwood, Medium Volume Deadwood and High Volume Deadwood.

Small Deadwood A dead branch up to 10mm diameter and usually <2 metres long, generally considered of low *risk* potential.

Large Deadwood A dead branch >10mm diameter and usually >2 metres long, generally considered of high *risk* potential.

Low Volume Deadwood Where <5 dead branches occur that may require *removal*.

Medium Volume Deadwood Where 5-10 dead branches occur that may require *removal*.

High Volume Deadwood Where >10 dead branches occur that may require *removal*.

Epicormic Shoots Juvenile shoots produced at branches or trunk from *epicormic strands* in some Eucalypts (Burrows 2002, pp. 111-131) or sprouts produced from dormant or latent buds concealed beneath the bark in some trees. Production can be triggered by fire, pruning, wounding, or root damage but may also be as a result of *stress* or *decline*. Epicormic shoots can be categorized as *Low Volume Epicormic Shoots*, *Medium Volume Epicormic Shoots* and *High Volume Epicormic Shoots*.

Low Volume Epicormic Shoots Where <10% of the *crown cover* is comprised of live *epicormic shoots*.

Medium Volume Epicormic Shoots Where 10-50% of the *crown cover* is comprised of live *epicormic shoots*.

High Volume Epicormic Shoots Where >50% of the *crown cover* is comprised of live *epicormic shoots*.

Dieback The death of some areas of the *crown*. Dieback can be categorized as *Low Volume Dieback*, *Medium Volume Dieback* and *High Volume Dieback*. Symptoms are leaf drop, bare twigs, dead branches and tree death, respectively. This can be caused by root damage, root disease, bacterial or fungal canker, severe bark damage, intensive grazing by insects, *abrupt changes* in growth conditions, drought, water-logging or over-maturity. Dieback often implies reduced *resistance*, *stress* or *decline* which may be temporary.

Low Volume Dieback Where <10% of the *crown cover* has died.

Medium Volume Dieback Where 10-50% of the *crown cover* has died.

High Volume Dieback Where >50% of the *crown cover* has died.

Crown Projection (CP) Area within the *dripline* or beneath the lateral extent of the *crown* (Geiger 2004, p. 2).

Dripline A line formed around the edge of a tree by the lateral extent of the *crown*. Such a line may be evident on the ground with some trees when exposed soil is displaced by rain shed from the crown.

First Order Roots (FOR) Initial woody roots arising from the *root crown* at the base of the *trunk*, or as an *adventitious root mass* for structural support and *stability*. Woody roots may be buttressed and divided as a marked gradation, gradually tapering and continuous or tapering rapidly at a short distance from the root crown. Depending on soil type these roots may descend initially and not be evident at the root crown, or become buried by changes in soil levels. Trees may develop 4-11 (Perry 1982, pp. 197-221), or more first order roots which may radiate from the trunk with a relatively even distribution, or be prominent on a particular aspect, dependant upon physical characteristics e.g. leaning trunk, *asymmetrical* crown; and constraints within the growing *environment* from topography e.g. slope, soil depth, rocky outcrops, exposure to predominant wind, soil moisture, depth of *water table* etc.

Orders of Roots The marked divisions between woody roots, commencing at the initial division from the base of the trunk, at the *root crown* where successive branching is generally characterised by a gradual reduction in root diameters and each gradation from the trunk and can be categorized numerically, e.g. *first order roots*, second order roots, third order roots etc. Roots may not always be evident at the *root crown* and this may be dependant on species, age class and the growing environment. Palms at maturity may form an adventitious root mass.

Root Plate The entire root system of a tree generally occupying the top 300-600mm of soil including roots at or above ground and may extend laterally for distances exceeding twice the height of the tree (Perry 1982, pp. 197-221). Development and extent is dependant on water availability, soil type, *soil depth* and the physical characteristics of the surrounding landscape.

Root Crown Roots arising at the base of a trunk.

Zone of Rapid Taper The area in the *root plate* where the diameter of *structural roots* reduces substantially over a short distance from the *trunk*. Considered to be the minimum radial distance to provide structural support and *root plate* stability.

Structural Roots Roots supporting the infrastructure of the *root plate* providing strength and *stability* to the tree. Such roots may taper rapidly at short distances from the *root crown* or become large and woody as with gymnosperms and dicotyledonous angiosperms and are usually 1st and 2nd order roots, or form an *adventitious root mass* in monocotyledonous angiosperms (palms). Such roots may be crossed and grafted and are usually contained within the area of *crown projection* or extend just beyond the *dripline*.

Appendix H & I

Appendix H – Survey of Subject Tree/s

Appendix I – Tree Protection Plan

Trees the subject of this report are marked on the plans in the following appendix and are numbered as listed below.

Tree No.	Genus and species	Common name
1	<i>Araucaria cunninghamii</i>	Hoop Pine
2	<i>Araucaria cunninghamii</i>	Hoop Pine
3	<i>Araucaria cunninghamii</i>	Hoop Pine
4	<i>Araucaria cunninghamii</i>	Hoop Pine
5	<i>Araucaria cunninghamii</i>	Hoop Pine
6	<i>Araucaria cunninghamii</i>	Hoop Pine
7	<i>Araucaria cunninghamii</i>	Hoop Pine
8	<i>Araucaria cunninghamii</i>	Hoop Pine
9	<i>Araucaria cunninghamii</i>	Hoop Pine
10	<i>Araucaria cunninghamii</i>	Hoop Pine
11	<i>Araucaria cunninghamii</i>	Hoop Pine
12	<i>Araucaria cunninghamii</i>	Hoop Pine
13	<i>Araucaria cunninghamii</i>	Hoop Pine
14	<i>Araucaria cunninghamii</i>	Hoop Pine
15	<i>Araucaria cunninghamii</i>	Hoop Pine
16	<i>Araucaria cunninghamii</i>	Hoop Pine
17	<i>Araucaria cunninghamii</i>	Hoop Pine
18	<i>Araucaria cunninghamii</i>	Hoop Pine
19	<i>Araucaria cunninghamii</i>	Hoop Pine
20	<i>Araucaria cunninghamii</i>	Hoop Pine

Appendix H


UTM Survey of Subject Tree/s

Survey Plan, by Craig & Rhodes, Ref: 233-06, Sheet 1 of 2, dated Dec 2006. Plan reproduced and no longer to original scale.



Legend

- 10. Trees numbered in **orange and bold** are recommended for **retention**.
- 11. Trees numbered in **blue and not bold** are proposed for **removal**.



Appendix I - TREE PROTECTION PLAN

Site: Site 13, Cnr Olympic Parade and Sarah Durack Avenue, Homebush. Reference 10261
Prepared by Urban Tree Management Australia P/L, 65 Excelsior Street, Merrylands NSW 2160,
tel. 02 9760 1389
From Architectural Design Report, by Batessmart, Project No. S10649, dated 5 March 2008. For other tree protection measures see sections 5.0 and Appendices D and E.

- Legend**
- Tree Protection Zone (TPZ)**, fencing with setbacks as indicated, or other protection measures or works as indicated.
 - Tree Protection Zone**, area of special protection measures or works outside of or instead of a fenced area.
 - Tree numbers – tree/s to be retained only.



Tree Protection Zone setbacks taken from Table 3.0 and Appendix B.		
UTM Tree No.	British Standard BS 5837:1991 Recommended distance per DBH in metres	Reduced distance by British Standard (one third on one side only) (m)
1-11	3	2
12-20	3	2

Trees 1- 11: TPZ fencing on side closet to works to provide a set back of 2.5m during excavation. This may further be reduced at commencement of construction to 1.5m for scaffolding. Ground surface between TPZ fence and construction to be further protected when re-located.

Tree Protection Works - Specific

Prior to Excavation

- Tree Protection Zones (TPZ) including fencing, are to be installed with set backs as detailed in Table 3. A 2.5m set back should be provided for Trees 1-11 on the side closet to works.
- All trees at the centre of the site within or proximate to the proposed building envelope should be removed.

During Excavation

- Excavation adjacent to Trees 1-11 should be piled by shord excavation. No batter slope or benching should be undertaken during excavation.
- Where structural woody roots (roots >20 mm diameter) are encountered, these are to be cut cleanly by hand to undamaged woody tissue. This will promote continued root growth and minimise infestation by decay pathogens.

During Construction

- Tree Protection Zone fencing adjacent to Trees 1-11 should be reduced to 1.5m to allow for construction access and scaffolding to be undertaken.
- The ground surface between the TPZ fencing and excavation works is to be protected by covering with metal or timber sheeting to displace loads whereby minimising compaction. Sand is to be used to level undulations in grade with geotextile fabric placed on top.
- For adequate scaffold clearance, some branches at the lower crowns may be required to be tie back. This is to be undertaken by securing back using 50mm hessian tie, in a figure eight arrangement between the branch and/or trunk. The distal and proximal ends of the ties are to be secured around a junction or if this is not feasible, rapped around the branch/trunk above and below the bracing point three times providing a cross formation to prevent the tie from slipping.
- Pruning should be avoided, however if it becomes unavoidable, this should be undertaken in consultation with the Consulting Arboriculturist.
- No utility services are to be located within the TPZ's (above and below ground). Where locating of such services is unavoidable it should only be undertaken in consultation with a Consulting Arboriculturist. Alternatively, for underground services within the TPZ, installation can be carried out by horizontal direction drilling beneath the root plate at a minimum depth of 800mm (See Part 1.2.1 of Appendix E). No open excavation should occur within the TPZ of any tree to be retained. Reason: Prevent impact on trees by the removal of roots during open excavation.

Post construction

- Tree Protection Zone fencing should be removed to allow for landscaping to be undertaken.
- All hessian ties should be removed, with all branches secured back allowed to regain their original positioning.

Tree Protection Works - General

- Trees to be retained are to be protected and not to be damaged and TPZ's retained and maintained.
- The Tree Protection Fence that defines the **Tree Protection Zone** is to be 1.8m high steel chain link with galvanised steel pipes, or approved similar, located around the dripline of the trees except where otherwise stated, as a minimum distance from the tree for its protection and should be made larger where possible.
- All retained trees Existing levels are to be preserved and no excavation except by hand to protect structural roots is to be undertaken within the Tree Protection Zones. No cut or fill filling is to be undertaken within any TPZ unless specified by the Consulting Arboriculturist.

