



COZENS • REGAN
WILLIAMS • PROVE PTY
LTD.
CONSULTING ENGINEERS
CIVIL • STRUCTURAL • LAND MANAGEMENT

TWIN TOWNS SERVICES CLUB

ADDITIONS AND ALTERATIONS

**Lot 1, DP 777183
WHARF STREET
TWEED HEADS**

STORMWATER MANAGEMENT PLAN



Suite 7 Advance Business Centre 39 Lawrence Drive Nerang PO Box 2711 Nerang 4211

Telephone (07) 5578 4100 Facsimile (07) 5578 4092

INCORPORATED IN QUEENSLAND ABN 23 009 914 274/ACN 009 914 274

DOCUMENT CONTROL RECORD

Report Details

Client: Twin Towns Services Club
Document Name: Stormwater Management Plan
Site Address: Wharf Street, Tweed Heads.
Job Number: 06337
File Name: 06337_SWMP_B.doc

Issue	Rev	Checked	Date	Approved	Date	Distributed to:	Qty.
Preliminary	A		11/04/07		11/04/07	GMP Management	12
DA Submission	B		26/11/08		26/11/08	Darryl Anderson Consulting Pty Ltd	1

This document is produced by Cozens Regan Williams Prove Pty Ltd for the benefit of and use by the client in accordance with the terms of the agreement. Cozens Regan Williams Prove Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by any third party on the content of this document.

ADDITIONS AND ALTERATIONS

**WHARF STREET, TWEED HEADS
LOT 1 ON DP 777183**

TABLE OF CONTENTS

1. Introduction

- 1.1 General Introduction
- 1.2 Scope of Plan
- 1.3 Site Description

2. Stormwater Management Plan – D7 Requirements

- 2.1 Adoption of Annexure A
- 2.2 Existing Site Drainage and Catchments
- 2.3 Operational Requirements

3. Stormwater Management – Operational Phase

- 3.1 Water Quality Parameters
- 3.2 Water Quality Assessment
 - 3.2.1 Treatment Goals
 - 3.2.2 Oil and Grit Separator
- 3.3 Water Quality Management
 - 3.3.1 Objectives
 - 3.3.2 Maintenance Control Measures
- 3.4 Discharge Management
 - 3.4.1 Peak Discharge Summary

4. Conclusion

References

Figures

Stormwater Management Plan – 06337/SK2B

1.0 Introduction

1.1 General Introduction

Cozens Regan Williams Prove Pty Ltd has been commissioned by Twin Towns Services Club to prepare a Stormwater Management Plan for the proposed additions and alterations to the existing buildings in Wharf Street, Tweed Heads.

The Plan is required to support an application to Tweed Shire Council for the proposed development and to provide documentation for the management of stormwater runoff during the operational phase in order to minimise any adverse downstream impacts created by the development.

Development of the site will involve earthworks and building works. The development will alter the present land use and an assessment is required to determine the impact of these proposed changes on the pollutant loads.

This plan is to provide an impact assessment and any amelioration measures required to offset any potential adverse impact.

1.2 Scope of Plan

The development impact on the peak discharge and runoff and details of any measures required to comply with the council's requirements is documented. The determination of the pollutant loads generated from the site will not be calculated in this plan as the provisions of Section D.7.12 will be used to determine the size of the required treatment device. The remedial measures to treat the runoff, to ensure compliance with the provisions within the "Tweed Urban Stormwater Quality Management Plan", specifically annexure D7 –"Stormwater Quality" are also documented.

1.3 Site Description

The subject site is a portion of the allotment that is described as Lot 1 DP 777183 Wharf Street, which currently is being used as a car park with building above. It is located on the eastern side of Wharf Street. Other commercial buildings and recreational facilities surround the site,

The proposed development comprises a multi storey addition to the existing building, associated driveway, car park and landscaped areas.

2.0 Stormwater Management Plan – D7 Requirements

The following documentation and assumptions have been used in the preparation of the Stormwater Management Plan. Plan 06337/SK2 should be read in conjunction with the details contained within this document.

2.1 Adoption of Annexure A

Analysis of the impacts of the proposed development will be determined in accordance with the provisions of Annexure D7 “Stormwater Quality” and this plan should be read in conjunction with the Stormwater Management Plan Drawing 06337/SK2. Notwithstanding these requirements, Annexure A “Code of Practice for Soil and Water Management on Construction works” has and should be adopted as the minimum requirements. Consideration of this reference material has been used in the preparation of this document.

2.2 Existing Site Drainage and Catchments

Drainage from the site is proposed to be collected in a piped system and directed to the existing piped system that runs through the site. The proposed legal point of discharge is the drainage system from Wharf Street that discharges into the Jack Evans Boat Harbour. Currently discharge from the site is via the existing drainage system.

The roof area will discharge to the legal point of discharge without treatment. The driveway area subject to rainfall will require treatment by an oil and grit separator.

2.3 Operation Requirements

During the Operational phase treatment is required to minimise the impact of Suspended Solids, Nutrients (Total Phosphorus and Total Nitrogen), litter and oil and grease. The provisions of Table 5.4 of the “Tweed Urban Stormwater Quality Management Plan” define the discharge criteria to be satisfied for the operational phase of any new development. Calculations for the pollutants generated and the treatment methods and expected results of the treatment are detailed in **Section 3**.

The impact on discharge from the site, due to increased impervious area is also considered in **Section 3**.

3.0 Water Quality

3.1 Water Quality Parameters

Appendix F of the NSW EPA publication "Managing Urban Stormwater: Council Handbook (Draft), December 1997", recommends that the modelling approach for this size development be a Level 1 assessment. Assessment of the average annual storm load is required and the treatment determined.

The buildings, driveways, car parks and landscaping areas, will generate pollutants. The base data adopted for this assessment is:

- | | |
|--|--------------|
| • Average annual rainfall | 1719 mm/year |
| • Runoff coefficient for impervious areas | 0.9 |
| • Runoff coefficient for landscaping areas | 0.5 |
| • Catchment Area (reconfigured car park) | 0.275ha |

3.2 Water Quality Assessment

The drainage system is proposed to discharge to the open channel at the rear of the site. The receiving body of water for this system is ultimately the Tweed River.

No investigations of the down stream area have been taken to establish a baseline since the design discharge parameters have been given by the "Tweed Urban Stormwater Quality Management Plan".

The primary pollutants of concern as a result of this development are:

- Sediments
- Nutrients
- Oils and grease

The following sections assess pollution generation and detail methods of treatment.

3.2.1 Treatment Goals

The "Tweed Urban Stormwater Quality Management Plan" needs to be satisfied for the Operational Phase of the project. As such the water quality objectives, for the hard stand areas only, as detailed in Table 5.4 of the "Tweed Urban Stormwater Quality Management Plan", equate to the following discharge criteria for an average year:

- | | |
|-------------------------|---------------|
| • Suspended Solids (SS) | 82.5 kg/year |
| • Total Phosphorus (TP) | 0.220 kg/year |
| • Total Nitrogen (TN) | 1.238 kg/year |

These water quality goals are to be achieved prior to discharging into the drainage system. Treatment of the runoff collected from the roof drainage is not required.

Using the “deemed to comply” provisions of Section D.7.12 of the “Tweed Urban Stormwater Quality Management Plan” a proprietary device can be determined on size and the treated pollutant loads not required to be determined. It therefore is proposed to provide a treatment device, for the removal of suspended solids and nutrients using this method.

3.2.2 Oil and Grit Separator

The potential for sediment generation and oil/grease within the driveways warrants the consideration of primary treatment in the form of an Oil and Grit Separator. This should be located prior to discharging into the existing system (Refer to drawing 06337/SK2). Oil and Grit Separators have varying efficiencies of pollutant removal dependant on the type unit selected, however the use of a Humeceptor STC3 (or equivalent) is proposed, with a minimum combined wet well size of **3.02m³**. The size of the wet well was determined using the requirements of Section D7.

The installation of closely spaced grated stormwater inlets should also be considered to assist in the removal of the gross pollutants (rubbish, leaf matter, etc.). Management of these structures will require regular maintenance and details for this are outlined below.

3.3 Water Quality Management

3.3.1 Objectives

The objectives are to provide a stormwater drainage system that reduces the impact of the development compared with the existing pre-development loads. Management practices to assist in the reduction of the reliance on the primary treatment structures will be implemented.

Provision of long-term water quality monitoring for this development is considered impractical and is not proposed.

3.3.2 Maintenance Control Measures

The Contractor/Builder is responsible for the installation and maintenance of the primary control measures during the construction phase and the defects liability period.

Maintenance responsibilities for the operating life of the project reverts to the Owner's/ business operators once the defects liability period has expired.

Maintenance will require:

- a) Regular sweeping and rubbish removal from the driveway and landscape areas, including rubbish removal from the grated stormwater inlets. This should be done visually on a daily basis.
- b) Monitoring the Oil and Grit Separator regularly and inspecting at least every three (3) months and after every storm event large enough to produce runoff.
- c) Cleaning out the Oil and Grit Separator when the storage capacity has

- been reduced by 30%.
- d) Collect all litter, cuttings and leaf litter for composting or disposal off site.

3.4 Discharge Management

This section deals with the change in characteristics of stormwater runoff as a result of the proposed development.

3.4.1 Peak Discharge Summary

The post development phase will not result in an increase in the impervious area of land and subsequently will not result in an increase in the peak discharge and volume of runoff. It is assumed that the existing system is adequately sized to cater for the peak discharge.

4.0 Conclusion

There is no need to provide mitigation of the peak stormwater discharge. Meeting the water quality objectives, as set out by the Tweed Shire Council is one of the primary objective and all aspects have been considered. The potential impact on the quality of receiving waters for this project is to be mitigated as follows:

- a) Provision of an Oil and Grit Separator to improve discharged water quality from the car park hardstand areas during the operational phase.
- b) Management of operations of the site during the life of the development to minimise the potential pollutant loads.

The implementation of standard industry site practices is considered satisfactory for this development.

References

1. NSW, Environment Protection Authority, 11/97, "*Managing Urban Stormwater: Council Handbook, (Draft)*".
2. NSW, Environment Protection Authority, 11/97, "Managing Urban Stormwater: Treatment Techniques".
3. The Institution of Engineers, Australia, Queensland Division, December 1996, "*Soil Erosion and Sediment Control, Engineering Guidelines for Queensland Construction Sites*".
4. NSW Department of Housing, 8/98, "Managing Urban Stormwater: *Soils and Construction*".
5. Brisbane City Council, Feb 2000, "*Sediment Basin Design, Construction and Maintenance*".

FIGURES

ALL PIPE WORK TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF AS3500 AND THE LOCAL AUTHORITY.

ALL PIPEWORK TO BE 100 DIA. LAYED AT 1.65% MIN. U.N.O.

ALL DIMENSIONS MUST BE TAKEN FROM SITE AND / OR VERIFIED BEFORE COMMENCEMENT OF WORK.



THESE DRAWINGS ARE DIAGRAMMATIC ONLY AND ARE INTENDED TO INDICATE DESIGN IN ACCORDANCE WITH THE RELEVANT REGULATIONS AND REQUIREMENTS OF THE LOCAL AUTHORITY AND DO NOT RELIEVE THE BUILDER FROM ANY RESPONSIBILITY EVEN IF PLANS ARE STAMPED APPROVED.

PLUMBER IS TO CO-ORDINATE WITH STRUCTURE PRIOR TO ANY CONSTRUCTION.

PLUMBER IS TO VERIFY ALL INVERT LEVELS AND COVER OVER DRAINAGE LINES ARE CORRECT AND OBTAINABLE BEFORE COMMENCEMENT.

— — — PROPOSED STORMWATER DRAINAGE

NOTE :
ALL EXISTING SERVICES TO BE LOCATED
PRIOR TO COMMENCEMENT OF WORKS.



B	11/08	BUILDING AMENDED	J.A.W
A	03/07	ORIGINAL ISSUE	J.A.W
No	DATE	ISSUE	CHECKED

IN ASSOCIATION WITH

0 5 10 1 : 250

DATUM AHD



PTY LTD SUITE 7 ADVANCE BUSINESS CENTRE
39 LAWRENCE DRIVE NERANG
PO BOX 2711 NERANG QLD 4211
Telephone: (07) 5578 4100
Facsimile: (07) 5578 4092
Email: mail@crwp.com.au

DESIGNED	J.A.W.
DRAWN	D.P.G.
CHECKED	J.A.W.
APPROVED FOR AND ON BEHALF OF COZENS REGAN WILLIAMS PROVE PTY LTD (RPECQ No 4)	

CLIENT **TWIN TOWNS SERVICES CLUB**

PROJECT	PROPOSED REDEVELOPMENT
D	WHARF ST, TWEED HEADS
	STORMWATER MANAGEMENT PLAN

JOB NO.
06337
 DRAWING NO.
SK2