



**Materials + Finishes Schedule**

- (AW1) Awning Type 1: Awning, retractable. Fabric finish. Future tenant to install.
- (AW2) Awning Type 2: Frameless glass on steel structure, to future detail.
- (BAL) Balustrade Type 1: Semi-frameless clear glass. Frame-steel. Finish equal in appearance to stainless steel.
- (CR1) Cement Render Type 1: Cement render or equal. Natural colour.
- (CW1) Curtain Wall System Type 1: Curtain wall system to Facade Engineer's specification. Aluminium frame- powdercoat finish. Colour equal to Dulux 'Weathered Copper'.
- (GC1) Glass panels- Colours equal to blue, bronze, grey, clear, clear reflective. Thermal performance to Facade Engineer's requirements. Solid panels- Colours and finish equal in appearance to terracotta. Random distribution of ground, matte and glazed panels in 5 colours. Colours equal to Moeding Alphonat 'Braun', 'Naturrot', 'Eisengrau', 'Blaugrau' and 'Perigrau'.

- (CW2) Curtain Wall System Type 2: Curtain wall system to Facade Engineer's specification. Aluminium frame- powdercoat finish. Colour equal to Dulux 'Weathered Copper'.
- (CW3) Curtain Wall System Type 3: Curtain wall system to Facade Engineer's specification. Aluminium frame- powdercoat finish. Colour equal to Dulux 'Weathered Copper'. Glass colour- green. Thermal performance to Facade Engineer's requirements.
- (CW4) Curtain Wall System Type 4: As per CW2. Screen printed supergraphics to inside face. Design TBC.
- (DWS) Decorative Wall System Type 1: Material and finish to future detail.
- (GD1) Glass, Clear Type 1: Framed door and window suite. Glass equal to CW2. Aluminium frame- powdercoat finish. Colour equal to Dulux 'Weathered Copper'
- (GD2) Garage Door Type 1: Metal roller door. Perforated. Powdercoat finish. Colour equal to MC1.

- (HR1) Handrail Type 1: Steel handrail. Finish equal in appearance and finish to stainless steel.
- (HR2) Handrail Type 2: Mild steel handrail. Paint finish. Colour equal to Dulux 'Weathered Copper'.
- (LV1) Louvre Type 1: Horizontal aluminium sunshade, variable depth, to Facade Engineer's specification. Integral to Curtain Wall System CW1. Finishes as per CW1.
- (LV2) Louvre Type 2: Aluminium louvre screen/door- powdercoat finish. Colour and finish equal to MC1.
- (LV3) Louvre Type 3: Retractable external blind. Powdercoat finish equal to LV2.
- (LV4) Louvre Type 4: Vertical sunshade. Powdercoat finish. Colour equal to Dulux 'Weathered Copper'.

- (MC1) Metal Cladding System Type 1: Cassette type metal cladding system. Finish and colour equal in appearance to pre-weathered zinc.
- (MC2) Metal Cladding System Type 2: Decorative metal cladding system equal to preweathered Corten steel. Natural finish and colour.
- (MC3) Metal Cladding System Type 3: Metal cladding system equal to stainless steel. Natural finish and colour.
- (MC4) Metal Cladding System Type 4: Prefinished screen system with integrated louvre panels as required. Colour and finish equal to LV2.
- (PC1) Concrete Column Type 1: Off form concrete, smooth finish. Colour equal to 'Brite and Lite'.
- (PCP) Precast Panel Type 1: Precast concrete panel with embossed graphics. Finish and colour equal to PCP1.

**NOTES**  
 THIS DRAWING IS COPYRIGHT © AND SHALL REMAIN THE PROPERTY OF TURNER + ASSOCIATES ARCHITECTS. NO REPRODUCTION WITHOUT PERMISSION. ALL DIMENSIONS AND FINISHES ARE TO BE CONFIRMED BY THE CLIENT. THIS DRAWING IS NOT FOR CONSTRUCTION. DO NOT SCALE FROM DRAWINGS. FIGURED DIMENSIONS SHALL TAKE PRECEDENCE.

**CLIENT**  
**THE GPT GROUP**  
 Level 52, MLC Centre 19 Martin Place,  
 Sydney, NSW 2000  
 02 8239 3555

**PROJECT MANAGER**  
**BOVIS LEND LEASE**  
 30 The Bond, 30 Hickson Road  
 Millers Point, NSW 2000  
 02 9236 6111



**PROJECT TITLE**  
**PARKVIEW PLACE BUILDING A**  
 7 PARKVIEW DRIVE, SYDNEY OLYMPIC PARK

**DRAWING TITLE**  
**North Elevation**

|        |                    |         |                         |
|--------|--------------------|---------|-------------------------|
| Rev    | Date               | DS      | EA Submission (Amended) |
| G      | 02.06.10           | DS      | EA Submission (Amended) |
| Scale  | 1:100@B1, 1:250@A3 | Job No. | 09039                   |
| Status | EA SUBMISSION      | DWG No. | EA302                   |
| Author | MH                 | Check   | MH                      |
| Drawn  | G                  | Rev     | G                       |

**TURNER + ASSOCIATES**  
 L1 410 Green Street Surry Hills NSW 2010 Australia t +61 2 8668 0000 f +61 2 8668 0088