

**CIVIL ENGINEERING MATTERS
LOTS 2 & 3 BILAMBIL ROAD BILAMBIL
PROPOSED SUBDIVISIONAL DEVELOPMENT**

REVISION F
OUR REF: O8418

REVISION	DATE	AMENDMENTS
A	4/08/08	-
B	4/08/08	Final Report for Submission
C	19/09/08	Effluent Disposal Proposal Amended
D	2/12/08	General Revision
E	15/03/09	Revised Layout
F	20/05/09	Amended Council Requirements

CLA CONSULTANTS
8/43 TALLEBUDGERA CREEK ROAD
WEST BURLEIGH
PH (07) 5520 1066
Fax (07) 5520 1077
mail@claconsultants.com.au

**Lots 2 & 3
Bilambil Road
Bilambil**

**Civil Engineering
Response to Director General's Environmental Assessment Requirements**

Note that Item Numbers reflect the requirement summary.

General

This report has been prepared in order to provide response to DGEARs in relation to civil engineering aspects of the project.

The site is located at the corner of Hogans Road, Bilambil Road and Urliup Road in Bilambil (Lots 2 & 3 on DP244652). The site is approximately 4.6Ha in area.

The site is to be developed as a residential subdivision comprising 57 allotments. Details of the proposed development are contained on CLA Drawing Nos 08418 – 001 to 009 inclusive.

Site Grading

The site is characterised by an isolated rock outcropping rising to a maximum of 20m above the adjacent plain. The outcropping is essentially contained within the confines of the subject sites. There is significant evidence of quarrying in the past, and it is obvious that such quarrying operations were undertaken without regard to practice that would be the norm today. In it's current state, the site not only provides an unsightly appearance, it also comprises a significant threat to the integrity of the receiving environment as a result of uncontrolled runoff from the significantly disturbed surface and is regarded as a potential danger to those who might trespass on account of the unprotected sheer faces left on cessation of the quarrying operations.

The design of the site grading has been undertaken with the following aims in mind:

- a) Limitation of surface discontinuity at property boundary
- b) Limitation of the general nature of the more rounded topography in the adjacent areas
- c) Limitation in the use of earth retaining structures
- d) Efficient control of stormwater runoff

The proposed earthworks are described in the CLA Consultant Drawings 08418-003,004 and 005 attached.

These drawings indicate that, with the exception of the boundary between the proposed commercial area and the existing hall finished surface matches existing surface at the boundaries of the development.

The finished landform presents a surface more in keeping with the general topography of the area.

It will be noted that in one particular area, the depth of the required excavation exceeds 5m. This is required to achieve an acceptable grading of the site. The area of such excavation represents approximately 10% of the site as a whole.

The use of retaining walls has been limited to three locations, as follows:

- a) The area bounded by the new roads, where the wall height is limited to a maximum of 1m along the property frontage boundary, and
- b) A larger retaining wall at the rear of the proposed commercial site. It will be understood that this wall has been proposed as a generality in order to create a level building pad over the whole of the site. This wall is not a pre requisite to the development proposal. In fact it is recommended that the earthworks in this area not be finalised until finalisation of the building approval of the commercial premises per se.
- c) Adjacent to the existing flow path in lot 2, where the height of the wall is less than 1m.

The maximum grade of the finished allotments is approximately 20%. In the main, batter slopes are significantly less than this. The Applicant advises us that the allotments exhibiting higher grades will be the subject of individual house design to ensure attractive and practical use of these lots. No access grades to all allotments exceed 25%.

Generally, the grading of the site is such that the water table will not be intercepted either in association with the earthworks (including the detention pond), or in the construction of the proposed engineering services.

Services Generally

4.1 We are advised that the site is readily serviced with potable water, power and telecommunication facilities. Council has advised the provision of a suitable sewer outlet is problematic. The capacity of the Bilambil Heights sewer system is currently under review by Tweed Shire Council. The outfall requirements for this development are dependant on the results of this investigation. In order to provide surety to the development proposal, the Developer and Council have agreed a draft statement of commitments, specifying the worst case solution to the problem. A copy of the draft Statement of Commitments is given at Attachment 5.

A proposed solution to this issue has been prepared, and has been provided to Council directly for review and concurrence. Details of the proposed solution are provided below.

It is not proposed to stage any of the external infrastructure provision.

It is proposed to provide sewerage services to a number of allotments by means of a low pressure pump system, such as the E one system or Mono PCC Eco 1-60 system. Details of the Mono system, including WSAA review, are given at Attachment 6.

Effluent Disposal

The provision of sewerage services to the site will entail the construction of a pumping station, to be located approximately where shown on CLA Drawing 08418-002. The nearest point of connection available in the reticulation system is pump station SPS2038 in Peninsula Drive.

Council has advised however that, due to capacity issues, they are not able to approve connection to the reticulation system upstream of this pumping station.

Council has confirmed however that the nominated point of sewage disposal for the development is Pump Station SPS2018 Gollan Drive. The anticipated route of the required rising main is shown on CLA Drawing 08418-010.

Flood Assessment

Council has nominated the design flood level consistent with the level of the 100-year ARI event. In this instance, that level has been nominated as RL3.500. Note that this level has been based on the historical flood level in the area. Calculated flood level, based upon the 36 hour duration flood in the Tweed Valley is approximately RL2.500.

It will be understood that the site is generally well above this level. A small area of the site (approximately 1,350m²) lies to a maximum depth of 0.700m below the design flood level. The area is generally constrained within the site, however it does extend to the Bilambil Road Reserve. The area is currently drained via the Bilambil Road table drain.

In accordance with accepted practice, the potential flood storage volume lost as a result of the filling is replaced by compensatory excavation associated with the construction of the detention pond. It is anticipated that the volume of flood storage lost as a result of the development is approximately 470m³. It is anticipated that this volume will be compensated for by the ordering regarding of Lot 5 and 55.

Filling this area will not impact on any adjacent property.

It is noted that the NSW Floodplain Development Manual 2005 refers to the appropriate Flood Planning Level as that defined by the Local Authority. As previously stated, this is the Q100 level. It is felt that the marginal quantity of filling required to achieve the proposed earthworks levels is not sufficient to warrant detailed investigation of potential impacts, particularly in the light of the compensatory earthworks proposed.

The final minimum level of the allotments has been set at RL4.400m AHD, 900mm above the nominated Q100 flood level.

The proposal satisfies the requirement for the provision of a high level evacuation route to land above the level of the probable maximum flood level (PMF). We are advised by Council that the PMF level has been assessed at RL5.5m AHD.

The Planning Scheme defines the High Level Evacuation Route as a road or footway whose entire length has a level of not less than the design flood level (ie the Q100 Flood Level) and which provides a route to enable people to evacuate to land above the PMF. Not only is the bulk of the development site above the PMF level, the stated requirements for an evacuation route are provided by the vehicular and pedestrian access to Carool Road, at the intersection of Bilambil and Urliup Roads at a level approximately 2m above the Q100 level.

Climate Change

The DECC Guidelines – “Practical Consideration of Climate Change” (Oct 2007) recommend that development proposals consider the impact of climate change on the particular development.

The Tweed Shire Council is currently in the process of investigating these impacts, including a “high” impact case with 0.91m sea level rise and 30% increase in rainfall intensity. Draft results of that study, specifically related to the 36 hour duration event indicate an impact of the order of 1.5m increase in the flood level at the Q100 event.

It is not considered appropriate to apply this impact to the historical flood level. Rather, the calculated impact should be superimposed on the calculated flood level. Thus in considering the impact of climate change, the anticipated flood level would increase from RL3.500

(historically based) to RL4.00 (Design Based). In this instance, the development is provided with a minimum freeboard of 0.40m.

Legal Point of Discharge

Tweed Shire Council requires that stormwater runoff be discharged to a legal point of discharge, defined as a point on or adjacent to the development site, and (amongst other definitions) “a natural watercourse or waterway to which the site naturally drains”. Accordingly, Bilambil Creek is nominated as the appropriate legal point of discharge. This has been confirmed by Council.

Spoil Disposal

The preliminary earthworks plans indicate a potential 19,060m³ of spoil to be removed from the site. Spoil is to be removed from site in trucks for disposal at an approved location.

Filling Impacts

Earthworks for the site have been designed so that there is no filling at any external boundary, with the exception of a maximum of 900mm at the boundary of the site with the existing village hall. This height is consistent with the Tweed Planning Scheme.

Some additional earthworks may be required at the road frontages once detailed design in these areas takes place, however we would expect the requirement for filling to be only sufficient to achieve a free draining surface in the existing road verges.

Review of the pre development and post development contours confirms that the proposed earthworks do not serve to concentrate flows on to adjacent property, and that there is no impact on upstream properties.

Water Cycle Management

Tweed Shire Council has advised that the development does not trigger requirements for water quality improvement devices, in that the development does not have more than 50 allotments in a contributing catchment.

Roadworks

Adopted Cross Section - Internal

The adopted cross section for the internal roads is in accordance with the TSC requirements for a road designed to service less than 3,000 vehicles per day. The peak traffic load for the development, assuming only one access point, would be 342 vehicles per day, based upon anticipated traffic loading of 6 trips per allotment per day.

The adopted road cross section is indicated on the drawings.

Adopted Cross Section – External

Tweed Shire Council have specified their requirements in respect of works required in Hogans Road, Urliup Road and Bilambil Roads. These requirements have been included on the drawings.

Intersections

Road #1/Urliup Road

Urliup Road is an existing sealed road with a sealed width of approximately 6m. The road crest exhibits a substandard level of sight distance. The proposal anticipates the lowering of the existing crest by approximately 800mm in order to achieve the TSC sight distance standards. The orderly lowering of the road profile adjacent to the proposed intersection, coupled with the construction of the swales, and the reduction of the existing cut batter slope ensures that intersection sight distance standards are achieved.

Road #1/Hogans Road

Hogans Road is an existing sealed road with a seal width of approximately 6m. The road is essentially flat, although it does grade gently down to the causeway crossing Bilambil Creek. Survey reveals sight distance available of approximately 90m, in excess of the required standard. No other issues are anticipated in respect of this intersection.


ATTACHMENTS

ATTACHMENT 1 – Perspective Images Pre and Post Development
ATTACHMENT 2 – CLA Consultant Drawings 08418-001 to 009 inclusive
ATTACHMENT 3 – Site Based Stormwater Management Report
ATTACHMENT 4 - Rising Main Alignment


ATTACHMENT 1
Perspective Images Pre and Post Development

```
File Edit View Options Window Help
C:\Users\user\Documents\08418 - bilambil road bilambil\08418ns-.utl >
1: 1000000
2: 1000000
3: 1000000
4: 1000000
5: 1000000
6: 1000000
7: 1000000
8: 1000000
9: 1000000
10: 1000000
11: 1000000
12: 1000000
13: 1000000
14: 1000000
15: 1000000
16: 1000000
17: 1000000
18: 1000000
19: 1000000
20: 1000000
21: 1000000
22: 1000000
23: 1000000
24: 1000000
25: 1000000
26: 1000000
27: 1000000
28: 1000000
29: 1000000
30: 1000000
31: 1000000
32: 1000000
33: 1000000
34: 1000000
35: 1000000
36: 1000000
37: 1000000
38: 1000000
39: 1000000
40: 1000000
41: 1000000
42: 1000000
43: 1000000
44: 1000000
45: 1000000
46: 1000000
47: 1000000
48: 1000000
49: 1000000
50: 1000000
51: 1000000
52: 1000000
53: 1000000
54: 1000000
55: 1000000
56: 1000000
57: 1000000
58: 1000000
59: 1000000
60: 1000000
61: 1000000
62: 1000000
63: 1000000
64: 1000000
65: 1000000
66: 1000000
67: 1000000
68: 1000000
69: 1000000
70: 1000000
71: 1000000
72: 1000000
73: 1000000
74: 1000000
75: 1000000
76: 1000000
77: 1000000
78: 1000000
79: 1000000
80: 1000000
81: 1000000
82: 1000000
83: 1000000
84: 1000000
85: 1000000
86: 1000000
87: 1000000
88: 1000000
89: 1000000
90: 1000000
91: 1000000
92: 1000000
93: 1000000
94: 1000000
95: 1000000
96: 1000000
97: 1000000
98: 1000000
99: 1000000
100: 1000000
```


PRE DEVELOPMENT



Title: < C:\CLA Consultants\08455 - Gray St Tallebudgera Valley\08455rc1.ut1 >
File: < C:\CLA Consultants\08418 - bilambil road bilambil\084183su.ut3 >
Thu Mar 19 10:30:38 200
Vert ext 1 000
eye.x 554561.1
eye.y 288774.9
eye.z 635
bearing 0
pitch -4.61




ATTACHMENT 2
CLA Consultant Drawings 08418-001 to 009 inclusive



LOCALITY PLAN

SEWER RETICULATION
STORMWATER DRAINAGE
ROOFWATER DRAINAGE




PROPOSED ALLOTMENTS



ROAD PAVEMENTS



ROAD VERGE



PUBLIC OPEN SPACE



SEWAGE PUMP STATION



DRAWING SCHEDULE

NUMBER	DESCRIPTION
08418 - 001	SITE PLAN, DRAWING SCHEDULE & NOTES
08418 - 002	GENERAL ARRANGEMENT
08418 - 003	EARTHWORKS PLAN
08418 - 003A	EARTHWORKS - ISOPACHE DETAILS
08418 - 004	EARTHWORKS - INDICATIVE SECTIONS
08418 - 005	ROAD LONG SECTIONS - SHEET 1 OF 2
08418 - 006	ROAD LONG SECTIONS - SHEET 2 OF 2
08418 - 007	SEWER LAYOUT - GENERAL ARRANGEMENT
08418 - 008	SEDIMENT & EROSION CONTROL PLAN
08418 - 009	CONSTRUCTION MANAGEMENT PLAN
08418 - 011	EXTERNAL SEWER RISING MAIN ALIGNMENT

CLA Consultants
Civil & Structural Engineers
8/43 Tallebudgera Creek Road
West Burleigh Qld 4219
Ph: 07 5520 1066
Fax: 07 5520 1077
mail@claconsultants.com.au

CLIENT
**JACKSON INTERNATIONAL
PTY LTD**

PROJECT
**LOTS 2 & 3
BILAMBIL ROAD
BILAMBIL**

ASSOCIATED CONSULTANTS
-

PROPERTY DESCRIPTION	LOTS 2 & 3 DP244652
UBD REF.	
DESIGNED	CBL
DRAWN	ACAD
REVIEWED	CBL
DATE	15 JUNE 2008
APPROVED	




D	TSC REQ'S	CBL	15/03/09	CBL
C	REV LAYOUT	CBL	15/03/09	CBL
B	DA SUBMISSION	CBL	4/08/08	CBL
A	DA PROPOSAL	CBL	14/06/08	CBL
REV.	DESCRIPTION	BY	DATE	APPR'D

NAME
**SITE PLAN, DRAWING
SCHEDULE & NOTES**

PROJECT REF.	DRAWING NO.	REVISION
08418	001	D

1:500 @ A1 0 10 20 30 40 50M





SECTION #3

VERTICAL 1:250 @ A1

HORIZONTAL 1:250 @ A1

0

5

10

15

20

25M

0

5

10

15

20

25M

CLACONSULTANTS

Civil & Structural Engineers

8/43 Tallebudgera Creek Road

West Burleigh Qld 4219

Ph: 07 5520 1066

Fax: 07 5520 1077

mail@claconsultants.com.au

CLIENT

JACKSON INTERNATIONAL PTY LTD

PROJECT

LOTS 2 & 3
BILAMBIL ROAD
BILAMBIL

ASSOCIATED CONSULTANTS

-

PROPERTY DESCRIPTION

LOTS 2 & 3 DP244652

UBD REF.

DESIGNED

CBL

DRAWN

ACAD

REVIEWED

CBL

DATE

15 JUNE 2008

APPROVED


FIEAust CPEng RPEQ 4293

D	TSC REQ'S	CBL	20/05/09	CBL	
C	REV LAYOUT	CBL	15/03/09	CBL	
B	DA SUBMISSION	CBL	4/08/08	CBL	
A	DA PROPOSAL	CBL	14/06/08	CBL	
REV.	DESCRIPTION	BY	DATE	APPR'D	

NAME

EARTHWORKS
CROSS SECTIONS
SHEET 1 OF 2

PROJECT REF.	DRAWING NO.	REVISION
08418	004	D



VERTICAL 1:100 @ A1
HORIZONTAL 1:1,000 @ A1

CLA Consultants

Civil & Structural Engineers

8/43 Tallebudgera Creek Road

West Burleigh Qld 4219

Ph: 07 5520 1066

Fax: 07 5520 1077

mail@claconsultants.com.au

CLIENT

JACKSON INTERNATIONAL PTY LTD

PROJECT

LOTS 2 & 3
BILAMBIL ROAD
BILAMBIL

ASSOCIATED CONSULTANTS

-

PROPERTY DESCRIPTION

LOTS 2 & 3 DP244652

UBD REF.

DESIGNED

CBL

DRAWN

ACAD

REVIEWED

CBL


DATE

15 JUNE 2008

APPROVED

FIEAust CPEng RPEQ 4293

C	REV LAYOUT	CBL	15/03/09	CBL
B	DA SUBMISSION	CBL	4/08/08	CBL
A	DA PROPOSAL	CBL	14/06/08	CBL
REV.	DESCRIPTION	BY	DATE	APPR'D
NAME				
ROAD #1 LONGITUDINAL SECTION				
PROJECT REF.	DRAWING NO.	REVISION		
08418	006	C		



VERTICAL 1:100 @ A1
HORIZONTAL 1:1,000 @ A1

0.0 2.0 4.0 6.0 8.0 10.0M
0 20 40 60 80 100M

CLA Consultants

Civil & Structural Engineers
8/43 Tallebudgera Creek Road
West Burleigh Qld 4219
Ph: 07 5520 1066
Fax: 07 5520 1077
mail@claconsultants.com.au

CLIENT
JACKSON INTERNATIONAL
PTY LTD

PROJECT
LOTS 2 & 3
BILAMBIL ROAD
BILAMBIL

ASSOCIATED CONSULTANTS
-

PROPERTY DESCRIPTION

LOTS 2 & 3 DP244652

UBD REF.

DESIGNED

CBL

DRAWN

ACAD

REVIEWED

CBL

DATE

15 JUNE 2008

APPROVED


FIEAust CPEng RPEQ 4293

C	REV LAYOUT	CBL	15/03/09	CBL
B	DA SUBMISSION	CBL	4/08/08	CBL
A	DA PROPOSAL	CBL	14/06/08	CBL
REV.	DESCRIPTION	BY	DATE	APPR'D

NAME

ROAD #2
LONGITUDINAL SECTIONS

PROJECT REF.	DRAWING NO.	REVISION
08418	007	C



LEGEND

SILT FENCING



VEHICLE SHAKEDOWN






SEDIMENTATION POND



- Sedimentation and Erosion Control
1. Sedimentation and erosion control implementation and maintenance shall be in accordance with Byron Shire Council's Development Manual as read in conjunction with the document titles "Environmental Best Management Practices". The Contractor shall make himself aware of the prevailing weather conditions and shall take all necessary precautions to secure the site at the completion of each day's work, and whenever else is considered necessary.
 2. Sediment and erosion control measures shall be provided as required to prevent the movement of dust and/or silt from the site.
 3. Sediment and erosion control measures shall be installed downstream of any work area prior to the commencement of work in that area.
 4. Erosion and sedimentation control measures shall be installed prior to the disturbance of the site and as required during the course of the works.
 5. Topsoil shall be stripped in accordance with the specification and stockpiles at locations as agreed by the superintendent and Council's designated representative.
 6. All disturbed areas shall be stabilised with the provision of 75mm minimum topsoil and grass seeded, mulched, re-vegetated etc within 7 days of the completion of final allotment earthworks.
 7. All sediment control measures and devices shall be inspected for structural damage after each rainfall event and at the completion of each days work. All trapped sediment shall be removed to an approved location on site for re-use on site or for subsequent removal from the site. Site disposal will only be approved when it can be established that no additional erosion can occur.
 8. Sediment and erosion control measures around stockpiles shall include but not necessarily be limited to--
 - a) Provision of a silt fence below the stockpile, as indicated by the natural slopes of the land,
 - b) Provision of grass cover if stockpile is to remain in place for more than 30 days,
 - c) Provision of a surface emulsion or approved equivalent to prevent wind erosion.
 - d) Diversion of runoff around stockpiles.
 9. Place 600mm width turf at both top and toes of retaining walls and tops of new kerb.
 10. Water areas of construction regularly as required to obviate potential for dust nuisance to adjoining properties and the site generally.
 11. Contractor to be responsible for removal of silt that is washed onto Council or private property from subject site.
 12. Contractor to make provision for containment of waste materials on site including waste oils etc from machinery servicing.
 13. Contractor to be responsible for the control of dust at all times including weekends and holidays.

Construction Traffic Shakedown
Provide construction traffic shake down device at all relevant site exit points. Clean out and maintain shake down device regularly to ensure efficient operation.



Prior to the Commencement of Works		
a	Submission of a copy of the Contractor's Program for the Works.	Contractor
b	Submit program for the implementation and monitoring (inspection type) of the specified sedimentation control measures for approval.	Contractor
c	Approve submitted program	Superintendent /Council
During Construction		
a	Install sedimentation and control measures (measures)	Contractor
b	Approval of the Measures as constructed	Superintendent
c	Periodic inspection of the measures	Contractor
d	Rectification of issues identified by periodic inspection	Contractor
e	Inspection of adjacent roads and drains	Contractor
On Maintenance		
a	Submit program for the continued maintenance of the works during the "On Maintenance" period.	Contractor
b	Approve submitted program	Superintendent in conjunction with Council
c	Install/maintain sedimentation and erosion control measures	Contractor
Off Maintenance		
d	Approval of Measures as implemented	Contractor
e	Routine inspection of implemented measures (including adjacent road network)	Superintendent
f	Rectification/Reinstatement of sediment and erosion control measures	Contractor
g	Removal of Erosion and sedimentation Control Measures	Contractor
Prior to the Pre-Start Meeting		
		Prior to the Pre-Start Meeting
		Prior to the Pre-Start Meeting
		Prior to the commencement of works necessitating the measures
		Prior to the commencement of works necessitating the measures
		Daily and after rainfall event
		At least weekly and/or in conjunction with other required inspections
		Immediately
		Daily and after rainfall event
		Prior to On Maintenance inspection.
		Prior to On Maintenance inspection.
		Prior to On Maintenance inspection.
		During On Maintenance Period
		At On Maintenance Inspection
		Weekly, and after each rainfall event
		As requested by the Contractor
		As soon as practicably possible (24 hours max)
		As directed by the Superintendent

SEWER RETICULATION

STORMWATER DRAINAGE

ROOFWATER DRAINAGE

PROPOSED ALLOTMENTS

ROAD PAVEMENTS


ROAD VERGE

PUBLIC OPEN SPACE

SEWAGE PUMP STATION



1:1,000 @ A1



CLA Consultants
Civil & Structural Engineers
8/43 Tallebudgera Creek Road
West Burleigh Qld 4219
Ph: 07 5520 1066
Fax: 07 5520 1077
mail@claconsultants.com.au

CLIENT
JACKSON INTERNATIONAL PTY LTD

PROJECT
**LOTS 2 & 3
BILAMBIL ROAD
BILAMBIL**

ASSOCIATED CONSULTANTS
-

PROPERTY DESCRIPTION
LOTS 2 & 3 DP244652

UBD REF.

DESIGNED
CBL

DRAWN
ACAD

REVIEWED
CBL

DATE
15 JUNE 2008

APPROVED

FIEAust CPEng RPEQ 4293

D	TSC REQ'S	CBL	20/05/09	CBL
C	REV LAYOUT	CBL	15/03/09	CBL
B	DA SUBMISSION	CBL	4/08/08	CBL
A	DA PROPOSAL	CBL	14/06/08	CBL
REV.	DESCRIPTION	BY	DATE	APPRD

NAME
**WATER QUALITY
MANAGEMENT
CONSTRUCTION PHASE**

PROJECT REF.	DRAWING NO.	REVISION
08418	008	D



- CONSTRUCTION MANAGEMENT PLAN
1. TEMPORARY LOCKABLE 1.8M CHAIN MESH FENCE TO BE ERECTED AS SHOWN.
 2. NOTICEBOARD SHOWING CONTACT DETAILS OF CONTRACTOR TO BE ERECTED NEAR CONSTRUCTION ENTRANCE. MUST BE VISIBLE FROM STREET.
 3. ALL WORKERS TO PARK VEHICLES ON SITE WHERE POSSIBLE.
 4. WATER SPRAYING OF DUST TO BE UNDERTAKEN AS REQUIRED.
 5. INSTALL CONSTRUCTION ENTRANCE/EXITS ON SITE AS SHOWN ABOVE AND ON SEDIMENT AND EROSION CONTROL PLAN.
 6. ALL WORKS TO BE CARRIED OUT BETWEEN 6:00AM AND 6:00PM MONDAY TO SATURDAY.
 7. ALL SUITABLE EXCAVATED MATERIAL TO BE REUSED ON SITE.
 8. CONSTRUCTION SKIPS TO BE PROVIDED ON SITE FOR BUILDERS' RUBBISH. TO BE EMPTIED AS REQUIRED.
 9. NO HAZARDOUS OR DANGEROUS MATERIALS TO BE KEPT ON SITE.
 10. ALL DELIVERIES TO BE STAGED TO AVOID CONGESTION ON PUBLIC ROADS.
 11. PEDESTRIAN DETOUR TO TAKE PLACE AT ALL TIMES WHEN WORKS ARE BEING UNDERTAKEN ON PUBLIC ROAD. ARRANGE PRE-START MEETING WITH COUNCIL TO ENSURE COMPLIANCE WITH COUNCIL REQUIREMENTS.

- PEDESTRIAN DETOUR
1. DIRECTION OF DETOUR TO BE CLEARLY MARKED TO PEDESTRIANS.
 2. DETOUR TO BE MINIMUM 1.5M WIDE, 2.0M PREFERABLE.
 3. CLEAR ALL DEBRIS FROM PEDESTRIAN PATH, MAKE GROUND FIRM AND LEVEL, ADD GRAVEL AND WHEEL ROLL AS REQUIRED.
 4. ERECT CONSTRUCTION FENCING TO BOTH SIDES OF DETOUR WITHIN SUBJECT SITE.
 5. ARRANGE INSPECTION WITH PARKS DEPARTMENT OF COUNCIL PRIOR TO DIVERSION OF PEDESTRIAN FLOW.
 6. RESTORE ALL AREAS OUTSIDE SUBJECT SITE TO PREDEVELOPMENT CONDITION TO THE SATISFACTION OF COUNCIL.

CLA Consultants
Civil & Structural Engineers
8/43 Tallebudgera Creek Road
West Burleigh Qld 4219
Ph: 07 5520 1066
Fax: 07 5520 1077
mail@claconsultants.com.au

CLIENT
JACKSON INTERNATIONAL
PTY LTD

PROJECT
LOTS 2 & 3
BILAMBIL ROAD
BILAMBIL

ASSOCIATED CONSULTANTS
-

PROPERTY DESCRIPTION	LOTS 2 & 3 DP244652
UBD REF.	
DESIGNED	CBL
DRAWN	ACAD
REVIEWED	CBL
DATE	15 JUNE 2008
APPROVED	 FIEAust CPEng RPEQ 4293

C	REV LAYOUT	CBL	15/03/09	CBL
B	DA SUBMISSION	CBL	4/08/08	CBL
A	DA PROPOSAL	CBL	14/06/08	CBL
REV.	DESCRIPTION	BY	DATE	APPR'D

NAME
CONSTRUCTION
MANAGEMENT PLAN

PROJECT REF.	DRAWING NO.	REVISION
08418	009	C