

Hyder Consulting Pty Ltd

ABN 76 104 485 289

Level 5, 141 Walker Street

Locked Bag 6503

North Sydney NSW 2060

Australia

Tel: +61 2 8907 9000

Fax: +61 2 8907 9001

www.hyderconsulting.com



24th November 2009

Abbey Johnson,
Bovis Lend Lease
The Bond, 30 Hickson Road,
Millers Point
SYDNEY NSW 2000

Your Ref:

Our Ref: DN00200

Direct phone: 8907 9065

Darling Walk Harbour Street – Footpath Alignment Levels.

Dear Abbey,

In response to City of Sydney comment regarding Alignment Levels raised in their letter reference R/2009/123.

Alignment levels have been coordinated with the Architectural Building entry levels so that footways throughout the site can be designed in accordance with Australian Standard 1428.1 – 2001 – Design for access and mobility – Part 1: General requirements for access – New building work. The minimum footpath width of 1.0m and the maximum footpath crossfall at 2.5% complies with the requirements of the above standard.

The minimum footpath width along Harbour Street is 3.5m as required by the RTA with a maximum crossfall of 2.5% falling away from the building. The footpath area at the Civic Connector has been designed to fall to the west to provide a safe overland flow path in the 100 year event.

Yours sincerely

A handwritten signature in black ink, appearing to read 'Michael Kurtz', with a long horizontal stroke extending to the right.

Michael Kurtz

For

Hyder Consulting Pty/Ltd