Appendix A - Updated project description

This appendix provides the proposed changes to the project description for the previously approved Stage 1 and Concept Plan. The updates are presented in bold **blue** text (for new text) or **red** strikethrough (for deleted text). The proposed modification of the Port Kembla Outer Harbour Development is comprised of three key stages as follows (Note: Stage 1A works associated with the Cement Australia Grinding Mill have been completed):

- Stage 1 (1A, 1B and 1C)
 - demolition of No.3, No. 4 Jetties (including) Berth 206 and Jetty No. 6
 - reclamation of and dredging for the footprint of the total development including dredging (except for the northern area of the multi-purpose terminal);
 - construction and operation of one new multi-purpose terminal (central area);
 - construction of first container berths;
 - extension of Salty Creek and Darcy Road drain, through the reclamation area, to the Outer Harbour
 - relocation of utilities for import of sulphuric acid (currently at Berth 206) to the multipurpose terminal;
 - new road link from Christy Drive;
 - rail infrastructure upgrade in South Yard, No.13 siding; and
 - civil works for construction of terminal facilities including services
 - New navigation lead towers
 - Stage 1A (Cement Australia Grinding Mill)
 - establishment of a processing plant including transfer hoppers, storage bins, grinding mill and storage silos for dispatch;
 - a materials transfer system, incorporating extensive covered and closed conveyor systems, transfer chutes, dust suppression system and bag house;
 - clinker storage shed;
 - truck and ship loading and unloading facilities;
 - internal road systems and parking;
 - temporary covered stockpile for raw product; and associated office amenities, workshop and substation.
- Stage 2
 - reclamation for the northern area of the multi-purpose terminals;
 - operation of the first container berth;
 - construction and operation of second container berth;
 - construction development and operation of a second multi-use berth and terminal (including but not limited to an offshore wind and cargo terminal uses)

- extension of new road link from Christy Drive (and option for a new parallel road to Foreshore Road);
- new road link from Darcy Road to the recreational boat harbour;
- new rail overbridge across Foreshore Road; and
- new rail link and siding to the container terminals.
- Stage 3
 - demolition of No. 6 Jetty;
 - reclamation and dredging for northern area for the multipurpose terminals and berth;
 - dredging to widen swing basin in northern Outer Harbour;
 - construction development and operation of container terminal second and third multipurpose berth and terminal;
 - Note: The Cement Australia Grinding Mill is subject to its own project approval
 (10_0102), including a number of monitoring and reporting requirements which are the
 responsibility of Cement Australia.
 - construction and operation of the eastern container terminals; (including third and fourth container berths); and
 - construction of the container terminal northern piled structure.
 - Rail link and siding to the container terminal