

Proposed Modification to Sapphire Wind Farm
Noise Impact Assessment

Report Number 640.11227R1

19 April 2016

Wind Prospect CWP Pty Ltd
45 Hunter Street
NEWCASTLE NSW 2300

Version: Revision 3

Proposed Modification to Sapphire Wind Farm

Noise Impact Assessment

PREPARED BY:

SLR Consulting Australia Pty Ltd
ABN 29 001 584 612
Suite 6, 131 Bulleen Road
Balwyn North VIC 3104 Australia

T: +61 3 9249 9400 F: +61 3 9249 9499
melbourne@slrconsulting.com www.slrconsulting.com

This report has been prepared by SLR Consulting Australia Pty Ltd with all reasonable skill, care and diligence, and taking account of the timescale and resources allocated to it by agreement with the Client. Information reported herein is based on the interpretation of data collected, which has been accepted in good faith as being accurate and valid.

This report is for the exclusive use of Wind Prospect CWP Pty Ltd. No warranties or guarantees are expressed or should be inferred by any third parties. This report may not be relied upon by other parties without written consent from SLR.

SLR disclaims any responsibility to the Client and others in respect of any matters outside the agreed scope of the work.

DOCUMENT CONTROL

Reference	Status	Date	Prepared	Checked	Authorised
640.11227R1	Revision 3	19 April 2016	Gustaf Reutersward	Jim Antonopoulos	Gustaf Reutersward
640.11227R1	Revision 2	1 March 2016	Gustaf Reutersward	Jim Antonopoulos	Gustaf Reutersward
640.11227R1	Revision 1	10 February 2016	Gustaf Reutersward	Jim Antonopoulos	Gustaf Reutersward
640.11227R1	Revision 0	9 February 2016	Gustaf Reutersward	Jim Antonopoulos	Gustaf Reutersward

EXECUTIVE SUMMARY

This report details a revised noise impact assessment for a proposed modification to the approved Sapphire Wind Farm. The proposed modified project utilises a reduced number of wind turbine generators (WTGs), each of greater size and capacity to those in the approved project. The proposed modification to Sapphire Wind Farm incorporates a layout of up to 109 WTGs, with a maximum tip height of 200 m and 3 MW to 3.4 MW capacities, whereas the approved wind farm had two alternative layout options of 159 WTGs and 125 WTGs with a maximum tip height of 159 m and between 2MW and 3MW capacity respectively.

Background noise monitoring was undertaken in July 2009. Full details of the monitoring are provided in the original Sapphire Wind Farm Noise Assessment report (reference: report 40.1822 – R1R3 Section 6, dated August 2011).

The noise criteria adopted for both the original Sapphire Wind Farm Noise Assessment in 2011 and this updated assessment are based on the South Australia EPA *Noise Guidelines for Wind Farms*, 2003 (SA EPA Guidelines). Where noise levels at project-involved residences do not comply with the SA EPA Guidelines, the proponent intends to enter into agreements with the owners of those residences to achieve noise criteria in accordance with World Health Organisation (WHO) Guidelines.

Noise predictions of the proposed modification to the wind farm layout were made using the SoundPLAN software package, utilising ISO9613 algorithms and have assumed acoustically hard ground. Four alternative turbine models were considered, being:

- Vestas V126 Standard Blade
- Vestas V126 Serrated Blade Option - Mode 0
- GE 137 3.4 MW (which uses a serrated blade design)
- Servion M122

The results for the Vestas V126 – Standard blade model, indicated that the wind farm may potentially exceed the relevant noise limits at up to 11 receptors.

The results for the Vestas V126 – serrated blade Option model, indicated that the wind farm may potentially marginally exceed the relevant noise limits at a single receptor.

A mitigation investigation was undertaken for the Vestas V126 serrated blade Option model utilising Sound Management Mode. Compliance at all receptors can be achieved using a mitigated layout where three WTGs are operated in Sound Management Mode 2. It should be noted that when WTGs are configured in Sound Management Mode they are always operating in the reduced noise mode, which is distinctly different from Sector Management.

The results for the Servion M122 and GE 137 layouts, indicate that the wind farm may potentially marginally exceed the relevant noise limits at a single receptor. It is anticipated that a mitigation layout for these models will be possible through the implementation of a reduced output Sound Management Mode or the removal of a turbine from the current layout.

This noise impact assessment of the proposed modifications to Sapphire Wind Farm has shown that compliance with the noise limit requirements is attainable.

Table of Contents

1	INTRODUCTION	5
2	SITE LAYOUT	6
3	LEGISLATION & GUIDELINES	11
3.1	SA EPA Wind Farm Noise Guidelines	11
3.2	World Health Organisation (WHO) Guidelines	12
4	BACKGROUND NOISE LEVELS	13
5	OPERATIONAL NOISE CRITERIA	15
6	NOISE ASSESSMENT	16
6.1	Model Inputs	16
6.2	Assessment of Tonality and Infrasound	16
6.3	Noise Model Predictions	17
6.4	Mitigation Layout	21
7	COMPARISON TO ORIGINAL LAYOUTS	22
8	CONCLUSION	23

TABLES

Table 1	Receptor locations (UTM, GDA 94)	6
Table 2	Sapphire - proposed WTG locations (UTM, GDA 94)	9
Table 3	WHO Guideline values for environmental noise in specific environments	12
Table 4	Background noise regression equations	13
Table 5	Wind Farm Noise Criteria	15
Table 6	WTG Manufacturers data	16
Table 7	WTG Sound Power Level values (dBA)	16
Table 8	Audible tonality $\Delta L_{A,k}$ assessment to IEC 61400-11	17
Table 9	Predicted Noise Levels – dBA Leq	17
Table 10	Vestas V126 Standard Blade - Predicted Exceedances (dBA)	19
Table 11	Vestas V126 Serrated Blade Option (Mode 0) - Predicted Exceedances (dBA)	19
Table 12	GE137 - Predicted Exceedances (dBA)	19
Table 13	Senvion M122 - Predicted Exceedances (dBA)	20
Table 14	Mitigated Turbine Layout - Vestas V126 WTG Serrated Blade Option	21

FIGURES

Figure 1	Site overview (image courtesy Google Earth)	6
Figure 2	Receptor groupings for background noise	14

APPENDIX A Noise Assessment Graphs

APPENDIX B Noise Contour Maps

1 INTRODUCTION

SLR Consulting Australia Pty Ltd (SLR) have been engaged by Wind Prospect CWP Pty Ltd to complete a noise impact assessment for a proposed modification to the approved Sapphire Wind Farm, located approximately 28 km east of Inverell and approximately 18 km west of Glen Innes in NSW.


SLR (previously Heggies Pty Ltd) has been involved with the project since 2009 having previously completed the original noise impact assessments for Sapphire Wind Farm EIS. The original noise impact assessment report (reference: 40.1822 – R1R3, dated August 2011) is still relevant as it details the baseline noise monitoring undertaken for the project in 2009.

The modified project utilises a reduced number of wind turbine generators (WTGs), each with greater size and capacity. A layout of 109 WTGs is now being considered, whereas the approved wind farm had two alternative layout options of 159 WTGs and 125 WTGs. The maximum tip height will be increased to 200 m (previously 159 m) and WTGs of 3 MW to 3.4 MW size are being considered.

2 SITE LAYOUT

Figure 1 shows the locations of all receptor and the proposed WTG positions of the modified layout for Sapphire Wind Farm.

Figure 1 Site overview (image courtesy Google Earth)



A tabulated list of the receptors with details including their position, distance to closest WTGs from Sapphire Wind Farm and project involved host property status are included in **Table 1**.

A tabulated list of the proposed WTG positions for the modified layout for Sapphire Wind Farm is included in **Table 2**.

Table 1 Receptor locations (UTM, GDA 94)

ID	Property Name	X (m East)	Y (m North)	Closest WTG (km)	Project Involved?
R4	Bon Vista	353963	6715399	5.2	No
R5*	Evergreen	356394	6711085	2.2	Yes
R6*	Farley	356456	6710613	2.1	Yes
R7	Arranmore	355281	6711556	1.8	No
R8*	Woodburn	354732	6711418	1.6	Yes
R9	Tomali Park	354057	6710881	1.1	No
R10*	Osterley	356198	6706640	1.2	Yes
R11*	Yarrabin	352430	6711700	1.4	Yes

ID	Property Name	X (m East)	Y (m North)	Closest WTG (km)	Project Involved?
R12*	Mubbarra	351836	6711039	1.0	Yes
R13*	Narren Vale	347974	6712731	1.2	Yes
R14*	Kingshill	347698	6712560	1.0	Yes
R15*	Kia-Tami	345866	6709763	1.7	Yes
R16*	Woodstock	344726	6710350	1.4	Yes
R17	Strathdarr	348058	6714317	1.6	No
R18*	Yarrandoo	347511	6714046	1.4	Yes
R19*	Warrandah	348550	6715477	1.3	Yes
R20*	Lochlea	348541	6715879	1.2	Yes
R21*	311	348398	6715876	1.1	Yes
R23*	Carinya	346594	6718876	1.6	Yes
R24*	Derra Downs	345940	6718333	1.1	Yes
R25	Coleraine	342378	6719178	2.1	No
R26*	Spring Creek	341800	6715923	1.8	Yes
R27	Frasers Creek	341601	6716137	2.0	No
R28*	Tralee	342175	6715048	1.3	Yes
R29	Krystal Blue	341123	6713504	2.8	No
R30	Argyle	340979	6711465	3.8	No
R31	Glen Valley	340512	6709341	5.0	No
R32	Swan Peak	341074	6709238	4.6	No
R33*	Highlands	344366	6709456	2.3	Yes
R34*	Bellview	345747	6705021	5.0	Yes
R35	Golden Grove	347645	6705095	4.0	No
R36*	Yarrawa Park	348460	6705713	3.2	Yes
R37*	Coorimbla Park	348720	6705206	3.6	Yes
R38*	Inverness	349208	6704597	4.1	Yes
R39	Bon Vista	350062	6706296	2.4	No
R40	Hillview	350617	6705977	2.8	No
R41	Royal Oaks	351407	6705486	3.4	No
R42	Ashgrove	351629	6705174	3.7	No
R43	Warrawee	352554	6704583	3.9	No
R44	Mindora	352071	6705883	2.9	No
R45	Glen Idle	352517	6705629	3.1	No
R46	Alkoomie	352981	6706029	2.5	No
R47	Pieta	353569	6705096	2.9	No
R48	Adavale	359518	6707474	4.1	No
R49*	Evergreen	359844	6709367	4.3	Yes
R50	Waterloo	361396	6709936	5.9	No
R52	Waterloo Cottage	361416	6710180	6.0	No
R53*	Maids Valley	360243	6711025	5.2	Yes
R54	Fassifern	361144	6710913	6.0	No

ID	Property Name	X (m East)	Y (m North)	Closest WTG (km)	Project Involved?
R55	Tarana	360055	6711821	5.5	No
R56*	Fruin Glen	359066	6713012	5.5	Yes
R76*	Cubba	352218	6715832	4.6	Yes
R77	Meadow Vale	352892	6715346	4.7	No
R78	Pine Grove	353148	6714764	4.4	No
R79*	Woodburn	353527	6714064	3.8	Yes
R80*	Weean Cottage	349763	6718186	2.5	Yes
R81*	Weean	349717	6718265	2.5	Yes
R84	Glenidle	350098	6719960	3.9	No
R85*	Windemere	348773	6720327	3.5	Yes
R86	Millie	346918	6720977	3.7	No
R87	Croye	345670	6720193	2.4	No
R88*	Woodlands	345634	6722038	4.1	Yes
R89	Tomali Park	341348	6716963	2.5	No
R90	Wirra Willa	340648	6716052	2.9	No
R91	Roseana	339091	6715753	4.4	No
R92	Lambert	339201	6714752	4.3	No
R93	Swamp Oak	338494	6714102	5.1	No
R94	The Knoll	339343	6714044	4.3	No
R95	Rock Leigh	339587	6713397	4.2	No
R96	Unknown	338144	6713314	5.6	No

Table 2 Sapphire - proposed WTG locations (UTM, GDA 94)

Name	X	Y	Name	X	Y
1	347266	6716525	60	348340	6709831
2	344448	6716872	61	348429	6709584
3	344926	6717491	62	348750	6709223
4	344998	6717747	63	349698	6708647
5	345798	6717147	64	349373	6708822
6	346048	6716872	65	348923	6708922
7	345625	6716269	70	350498	6708972
8	344648	6717197	71	351173	6709797
9	346578	6716639	72	350664	6709622
10	347523	6717047	73	350748	6709322
11	347648	6716697	74	351458	6709627
12	346598	6716922	75	352223	6708847
13	346324	6717322	76	351898	6708822
14	347223	6715697	77	351748	6709097
15	346548	6715672	78	351455	6709353
16	346473	6715397	79	351323	6710022
17	344023	6715872	80	351097	6710241
18	344223	6715572	81	350946	6710557
19	344323	6715147	82	349451	6710805
20	343623	6714847	83	350035	6710600
21	343498	6715397	84	349573	6709797
22	343623	6715647	85	349448	6710222
23	343473	6715097	86	349198	6709972
24	343823	6714547	87	349954	6709563
28	345198	6713672	88	350351	6710840
29	345323	6713997	89	350285	6711138
30	345173	6714497	90	349873	6711322
33	344774	6713167	91	349898	6711697
34	345018	6713397	92	350142	6711527
36	345542	6714321	93	349726	6711927
37	345023	6714722	94	349003	6712128
38	344873	6714947	95	349149	6711937
39	344798	6714172	96	349420	6711771
40	344448	6714297	97	353073	6710047
41	344373	6714597	98	353098	6709772
42	345898	6713747	99	353198	6709422
43	345848	6713997	100	353433	6708881
44	346223	6713497	101	353923	6709522
45	345673	6711472	102	353923	6709797
46	345148	6711647	103	354398	6709372

Name	X	Y	Name	X	Y
47	344798	6711922	104	354423	6709647
48	344673	6712197	105	354523	6709872
155	344633	6718073	106	354423	6709122
156	343761	6717550	107	354398	6708872
157	344316	6717905	108	352898	6710349
158	344086	6717689	109	353300	6709174
159	346737	6716252	110	354198	6708622
52	347723	6711197	111	354323	6708297
53	347973	6710822	112	353774	6708606
54	347998	6710572	113	355441	6708221
55	347998	6710297	114	355598	6708672
56	348073	6710022	115	354843	6707728
57	347848	6711447	116	354848	6708097
58	348794	6711276	117	355298	6707422
59	347498	6711572			

3 LEGISLATION & GUIDELINES

The noise criteria adopted for both the original Sapphire Wind Farm Noise Assessment in 2011 and this updated assessment are based on the South Australia EPA *Noise Guidelines for Wind Farms*, 2003 (SA EPA Guidelines).

The SA EPA Guidelines are still the current assessment guideline adopted in NSW.

3.1 SA EPA Wind Farm Noise Guidelines

The SA EPA Guidelines recommend the following noise criteria for new wind farms,

“The predicted equivalent noise level ($L_{Aeq, 10min}$), adjusted for tonality in accordance with these guidelines, should not exceed:

- 35 dBA, or
- the background noise level by more than 5 dBA,

whichever is the greater, at all relevant receivers for each integer wind speed from cut-in to rated power of the WTG.”

The guidelines also provide information on measuring the background noise levels, locations and requirements on the number of valid data points to be obtained and the methodology for excluding invalid data points. It also outlines the process for determining lines of best fit for the background data, and determination of the noise limit.

The Guideline explicitly states that the “swish” or normal modulation noise from wind turbines is a fundamental characteristic of such turbines; however, it specifies that tonal or annoying characteristics of turbine noise should be penalised.

A 5 dBA penalty should be applied to the measured noise level if an “authorised” officer determines that tonality is an issue and that tonality should be assessed in a way acceptable to the EPA.

The Guideline does not provide an assessment for the potential of low frequency noise or infrasound, but it does state that recent turbine designs do not appear to generate significant levels of infrasound, as the earlier turbine models did.

The Guideline accepts that wind farm developers commonly enter into agreements with private landowners in which they are provided compensation. The guideline is intended to be applied to premises that do not have an agreement with the wind farm developer. This does not absolve the obligations of the wind farm developer entirely as appropriate action can be taken under the *Environmental Protection Act* if a development ‘unreasonably interferes’ with the amenity of an area. The guideline lists that there is unlikely to be unreasonable interference if:

- a formal agreement is documented between the parties
- the agreement clearly outlines to the landowner the expected impact of the noise from the wind farm and its effect on the landowner’s amenity
- the likely impact of exposure will not result in adverse health impacts (e.g. the level does not result in sleep disturbance)

The proponent has discussed the possible noise implications of the proposed turbine layout with the involved residents whose property the turbines would be located on and will enter into agreements with these parties.

These agreements would specify that:

- (a) The proponent would ensure that noise levels at the properties meet the World Health Organisation noise guidelines (see **Section 3.2**); and,
- (b) The proponent would implement an adaptive management approach which could include the use of building treatments and turbine operation / management strategies if operational noise causes significant impact to the amenity of involved residents.

This noise agreement would only be required under those turbine configurations where the SA EPA Guidelines would be exceeded for that particular property.

3.2 World Health Organisation (WHO) Guidelines

Where noise levels at project-involved residences do not comply with the SA EPA Guidelines, the proponent intends to enter into agreements with the owners of those residences to achieve noise criteria in accordance with World Health Organisation (WHO) Guidelines. The proponent will apply those guidelines as necessary to ensure that the project does not result in an 'unreasonable interference' with the amenity or cause any adverse health effects at those residences. (See **Section 3.1**)

The WHO publication '*Guidelines for Community Noise*' identifies the main health risks associated with noise and derives acceptable environmental noise limits for various activities and environments.

The appropriate guideline limits are listed in **Table 3** below.

Table 3 WHO Guideline values for environmental noise in specific environments

Specific Environment	Critical Health Effect(s)	Leq (dBA)	Time base (hours)	L _{Max} (dBA, Fast)
Outdoor living area	Serious Annoyance, daytime & evening	55	16	-
	Moderate annoyance, daytime & evening	50	16	-
Dwelling indoors	Speech Intelligibility & moderate annoyance, daytime & evening	35	16	
Inside bedrooms	Sleep disturbance, night-time	30	8	45
Outside bedrooms	Sleep disturbance – window open, night-time	45	8	60

For the assessment of project involved residences the adopted external criteria of 45 dBA or the level given by the SA EPA Guideline criteria, where higher, will be adopted. Effectively this becomes 45 dBA or background + 5 dBA, whichever is the higher.

4 BACKGROUND NOISE LEVELS

Background noise monitoring was undertaken in July 2009. The noise data was correlated to wind speed at a reference height of 100 m above ground level. Full details of the monitoring are provided in the original Sapphire Wind Farm Noise Assessment report (reference: report 40.1822 – R1R3 Section 6, dated August 2011).

Table 4 shows the background noise at each monitoring location, regressed to a third order polynomial function.


Table 4 Background noise regression equations

Location	Indicative of	
R3-Falkland *	R1*, R3*, R59*, R2*, R57, R56*, R58	$y = -0.0119x^3 + 0.2502x^2 - 1.1965x + 29.512$
R64-Springfield	R60, R61, R62*, R63, R64*, R65, R73, R72, R71, R70, R69, R74	$y = 0.0016x^3 - 0.114x^2 + 1.8662x + 21.965$
R43- Ardleigh	R43, R47	$y = -0.0118x^3 + 0.4502x^2 - 3.071x + 33.042$
R5- Down Field *	R5*, R55, R49*, R53, R54, R6*, R52, R50, R7, R8*, R9*, R11*, R12*	$y = -0.0185x^3 + 0.4987x^2 - 3.4598x + 45.145$
R14-Kingshill *	R14*, R13*, R17, R18*, R15*, R16*, R33*	$y = 0.0079x^3 - 0.1564x^2 + 1.6257x + 33.331$
R23-Carinya *	R24*, R23*, R25, R87, R86, R80*, R81*, R84, R85*, R88*	$y = 0.0137x^3 - 0.2774x^2 + 2.6662x + 18.733$
R28-Tralee *	R28*, R26*, R27, R29, R90, R30, R94, R91, R93, R92, R31, R32, R89, R95, R96	$y = 0.0191x^3 - 0.4642x^2 + 4.0333x + 18.138$
R36 Yarrawah Park *	R36*, R37*, R35, R38*, R34*	$y = 0.0056x^3 - 0.0723x^2 + 0.5553x + 27.644$
R44-Mindora	R46, R45, R41, R42, R39, R40, R44	$y = 0.0296x^3 - 0.6802x^2 + 5.6064x + 15.111$
R10-Mt Buckley	R10, R48	$y = -0.0168x^3 + 0.5433x^2 - 3.3808x + 32.251$
R19-Warrandah *	R20*, R21*, R19*, R76*, R77, R4*, R78, R79*	$y = -0.0301x^3 + 0.894x^2 - 6.3934x + 39.852$

Note: * denotes that property is project involved

Receptors were grouped into general regions where background noise monitoring locations were deemed indicative of the receptors of that region. The groupings are presented pictorially in **Figure 2**.

Figure 2 Receptor groupings for background noise



5 OPERATIONAL NOISE CRITERIA

As discussed in **Section 4** the noise criteria for the project are based on the monitoring and analysis completed for the original Noise Impact Assessment for Sapphire Wind Farm and are re-presented in **Table 5** as a function of hub height wind speed.

Table 5 Wind Farm Noise Criteria

Receiver Location / Group	Height z	Noise Limit, dBA @ Wind Speed Vz (m/s)									
	10m	3	4	5	6	7	8	9	10	11	12
	100m	4.3	5.7	7.2	8.6	10.0	11.5	12.9	14.3	15.8	17.2
	139m	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0	16.5	18.0
R3-Falkland *		35	35	35	35	36	36	35	35	35	35
R64-Springfield		35	35	35	36	36	36	35	35	35	35
43- Ardleigh *		35	35	35	37	41	44	48	52	55	58
R5- Down Field *		43	43	44	46	47	48	49	49	47	44
R14-Kingshill *		43	44	45	46	47	48	50	53	56	60
R23-Carinya *		35	35	35	35	36	39	41	45	51	57
R28-Tralee *		35	35	35	36	36	37	39	42	46	52
R36 Yarrawah Park *		35	35	35	36	37	38	40	42	45	49
R44-Mindora		35	35	36	37	38	40	43	48	56	66
R10-Mt Buckley		35	35	35	38	41	45	48	51	53	54
R19-Warrandah *		35	35	35	37	40	44	47	48	48	46

Note: * denotes that property is project involved

6 NOISE ASSESSMENT

6.1 Model Inputs

Noise emissions for the proposed WTG have been determined or estimated by the manufacturers from measurements conducted in accordance with International Standard IEC 61400-11. Copies of the certification test or manufacturers documentation that give the sound power level variation with wind speed, frequency spectra and tonality assessment have been provided to SLR by Wind Prospect CWP Pty Ltd and will be made available on request

Table 6 and **Table 7** summarise the relevant turbine input data used for noise level prediction.

Table 6 WTG Manufacturers data

Make, model, power	Vestas V126 3.3 MW	GE 137 3.4 MW	Senvion M122 3.0 MW
Rotor diameter	126 m	137 m	122 m
Hub height	137 m	135 m	139 m
Cut-in wind speed	3 m/s	3 m/s	3 m/s
Rated wind speed	7.5 m/s		11 m/s
Rotor speed	5.3 -16.5 rpm		5.6 -11.3 rpm
'Standard Mode' Sound Power Level, LWA,ref 8 m/s	108.5 ¹ dBA	106 dBA	103.9 dBA

Note: 1 Sound power level of standard blade option

Table 7 WTG Sound Power Level values (dBA)

Wind Turbine Model	Wind speed Vs (m/s) ref: 10 m AGL									
	3	4	5	6	7	8	9	10	11	12
Vestas V126 Standard Blade	95.2	98.3	103.1	107.8	108.5	108.5	108.5	108.5	108.5	108.5
Vestas V126 Serrated Blade - Mode 0	93.4	96.3	101.1	105.0	106.0	106.0	106.0	106.0	106.0	106.0
Vestas V126 Serrated Blade - Mode 2	93.4	96.3	100.6	102.6	103.1	104.2	104.5	104.5	104.5	104.5
GE 137 3.4 MW	93.5	98.5	103.3	106.0	106.0	106.0	106.0	106.0	106.0	106.0
Senvion M122		99.8	103.1	104.5	104.4	103.9	103.8	103.8		

6.2 Assessment of Tonality and Infrasound

A part of IEC 61400-11 noise testing is to conduct an assessment of the audibility of any tones present.

The tonal audibility is assessed using the methodology outlined in *Joint Nordic Method Version 2 – Objective Method for Assessing the Audibility of Tones in Noise* (JNM2). It should be noted that JNM2 imposes a sliding scale tonality penalty commencing when the tonal audibility $\Delta L_{A,k} > 4$ dB, and reaches the maximum allowable penalty of +6 dB when the tonal audibility $\Delta L_{A,k} > 10$ dB. The absence of any audible tones when tested in the near field as per IEC 61400-11 requirements, ensures that no audible tones will be experienced in the far field at receptors.

The tonal audibility data $\Delta L_{A,k}$ values have been supplied by the WTG manufacturers as follows:

Table 8 Audible tonality $\Delta L_{A,k}$ assessment to IEC 61400-11

Wind Turbine Model	Wind speed Vs (Hub Height) (m/s)									
	7	8	9	10	11	12	13	14	15	16
Vestas V126 3.3MW	-0.49	-2.47	-	-2.5	-0.34	-0.99	-1.71	-2.64	-	-
GE 137 3.4 3.4MW	≤ 4	≤ 4	≤ 4	≤ 4	≤ 4	≤ 4	≤ 4	≤ 4	≤ 4	≤ 4

The Servion M122 has no statement with regard to tonality. Confirmation of the $\Delta L_{A,k}$ tests should be provided by the manufacturer prior to approval.

Infrasound is not tested as an obligatory part of IEC 61400-11. It is noted that, in general, modern WTG's do not exhibit significant levels of infrasound emissions.

6.3 Noise Model Predictions

The results of noise modelling are presented in **Table 9** for all assessed receptor locations for the three investigated WTG models for Sapphire Wind Farm at a reference wind speed of 8 m/s (10m AGL).

Table 9 Predicted Noise Levels – dBA Leq

Receiver	Vestas V126 Standard Blade	Vestas V126 serrated blade Option Mode 0	Servion M122	GE 137	Receiver	Vestas V126 Standard Blade	Vestas V126 serrated blade Option Mode 0	Servion M122	GE 137
R1	24.7	22.2	20.8	22.9	R46	38.9	36.4	34.6	36.8
R2	22.4	19.9	18.6	20.6	R47	36.2	33.7	31.9	34.2
R3	24.8	22.2	20.8	22.9	R48	30.6	28.0	26.4	28.6
R4	33.2	30.7	29.1	31.4	R49	30.6	28.1	26.5	28.7
R5	36.6	34.1	32.3	34.4	R50	24.4	21.9	20.4	22.6
R6	39.0	36.5	34.8	36.9	R52	24.3	21.8	20.4	22.5
R7	40.3	37.8	36.0	38.1	R53	26.1	23.6	22.0	24.2
R8	42.0	39.5	37.7	39.8	R54	24.7	22.2	20.7	22.9
R9	46.1	43.6	41.8	43.8	R55	27.9	25.4	23.8	26.0
R10	39.8	37.3	35.5	37.6	R56	26.5	24.0	22.4	24.6
R11	43.6	41.1	39.3	41.5	R57	25.9	23.4	21.9	24.1
R12	47.0	44.5	42.7	44.7	R58	22.5	20.0	18.6	20.7
R13	45.4	42.9	41.1	43.1	R59	21.8	19.2	17.9	19.9
R14	45.8	43.3	41.5	43.5	R60	21.8	19.2	18.0	19.9
R15	40.4	37.9	36.1	38.3	R61	22.3	19.7	18.4	20.4
R16	39.9	37.4	35.6	37.6	R62	21.5	18.9	17.7	19.6
R17	41.8	39.3	37.6	39.7	R63	21.4	18.8	17.6	19.5
R18	43.9	41.4	39.6	41.7	R64	20.7	18.2	16.9	18.8
R19	42.0	39.5	37.7	39.8	R65	20.4	17.8	16.6	18.5
R20	43.0	40.5	38.7	40.7	R69	19.2	16.7	15.5	17.3
R21	43.6	41.1	39.3	41.3	R70	19.3	16.8	15.6	17.5

Receiver	Vestas V126 Standard Blade	Vestas V126 serrated blade Option Mode 0	Senvion M122	GE 137	Receiver	Vestas V126 Standard Blade	Vestas V126 serrated blade Option Mode 0	Senvion M122	GE 137
R23	41.1	38.6	36.7	38.8	R71	20.0	17.5	16.3	18.2
R24	45.5	43.0	41.2	43.2	R72	20.6	18.1	16.8	18.7
R25	37.0	34.5	32.6	34.7	R73	25.1	22.6	21.2	23.3
R26	41.2	38.7	36.9	39.0	R74	27.3	24.8	23.3	25.4
R27	39.5	37.0	35.1	37.2	R76	34.1	31.6	29.9	32.2
R28	43.0	40.5	38.7	40.7	R77	33.2	30.7	29.0	31.2
R29	37.5	35.0	33.2	35.4	R78	35.9	33.4	31.7	34.0
R30	35.2	32.7	31.0	33.2	R79	36.6	34.1	32.4	34.6
R31	32.2	29.7	28.1	30.3	R80	32.6	30.1	28.4	30.6
R32	32.7	30.2	28.6	30.9	R81	32.6	30.1	28.4	30.6
R33	38.1	35.6	33.8	36.0	R84	31.0	28.5	26.8	29.1
R34	32.5	30.0	28.4	30.6	R85	32.4	29.9	28.2	30.4
R35	34.2	31.7	30.0	32.3	R86	32.7	30.2	28.4	30.6
R36	35.9	33.4	31.6	33.9	R87	35.6	33.1	31.3	33.4
R37	35.1	32.6	30.9	33.1	R88	28.5	26.0	24.4	26.6
R38	34.2	31.7	30.1	32.3	R89	36.4	33.9	32.1	34.3
R39	38.4	35.9	34.1	36.3	R90	36.2	33.7	31.9	34.1
R40	37.7	35.2	33.5	35.7	R91	33.3	30.8	29.1	31.4
R41	36.4	33.9	32.1	34.3	R92	30.0	27.5	25.8	28.1
R42	36.0	33.5	31.8	34.0	R93	31.5	29.0	27.4	29.7
R43	35.1	32.6	30.9	33.2	R94	33.7	31.2	29.5	31.8
R44	36.1	33.6	31.8	34.0	R95	34.0	31.5	29.8	32.1
R45	37.2	34.7	32.9	35.1	R96	31.4	28.9	31.4	31.4

The full assessment graphs are presented in;

- **Appendix A1** for the Vestas V126 Standard Blade layout
- **Appendix A2** for the Vestas V126 Serrated Blade Option (Mode 0) layout
- **Appendix A3** for the Senvion M122 layout
- **Appendix A4** for the GE 137 layout

Noise contour plots calculated at a reference wind speed of 8 m/s (10m AGL) are presented in;

- **Appendix B1** for the Vestas V126 Standard Blade layout
- **Appendix B2** for the Vestas V126 Serrated Blade Option (Mode 0) layout
- **Appendix B3** for the Senvion M122 layout
- **Appendix B4** for the GE 137 layout

The predicted exceedances for each turbine type are shown in **Table 10**, **Table 11**, **Table 12** and **Table 13**.

Table 10 Vestas V126 Standard Blade - Predicted Exceedances (dBA)

Location	Height z	Hub height wind speed, m/s										Max
	10m	3	4	5	6	7	8	9	10	11	12	
	100m	4.3	5.7	7.2	8.6	10.0	11.5	12.9	14.3	15.8	17.2	
	139m	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0	16.5	18.0	
R24* Derra Downs					0.5	0.5	0.5	0.5	0.1			0.5
R25 Coleraine					2.0	0.6						2.0
R87 Croye					0.6							0.6
R27 Frasers Creek				1.5	3.8	3.3	2.3	0.5				3.8
R29 Krystal Blue					1.8	1.3	0.3					1.8
R90 Wirra Willa					0.5							0.5
R89 Tomali Park					0.8	0.3						0.8
R46 Alkoomie					2.0	1.1						2.0
R45 Glen Idle					0.3							0.3
R39 Bon Vista					1.5	0.6						1.5
R40 Hillview					0.9							0.9
R10 Mt Buckley				2.1	2.1							2.1

Note: * denotes that property is project involved and predicted exceedance is from the WHO limit

The highest predicted exceedance for the Vestas V126 (Standard Blade) layout is at location R27 Frasers Creek with a level 3.8 dBA higher than the SA EPA limit.

Table 11 Vestas V126 Serrated Blade Option (Mode 0) - Predicted Exceedances (dBA)

Location	Height z	Hub height wind speed, m/s										Max
	10m	3	4	5	6	7	8	9	10	11	12	
	100m	4.3	5.7	7.2	8.6	10.0	11.5	12.9	14.3	15.8	17.2	
	139m	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0	16.5	18.0	
R27 Frasers Creek					0.3	0.8						0.8

The highest predicted exceedance for the Vestas V126 Serrated Blade Option layout is at location R27 Frasers Creek with a level 0.8 dBA higher than the SA EPA limit.

Table 12 GE137 - Predicted Exceedances (dBA)

Location	Height z	Hub height wind speed, m/s										Max
	10m	3	4	5	6	7	8	9	10	11	12	
	100m	4.3	5.7	7.2	8.6	10.0	11.5	12.9	14.3	15.8	17.2	
	139m	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0	16.5	18.0	
R27 Frasers Creek					1.6	1.1	0.1					1.6

The highest predicted exceedance for the GE 137 layout is at location R27 Frasers Creek with a level 1.6 dBA higher than the SA EPA limit.

Table 13 Senvion M122 - Predicted Exceedances (dBA)

Location	Height z	Hub height wind speed, m/s										Max
	10m	3	4	5	6	7	8	9	10	11	12	
	100m	4.3	5.7	7.2	8.6	10.0	11.5	12.9	14.3	15.8	17.2	
	139m	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0	16.5	18.0	
R27 Frasers Creek					0.1							0.1

The highest predicted exceedance for the Senvion M122 layout is at location R27 Frasers Creek with a level 0.1 dBA higher than the SA EPA limit.

6.4 Mitigation Layout

Information regarding Noise Management Mode for the GE137 WTG model was not available at the time of compiling this report as the turbine is relatively new. It is expected that subsequent testing will be undertaken to show the possibility of operating in Noise Management Mode.

A mitigated layout was developed using Mode 2 of the Vestas V126 WTG Serrated Blade Option. A total of 3 WTGs were placed into Mode 2 operation, which reduces the sound power output of those turbines compared to standard Mode 0 operation. **Table 14** shows a list of the WTGs placed in Mode 2 for the mitigated scenario.

Table 14 Mitigated Turbine Layout - Vestas V126 WTG Serrated Blade Option

Turbine Name	Type
T21	Mode 2
T22	Mode 2
T23	Mode 2

Full results at all wind speeds are shown in **Appendix A5**.

A noise contour plot is shown in **Appendix B5**.

The mitigated layout is shown to comply at all receptors at all wind speeds.

7 COMPARISON TO ORIGINAL LAYOUTS

The proposed modification to Sapphire Wind Farm incorporates a layout of up to 109 WTGs, with a maximum tip height of 200 m and 3 MW to 3.4 MW capacities, whereas the approved wind farm had two alternative layout options of 159 WTGs and 125 WTGs with a maximum tip height of 159 m and between 2 MW and 3 MW capacity respectively.

Making a precise comparison of the predicted noise levels between the approved layouts and the proposed modification is difficult given the potential number of combinations of layouts and turbine models involved. However, in general a comparative evaluation reveals that noise levels will be marginally higher at some receptors (where nearby turbines are common to both the approved and proposed modified layout, owing to the larger size and marginally higher sound power level of the latter) and lower at others (where clusters of turbines have been dropped from the approved layout). Furthermore, in regions where noise levels are expected to be higher compared to the approved layout, there are a high proportion of project involved receptors.

It should be noted that whilst the predicted noise level for the proposed modified layout may be marginally higher than approved layouts at some receptors, the noise level will be below the appropriate limit.

8 CONCLUSION

SLR has conducted a noise impact assessment of the proposed modification to Sapphire Wind Farm.

Computer noise modelling using the standard ISO9613 algorithm was completed for four alternative WTG models.

The results for the Vestas V126 – Standard blade model, indicated that the wind farm may potentially exceed the relevant noise limits at up to 11 receptors.

The results for the Vestas V126 – serrated blade Option model, indicated that the wind farm may potentially marginally exceed the relevant noise limits at a single receptor.


A mitigation investigation was undertaken for the Vestas V126 serrated blade Option model utilising Sound Management Mode. Compliance at all receptors can be achieved using a mitigated layout where three WTGs are operated in Sound Management Mode 2. It should be noted that when WTGs are configured in Sound Management Mode they are always operating in the reduced noise mode, which is distinctly different from Sector Management.





The results for the, indicated that the wind farm would comply with relevant noise limits at all receptors.




The results for the Senvion M122 and GE 137 layouts, indicate that the wind farm may potentially marginally exceed the relevant noise limits at a single receptor. It is anticipated that a mitigation layout for these models will be possible through the implementation of a reduced output Sound Management Mode or the removal of a turbine from the current layout.


This noise impact assessment of the proposed modifications to Sapphire Wind Farm has shown that compliance with the noise limit requirements is attainable.


APPENDIX A NOISE ASSESSMENT GRAPHS

















































APPENDIX B NOISE CONTOUR MAPS



SCALE:

Scale 1:80000



ORIENTATION:



PROJECT NO. 640.11227

REPORT NO. 640.11227-R1

APPENDIX: B1

PREPARED: DWW

DATE 10/02/2016

PREDICTION ALGORITHM:
ISO 9613-2 1996

CLIENT:

Wind Prospect CWP Pty Ltd


PROJECT:

Sapphire Wind Farm Revised NIA

DESCRIPTION:

109 x Vestas V126 Standard 3.3MW
Hub Height 139m

Level: dBA



REV NO. :

001


MAP NO. :

001



SLR Consulting Australia

Suite 6, 131 Bulleen Road
Balwyn North
VIC 3104
Australia



SLR Consulting Australia

Suite 6, 131 Bulleen Road
Balwyn North
VIC 3104
Australia

SCALE:

Scale 1:80000



ORIENTATION:



PROJECT NO. 640.11227

REPORT NO. 640.11227-R1

APPENDIX: B2

PREPARED: DWW

DATE 10/02/2016

PREDICTION ALGORITHM:
ISO 9613-2 1996

CLIENT:

Wind Prospect CWP Pty Ltd


PROJECT:

Sapphire Wind Farm Revised NIA

DESCRIPTION:

109 x Vestas V126 Serrated 3.3MW
Hub Height 139m

Level: dBA




REV NO. :

001

MAP NO. :

002



SLR Consulting Australia

Suite 6, 131 Bulleen Road
Balwyn North
VIC 3104
Australia

SCALE:

Scale 1:80000

0 0.5 1 2 3
km

ORIENTATION:



PROJECT NO. 640.11227

REPORT NO. 640.11227-R1

APPENDIX: B3

PREPARED: DWW

DATE 10/02/2016

PREDICTION ALGORITHM:
ISO 9613-2 1996

CLIENT:

Wind Prospect CWP Pty Ltd


PROJECT:

Sapphire Wind Farm Revised NIA

DESCRIPTION:

109 x Senvion M122 3.0MW
Hub Height 139m

Level: dBA




REV NO. :

001

MAP NO. :

003



SCALE:

Scale 1:80000



ORIENTATION:



PROJECT NO. 640.11227

REPORT NO. 640.11227-R1

APPENDIX: B4

PREPARED: DWW

DATE 10/02/2016

PREDICTION ALGORITHM:
ISO 9613-2 1996

CLIENT:

Wind Prospect CWP Pty Ltd


PROJECT:

Sapphire Wind Farm Revised NIA

DESCRIPTION:

109 x GE 137 3.4MW
Hub Height 139m

Level: dBA



REV NO. :

001


MAP NO. :

004



SLR Consulting Australia

Suite 6, 131 Bulleen Road
Balwyn North
VIC 3104
Australia



SCALE:

Scale 1:80000



ORIENTATION:



PROJECT NO. 640.11227

REPORT NO. 640.11227-R1

APPENDIX: B5

PREPARED: DWW

DATE 10/02/2016

PREDICTION ALGORITHM:
ISO 9613-2 1996

CLIENT:

Wind Prospect CWP Pty Ltd


PROJECT:

Sapphire Wind Farm Revised NIA

DESCRIPTION:

106 x Vestas V126 Serrated Mode 0 3.3MW
3 x Vestas V126 Serrated Mode 2 3.3MW
Hub Height 139m

Level: dBA



REV NO. :

001

MAP NO. :

005



SLR Consulting Australia

Suite 6, 131 Bulleen Road
Balwyn North
VIC 3104
Australia

Vestas V126 non-serrated

Wind Speed (m/s) @

10m AGL

Hub Height

3

4

5

6

7

8

9

10

11

12

4.5

6.0

7.5

9.0

10.5

12.0

13.5

15.0

16.5

18.0

SA EPA Criteria

R3-Falkland Group

35.0

35.0

35.0

35.2

35.7

35.7

35.2

35.0

35.0

35.0

R1* Osterley

11.4

14.5

19.4

24.0

24.7

24.7

24.7

24.7

24.7

24.7

R3* Falkland

11.4

14.6

19.4

24.1

24.8

24.8

24.8

24.8

24.8

24.8

R59* Farley

8.4

11.6

16.4

21.1

21.8

21.8

21.8

21.8

21.8

21.8

R2* Fairy Meadow

9.1

12.2

17.1

21.7

22.4

22.4

22.4

22.4

22.4

22.4

R57 Karoola

12.6

15.7

20.5

25.2

25.9

25.9

25.9

25.9

25.9

25.9

R56* Fruin Glen

13.1

16.3

21.1

25.8

26.5

26.5

26.5

26.5

26.5

26.5

R58 Pitiochry

9.2

12.3

17.1

21.8

22.5

22.5

22.5

22.5

22.5

22.5

SA EPA Criteria

R64-Springfield Group

35.0

35.0

35.1

35.6

35.8

35.8

35.5

35.0

35.0

35.0

R60 Greenfield

8.5

11.6

16.4

21.1

21.8

21.8

21.8

21.8

21.8

21.8

R61 Rutherglen

9.0

12.1

16.9

21.6

22.3

22.3

22.3

22.3

22.3

22.3

R62* Linden Lea

8.1

11.3

16.1

20.8

21.5

21.5

21.5

21.5

21.5

21.5

R63 Junee

8.1

11.2

16.0

20.7

21.4

21.4

21.4

21.4

21.4

21.4

R64* Springfield

7.4

10.5

15.3

20.0

20.7

20.7

20.7

20.7

20.7

20.7

R65 Blumkaitis

7.1

10.2

15.0

19.7

20.4

20.4

20.4

20.4

20.4

20.4

R73 Nolimba

11.8

14.9

19.7

24.4

25.1

25.1

25.1

25.1

25.1

25.1

R72 Tantangra

7.3

10.4

15.2

19.9

20.6

20.6

20.6

20.6

20.6

20.6

R71 Highview

6.7

9.9

14.7

19.3

20.0

20.0

20.0

20.0

20.0

20.0

R70 Wangalee

6.0

9.2

14.0

18.6

19.3

19.3

19.3

19.3

19.3

19.3

R69 Arranmore

5.9

9.1

13.9

18.5

19.2

19.2

19.2

19.2

19.2

19.2

R74 Kaludabah

13.9

17.1

21.9

26.6

27.3

27.3

27.3

27.3

27.3

27.3

SA EPA Criteria

R43- Ardleigh Group

35.0

35.0

35.0

37.4

40.7

44.3

48.0

51.8

55.3

58.4

R43 Warrawee

21.8

25.0

29.8

34.4

35.1

35.1

35.1

35.1

35.1

35.1

R47 Pieta

22.9

26.0

30.8

35.5

36.2

36.2

36.2

36.2

36.2

36.2

SA EPA Criteria

R5- Down Field Group

43.0

43.2

44.2

45.5

47.0

48.2

48.8

48.5

47.0

44.0

R24*	Derra Downs	33.0	38.0	42.8	45.5	45.5	45.5	45.5	45.5	45.5	45.5
R23*	Carinya	28.6	33.6	38.4	41.1	41.1	41.1	41.1	41.1	41.1	41.1
R25	Coleraine	24.5	29.5	34.3	37.0	37.0	37.0	37.0	37.0	37.0	37.0
R87	Croye	23.1	28.1	32.9	35.6	35.6	35.6	35.6	35.6	35.6	35.6
R86	Millie	20.2	25.2	30.0	32.7	32.7	32.7	32.7	32.7	32.7	32.7
R81*	Weean	20.1	25.1	29.9	32.6	32.6	32.6	32.6	32.6	32.6	32.6
R84	Glenidle	18.5	23.5	28.3	31.0	31.0	31.0	31.0	31.0	31.0	31.0
R85*	Windemere	19.9	24.9	29.7	32.4	32.4	32.4	32.4	32.4	32.4	32.4
R88*	Woodlands	16.0	21.0	25.8	28.5	28.5	28.5	28.5	28.5	28.5	28.5

[illegible][illegible][illegible][illegible][illegible]

Vestas V126 serrated - Mode 0

Wind Speed (m/s) @

10m AGL

Hub Height

3 4 5 6 7 8 9 10 11 12
4.5 6.0 7.5 9.0 10.5 12.0 13.5 15.0 16.5 18.0

SA EPA Criteria										
R3-Falkland Group										
R1* Osterley	9.6	12.5	17.3	21.2	22.2	22.2	22.2	22.2	22.2	22.2
R3* Falkland	9.7	12.6	17.3	21.3	22.2	22.2	22.2	22.2	22.2	22.2
R59* Farley	6.7	9.6	14.3	18.2	19.2	19.2	19.2	19.2	19.2	19.2
R2* Fairy Meadow	7.3	10.2	14.9	18.9	19.9	19.9	19.9	19.9	19.9	19.9
R57 Karoola	10.8	13.7	18.4	22.4	23.4	23.4	23.4	23.4	23.4	23.4
R56* Fruin Glen	11.4	14.3	19.0	23.0	24.0	24.0	24.0	24.0	24.0	24.0
R58 Pitiochry	7.4	10.3	15.0	19.0	20.0	20.0	20.0	20.0	20.0	20.0

SA EPA Criteria										
R64-Springfield Group										
R60 Greenfield	6.7	9.6	14.3	18.3	19.2	19.2	19.2	19.2	19.2	19.2
R61 Rutherglen	7.2	10.1	14.8	18.8	19.7	19.7	19.7	19.7	19.7	19.7
R62* Linden Lea	6.4	9.3	14.0	17.9	18.9	18.9	18.9	18.9	18.9	18.9
R63 Junee	6.3	9.2	13.9	17.8	18.8	18.8	18.8	18.8	18.8	18.8
R64* Springfield	5.6	8.5	13.2	17.2	18.2	18.2	18.2	18.2	18.2	18.2
R65 Blumkaitis	5.3	8.2	12.9	16.8	17.8	17.8	17.8	17.8	17.8	17.8
R73 Nolimba	10.0	12.9	17.6	21.6	22.6	22.6	22.6	22.6	22.6	22.6
R72 Tantara	5.5	8.4	13.1	17.1	18.1	18.1	18.1	18.1	18.1	18.1
R71 Highview	4.9	7.8	12.6	16.5	17.5	17.5	17.5	17.5	17.5	17.5
R70 Wangalee	4.2	7.1	11.8	15.8	16.8	16.8	16.8	16.8	16.8	16.8
R69 Arranmore	4.1	7.0	11.7	15.7	16.7	16.7	16.7	16.7	16.7	16.7
R74 Kaludabah	12.2	15.1	19.8	23.8	24.8	24.8	24.8	24.8	24.8	24.8

SA EPA Criteria										
R43- Ardleigh Group										
R43 Warrawee	20.1	23.0	27.7	31.6	32.6	32.6	32.6	32.6	32.6	32.6
R47 Pieta	21.1	24.0	28.7	32.7	33.7	33.7	33.7	33.7	33.7	33.7

SA EPA Criteria										
R5- Down Field Group										
R5* Down Field	21.6	24.5	29.2	33.1	34.1	34.1	34.1	34.1	34.1	34.1
R55 Tarana	12.9	15.8	20.5	24.4	25.4	25.4	25.4	25.4	25.4	25.4
R49* Evergreen	15.6	18.5	23.2	27.1	28.1	28.1	28.1	28.1	28.1	28.1
R53* Maids Valley	11.0	13.9	18.6	22.6	23.6	23.6	23.6	23.6	23.6	23.6
R54 Fassifern	9.7	12.5	17.3	21.2	22.2	22.2	22.2	22.2	22.2	22.2
R6* Tauranga	24.0	26.9	31.6	35.6	36.5	36.5	36.5	36.5	36.5	36.5
R52 Waterloo Cottage	9.3	12.2	16.9	20.8	21.8	21.8	21.8	21.8	21.8	21.8
R50 Waterloo	9.4	12.2	17.0	20.9	21.9	21.9	21.9	21.9	21.9	21.9
R7 Kings Land (House #2)	25.2	28.1	32.8	36.8	37.8	37.8	37.8	37.8	37.8	37.8
R8* Manaroo	27.0	29.9	34.6	38.5	39.5	39.5	39.5	39.5	39.5	39.5
R9* Leeweena	31.0	33.9	38.6	42.6	43.6	43.6	43.6	43.6	43.6	43.6
R11* Yarrabin	28.6	31.5	36.2	40.1	41.1	41.1	41.1	41.1	41.1	41.1
R12* Mubbarra	31.9	34.8	39.5	43.5	44.5	44.5	44.5	44.5	44.5	44.5

SA EPA Criteria										
R14-Kingshill Group										
R14* Kingshill	30.7	33.6	38.3	42.3	43.3	43.3	43.3	43.3	43.3	43.3
R13* Narren Vale	30.3	33.2	37.9	41.9	42.9	42.9	42.9	42.9	42.9	42.9
R17 Strathdarr	26.8	29.7	34.4	38.4	39.3	39.3	39.3	39.3	39.3	39.3
R18* Yarrandoo	28.8	31.7	36.5	40.4	41.4	41.4	41.4	41.4	41.4	41.4
R15* Kia-Tami	25.4	28.3	33.0	36.9	37.9	37.9	37.9	37.9	37.9	37.9
R16* Woodstock	24.8	27.7	32.4	36.4	37.4	37.4	37.4	37.4	37.4	37.4
R33* Highlands	23.0	25.9	30.6	34.6	35.6	35.6	35.6	35.6	35.6	35.6

SA EPA Criteria										
R23-Carinya Group										
	35.0	35.0	35.0	35.0	36.4	38.5	41.4	45.3	50.6	57.3

R24* Derra Downs	30.4	33.3	38.0	42.0	43.0	43.0	43.0	43.0	43.0	43.0
R23* Carinya	26.0	28.9	33.6	37.6	38.6	38.6	38.6	38.6	38.6	38.6
R25 Coleraine	21.9	24.8	29.5	33.5	34.5	34.5	34.5	34.5	34.5	34.5
R87 Croye	20.5	23.4	28.1	32.1	33.1	33.1	33.1	33.1	33.1	33.1
R86 Millie	17.7	20.6	25.3	29.2	30.2	30.2	30.2	30.2	30.2	30.2
R81* Weean	17.6	20.5	25.2	29.1	30.1	30.1	30.1	30.1	30.1	30.1
R84 Glenidle	16.0	18.9	23.6	27.6	28.5	28.5	28.5	28.5	28.5	28.5
R85* Windemere	17.4	20.3	25.0	28.9	29.9	29.9	29.9	29.9	29.9	29.9
R88* Woodlands	13.5	16.4	21.1	25.1	26.0	26.0	26.0	26.0	26.0	26.0

SA EPA Criteria										
R28-Tralee Group	35.0	35.0	35.2	35.6	36.2	37.2	38.9	41.9	46.2	52.4
R28* Tralee	27.9	30.8	35.6	39.5	40.5	40.5	40.5	40.5	40.5	40.5
R26* Spring Creek	26.1	29.0	33.7	37.7	38.7	38.7	38.7	38.7	38.7	38.7
R27 Frasers Creek	24.4	27.3	32.0	36.0	37.0	37.0	37.0	37.0	37.0	37.0
R29 Krystal Blue	22.4	25.3	30.0	34.0	35.0	35.0	35.0	35.0	35.0	35.0
R90 Wirra Willa	21.1	24.0	28.7	32.7	33.7	33.7	33.7	33.7	33.7	33.7
R30 Argyle	20.1	23.0	27.7	31.7	32.7	32.7	32.7	32.7	32.7	32.7
R94 The Knoll	18.6	21.5	26.2	30.2	31.2	31.2	31.2	31.2	31.2	31.2
R91 Roseana	18.2	21.1	25.9	29.8	30.8	30.8	30.8	30.8	30.8	30.8
R93 Swamp Oak	16.5	19.4	24.1	28.1	29.0	29.0	29.0	29.0	29.0	29.0
R92 Lambert	14.9	17.8	22.5	26.5	27.5	27.5	27.5	27.5	27.5	27.5
R31 Glen Valley	17.1	20.0	24.8	28.7	29.7	29.7	29.7	29.7	29.7	29.7
R32 Swan Peak	17.7	20.6	25.3	29.3	30.2	30.2	30.2	30.2	30.2	30.2
R80* Weean Cottage	17.6	20.5	25.2	29.1	30.1	30.1	30.1	30.1	30.1	30.1
R89 Tomali Park	21.4	24.3	29.0	32.9	33.9	33.9	33.9	33.9	33.9	33.9
R95 Rock Leigh	18.9	21.8	26.5	30.5	31.5	31.5	31.5	31.5	31.5	31.5
R96 Unknown	16.4	19.3	24.0	28.0	28.9	28.9	28.9	28.9	28.9	28.9

SA EPA Criteria										
R36 Yarrawah Park Group	35.0	35.0	35.0	35.6	36.6	38.0	39.8	42.3	45.4	49.3
R36* Yarrawah Park	20.8	23.7	28.4	32.4	33.4	33.4	33.4	33.4	33.4	33.4
R37* Coorimbla Park	20.0	22.9	27.6	31.6	32.6	32.6	32.6	32.6	32.6	32.6
R35 Golden Grove	19.2	22.1	26.8	30.7	31.7	31.7	31.7	31.7	31.7	31.7
R38* Inverness	19.2	22.1	26.8	30.8	31.7	31.7	31.7	31.7	31.7	31.7
R34* Bellview	17.5	20.4	25.1	29.0	30.0	30.0	30.0	30.0	30.0	30.0

SA EPA Criteria										
R44-Mindora Group	35.0	35.5	36.3	36.8	37.8	39.6	42.8	47.9	55.5	66.1
R46 Alkoomie	23.8	26.7	31.4	35.4	36.4	36.4	36.4	36.4	36.4	36.4
R45 Glen Idle	22.1	25.0	29.7	33.7	34.7	34.7	34.7	34.7	34.7	34.7
R41 Royal Oaks	21.3	24.2	28.9	32.9	33.9	33.9	33.9	33.9	33.9	33.9
R42 Ashgrove	21.0	23.8	28.6	32.5	33.5	33.5	33.5	33.5	33.5	33.5
R39 Bon Vista	23.3	26.2	31.0	34.9	35.9	35.9	35.9	35.9	35.9	35.9
R40 Hillview	22.7	25.6	30.3	34.3	35.2	35.2	35.2	35.2	35.2	35.2
R44 Mindora	21.0	23.9	28.7	32.6	33.6	33.6	33.6	33.6	33.6	33.6

SA EPA Criteria										
R10-Mt Buckley Group	35.0	35.0	35.0	37.7	41.1	44.6	48.0	51.0	53.2	54.4
R10 Mt Buckley	24.8	27.7	32.4	36.4	37.3	37.3	37.3	37.3	37.3	37.3
R48 Adavale	15.5	18.4	23.1	27.1	28.0	28.0	28.0	28.0	28.0	28.0

SA EPA Criteria										
R19-Warrandah Group	35.0	35.0	35.0	36.9	40.3	43.7	46.6	48.3	48.3	46.2
R20* Lochlea	27.9	30.8	35.5	39.5	40.5	40.5	40.5	40.5	40.5	40.5
R21* 311	28.5	31.4	36.2	40.1	41.1	41.1	41.1	41.1	41.1	41.1
R19* Warrandah	27.0	29.9	34.6	38.5	39.5	39.5	39.5	39.5	39.5	39.5
R76* Cubba	19.1	21.9	26.7	30.6	31.6	31.6	31.6	31.6	31.6	31.6
R77 Meadow Vale	18.1	21.0	25.7	29.7	30.7	30.7	30.7	30.7	30.7	30.7
R4* Ardleigh	18.2	21.1	25.8	29.8	30.7	30.7	30.7	30.7	30.7	30.7
R78 Pine Grove	20.8	23.7	28.4	32.4	33.4	33.4	33.4	33.4	33.4	33.4
R79* Woodburn	21.5	24.4	29.1	33.1	34.1	34.1	34.1	34.1	34.1	34.1

Senvion M122

Wind Speed (m/s) @

10m AGL

Hub Height

3 4 5 6 7 8 9 10 11 12
4.5 6.0 7.5 9.0 10.5 12.0 13.5 15.0 16.5 18.0

SA EPA Criteria										
R3-Falkland Group	35.0	35.0	35.0	35.2	35.7	35.7	35.2	35.0	35.0	35.0
R1* Osterley		16.7	20.0	21.4	21.3	20.8	20.7	20.7		
R3* Falkland		16.7	20.0	21.4	21.3	20.8	20.7	20.7		
R59* Farley		13.8	17.1	18.5	18.4	17.9	17.8	17.8		
R2* Fairy Meadow		14.5	17.8	19.2	19.1	18.6	18.5	18.5		
R57 Karoola		17.8	21.1	22.5	22.4	21.9	21.8	21.8		
R56* Fruin Glen		18.3	21.6	23.0	22.9	22.4	22.3	22.3		
R58 Pitiochry		14.5	17.8	19.2	19.1	18.6	18.5	18.5		

SA EPA Criteria										
R64-Springfield Group	35.0	35.0	35.1	35.6	35.8	35.8	35.5	35.0	35.0	35.0
R60 Greenfield		13.9	17.2	18.6	18.5	18.0	17.9	17.9		
R61 Rutherglen		14.3	17.6	19.0	18.9	18.4	18.3	18.3		
R62* Linden Lea		13.6	16.9	18.3	18.2	17.7	17.6	17.6		
R63 Junee		13.5	16.8	18.2	18.1	17.6	17.5	17.5		
R64* Springfield		12.8	16.1	17.5	17.4	16.9	16.8	16.8		
R65 Blumkaitis		12.5	15.8	17.2	17.1	16.6	16.5	16.5		
R73 Nolimba		17.1	20.4	21.8	21.7	21.2	21.1	21.1		
R72 Tantangra		12.7	16.0	17.4	17.3	16.8	16.7	16.7		
R71 Highview		12.2	15.5	16.9	16.8	16.3	16.2	16.2		
R70 Wangalee		11.5	14.8	16.2	16.1	15.6	15.5	15.5		
R69 Arranmore		11.4	14.7	16.1	16.0	15.5	15.4	15.4		
R74 Kaludabah		19.2	22.5	23.9	23.8	23.3	23.2	23.2		

SA EPA Criteria										
R43- Ardleigh Group	35.0	35.0	35.0	37.4	40.7	44.3	48.0	51.8	55.3	58.4
R43 Warrawee		26.8	30.1	31.5	31.4	30.9	30.8	30.8		
R47 Pieta		27.8	31.1	32.5	32.4	31.9	31.8	31.8		

SA EPA Criteria										
R5- Down Field Group	43.0	43.2	44.2	45.5	47.0	48.2	48.8	48.5	47.0	44.0
R5* Down Field		28.2	31.5	32.9	32.8	32.3	32.2	32.2		
R55 Tarana		19.7	23.0	24.4	24.3	23.8	23.7	23.7		
R49* Evergreen		22.4	25.7	27.1	27.0	26.5	26.4	26.4		
R53* Maids Valley		17.9	21.2	22.6	22.5	22.0	21.9	21.9		
R54 Fassifern		16.6	19.9	21.3	21.2	20.7	20.6	20.6		
R6* Taurauga		30.7	34.0	35.4	35.3	34.8	34.7	34.7		
R52 Waterloo Cottage		16.3	19.6	21.0	20.9	20.4	20.3	20.3		
R50 Waterloo		16.3	19.6	21.0	20.9	20.4	20.3	20.3		
R7 Kings Land (House #2)		31.9	35.2	36.6	36.5	36.0	35.9	35.9		
R8* Manaroo		33.6	36.9	38.3	38.2	37.7	37.6	37.6		
R9* Leeweena		37.7	41.0	42.4	42.3	41.8	41.7	41.7		
R11* Yarrabin		35.2	38.5	39.9	39.8	39.3	39.2	39.2		
R12* Mubbarra		38.6	41.9	43.3	43.2	42.7	42.6	42.6		

SA EPA Criteria										
R14-Kingshill Group	43.1	44.0	44.9	45.8	46.9	48.3	50.3	52.8	56.1	60.3
R14* Kingshill		37.4	40.7	42.1	42.0	41.5	41.4	41.4		
R13* Narren Vale		37.0	40.3	41.7	41.6	41.1	41.0	41.0		
R17 Strathdarr		33.5	36.8	38.2	38.1	37.6	37.5	37.5		
R18* Yarrandoo		35.5	38.8	40.2	40.1	39.6	39.5	39.5		
R15* Kia-Tami		32.0	35.3	36.7	36.6	36.1	36.0	36.0		
R16* Woodstock		31.5	34.8	36.2	36.1	35.6	35.5	35.5		
R33* Highlands		29.7	33.0	34.4	34.3	33.8	33.7	33.7		

SA EPA Criteria										
R23-Carinya Group	35.0	35.0	35.0	35.0	36.4	38.5	41.4	45.3	50.6	57.3

R24* Derra Downs	37.1	40.4	41.8	41.7	41.2	41.1	41.1
R23* Carinya	32.6	35.9	37.3	37.2	36.7	36.6	36.6
R25 Coleraine	28.5	31.8	33.2	33.1	32.6	32.5	32.5
R87 Croye	27.2	30.5	31.9	31.8	31.3	31.2	31.2
R86 Millie	24.3	27.6	29.0	28.9	28.4	28.3	28.3
R81* Weean	24.3	27.6	29.0	28.9	28.4	28.3	28.3
R84 Glenidle	22.7	26.0	27.4	27.3	26.8	26.7	26.7
R85* Windemere	24.1	27.4	28.8	28.7	28.2	28.1	28.1
R88* Woodlands	20.3	23.6	25.0	24.9	24.4	24.3	24.3

SA EPA Criteria										
R28-Tralee Group	35.0	35.0	35.2	35.6	36.2	37.2	38.9	41.9	46.2	52.4
R28* Tralee	34.6	37.9	39.3	39.2	38.7	38.6	38.6			
R26* Spring Creek	32.8	36.1	37.5	37.4	36.9	36.8	36.8			
R27 Frasers Creek	31.0	34.3	35.7	35.6	35.1	35.0	35.0			
R29 Krystal Blue	29.1	32.4	33.8	33.7	33.2	33.1	33.1			
R90 Wirra Willa	27.8	31.1	32.5	32.4	31.9	31.8	31.8			
R30 Argyle	26.9	30.2	31.6	31.5	31.0	30.9	30.9			
R94 The Knoll	25.4	28.7	30.1	30.0	29.5	29.4	29.4			
R91 Roseana	25.0	28.3	29.7	29.6	29.1	29.0	29.0			
R93 Swamp Oak	23.3	26.6	28.0	27.9	27.4	27.3	27.3			
R92 Lambert	21.7	25.0	26.4	26.3	25.8	25.7	25.7			
R31 Glen Valley	24.0	27.3	28.7	28.6	28.1	28.0	28.0			
R32 Swan Peak	24.5	27.8	29.2	29.1	28.6	28.5	28.5			
R80* Weean Cottage	23.4	26.7	28.1	28.0	27.5	27.4	27.4			
R89 Tomali Park	28.0	31.3	32.7	32.6	32.1	32.0	32.0			
R95 Rock Leigh	25.7	29.0	30.4	30.3	29.8	29.7	29.7			
R96 Unknown	27.3	30.6	32.0	31.9	31.4	31.3	31.3			

SA EPA Criteria										
R36 Yarrawah Park Group	35.0	35.0	35.0	35.6	36.6	38.0	39.8	42.3	45.4	49.3
R36* Yarrawah Park	27.5	30.8	32.2	32.1	31.6	31.5	31.5			
R37* Coorimbla Park	26.8	30.1	31.5	31.4	30.9	30.8	30.8			
R35 Golden Grove	25.9	29.2	30.6	30.5	30.0	29.9	29.9			
R38* Inverness	26.0	29.3	30.7	30.6	30.1	30.0	30.0			
R34* Bellview	24.3	27.6	29.0	28.9	28.4	28.3	28.3			

SA EPA Criteria										
R44-Mindora Group	35.0	35.5	36.3	36.8	37.8	39.6	42.8	47.9	55.5	66.1
R46 Alkoomie		30.5	33.8	35.2	35.1	34.6	34.5	34.5		
R45 Glen Idle		28.8	32.1	33.5	33.4	32.9	32.8	32.8		
R41 Royal Oaks		28.0	31.3	32.7	32.6	32.1	32.0	32.0		
R42 Ashgrove		27.7	31.0	32.4	32.3	31.8	31.7	31.7		
R39 Bon Vista		30.0	33.3	34.7	34.6	34.1	34.0	34.0		
R40 Hillview		29.4	32.7	34.1	34.0	33.5	33.4	33.4		
R44 Mindora		27.7	31.0	32.4	32.3	31.8	31.7	31.7		

SA EPA Criteria										
R10-Mt Buckley Group	35.0	35.0	35.0	37.7	41.1	44.6	48.0	51.0	53.2	54.4
R10 Mt Buckley		31.4	34.7	36.1	36.0	35.5	35.4	35.4		
R48 Adavale		22.3	25.6	27.0	26.9	26.4	26.3	26.3		

SA EPA Criteria										
R19-Warrandah Group	35.0	35.0	35.0	36.9	40.3	43.7	46.6	48.3	48.3	46.2
R20* Lochlea		34.6	37.9	39.3	39.2	38.7	38.6	38.6		
R21* 311		35.2	38.5	39.9	39.8	39.3	39.2	39.2		
R19* Warrandah		33.6	36.9	38.3	38.2	37.7	37.6	37.6		
R76* Cubba		25.8	29.1	30.5	30.4	29.9	29.8	29.8		
R77 Meadow Vale		24.9	28.2	29.6	29.5	29.0	28.9	28.9		
R4* Ardleigh		25.0	28.3	29.7	29.6	29.1	29.0	29.0		
R78 Pine Grove		27.6	30.9	32.3	32.2	31.7	31.6	31.6		
R79* Woodburn		28.3	31.6	33.0	32.9	32.4	32.3	32.3		

GE 137

Wind Speed (m/s) @

10m AGL

Hub Height

3 4 5 6 7 8 9 10 11 12
4.5 6.0 7.5 9.0 10.5 12.0 13.5 15.0 16.5 18.0

SA EPA Criteria										
R3-Falkland Group										
R1* Osterley	10.4	15.4	20.2	22.9	22.9	22.9	22.9	22.9	22.9	22.9
R3* Falkland	10.4	15.4	20.2	22.9	22.9	22.9	22.9	22.9	22.9	22.9
R59* Farley	7.4	12.4	17.2	19.9	19.9	19.9	19.9	19.9	19.9	19.9
R2* Fairy Meadow	8.1	13.1	17.9	20.6	20.6	20.6	20.6	20.6	20.6	20.6
R57 Karoola	11.6	16.6	21.4	24.1	24.1	24.1	24.1	24.1	24.1	24.1
R56* Fruin Glen	12.1	17.1	21.9	24.6	24.6	24.6	24.6	24.6	24.6	24.6
R58 Pitiochry	8.2	13.2	18.0	20.7	20.7	20.7	20.7	20.7	20.7	20.7

SA EPA Criteria										
R64-Springfield Group										
R60 Greenfield	7.4	12.4	17.2	19.9	19.9	19.9	19.9	19.9	19.9	19.9
R61 Rutherglen	7.9	12.9	17.7	20.4	20.4	20.4	20.4	20.4	20.4	20.4
R62* Linden Lea	7.1	12.1	16.9	19.6	19.6	19.6	19.6	19.6	19.6	19.6
R63 Junee	7.0	12.0	16.8	19.5	19.5	19.5	19.5	19.5	19.5	19.5
R64* Springfield	6.3	11.3	16.1	18.8	18.8	18.8	18.8	18.8	18.8	18.8
R65 Blumkaitis	6.0	11.0	15.8	18.5	18.5	18.5	18.5	18.5	18.5	18.5
R73 Nolimba	10.8	15.8	20.6	23.3	23.3	23.3	23.3	23.3	23.3	23.3
R72 Tantara	6.2	11.2	16.0	18.7	18.7	18.7	18.7	18.7	18.7	18.7
R71 Highview	5.7	10.7	15.5	18.2	18.2	18.2	18.2	18.2	18.2	18.2
R70 Wangalee	5.0	10.0	14.8	17.5	17.5	17.5	17.5	17.5	17.5	17.5
R69 Arranmore	4.8	9.8	14.6	17.3	17.3	17.3	17.3	17.3	17.3	17.3
R74 Kaludabah	12.9	17.9	22.7	25.4	25.4	25.4	25.4	25.4	25.4	25.4

SA EPA Criteria										
R43- Ardleigh Group										
R43 Warrawee	20.7	25.7	30.5	33.2	33.2	33.2	33.2	33.2	33.2	33.2
R47 Pieta	21.7	26.7	31.5	34.2	34.2	34.2	34.2	34.2	34.2	34.2

SA EPA Criteria										
R5- Down Field Group										
R5* Down Field	21.9	26.9	31.7	34.4	34.4	34.4	34.4	34.4	34.4	34.4
R55 Tarana	13.5	18.5	23.3	26.0	26.0	26.0	26.0	26.0	26.0	26.0
R49* Evergreen	16.2	21.2	26.0	28.7	28.7	28.7	28.7	28.7	28.7	28.7
R53* Maids Valley	11.7	16.7	21.5	24.2	24.2	24.2	24.2	24.2	24.2	24.2
R54 Fassifern	10.4	15.4	20.2	22.9	22.9	22.9	22.9	22.9	22.9	22.9
R6* Tauranga	24.4	29.4	34.2	36.9	36.9	36.9	36.9	36.9	36.9	36.9
R52 Waterloo Cottage	10.0	15.0	19.8	22.5	22.5	22.5	22.5	22.5	22.5	22.5
R50 Waterloo	10.1	15.1	19.9	22.6	22.6	22.6	22.6	22.6	22.6	22.6
R7 Kings Land (House #2)	25.6	30.6	35.4	38.1	38.1	38.1	38.1	38.1	38.1	38.1
R8* Manaroo	27.3	32.3	37.1	39.8	39.8	39.8	39.8	39.8	39.8	39.8
R9* Leeweena	31.3	36.3	41.1	43.8	43.8	43.8	43.8	43.8	43.8	43.8
R11* Yarrabin	29.0	34.0	38.8	41.5	41.5	41.5	41.5	41.5	41.5	41.5
R12* Mubbarra	32.2	37.2	42.0	44.7	44.7	44.7	44.7	44.7	44.7	44.7

SA EPA Criteria										
R14-Kingshill Group										
R14* Kingshill	31.0	36.0	40.8	43.5	43.5	43.5	43.5	43.5	43.5	43.5
R13* Narren Vale	30.6	35.6	40.4	43.1	43.1	43.1	43.1	43.1	43.1	43.1
R17 Strathdarr	27.2	32.2	37.0	39.7	39.7	39.7	39.7	39.7	39.7	39.7
R18* Yarrandoo	29.2	34.2	39.0	41.7	41.7	41.7	41.7	41.7	41.7	41.7
R15* Kia-Tami	25.8	30.8	35.6	38.3	38.3	38.3	38.3	38.3	38.3	38.3
R16* Woodstock	25.1	30.1	34.9	37.6	37.6	37.6	37.6	37.6	37.6	37.6
R33* Highlands	23.5	28.5	33.3	36.0	36.0	36.0	36.0	36.0	36.0	36.0

SA EPA Criteria										
R23-Carinya Group										
	35.0	35.0	35.0	35.0	36.4	38.5	41.4	45.3	50.6	57.3

R24*	Derra Downs	30.7	35.7	40.5	43.2	43.2	43.2	43.2	43.2	43.2
R23*	Carinya	26.3	31.3	36.1	38.8	38.8	38.8	38.8	38.8	38.8
R25	Coleraine	22.2	27.2	32.0	34.7	34.7	34.7	34.7	34.7	34.7
R87	Croye	20.9	25.9	30.7	33.4	33.4	33.4	33.4	33.4	33.4
R86	Millie	18.1	23.1	27.9	30.6	30.6	30.6	30.6	30.6	30.6
R81*	Weean	18.1	23.1	27.9	30.6	30.6	30.6	30.6	30.6	30.6
R84	Glenidle	16.6	21.6	26.4	29.1	29.1	29.1	29.1	29.1	29.1
R85*	Windemere	17.9	22.9	27.7	30.4	30.4	30.4	30.4	30.4	30.4
R88*	Woodlands	14.1	19.1	23.9	26.6	26.6	26.6	26.6	26.6	26.6

[illegible][illegible][illegible][illegible][illegible]

Vestas V126 serrated -Mitigated

Wind Speed (m/s) @

10m AGL

Hub Height

3 4 5 6 7 8 9 10 11 12
4.5 6.0 7.5 9.0 10.5 12.0 13.5 15.0 16.5 18.0

SA EPA Criteria										
R3-Falkland Group										
R1* Osterley	9.6	12.5	17.2	21.2	22.2	22.2	22.2	22.2	22.2	22.2
R3* Falkland	9.7	12.6	17.3	21.2	22.2	22.2	22.2	22.2	22.2	22.2
R59* Farley	6.7	9.6	14.3	18.2	19.2	19.2	19.2	19.2	19.2	19.2
R2* Fairy Meadow	7.3	10.2	14.9	18.9	19.9	19.9	19.9	19.9	19.9	19.9
R57 Karoola	10.8	13.7	18.4	22.4	23.4	23.4	23.4	23.4	23.4	23.4
R56* Fruin Glen	11.4	14.3	19.0	23.0	23.9	23.9	23.9	23.9	23.9	23.9
R58 Pitiochry	7.4	10.3	15.0	19.0	20.0	20.0	20.0	20.0	20.0	20.0

SA EPA Criteria										
R64-Springfield Group										
R60 Greenfield	6.7	9.6	14.3	18.2	19.2	19.2	19.2	19.2	19.2	19.2
R61 Rutherglen	7.2	10.1	14.8	18.7	19.7	19.7	19.7	19.7	19.7	19.7
R62* Linden Lea	6.4	9.3	14.0	17.9	18.9	18.9	18.9	18.9	18.9	18.9
R63 Junee	6.3	9.2	13.9	17.8	18.8	18.8	18.8	18.8	18.8	18.8
R64* Springfield	5.6	8.5	13.2	17.2	18.1	18.1	18.2	18.2	18.2	18.2
R65 Blumkaitis	5.3	8.2	12.9	16.8	17.8	17.8	17.8	17.8	17.8	17.8
R73 Nolimba	10.0	12.9	17.6	21.6	22.6	22.6	22.6	22.6	22.6	22.6
R72 Tantangra	5.5	8.4	13.1	17.0	18.0	18.0	18.0	18.0	18.0	18.0
R71 Highview	4.9	7.8	12.5	16.5	17.5	17.5	17.5	17.5	17.5	17.5
R70 Wangalee	4.2	7.1	11.8	15.8	16.7	16.7	16.8	16.8	16.8	16.8
R69 Arranmore	4.1	7.0	11.7	15.7	16.6	16.6	16.7	16.7	16.7	16.7
R74 Kaludabah	12.2	15.1	19.8	23.7	24.7	24.7	24.7	24.7	24.7	24.7

SA EPA Criteria										
R43- Ardleigh Group										
R43 Warrawee	20.1	23.0	27.7	31.6	32.6	32.6	32.6	32.6	32.6	32.6
R47 Pieta	21.1	24.0	28.7	32.7	33.7	33.7	33.7	33.7	33.7	33.7

SA EPA Criteria										
R5- Down Field Group										
R5* Down Field	21.6	24.5	29.2	33.1	34.1	34.1	34.1	34.1	34.1	34.1
R55 Tarana	12.9	15.8	20.5	24.4	25.4	25.4	25.4	25.4	25.4	25.4
R49* Evergreen	15.6	18.5	23.2	27.1	28.1	28.1	28.1	28.1	28.1	28.1
R53* Maids Valley	11.0	13.9	18.6	22.6	23.6	23.6	23.6	23.6	23.6	23.6
R54 Fassifern	9.7	12.5	17.3	21.2	22.2	22.2	22.2	22.2	22.2	22.2
R6* Tauranga	24.0	26.9	31.6	35.6	36.5	36.5	36.5	36.5	36.5	36.5
R52 Waterloo Cottage	9.3	12.2	16.9	20.8	21.8	21.8	21.8	21.8	21.8	21.8
R50 Waterloo	9.4	12.2	17.0	20.9	21.9	21.9	21.9	21.9	21.9	21.9
R7 Kings Land (House #2)	25.2	28.1	32.8	36.8	37.8	37.8	37.8	37.8	37.8	37.8
R8* Manaroo	27.0	29.9	34.6	38.5	39.5	39.5	39.5	39.5	39.5	39.5
R9* Leeweena	31.0	33.9	38.6	42.6	43.6	43.6	43.6	43.6	43.6	43.6
R11* Yarrabin	28.6	31.5	36.2	40.1	41.1	41.1	41.1	41.1	41.1	41.1
R12* Mubbarra	31.9	34.8	39.5	43.5	44.5	44.5	44.5	44.5	44.5	44.5

SA EPA Criteria										
R14-Kingshill Group										
R14* Kingshill	30.7	33.6	38.3	42.3	43.3	43.3	43.3	43.3	43.3	43.3
R13* Narren Vale	30.3	33.2	37.9	41.9	42.9	42.9	42.9	42.9	42.9	42.9
R17 Strathdarr	26.8	29.7	34.4	38.3	39.3	39.3	39.3	39.3	39.3	39.3
R18* Yarrandoo	28.8	31.7	36.5	40.4	41.4	41.4	41.4	41.4	41.4	41.4
R15* Kia-Tami	25.4	28.3	33.0	36.9	37.9	37.9	37.9	37.9	37.9	37.9
R16* Woodstock	24.8	27.7	32.4	36.4	37.3	37.3	37.3	37.3	37.3	37.3
R33* Highlands	23.0	25.9	30.6	34.6	35.6	35.6	35.6	35.6	35.6	35.6

SA EPA Criteria										
R23-Carinya Group										
	35.0	35.0	35.0	35.0	36.4	38.5	41.4	45.3	50.6	57.3

R24* Derra Downs	30.4	33.3	38.0	42.0	43.0	43.0	43.0	43.0	43.0	43.0
R23* Carinya	26.0	28.9	33.6	37.6	38.6	38.6	38.6	38.6	38.6	38.6
R25 Coleraine	21.9	24.8	29.4	33.3	34.3	34.3	34.3	34.3	34.3	34.3
R87 Croye	20.5	23.4	28.1	32.1	33.0	33.1	33.1	33.1	33.1	33.1
R86 Millie	17.6	20.5	25.3	29.2	30.2	30.2	30.2	30.2	30.2	30.2
R81* Weean	17.6	20.5	25.2	29.1	30.1	30.1	30.1	30.1	30.1	30.1
R84 Glenidle	16.0	18.9	23.6	27.5	28.5	28.5	28.5	28.5	28.5	28.5
R85* Windemere	17.3	20.2	25.0	28.9	29.9	29.9	29.9	29.9	29.9	29.9
R88* Woodlands	13.5	16.3	21.1	25.0	25.9	26.0	26.0	26.0	26.0	26.0

SA EPA Criteria										
R28-Tralee Group	35.0	35.0	35.2	35.6	36.2	37.2	38.9	41.9	46.2	52.4
R28* Tralee	27.7	30.6	35.2	38.6	39.5	39.7	39.8	39.8	39.8	39.8
R26* Spring Creek	26.0	28.8	33.5	37.0	37.9	38.1	38.2	38.2	38.2	38.2
R27 Frasers Creek	24.2	27.1	31.7	35.3	36.2	36.4	36.5	36.5	36.5	36.5
R29 Krystal Blue	22.3	25.2	29.9	33.6	34.6	34.7	34.7	34.7	34.7	34.7
R90 Wirra Willa	21.0	23.9	28.5	32.2	33.1	33.2	33.3	33.3	33.3	33.3
R30 Argyle	20.1	23.0	27.7	31.5	32.5	32.5	32.6	32.6	32.6	32.6
R94 The Knoll	18.5	21.4	26.1	29.9	30.9	30.9	31.0	31.0	31.0	31.0
R91 Roseana	18.2	21.1	25.7	29.5	30.5	30.5	30.6	30.6	30.6	30.6
R93 Swamp Oak	16.4	19.3	24.0	27.7	28.7	28.8	28.8	28.8	28.8	28.8
R92 Lambert	14.9	17.8	22.4	26.3	27.2	27.3	27.3	27.3	27.3	27.3
R31 Glen Valley	17.1	20.0	24.7	28.6	29.6	29.6	29.6	29.6	29.6	29.6
R32 Swan Peak	17.7	20.5	25.3	29.1	30.1	30.1	30.2	30.2	30.2	30.2
R80* Weean Cottage	16.5	19.4	24.0	27.8	28.8	28.9	28.9	28.9	28.9	28.9
R89 Tomali Park	21.2	24.1	28.7	32.3	33.2	33.4	33.4	33.4	33.4	33.4
R95 Rock Leigh	18.8	21.7	26.4	30.2	31.2	31.2	31.3	31.3	31.3	31.3
R96 Unknown	16.3	19.2	23.9	27.7	28.7	28.7	28.8	28.8	28.8	28.8

SA EPA Criteria										
R36 Yarrawah Park Group	35.0	35.0	35.0	35.6	36.6	38.0	39.8	42.3	45.4	49.3
R36* Yarrawah Park	20.8	23.7	28.4	32.4	33.4	33.4	33.4	33.4	33.4	33.4
R37* Coorimbla Park	20.0	22.9	27.6	31.6	32.6	32.6	32.6	32.6	32.6	32.6
R35 Golden Grove	19.2	22.1	26.8	30.7	31.7	31.7	31.7	31.7	31.7	31.7
R38* Inverness	19.2	22.1	26.8	30.8	31.7	31.7	31.7	31.7	31.7	31.7
R34* Bellview	17.5	20.3	25.1	29.0	30.0	30.0	30.0	30.0	30.0	30.0

SA EPA Criteria										
R44-Mindora Group	35.0	35.5	36.3	36.8	37.8	39.6	42.8	47.9	55.5	66.1
R46 Alkoomie	23.8	26.7	31.4	35.4	36.4	36.4	36.4	36.4	36.4	36.4
R45 Glen Idle	22.1	25.0	29.7	33.7	34.7	34.7	34.7	34.7	34.7	34.7
R41 Royal Oaks	21.3	24.2	28.9	32.9	33.9	33.9	33.9	33.9	33.9	33.9
R42 Ashgrove	21.0	23.8	28.6	32.5	33.5	33.5	33.5	33.5	33.5	33.5
R39 Bon Vista	23.3	26.2	31.0	34.9	35.9	35.9	35.9	35.9	35.9	35.9
R40 Hillview	22.7	25.6	30.3	34.3	35.2	35.2	35.2	35.2	35.2	35.2
R44 Mindora	21.0	23.9	28.7	32.6	33.6	33.6	33.6	33.6	33.6	33.6

SA EPA Criteria										
R10-Mt Buckley Group	35.0	35.0	35.0	37.7	41.1	44.6	48.0	51.0	53.2	54.4
R10 Mt Buckley	24.8	27.7	32.4	36.4	37.3	37.3	37.3	37.3	37.3	37.3
R48 Adavale	15.5	18.4	23.1	27.1	28.0	28.0	28.0	28.0	28.0	28.0

SA EPA Criteria										
R19-Warrandah Group	35.0	35.0	35.0	36.9	40.3	43.7	46.6	48.3	48.3	46.2
R20* Lochlea	27.9	30.8	35.5	39.5	40.5	40.5	40.5	40.5	40.5	40.5
R21* 311	28.5	31.4	36.2	40.1	41.1	41.1	41.1	41.1	41.1	41.1
R19* Warrandah	27.0	29.9	34.6	38.5	39.5	39.5	39.5	39.5	39.5	39.5
R76* Cubba	19.1	21.9	26.7	30.6	31.6	31.6	31.6	31.6	31.6	31.6
R77 Meadow Vale	18.1	21.0	25.7	29.7	30.7	30.7	30.7	30.7	30.7	30.7
R4* Ardleigh	18.2	21.1	25.8	29.8	30.7	30.7	30.7	30.7	30.7	30.7
R78 Pine Grove	20.8	23.7	28.4	32.4	33.4	33.4	33.4	33.4	33.4	33.4
R79* Woodburn	21.5	24.4	29.1	33.1	34.1	34.1	34.1	34.1	34.1	34.1