

# BASIX<sup>®</sup>Certificate

Building Sustainability Index [www.basix.nsw.gov.au](http://www.basix.nsw.gov.au)

## Multi Dwelling

Certificate number: 348978M

This certificate confirms that the proposed development will meet the NSW government's requirements for sustainability, if it is built in accordance with the commitments set out below. Terms used in this certificate, or in the commitments, have the meaning given by the document entitled "BASIX Definitions" dated 29/06/2009 published by the Department of Planning. This document is available at [www.basix.nsw.gov.au](http://www.basix.nsw.gov.au)

Director-General

Date of issue: Monday, 29 November 2010



Planning

Project summary		
Project name	7 Railway Street, Chatswood (601-1304) (noRWlands)	
Street address	7 Railway Street Chatswood 2067	
Local Government Area	Willoughby City Council	
Plan type and plan number	deposited 1058962	
Lot no.	6	
Section no.	-	
No. of unit buildings	1	
No. of units in unit buildings	74	
No. of attached dwelling houses	0	
No. of separate dwelling houses	0	
Project score		
Water	✓ 43	Target 40
Thermal Comfort	✓ Pass	Target Pass
Energy	✓ 20	Target 20

### Certificate Prepared by (please complete before submitting to Council or PCA)

Name / Company Name:

ABN (if applicable):

# Description of project

Project address	
Project name	7 Railway Street, Chatswood (601-1304) (noRWlands)
Street address	7 Railway Street Chatswood 2067
Local Government Area	Willoughby City Council
Plan type and plan number	deposited 1058962
Lot no.	6
Section no.	-
Project type	
No. of unit buildings	1
No. of units in unit buildings	74
No. of attached dwelling houses	0
No. of separate dwelling houses	0
Site details	
Site area (m <sup>2</sup> )	1228.25
Roof area (m <sup>2</sup> )	293.75
Non-residential floor area (m <sup>2</sup> )	1248.3
Residential car spaces	74
Non-residential car spaces	10

Common area landscape		
Common area lawn (m <sup>2</sup> )	121.5	
Common area garden (m <sup>2</sup> )	325	
Area of indigenous or low water use species (m <sup>2</sup> )	250	
Assessor details		
Assessor number	20241	
Certificate number	37064536	
Climate zone	56	
Project score		
Water	✓ 43	Target 40
Thermal Comfort	✓ Pass	Target Pass
Energy	✓ 20	Target 20

## Description of project

The tables below describe the dwellings and common areas within the project

### Unit building - 601-1304, 74 dwellings, 42 storeys above ground

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
601	2	101.0	0.0	0	0
605	1	57.0	0.0	0	0
609	2	104.0	0.0	0	0
703	2	95.0	0.0	0	0
707	1	59.0	0.0	0	0
801	2	101.0	0.0	0	0
805	1	57.0	0.0	0	0
809	2	104.0	0.0	0	0
903	2	95.0	0.0	0	0
907	1	59.0	0.0	0	0
1001	2	101.0	0.0	0	0
1005	1	57.0	0.0	0	0
1009	2	104.0	0.0	0	0
1103	2	95.0	0.0	0	0
1107	1	59.0	0.0	0	0
1201	2	101.0	0.0	0	0
1205	1	57.0	0.0	0	0
1209	2	104.0	0.0	0	0

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
602	1	59.0	0.0	0	0
606	1	54.0	0.0	0	0
610	3	135.0	0.0	0	0
704	1	61.0	0.0	0	0
708	2	104.0	0.0	0	0
802	1	59.0	0.0	0	0
806	1	54.0	0.0	0	0
810	3	135.0	0.0	0	0
904	1	61.0	0.0	0	0
908	2	104.0	0.0	0	0
1002	1	59.0	0.0	0	0
1006	1	54.0	0.0	0	0
1010	3	135.0	0.0	0	0
1104	1	61.0	0.0	0	0
1108	2	104.0	0.0	0	0
1202	1	59.0	0.0	0	0
1206	1	54.0	0.0	0	0
1210	3	135.0	0.0	0	0

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
603	2	95.0	0.0	0	0
607	1	59.0	0.0	0	0
701	2	101.0	0.0	0	0
705	1	57.0	0.0	0	0
709	2	104.0	0.0	0	0
803	2	95.0	0.0	0	0
807	1	59.0	0.0	0	0
901	2	101.0	0.0	0	0
905	1	57.0	0.0	0	0
909	2	104.0	0.0	0	0
1003	2	95.0	0.0	0	0
1007	1	59.0	0.0	0	0
1101	2	101.0	0.0	0	0
1105	1	57.0	0.0	0	0
1109	2	104.0	0.0	0	0
1203	2	95.0	0.0	0	0
1207	1	59.0	0.0	0	0
1301	2	101.0	0.0	0	0

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
604	1	61.0	0.0	0	0
608	2	104.0	0.0	0	0
702	1	59.0	0.0	0	0
706	1	54.0	0.0	0	0
710	3	135.0	0.0	0	0
804	1	61.0	0.0	0	0
808	2	104.0	0.0	0	0
902	1	59.0	0.0	0	0
906	1	54.0	0.0	0	0
910	3	135.0	0.0	0	0
1004	1	61.0	0.0	0	0
1008	2	104.0	0.0	0	0
1102	1	59.0	0.0	0	0
1106	1	54.0	0.0	0	0
1110	3	135.0	0.0	0	0
1204	1	61.0	0.0	0	0
1208	2	104.0	0.0	0	0
1302	1	59.0	0.0	0	0

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
1303	3	95.0	0.0	0	0

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
1304	1	61.0	0.0	0	0

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
--------------	-----------------	--	--	---	---

Dwelling no.	No. of bedrooms	Conditioned floor area (m <sup>2</sup> )	Unconditioned floor area (m <sup>2</sup> )	Area of garden & lawn (m <sup>2</sup> )	Indigenous species (min area m <sup>2</sup> )
--------------	-----------------	--	--	---	---

## Description of project

The tables below describe the dwellings and common areas within the project

### Common areas of unit building - 601-1304

Common area	Floor area (m <sup>2</sup> )
Indoor pool &/or spa area (No. 1)	37
Lift car (No. 1)	-
Lift car (No. 4)	-
Lift motor room (No. 1)	14.25
Plant or service room (No. 1)	456.25
Hallway/lobby type (No. 1)	520

Common area	Floor area (m <sup>2</sup> )
Gym (No. 1)	8.25
Lift car (No. 2)	-
Lift car (No. 5)	-
Switch room (No. 1)	7.5
Ground floor lobby type (No. 1)	16

Common area	Floor area (m <sup>2</sup> )
Car park area (No. 1)	3665
Lift car (No. 3)	-
Lift car (No. 6)	-
Garbage room (No. 1)	35
Ground floor lobby type (No. 2)	30

# Schedule of BASIX commitments

## 1. Commitments for unit building - 601-1304

### (a) Dwellings

- (i) Water
- (ii) Energy
- (iii) Thermal Comfort

### (b) Common areas and central systems/facilities

- (i) Water
- (ii) Energy

## 2. Commitments for attached dwelling houses

## 3. Commitments for separate dwelling houses

## 4. Commitments for common areas and central systems/facilities for the development (non-building specific)

- (i) Water
- (ii) Energy

## Schedule of BASIX commitments

The commitments set out below regulate how the proposed development is to be carried out. It is a condition of any development consent granted, or complying development certificate issued, for the proposed development, that BASIX commitments be complied with.

### 1. Commitments for unit building - 601-1304

#### (a) Dwellings

(i) Water	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must comply with the commitments listed below in carrying out the development of a dwelling listed in a table below.			
(b) The applicant must plant indigenous or low water use species of vegetation throughout the area of land specified for the dwelling in the "Indigenous species" column of the table below, as private landscaping for that dwelling. (This area of indigenous vegetation is to be contained within the "Area of garden and lawn" for the dwelling specified in the "Description of Project" table).	✓	✓	
(c) If a rating is specified in the table below for a fixture or appliance to be installed in the dwelling, the applicant must ensure that each such fixture and appliance meets the rating specified for it.		✓	✓
(d) The applicant must install an on demand hot water recirculation system which regulates all hot water use throughout the dwelling, where indicated for a dwelling in the "HW recirculation or diversion" column of the table below.		✓	✓
(e) The applicant must install: <ul style="list-style-type: none"> <li>(aa) a hot water diversion system to all showers, kitchen sinks and all basins in the dwelling, where indicated for a dwelling in the "HW recirculation or diversion" column of the table below; and</li> <li>(bb) a separate diversion tank (or tanks) connected to the hot water diversion systems of at least 100 litres. The applicant must connect the hot water diversion tank to all toilets in the dwelling.</li> </ul>		✓	✓
(e) The applicant must not install a private swimming pool or spa for the dwelling, with a volume exceeding that specified for it in the table below.	✓	✓	
(f) If specified in the table, that pool or spa (or both) must have a pool cover or shading (or both).		✓	
(g) The pool or spa must be located as specified in the table.	✓	✓	
(h) The applicant must install, for the dwelling, each alternative water supply system, with the specified size, listed for that dwelling in the table below. Each system must be configured to collect run-off from the areas specified (excluding any area which supplies any other alternative water supply system), and to divert overflow as specified. Each system must be connected as specified.	✓	✓	✓

Dwelling no.	Fixtures					Appliances		Individual pool				Individual spa		
	All shower-heads	All toilet flushing systems	All kitchen taps	All bathroom taps	HW recirculation or diversion	All clothes washers	All dish-washers	Volume (max volume)	Pool cover	Pool location	Pool shaded	Volume (max volume)	Spa cover	Spa shaded
All dwellings	3 star (> 7.5 but <= 9 L/min)	4 star	4 star	4 star	no	4 star	3 star	-	-	-	-	-	-	-

Dwelling no.	Alternative water source							
	Alternative water supply systems	Size	Configuration	Landscape connection	Toilet connection (s)	Laundry connection	Pool top-up	Spa top-up
All dwellings	central water tank (no. 1)	See central systems	See central systems	no	yes	no	no	no
None	-	-	-	-	-	-	-	-

(ii) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must comply with the commitments listed below in carrying out the development of a dwelling listed in a table below.			
(b) The applicant must install each hot water system specified for the dwelling in the table below, so that the dwelling's hot water is supplied by that system. If the table specifies a central hot water system for the dwelling, then the applicant must connect that central system to the dwelling, so that the dwelling's hot water is supplied by that central system.	✓	✓	✓
(c) The applicant must install, in each bathroom, kitchen and laundry of the dwelling, the ventilation system specified for that room in the table below. Each such ventilation system must have the operation control specified for it in the table.		✓	✓
(d) The applicant must install the cooling and heating system/s specified for the dwelling under the "Living areas" and "Bedroom areas" headings of the "Cooling" and "Heating" columns in the table below, in/for at least 1 living/bedroom area of the dwelling. If no cooling or heating system is specified in the table for "Living areas" or "Bedroom areas", then no systems may be installed in any such areas. If the term "zoned" is specified beside an air conditioning system, then the system must provide for day/night zoning between living areas and bedrooms.		✓	✓
(e) This commitment applies to each room or area of the dwelling which is referred to in a heading to the "Artificial lighting" column of the table below (but only to the extent specified for that room or area). The applicant must ensure that the "primary type of artificial lighting" for each such room in the dwelling is fluorescent lighting or light emitting diode (LED) lighting. If the term "dedicated" is specified for a particular room or area, then the light fittings in that room or area must only be capable of being used for fluorescent lighting or light emitting diode (LED) lighting.		✓	✓

<b>(ii) Energy</b>	<b>Show on DA plans</b>	<b>Show on CC/CDC plans &amp; specs</b>	<b>Certifier check</b>
(f) This commitment applies to each room or area of the dwelling which is referred to in a heading to the "Natural lighting" column of the table below (but only to the extent specified for that room or area). The applicant must ensure that each such room or area is fitted with a window and/or skylight.	✓	✓	✓
(g) This commitment applies if the applicant installs a water heating system for the dwelling's pool or spa. The applicant must: (aa) install the system specified for the pool in the "Individual Pool" column of the table below (or alternatively must not install any system for the pool). If specified, the applicant must install a timer, to control the pool's pump; and (bb) install the system specified for the spa in the "Individual Spa" column of the table below (or alternatively must not install any system for the spa). If specified, the applicant must install a timer to control the spa's pump.		✓ ✓	
(h) The applicant must install in the dwelling: (aa) the kitchen cook-top and oven specified for that dwelling in the "Appliances & other efficiency measures" column of the table below; (bb) each appliance for which a rating is specified for that dwelling in the "Appliances & other efficiency measures" column of the table, and ensure that the appliance has that minimum rating; and (cc) any clothes drying line specified for the dwelling in the "Appliances & other efficiency measures" column of the table.		✓ ✓ ✓	✓
(i) If specified in the table, the applicant must carry out the development so that each refrigerator space in the dwelling is "well ventilated".		✓	

	<b>Hot water</b>	<b>Bathroom ventilation system</b>		<b>Kitchen ventilation system</b>		<b>Laundry ventilation system</b>	
<b>Dwelling no.</b>	<b>Hot water system</b>	<b>Each bathroom</b>	<b>Operation control</b>	<b>Each kitchen</b>	<b>Operation control</b>	<b>Each laundry</b>	<b>Operation control</b>
1208, 1209, 1210, 1301, 1302, 1303, 1304	central hot water system 1	individual fan into central duct + VSD	manual switch on/off	individual fan, ducted to façade or roof	manual switch on/off	individual fan into central duct + VSD	manual switch on/off

	Hot water	Bathroom ventilation system		Kitchen ventilation system		Laundry ventilation system	
Dwelling no.	Hot water system	Each bathroom	Operation control	Each kitchen	Operation control	Each laundry	Operation control
601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 1001, 1002, 1003, 1004, 1005, 1006, 1007, 1008, 1009, 1010, 1101, 1102, 1103, 1104, 1105, 1106, 1107, 1108, 1109, 1110, 1201,	central hot water system 1	motorised damper into central duct + VSD	manual switch on/off	individual fan, ducted to façade or roof	manual switch on/off	motorised damper into central duct + VSD	manual switch on/off

	Hot water	Bathroom ventilation system		Kitchen ventilation system		Laundry ventilation system	
Dwelling no.	Hot water system	Each bathroom	Operation control	Each kitchen	Operation control	Each laundry	Operation control
1202, 1203, 1204, 1205, 1206, 1207							

	Cooling		Heating		Artificial lighting					Natural lighting		
Dwelling no.	living areas	bedroom areas	living areas	bedroom areas	No. of bedrooms &/or study	No. of living &/or dining rooms	Each kitchen	All bathrooms/toilets	Each laundry	All hallways	No. of bathrooms &/or toilets	Main kitchen
1302, 1304	central cooling system 1 (zoned)	central cooling system 1 (zoned)	central heating system 1 (zoned)	central heating system 1 (zoned)	1 (dedicated)	0	no	yes	yes	no	0	yes
610, 710, 810, 910, 1010, 1110, 1210, 1303	central cooling system 1 (zoned)	central cooling system 1 (zoned)	central heating system 1 (zoned)	central heating system 1 (zoned)	3 (dedicated)	0	no	yes (dedicated)	yes (dedicated)	no	0	yes

Dwelling no.	Cooling		Heating		Artificial lighting					Natural lighting		
	living areas	bedroom areas	living areas	bedroom areas	No. of bedrooms &/or study	No. of living &/or dining rooms	Each kitchen	All bathrooms/toilets	Each laundry	All hallways	No. of bathrooms &/or toilets	Main kitchen
601, 603, 608, 609, 701, 703, 708, 709, 801, 803, 808, 809, 901, 903, 908, 909, 1001, 1003, 1008, 1009, 1101, 1103, 1108, 1109, 1201, 1203, 1208, 1209, 1301	central cooling system 1 (zoned)	central cooling system 1 (zoned)	central heating system 1 (zoned)	central heating system 1 (zoned)	2 (dedicated)	0	no	yes (dedicated)	yes (dedicated)	no	0	yes

Dwelling no.	Cooling		Heating		Artificial lighting					Natural lighting		
	living areas	bedroom areas	living areas	bedroom areas	No. of bedrooms &/or study	No. of living &/or dining rooms	Each kitchen	All bathrooms/toilets	Each laundry	All hallways	No. of bathrooms &/or toilets	Main kitchen
602, 604, 605, 606, 607, 702, 704, 705, 706, 707, 802, 804, 805, 806, 807, 902, 904, 905, 906, 907, 1002, 1004, 1005, 1006, 1007, 1102, 1104, 1105, 1106, 1107, 1202, 1204, 1205, 1206, 1207	central cooling system 1 (zoned)	central cooling system 1 (zoned)	central heating system 1 (zoned)	central heating system 1 (zoned)	1 (dedicated)	0	no	yes (dedicated)	yes (dedicated)	no	0	yes

Dwelling no.	Individual pool		Individual spa		Appliances & other efficiency measures							
	Pool heating system	Timer	Spa heating system	Timer	Kitchen cooktop/oven	Refrigerator	Well ventilated fridge space	Dishwasher	Clothes washer	Clothes dryer	Indoor or sheltered clothes drying line	Private outdoor or unsheltered clothes drying line
All dwellings	-	-	-	-	gas cooktop & electric oven	-	yes	3 star	2.5 star	2 star	yes	no

(iii) Thermal Comfort	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must attach the certificate referred to under "Assessor details" on the front page of this BASIX certificate (the "Assessor Certificate") to the development application and construction certificate application for the proposed development (or, if the applicant is applying for a complying development certificate for the proposed development, to that application). The applicant must also attach the Assessor Certificate to the application for a final occupation certificate for the proposed development.			
(b) The Assessor Certificate must have been issued by an Accredited Assessor in accordance with the Thermal Comfort Protocol.			
(c) The details of the proposed development on the Assessor Certificate must be consistent with the details shown in this BASIX Certificate, including the details shown in the "Thermal Loads" table below.			
(d) The applicant must show on the plans accompanying the development application for the proposed development, all matters which the Thermal Comfort Protocol requires to be shown on those plans. Those plans must bear a stamp of endorsement from the Accredited Assessor, to certify that this is the case.			
(e) The applicant must show on the plans accompanying the application for a construction certificate (or complying development certificate, if applicable), all thermal performance specifications set out in the Assessor Certificate, and all aspects of the proposed development which were used to calculate those specifications.			
(f) The applicant must construct the development in accordance with all thermal performance specifications set out in the Assessor Certificate, and in accordance with those aspects of the development application or application for a complying development certificate which were used to calculate those specifications.		✓	✓
(g) Where there is an in-slab heating or cooling system, the applicant must:  (aa) Install insulation with an R-value of not less than 1.0 around the vertical edges of the perimeter of the slab; or (bb) On a suspended floor, install insulation with an R-value of not less than 1.0 underneath the slab and around the vertical edges of the perimeter of the slab.	✓	✓	✓
(h) The applicant must construct the floors and walls of the development in accordance with the specifications listed in the table below.	✓	✓	✓

Dwelling no.	Thermal loads	
	Area adjusted heating load (in mJ/m <sup>2</sup> /yr)	Area adjusted cooling load (in mJ/m <sup>2</sup> /yr)
605, 705, 805, 905, 1005, 1105, 1205	34.9	30
606, 706, 806, 906, 1006, 1106, 1206	30.3	14.4
607, 707, 807, 907, 1007, 1107, 1207	19.4	24.8
608, 708, 808, 908, 1008, 1108, 1208	18.1	13.4
609, 709, 809, 909, 1009, 1109, 1209	11.7	18.9
610, 710, 810, 910, 1010, 1110, 1210	27.2	26.9
601, 701, 801, 901, 1001, 1101, 1201, 1301	25.3	24.9
602, 702, 802, 902, 1002, 1102, 1202, 1302	13.8	23.1
603, 703, 803, 903, 1003, 1103, 1203, 1303	14.5	28.2
All other dwellings	15.8	25.4

**(b) Common areas and central systems/facilities**

(i) Water	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a showerhead, toilet, tap or clothes washer into a common area, then that item must meet the specifications listed for it in the table.		✓	✓
(b) The applicant must install (or ensure that the development is serviced by) the alternative water supply system(s) specified in the "Central systems" column of the table below. In each case, the system must be sized, be configured, and be connected, as specified in the table.	✓	✓	✓
(c) A swimming pool or spa listed in the table must not have a volume (in kLs) greater than that specified for the pool or spa in the table.	✓	✓	
(d) A pool or spa listed in the table must have a cover or shading if specified for the pool or spa in the table.		✓	
(e) The applicant must install each fire sprinkler system listed in the table so that the system is configured as specified in the table.		✓	✓
(f) The applicant must ensure that the central cooling system for a cooling tower is configured as specified in the table.		✓	✓

Common area	Showerheads rating	Toilets rating	Taps rating	Clothes washers rating
All common areas	3 star (> 7.5 but ≤ 9 L/min)	3 star	4 star	no common laundry facility

Central systems	Size	Configuration	Connection (to allow for...)
Central water tank - rainwater or stormwater (No. 1)	12500	To collect run-off from at least: - 250 square metres of roof area of buildings in the development - 0 square metres of impervious area in the development - 0 square metres of garden/lawn area in the development - 0 square metres of planter box area in the development (excluding, in each case, any area which drains to, or supplies, any other alternative water supply system).	- irrigation of 0 square metres of common landscaped area on the site - car washing in 0 car washing bays on the site
Pool (No. 1)	Volume: 18 kLs	Location: Indoor pool &/or spa area (No. 1)	-
Fire sprinkler system (No. 1)	-	-	-

<b>(ii) Energy</b>	<b>Show on DA plans</b>	<b>Show on CC/CDC plans &amp; specs</b>	<b>Certifier check</b>
(a) If, in carrying out the development, the applicant installs a ventilation system to service a common area specified in the table below, then that ventilation system must be of the type specified for that common area, and must meet the efficiency measure specified.		✓	✓
(b) In carrying out the development, the applicant must install, as the "primary type of artificial lighting" for each common area specified in the table below, the lighting specified for that common area. This lighting must meet the efficiency measure specified. The applicant must also install a centralised lighting control system or Building Management System (BMS) for the common area, where specified.		✓	✓
(c) The applicant must install the systems and fixtures specified in the "Central energy systems" column of the table below. In each case, the system or fixture must be of the type, and meet the specifications, listed for it in the table.	✓	✓	✓

	<b>Common area ventilation system</b>		<b>Common area lighting</b>		
<b>Common area</b>	<b>Ventilation system type</b>	<b>Ventilation efficiency measure</b>	<b>Primary type of artificial lighting</b>	<b>Lighting efficiency measure</b>	<b>Lighting control system/BMS</b>
Indoor pool &/or spa area (No. 1)	air conditioning system	time clock or BMS controlled	compact fluorescent	manual on / manual off	No
Gym (No. 1)	air conditioning system	time clock or BMS controlled	compact fluorescent	manual on / manual off	No
Car park area (No. 1)	ventilation (supply + exhaust)	carbon monoxide monitor + VSD fan	fluorescent	zoned switching with motion sensor	No
Lift car (No. 1)	-	-	compact fluorescent	none	No
Lift car (No. 2)	-	-	compact fluorescent	none	No
Lift car (No. 3)	-	-	compact fluorescent	none	No
Lift car (No. 4)	-	-	compact fluorescent	none	No
Lift car (No. 5)	-	-	compact fluorescent	none	No
Lift car (No. 6)	-	-	compact fluorescent	none	No
Lift motor room (No. 1)	ventilation exhaust only	none ie. continuous	compact fluorescent	manual on / manual off	No
Switch room (No. 1)	ventilation exhaust only	none ie. continuous	compact fluorescent	manual on / manual off	No
Garbage room (No. 1)	ventilation exhaust only	-	compact fluorescent	manual on / manual off	No
Plant or service room (No. 1)	ventilation exhaust only	none ie. continuous	compact fluorescent	manual on / manual off	No

Common area	Common area ventilation system		Common area lighting		
	Ventilation system type	Ventilation efficiency measure	Primary type of artificial lighting	Lighting efficiency measure	Lighting control system/BMS
Ground floor lobby type (No. 1)	air conditioning system	time clock or BMS controlled	compact fluorescent	time clock and motion sensors	No
Ground floor lobby type (No. 2)	air conditioning system	time clock or BMS controlled	compact fluorescent	time clock and motion sensors	No
Hallway/lobby type (No. 1)	ventilation supply only	time clock or BMS controlled	compact fluorescent	time clock and motion sensors	No

Central energy systems	Type	Specification
Central hot water system (No. 1)	gas-fired boiler	Piping insulation (ringmain & supply risers): (b) Piping internal to building: R1.0 (~38 mm)
Central cooling system (No. 1)	water source packaged units	Heat rejection method: cooling tower Unit efficiency (min): low - COP < 3.5
Central heating system (No. 1)	water source packaged units + heated water	Energy source: gas boiler Unit efficiency: medium - COP 3.5 - 4.5
Lift (No. 1)	gearless traction with V V V F motor	Number of levels (including basement): 10
Lift (No. 2)	gearless traction with V V V F motor	Number of levels (including basement): 10
Lift (No. 3)	gearless traction with V V V F motor	Number of levels (including basement): 10
Lift (No. 4)	gearless traction with V V V F motor	Number of levels (including basement): 10
Lift (No. 5)	gearless traction with V V V F motor	Number of levels (including basement): 3
Lift (No. 6)	gearless traction with V V V F motor	Number of levels (including basement): 3
Pool (No. 1)	Heating source: gas	Pump controlled by timer: yes
Sauna (No. 1)	Heating source: electric resistance	Efficiency measure: manual on / timer off

#### 4. Commitments for common areas and central systems/facilities for the development (non-building specific)

##### (b) Common areas and central systems/facilities

(i) Water	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a showerhead, toilet, tap or clothes washer into a common area, then that item must meet the specifications listed for it in the table.		✓	✓
(b) The applicant must install (or ensure that the development is serviced by) the alternative water supply system(s) specified in the "Central systems" column of the table below. In each case, the system must be sized, be configured, and be connected, as specified in the table.	✓	✓	✓
(c) A swimming pool or spa listed in the table must not have a volume (in kLs) greater than that specified for the pool or spa in the table.	✓	✓	
(d) A pool or spa listed in the table must have a cover or shading if specified for the pool or spa in the table.		✓	
(e) The applicant must install each fire sprinkler system listed in the table so that the system is configured as specified in the table.		✓	✓
(f) The applicant must ensure that the central cooling system for a cooling tower is configured as specified in the table.		✓	✓

Common area	Showerheads rating	Toilets rating	Taps rating	Clothes washers rating
All common areas	3 star (> 7.5 but ≤ 9 L/min)	3 star	4 star	no common laundry facility

(ii) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a ventilation system to service a common area specified in the table below, then that ventilation system must be of the type specified for that common area, and must meet the efficiency measure specified.		✓	✓
(b) In carrying out the development, the applicant must install, as the "primary type of artificial lighting" for each common area specified in the table below, the lighting specified for that common area. This lighting must meet the efficiency measure specified. The applicant must also install a centralised lighting control system or Building Management System (BMS) for the common area, where specified.		✓	✓
(c) The applicant must install the systems and fixtures specified in the "Central energy systems" column of the table below. In each case, the system or fixture must be of the type, and meet the specifications, listed for it in the table.	✓	✓	✓

Central energy systems	Type	Specification
Alternative energy supply	Photovoltaic system	Rated electrical output (min): 11.8 peak kW

## Notes

1. In these commitments, "applicant" means the person carrying out the development.
2. The applicant must identify each dwelling, building and common area listed in this certificate, on the plans accompanying any development application, and on the plans and specifications accompanying the application for a construction certificate / complying development certificate, for the proposed development, using the same identifying letter or reference as is given to that dwelling, building or common area in this certificate.
3. This note applies if the proposed development involves the erection of a building for both residential and non-residential purposes (or the change of use of a building for both residential and non-residential purposes). Commitments in this certificate which are specified to apply to a "common area" of a building or the development, apply only to that part of the building or development to be used for residential purposes.
4. If this certificate lists a central system as a commitment for a dwelling or building, and that system will also service any other dwelling or building within the development, then that system need only be installed once (even if it is separately listed as a commitment for that other dwelling or building).
5. If a star or other rating is specified in a commitment, this is a minimum rating.
6. All alternative water systems to be installed under these commitments (if any), must be installed in accordance with the requirements of all applicable regulatory authorities. NOTE: NSW Health does not recommend that stormwater, recycled water or private dam water be used to irrigate edible plants which are consumed raw, or that rainwater be used for human consumption in areas with potable water supply.

## Legend

1. Commitments identified with a "✓" in the "Show on DA plans" column must be shown on the plans accompanying the development application for the proposed development (if a development application is to be lodged for the proposed development).
2. Commitments identified with a "✓" in the "Show on CC/CDC plans and specs" column must be shown in the plans and specifications accompanying the application for a construction certificate / complying development certificate for the proposed development.
3. Commitments identified with a "✓" in the "Certifier check" column must be certified by a certifying authority as having been fulfilled. (Note: a certifying authority must not issue an occupation certificate (either interim or final) for a building listed in this certificate, or for any part of such a building, unless it is satisfied that each of the commitments whose fulfilment it is required to monitor in relation to the building or part, has been fulfilled).