

17 April 2013

Newland Developers Pty Ltd
Suite 205, Level 2, Eastside
232 Robina Town Centre Drive
Robina Q4226

Attention: Shaun Nicholson – Regional Manager, North Queensland

Dear Shaun,

Re: Revised Preferred Project Application, Altitude Aspire, Terranora, New South Wales – Summary of soil contamination assessments

Newland Developers Pty Ltd commissioned Gilbert & Sutherland Pty Ltd (G&S) to prepare a summary of contamination assessments conducted at the proposed Altitude Aspire residential development site (herein referred to as 'the site') for input into the Revised Preferred Project Report (PPR).

Background

Glazebrook & Associates Pty Ltd conducted a detailed site history investigation of the entire Terranora 'Area E' in May 2003. That assessment identified potentially contaminating activities associated with historical agricultural practices. That report was included as Appendix A in G&S's *Soil Contamination Assessment for 'Area E' Properties Terranora, Volume 1 – Report*, prepared for Metricon Qld Pty Ltd (Metricon) in October 2003, ('the 2003 contamination assessment', which is provided as Attachment 1).

Contamination assessment

G&S provided Metricon with a summary of contamination issues relating to the site (formerly known as 'Altitude 1') in advice dated 2 October 2009 (included herein as Attachment 2). The soil testing conducted as part of the 2003 contamination assessment found no soil contamination on lands that now comprise the Altitude Aspire development site. That testing included the recovery and NATA-accredited laboratory analysis of shallow soil samples from 508 boreholes drilled within the site.

The suite of analytes was particular to the identified historical activities that had occurred on the site. Contaminants of Potential Concern (COPC) were identified as:

- Arsenic
- Lead
- Aldrin/Dieldrin
- Chlordane
- DDT, DDD and DDE (attributable to pesticide use)
- Cadmium
- Copper
- Mercury
- Zinc.

The analytical results identified no contamination exceeding the applicable Health-Based Investigation Levels (HILs).

Conclusion

The 2003 contamination assessment found no contamination in excess of the adopted HILs associated with historical agricultural use of the lots that now comprise the Altitude Aspire site. We understand that report was accepted by TSC. The site was in a similar, undeveloped state at the time we prepared our 2 October 2009 advice, which concluded that the 2003 contamination report findings remained valid and no further contamination assessment was required. We understand that advice was accepted by the NSW Department of Planning.

The site is currently in a similar, undeveloped condition to that encountered by us in 2003 and 2009. We have visited, inspected and undertaken works at the site since 2009. We have observed nothing that would cause us to now change our conclusions from those of our 2 October 2009 advice. On the basis of our 2003 assessment and subsequent review (2009), with respect to contamination, we consider the site to be suitable for its intended residential use. The conclusions of our 2003 report and 2009 correspondence address the DGRs with respect to the information required to address SEPP 55 – Remediation of Land. A Site Audit Statement is not required, as SEPP 55 has already been addressed.

We trust that this is acceptable. Please do not hesitate to contact this office should you require any further details or elaboration.

Yours sincerely,



Nathan Zurig
Director/Principal Environmental Scientist
BAppScEnv(Hons)



Michelle Foster
Senior Environmental Scientist
BAppSc(ResMan)

Author Michelle Foster

Our Reference 10849_ADV_CA_MLF1F.docx

Your Reference

By ☐ Courier ☒ Email ☐ Facsimile ☐ Post

Enclosures 2 (2003 contamination report; 2009 letter)

Attachment 1 G&S 2003 contamination report



**Soil Contamination
Assessment for
'Area E' Properties
Terranora**

Volume 1 - Report

Prepared for
Metricon Queensland Pty Ltd

October, 2003

Originating office:

Suite 12, Riverwalk One
Robina Town Centre Drive, Robina Q4230
PO Box 4115, Robina Q4226
Telephone 07 5578 9944
Facsimile 07 5578 9945
gsrobina@bigpond.com

Also at Kawana and Ballina

Table of Contents

1. Introduction	3
1.1 Background	3
1.2 Scope of works	4
1.3 Report structure	4
2. Site history	5
3. Historical use of chemicals	6
4. Site description	8
4.1 Study area	8
4.2 Geology and soils	8
4.3 Topography and drainage	8
4.4 Vegetation	8
5. Subsurface investigation	9
5.1 Fieldwork	9
5.2 Laboratory analysis	9
6. Results	10
6.1 Soil investigation levels	10
6.2 Results for Lot 2 DP 785420 (Cartwright)	10
6.3 Results for Lot 376 DP 755740 (Greber)	12
6.4 Results for Lot 377 DP 755740 (Greber)	12
6.5 Results for Lot 1 DP 962558 (Greber)	13
6.6 Results for Lot 1 DP 225183 (Greber)	14
6.7 Results for Lot 4 DP 582842 (James)	15
6.7.1 (Site A)	15
6.7.2 (Site B)	16
6.8 Results for Lot 1 DP 215959 (Nichols)	17
6.9 Results for Lot 2 DP 215959 (Nichols)	18
6.10 Results for Lot 12 DP 534942 (Nichols)	19
6.11 Results for Lot 1 DP 723050 (Nichols)	20
6.12 Results for Lot 1 DP 984118 (Nichols)	20
6.13 Results for Lot 2 DP 778727 & Lot 3 DP 587869 (Abernathy)	21
6.14 Results for Lot 1 DP 781697, Lot 1 DP 169490 & Lot 40 DP 254416 (Abernathy)	22
6.15 Results for Lot 1 DP 781687 & Lot 43 DP 254416 (Abernathy)	22
6.16 Results for Lot 1 DP 175235 (Abernathy)	23
6.17 Results for Lot 1 DP 304649 (Abernathy)	24
5. Conclusions and recommendations	26
Appendix A. Site history assessment report	27
Appendix B. Laboratory certificates	Volume 2
Appendix B. Laboratory certificates	Volume 3

1. Introduction

1.1 Background

Gilbert and Sutherland Pty Ltd was commissioned by Metricon QLD Pty Ltd to conduct a Soil Contamination Assessment for several properties located within the 'Area E' planning catchment, Terranora. The property locations are shown on Drawing Number GJ0128.1.1. The properties investigated are listed in Table 1 below:


Table 1. Properties investigated for soil chemical residues.

Lot	DP	Ha	Current owner
2	785420	2.405	Cartwright, C. J. & J. M.
376	755740	4.429	Greber, D. W.
377	755740	4.047	Greber, D. W.
1	962558	4.047	Greber, D. W.
1	225183	12.780	Greber, G. L & A. M.
4 (Site A)	582842	4.4	James, G. R & L. J.
4 (Site B)	582842	5.84	James, G. R & L. J.
227	755740	51.900	Bolster, J.
1	215959	9.423	Nichols, B. I. O & D. J. (Est.)
2	215959	3.017	Nichols, B. I. O & D. J. (Est.)
12	534942	22.340	Nichols, B. I. O & D. J. (Est.)
1	723050	0.755	Nichols, B. I. O & D. J. (Est.)
1	984118	4.838	Nichols, B. I. O & D. J. (Est.)
3	587869	0.246	Abemathy, G. R.
1	169490	0.348	Abemathy, F.
1	175235	13.840	Abemathy, F.
40	254416	0.065	Abemathy, F.
43	254416	0.036	Abemathy, F.
1	304649	4.702	Abemathy, F.
2	778727	8.525	Abemathy, F.
1	781687	4.707	Abemathy, F.
1	781697	3.523	Abemathy, F.

The "site" properties are zoned rural and have been used for agriculture. To cater for urban expansion within the area, Metricon QLD Pty Ltd proposes to subdivide the subject properties into a number of smaller residential house blocks.

This soil contamination assessment was conducted in accordance with the following guidelines:

- Guidelines for Consultants Reporting on Contaminated Sites (NSW EPA 2000),
- Guidelines for Assessing Banana Plantation Sites (NSW EPA 1997),
- Contaminated Sites Sampling Design Guidelines (NSW EPA 1995),
- Assessment of Orchard and Market Garden Contaminated Sites Discussion Paper (NSW EPA 1995), and
- Guideline on the Investigation Levels for Soil and Groundwater Schedule B (1) (National Environment Protection Council).



Gilbert & Sutherland
— Specialists Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 780919 Fax 55789945



PROJECT

SITE LAYOUT

METRICON

L'AREA E' TERRANORA

SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCALING.

APPROVED

SCOTT & BOWEN

001501 017	
------------	--

DRAFTING No.

GJ0128.1.1

1.2 Scope of works

The following scope of works was conducted by Gilbert and Sutherland:

- identify potential contamination types,
- discuss the site condition,
- provide an assessment of the site contamination, and
- determine any need for further investigations.

1.3 Report structure

This report comprises three volumes and should only be referenced in its entirety.

2. Site history

A detailed site history assessment for several properties within "Area E" was undertaken on behalf of Gilbert & Sutherland by Glazebrook & Associates Pty Ltd in May 2003. The report is attached as Appendix A. The site history assessment was conducted by examining topographic maps, aerial photographs and by reviewing a report prepared previously by Wilkie Fleming & Associates Pty Ltd and Property Management Consultants "Assessment of Soil Chemical Residues and Agricultural Report, 1994".

In relation to the subject properties the site history report generally identified the following agricultural usages:

- banana plantations and possible stockyards were identified on various properties as early as 1935,
- presence of buildings, sheds and dams,
- broad clearance of land, and
- small crops including zucchini, sweet potatoes, tomatoes, peas, beans, paw-paw and passionfruit.

Low intensity cattle grazing was additionally observed across the lower slopes of some properties during the contamination sampling program undertaken by G&S.

The NSW EPA considers all of the above listed uses to be potentially contaminating activities. Properties characterised by these uses generally require further assessment as part of the approval process prior to development application approval. A detailed soil contamination assessment was conducted for all site properties, with the exception of Lot 227 DP 755740 (Bolster). Lot 227 was not characterised by any of the above listed potentially contaminating activities.

3. Historical use of chemicals

As with all areas in the region, there appears to have been many chemicals applied to agricultural land within the site catchment. Given the nature and extensive period of use of these chemicals (approximately 60 to 80 years), it is possible that trace amounts of these chemicals may be present within the site soils. Some of these chemicals are known to persist in the environment whilst others leave little or no residues within the soil.

The likelihood of high residual contamination in the cultivated areas is relatively low given that the majority of the modern agricultural chemicals are not persistent in the environment. Additionally, the use of the more persistent chemicals has been restricted or prohibited from use since the mid 1980's. However, chemicals may have been applied at higher concentrations than recommended and the method of application may have varied from the manufacturers specifications. Contaminated "hot spots" may have resulted from spillage of chemicals within storage and mixing areas.

Brief descriptions of chemical residues most commonly used on agricultural lands, in accordance with Baird¹, are listed below:

Organochlorine pesticides (OC's)

- were first introduced in agriculture during the Second World War,
- have been used extensively in NSW i.e. small cropping and banana plantations,
- are stable against decomposition or degradation in the environment,
- have very low solubility in water and have high solubility in hydrocarbon-like environments and;
- have a relatively high toxicity to insects but low toxicity to humans.

Organophosphate pesticides (OP's)

- are generally nonpersistent in the environment,
- generally decompose within days or weeks of application and thus are seldom found in food chains,
- are more acutely toxic to humans than OC's and;
- exposure to OP's is typically percutaneous or by inhalation.

Arsenic (As)

- compounds of arsenic are used in weedicides, termiticides and pesticides,
- is a known carcinogen in humans and;
- was replaced by OC's & OP's in the 1950's and 1960's however is still in limited use today.

¹ Baird, C. 2001. Environmental Chemistry. W. H. Freeman and Company. New York.

Cadmium (Cd)

- is a highly toxic, non-essential element with no known biological function,
- is an impurity in some phosphate fertilizers and;
- is bioavailable in soils.

Copper (Cu)

- is a constituent of many agricultural pesticides and fertilizers,
- is known to cause mucosal irritation of the eyes and;
- may in some instances cause pruritic dermatitis and allergic contact dermatitis in humans.

Lead (Pb)

- is a non-essential element with no known biological function,
- is comparatively less toxic and bioavailable than other heavy metals and;
- was historically applied in agriculture via the compound lead arsenate $Pb_3(AsO_4)_2$.

Mercury (Hg)

- is a non-essential element with no known biological function,
- was used (alkyl-Hg's) to prevent fungal disease in germinating seeds resulting in the addition of large amounts of Hg to soils and;
- is a potent neurotoxin causing serious damage to the central nervous system.

Zinc (Zn)

- is a component and impurity in many agricultural fertilizers and;
- is commonly used as a rodenticide and pesticide.

4. Site description

4.1 Study area

The total assessment area is approximately 166.5 hectares. The property boundaries are generally defined by the Terranora Broadwater to the north, Terranora Road to the south, Fraser Drive to the east and Mahers Lane to the west.

4.2 Geology and soils

Based on observations made during the contamination sampling program, the predominant soil type was Ferrosol. Ferrosol is characteristically red brown with a light to medium silty clay texture. Alluvial and colluvial soils were observed across the lower areas of the site properties.

4.3 Topography and drainage

Site elevation ranges from approximately 0 to 130m AHD. The site is characterized by north facing slopes with grades ranging from level to > 25° (gently to steeply inclined).

4.4 Vegetation

Widespread clearance of native vegetation for the purpose of agricultural cropping is evident across much of the subject land. Small pockets of remnant vegetation can be observed across some of the steeply sloping areas, within gullies and across some of the lower areas of site. Weed infestation is prolific across areas left fallow and uncropped.

5. Subsurface investigation

5.1 Fieldwork

The sampling protocol adopted was based on the requirements specified within the EPA guidelines listed in Section 1.1 of this report. Similarly, the adopted sampling protocol is considered to be acceptable by Tweed Shire Council, which was confirmed by Tweed Shire Council staff² during briefings prior to the commencement of the field investigations.

The sampling was conducted across the subject lots by experienced environmental scientists from the Gilbert & Sutherland Robina office. All soil samples were collected from 0.0 – 0.15m depth near surface level (NSL) using a 60mm diameter push-tube sampler. The sampler was washed thoroughly using diluted Extran MA03 cleaner and re-rinsed in water prior to use. Upon recovery, all samples were stored in an ice-filled insulated container and placed out of direct sunlight. Approximately sixteen (16) samples were recovered for every one (1) hectare of property in accordance with the NSW EPA guidelines (refer Section 1.1).

The samples were composited prior to being sent for laboratory analysis. Equal masses of four (4) samples were combined to form a one (1) composite sample. Blind replicate and split samples were prepared for a number of samples for the purpose of quality assurance.

5.2 Laboratory analysis

The majority of composite samples were analysed by ALS for organochlorine and organophosphate pesticides, arsenic, cadmium, copper, lead, mercury and zinc. Where banana growing was determined to be the predominant former agricultural land use, organochlorine and organophosphate pesticides, arsenic, and lead were analysed. ALS is located at 32 Shand Street, Stafford, Brisbane, Queensland and is a National Association of Testing Authorities, Australia (NATA) registered laboratory.

² Brad Pearce, Mark Tunks.

6. Results

6.1 Soil investigation levels

The NEPM Level A Health Investigation Levels (HIL's) for frequently occurring substances are shown in Table 6.1.1 below. Consideration must be given to the future use of areas within the subject properties where the concentration/s of substances are found to exceed one or more of the HIL's described below.

Table 6.1.1 The NEPM HIL's for frequently occurring substances (mg/kg).

Analyte	Background ranges	HIL's	HIL's adjusted for composite sampling
Metals/Metalloids			
Arsenic	1 - 50	100	25
Cadmium	1	20	5
Copper	2 - 100	1000	250
Lead	1 - 200	300	75
Mercury (inorganic)	0.03	15	3.75
Zinc	10 - 300	7000	1750
Organics			
Aldrin + Dieldrin (A+D)	-	10	2.5
Chlordane	-	50	12.5
DDT + DDD + DDE	-	200	50

Summaries of the laboratory results for all properties investigated are shown in the sections below and the laboratory certificates are attached in Appendix B. Results exceeding the HIL's are shown in bold type. This summary does not discuss the ALS results for detectable substances where HIL's were nonexistent (i.e. endosulfan).

6.2 Results for Lot 2 DP 785420 (Cartwright)

A summary of the analytical results for Lot 2 DP 785420 are shown in Table 6.2.1 below. The sample locations are shown on Drawing Number GJ0128.1.2.

Table 6.2.1. Summary of analytical results for Lot 2 DP 785420 (mg/kg).

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin + Dieldrin	Chlordane	DDT+ DDD+ DDE
C1 (S1,S2,S3,S4)	23	<1	20	8	116	0.1	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	34	<1	22	8	113	0.1	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	32	<1	19	8	97	0.1	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	19	<1	22	7	116	0.1	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	8	<1	16	7	120	0.1	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	17	<1	18	8	87	0.1	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	5	<1	16	6	88	0.1	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	6	<1	20	8	102	0.2	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	20	<1	17	9	83	0.1	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	6	<1	26	7	118	0.1	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	3	<1	20	8	109	0.1	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	28	<1	23	9	142	0.1	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	40	<1	34	9	149	0.2	<0.1	<0.1	<0.3



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 780919 Fax 55789945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCALING.

APPROVED

.....

SCALE AS SHOWN
DATE 30/09/03

DRAWN C.M.A.
CHECKED

DRAWING No.
GJ0128.1.2

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin + Dieldrin	Chlordane	DDT+ DDD+ DDE
C14 (S53,S54,S55,S56)	27	<1	25	11	206	0.1	<0.1	<0.1	<0.3
Mean	19	<1	21	8	118	0.1	<0.1	<0.1	<0.3

Five (5) of the fourteen (14) composite samples (C2, C3, C12, C13 & C14) analysed exceeded the adjusted HIL of 25mg/kg for arsenic. The arsenic concentration of these composite samples was 34, 32, 28, 40 & 27 mg/kg respectively. The concentrations of lead, cadmium, copper, zinc, mercury and organochlorine compounds were below the adjusted HIL's within all fourteen (14) of the composite samples analysed.

The twenty (20) samples used to form composite samples C2, C3, C12, C13 & C14 were analysed for arsenic concentration. The analytical results for these samples are shown in Table 6.2.2 below.

Table 6.2.2. Arsenic results (mg/kg).

Sample no.	Arsenic	
	ALS Brisbane	ALS Newcastle
S5	37	32
S6	38	38
S7	34	32
S8	31	26
S9	29	24
S10	34	35
S11	39	32
S12	36	38
S45	3	4
S46	51	57
S47	61	69
S48	21	25
S49	18	19
S50	23	21
S51	24	33
S52	71	72
S53	41	44
S54	40	37
S55	13	18
S56	15	14
Mean	32.95	33.5

The concentration of arsenic was below the HIL of 100 mg/kg for all twenty (20) samples submitted to ALS Brisbane. To provide a check on the analytical proficiency of the Brisbane laboratory, twenty split samples representative of the samples analysed by ALS Brisbane, were forwarded to ALS Newcastle for analysis of arsenic. Similarly, the concentration of arsenic was below the HIL of 100 mg/kg for all twenty of the split samples analysed by ALS Newcastle.

Inferential testing was conducted to compare the results obtained by ALS Brisbane with those of ALS Newcastle across the distribution of results. A paired samples t-test confirmed that there was no significant difference ($P = 0.964$) between the distribution of results between the two laboratories, which demonstrates a satisfactory proficiency of the Brisbane laboratory.

6.3 Results for Lot 376 DP 755740 (Greber)

A summary of the analytical results for Lot 376 DP 755740 are shown in Table 6.3.1 below. The sample locations are shown on Drawing Number GJ0128.1.3.

Table 6.3.1. Summary of analytical results for Lot 376 DP 755740 (mg/kg).

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	7	<1	62	6	70	<0.1	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	6	<1	36	6	53	<0.1	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	7	<1	54	5	67	<0.1	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	9	<1	31	6	60	0.1	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	22	<1	62	7	72	0.1	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	14	<1	32	6	72	0.1	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	12	<1	35	10	88	0.1	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	14	<1	33	4	73	0.1	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	12	<1	47	8	92	0.1	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	19	<1	52	6	92	0.1	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	12	<1	40	7	86	0.1	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	18	<1	40	7	88	0.2	<0.1	<0.1	<0.3
Mean	13	<1	44	6	76	<0.1	<0.1	<0.1	<0.3

The concentrations of arsenic, cadmium, copper, lead, zinc, mercury and organochlorine compounds within all twelve (12) of the composite samples analysed, complied with the adjusted HIL's for each analyte.


6.4 Results for Lot 377 DP 755740 (Greber)

A summary of the analytical results for Lot 377 DP 755740 are shown in Table 6.4.1 below. The sample locations are shown on Drawing Number GJ0128.1.4.

Table 6.4.1. Summary of analytical results for Lot 377 DP 755740 (mg/kg).

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin+ Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	5	<1	28	24	108	0.1	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	2	<1	34	7	75	0.1	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	4	<1	25	14	89	<0.1	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	3	<1	41	8	80	0.1	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	2	<1	29	8	76	0.1	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	4	<1	40	8	92	0.1	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	<1	<1	33	7	72	0.1	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	4	<1	32	7	75	<0.1	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	1	<1	54	8	79	0.1	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	4	<1	53	8	76	0.1	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	7	<1	47	8	69	0.1	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	4	<1	45	7	77	0.1	<0.1	<0.1	<0.3
Mean	<3	<1	38	10	81	<0.1	<0.1	<0.1	<0.3

The concentrations of arsenic, cadmium, copper, lead, zinc, mercury and organochlorine compounds within all twelve (12) of the composite samples analysed, complied with the adjusted HIL's for each analyte.



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 760919 Fax 55789945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCALING.

APPROVED

SCALE AS SHOWN


DRAWN C.M.A.

DRAWING No.

GJ0128.1.3

CHECKED

DATE 30/09/03



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 760919 Fax 55789945

PROJECT

METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCALING.

APPROVED

SCALE AS SHOWN

DRAWN C.M.A.

DRAWING No.

CHECKED

DATE 30/09/03

GJ0128.1.4

6.5 Results for Lot 1 DP 962558 (Greben)

A summary of the analytical results for Lot 1 DP 962558 are shown in Table 6.5.1 below. The sample locations are shown on Drawing Number GJ0128.1.5.

Table 6.5.1. Summary of analytical results for Lot 1 DP 962558 (mg/kg).

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin+ Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	6	<1	30	11	108	0.2	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	4	<1	31	6	67	0.1	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	5	<1	31	10	65	0.1	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	3	<1	48	7	57	<0.1	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	5	<1	31	9	62	<0.1	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	4	<1	44	8	83	0.1	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	29	<1	18	6	72	0.1	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	34	<1	19	8	110	0.1	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	30	<1	20	8	109	0.1	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	2	<1	64	7	66	0.1	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	7	<1	14	13	45	0.1	<0.1	<0.1	<0.3
Mean	12	<1	32	8	77	<0.1	<0.1	<0.1	<0.3


Three (3) of the eleven (11) composite samples (C7, C8, & C9) analysed exceeded the adjusted HIL of 25mg/kg for arsenic. The arsenic concentration of these samples was 29, 34, & 30 mg/kg respectively. The concentrations of lead, cadmium, copper, zinc, mercury and organochlorine compounds were below the adjusted HIL's within all eleven (11) of the composite samples analysed.

The eight (8) samples used to form composite samples C7 & C8 were subsequently analysed for arsenic concentration. The analytical results for these samples are shown in Table 6.5.2 below. No analyses were undertaken on samples S33 to S36 representing composite sample C9, due to these samples being misplaced by the laboratory.

Table 6.5.2. Arsenic results (mg/kg).

Sample no.	Arsenic	
	ALS Brisbane	ALS Newcastle
S25	27	23
S26	48	46
S27	56	60
S28	10	12
S29	37	39
S30	49	49
S31	19	18
S32	39	38
Mean	35.63	35.63

The concentration of arsenic was below the HIL of 100 mg/kg for all eight (8) samples submitted to ALS Brisbane. To provide a check on the analytical proficiency of the Brisbane laboratory, eight split samples representative of the samples analysed by ALS Brisbane, were forwarded to ALS Newcastle for analysis of arsenic. Similarly, the concentration of arsenic was below the HIL of 100 mg/kg for all eight of the split samples analysed by ALS Newcastle.



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 760919 Fax 55789945

PROJECT

METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCALING.

APPROVED

SCALE AS SHOWN

DRAWN C.M.A.

DRAWING No.

1/635024

DATE 30/09/03

CHECKED

GJ0128.1.5



Inferential testing was conducted to compare the results obtained by ALS Brisbane with those of ALS Newcastle across the distribution of results. A paired samples t-test confirmed that there was no significant difference ($P=1.0$) between the distribution of results between the two laboratories, which demonstrates a satisfactory proficiency of the Brisbane laboratory.


6.6 Results for Lot 1 DP 225183 (Greben)

A summary of the analytical results for Lot 1 DP 225183 are shown in Table 6.6.1 below. The sample locations are shown on Drawing Number GJ0128.1.6.

Table 6.6.1. Summary of analytical results for Lot 1 DP 225183 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin+ Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	8	7	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	7	7	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	12	6	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	11	8	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	9	7	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	9	7	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	18	7	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	21	8	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	11	7	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	18	8	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	25	8	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	12	7	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	8	7	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	7	7	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	10	6	<0.1	<0.1	<0.3
C16 (S61,S62,S63,S64)	8	7	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	6	5	<0.1	<0.1	<0.3
C18 (S69,S70,S71,S72)	8	9	<0.1	<0.1	<0.3
C19 (S73,S74,S75,S76)	10	9	<0.1	<0.1	<0.3
C20 (S77,S78,S79,S80)	11	6	<0.1	<0.1	<0.3
C21 (S81,S82,S83,S84)	8	7	<0.1	<0.1	<0.3
C22 (S85,S86,S87,S88)	4	4	<0.1	<0.1	<0.3
C23 (S89,S90,S91,S92)	7	7	<0.1	<0.1	<0.3
C24 (S93,S94,S95,S96)	5	7	<0.1	<0.1	<0.3
C25 (S97,S98,S99,S100)	8	7	<0.1	<0.1	<0.3
C26 (S101,S102,S103,S104)	11	27	<0.1	<0.1	<0.3
C27 (S105,S106,S107,S108)	6	8	<0.1	<0.1	<0.3
C28 (S109,S110,S111,S112)	10	8	<0.1	<0.1	<0.3
C29 (S113,S114,S115,S116)	7	6	<0.1	<0.1	<0.3
C30 (S117,S118,S119,S120)	7	9	<0.1	<0.1	<0.3
C31 (S121,S122,S123,S124)	6	7	<0.1	<0.1	<0.3
C32 (S125,S126,S127,S128)	6	7	<0.1	<0.1	<0.3
C33 (S129,S130,S131,S132)	13	7	<0.1	<0.1	<0.3
C34 (S133,S134,S135,S136)	7	7	<0.1	<0.1	<0.3
C35 (S137,S138,S139,S140)	17	9	<0.1	<0.1	<0.3
C36 (S141,S142,S143,S144)	7	6	<0.1	<0.1	<0.3
Mean	10	8	<0.1	<0.1	<0.3

One (1) of the thirty-six (36) composite samples (C11) analysed exhibited an arsenic concentration of 25mg/kg, being equivalent to the adjusted HIL for arsenic. The concentrations of lead and organochlorine compounds were below the adjusted HIL's within all thirty-six (36) of the composite samples analysed.



Gilbert & Sutherland
Specialist Soil and Water Scientists

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 557 89944 Mobile 0418 760919 Fax 557 89945

FIGURED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCALING.

APPROVED

PROJECT

METRICON

'AREA E' TERRANORA

SOIL CONTAMINATION ASSESSMENT

SCALE AS SHOWN

DRAWN C.A.B.

DRAWING No.

DATE 29/09/03

CHECKED

GJ0128.1.6

The four (4) samples used to form composite sample C11 were subsequently analysed for arsenic concentration. The analytical results for these samples are shown in Table 6.6.2 below.

Table 6.6.2. Arsenic results (mg/kg).

Sample no.	Arsenic	
	ALS Brisbane	ALS Newcastle
S41	16	16
S42	20	18
S43	20	15
S44	3	3
Mean	15	13

The concentration of arsenic was below the HIL of 100 mg/kg for all four (4) samples submitted to ALS Brisbane. To provide a check on the analytical proficiency of the Brisbane laboratory, four split samples representative of the samples analysed by ALS Brisbane, were forwarded to ALS Newcastle for analysis of arsenic. Similarly, the concentration of arsenic was below the HIL of 100 mg/kg for all four of the split samples analysed by ALS Newcastle.

Due to the low sample number (n=4) and hence a low statistical power, no inferential testing was conducted. However, the arsenic results obtained by both ALS Brisbane and ALS Newcastle appear to be similar, indicating a satisfactory proficiency of the Brisbane laboratory.

Additionally, one (1) sample was recovered from within the vicinity of a shed used possibly for the storage and mixing of agricultural chemicals. The results are shown in Table 6.6.2 below.

Table 6.6.2. Summary of analytical results for a sample recovered from within the vicinity of a shed located on Lot 1 DP 225183 (mg/kg).

Sample no.	Arsenic	Lead	Aldrin+ Dieldrin	Chlordane	DDT + DDD + DDE
S145 (Shed)	7	8	<0.1	<0.1	<0.3

The concentrations of arsenic, lead and organochlorine compounds were below the HIL's (100, 300, 10, 50 & 200 mg/kg respectively) within the recovered sample S145.

6.7 Results for Lot 4 DP 582842 (James)

6.7.1 (Site A)

A summary of the analytical results for Lot 4 (Site A) DP 582842 are shown in Table 6.7.1 on the following page. The sample locations are shown on Drawing Number GJ0128.1.7.





Gilbert & Sutherland
Specialist Soil and Water Scientists

12, Rivervale One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 760919 Fax 55789945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

SCALE AS SHOWN	DRAWN C.A.B.	DRAWING No.
DATE 29/09/08	CHECKED	GJ0128.1.7

APPROVED

FIGURED DIMENSIONS TO BE USED IN ALL CASES TO SCALE



Table 6.7.1. Summary of analytical results for Lot 4 (Site A) DP 582842 (mg/kg).

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	3	<1	14	6	72	0.1	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	3	<1	13	5	69	<0.1	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	2	<1	18	6	67	0.1	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	4	<1	14	5	53	<0.1	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	4	<1	14	7	65	0.1	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	6	<1	21	10	88	0.1	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	7	<1	27	11	174	0.2	<0.1	<0.1	<0.33
C8 (S29,S30,S31,S32)	4	<1	20	9	79	0.2	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	6	<1	16	6	76	0.2	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	8	<1	16	6	80	0.2	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	8	<1	16	6	72	0.2	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	6	<1	13	5	65	0.2	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	7	<1	14	6	69	0.2	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	5	<1	13	5	58	0.2	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	6	<1	15	6	75	0.2	<0.1	<0.1	<0.3
C16 (S61,S62,S63,S64)	5	<1	13	6	63	0.2	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	4	<1	12	7	69	0.2	<0.1	<0.1	<0.3
Mean	5	<1	16	7	76	<0.16	<0.1	<0.1	<0.30

The concentrations of arsenic, cadmium, copper, lead, zinc, mercury and organochlorine compounds were below the adjusted HIL's within all seventeen (17) of the composite samples analysed.

6.7.2 (Site B)

A summary of the analytical results for Lot 4 (Site B) DP 582842 are shown in Table 6.7.2.1 below. The sample locations are shown on Drawing Number GJ0128.1.7.A.

Table 6.7.2.1. Summary of analytical results for Lot 4 (Site B) DP 582842 (mg/kg).

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	4	<1	62	8	60	0.1	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	9	<1	61	7	64	0.1	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	8	<1	66	7	62	0.1	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	8	<1	64	6	62	0.1	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	7	<1	50	6	61	0.2	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	9	<1	64	6	59	0.1	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	7	<1	54	7	61	0.2	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	10	<1	69	7	62	0.1	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	7	<1	52	8	72	0.2	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	4	<1	62	8	62	0.1	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	3	<1	48	7	63	0.2	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	3	<1	56	7	53	0.1	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	4	<1	58	8	61	0.1	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	31	<1	50	7	59	0.2	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	31	<1	51	8	57	0.2	<0.1	<0.1	<0.3
C16 (S61,S62,S63,S64)	2	<1	65	8	52	0.1	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	3	<1	65	8	60	0.1	<0.1	<0.1	<0.3



Gilbert & Sutherland
Specialist Soil and Water Scientists

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4228
Phone 557 88944 Mobile 0418 760919 Fax 557 88945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

APPROVED		SCALE AS SHOWN	DRAWN C.A.B.	DRAWING No.
FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING.		DATE 27.10.08	CHECKED	GJ0128.1.7A



Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C18 (S69,S70,S71,S72)	3	<1	59	9	55	0.1	<0.1	<0.1	<0.3
C19 (S73,S74,S75,S76)	5	<1	65	9	55	0.2	<0.1	<0.1	<0.3
C20 (S77,S78,S79,S80)	10	<1	46	7	217	0.1	<0.1	<0.1	<0.3
C21 (S81,S82,S83,S84)	4	<1	53	9	52	0.1	<0.1	<0.1	<0.3
C22 (S85,S86,S87,S88)	6	<1	5	11	66	0.2	<0.1	<0.1	<0.3
C23 (S89,S90,S91,S92)	1	<1	47	8	58	0.1	<0.1	<0.1	<0.3
C24 (S93,S94,S95,S96)	2	<1	57	7	48	0.2	<0.1	<0.1	<0.3
Mean	7.5	<1	55	8	66	0.14	<0.1	<0.1	<0.3

Two (2) of the twenty-four (24) composite samples (C14 & C15) analysed exceeded the adjusted HIL of 25mg/kg for arsenic. The arsenic concentration of these samples was 31mg/kg for both samples. The concentrations of lead, cadmium, copper, zinc, mercury and organochlorine compounds were below the adjusted HIL's within all twenty-four (24) of the composite samples analysed.

The eight (8) samples used to form composite samples C14 & C15 were subsequently analysed for arsenic concentration. The analytical results for these samples are shown in Table 6.7.2.2 below.

Table 6.7.2.2. Arsenic results (mg/kg).

Sample no.	Arsenic
S53	27
S54	44
S55	16
S56	8
S57	43
S58	54
S59	12
S60	15
Mean	17


The concentration of arsenic was below the HIL of 100 mg/kg for all eight (8) samples submitted to ALS.

6.8 Results for Lot 1 DP 215959 (Nichols)

A summary of the analytical results for Lot 1 DP 215959 are shown in Table 6.8.1 below. The sample locations are shown on Drawing Number GJ0128.1.8.

Table 6.8.1. Summary of analytical results for Lot 1 DP 215959 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	2	12	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	<1	8	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	2	7	<0.1	<0.1	<0.31
C4 (S13,S14,S15,S16)	5	6	<0.1	<0.1	<0.36
C5 (S17,S18,S19,S20)	<1	6	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	4	6	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	2	6	<0.1	<0.1	<0.33
C8 (S29,S30,S31,S32)	<1	7	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	<1	6	<0.1	<0.1	<0.3



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 760919 Fax 55789945

PROJECT

METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING.	APPROVED	SCALE AS SHOWN	DRAWN CMA	DRAWING No.
		DATE 01.10.03	CHECKED	GJ0128.1.8



Composite sample no.	Arsenic	Lead	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C10 (S37,S38,S39,S40)	3	8	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	<1	6	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	<1	6	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	<1	7	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	2	6	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	<1	7	<0.1	<0.1	<0.3
C16 (S61,S62,S63,S64)	7	6	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	<1	7	<0.1	<0.1	<0.3
Mean	<2	7	<0.1	<0.1	<0.31

The concentrations of arsenic, lead and organochlorine compounds were below the adjusted HIL's within all seventeen (17) of the composite samples analysed.

Additionally, four (4) samples were recovered from within the vicinity of a shed used possibly for the storage and mixing of agricultural chemicals. The results are shown in Table 6.8.2 below.

Table 6.8.2. Summary of analytical results for samples recovered from within the vicinity of a shed located on Lot 1 DP 215959 (mg/kg).

Sample no.	Arsenic	Lead	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
#A Shed	4	58	<0.1	<0.1	<3.56
#B Shed	2	9	<0.1	<0.1	<0.3
#C Shed	6	11	<0.1	<0.1	<0.35
#D Shed	4	18	<0.1	<0.1	<0.49
Mean	4	24	<0.1	<0.1	<4.70


The concentrations of arsenic, lead and organochlorine compounds were below the HIL's (100, 300, 10, 50 & 200 mg/kg respectively) within all four (4) of the samples analysed.

6.9 Results for Lot 2 DP 215959 (Nichols)

A summary of the analytical results for Lot 2 DP 215959 are shown in Table 6.9.1 below. The sample locations are shown on Drawing Number GJ0128.1.9.

Table 6.9.1. Summary of analytical results for Lot 2 DP 215959 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	2	7	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	<1	7	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	1	7	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	2	8	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	<1	8	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	4	18	<0.1	<0.1	<0.31
Mean	<2	9	<0.1	<0.1	<0.30



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Rivervale One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 760919 Fax 55789945

PROJECT

METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO
BE USED IN PREFERENCE
TO SCALING.

APPROVED

SCALE AS SHOWN

DRAWN C.A.B.

DRAWING No.

CHECKED

DATE 29/09/03

GJ0128.1.9

The concentrations of arsenic, lead and organochlorine compounds were below the adjusted HIL's within all six (6) of the composite samples analysed.

6.10 Results for Lot 12 DP 534942 (Nichols)


A summary of the analytical results for Lot 12 DP 534942 are shown in Table 6.10.1 below. The sample locations are shown on Drawing Number GJ0128.1.10.

Table 6.10.1. Summary of analytical results for Lot 12 DP 534942 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin+ Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	<1	6	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	1	7	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	1	8	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	<1	7	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	<1	6	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	<1	8	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	4	6	<0.1	<0.1	<0.32
C8 (S29,S30,S31,S32)	<1	7	<0.1	<0.1	0.71
C9 (S33,S34,S35,S36)	2	11	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	2	7	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	3	8	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	3	10	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	8	8	<0.1	<0.1	<0.32
C14 (S53,S54,S55,S56)	2	6	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	8	9	<0.1	<0.1	<0.3
C16 (S61,S62,S63,S64)	3	7	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	3	8	<0.1	<0.1	<0.3
C18 (S69,S70,S71,S72)	1	8	<0.1	<0.1	<0.3
C19 (S73,S74,S75,S76)	2	8	<0.1	<0.1	<0.3
C20 (S77,S78,S79,S80)	4	8	<0.1	<0.1	<0.3
C21 (S81,S82,S83,S84)	5	9	<0.1	<0.1	<0.3
C22 (S85,S86,S87,S88)	5	14	<0.1	<0.1	<0.3
C23 (S89,S90,S91,S92)	8	7	<0.1	<0.1	<0.3
C24 (S93,S94,S95,S96)	8	10	<0.1	<0.1	<0.3
C25 (S97,S98,S99,S100)	4	7	<0.1	<0.1	<0.3
C26 (S101,S102,S103,S104)	2	7	<0.1	<0.1	<0.3
C27 (S105,S106,S107,S108)	8	9	<0.1	<0.1	<0.32
C28 (S109,S110,S112,S113)	53	6	<0.1	<0.1	<0.3
C29 (S115,S116,S117,S118)	<1	6	<0.1	<0.1	<0.3
C30 (S119,S120,S121,S122)	9	13	<0.1	<0.1	<0.3
C31 (S123,S124,S125,S126)	7	8	<0.1	<0.1	<0.3
C32 (S127,S128,S129,S130)	8	8	<0.1	<0.1	<0.31
C33 (S131,S132,S133,S134)	6	8	<0.1	<0.1	<0.3
Mean	<6	8	<0.1	<0.1	<0.31

One (1) of the thirty-three (33) composite samples, (C28) exceeded the adjusted HIL of 25mg/kg for arsenic. The arsenic concentration of this sample was 53 mg/kg. The concentrations of lead and organochlorine compounds were below the adjusted HIL's within all thirty-three (33) of the composite samples analysed.

The four (4) samples used to form composite sample C28 were subsequently analysed for arsenic. Additionally, samples S111 and S114 were analysed to further determine the extent of contamination within this area of the subject property. The analytical results for these samples are shown in Table 6.10.2 on the following page.



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Rivervale One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 780919 Fax 55789945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

SCALE AS SHOWN	DRAWN C.A.B.	DRAWING No.
DATE 29/09/03	CHECKED	GJ0128.1.10

APPROVED
REVIEWED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCALING.

Table 6.10.2. Arsenic results (mg/kg).

Sample no.	Arsenic	
	ALS Brisbane	ALS Newcastle
S109	9	10
S110	81	93
S111	27	28
S112	5	4
S113	6	5
S114	51	56
Mean	29.83	32.67

The concentration of arsenic was below the HIL of 100 mg/kg for all six (6) samples submitted to ALS Brisbane. To provide a check on the analytical proficiency of the Brisbane laboratory, six split samples representative of the samples analysed by ALS Brisbane, were forwarded to ALS Newcastle for analysis of arsenic. Similarly, the concentration of arsenic was below the HIL of 100 mg/kg for all six of the split samples analysed by ALS Newcastle.

Due to the low sample number (n=6) and hence a low statistical power, no inferential testing was conducted. However, the arsenic results obtained by both ALS Brisbane and ALS Newcastle appear to be similar, indicating a satisfactory proficiency of the Brisbane laboratory.

6.11 Results for Lot 1 DP 723050 (Nichols)

A summary of the analytical results for Lot 1 DP 723050 are shown in Table 6.11.1 below. The sample locations are shown on Drawing Number GJ0128.1.11.

Table 6.11.1. Summary of analytical results for Lot 1 DP 723050 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	1	7	<0.1	<0.1	<0.3

The concentrations of arsenic, lead and organochlorine compounds were below the adjusted HIL's within the composite sample analysed.

6.12 Results for Lot 1 DP 984118 (Nichols)

A summary of the analytical results for Lot 1 DP 984118 are shown in Table 6.12.1 below. The sample locations are shown on Drawing Number GJ0128.1.12.

Table 6.12.1. Summary of analytical results for Lot 1 DP 984118 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	<1	8	<0.1	<0.1	<0.31
C2 (S5,S6,S7,S8)	<1	7	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	4	8	<0.1	<0.1	<0.34





Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 780919 Fax 55789945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

SCALE AS SHOWN	DRAWN C.A.B.	DRAWING No.
DATE 29/09/03	CHECKED	GJ0128.1.11

APPROVED

FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING.

83/804148

1/215959

12/534942

11/534942

1/220271

4/582842

1/984118

2/1018747

7/740104

2/622318

622318

216360

10/252299

S1

S2

S3

S4


0

7

Scale of metres

0 10 20 30 40 50 60 70 80 90 100

North Arrow



Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789944 Mobile 0418 760919 Fax 55789945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO
BE READ IN PREFERENCE
TO SCAILING.

APPROVED

SCALE AS SHOWN

DRAWN C.A.B.

CHECKED

DRAWING No.
GJ0128.1.12



Composite sample no.	Arsenic	Lead	Aldrin + Dieldrin	Chlordane	DDT + DDD + DDE
C4 (S13,S14,S15,S16)	4	5	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	1	7	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	1	7	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	3	8	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	4	11	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	3	7	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	6	6	<0.1	<0.1	<0.3
Mean	3	7	<0.1	<0.1	<0.31


The concentrations of arsenic, lead and organochlorine compounds were below the adjusted HIL's within all ten (10) of the composite samples analysed.

6.13 Results for Lot 2 DP 778727 & Lot 3 DP 587869 (Abernathy)

A summary of the analytical results for Lot 2 DP 778727 & Lot 3 DP 587869 are shown in Table 6.13.1 below. The sample locations are shown on Drawing Number GJ0128.1.13.

Table 6.13.1. Summary of analytical results for Lot 2 DP 778727 & Lot 3 DP 587869 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin+ Dieldrin	Chlordane	DDT + DDD + DDE
C1 (S1,S2,S3,S4)	2	14	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	<1	8	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	<1	6	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	<1	5	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	<1	5	<0.1	<0.1	<0.31
C6 (S21,S22,S23,S24)	1	6	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	2	19	<0.1	<0.1	<0.32
C8 (S29,S30,S31,S32)	<1	5	<0.1	<0.1	<0.32
C9 (S33,S34,S35,S36)	4	7	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	3	7	<0.15	<0.1	<0.37
C11 (S41,S42,S43,S44)	3	6	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	2	7	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	1	9	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	1	7	<0.1	<0.1	<0.33
C15 (S57,S58,S59,S60)	<1	7	<0.1	<0.1	<0.3
C16 (S61,S62,S63,S64)	<1	11	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	2	7	<0.1	<0.1	<0.31
C18 (S69,S70,S71,S72)	<1	7	<0.1	<0.1	<0.3
C19 (S73,S74,S75,S76)	<1	10	<0.1	<0.1	<0.3
C20 (S77,S78,S79,S80)	<1	6	<0.1	<0.1	<0.3
C21 (S81,S82,S83,S84)	<1	8	<0.1	<0.1	<0.3
C22 (S85,S86,S87,S88)	1	10	<0.1	<0.1	<0.3
C23 (S89,S90,S91,S92)	<1	6	<0.1	<0.1	<0.3
C24 (S93,S94,S95,S96)	1	8	<0.1	<0.1	<0.34
C25 (S97,S98,S99,S100)	<1	11	<0.1	<0.1	<0.33
C26 (S101,S102,S103,S104)	2	8	<0.1	<0.1	<0.37
C27 (S105,S106,S107,S108)	<1	7	<0.1	<0.1	<0.3
C28 (S109,S110,S111,S112)	<1	6	<0.1	<0.1	<0.3
C29 (S113,S114,S115,S116)	<1	7	<0.1	<0.1	<0.3
C30 (S117,S118,S119,S120)	1	20	<0.1	<0.1	<0.3
C31 (S121,S122,S123,S124)	2	6	<0.1	<0.1	<0.3
C32 (S125,S126,S127,S128)	<1	6	<0.1	<0.1	<0.3
Mean	<1	8	<0.1	<0.1	<0.31



Gilbert & Sutherland
Specialist Soil and Water Scientists

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55789644 Mobile 0418 760919 Fax 55789645

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING.	APPROVED	DRAWING No.			
		SCALE AS SHOWN	DRAWN C.M.A.	CHECKED	GJ0128.1.13
		DATE 30.09.03			



The concentrations of arsenic, lead, and organochlorine compounds were below the adjusted HIL's within all thirty-two (32) of the composite samples analysed.

6.14 Results for Lot 1 DP 781697, Lot 1 DP 169490 & Lot 40 DP 254416 (Abermathy)

A summary of the analytical results for Lot 1 DP 781697, Lot 1 DP 169490 & Lot 40 DP 254416 are shown in Table 6.14.1 below. The sample locations are shown on Drawing Number GJ0128.1.14.

Table 6.14.1. Summary of analytical results for Lot 1 DP 781697, Lot 1 DP 169490 & Lot 40 DP 254416 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin+ Dieldrin	Chlordane	DDT+ DDD+ DDE
C1 (S1,S2,S3,S4)	5	8	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	2	4	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	1	6	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	6	8	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	1	5	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	<1	7	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	7	8	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)*	-	-	-	-	-
C9 (S33,S34,S35,S36)	<1	6	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	<1	7	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	<1	5	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	<1	5	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	<1	4	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	<1	4	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	<1	6	<0.1	<0.1	<0.3
Mean	<2	6	<0.1	<0.1	<0.3

*Sample misplaced.

The concentrations of arsenic, lead, and organochlorine compounds were below the adjusted HIL's within all fourteen (14) of the composite samples analysed.

6.15 Results for Lot 1 DP 781687 & Lot 43 DP 254416 (Abermathy)

A summary of the analytical results for Lot 1 DP 781687 & Lot 43 DP 254416 are shown in Table 6.15.1 below. The sample locations are shown on Drawing Number GJ0128.1.15.

Table 6.15.1. Summary of analytical results for Lot 1 DP 781687 & Lot 43 DP 254416 (mg/kg).

Composite sample no.	Arsenic	Lead	Aldrin+ Dieldrin	Chlordane	DDT+ DDD+ DDE
C1 (S1,S2,S3,S4)	<1	5	<0.1	<0.1	<0.33
C2 (S5,S6,S7,S8)	<1	5	<0.34	<0.1	<0.3
C3 (S9,S10,S11,S12)	<1	4	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	<1	5	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	1	6	<0.1	<0.1	<0.31



Composite sample no.	Arsenic	Lead	Aldrin+ Dieldrin	Chlordane	DDT+ DDD+ DDE
C6 (S21,S22,S23,S24)	<1	5	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	<1	8	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	<1	6	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	<1	6	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	<1	7	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	<1	5	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	<1	4	<0.34	<0.1	<0.3
C13 (S49,S50,S51,S52)	<1	6	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	<1	5	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	<1	5	<0.14	<0.1	<0.3
C16 (S61,S62,S63,S64)	<1	7	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	<1	6	<0.1	<0.1	<0.3
C18 (S69,S70,S71,S72)	<1	5	<0.21	<0.1	<0.3
Mean	<1	6	<0.13	<0.1	<0.30


The concentrations of arsenic, lead, and organochlorine compounds were below the adjusted HIL's within all eighteen (18) of the composite samples analysed.

6.16 Results for Lot 1 DP 175235 (Abermathy)

A summary of the analytical results for Lot 1 DP 175235 are shown in Table 6.16.1 below. The sample locations are shown on Drawing Number GJ0128.1.16.

Table 6.16.1. Summary of analytical results for Lot 1 DP 175235 (mg/kg).

Composite sample no.	Arsenic	Cadmium	Copper	Lead	Zinc	Mercury	Aldrin+ Dieldrin	Chlordane	DDT+ DDD+ DDE
C1 (S1,S2,S3,S4)	2	<1	227	17	93	0.1	<0.1	<0.1	<0.3
C2 (S5,S6,S7,S8)	<1	<1	112	14	90	0.1	<0.1	<0.1	<0.3
C3 (S9,S10,S11,S12)	4	<1	82	12	85	<0.1	<0.1	<0.1	<0.3
C4 (S13,S14,S15,S16)	3	<1	36	7	82	0.1	<0.1	<0.1	<0.3
C5 (S17,S18,S19,S20)	3	<1	66	8	77	0.1	<0.1	<0.1	<0.3
C6 (S21,S22,S23,S24)	1	<1	105	16	117	0.2	<0.1	<0.1	<0.3
C7 (S25,S26,S27,S28)	5	<1	125	12	106	0.1	<0.1	<0.1	<0.3
C8 (S29,S30,S31,S32)	2	<1	47	8	89	0.1	<0.1	<0.1	<0.3
C9 (S33,S34,S35,S36)	7	<1	110	30	84	0.1	<0.1	<0.1	<0.3
C10 (S37,S38,S39,S40)	2	<1	122	17	118	0.1	<0.1	<0.1	<0.3
C11 (S41,S42,S43,S44)	3	<1	30	7	85	<0.1	<0.1	<0.1	<0.3
C12 (S45,S46,S47,S48)	3	<1	88	8	76	0.1	<0.1	<0.1	<0.3
C13 (S49,S50,S51,S52)	3	<1	63	10	77	0.1	<0.1	<0.1	<0.3
C14 (S53,S54,S55,S56)	2	<1	82	10	73	0.1	<0.1	<0.1	<0.3
C15 (S57,S58,S59,S60)	8	<1	18	8	75	<0.1	<0.1	<0.1	<0.3
C16 (S61,S62,S63,S64)	3	<1	55	14	274	0.1	<0.1	<0.1	<0.3
C17 (S65,S66,S67,S68)	4	<1	61	11	157	0.1	<0.1	<0.1	<0.3
C18 (S69,S70,S71,S72)	2	<1	56	16	101	0.1	<0.1	<0.1	<0.3
C19 (S73,S74,S75,S76)	2	<1	49	7	63	<0.1	<0.1	<0.1	<0.3
C20 (S77,S78,S79,S80)	6	<1	38	7	66	0.1	<0.1	<0.1	<0.3
C21 (S81,S82,S83,S84)	2	<1	66	7	57	<0.1	<0.1	<0.1	<0.3
C22 (S85,S86,S87,S88)	2	<1	25	9	58	<0.1	<0.1	<0.1	<0.3
C23 (S89,S90,S91,S92)	5	<1	32	6	75	<0.1	<0.1	<0.1	<0.3
C24 (S93,S94,S95,S96)	4	<1	92	7	71	<0.1	<0.1	<0.1	<0.3
C25 (S97,S98,S99,S100)	3	<1	54	11	59	<0.1	<0.1	<0.1	<0.3
C26 (S101,S102,S103,S104)	2	<1	18	8	57	<0.1	<0.1	<0.1	<0.3
C27 (S105,S106,S107,S108)	6	<1	17	8	61	0.1	<0.1	<0.1	<0.3
C28 (S109,S110,S112,S113)	2	<1	76	8	65	<0.1	<0.1	<0.1	<0.3
C29 (S115,S116,S117,S118)	2	<1	81	8	57	<0.1	<0.1	<0.1	<0.3





Gilbert & Sutherland
— Specialist Soil and Water Scientists —

12, Riverwalk One
140 Robina Town Centre Drive, Robina, Qld. 4226
Phone 55785944 Mobile 0418 760619 Fax 55789945

PROJECT
METRICON
'AREA E' TERRANORA
SOIL CONTAMINATION ASSESSMENT

SCALE AS SHOWN	DRAWN C.M.A.	DRAWING No.
DATE 30/09/03	CHECKED	GJ0128.1.16

FIGURED DIMENSIONS TO BE READ IN PREFERENCE TO SCALING.

APPROVED

