

Assessor # 20209

Certificate # 11030446

Issued: 18-Jun-10

Thermal Performance Specifications

These are the Specifications upon which the Certified Assessment is based. If details included in these Specifications vary from other drawings or written specifications, these Specifications shall take precedence. If only one specification option is detailed for a building element, that specification must apply to all instances of that element for the project. If alternate specifications are detailed for a building element, the location and extent of alternate specifications must be detailed below and / or clearly indicated on referenced documents.

Windows	Product ID	Glass	Frame	U value	SHGC	Area M	Detail
Windows/doors		Low E	Aluminium	4.5	0.45		NFRC values

Skylights	Product ID	Glass	Frame	U value	SHGC	Area M	Detail

Any U and SHGC values specified on Certificates Issued after 1 May 2007 are according to NFRC 100. All values prior to this date are ANAC. Alternate products may be used if their U value is lower, and the SHGC value is less than 10% higher or lower.

External walls	Construction	Insulation	Colour - Solar absorptanc	Detail
Concrete + battns + PB		None	Medium - SA 0.475 - 0.7	

Internal walls	Construction	Insulation	Detail
Plasterboard on Studs		None	

Floors	Construction	Insulation	Covering	Detail
Concrete		None	Carpet	

Ceilings	Construction	Insulation	Detail
Plasterboard		Penthouses R2.0	

Roof	Construction	Insulation	Colour	Detail
Concrete		None	Medium - SA 0.475 - 0.7	

Window cover	Internal (curtains)	External (awnings, shutters, etc)
Open Weave		None

Fixed shading	Eaves (width - inc. gutters, height above windows, Verandahs, Pergolas (type, description)
0	0 As per detail on plans

Overshadowing	Overshadowing structures	Overshadowing trees

Orientation, Exposure, Ventilation and Infiltration

Orientation of nominal north: 0 degrees	Living area open to entry: Yes	Ventilated skylights: No
Terrain category Suburban	Living areas separated by doors: No	Open fire or unflued gas heat: No
Roof ventilation: Unventilated	Stair open to heated areas: No	Vented downlights: No
Cross ventilation: Standard	Seals to windows and doors: Yes	Wall and ceiling vents: No
Subfloor ventilation Enclosed	Exhaust fans without dampers: No	

