

# **Hydrogeological Assessment (Douglas Partners 2010)**



**APPENDIX R**





**Douglas Partners**  
*Geotechnics | Environment | Groundwater*

Report on  
Hydrogeological Assessment for  
Rocglen Coal Mine Extension Project

Rocglen Coal Mine  
Via Gunnedah

Prepared for  
Whitehaven Coal Limited

Project 49532.01  
December 2010

Integrated Practical Solutions



## Document History

### Document details

|                     |                                                                              |              |   |
|---------------------|------------------------------------------------------------------------------|--------------|---|
| Project No.         | 49532.01                                                                     | Document No. | 1 |
| Document title      | Report on Hydrogeological Assessment for Rocglen Coal Mine Extension Project |              |   |
| Site address        | Rocglen Coal Mine Via Gunnedah                                               |              |   |
| Report prepared for | Whitehaven Coal Limited                                                      |              |   |
| File name           | P:\49532.01\Docs\49532.01 New.doc                                            |              |   |


### Document status and review

| Revision | Prepared by             | Reviewed by | Date issued      |
|----------|-------------------------|-------------|------------------|
| 0        | Will Wright & Iain Hair | Carl Deegan | 16 December 2010 |
|          |                         |             |                  |
|          |                         |             |                  |
|          |                         |             |                  |

### Distribution of copies

| Revision | Electronic | Paper | Issued to                 |
|----------|------------|-------|---------------------------|
| 0        | 1          | 3     | E Bath, GSS Environmental |
|          |            |       |                           |
|          |            |       |                           |
|          |            |       |                           |

The undersigned, on behalf of Douglas Partners Pty Ltd, confirm that this document and all attached drawings, logs and test results have been checked and reviewed for errors, omissions and inaccuracies.

| Signature                                                                                    | Date       |
|----------------------------------------------------------------------------------------------|------------|
| Author    | 17/12/2010 |
| Reviewer  | 17/12/2010 |

## Table of Contents

|                                                     | Page |
|-----------------------------------------------------|------|
| 1. Introduction.....                                | 1    |
| 2. Site Description .....                           | 1    |
| 2.1 Data Sources .....                              | 1    |
| 2.2 Previous Investigations .....                   | 1    |
| 2.3 Consultations .....                             | 4    |
| 3. Regional Setting .....                           | 4    |
| 3.1 Topography and Drainage.....                    | 4    |
| 3.2 Geology.....                                    | 4    |
| 3.3 Climate .....                                   | 5    |
| 4. Project Description.....                         | 8    |
| 4.1 Existing Approval .....                         | 8    |
| 4.2 Existing Groundwater Licences .....             | 9    |
| 4.3 Current Mine Status.....                        | 10   |
| 4.4 Proposed Expansion.....                         | 13   |
| 4.5 Additional Pit Flow Information.....            | 15   |
| 5. Relevant Groundwater Guidelines / Policies ..... | 16   |
| 6. Local Hydrogeological Regime .....               | 16   |
| 6.1 Identified Aquifers .....                       | 16   |
| 6.2 Aquifer Hydraulic Parameters.....               | 17   |
| 6.3 Groundwater Levels and Flow Directions .....    | 19   |
| 6.4 Groundwater Recharge .....                      | 21   |
| 6.5 Groundwater Quality .....                       | 21   |
| 6.6 Groundwater Utilisation .....                   | 23   |
| 7. Conceptual Hydrogeological Model .....           | 25   |
| 8. Monitored Impact to Date.....                    | 28   |
| 9. Numerical Modelling.....                         | 30   |
| 9.1 Introduction .....                              | 30   |
| 9.2 Steady State Modelling .....                    | 30   |
| 9.2.1 Calibration of Existing Heads.....            | 30   |
| 9.2.2 Sensitivity to Fault Permeability.....        | 37   |

|       |                                       |    |
|-------|---------------------------------------|----|
| 9.3   | Transient Modelling .....             | 43 |
| 9.3.1 | Calibration .....                     | 43 |
| 9.3.2 | Predictive Modelling .....            | 49 |
| 9.4   | Mine Closure .....                    | 60 |
| 10.   | Conclusions and Recommendations ..... | 61 |
| 11.   | References .....                      | 64 |
| 12.   | Limitations .....                     | 65 |

|              |                                                                                                          |  |
|--------------|----------------------------------------------------------------------------------------------------------|--|
| Text Figures | Figure 1 - Mine Plan Year 1                                                                              |  |
|              | Figure 2 - Mine Plan Year 5                                                                              |  |
|              | Figure 3 - Mine Plan End of Mine                                                                         |  |
|              | Figure 4 - Site Terrain and Contours of Groundwater Head (AHD) in July 2008                              |  |
|              | Figure 5 - Distribution of Alluvial Soils and Volcanics                                                  |  |
|              | Figure 6 - Modelled Extent of Coal Seams                                                                 |  |
|              | Figure 7 - Section Showing Folded and Truncated Coal Seam                                                |  |
|              | Figure 8 - Calibrated Steady State Head Distribution in Layer 3<br>(includes coal seams) for Case 1      |  |
|              | Figure 9 - Modelled and Observed Heads for Case 1 Calibration                                            |  |
|              | Figure 10 - Calculated Heads during First Year of Mine Operation – Case 1                                |  |
|              | Figure 11 - Calculated Heads during First Year of Mine Operation – Case 1                                |  |
|              | Figure 12 - Distribution of Permeability for Model Layer 1                                               |  |
|              | Figure 13 - Predicted Drawdowns for Northern Mining Phase - Case 1                                       |  |
|              | Figure 14 - Predicted Distribution of Head in Layer 3 at end of Northern Mining<br>Phase (Case 1)        |  |
|              | Figure 15 - Predicted Drawdowns from for Northern Mining Phase - Case 2                                  |  |
|              | Figure 16 - Predicted Drawdowns for Southern Mining Phase - Case 1                                       |  |
|              | Figure 17 - Predicted Distribution of Head in Layer 3 at Completion of Southern<br>Mining Phase (Case 1) |  |
|              | Figure 18 - Predicted Drawdowns for Southern Mining Phase - Case 2                                       |  |
|              | Figure 19 – Distribution of Head in Layer 3 at Completion of Southern Mining<br>Phase (Case 2)           |  |

|             |                                                                     |
|-------------|---------------------------------------------------------------------|
| Appendix A: | About this Report                                                   |
| Appendix B: | Hydrographs of Groundwater Levels for Rocglen Mine Monitoring Bores |
| Appendix C: | Groundwater Quality and ANZECC (200) Guidelines Values              |
| Appendix D: | Groundwater Works Summary Sheets – Private Bores                    |
| Appendix E: | Drawing 1 – Location of Rocglen Mine                                |
|             | Drawing 2 – Local Topography and Drainage                           |
|             | Drawing 3 – Regional Geology                                        |
|             | Drawing 4 – Structure Contours – Base of Belmont Seam               |
|             | Drawing 5 – Monthly Average Rinfall and Evaporation – Gunnedah Area |
|             | Drawing 6 – Locations of Faults – Rocglen Mine                      |
|             | Drawing 7 – Lithostratigraphy at Rocglen Mine – Bore EVK110         |
|             | Drawing 8 – Local Geology – Alluvium North and South of the Mine    |
|             | Drawing 9 – Pre-mine Groundwater Levels (After RCA, 2007)           |
|             | Drawing 10 – Locations of Groundwater Monitoring Bores              |
|             | Drawing 11 – Locations of Private Groundwater Bores                 |
|             | Drawing 12 – Model Predicted and Monitored Drawdown – Rocglen Pit   |

# **Report on Hydrogeological Assessment for Rocglen Coal Mine Extension Project Rocglen Coal Mine Via Gunnedah**

---

## **1. Introduction**

Whitehaven Coal Limited (WHC) is planning an expansion of the Rocglen Coal Mine, located approximately 25 km north of Gunnedah and 23 km southeast of Boggabri in North West NSW.

GSS Environmental (GSSE) is project managing the compilation of an Environmental Assessment (EA) for the expansion. WHC has commissioned Douglas Partners Pty Ltd (DP) to address hydrogeological (groundwater) components of the EA.

Rocglen Coal Mine has been operating for approximately 18 months and has an existing approval within ML 1620. The location of Rocglen Mine is shown on Drawing 1 in Appendix E.

## **2. Site Description**

### **2.1 Data Sources**

Data utilised in this investigation included:

- Topographic and geological mapping;
- Coal exploration drilling data provided by WHC;
- Information from the NSW Office of Water Groundwater Database;
- Previous investigation reports; and
- Groundwater monitoring data (levels and water quality) provided by WHC.

The above information was supplemented by a site visit / inspection undertaken by DP Principal Mr Will Wright, and discussions held with WHC personnel.

### **2.2 Previous Investigations**

#### ***Coal Exploration Reports 1993 to 1994***

Two coal exploration reports by McElroy Bryan Geological Services Pty Ltd were provided for the study. The reports are summarised as follows:

**1993 Program (MBGS, 1993)**

Two lines of bores were drilled, oriented in an east-west direction and spanning across the Belmont Fault which passes immediately to the east of the mine.

The northern drill line comprised 10 bores over a distance of 440 m, located about 2 km north of the proposed extent of mining. Drilling results indicated between about 10 m and 45 m of colluvium/weathered zone. Several thin coal seams were identified below about 70 m depth on the western parts of the site, with no coal seam on the eastern parts of the site. The basement of the coal measures was identified immediately below the weathered zone on the eastern parts of the site, indicating a substantial upthrust to the east of the Belmont Fault.

The southern line of bores, which passes through the northern end of the proposed extent of mining, comprised 10 bores over a distance of about 350 m and indicated no weathered zone/colluvium on the western parts of the site and between 10 m and 20 m of weathered zone/colluvium on the eastern parts of the proposed mine extent, becoming slightly deeper to the east of the mine. Several coal seams were identified on the western parts of the site below about 40 m to 70 m depth, ranging up to about 20 m in thickness. No coal seams were identified on the eastern side of the Belmont Fault, with the basement of the coal measures immediately below the weathered zone.

Groundwater depths were measured in some of the bores and were in the range 40 m to 53 m, well below the depth of the alluvium. Groundwater inflow rates were measured in the bores and generally ranged from 0.8 L/s to 3.4 L/s. A flow rate of 12 L/s was measured in one bore at a depth of 108 m, however this was in a fault zone.

**1994 Program (MBGS, 1994)**

This report included drilling results for an additional five bores, which were generally consistent with previous results. Comments were also provided regarding the potential for coal resources, including the following:

- The site is located in the eastern portion of the Maules Creek Sub-basin and is truncated to the east by the Mooki Thrust Fault System;
- There are numerous northwest to southeast trending structures parallel to the Mooki Thrust which limit the potential for coal resources, with no potential for coal resources to the east of the Belmont Fault;
- There is an east-west lineament (Driggle Draggie Fault) to the north of the site, with limited coal reserves to the north of this lineament; and
- Coal is moderately to extremely faulted and steeply dipping.

### **Groundwater Assessment 2002**

A groundwater assessment was undertaken by Robert Carr & Associates Pty Ltd in 2002. A draft copy of the report text (RCA, 2002) was made available for this assessment. RCA (2002) provided the following:

- Installation of three piezometers in existing bores; one bore was screened in the Belmont Seam (EVK64), another in the Glenroc Seam (EVK25) and the third in the inter-burden between the seams (EVK64);
- Falling head tests on each bore were undertaken to assess hydraulic parameters, and indicated permeability in the range  $7 \times 10^{-7}$  m/s to  $9 \times 10^{-7}$  m/s in the coal seams and  $1 \times 10^{-8}$  m/s for the inter-burden strata;
- Groundwater depths were measured and ranged from 31.9 m to 37.3 m;
- A pumping test was undertaken on an existing registered bore (GW016874) which was screened across the Belmont Seam and underlying sandstone floor. The test was continued for 8 hours and indicated permeability in the range  $4 \times 10^{-6}$  m/s to  $5 \times 10^{-6}$  m/s;
- Rock core was inspected and no pervasive partings/fractures were noted, indicating that the inter-burden strata did not contain any moderate to high permeability layers;
- A conceptual hydrogeological model (CHM) was developed for the site which indicated the main water bearing zones or aquifers were in the coal seams with minor water bearing zones in the inter-burden rocks;
- Groundwater was sampled at nine locations and indicated that the water generally did not meet drinking water requirements, with some exceedences of irrigation guidelines. The groundwater is generally suitable for livestock watering; and
- A numerical groundwater flow model was set up and run in steady state to assess potential mine inflows and drawdowns in surrounding wells. Inflows were predicted to be initially about 7,500 m<sup>3</sup>/day, reducing to 1,000 m<sup>3</sup>/day after 10 years. Drawdown in surrounding wells was estimated to range from 0.7 m to 39.8 m.

### **Groundwater Impact Assessment, 2007**

A groundwater impact assessment was carried out by Robert Carr & Associates Pty Ltd in 2007 (RCA, 2007). The assessment included the following:

- Water level survey of 14 bores;
- Sampling and testing of 4 groundwater samples;
- Additional numerical groundwater flow modelling;
- The report concluded that a 2 m groundwater drawdown could occur a distance of 5 km from the mine and predictions of flows in the range 1643 to 2235 m<sup>3</sup>/day; and
- Recommendations were made with regard to ongoing groundwater monitoring.

## 2.3 Consultations

Consultation was undertaken with Mr Martin O'Rourke of the NSW Office of Water (NOW) with regard to their requirements. Mr O'Rourke indicated that NOW's main concern with the expansion of Rocglen Coal Mine was the possible affect on the Namoi Alluvium which is subject to a fully allocated water sharing plan. He indicated that Rocglen Coal Mine had an existing allocation of water from the Namoi Alluvium and the groundwater assessment for the expansion would need to assess if drainage of groundwater into the coal mine was likely to lead to extraction of water from the alluvium and if so, the predicted extraction rate compared to the existing licence.

It was noted by DP that the presence of extensive faulting around the site would complicate any modelling and that the extent of the model would be significantly less than the RCA model as the previous model did not take account of the limited extent of the coal seams. NOW indicated that in terms of the previous model by RCA, the model was probably more extensive in plan than necessary, however more importantly did not represent the Namoi Alluvium satisfactorily. It was noted that the alluvium is known to be up to 100 m thick in some places and the RCA model used a 10 m alluvium thickness.

## 3. Regional Setting

### 3.1 Topography and Drainage

Rocglen Coal Mine is located within a 3 km wide valley between elevated areas in the Vickery State Forest to the west, and Community Conservation Area (CCA) Zone 2 – Kelvin to the east (Drawing 2). The elevation of the land reaches a maximum of 479 m AHD at Bull Mountain within the Vickery State Forest. CCA Zone 2 covers much of a north-south trending ridge. The survey mark of Tulcomba is located on the ridge line at an elevation of 885 m AHD.

The land surface within ML 1620 grades from 300 m AHD on the northwestern boundary to 280 m AHD on the southwestern boundary with slopes ranging between 0.5 degrees and 8 degrees.

An ephemeral creek in the valley commences near the mine and flows in a southerly and westerly direction toward the Namoi River, which is approximately 10 km from the mine site. A second creek, named Driggle Draggles Creek, flows to the north and also eventually joins the Namoi River. The valley deepens in this northerly direction and directs surface water away from the mine site.

### 3.2 Geology

The project area lies within the sedimentary units of the Gunnedah Basin, which covers an area of over 15000 km<sup>2</sup> in North West NSW. The basin is elongated in a north-south direction, widening into the Sydney Basin at its southern boundary. The Gunnedah sedimentary sequence of Permian age uncomfortably overlies Ordovician-Devonian metamorphic strata of the Lachlan Fold Belt. The Gunnedah Basin is bounded to the west by Lachlan Fold strata and to the east by the Hunter-Mooki Thrust and associated New England Fold Belt strata (Drawing 3).

Rocglen Coal Mine is situated within the Maules Creek Sub-basin which is characterised by the following geologic units, as identified from Raymond, et. al. (2007):

- **Willuri Formation** (Early Permian): rhyolitic to andesitic ignimbrites, rhyolite flows and dacite domes, interbedded with ash-rich siltstone and volcanolithic sandstone and conglomerate;
- **Maules Creek Formation** (Middle Permian): basal carbonaceous claystone, sandstone and minor coal, progressing into normally graded, inter-bedded sandstone/siltstone and coal measures with conglomerate dominant near top;
- **Colluvium** (Quaternary): colluvium and/or residual deposits, talus, sheet wash and scree boulders, gravels and sands; and
- **Alluvium** (Quaternary): channel and floodplain gravels, sands and silts.

The mine is located within an outcrop area of the Maules Creek Formation with Quaternary alluvium and colluvium straddling topographic lows to both the north and south. The Willuri Formation (New England Fold Belt strata) and associated Hunter-Mooki Thrust occur approximately 3.5 km east of the mine, and form the eastern margin of the Gunnedah Basin.

Three economic coal seams relevant to the Rocglen Coal Mine and proposed extension comprise the Upper and Lower Glenroc Seams and the Belmont Seam. The Belmont Seam, with an average thickness of 8 m across the mine site is the main economic target. A local northwest trending anticline and localised northwest trending fault system influence the Maules Creek Sub-basin strata in the vicinity of the mine. The Belmont Fault intersects the northeast portion of the current Rocglen Mine. Structure contours of the Belmont Seam are shown in Drawing 4.

### 3.3 Climate

Climatic data for the region were sourced from Bureau of Meteorology (BoM) SILO Database system using the Data Drill option, for the latitude and longitude co-ordinates of Rocglen Coal Mine. The Data Drill accesses grids of data derived by interpolating the BoM's station records. Interpolations are calculated by splining and kriging techniques. The data in the Data Drill are all synthetic; there are no original meteorological station data left in the calculated grid fields. However, the Data Drill does have the advantage of being available for any set of co-ordinates in Australia.

Rainfall and evaporation data were analysed to produce long term average monthly rainfall and evaporation totals for the mine site and surrounding region. Long term average monthly rainfall and evaporation totals are presented in Table 1, and plotted in graphical form on Drawing 5.

**Table 1 - Long Term Average Monthly Rainfall and Evaporation Totals**

| Month         | Rainfall (mm) | Evaporation (mm) | Evaporation / Rainfall |
|---------------|---------------|------------------|------------------------|
| January       | 78            | 246              | 3.2                    |
| February      | 63            | 199              | 3.1                    |
| March         | 49            | 186              | 3.8                    |
| April         | 38            | 128              | 3.4                    |
| May           | 43            | 82               | 1.9                    |
| June          | 45            | 55               | 1.2                    |
| July          | 45            | 59               | 1.3                    |
| August        | 40            | 86               | 2.1                    |
| September     | 40            | 123              | 3.1                    |
| October       | 54            | 175              | 3.2                    |
| November      | 59            | 205              | 3.5                    |
| December      | 64            | 249              | 3.9                    |
| <b>Annual</b> | <b>618</b>    | <b>1793</b>      | <b>2.9</b>             |

Notes: Shaded cells indicate higher rainfall months

Table 1 shows that the four wettest months of the year (November to February inclusive) account for a little over 40% of total annual rainfall. Monthly rainfall totals are relatively even throughout the year with the four months May to August accounting for almost 30% of total annual rainfall.

Evaporation is highest in the summer months, with evaporation exceeding rainfall by almost three times. In the winter months of June and July, evaporation is only slightly in excess of rainfall. During the winter months, significant rainfall events have the potential to result in groundwater recharge because of the relatively low total evaporation during this period. Table 2 lists monthly total rainfall and evaporation for the period June 2008 to February 2010, and compares monthly totals with long-term averages for each month

**Table 2 - Monthly Rainfall and Evaporation Totals, June 2008 to February 2010**

| Month-Year | Recorded Rainfall (mm) | Monthly Average Rainfall (mm) | Recorded Evaporation (mm) | Monthly Average Evaporation (mm) |
|------------|------------------------|-------------------------------|---------------------------|----------------------------------|
| Jun-2008   | 58                     | 45                            | 60                        | 54.8                             |
| Jul-2008   | 25                     | 45                            | 66                        | 59.2                             |
| Aug-2008   | 33                     | 40                            | 86                        | 86.4                             |
| Sep-2008   | <b>90</b>              | 40                            | 117                       | 123.5                            |
| Oct-2008   | <b>81</b>              | 54                            | 176                       | 174.7                            |
| Nov-2008   | <b>99</b>              | 59                            | <b>176</b>                | 204.8                            |
| Dec-2008   | 84                     | 64                            | <b>211</b>                | 249.2                            |
| Jan-2009   | 18                     | 78                            | 249                       | 245.7                            |
| Feb-2009   | 91                     | 63                            | 206                       | 198.8                            |
| Mar-2009   | 1                      | 49                            | 195                       | 186.3                            |
| Apr-2009   | 44                     | 38                            | 124                       | 127.7                            |
| May-2009   | 33                     | 43                            | 90                        | 81.6                             |
| Jun-2009   | 35                     | 45                            | 57                        | 54.8                             |
| Jul-2009   | 24                     | 45                            | 65                        | 59.2                             |
| Aug-2009   | 8                      | 40                            | 112                       | 86.4                             |
| Sep-2009   | 47                     | 40                            | 138                       | 123.5                            |
| Oct-2009   | 49                     | 54                            | 193                       | 174.7                            |
| Nov-2009   | 25                     | 59                            | 270                       | 204.8                            |
| Dec-2009   | <b>134</b>             | 64                            | 267                       | 249.2                            |
| Jan-2010   | <b>114</b>             | 78                            | 226                       | 245.7                            |
| Feb-2010   | 80                     | 63                            | 167                       | 198.8                            |

Notes: **Shaded cells** indicate monthly rainfall totals considerably in excess of long-term averages.  
**Shaded cells** indicate monthly evaporation totals considerably less than long-term averages.

Table 2 shows that since the mine began operating, there have been two periods (September to November 2008 and December 2009 to January 2010) during which higher than average monthly rainfall totals have been recorded. Table 2 also shows that for the months of November and December 2008, evaporation was considerably less than the long term average for these months.

## 4. Project Description

### 4.1 Existing Approval

The Rocglen Coal Mine (formally known as Belmont Coal Project) was originally approved by the Minister on the 15 April 2008 under PA 06\_0198. It was classified as a Major Project in accordance with the *State Environmental Planning Policy (Major Projects) 2005* and, subsequently, was determined under Part 3A of the *EP&A Act*. Whitehaven commenced coal production at Rocglen in late 2008.

In summary, the key activities approved are:

- a) **Coal Mining by Open Cut Mining Methods** – extraction of coal by open cut mining methods within an area of approximately 114 hectares. This involves the extraction of three (3) separate coal seams with a combined thickness of up to 17 m, at an approved production rate of 1.5 million tonne per annum (Mtpa);
- b) **Open Cut Mining by Auger Mining** – extraction of additional coal reserves that are uneconomical to extract by open cut mining methods using auger mining techniques;
- c) **On-Site Coal Processing** – transfer of mined coal by haul truck to a coal handling and processing area located immediately south of the limit of open cut mining for crushing, screening and loading into single or B-double trucks for transport off-site;
- d) **Transportation** – crushed and screened coal is transported to the Whitehaven Coal Handling and Processing Plant (CHPP) around 6 km west of Gunnedah;
- e) **Relocation of Public Roads** – relocation of sections of Wean Road (not yet undertaken) and Jaeger Lane (completed) to allow for open-cut mining activities and infrastructure within these areas;
- f) **Biodiversity Offset Strategy** – implement the biodiversity offset strategy to compensate for the direct loss of 95.44 ha of vegetation in various states and replacement offsets for impacts to 47.9 ha of the 131.84 ha of approved offsets on a 'like for like' basis with over 525 ha of vegetation in the Whitehaven Regional Biobank Site; and
- g) **Rehabilitation** – progressive use of out-of-pit and in-pit overburden emplacements to shape and recreate the landform comparable to that of the pre-mining environment.

Based on the open cut reserves at time of approval and a maximum production rate of 1.5 Mtpa, Rocglen has a current projected life for coal extraction of between 8 to 10 years under the existing Project Approval.

## 4.2 Existing Groundwater Licences

Rocglen Mine currently has three groundwater extraction licences, the details of which are summarised in Table 3.

**Table 3 - Rocglen Mine Groundwater Extraction Licences**

| Licence Number                             | Date of Issue | Valid Until | Allocation                                     | Conditions                                                                                                                        |
|--------------------------------------------|---------------|-------------|------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------|
| Aquifer Interference<br>(90BL254684)       | 12-May-09     | 11-May-14   | 700 ML/a                                       | Metering and annual (July) reporting, development of model, monitoring of groundwater levels and quality.                         |
| Linked Groundwater Licence<br>(90BL254758) | 18-Jan-10     | 17-Jan-15   | 120 ML/a<br>(Total combined as linked licence) | Metering and annual (July) reporting, development of model, monitoring of groundwater levels and quality.                         |
| Linked Groundwater Licence<br>(90BL255249) | 18-Jan-10     | 17-Jan-15   |                                                | Metering and annual (July) reporting, monitoring of groundwater levels and quality (requirements outlined in detail – See below). |

Environmental monitoring for 90BL255249 licence includes the following conditions:

- Desired Outcome: Monitor and record environmental impacts on the local environment;
- Monitor the surface water level (SWL) and saturated thickness and water quality of the following registered bores:
  - o GW050395, GW050166, and GW011066 on the Glenroc Property;
  - o GW045621 on the Yarrawonga Property;
  - o GW044068 and GW044069 on the Yarrari Property;
  - o GW022319 on the Roseberry Property;
  - o GW013369 on the Brolga Property.
- Timing - SWL and saturated thickness quarterly, water quality annually (subject to review).
- Construct and monitor the SWL of the three piezometers on proponent owned land between the open cut and the nearest non-project related groundwater bores.
- Timing - Continuously (data logger) with downloads monthly;
- Monitor water quality of the in-pit sump.
- Timing - 6 monthly;
- Prepare and implement a groundwater monitoring program, in consultation with DECCW, NOW and DOP.

Timing - Before commencement of mining.

The bores required to be monitored as part of the programme are listed in Table 4 below.

**Table 4 - Bores to be Monitored as Condition for Licence 90BL255249**

| <b>Easting</b> | <b>Northing</b> | <b>Bore ID</b>          | <b>WHC Number</b>          | <b>Property</b> | <b>Depth</b> | <b>Aquifer</b>   |
|----------------|-----------------|-------------------------|----------------------------|-----------------|--------------|------------------|
| 239949         | 6596450         | GW050395                | WB02                       | Glenroc         | 36.6         | Unknown          |
| 239379         | 6595789         | GW050166                | WB03                       | Glenroc         | 18.3         | Well - unknown   |
| 239607         | 6595178         | GW011066                | WB05                       | Glenroc         | 47.9         | Maules Creek Fmn |
| 237808         | 6595812         | GW045621                | WB04                       | Yarrowonga      | 10.0         | Unknown          |
| 241030         | 6594658         | GW044068                | WB06                       | Yarrari         | 43.6         | Maules Creek Fmn |
| 240970         | 6594934         | GW044069 <sup>(1)</sup> | Not Monitored <sup>3</sup> | Yarrari         | 47.9         | Maules Creek Fmn |
| 239299         | 6592520         | GW022319                | WB07                       | Roseberry       | 52.4         | Maules Creek Fmn |
| 236815         | 6588545         | GW013369 <sup>(2)</sup> | Not Monitored <sup>3</sup> | Brolga          | 22.3         | Unknown          |

Notes: 1. Closest monitored bore is WB06, ~0.48 km distant  
 2. Closest monitored bore is WB12, ~1.25 km distant  
 3. These bores are not serviceable and are not required to be monitored as part of Rocglen's Site Water Management Plan which is approved by NOW.

### 4.3 Current Mine Status

#### *General*

A site visit was undertaken on 4 February 2010 by a DP Principal Groundwater Engineer. The visit included the following:

- Inspection of the existing open cut operations;
- Discussions with Rocglen Project Manager, Tony Heinrich, regarding site water management;
- Overview of monitoring well locations;
- Discussions with Whitehaven Coal Geologist, Mark Dawson, regarding the regional geology of the area; and
- Obtaining geological and bore data from recent coal exploration.

**Open Cut Pit:**

- Current operations were focussed on the northern end of the pit;
- In the northwest end, the Belmont Seam was exposed at the base of the pit at about RL 220 m AHD. The Upper and Lower Glenroc Seams were not present in this location. A shear zone was evident in the northern face of the pit;
- In the northeast end of the pit, to the east of the shear zone, the Glenroc Seam was exposed at the base of the cut, on a slightly higher bench level of RL 230. It is understood that the strata dips steeply to the east at this location and the Belmont Seam has not yet been excavated;
- The faces of all the seams exposed in the pit were dry;
- The Belmont Seam has been excavated on the eastern side of the pit, south of the current face and in this location it is understood that minor seepage occurred. It is understood that a 4" suction pump ran for about one quarter of the time when this face was exposed. No seepage has been observed in any other locations within the pit.



**Photo 1 - Northern face showing shear zone with Belmont Seam to the west and Glenroc Seams to the east**



**Photo 2 - Belmont Seam exposed in the northern face of the pit**

### ***Local Geology***

Discussions with mine staff indicated the following:

- The pit area includes three seams: Upper and Lower Glenroc, as well as the underlying Belmont Seam. There is an anticline aligned in an approximate north-south direction. The floor of the Belmont Seam is generally at about RL 240 to RL 260 m AHD along the central axis of the anticline, dropping to about RL 180 to RL 200 m AHD on the eastern and western sides of the pit;
- Although the main fault is to the east (as described below) there is some minor faulting in the northern face of the pit. In the northwest corner of the pit, the Belmont seam is evident and the Glenroc seams are eroded. In the northeast corner of the pit, the Glenroc Seams are present near the base of the pit and the Belmont Seam is still to be excavated (although it has already been excavated to the south);
- The strata overlying the coal seams in the pit is generally a conglomerate;
- There is a major fault (Belmont Fault) to the east of the proposed extent of mining. This fault is in an approximate northwest to southeast orientation and defines the eastern extent of the proposed mining. This is because there is an upthrow to the east, and the Belmont and Glenroc seams are not present as they have been eroded. There are some minor seams present but they correlate with seams well below the Belmont and Glenroc Seams;
- Further to the east there is the Mooki Thrust, to the east of which are volcanics associated with the mountain range;
- To the west and south of the site is the Roseberry Fault which is sub-parallel to the Belmont Fault and the strata to the west of this is down thrust by an estimated 100 to 150 m; however there is very little bore data in this area as it is a State Forest. This fault separates the site from the Namoi Alluvium to the south;

- Further west there are several other faults with the strata to the west up thrust in each case. Between the Karu Fault and the Wamboola Fault the coal is shallow again and outcrops in several locations. There are several abandoned open cut remnants in this area, within the former Vickery Mine area. The Namoi River is just to the west of the former Vickery Mine; and
- To the north of the site is the Driggle Draggles Lineament, which runs orthogonal to the Belmont and Roseberry Faults in an approximate northeast to southwest orientation.

Drawing 6 shows the location of the faults relative to the site and the proposed extent of mining.

#### 4.4 Proposed Expansion

Following further drilling and definition of the local geological features, as well as additional reviews of the mine plan, Whitehaven proposes to expand operations at the Rocglen Coal Mine in order to maximise coal recovery and allow for improved mine progression.

The primary components of the Rocglen Project, over and above the current operations, relevant to the groundwater assessment are summarised below:

- a) **Expansion of Open Cut Pit** – expansion of the open cut pit design limit in order to access an additional 4.5 to 5 Mt of coal not previously considered in the life of mine plan, which will increase coal recovery by close to 30%. The footprint of the open cut pit will increase by approximately 50 ha from the currently approved 114 ha to approximately 164 ha. Coal will be extracted from the expanded pit using the current open cut mining methods approved at Rocglen, and at the existing production rate of 1.5 Mtpa. The increase in extent is typically less than an additional 50 m width on the western and southern sides of the pit and locally up to about 250 m additional width on the eastern side; and
- b) **Extension to Life of Mine** – based on the current coal production rate at Rocglen of 1.5 Mtpa, which will be maintained, it is anticipated that extraction activities will occur for approximately 10 years following the issue of Project Approval and the mining lease. This represents an increase to the project life of mine, for coal extraction, of between 2 and 4 years.

The proposed excavation sequencing will comprise a continuation towards the northern end of the extent in about 2011, followed by a retreat to the south, extending out to the eastern and western boundaries towards the central sections, then to the southern end along the western boundary, completing on the mid eastern side. The sequencing is illustrated in Figures 1 to 3 which show the active face as green for Years 1 and 5 of the expanded operation and at end of mine life, which is anticipated to be around 10 years following commencement of the expanded operation. .




**Figure 1 – Mine Plan Year 1**




**Figure 2 -Mine Plan Year 5**




**Figure 3 - Mine Plan End of Mine Life**

#### **4.5 Additional Pit Flow Information**

Subsequent to the site visit in February, updated information regarding groundwater inflows to the pit was provided by Danny Young of Whitehaven Coal in November 2010 who indicated the following: "In terms of pit inflows there has been no substantial volume of water intersected in [the] pit itself. Water has had to be pumped out of pit (23ML for period August 2009 – July 2010) but this is predominantly from the substantial extent of rainfall over the period December - July. Without this rainfall, there would have been no requirement to pump water from the pit itself. Up to December 09, the site was carting water in due to dry conditions and no perceptible water flows in pit."

## 5. Relevant Groundwater Guidelines / Policies

There is a Water Sharing Plan for the Upper and Lower Namoi Groundwater Sources 2003, amended 27 June 2008. This Water Sharing Plan identifies and regulates groundwater sources within the alluvial aquifer of the Namoi River floodplain. The identified alluvium extends into the Project Site and borders the limit of open cut mining as shown on Drawing 8.

Consultation with the NSW Office of Water indicates their primary concern with the development is the potential for the excavation to lead to extraction of water from the alluvium. Groundwater resources of the Namoi Alluvium are fully allocated. Rocglen Coal Mine currently has an annual allocation of 700 ML/yr for aquifer interference and if the mine has the potential to remove more than this volume, then it will need to source additional allocations from existing allocation holders.

The Water Sharing Plan indicates that there are no high priority groundwater dependant ecosystems within the alluvium.

It is noted Section 4, subsection 3 of the Water Sharing Plan states:

*“The Upper and Lower Namoi Groundwater Sources include all water contained in the unconsolidated alluvial sediment aquifers associated with the Namoi River and its tributaries”. “Note: Bores drilled through the unconsolidated alluvial sediments into the underlying Great Artesian Basin (GAB) are tapping a different groundwater source. On a map, they may appear to lie within the boundaries of the Lower Namoi, however they are within the deeper GAB groundwater source and are not included as a part of this Plan”.*

## 6. Local Hydrogeological Regime

### 6.1 Identified Aquifers

The stratigraphy of Rocglen Coal Mine and surrounding areas has been assessed from geological mapping, a review of coal exploration drilling data, a review of hydrogeological information from the NSW Office of Water Groundwater Database, and from information contained in previous groundwater investigation reports.

WHC provided data from the drilling of more than 160 coal exploration holes. The stratigraphy of the Maules Creek Formation in the vicinity of Rocglen Mine comprises the Upper Glenroc and Lower Glenroc Coal Seams, non-coal strata (between seams) comprising lithic conglomerates, sandstones and mudstones, and the basal Belmont Coal Seam, which is the coal seam of main economic interest.

During the drilling of the coal exploration bores, it was noted that groundwater was mainly limited to the coal seams, (particularly the Belmont Coal Seam) which is considered to be the main aquifer zone within the Maules Creek Formation sequence. The Belmont Coal Seam is generally consistent in thickness (~8 m average) and groundwater occurs in fracture cleat within the seam. A generalised stratigraphy of the Rocglen Coal Mine area is illustrated by the lithographic log of Bore EVK 110 (Drawing 7). Structure contours of the base of the Belmont Coal Seam are presented in Drawing 4.

The other major aquifer of the region is the sand/gravel accumulations within alluvium associated with the Namoi River and associated tributaries. Alluvium abuts the Maules Creek Formation to the north and to the southwest of Rocglen Mine (Drawing 8).

## 6.2 Aquifer Hydraulic Parameters

Evaluations of the hydraulic parameters of Maules Creek Formation strata were undertaken by RCA (2002) and RCA (2007). Hydraulic testing by RCA (2002) involved the falling head permeability testing of piezometers installed in Bores EVK25, EVK30 and EVK64. Testing assessed the permeability of the Glenroc Seams, the Belmont Seam and the interburden between the Belmont and Glenroc Seams.

Test pumping was also undertaken on Bore GW016874 and reported by RCA (2002). The test involved pumping from the bore for a period of 8 hours and measuring drawdown and recovery in the bore. The pumping rate over the test period was recorded at 0.63 L/s. Test pumping data were analysed by RCA (2002) using the program "RADFLOW". Recovery data were also analysed using the method of Hvorslev (1951).

During the RCA (2007) investigation, the permeability of the coal seams and interburden was assessed in piezometers installed in Bores EVK61 and EVK40 (EVK40-P1 and EVK40-P2) by falling head permeability testing. Test data were analysed using the method of Hvorslev (1951).

Results of the hydraulic testing of RCA (2002) and RCA (2007) are summarised in Table 5.

**Table 5 - Results of Hydraulic Testing for Rocglen Mine**

| Bore     | Screened Interval | Strata Screened                                   | Permeability (m/d)   | Permeability m/s     | Source                                   |
|----------|-------------------|---------------------------------------------------|----------------------|----------------------|------------------------------------------|
| EVK25    | 39 m to 72 m      | Glenroc Seams and interburden between these seams | $8.6 \times 10^{-4}$ | $9 \times 10^{-9}$   | FHT; RCA (2002)                          |
| EVK64    | 55 m to 70 m      | Interburden between Glenroc and Belmont Seams     | $7.8 \times 10^{-2}$ | $9 \times 10^{-7}$   | FHT; RCA (2002)                          |
| EVK61    | 48 m to 51 m      | Interburden between Glenroc and Belmont Seams     | $1.4 \times 10^{-2}$ | $1.6 \times 10^{-7}$ | FHT; RCA (2007)                          |
| EVK40-P2 | 84 m to 85.5 m    | Lower Glenroc Seam                                | $2.1 \times 10^{-1}$ | $2.4 \times 10^{-6}$ | FHT; RCA (2007)                          |
| EVK30    | 42 m to 48 m      | Belmont Seam                                      | $6.0 \times 10^{-2}$ | $7 \times 10^{-7}$   | FHT; RCA (2002)                          |
| EVK40-P1 | 91 m to 94 m      | Belmont Seam                                      | $4.3 \times 10^{-1}$ | $5 \times 10^{-6}$   | FHT; RCA (2007)                          |
| GW016874 | 40.8 m to 54 m    | Belmont Seam                                      | $4.3 \times 10^{-1}$ | $5 \times 10^{-6}$   | PT; RCA (2002)                           |
| GW016874 | 40.8 m to 54 m    | Belmont Seam                                      | $3.5 \times 10^{-1}$ | $4 \times 10^{-6}$   | PT; RCA (2002)                           |
| EVK110   | -                 | Belmont Seam                                      | $5.5 \times 10^0$    | $6 \times 10^{-5}$   | Cooper Jacob Method (This investigation) |
| EVK114   | -                 | Belmont Seam                                      | $2.8 \times 10^0$    | $3 \times 10^{-5}$   | Cooper Jacob Method (This investigation) |
| EVK162   | -                 | Belmont Seam                                      | $5.1 \times 10^{-1}$ | $6 \times 10^{-6}$   | Cooper Jacob Method (This investigation) |

Coal exploration holes EVK110, EVK114 and EVK162 have been converted to water bores in order to provide water for mining activities (principally dust suppression). Each of these bores were test pumped by Lambert & Torrens Pty Ltd of Gunnedah. The test pumping data have been analysed using the method of Cooper & Jacob (1946) and values of permeability assessed. Results are also included in Table 5.

Results listed in Table 5 show that the coal seams are generally at least 2 orders of magnitude more permeable than the interburden strata. Permeability values derived from test pumping are generally greater than results obtained from falling head testing.

### 6.3 Groundwater Levels and Flow Directions

RCA (2007) recorded groundwater levels in a number of bores throughout the region and calculated approximate reduced levels to a common datum. The reduced levels were then contoured to assess groundwater levels and flow directions.

RCA (2008) designed a groundwater monitoring program (GWMP) for the original Rocglen Coal Project which involved the monitoring of groundwater levels and groundwater quality in eleven registered bores, and five piezometers (MP-01 to MP-05) to be constructed by WHC.

WHC has installed the piezometers and has also monitored groundwater levels and quality in 13 private bores, which are designated/known as WB-01 to WB-12, Yarrari Bore and Wundurra Bore. Bore WB-04 is not monitored due to casing around the bore preventing access. Summary details of monitoring bores in the Rocglen Coal GWMP are provided in Table 6. Locations of the bores are shown in Drawing 10.

**Table 6 - Monitoring Bores of the Rocglen Mine GWMP**

| Easting<br>(GDA-94) | Northing<br>(GDA-94) | Bore ID  | Alternate<br>ID (RN) | Distance<br>from<br>Centre of<br>Pit (km) | Water Levels<br>(AHD) |       | Interval Monitored /<br>Comments / Notes         |
|---------------------|----------------------|----------|----------------------|-------------------------------------------|-----------------------|-------|--------------------------------------------------|
|                     |                      |          |                      |                                           | 2007<br>(RCA)         | 2009  |                                                  |
| 238941.4            | 6595440.7            | MP-01    | GW968533             | 1.2                                       | -                     | 278.5 | Conglomerate                                     |
| 239156.0            | 6592782.9            | MP-02    | GW968534             | 1.5                                       | -                     | 269   | Unknown                                          |
| 238649.0            | 6590866.0            | MP-03    | GW968535             | 3.4                                       | -                     | 253   | Alluvium                                         |
| 238838.0            | 6589909.1            | MP-04    | GW968536             | 4.4                                       | -                     | 248   | Alluvium                                         |
| 238268.6            | 6594816.8            | MP-05    | GW968537             | 0.8                                       | -                     | 257   | Conglomerate                                     |
| 238738.0            | 6597885.0            | WB-01    | GW000743             | 3.6                                       | 277                   | 277.5 | Black Shale                                      |
| 239906.0            | 6596452.0            | WB-02    | GW050395             | 2.4                                       | 286                   | 289.5 | Unknown                                          |
| 239394.0            | 6595776.0            | WB-03    | GW050166             | 1.6                                       | -                     | 292.5 | Shallow; Alluvium?                               |
| 239586.0            | 6595157.0            | WB-05    | GW011066             | 1.2                                       | -                     | 292.5 | Black Shale                                      |
| 240696.0            | 6594539.0            | WB-06    | GW044068             | 1.9                                       | 289                   | 305   | Black Rock; Coal, Shale?                         |
| 239321.0            | 6592514.0            | WB-07    | GW022319             | 1.8                                       | 268                   | 262   | Gravel; Conglomerate?                            |
| 240654.0            | 6589786.0            | WB-08    | GW052958             | 4.8                                       | -                     | 250   | Conglomerate                                     |
| 240222.0            | 6588393.0            | WB-09    | Unknown              | 6                                         | -                     | 254   | Unknown                                          |
| 237137.0            | 6586489.0            | WB-10    | Unknown              | 8                                         | -                     | 254.5 | Unknown                                          |
| 236405.0            | 6585725.0            | WB-11    | Unknown              | 8.9                                       | -                     | 246   | Unknown                                          |
| 237562.0            | 6587535.0            | WB-12    | Unknown              | 6.9                                       | -                     | 256   | Unknown                                          |
| 239156.0            | 6592782.9            | Yarrari  | Unknown              | 1.5                                       | -                     | 232.5 | Unknown                                          |
| 239156.0            | 6592782.9            | Wundurra | Unknown              | 1.5                                       | -                     | 262.5 | Unknown                                          |
| 239097.9            | 6594298.8            | EVK25    | None                 | Within pit                                | 256                   | -     | Glenroc Seams and inter-burden between the seams |
| 238777.6            | 6593659.5            | EVK30    | None                 | Within pit                                | 258                   | -     | Belmont Seam                                     |
| 239034.1            | 6594300.1            | EVK64    | None                 | Within pit                                | 255                   | -     | Interburden between Glenroc and Belmont Seams    |
| 239322.7            | 6590412              | EVK40-P1 | None                 | Within pit                                | 258                   | -     | Belmont Seam                                     |
|                     |                      | EVK40-P2 | None                 | Within pit                                | 258                   | -     | Lower Glenroc Seam                               |
| 238846.7            | 6594417.7            | EVK61    | None                 | Within pit                                | 252                   | -     | Interburden between Glenroc and Belmont Seams    |

Groundwater levels have been monitored in these bores since the commencement of mining in mid 2008. Hydrographs of groundwater levels for these monitoring bores are presented in Appendix B (Drawings A-1 to A-4).

The RCA monitoring in 2007 included bores screened in the coal seams and within the mine footprint. As is evident from Table 6 above, the current monitoring bores generally do not intersect the coal seams. This is because they are located outside the mining footprint (to avoid disturbance by mining) and, due to the geology, the coal is generally not present outside of the mine footprint.

Drawing 9 shows approximate groundwater levels across the area prior to the commencement of mining, based on the current monitoring wells shown in Table 6. The contoured surface suggests that the groundwater table is a subdued reflection of topography, and that groundwater flows from elevated areas east of the mine, westward towards the Namoi River.

The contoured groundwater levels on Drawing 9 are similar to those contoured by RCA (2007). Of particular note is that the bores within the mine footprint, which were measured in 2007 were no longer available in 2008 and were not able to be used to calculate the contours shown on Drawing 9. Reference to Table 6 indicates that for these bores the heads were generally in the range RL 252 to RL 258 in 2007. Reference to Drawing 9 indicates interpolated groundwater contours in the range RL 255 to RL 260, which is similar to the heads measured in 2007.

#### 6.4 Groundwater Recharge

Hydrographs of groundwater levels presented in Appendix B show that recharge of the groundwater system in the vicinity of Rocglen Mine is poor. No significant groundwater level rises in response to rainfall events are apparent in any of the hydrographs presented in Drawings A-1 to A-4.

During the monitoring period, there have been a number of significant rainfall events which would be expected to result in groundwater recharge. In particular, the periods September to November 2008 and December 2009 and January 2010 recorded above average rainfall (Table 2), yet groundwater level rises did not follow.

Poor recharge of the strata in the vicinity of Rocglen Mine is probably a function of low permeability, in addition to the general exceedance of evaporation over rainfall (Table 1).

#### 6.5 Groundwater Quality

RCA (2007) assessed baseline groundwater quality based on the laboratory analysis of 13 groundwater samples. Samples were analysed for: alkalinity, aluminium, arsenic, chloride, electrical conductivity, iron, magnesium, manganese, nitrates, nitrites, pH, potassium, sodium and sulphates.

RCA (2007) concluded that groundwater in the vicinity of Rocglen Coal Mine could be characterised as follows:

- pH ranging from 6.3 to 7.7 (essentially neutral);
- Electrical Conductivity values indicate that the groundwater is brackish; and
- The groundwater is generally of a sodium-bicarbonate/chloride type.

The range of chemical parameters analysed for by RCA (2007) was limited. Of the major ions, calcium was not included in the analysis. It is not possible to assess the “type” of groundwater without analysing for all major ions, unless 7 of the 8 major ions are analysed for and it is assumed that the groundwaters are in ionic balance. The RCA (2007) characterisation of groundwater quality cannot be relied upon.

Since mining began, WHC has periodically collected groundwater samples from a number of monitoring bores and had them laboratory analysed for an extensive range of chemical parameters. A total of 35 groundwater samples from 13 monitoring bores have been analysed since October 2008. The laboratory results have been analysed to calculate Percentage Reacting Values (PRVs) of major ions and assess water type. Table 7 lists average PRVs for groundwaters from each of the 13 monitoring bores.

**Table 7 - Percentage Reacting Values of Major Ions in Groundwater at Rocglen Coal Mine**

| Sample ID / Source | Na    | K    | Ca    | Mg    | Cl    | CO <sub>3</sub> | HCO <sub>3</sub> | SO <sub>4</sub> | Type                         |
|--------------------|-------|------|-------|-------|-------|-----------------|------------------|-----------------|------------------------------|
| Bore MP-01         | 81.6% | 0.4% | 8.5%  | 9.6%  | 28.4% | 0.0%            | 64.1%            | 7.5%            | Na-HCO <sub>3</sub> /Cl      |
| Bore MP-02         | 53.4% | 0.3% | 23.1% | 23.2% | 75.6% | 0.0%            | 22.5%            | 1.9%            | Na-Cl                        |
| Bore WB01          | 91.6% | 0.6% | 2.4%  | 5.4%  | 44.0% | 0.0%            | 52.6%            | 3.4%            | Na-HCO <sub>3</sub> /Cl      |
| Bore WB02          | 38.2% | 0.3% | 32.5% | 29.0% | 72.0% | 0.0%            | 26.9%            | 1.1%            | Na/Ca/Mg-Cl/HCO <sub>3</sub> |
| Bore WB03          | 37.1% | 0.1% | 27.7% | 35.1% | 81.0% | 0.0%            | 17.8%            | 1.2%            | Na/Mg/Ca-Cl                  |
| Bore WB05          | 53.3% | 0.3% | 18.5% | 28.0% | 85.0% | 0.0%            | 13.1%            | 1.9%            | Na/Mg-Cl                     |
| Bore WB07          | 61.7% | 0.4% | 20.1% | 17.9% | 60.0% | 0.0%            | 37.9%            | 2.1%            | Na-Cl/HCO <sub>3</sub>       |
| Bore WB08          | 76.4% | 0.7% | 10.0% | 12.8% | 47.4% | 0.0%            | 49.2%            | 3.4%            | Na-HCO <sub>3</sub> /Cl      |
| Bore WB09          | 42.5% | 0.9% | 28.0% | 28.7% | 19.9% | 0.0%            | 73.1%            | 7.0%            | Na/Mg/Ca-HCO <sub>3</sub>    |
| Bore WB10          | 47.7% | 0.0% | 27.7% | 24.7% | 16.5% | 0.0%            | 60.1%            | 23.4%           | Na/Ca-HCO <sub>3</sub>       |
| Bore WB11          | 60.7% | 1.0% | 16.2% | 22.1% | 39.0% | 0.0%            | 57.7%            | 3.3%            | Na-HCO <sub>3</sub> /Cl      |
| Bore WB12          | 66.1% | 0.5% | 6.6%  | 26.8% | 31.0% | 5.4%            | 63.0%            | 0.5%            | Na/Mg-HCO <sub>3</sub> /Cl   |
| Yarri Production   | 64.6% | 0.2% | 26.2% | 9.0%  | 74.4% | 0.0%            | 23.1%            | 2.5%            | Na/Ca-Cl                     |

Notes:   
 Shaded cells indicate the dominant cation  
 Shaded cells indicate a prominent, but not dominant cation  
 Shaded cells indicate the dominant anion  
 Shaded cells indicate a prominent, but not dominant anion

Sodium is the dominant cation with an average PRV of about 60%. Calcium and magnesium are also prominent cations in groundwaters from a number of monitoring bores with PRVs in excess of 25%. Chloride and bi-carbonate are the dominant anions with average PRVs of 52% and 43%, respectively. While the waters can generally be described as either sodium chloride or sodium bi-carbonate in type, the prominence of calcium and magnesium in some groundwaters indicates a wide range of chemical types.

A significant range in water quality is characteristic of groundwater systems with low permeability, minimal flow and structural complexity.

A summary of water quality is provided in Appendix C (Table B-1). This table lists averaged concentrations of all chemical parameters tested for samples from each of the monitoring bores. Results are compared with ANZECC (2000) guideline values for potable water quality and for livestock watering guideline values.

In regard to potable water quality, many of the groundwaters sampled exceed guideline values for the following parameters:

- pH and salinity (EC and TDS);
- Sodium, chloride and sulphate;
- Ammonia; and
- Arsenic, iron, lead, manganese and nickel.

In regard to stock watering guidelines, no guideline values are exceeded for the parameters analysed, with the exception of groundwater from Bore WB-5 which has an average salinity (TDS) value in excess of 5,000 mg/L.

## 6.6 Groundwater Utilisation

Groundwater resources are used by landholders throughout the area for domestic use, stock watering and irrigation. The major use is for stock watering. Individual bore yields are generally low (less than 1 L/s). RCA (2007) undertook a search of the former NSW Department of Water & Energy (DWE) Groundwater Database to identify groundwater users in the vicinity of Rocglen Coal Mine. DP has repeated the search for this study; results are summarised in Table 8.

The locations of the 32 identified bores are shown with respect to Rocglen Coal Mine on Drawing 11. Groundwater Works Summary sheets for each of the bores are provided in Appendix D.

**Table 8 - Summary Details of Registered Bores in Close Proximity to Rocglen Mine**

| <b>Easting<br/>(GDA94)</b> | <b>Northing<br/>(GDA94)</b> | <b>Bore ID</b> | <b>Distance<br/>from Mine<br/>(km)</b> | <b>Type / Use</b>          | <b>Property</b> |
|----------------------------|-----------------------------|----------------|----------------------------------------|----------------------------|-----------------|
| 240371                     | 6590019                     | GW000122       | 4.5                                    | Not known                  | Not stated      |
| 241481                     | 6598028                     | GW000713       | 4.6                                    | Not known                  | Penryn          |
| 238686                     | 6598022                     | GW000743       | 3.8                                    | Not known                  | Costa Vale      |
| 235611                     | 6599611                     | GW003083       | 6.2                                    | Not known                  | Not stated      |
| 240560                     | 6599793                     | GW009830       | 5.8                                    | Stock                      | Penryn          |
| 239507                     | 6594898                     | GW011015       | 0.9                                    | Stock                      | Glenroc         |
| 239607                     | 6595178                     | GW011066       | 1.2                                    | Stock                      | Glenroc         |
| 237892                     | 6588017                     | GW013284       | 6.3                                    | Stock                      | Brolga          |
| 236815                     | 6588545                     | GW013369       | 6.1                                    | Stock                      | Brolga          |
| 239981                     | 6594016                     | GW016871       | 1.2                                    | Stock                      | Belmont         |
| 238943                     | 6594022                     | GW016874       | 0.3                                    | Stock and Domestic         | Belmont         |
| 236691                     | 6589282                     | GW017198       | 5.4                                    | Stock                      | Brolga          |
| 234123                     | 6589835                     | GW017199       | 6.5                                    | Stock                      | Brolga          |
| 241539                     | 6589031                     | GW020454       | 5.9                                    | Stock                      | Carlton         |
| 242502                     | 6588807                     | GW020456       | 6.6                                    | Stock                      | Carlton         |
| 240862                     | 6588429                     | GW020461       | 6.2                                    | Irrigation                 | Carlton         |
| 239299                     | 6592520                     | GW022319       | 1.8                                    | Stock                      | Roseberry       |
| 241070                     | 6593026                     | GW035706       | 2.6                                    | Stock and Domestic         | Surrey          |
| 238480                     | 6587908                     | GW036484       | 6.4                                    | Groundwater<br>Exploration | Not stated      |
| 241213                     | 6594786                     | GW044067       | 2.4                                    | Stock and Domestic         | Highview        |
| 241030                     | 6594658                     | GW044068       | 2.2                                    | Stock and Domestic         | Yarrari         |
| 240970                     | 6594934                     | GW044069       | 2.2                                    | Stock and Domestic         | Yarrari         |
| 237808                     | 6595812                     | GW045621       | 1.9                                    | Stock                      | Yarrawonga      |
| 239379                     | 6595789                     | GW050166       | 1.6                                    | Stock                      | Glenroc         |
| 239906                     | 6596452                     | GW050395       | 2.4                                    | Stock                      | Glenroc         |
| 240560                     | 6589603                     | GW052956       | 5.0                                    | Not known                  | Surrey          |
| 240669                     | 6589780                     | GW052958       | 4.9                                    | Stock and Domestic         | Surrey          |
| 237382                     | 6595907                     | GW060867       | 2.2                                    | Stock and Domestic         | Yarrawonga      |
| 234694                     | 6589356                     | GW062364       | 6.4                                    | Groundwater<br>Exploration | Stratford       |
| 234322                     | 6590395                     | GW064948       | 6.0                                    | Monitoring Bore            | Not stated      |
| 234359                     | 6589964                     | GW064949       | 6.2                                    | Monitoring Bore            | Not stated      |
| 240917                     | 6594447                     | GW968918       | 2.1                                    | Stock and Domestic         | Yarrari         |

The recent database search identified one bore not previously picked up by RCA (2007) (Bore GW060867), and another (Bore GW968918) which has been drilled since the RCA (2007) study.

Results of the database search show that bores in the region are on average 60 m deep. Very few bores are greater than 100 m depth or shallower than 30 m. Bore yields average 0.5 L/s, ranging from 0.1 L/s to 1.3 L/s. The depth to the groundwater table is generally about 25 m for most bores, ranging from the shallowest at ~10 m to the deepest at ~50 m.

## 7. Conceptual Hydrogeological Model

Figure 4 presented below is useful for explanation of a conceptual model for groundwater flow at the site. The figure shows the following items:

- General terrain, shown as shaded contours, indicating a mountainous region to the east of the site, as well as a lower, however distinct mountainous area to the west of the site;
- Alluvial soils, as defined by the Namoi Alluvium Water Sharing Plan are shown to the north of the site on relatively flat ground, with the interface with the residuals marked as a yellow line. Alluvial soils are also present to the south of the site, on relatively flat ground, at a lower elevation to the northern alluvial soils. The northern tip of the southern alluvial soils reaches within close proximity of the southern extent of proposed mining;
- The locations of faults are shown as pink lines and indicate that the site is separated from the northern alluvium by several faults, however the southern alluvium extends across the faulting to the south of the site; and
- Approximate contours of groundwater head at the various monitoring wells are also presented for July 2008, immediately prior to commencement of mining. It is noted that the contours provide only an indication of the distribution of groundwater head between monitoring points, as these are likely to be locally affected by the presence of faults and the coal seams.




**Figure 4 - Site Terrain and Contours of Groundwater Head (m AHD) in July 2008**

The conceptual model for the groundwater flow at the site is described as follows:

- Rainfall recharge occurs across the model domain;
- Flow from recharge on the eastern valley sides flows in a generally westerly direction towards the site. Flow at the southern end of this range is diverted in a south-westerly direction discharging towards the southern alluvium. Flow from the northern end of the range is diverted in a north-westerly direction towards the northern alluvium;
- A similar flow regime is expected to occur on the western side of the valley, with flow in a generally easterly direction. There is little groundwater data on the western side of the valley to fully characterise this, however the groundwater divide is likely to be offset to the western side of the valley due to the reduced relief on this side;

- The head in the northern alluvium is expected to be about 20 m higher than the southern alluvium and there will also be some recharge to the site from the northern alluvium and discharge of flow from the site to the southern alluvium. It is noted that although WB01 is not screened directly in the alluvium it is screened below the alluvium in the shale, however only a slight variation in head would be expected due to some limited vertical flow, WB01 is expected to give a reasonable representation of the head in the northern alluvium. The hydraulic gradient in the alluvium is generally expected to be low, because of its relatively high permeability with respect to the coal measures rocks. In the southern alluvium there are indications of localised drawdowns (Near MP-004) which are probably related to groundwater extraction. It is noted that groundwater monitoring was prevented at times in WB07 because of the presence of a pump in the well and during the site visit high volume extraction was noted from several bores to the south of the site;
- Within the mine site the Glenroc and Belmont coal seams are the primary water bearing zones, with estimated permeability of at least two orders of magnitude higher than the surrounding strata. The seams are only present between the Belmont and Roseberry Fault, and also subcrop in several locations around the proposed extent of mining. The full extent of the seams within the areas between the faults has not been established, in particular to the south of the site, however is likely to be less than the full extent between the faults;
- Recharge into the coal seams is expected to occur from the northern alluvium and eastern and western valley sides and is expected to be impeded by the presence of faulting as discussed further below. Some very limited direct rainfall recharge on the site may also recharge the coal seams.
- Preferential flow is expected to occur within the coal seams below the site towards the south of the site which eventually discharge into the alluvium through a limited hydraulic connection. The coal will in essence act as a drainage blanket.
- The Belmont and Glenroc Coal seams are truncated by faulting and do not continue significantly to the east, west or north of the immediate mine site. The role that the faults are expected to play in the interaction between the coal seams and the surrounding strata are discussed as follows:
  - o The Belmont fault immediately to the east of the site has no direct connection to the southern alluvium, however it does connect with the Mooki Thrust, further to the east, which does intersect with the southern alluvium several kilometres south of the site. The region where the faults are present to the east of the site is characterised by relatively high groundwater heads compared with heads within the coal seams at the site. This indicates that flow occurs from the strata to the east into the coal seams towards the west, however the connection seems limited, as evidenced by the elevated head to the east of the fault, suggesting the fault is having a damming effect rather than a draining effect. There is also no indication of a significant connection between the eastern faults and the southern alluvium. If a significant connection was present the faults would be expected to act as drains, leading to drawdown of head in adjacent strata and possible flow from the west towards the eastern fault; however this is not evident.

- o The fault immediately east of the site also connects with a lineament to the north of the site which does intersect with the northern alluvium. However, the groundwater contours indicate there is no significant hydraulic connection between the alluvium and the coal seam. There is a minor hydraulic connection between the northern alluvium and the coal seams, however it doesn't necessarily occur through the faulting. If a significant hydraulic connection was present, the heads in the coal seams below the site would be closer to the head in the northern alluvium. However, the head in the coal seams below the site are closer to those in the southern alluvium, suggesting more connectivity to the southern alluvium than to the northern alluvium.
- o The fault to the west of the site continues directly below the alluvium to the south. There are limited monitoring data to the west of the site and it is possible that the hydraulic connection between coal seams below the site could be at least partly due to preferential flow throughout the fault, however it would also be due to vertical flow between the strata separating the alluvium and the coal seams.

Based on the conceptual model, the impacts of mine drainage would be expected to be subdued due to the presence of faulting to the east, west and north of the site, effectively limiting hydraulic connection between the coal seams within the site and the surrounding strata. There is likely to be some hydraulic connection between the coal seams and the southern alluvium. The degree of connection has been further assessed by numerical modelling, as presented in the following sections.

## 8. Monitored Impact to Date

RCA (2007) utilised numerical modelling techniques to assess the likely magnitude of groundwater inflows into the open pit, and the drawdown impact on the surrounding groundwater regime that would result from those inflows.

RCA (2007) predicted that over the 7 year period of mining, inflows to the open pit would be as follows:

- During mine years 1 to 3: average inflow of 1,643 m<sup>3</sup>/day (~19 L/s);
- During mine years 4 and 5: average inflow of 2,235 m<sup>3</sup>/day (~26 L/s); and
- During mine years 6 and 7: average inflow of 1,813 m<sup>3</sup>/day (~20 L/s).

RCA (2007) further considered that these inflows would be balanced by evaporation in excess of rainfall, and that as a result, net seepage into the pit would be limited and not noticeable. DP does not concur with this conclusion.

While evaporation does exceed rainfall markedly on an annual basis (Table 1), there are periods during the year, notably the months of June and July, where rainfall almost balances evaporation. During such times, a baseline inflow of the order of 20 L/s to 25 L/s would be apparent. During the period of mining from mid 2008 to present, there have been a few such occasions where an inflow of the order of 20 L/s should have presented. Table 2 shows that during the period September to November 2008, June 2009, and December 2009 and January 2010, rainfall was generally high and or evaporation was low. Under such circumstances, a baseline inflow of ~20 L/s would have been noticeable.

WHC mine site personnel reported that there have generally been no noticeable inflows from the inception of mining to date, with the exception of the eastern extent where the seams dip are locally deeper. In this location it was reported that inflows were sufficient for a 4" pump to run for half of the time.

Therefore, based on site observations it seems that the predicted inflows were slightly overestimated, although such flows have probably occurred for the locally deeper parts of the excavation.

The RCA (2007) numerical model predicted the drawdown in a number of landholder's bores within 5 km of the mine, that would ensue from the aquifer dewatering impact of inflows to the mine. Table 13 of RCA (2007) lists 20 bores and outlines model predicted drawdown for each of these bores that would result from mining at the end of 7 years. DP has plotted the RCA (2007) model predicted drawdown for each of these bores against distance from the centre of the Rocglen open pit (Drawing 12). Drawing 12 also includes a plot of monitored groundwater decline (as of end 2009) for bores of the Rocglen Mine Monitoring Bore Network against distance from the mine. Apart from the groundwater levels recorded for monitoring bore WB-05, which is likely to be anomalous and affected by nearby pumping, **it is apparent that the mine has had very little impact on surrounding groundwater levels over the period mid 2008 to present.**

Based on the comparison between RCA (2007) numerical model predictions, and monitored groundwater levels to date (Drawing 12), it is considered that the RCA (2007) model over-predicts the mine induced impact on the groundwater system. This is likely to be because the model assumed that the coal seam was continuous beyond the site, and did not take account of the faulting, which is present.

In comparison with the extent of Rocglen Mine which has already been approved, the proposed extension comprises a reasonably uniform increase around the existing perimeter and therefore is not expected to have a significantly different impact on groundwater flow directions. The existing approved mine area totals ~1.14 km<sup>2</sup>. The extension covers (approximately) an additional 0.5 km<sup>2</sup> in area.

## 9. Numerical Modelling

### 9.1 Introduction

In order to clarify the conceptual model, a 3D numerical model was developed using the software Visual MODFLOW. MODFLOW is a modular three dimensional finite difference groundwater model for the description and prediction of the behaviour of groundwater systems.

Due to the complexity of the geology at the site, including the presence of very steeply dipping coal seams and faulting, which is impossible to characterise in detail, the model was limited to four layers as follows:

- Layer 1: Alluvium/General Overburden;
- Layer 2: General Overburden (Volcanics on eastern part of the site);
- Layer 3: Coal Seams and Interburden (combined as one layer) between the Belmont and Roseberry Faults and General Overburden elsewhere; and
- Layer 4: Sandstone Floor.

The primary aim of the modelling was to assess potential impacts of the mine drainage on the aquifers, in particular the magnitude of interference to flow to the southern alluvium. The model domain was limited to the extent of groundwater monitoring data, as per the conceptual model. The following boundary conditions were adopted:

- Fixed head of RL 278 within the alluvium at the northern extent of the model;
- Fixed head of RL 250 within the alluvium at the southern extent of the model; and
- No flow boundaries along the western and eastern ridge lines.

As the faults were expected to be key barriers and possible conduits for groundwater flow, the model was oriented in the direction of the faulting. A variably spaced rectangular mesh was adopted with grid spacings ranging from 500 m at the outer edges of the model domain to 60 m in the location of the proposed open cut pit. The model domain extended about 5 to 6 km to the north and south of the site and 3 to 4 km to the east and west of the site.

### 9.2 Steady State Modelling

#### 9.2.1 Calibration of Existing Heads

Steady state modelling was undertaken to replicate the groundwater heads measured in July/August 2008, prior to commencement of mining. As it is possible to have differing sets of permeability/recharge provide the same outcome, the model was run for a range of plausible parameters. Case 1 was based on a best estimate of the permeability of the coal seams ( $1.0 \times 10^{-5}$  m/s / 0.86 m/day), from the well test data. The permeability of the overburden strata and recharge were then adjusted to match the observed head distribution.

For Case 2 the permeability of the coal was set to a maximum credible value ( $4.6 \times 10^{-5}$  m/s / 4.0 m/day) and the permeability of the overburden and recharge were adjusted to fit the data.

A permeability of  $5.0 \times 10^{-5}$  m/s (4.3 m/day) was adopted as being typical of alluvial strata and to replicate the relatively low hydraulic gradients in the alluvium. The thickness of alluvium was based on bore logs from registered wells and typically ranged up to about 70 m in the model domain. The extent of alluvium was based on the Namoi Alluvium mapping, however was extended slightly to the east as part of the calibration process and the extent is shown on Figure 5 below.




**Figure 5 - Distribution of Strata in Layer 1**

Due to the highly folded and faulted nature of the strata, the permeability of the coal and inter-burden were assumed as isotropic, with the other layers generally having a vertical permeability of 10% of the horizontal permeability.

The coal and inter-burden were modelled as one layer, as the seam thicknesses were too small to allow representation of such steeply and variable dipping strata. The coal seams, however are the primary water bearing zones and where faults or outcrops are present the actual contact between the seams adjacent to the lower permeability strata is significantly less than for the overall composite layer. Therefore in order to obtain an acceptable calibration it was necessary to place a strip of lower permeability material at the edge of the layer, to replicate the actual low connectivity between the strata. Without this low permeability strip it was impossible to provide the contrast in head across the faults and outcrops which is evident in the monitoring data. The approximate extent of the coal, limited by faulting and outcropping is shown in red/rust in Figure 6 below, and in a cross section in Figure 7.




**Figure 6 - Modelled Extent of Coal Seams**




**Figure 7 - Section Showing Folded and Truncated Coal Seam (rust)**

The calibrated data sets are presented in Table 9 below.

**Table 9 - Calibrated Steady State Parameters**

| Case                    | Case 1                                | Case 2                                |
|-------------------------|---------------------------------------|---------------------------------------|
| Description             | Upper Bound Seam Permeability         | Lower Bound Recharge                  |
| Recharge                | 4 mm/yr                               | 1 mm/yr                               |
| Alluvium K              | $5 \times 10^{-5}$ m/s<br>4.3 m/day   | $5 \times 10^{-5}$ m/s<br>4.3 m/day   |
| Volcanics K             | $1 \times 10^{-8}$ m/s<br>0.01 m/day  | $1 \times 10^{-8}$ m/s<br>0.001 m/day |
| Overburden K            | $5 \times 10^{-8}$ m/s<br>0.004 m/day | $1 \times 10^{-8}$ m/s<br>0.001 m/day |
| Coal and Interburden K  | $5 \times 10^{-5}$ m/s<br>0.45 m/day  | $1 \times 10^{-5}$ m/s<br>0.90 m/day  |
| Sandstone Floor K       | $5 \times 10^{-8}$ m/s<br>0.004 m/day | $1 \times 10^{-8}$ m/s<br>0.001 m/day |
| Belmont Fault Interface | $1 \times 10^{-5}$ m/s<br>0.86 m/day  | $1 \times 10^{-5}$ m/s<br>0.86 m/day  |

The calibrated recharge rates are very low, however this is consistent with the relatively steep slopes, arid climate and stability of the monitored groundwater levels, which showed little variation in response to rainfall recharge or to mining, however did respond to pumping.

The resulting head distributions are very similar and Case 1 is presented in Figure 8 below.




**Figure 8 - Calibrated Steady State Head Distribution in Layer 3  
(includes coal seams) for Case 1**




**Figure 9 - Modelled and Observed Heads for Case 1 Calibration**

When compared with the monitoring data from July 2008, the maximum residual head was 7.1 m with an absolute residual mean of 3.6 m and a correlation coefficient of 0.975. The model converged with a 0.01% discrepancy in the overall flow budget which is summarised in Table 9a below. Given the highly complex nature of the geology at the site, this is considered a good representation. The head distribution is also consistent with the conceptual model.

**Table 9a – Steady State Water Budget**

| Budget Component       | Rate (m <sup>3</sup> /d) |        |
|------------------------|--------------------------|--------|
|                        | Case 1                   | Case 2 |
| IN                     |                          |        |
| Constant Head          | 0                        | 0      |
| Recharge               | 1114.9                   | 286.21 |
| OUT                    |                          |        |
| Constant Head          | 1114.9                   | 286.19 |
| Recharge               | 0                        | 0      |
| Percentage Discrepancy | 0                        | 0.01   |

### 9.2.2 Sensitivity to Fault Permeability

For the cases above it was assumed that there was limited hydraulic conductivity across the faults, as per the conceptual model. In order to assess the possibility that the faults were in fact conduits for flow, a number of additional cases were modelled to assess the plausibility of the faults being conduits for flow. A number of sub-cases were assessed as follows:

- Case 1A – All faults high permeability
- Case 1B – western and northern faults high permeability
- Case 1C – only western fault high permeability

The faults were modelled with a hydraulic conductivity of  $1 \times 10^{-4}$  m/s.

For Case 1A, the presence of the faults resulted in heads to the east of the site being too low. If the recharge was then adjusted to increase the heads to the east, the heads in the coal seams below the site were too high. In essence, the high hydraulic gradient to the east of the mine could not be replicated. The resulting head distribution and correlations are presented in Figures 20 and 21 below.




**Figure 20 - Calibrated Steady State Head Distribution in Layer 3  
(includes coal seams) for Case 1A**




**Figure 21 - Modelled and Observed Heads for Case 1A Calibration**

For Case 1B the heads to the east of the site could be more closely replicated, however the heads in the coal seam were too high, and increasing the permeability of the fault lines actually made the heads higher rather than lower. This is because the strong hydraulic connection to the north alluvium resulted in the heads in the coal seam being more an average of the heads in the north and south alluvium, which is not the case. The resulting head distribution and correlations are presented in Figures 22 and 23 below.




**Figure 22 - Calibrated Steady State Head Distribution in Layer 3  
(includes coal seams) for Case 1B**




**Figure 23 - Modelled and Observed Heads for Case 1B Calibration**

For Case 1C, it was possible to gain a calibration close to, though not quite as good a fit as Case 1. Case 1C did not require any restriction in flow between the coal seams and eastern strata as it was offset by the additional connection to the southern alluvium. The resulting head distribution and correlations are presented in Figures 24 and 25 below.




**Figure 22 - Calibrated Steady State Head Distribution in Layer 3  
(includes coal seams) for Case 1C**




**Figure 23 - Modelled and Observed Heads for Case 1C Calibration**

Therefore Case 1C with a permeable fault to the west, connecting to the southern alluvium is considered a plausible alternative to Cases 1 and 2. The presence of permeable faults connecting to the alluvium to the east and/or north are considered implausible, based on an analysis of the data available.

## 9.3 Transient Modelling

### 9.3.1 Calibration

The results of groundwater monitoring during the first year of operation of the pit indicated minimal impact on water levels and generally no observable or only slight inflows to the pit. The level of excavation during this period ranged down to about RL 200, however more generally in the range RL 220 to RL 240, and an average drainage RL of about RL 230 was modelled.

The model was run in transient mode, simulating a 12 month period, to allow calibration to the observed changes in head. Daily time steps were used.

The pumping test data did not include observation wells and therefore no measurements of Storage Coefficients were available. Therefore typical storage coefficients were adopted, based on DPs experience with coal measures rocks. In the case of the composite coal and interburden layer the storage was based on a weighted average of a typical coal measures interburden ( $S_y=1\%$ ) and typical coal ( $S_y=5\%$ ). The adopted parameters are presented in Table 10 below.

**Table 10 - Adopted Storage Coefficients**

| Storage                | Specific Yield | Specific Storage   |
|------------------------|----------------|--------------------|
| Alluvium K             | 0.20           | $1 \times 10^{-4}$ |
| Volcanics K            | 0.01           | $1 \times 10^{-5}$ |
| Overburden K           | 0.01           | $1 \times 10^{-5}$ |
| Coal and Interburden K | 0.02           | $1 \times 10^{-5}$ |
| Sandstone Floor K      | 0.01           | $1 \times 10^{-5}$ |

The four cases were modelled as follows:

- Case 1 Upper Bound Permeability
- Case 1C Upper Bound Permeability with Permeable Western Fault
- Case 2 Lower Bound Permeability; and
- Case 2C Lower Bound Permeability with Permeable Western Fault

The resulting variations in head at each monitoring well are presented in Figures 10 and 11 below for Cases 1 and 2.




**Figure 10 - Calculated Heads during First Year of Mine Operation – Case 1**




**Figure 11 - Calculated Heads during First Year of Mine Operation – Case 2**

The observed changes in head versus the calibrated changes in head are presented in Table 11 below.

**Table 11 - Calibrated Drawdown at Monitoring Points in First Year**

| Monitoring Well | Observed | Case 1 | Case 1C | Case 2 | Case 2C | Comment                                                                           |
|-----------------|----------|--------|---------|--------|---------|-----------------------------------------------------------------------------------|
| MP01            | 0.3      | 0.2    | 0.01    | 0.01   | 0.02    |                                                                                   |
| MP02            | 0.35     | 1.2    | 2.86    | 0.63   | 1.02    |                                                                                   |
| MP03            | >0.9     | 0.03   | 0.19    | 0      | 0.05    | Incomplete data set. Drawdown is likely to be due to pumping of WB08              |
| MP04            | >1.5     | 0.01   | 0.02    | 0      | 0.01    | Incomplete data set. Drawdown is likely to be due to pumping of WB08              |
| MP05            | 1.5      | 3.4    | 1.94    | 0.68   | 0.2     |                                                                                   |
| WB01            | 0.1      | 0.01   | 0.01    | 0.01   | 0.01    | Incomplete data set                                                               |
| WB02            | 0.42     | 0.35   | 0.01    | 0.5    | 0.01    |                                                                                   |
| WB03            | 0.2      | 0.03   | 0.18    | 0.3    | 0.01    |                                                                                   |
| WB05            | 10       | 0.13   | 0.01    | 0      | 0.01    | Observed head variation likely to be due to pumping                               |
| WB06            | 0.84     | 0      | 0.01    | 0.06   | 0.01    | Observed head variation is unlikely to be due to mine, due to proximity from site |
| WB07            | 2.0      | 1.4    | 1.1     | 1.7    | 0.4     | Incomplete data set                                                               |
| WB08            | -14/-3   | 0.06   | 0.01    | 0      | 0.01    | Observed head variation likely to be due to pumping                               |
| WB09            | 0.2      | 0.02   | 0.02    | 0      | 0.01    |                                                                                   |
| WB10            | 0.85     | 0      | 0       | 0      | 0       |                                                                                   |
| WB12            | 0.2      | 0      | 0       | 0      | 0       |                                                                                   |

Table 11 above generally indicates that the monitoring data falls between the two cases, with some outliers, such as WB05 and WB08 which have atypical drawdown and are likely to be due to pumping from the wells.

WB-05 indicated a relatively large drawdown which isn't matched in other bores similar distances from the mining, such as MP-01. WB-05 was an existing registered water bore and is also in close proximity to EVK114, which has been converted to a bore used to provide water for dust suppression. It is considered likely that the drawdown in WB-05 is due to pumping from a well or well in the vicinity, and not due to the excavations associated with mining. It is also understood that more recent monitoring has indicated that the water level in WB-05 has returned to near pre-mining levels.

In January 2009, the groundwater level for Bore WB-08 was initially at about RL 235 m AHD, which is well below the regional level. It then rebounded to about RL 250 in June 2009, similar to regional water levels and then fell again to about RL 235 by February 2010. The water level in Bore WB-08 is currently at about RL 250. The varying nature of groundwater levels in this bore indicates that it is subject to the influence of intermittent pumping. The heads in MP-02 and MP-03, just to the north west of WB-08, also fell slightly for the period they were monitored and this is consistent with drawdown associated with WB-08.

The calibrated flows into the pit are presented in Table 12 below. The model assumes an instant drawdown occurs, however, in reality the mining occurs over a period and the drawdown is more gradual. As the model simulates instant drainage, the initial flow rates are over-estimated. Therefore the first 50 days of calculations has been ignored for the purpose of the flow assessment.

**Table 12 – Calibrated Flow in Pit During First Year of Operation**

| <b>Flow into Pit</b> | <b>Case 1</b>                      | <b>Case 1C</b>                     | <b>Case 2</b>                      | <b>Case 2C</b>                     |
|----------------------|------------------------------------|------------------------------------|------------------------------------|------------------------------------|
| Initial (50 days)    | 2850 m <sup>3</sup> /day<br>33 L/s | 2534 m <sup>3</sup> /day<br>29 L/s | 1656 m <sup>3</sup> /day<br>19 L/s | 1097 m <sup>3</sup> /day<br>13 L/s |
| Final (360 days)     | 1664 m <sup>3</sup> /day<br>19 L/s | 1641 m <sup>3</sup> /day<br>19 L/s | 607 m <sup>3</sup> /day<br>7 L/s   | 509 m <sup>3</sup> /day<br>6 L/s   |

Observations from the mine were that there was generally no seepage observed in the pit during this time, with some localised seepage on the eastern side where the excavation was deeper and in this instance the flow may have been in the order of about 20 L/s.

The model simulates an average drainage level, however due to the steep dip of the seams, the drainage level will vary and in cases where the mining is locally deeper, such as along the eastern side, the flow rates will be above the average and visa-versa. Therefore the Case 2/2C calculated flow rates are considered more consistent with site observations. Flows in the range 19 to 32 L/s, as calculated for Case 1 would be expected to have resulted in clearly evident flows much of the time.

Subsequent records from the mine indicate that 23ML has been pumped from the pit for the period August 2009 to July 2010 which is equivalent to 63 m<sup>3</sup>/day (0.7 L/s). Much of this is likely to have been from rainfall, which further supports that Case 2 conditions are more likely.

### 9.3.2 Predictive Modelling

The calibrated models were used to simulate flow rates and drawdowns for the future mine operations. The mining sequence was split into two periods as follows:

- Northern Mining Phase – to simulate mining in the northern parts of the pits which is anticipated to be from 2008 to 2015;
- Southern Mining Phase – to simulate mining in the southern parts of the pits which is anticipated to be from 2015 to 2020.

For the northern end of the pit the floor level of the Belmont Seam is in the range RL 180 to RL 240 and for purposes of the modelling an average drainage level of RL 210 was adopted.

The pit was modelled as a material with a high permeability of  $1 \times 10^{-4}$  m/s (8.6 m/day), commensurate with mine spoil. In order to assist with numerical stability a transition material was placed around the perimeter of the area with an intermediate permeability of  $1 \times 10^{-6}$  m/s (0.086 m/day). Figure 12 below provided the distribution of permeability used for layer 1.




**Figure 12 - Distribution of Permeability for Model Layer 1 for Northern Mining Phase**

The predicted drawdown in monitoring wells for Case 1 parameters over the Northern Mining Phase is presented in Figure 13 below.




**Figure 13 - Predicted Drawdowns for Northern Mining Phase - Case 1**

The predicted distribution of head in Layer 3 at end of Northern Mining Phase is shown in Figure 14.




**Figure 14 - Predicted Distribution of Head in Layer 3 at completion of Northern Mining Phase**

The predicted drawdown in monitoring wells for Case 2 parameters over the Northern Mining Phase is presented in Figure 15 below.




**Figure 15 - Predicted Drawdowns for Northern Mining Phase - Case 2**

The predicted drawdown in monitoring wells for Case 1 parameters over the Southern Mining Phase is presented in Figure 16 below.





**Figure 16 - Predicted Drawdowns for Southern Mining Phase - Case 1**

The predicted distribution of head in Layer 3 for Case 1 at the completion of the Southern Mining Phase (end of all mining) is shown in Figure 17 below.



Hydrogeological Assessment for Rocglen Coal Mine  
Extension Project  
Rocglen Coal Mine Via Gunnedah




**Figure 18 - Predicted Drawdowns for Southern Mining Phase - Case 2**

The predicted distribution of head in Layer 3 for Case 2 at the completion of the Southern Mining Phase (end of all mining) is shown in Figure 19 below.



**Table 13 - Predicted Drawdown at Monitoring Points (m)**

| Monitoring Well | Case 1 (Case 1C)             |                    | Case 2 (Case 2C)             |                       |
|-----------------|------------------------------|--------------------|------------------------------|-----------------------|
|                 | End of Northern Mining Phase | End Southern Phase | End of Northern Mining Phase | End of Southern Phase |
| MP-01           | 2.2 (1.9)                    | 3.0 (5.2)          | 0.5 (0.5)                    | 0.6 (3.7)             |
| MP-02           | 7.4 (6.5)                    | 27.8 (30.0)        | 4.0 (3.2)                    | 24.3 (32.1)           |
| MP-03           | 0.5 (1.8)                    | 0.65 (2.4)         | 0.1 (0.6)                    | 0.2 (1.4)             |
| MP-04           | 0.2 (0.1)                    | 0.3 (1.9)          | 0.1 (0.2)                    | 0.1 (1.0)             |
| MP-05           | 13.4 (8.7)                   | 21.2 (24.7)        | 6.2 (2.7)                    | 22.9 (9.9)            |
| WB-01           | 0.1 (0.1)                    | 0.1 (0.1)          | 0.1 (0.1)                    | 0.1 (0.1)             |
| WB-02           | 0.7 (0.6)                    | 1.0 (0.7)          | 0.5 (0.4)                    | 0.8 (0.3)             |
| WB-03           | 0.9 (0.6)                    | 1.1 (1.9)          | 0.3 (0.1)                    | 0.5 (0.3)             |
| WB-05           | 2.5 (2.8)                    | 3.2 (5.4)          | 0.5 (0.5)                    | 0.7 (1.6)             |
| WB-06           | 0.6 (0.6)                    | 0.7 (1.7)          | 0.1 (0.1)                    | 0.2 (0.1)             |
| WB-07           | 2.9 (3.3)                    | 12.9 (20.9)        | 3.3 (1.3)                    | 13.2 (14.0)           |
| WB-08           | 0.7 (0.4)                    | 0.9 (2.1)          | 0.1 (0.1)                    | 0.1 (0.3)             |
| WB-09           | 0.3 (0.4)                    | 0.4 (2.3)          | 0.1 (0.1)                    | 0.1 (0.2)             |
| WB-10           | 0.1 (0.1)                    | 0.1 (0.1)          | 0.1 (0.1)                    | 0.1 (0.1)             |
| WB-12           | 0.1 (0.1)                    | 0.1 (0.1)          | 0.1 (0.1)                    | 0.1 (0.1)             |

Table 13 indicates high drawdowns in close proximity to the mine site, up to about 30 m near MP-02 and MP-05, with relatively low impacts to the east of the faulting. The predicted impacts on the alluvium are also low, however are slightly higher in the alluvium immediately south of the pit in the case that a permeable fault was present to the west of the site. The extent of the impacts on groundwater head are expected to be less than previously predicted by RCA (2007) for areas outside the area of faulting.

It is noted that the geology at the site is very complex and actual drawdowns may vary somewhat from those predicted. An ongoing monitoring programme is important to allow measurement of the ongoing impacts and further development of the groundwater model. Comments on groundwater monitoring are provided in Section 10.

Table 14 below presents the predicted flow rates into the pit for current, end of Northern Mining Phase and end of Southern Phase. The table also includes the estimated interference that the mine drainage will have on base flows into the alluvium.

**Table 14 - Modelled Pit Inflows**

| Time                         | Case 1 – Flow Components (m <sup>3</sup> /day)<br>(Case 1C – Permeable Faulting) |                            |                                 | Case 2 – Flow Components (m <sup>3</sup> /day)<br>(Case 2C – Permeable Faulting) |                            |                                 |
|------------------------------|----------------------------------------------------------------------------------|----------------------------|---------------------------------|----------------------------------------------------------------------------------|----------------------------|---------------------------------|
|                              | Into Pit                                                                         | Storage loss from Alluvium | Reduction of flow in Alluvium** | Into Pit                                                                         | Storage loss from Alluvium | Reduction of flow in Alluvium** |
| Initial (50 days)*           | 2850 (2534)                                                                      | 189 (611)                  | 1                               | 1656 (1097)                                                                      | 66 (136)                   | <1                              |
| 2009                         | 1664 (1641)                                                                      | 419 (833)                  | 4                               | 607 (509)                                                                        | 70 (254)                   | <1                              |
| End of Northern Mining Phase | 1105 (1326)                                                                      | 518 (809)                  | 52 (30)                         | 491 (516)                                                                        | 106 (243)                  | 6 (2)                           |
| End of Southern Mining Phase | 2614 (3381)                                                                      | 1206 (1932)                | 191 (187)                       | 1057 (1504)                                                                      | 270 (751)                  | 37 (25)                         |

Notes: \* assumes instant excavation and over-estimates initial flow rates

\*\* measured at constant head boundaries

Flow rates are generally expected to decrease as mining continues in the northern end of the pit, however are expected to increase as the mining progresses to the southern end of the pit, due to the increased area of the pit and because the flow is less restricted by the faulting at the northern end of the pit. The variations in flow between the various years will be less distinct than those predicted as the modelling assumed three distinct stages of mining, however in reality the sequencing will be gradual.

As the floor of the Belmont Seam ranges in elevation, the flow rates into the pit will vary according to the depth of the seam. For areas where the seam floor is about RL 210, mostly on the central parts of the proposed mining extent, the flows can be expected to be less than the average predicted values and will probably generally not be visible in the pit due to evaporative effects. For deeper parts of the excavation the flow rates can be expected to be higher and free flow into the pit can be expected.

The predicted impact on flows in the alluvium, as measured from the reduction in flows to the constant head boundaries, is minor as most of the flow comes from storage, however as the life of the mine increases the influence of storage reduces and the impact of flows to the alluvium increases slightly. Impacts on storage in the alluvium occur in close proximity to the mine and the percentage contribution to the inflow to the mine from storage depends on the presence of permeable faulting to the west of the site. For possible permeable faulting to the west of the site or for the higher ranges of permeability with no faulting, the component of flow from alluvial storage is initially low and then ranges up to about 50%. For the more likely Case 2, with lower permeability and limited permeability faulting to the west of the site, the component ranges up to about 25%. The impact on flows/storage in the alluvium is primarily to the southern alluvium (at least 90%) as the northern alluvium is up gradient and essentially hydraulically separated.

The range of possible inflows to the pit, based on the credible range of parameters, ranges from 1057 to 3381 m<sup>3</sup>/day. Overall, the predictions for Case 1 are similar to the predictions of the previous modelling by RCA (2007), however based on site observations to date it is considered that the Case 2 flows are more likely to occur. Therefore it is unlikely that the annual flow rates into the pit will exceed the existing groundwater interference licence of 700ML/yr (1918m<sup>3</sup>/day). It is noted however that there is some uncertainty in the site conditions, in particular to the south west of the site, and flows greater than 700 ML/yr may be possible if adverse conditions occur. Therefore a robust ongoing monitoring program and updating of the predictive model are recommended as mining continues.

#### 9.4 Mine Closure

It is understood that the majority of the pit will be backfilled to an elevation above 250 m AHD, with the exception of an area of about 38 ha in the southern side of the pit where the surface levels will be in the range RL 225 to RL 250. It is expected that once mining is complete, recharge of groundwater and rainfall infiltration into the pit will result in the formation of a water table within the backfill. It is likely that this will eventually lead to the formation of surface water in the southern part of the pit with the locally deeper final surface level.

The inflow to the pit will be offset by evaporation from the area of surface water and therefore it is unlikely that the groundwater levels within the pit will ever fully recover to pre-development levels. It is estimated that the final equilibrium water levels will range between RL 220 and RL 245, however this may take 20 to 50 years to occur and would also be subject to variations according to climatic conditions.

The existing groundwater in the Maules Creek Formation is generally brackish with total dissolved solids in the range 1000 to 5130 mg/L. In general, the pore water in the backfilled mine spoil is expected to become less saline over time due to the percolation of rainfall through the spoil pile. The exception to this will be in the area of surface water in the non-backfilled portion of the pit. In this location, the salinity is expected to increase over time as the evaporation leads to reduction in water volume and leaves the dissolved salt behind. The increase in concentration is expected to be generally isolated to the surface water in the locally deep area, with some minor mixing with the adjacent pore water in the mine spoil.

Consideration was given to raising the backfill levels such that surface water is never formed within the pit, thereby reducing evaporation and associated increase in salinity over time. Calculations indicate that a final fill level of about RL 275 m AHD is required to prevent surface water ever occurring. This level is above the pre-development groundwater level because the mine spoil will be relatively permeable and porous, and recharge rates into the mine spoil will be substantially higher than for the surrounding undisturbed ground. Such a high final ground level, well above pre-development groundwater levels, is understood to be impractical from a mine spoil management perspective.

It is considered that, although the proposed final void form will, over time, lead to increasing salt concentrations in the localised area of surface water within the final void, this will be of minimal impact outside the final void for the following reasons:

- The final void will behave as a groundwater sink. Therefore any increases in salinity within the sink will not affect the surrounding groundwater quality as the flow will be towards the area of higher salinity and not away from it;
- The surface water level at equilibrium will be well below surrounding groundwater levels; and
- The surface water will be located within a small final void with relatively steep sloping sides. This small area will be unsuitable for alternative land uses which would be sensitive to the potential saline surface water.

## 10. Conclusions and Recommendations

The groundwater investigation documented in this report has been undertaken in support of an application for expansion of the Rocglen Coal Mine, near Gunnedah in North West NSW. This hydrogeological assessment of the area around the mine is aimed at evaluating the potential impact of the expanded mine on the groundwater system, and assessing the quantum of groundwater inflow that is likely to occur.

Data relied upon for this investigation included previous study reports, topographic and geographic mapping, information from the NSW Office of Water, coal exploration drilling data provided by WHC, and information from a groundwater monitoring program undertaken by WHC since the commencement of mining in mid 2008.

The Conceptual Hydrogeological Model (CHM) derived by RCA (2002) and RCA (2007) has been confirmed and updated. A revised numerical groundwater flow model has been structured and calibrated in order to assess impact on the surrounding groundwater system and assess the quantum of groundwater seepage that may occur into the pit.

### **Study Findings**

The results of the investigation are summarised as follows:

- Rocglen Coal Mine is located within the Maules Creek Formation of Permian age and mines coal from the Glenroc Seams (Upper and Lower) and (mainly) from the Belmont Seam. The Belmont Seam averages about 8 m in thickness;
- Rocglen Coal Mine is situated within a narrow valley between elevated topography of the Vickery State Forest to the west and the Community Conservation Area (CCA) Zone 2 – Kelvin to the east. Rocglen Coal Mine is situated on a saddle, with the land slightly sloping to the north and to the south;
- Alluvium associated with the Namoi River and tributaries borders ML 1620 to the north and also exists approximately 2 km south and southwest of the limit of the proposed expanded open cut. The NSW Office of Water is concerned about the potential for mining to impact on significant groundwater resources within the alluvium associated with the Namoi River and tributaries;

- A number of private bores have been identified within a 5 km distance of the mine. Some of these bores draw water from the alluvium, but most in close proximity to the mine draw water from the coal seams and sandstone / conglomerate intervals of the Maules Creek Formation;
- Groundwater resources in the region are utilised primarily for stock watering;
- The geology in close proximity to the mine is disturbed by folding and faulting, thereby complicating the groundwater flow regime. The Mooki Thrust which forms the margin of the Gunnedah Basin, is located only a few kilometres east of the mine. Several smaller faults with near vertical displacements of up to 150 m surround the mine;
- Within the Maules Creek Formation, groundwater is more prevalent in the coal seams than in the intervening interburden sediments. Hydraulic testing shows that the hydraulic conductivity of the coal seams is at least an order of magnitude greater than that of the interburden sandstone, conglomerate, siltstone and shale;
- An analysis of monitoring data shows that to date, the mine has had little effect on surrounding groundwater levels. Drawdown has been proportionately less than was predicted by the numerical modelling of RCA (2007). Similarly, recorded inflows have been much less than the seepage volumes predicted by the RCA (2007) modelling;
- Long-term average monthly rainfall data show that rainfall is relatively evenly distributed throughout the year, with slightly more rainfall occurring during the summer months. Evaporation greatly exceeds rainfall during most months, however it is almost balanced by rainfall during the winter months of June and July;
- Recharge of the groundwater system is small. No recharge events of significance are noted in groundwater hydrographs since mid 2008, despite some considerable rainfalls being recorded during that period;
- Laboratory analysis of groundwater samples shows that quality is spatially highly variable. This is probably a function of the amount of faulting in the area restricting groundwater flow; and
- Based on the conceptual hydrological model it is considered that drawdown on the surrounding groundwater system as a result of the expanded mining operation will be limited in the future. Because of the many faults in the vicinity of the mine and generally low permeability of the Maules Creek Formation strata, hydraulic connectivity with the alluvium is considered to be limited. It is possible that the faulting to the west of the site has some elevated permeability and in this case slightly increased drawdowns could occur in the southern alluvium, however this would still be expected to be no more than about 2 m near the pit to minimal impact to the south of the pit.

A revised numerical groundwater flow model has been calibrated in steady state to match groundwater levels recorded in July 2008. There is a reasonable degree of replication of the pre-mining groundwater levels by the model, particularly considering the geological complexity in the vicinity of the mine.

In transient mode, the revised model simulates observed changes in head reasonably well, apart from a few instances in which recorded groundwater levels may be related to local pumping.

The revised numerical model has been used to assess the likely impact of Rocglen Mine to the end of mine life, which is anticipated to be around 10 years following commencement of the expanded operation (at this point in time, this is considered year 2020). Modelling results suggest that groundwater levels will be drawn down ~30 m in close proximity to the pit, but that drawdown will be mostly limited to within the fault block which surrounds the mine. Relatively little drawdown is predicted to occur outside the faults.

Average inflows to the pit going forward are expected to be lower than previously modelled by RCA (2007). Depending on the permeability case value adopted, inflows are expected to be of the order of 6 L/s to 15 L/s mid way through the project (Year 5 of expanded operation, which is anticipated to be year 2015), and between 13 L/s and 40 L/s at the end of mining (anticipated to be around 10 years following commencement of the expanded operation, which, at this point in time, is thought to be year 2020).

Final water levels within the pit are expected to be equilibrate at about RL RL220 to RL245 AHD and would be expected to take about 20 to 50 years to occur. Some increase in salinity will occur in surface water in the remnant pit due to evaporative effects, however this would be expected to have very limited impact on the surrounding land and groundwater.

### **Recommendations**

Groundwater monitoring undertaken since 2008 has been based on available existing bores in proximity to the mine site and several established bores for monitoring purposes. Whilst this extent of monitoring has allowed review of impacts for the purposes of this assessment, DP recommends the following actions to improve monitoring outcomes moving forward:

- The aquifer interval monitored by each of the bores is not known with certainty. Bores should be cleaned out (air-lift developed) and depth checked with a weighted tape. Bores should then be geophysically wireline logged (SP/SPR and Gamma) to confirm slotted intervals and the nature of the strata over slotted intervals;
- All monitoring bores should be surveyed for location and level (both ground level and the level of the Reference Point (RP) from which groundwater levels are measured);
- Monitoring of groundwater levels should initially be undertaken on a monthly basis for the first year of the expansion, after which the monitoring interval could potentially be relaxed subject to review of the results. In the longer term a monitoring interval of three months is anticipated. The monitoring should be undertaken in the first week of the nominated month. The frequency of groundwater sampling and laboratory analysis of water samples should remain as is. Water samples should be analysed for all major ions, including carbonate; and
- Pressure transducers/dataloggers should be installed in monitoring bores MP-01 to MP-05 for the continual recording of groundwater levels. These instruments should be downloaded every 2 months. In the case of MP-04 and MP-05, these wells only just intersected the water table when installed and have been observed to run dry. It is recommended that these bores be deepened to at least 10 m below the water table.

The above improvements to the groundwater monitoring regime will facilitate easier upgrading of the current groundwater flow model at a later date.

In order to address the concerns of the NSW Office of Water in regard to the potential for impact on alluvial aquifers of the Namoi River and associated tributaries, the following program of investigations is recommended:

- Bore MP-4 is nominally located within the alluvium south of the mine. Once this is confirmed through the activity recommended above, a second bore should be drilled adjacent to it, to a depth at which the base of the alluvium is intersected. This adjacent bore should be completed as a monitoring bore in the Maules Creek Formation and have a pressure transducer/datalogger installed for continuous water level monitoring; and
- Bore WB-01 is located within the alluvium north of the mine. Once this is confirmed through the activity recommended above, a second bore should be drilled adjacent to it, to a depth at which the base of the alluvium is intersected. This adjacent bore should be completed as a monitoring bore in the Maules Creek Formation and have a pressure transducer/datalogger installed for continuous water level monitoring. Such actions will need to be agreed to by the relevant landowners;
- There is some uncertainty regarding the nature of the interface between the southern alluvium and the weathered conglomerate profile of the Maules Creek Formation at the southern end of the proposed pit. It is recommended that a pair of piezometers be installed immediately to the south of the proposed pit, one in the Belmont Seam and one in the alluvium/weathered conglomerate. It is also recommended that hydraulic testing be undertaken on the bore in the alluvium/weathered conglomerate to allow refinement of the groundwater model in this regard.

Regular monitoring of both MP-4 and WB-01, the new piezometers immediately to the south of the pit, and their adjacent bores will assist in assessing the degree of hydraulic connection between the Maules Creek Formation and the alluvial aquifer.

## 11. References

1. **Cooper, H. H., & Jacob, C. E., 1946:** A Generalized Graphical Method for Evaluating Formation Constants and Summarizing Well Field History. Transactions of the American Geophysical Union. Vol. 27, pp. 526 - 534.
2. **Hvorslev, M. J., 1951:** Time Lag and Soil Permeability in Ground-Water Observations, U.S. Army Corps of Engineers. Waterways Experiment Station. Vicksburg, Mississippi. Bulletin No. 36, pp. 1-50.
3. **Land & Water Biodiversity Committee, 2003:** Minimum Construction Requirements for Water Bores in Australia. Edition 2. Revised September 2003. ISBN 1 9209 2009 9. QNRM04027.
4. **McDonald, M. G., & Harbaugh, A. W., 1988:** A modular three-dimensional finite-difference ground-water flow model. USGS Techniques of Water Resources Investigations, Book 6, Chapter A1. Washington DC.
5. **McElroy Bryan Geological Services Pty Ltd., 1993:** Exploration Report - Exploration Licence 4501, East Vickery Area, Gunnedah NSW. Report prepared for Novacoal Australia Pty Ltd. Report No 129/4/2. October, 1993.

6. **McElroy Bryan Geological Services Pty Ltd., 1994:** Exploration Report - Exploration Licence 4501, East Vickery Area, Gunnedah NSW. Report prepared for Novacoal Australia Pty Ltd. Report No 129/4/3. December 1994.
7. **Raymond, O. L., Liu, S. F., Kilgour, P., Retter, A. J., Stewart, A. J., & Stewart, G., 2007:** Surface Geology of Australia 1:1,000,000 scale, New South Wales 2nd edition [Digital Dataset] Canberra. The Commonwealth of Australia, Geoscience Australia website. <http://www.ga.gov.au>.
8. **Robert Carr & Associates Pty Ltd., 2002:** Groundwater Assessment Proposed Belmont Mine near Boggabri. Report prepared for Whitehaven Coal Mining Limited. Report 3065-001. October 2002.
9. **Robert Carr & Associates Pty Ltd., 2007:** Groundwater Impact Assessment of the Belmont Coal Project via Gunnedah. Report prepared for R.W. Corkery & Co. Pty Limited on behalf of Whitehaven Coal Mining Pty Ltd. Report No. 584/02. August 2007.
10. **Robert Carr & Associates Pty Ltd., 2008:** Site Water Management Plan for the Rocglen Coal Mine. Prepared in conjunction with the Soil Conservation Service of NSW Department of Lands for Whitehaven Coal Mining Pty Ltd.

## 12. Limitations

Douglas Partners Pty Ltd (DP) has prepared this report for a project at Rocglen Coal Mine, Gunnedah in accordance with DP's proposal dated 23 December 2009 and acceptance received from Whitehaven Coal Limited dated 29 January 2010. The report is provided for the exclusive use of GSS Environmental and Whitehaven Coal Limited for this project only and for the purpose(s) described in the report. It should not be used for other projects or by a third party. In preparing this report DP has necessarily relied upon information provided by the client and/or their agents.

The results provided in the report are indicative of the sub-surface conditions only at the specific sampling or testing locations, and then only to the depths investigated and at the time the work was carried out. Sub-surface conditions can change abruptly due to variable geological processes and also as a result of anthropogenic influences. Such changes may occur after DP's field testing has been completed.

DP's advice is based upon the conditions encountered during this investigation. The accuracy of the advice provided by DP in this report may be limited by undetected variations in ground conditions between sampling locations. The advice may also be limited by budget constraints imposed by others or by site accessibility.

This report must be read in conjunction with all of the attached notes and should be kept in its entirety without separation of individual pages or sections. DP cannot be held responsible for interpretations or conclusions made by others unless they are supported by an expressed statement, interpretation, outcome or conclusion given in this report.

---

**Douglas Partners Pty Ltd**

---

## Appendix A

---

About this Report

# About this Report

# Douglas Partners



## Introduction

These notes have been provided to amplify DP's report in regard to classification methods, field procedures and the comments section. Not all are necessarily relevant to all reports.

DP's reports are based on information gained from limited subsurface excavations and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

## Copyright

This report is the property of Douglas Partners Pty Ltd. The report may only be used for the purpose for which it was commissioned and in accordance with the Conditions of Engagement for the commission supplied at the time of proposal. Unauthorised use of this report in any form whatsoever is prohibited.

## Borehole and Test Pit Logs

The borehole and test pit logs presented in this report are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable or possible to justify on economic grounds. In any case the boreholes and test pits represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes or pits, the frequency of sampling, and the possibility of other than 'straight line' variations between the test locations.

## Groundwater

Where groundwater levels are measured in boreholes there are several potential problems, namely:

- In low permeability soils groundwater may enter the hole very slowly or perhaps not at all during the time the hole is left open;

- A localised, perched water table may lead to an erroneous indication of the true water table;
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report; and
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water measurements are to be made.

More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from a perched water table.

## Reports

The report has been prepared by qualified personnel, is based on the information obtained from field and laboratory testing, and has been undertaken to current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal, the information and interpretation may not be relevant if the design proposal is changed. If this happens, DP will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical and environmental aspects, and recommendations or suggestions for design and construction. However, DP cannot always anticipate or assume responsibility for:

- Unexpected variations in ground conditions. The potential for this will depend partly on borehole or pit spacing and sampling frequency;
- Changes in policy or interpretations of policy by statutory authorities; or
- The actions of contractors responding to commercial pressures.

If these occur, DP will be pleased to assist with investigations or advice to resolve the matter.

# *About this Report*

## **Site Anomalies**

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, DP requests that it be immediately notified. Most problems are much more readily resolved when conditions are exposed rather than at some later stage, well after the event.

## **Information for Contractual Purposes**

Where information obtained from this report is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a specially edited document. DP would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

## **Site Inspection**



The company will always be pleased to provide engineering inspection services for geotechnical and environmental aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.

---


## **Appendix B**

---

Hydrographs of Groundwater Levels for Rocglen Mine Monitoring Bores




|                                                                                                                                                                                          |  |                                                                                  |                                                                                  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br><i>Geotechnics • Environment • Groundwater</i>                          |  | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| <b>TITLE:</b> HYDROGRAPHS FOR BORES MP-01, MP-02, MP-03, MP-04 & MP-05<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |  |                                                                                  |                                                                                  |
| <b>CLIENT:</b> GSS ENVIRONMENTAL                                                                                                                                                         |  |                                                                                  | <b>OFFICE:</b> NEWCASTLE                                                         |
| <b>DRAWN BY:</b> AP                                                                                                                                                                      |  | <b>PROJECT NO:</b> 49532.00                                                      | <b>DRAWING NO:</b> A-1                                                           |
| <b>APPROVED:</b>                                                                                                                                                                         |  | <b>DATE:</b> Nov 2010                                                            |                                                                                  |




- + + + **Monitoring Bore WB-01**
- ◆ ◆ ◆ **Monitoring Bore WB-02**
- ■ ■ **Monitoring Bore WB-03**
- ● ● **Monitoring Bore WB-05**
- ▲ ▲ ▲ **Monitoring Bore WB-06**

|                                                                                                                                                                                          |  |                                                                                  |                                                                                  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br><i>Geotechnics • Environment • Groundwater</i>                          |  | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| <b>TITLE:</b> HYDROGRAPHS FOR BORES WB-01, WB-02, WB-03, WB-05 & WB-06<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |  |                                                                                  |                                                                                  |
| <b>CLIENT:</b> GSS ENVIRONMENTAL                                                                                                                                                         |  |                                                                                  | <b>OFFICE:</b> NEWCASTLE                                                         |
| <b>DRAWN BY:</b> AP                                                                                                                                                                      |  | <b>PROJECT NO:</b> 49532.00                                                      | <b>DRAWING NO:</b> A-2                                                           |
| <b>APPROVED:</b>                                                                                                                                                                         |  | <b>DATE:</b> Nov 2010                                                            |                                                                                  |




- + + + **Monitoring Bore WB-01**
- ◆ ◆ ◆ **Monitoring Bore WB-02**
- ■ ■ **Monitoring Bore WB-03**
- ● ● **Monitoring Bore WB-05**
- ▲ ▲ ▲ **Monitoring Bore WB-06**

|                                                                                                                                                                                          |  |                                                                                  |                                                                                  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br><i>Geotechnics • Environment • Groundwater</i>                          |  | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| <b>TITLE:</b> HYDROGRAPHS FOR BORES WB-01, WB-02, WB-03, WB-05 & WB-06<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |  |                                                                                  |                                                                                  |
| <b>CLIENT:</b> GSS ENVIRONMENTAL                                                                                                                                                         |  |                                                                                  | <b>OFFICE:</b> NEWCASTLE                                                         |
| <b>DRAWN BY:</b> AP                                                                                                                                                                      |  | <b>PROJECT NO:</b> 49532.00                                                      | <b>DRAWING NO:</b> A-2                                                           |
| <b>APPROVED:</b>                                                                                                                                                                         |  | <b>DATE:</b> Nov 2010                                                            |                                                                                  |



- + + + Monitoring Bore WB-07**
- ◆ ◆ ◆ Monitoring Bore WB-08**
- ■ ■ Monitoring Bore WB-09**
- ● ● Monitoring Bore WB-10**
- ▲ ▲ ▲ Monitoring Bore WB-11**

|                                                                                                                                                                                          |  |                                                                                  |                                                                                  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br><i>Geotechnics • Environment • Groundwater</i>                          |  | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| <b>TITLE:</b> HYDROGRAPHS FOR BORES WB-07, WB-08, WB-09, WB-10 & WB-11<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |  |                                                                                  |                                                                                  |
| <b>CLIENT:</b> GSS ENVIRONMENTAL                                                                                                                                                         |  |                                                                                  | <b>OFFICE:</b> NEWCASTLE                                                         |
| <b>DRAWN BY:</b> AP                                                                                                                                                                      |  | <b>PROJECT NO:</b> 49532.00                                                      | <b>DRAWING NO:</b> A-3                                                           |
| <b>APPROVED:</b>                                                                                                                                                                         |  | <b>DATE:</b> Nov 2010                                                            |                                                                                  |



Monitoring Bore WB-12  
 Yarrari Bore  
 Wundurra Bore

|                                                                                                                                                                                 |  |                                                                                  |                                                                                  |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| <b>Douglas Partners</b><br>Geotechnics • Environment • Groundwater                                                                                                              |  | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| <b>TITLE:</b> HYDROGRAPHS FOR BORES WB-12, YARRARI & WUNDURRA<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |  |                                                                                  |                                                                                  |
| <b>CLIENT:</b> GSS ENVIRONMENTAL                                                                                                                                                |  | <b>OFFICE:</b> NEWCASTLE                                                         |                                                                                  |
| <b>DRAWN BY:</b> AP                                                                                                                                                             |  | <b>PROJECT NO:</b> 49532.00                                                      | <b>DRAWING NO:</b> A-4                                                           |
| <b>APPROVED:</b>                                                                                                                                                                |  | <b>DATE:</b> Nov 2010                                                            |                                                                                  |

---

## Appendix C

---

Groundwater Quality and ANZECC (200) Guidelines Values

**Table B-1: Summary Chemical Analyses for Groundwaters – Rocglen Coal Mine**

| <b>Bore ID</b>                                                   | <b>MP-01</b> | <b>MP-02</b> | <b>WB-01</b> | <b>WB-02</b> | <b>WB-03</b> | <b>WB-05</b> | <b>WB-07</b> | <b>DW GV's</b> | <b>CW GV's</b> |
|------------------------------------------------------------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|----------------|----------------|
| <b>Field Parameters</b>                                          |              |              |              |              |              |              |              |                |                |
| pH - Field                                                       | 7.7          | 7.1          | 7.9          | 7.8          | 7.5          | 7.0          | 7.3          | 6.5 - 8.0      | -              |
| EC - Field - $\mu\text{S}/\text{cm}$                             | 2290         | 4875         | 1995         | 2885         | 3920         | 7070         | 2710         | 2200           | -              |
| <b>General Parameters</b>                                        |              |              |              |              |              |              |              | -              | -              |
| pH - Lab                                                         | 7.9          | 7.0          |              |              | 7.7          | 7.3          | 7.3          | 6.5 - 8.0      | -              |
| EC - Lab - $\mu\text{S}/\text{cm}$                               | 2230         | 4695         |              | 3050         | 3985         | 7420         | 2460         | 2200           | -              |
| Total Dissolved Solids                                           |              |              | 1050         | 2030         | 2690         | 5130         | 1500         | 1000           | -              |
| Alkalinity - $\text{mg}/\text{L}$                                | 726          | 514          | 483          | 427          | 384          | 537          | 506          | -              | -              |
| <b>Major Ions</b>                                                |              |              |              |              |              |              |              |                | -              |
| Sodium (Na) - $\text{mg}/\text{L}$                               | 451          | 589          | 388          | 278          | 377          | 1008         | 390          | 180            | -              |
| Potassium (K) - $\text{mg}/\text{L}$                             | 4            | 6            | 4            | 4            | 2            | 9            | 4            | -              | -              |
| Calcium (Ca) - $\text{mg}/\text{L}$                              | 40           | 225          | 9            | 206          | 246          | 305          | 111          | -              | 1000           |
| Magnesium (Mg) - $\text{mg}/\text{L}$                            | 28           | 137          | 12           | 112          | 188          | 279          | 60           | -              | -              |
| Chloride (Cl) - $\text{mg}/\text{L}$                             | 227          | 1269         | 286          | 807          | 1233         | 2453         | 568          | 250            | -              |
| Carbonate Alkalinity as $\text{CaCO}_3$ - $\text{mg}/\text{L}$   | <1           | <1           | <1           | <1           | <1           | <1           | <1           | -              | -              |
| Bicarbonate Alkalinity as $\text{CaCO}_3$ - $\text{mg}/\text{L}$ | 726          | 514          | 483          | 427          | 384          | 537          | 506          | -              | -              |
| Sulfate ( $\text{SO}_4$ ) - $\text{mg}/\text{L}$                 | 83           | 42           | 30           | 17           | 24           | 73           | 27           | 250            | 1000           |
| <b>Nutrients</b>                                                 |              |              |              |              |              |              |              |                |                |
| Ammonia as Nitrogen (N)                                          | <0.01        | 0.02         | 1.23         | 0.13         | 0.12         | 0.12         | 1.40         | 0.5            | -              |
| Nitrite as N ( $\text{mg}/\text{L}$ )                            | <0.01        | <0.01        |              |              | <0.01        | <0.01        | 0.09         | 3              | 30             |
| Nitrate as N ( $\text{mg}/\text{L}$ )                            | 0.17         | 0.60         |              |              | 3.78         | 2.23         | 5.94         | 50             | 400            |
| NOX as N ( $\text{mg}/\text{L}$ )                                | 0.17         | 0.60         |              |              | 3.78         | 2.23         | 6.03         | -              | -              |

| <b>Bore ID</b>        | <b>MP-01</b> | <b>MP-02</b> | <b>WB-01</b> | <b>WB-02</b> | <b>WB-03</b> | <b>WB-05</b> | <b>WB-07</b> | <b>DW GVs</b> | <b>CW GVs</b> |
|-----------------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|
| <b>Metals</b>         |              |              |              |              |              |              |              |               |               |
| Aluminium (Al) - mg/L | <0.01        | <0.01        |              | <0.01        | <0.01        | <0.01        | <0.01        | <b>0.2</b>    | <b>5</b>      |
| Arsenic (As) - mg/L   | <b>0.009</b> | 0.001        | <b>0.018</b> | 0.003        | 0.002        | <0.001       | 0.002        | <b>0.007</b>  | <b>0.5</b>    |
| Barium (Ba) - mg/L    | 0.148        | 0.692        | 0.355        | 0.128        | 0.009        | 0.164        | 0.637        | <b>0.7</b>    | <b>1</b>      |
| Beryllium (Be) - mg/L | <0.001       | <0.001       | <0.001       | <0.001       | <0.001       | <0.001       | <0.001       | -             | -             |
| Cadmium (Cd) - mg/L   | 0.0001       | 0.0001       | 0.0001       | <0.0001      | 0.0004       | 0.0002       | <0.0001      | <b>0.002</b>  | <b>0.01</b>   |
| Chromium (Cr) - mg/L  | 0.006        | 0.006        | <0.001       | 0.001        | 0.050        | <0.001       | <0.001       | <b>0.05</b>   | <b>1</b>      |
| Cobalt (Co) - mg/L    | 0.002        | 0.002        | <0.001       | <0.001       | 0.001        | <0.001       | <0.001       | -             | <b>1</b>      |
| Copper (Cu) - mg/L    | 0.006        | 0.010        | 0.009        | 0.072        | 0.018        | 0.002        | 0.020        | <b>2</b>      | -             |
| Iron (Fe) - mg/L      | <b>1.0</b>   | <b>3.1</b>   | <b>8.7</b>   | <b>10.1</b>  | 0.3          | <b>1.4</b>   | 0.1          | <b>0.3</b>    | -             |
| Lead (Pb) - mg/L      | 0.004        | 0.009        | <b>0.027</b> | <b>0.012</b> | 0.003        | <0.001       | <0.001       | <b>0.01</b>   | <b>0.1</b>    |
| Manganese (Mn) - mg/L | <b>0.273</b> | <b>0.150</b> | 0.045        | <b>0.418</b> | 0.011        | <b>0.250</b> | 0.010        | <b>0.1</b>    | -             |
| Mercury (Hg) - mg/L   | <0.0001      | <0.0001      | <0.0001      | <0.0001      | <0.0001      | <0.0001      | <0.0001      | <b>0.001</b>  | <b>0.002</b>  |
| Nickel (Ni) - mg/L    | <b>0.120</b> | <b>0.084</b> | <b>0.045</b> | 0.017        | 0.012        | <b>0.090</b> | 0.012        | <b>0.02</b>   | <b>1</b>      |
| Vanadium (V) - mg/L   | <0.01        | 0.010        | <0.01        | 0.035        | 0.040        | <0.01        | 0.020        | -             | -             |
| Zinc (Zn) - mg/L      | 0.042        | 0.049        | 1.190        | 0.672        | 0.078        | 0.078        | 0.042        | <b>3</b>      | <b>20</b>     |

**Table B-1: Summary Chemical Analyses for Groundwaters – Rocglen Coal Mine (Cont'd)**

| Bore ID                                                          | WB-08 | WB-09 | WB-10 | WB-11 | WB-12 | Yarri PB | DW GVs    | CW GVs |
|------------------------------------------------------------------|-------|-------|-------|-------|-------|----------|-----------|--------|
| <b>Field Parameters</b>                                          |       |       |       |       |       |          |           |        |
| pH - Field                                                       | 8.2   | 7.4   | 7.2   | 7.7   | 8.3   | 7.2      | 6.5 - 8.0 | -      |
| EC - Field - $\mu\text{S}/\text{cm}$                             | 2240  | 1100  | 2170  | 1012  | 1920  | 3465     | 2200      | -      |
| <b>General Parameters</b>                                        |       |       |       |       |       |          | -         | -      |
| pH - Lab                                                         |       | 7.1   | 6.9   | 6.7   | 8.3   | 7.2      | 6.5 - 8.0 | -      |
| EC - Lab - $\mu\text{S}/\text{cm}$                               | 2190  | 1020  | 1935  | 930   | 1815  | 3115     | 2200      | -      |
| Total Dissolved Solids                                           | 1210  | 417   | 1315  | 575   | 1045  | 1980     | 1000      | -      |
| Alkalinity - $\text{mg}/\text{L}$                                | 554   | 414   | 700   | 287   | 659   | 394      | -         | -      |
| <b>Major Ions</b>                                                |       |       |       |       |       |          |           | -      |
| Sodium (Na) - $\text{mg}/\text{L}$                               | 429   | 107   | 263   | 136   | 303   | 525      | 180       | -      |
| Potassium (K) - $\text{mg}/\text{L}$                             | 7     | 4     | 1     | 4     | 4     | 3        | -         | -      |
| Calcium (Ca) - $\text{mg}/\text{L}$                              | 49    | 66    | 133   | 32    | 27    | 186      | -         | 1000   |
| Magnesium (Mg) - $\text{mg}/\text{L}$                            | 38    | 39    | 72    | 26    | 67    | 39       | -         | -      |
| Chloride (Cl) - $\text{mg}/\text{L}$                             | 378   | 72    | 136   | 136   | 221   | 908      | 250       | -      |
| Carbonate Alkalinity as $\text{CaCO}_3$ - $\text{mg}/\text{L}$   | <1    | <1    | <1    | <1    | 29    | <1       | -         | -      |
| Bicarbonate Alkalinity as $\text{CaCO}_3$ - $\text{mg}/\text{L}$ | 554   | 414   | 700   | 287   | 630   | 394      | -         | -      |
| Sulfate ( $\text{SO}_4$ ) - $\text{mg}/\text{L}$                 | 37    | 41    | 261   | 17    | 6     | 41       | 250       | 1000   |
| <b>Nutrients</b>                                                 |       |       |       |       |       |          |           |        |
| Ammonia as Nitrogen (N)                                          | 0.12  | 4.5   | 0.13  | 0.78  | 6.89  | <0.01    | 0.5       | -      |
| Nitrite as N ( $\text{mg}/\text{L}$ )                            |       | <0.01 | <0.01 | <0.01 | 0.02  | <0.01    | 3         | 30     |
| Nitrate as N ( $\text{mg}/\text{L}$ )                            |       | 0.20  | 0.15  | 0.08  | 1.37  | 0.51     | 50        | 400    |
| NOX as N ( $\text{mg}/\text{L}$ )                                |       | 0.20  | 0.15  | 0.08  | 1.39  | 0.51     | -         | -      |

| <i>Bore ID</i>        | <i>WB-08</i> | <i>WB-09</i> | <i>WB-10</i> | <i>WB-11</i> | <i>WB-12</i> | <i>Yarri PB</i> | <i>DW GV's</i> | <i>CW GV's</i> |
|-----------------------|--------------|--------------|--------------|--------------|--------------|-----------------|----------------|----------------|
| <b>Metals</b>         |              |              |              |              |              |                 |                |                |
| Aluminium (Al) - mg/L |              | <0.01        | <0.01        | <0.01        | <0.01        | <0.01           | <b>0.2</b>     | <b>5</b>       |
| Arsenic (As) - mg/L   | <b>0.020</b> | <b>0.011</b> | 0.002        | <0.001       | 0.001        | 0.003           | <b>0.007</b>   | <b>0.5</b>     |
| Barium (Ba) - mg/L    | 0.173        | 0.459        | 0.048        | 0.124        | 0.105        | 0.083           | <b>0.7</b>     | <b>1</b>       |
| Beryllium (Be) - mg/L | <0.001       | <0.001       | <0.001       | <0.001       | <0.001       | <0.001          | -              | -              |
| Cadmium (Cd) - mg/L   | 0.0004       | 0.0008       | <0.0001      | <0.0001      | 0.0001       | <0.0001         | <b>0.002</b>   | <b>0.01</b>    |
| Chromium (Cr) - mg/L  | <0.001       | 0.001        | 0.001        | <0.001       | 0.003        | <0.001          | <b>0.05</b>    | <b>1</b>       |
| Cobalt (Co) - mg/L    | <0.001       | <0.001       | <0.001       | <0.001       | 0.001        | 0.004           | -              | <b>1</b>       |
| Copper (Cu) - mg/L    | 0.004        | 0.012        | 0.005        | 0.003        | 0.005        | 0.009           | <b>2</b>       | -              |
| Iron (Fe) - mg/L      | <b>0.4</b>   | <b>18.8</b>  | <b>6.7</b>   | <b>2.1</b>   | <b>7.3</b>   | 0.1             | <b>0.3</b>     | -              |
| Lead (Pb) - mg/L      | 0.003        | <b>0.017</b> | 0.004        | 0.002        | 0.003        | <0.001          | <b>0.01</b>    | <b>0.1</b>     |
| Manganese (Mn) - mg/L | 0.016        | <b>0.158</b> | 0.018        | <b>0.253</b> | 0.086        | 0.019           | <b>0.1</b>     | -              |
| Mercury (Hg) - mg/L   | <0.0001      | <0.0001      | <0.0001      | <0.0001      | <0.0001      | <0.0001         | <b>0.001</b>   | <b>0.002</b>   |
| Nickel (Ni) - mg/L    | <0.001       | <b>0.080</b> | 0.008        | <b>0.253</b> | <b>0.036</b> | <0.001          | <b>0.02</b>    | <b>1</b>       |
| Vanadium (V) - mg/L   | 0.010        | 0.020        | 0.010        | <0.01        | <0.01        | <0.01           | -              | -              |
| Zinc (Zn) - mg/L      | 0.335        | 2.110        | 0.541        | 0.027        | 0.401        | 0.021           | <b>3</b>       | <b>20</b>      |

---

## **Appendix D**

---

### Groundwater Works Summary Sheets – Private Bores

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW000122

### Works Details [\(top\)](#)

**GROUNDWATER NUMBER** GW000122  
**LIC-NUM**  
**AUTHORISED-PURPOSES**  
**INTENDED-PURPOSES** NOT KNOWN  
**WORK-TYPE** Bore  
**WORK-STATUS** (Unknown)  
**CONSTRUCTION-METHOD** Cable Tool  
**OWNER-TYPE** Private  
**COMMENCE-DATE**  
**COMPLETION-DATE** 1917-09-01  
**FINAL-DEPTH (metres)** 152.40  
**DRILLED-DEPTH (metres)** 152.40  
**CONTRACTOR-NAME**  
**DRILLER-NAME**  
**PROPERTY**  
**GWMA**  
**GW-ZONE**  
**STANDING-WATER-LEVEL**  
**SALINITY**  
**YIELD**

### Site Details [\(top\)](#)

**REGION** 90 - BARWON  
**RIVER-BASIN** 419 - NAMOI RIVER  
**AREA-DISTRICT**  
**CMA-MAP** 8936-2N  
**GRID-ZONE** 56/1  
**SCALE** 1:25,000  
**ELEVATION**  
**ELEVATION-SOURCE** (Unknown)  
**NORTHING** 6590019.00  
**EASTING** 240371.00  
**LATITUDE** 30 47' 40"  
**LONGITUDE** 150 17' 12"  
**GS-MAP** 0028B4

AMG-ZONE 56  
 COORD-SOURCE PR.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 37

### Licensed [\(top\)](#)

no details

### Water Bearing Zones [\(top\)](#)

| FROM-DEPTH<br>(metres) | TO-DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-DESC  | S-W-L | D-D-L | YIELD | TEST-HOLE-DEPTH<br>(metres) | DURATION | SALINITY  |
|------------------------|----------------------|-----------------------|----------------|-------|-------|-------|-----------------------------|----------|-----------|
| 39.60                  | 39.60                | 0.00                  | Unconsolidated |       |       | 0.00  |                             |          | Good      |
| 102.10                 | 102.10               | 0.00                  | Fractured      |       |       | 0.00  |                             |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM   | TO     | THICKNESS | DESC                      | GEO-MATERIAL | COMMENT |
|--------|--------|-----------|---------------------------|--------------|---------|
| 0.00   | 34.75  | 34.75     | Sand Boulder              |              |         |
| 34.75  | 36.48  | 1.73      | Conglomerate              |              |         |
| 36.48  | 51.82  | 15.34     | Clay Yellow Water Bearing |              |         |
| 51.82  | 60.96  | 9.14      | Sand Boulder              |              |         |
| 60.96  | 68.88  | 7.92      | Clay Yellow Sand          |              |         |
| 60.96  | 68.88  | 7.92      | Boulders                  |              |         |
| 68.88  | 83.52  | 14.64     | Clay Yellow Sand          |              |         |
| 83.52  | 100.58 | 17.06     | Shale                     |              |         |
| 100.58 | 128.02 | 27.44     | Shale Water Bearing       |              |         |
| 100.58 | 128.02 | 27.44     | Sandstone Streaks         |              |         |
| 128.02 | 152.40 | 24.38     | Shale                     |              |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW000713

### Works Details [\(top\)](#)

**GROUNDWATER NUMBER** GW000713  
**LIC-NUM**  
**AUTHORISED-PURPOSES**  
**INTENDED-PURPOSES** NOT KNOWN  
**WORK-TYPE** Bore open thru rock  
**WORK-STATUS** Supply Obtained  
**CONSTRUCTION-METHOD** Cable Tool  
**OWNER-TYPE** Private  
**COMMENCE-DATE**  
**COMPLETION-DATE** 1921-05-01  
**FINAL-DEPTH (metres)** 65.20  
**DRILLED-DEPTH (metres)** 65.20  
**CONTRACTOR-NAME**  
**DRILLER-NAME**  
**PROPERTY**  
**GWMA**  
**GW-ZONE**  
**STANDING-WATER-LEVEL**  
**SALINITY**  
**YIELD**

### Site Details [\(top\)](#)

**REGION** 90 - BARWON  
**RIVER-BASIN** 419 - NAMOI RIVER  
**AREA-DISTRICT**  
**CMA-MAP** 8936-1S  
**GRID-ZONE** 56/1  
**SCALE** 1:25,000  
**ELEVATION**  
**ELEVATION-SOURCE** (Unknown)  
**NORTHING** 6598028.00  
**EASTING** 241481.00  
**LATITUDE** 30 43' 21"  
**LONGITUDE** 150 18' 1"  
**GS-MAP** 0028B3

AMG-ZONE 56  
 COORD-SOURCE PR.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH WILLURI  
 PORTION-LOT-DP 32

### Licensed [\(top\)](#)

no details

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|-----------|
| 1           | 1           | Casing             | Threaded Steel     | 0.00                       | 40.00                    | 152        |            |          | (Unknown) |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-----------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 64.60                      | 64.60                    | 0.00                  | Fractured             | 33.50     |               | 0.51  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                    | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|-------------------------|--------------|---------|
| 0.00  | 22.25 | 22.25     | Clay Yellow             |              |         |
| 22.25 | 24.38 | 2.13      | Stones                  |              |         |
| 24.38 | 26.52 | 2.14      | Stones Clay             |              |         |
| 26.52 | 30.78 | 4.26      | Rock                    |              |         |
| 30.78 | 33.83 | 3.05      | Sandstone Yellow        |              |         |
| 33.83 | 35.05 | 1.22      | Stones                  |              |         |
| 35.05 | 37.49 | 2.44      | Sandstone               |              |         |
| 37.49 | 40.54 | 3.05      | Rock                    |              |         |
| 40.54 | 41.76 | 1.22      | Clay Swelling           |              |         |
| 41.76 | 65.23 | 23.47     | Rock Black Water Supply |              |         |

---

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW000743

### Works Details [\(top\)](#)

**GROUNDWATER NUMBER** GW000743  
**LIC-NUM**  
**AUTHORISED-PURPOSES**  
**INTENDED-PURPOSES** NOT KNOWN  
**WORK-TYPE** Bore open thru rock  
**WORK-STATUS** Supply Obtained  
**CONSTRUCTION-METHOD** Cable Tool  
**OWNER-TYPE** Private  
**COMMENCE-DATE**  
**COMPLETION-DATE** 1921-06-01  
**FINAL-DEPTH (metres)** 70.40  
**DRILLED-DEPTH (metres)** 70.40  
**CONTRACTOR-NAME**  
**DRILLER-NAME**  
**PROPERTY**  
**GWMA**  
**GW-ZONE**  
**STANDING-WATER-LEVEL**  
**SALINITY**  
**YIELD**

### Site Details [\(top\)](#)

**REGION** 90 - BARWON  
**RIVER-BASIN** 419 - NAMOI RIVER  
**AREA-DISTRICT**  
**CMA-MAP** 8936-1S  
**GRID-ZONE** 56/1  
**SCALE** 1:25,000  
**ELEVATION**  
**ELEVATION-SOURCE** (Unknown)  
**NORTHING** 6598022.00  
**EASTING** 238686.00  
**LATITUDE** 30 43' 19"  
**LONGITUDE** 150 16' 16"  
**GS-MAP** 0028B3

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH WEAN  
 PORTION-LOT-DP 59

### Licensed [\(top\)](#)

no details

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|-----------|
| 1           | 1           | Casing             | Threaded Steel     | 0.00                       | 48.10                    | 152        |            |          | (Unknown) |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-----------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 54.90                      | 54.90                    | 0.00                  | Fractured             | 25.90     |               | 0.72  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC              | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|-------------------|--------------|---------|
| 0.00  | 12.19 | 12.19     | Clay Yellow       |              |         |
| 12.19 | 20.42 | 8.23      | Clay Sandstone    |              |         |
| 20.42 | 30.18 | 9.76      | Sandstone         |              |         |
| 30.18 | 32.00 | 1.82      | Shale             |              |         |
| 32.00 | 39.62 | 7.62      | Shale Stones      |              |         |
| 39.62 | 46.94 | 7.32      | Shale Grey        |              |         |
| 46.94 | 57.91 | 10.97     | Rock Water Supply |              |         |
| 57.91 | 63.09 | 5.18      | Shale Grey        |              |         |
| 63.09 | 70.41 | 7.32      | Rock              |              |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW003083

### Works Details [\(top\)](#)

**GROUNDWATER NUMBER** GW003083

**LIC-NUM**

**AUTHORISED-PURPOSES**

**INTENDED-PURPOSES** NOT KNOWN

**WORK-TYPE** Bore open thru rock

**WORK-STATUS** (Unknown)

**CONSTRUCTION-METHOD** Cable Tool

**OWNER-TYPE** Private

**COMMENCE-DATE**

**COMPLETION-DATE** 1932-01-01

**FINAL-DEPTH (metres)** 100.00

**DRILLED-DEPTH (metres)** 100.00

**CONTRACTOR-NAME**

**DRILLER-NAME**

**PROPERTY**

**GWMA**

**GW-ZONE**

**STANDING-WATER-LEVEL**

**SALINITY**

**YIELD**

### Site Details [\(top\)](#)

**REGION** 90 - BARWON

**RIVER-BASIN** 419 - NAMOI RIVER

**AREA-DISTRICT**

**CMA-MAP** 8936-4S

**GRID-ZONE** 56/1

**SCALE** 1:25,000

**ELEVATION**

**ELEVATION-SOURCE** (Unknown)

**NORTHING** 6599611.00

**EASTING** 235611.00

**LATITUDE** 30 42' 25"

**LONGITUDE** 150 14' 22"

**GS-MAP** 0028A3

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH VICKERY  
 PORTION-LOT-DP 6

### Licensed [\(top\)](#)

no details

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | 87.60                    | 152        |            |          | Suspended<br>in Clamps |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 30.80                      | 30.80                    | 0.00                  | (Unknown)         | 20.10     |               | 0.09  |                                     |          | Good     |
| 93.90                      | 99.40                    | 5.50                  | Fractured         | 30.80     |               | 0.61  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                       | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|----------------------------|--------------|---------|
| 0.00  | 2.13  | 2.13      | Clay Reddish               |              |         |
| 2.13  | 8.23  | 6.10      | Clay Yellow                |              |         |
| 8.23  | 10.06 | 1.83      | Conglomerate               |              |         |
| 10.06 | 26.82 | 16.76     | Clay Yellow                |              |         |
| 26.82 | 32.61 | 5.79      | Stones Large Coarse Gravel | Water Supply |         |
| 32.61 | 36.58 | 3.97      | Gravel Coarse              |              |         |
| 36.58 | 54.86 | 18.28     | Conglomerate               |              |         |
| 54.86 | 64.92 | 10.06     | Clay Yellow                |              |         |
| 64.92 | 76.20 | 11.28     | Clay                       |              |         |
| 76.20 | 80.77 | 4.57      | Conglomerate               |              |         |
| 80.77 | 85.34 | 4.57      | Sand Rock                  |              |         |
| 85.34 | 91.44 | 6.10      | Shale Grey                 |              |         |
| 91.44 | 92.96 | 1.52      | Coal                       |              |         |

|       |       |      |                                     |
|-------|-------|------|-------------------------------------|
| 92.96 | 93.88 | 0.92 | Shale Black                         |
| 93.88 | 99.36 | 5.48 | Shale Black Coal Bands Water Supply |
| 99.36 | 99.97 | 0.61 | Rock                                |

---

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW009830

### Works Details [\(top\)](#)

|                               |                      |
|-------------------------------|----------------------|
| <b>GROUNDWATER NUMBER</b>     | GW009830             |
| <b>LIC-NUM</b>                | 90BL002917           |
| <b>AUTHORISED-PURPOSES</b>    | STOCK                |
| <b>INTENDED-PURPOSES</b>      | STOCK                |
| <b>WORK-TYPE</b>              | Bore                 |
| <b>WORK-STATUS</b>            | (Unknown)            |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool           |
| <b>OWNER-TYPE</b>             | Private              |
| <b>COMMENCE-DATE</b>          |                      |
| <b>COMPLETION-DATE</b>        | 1951-03-01           |
| <b>FINAL-DEPTH (metres)</b>   | 67.10                |
| <b>DRILLED-DEPTH (metres)</b> | 67.10                |
| <b>CONTRACTOR-NAME</b>        |                      |
| <b>DRILLER-NAME</b>           |                      |
| <b>PROPERTY</b>               | PENRYN               |
| <b>GWMA</b>                   | 604 - GUNNEDAH BASIN |
| <b>GW-ZONE</b>                | -                    |
| <b>STANDING-WATER-LEVEL</b>   |                      |
| <b>SALINITY</b>               |                      |
| <b>YIELD</b>                  |                      |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-1S           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6599793.00        |
| <b>EASTING</b>          | 240560.00         |
| <b>LATITUDE</b>         | 30 42' 23"        |
| <b>LONGITUDE</b>        | 150 17' 28"       |
| <b>GS-MAP</b>           | 0028B3            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH WEAN  
 PORTION-LOT-DP 96

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH WEAN  
 PORTION-LOT-DP 96

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | 67.10                    | 127        |            |          | Seated<br>on<br>Bottom |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 61.00                      | 62.80                    | 1.80                  | Consolidated      | 18.30     |               | 0.76  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM | TO    | THICKNESS | DESC      | GEO-MATERIAL | COMMENT |
|------|-------|-----------|-----------|--------------|---------|
| 0.00 | 1.52  | 1.52      | Soil      |              |         |
| 1.52 | 67.06 | 65.54     | Sandstone | Water Supply |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW011015

### Works Details [\(top\)](#)

|                               |                      |
|-------------------------------|----------------------|
| <b>GROUNDWATER NUMBER</b>     | GW011015             |
| <b>LIC-NUM</b>                | 90BL004125           |
| <b>AUTHORISED-PURPOSES</b>    | STOCK                |
| <b>INTENDED-PURPOSES</b>      | STOCK                |
| <b>WORK-TYPE</b>              | Bore                 |
| <b>WORK-STATUS</b>            | (Unknown)            |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool           |
| <b>OWNER-TYPE</b>             | Private              |
| <b>COMMENCE-DATE</b>          |                      |
| <b>COMPLETION-DATE</b>        | 1954-11-01           |
| <b>FINAL-DEPTH (metres)</b>   | 39.00                |
| <b>DRILLED-DEPTH (metres)</b> | 39.00                |
| <b>CONTRACTOR-NAME</b>        |                      |
| <b>DRILLER-NAME</b>           |                      |
| <b>PROPERTY</b>               | N/A                  |
| <b>GWMA</b>                   | 604 - GUNNEDAH BASIN |
| <b>GW-ZONE</b>                | -                    |
| <b>STANDING-WATER-LEVEL</b>   |                      |
| <b>SALINITY</b>               |                      |
| <b>YIELD</b>                  |                      |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6594898.00        |
| <b>EASTING</b>          | 239507.00         |
| <b>LATITUDE</b>         | 30 45' 1"         |
| <b>LONGITUDE</b>        | 150 16' 44"       |
| <b>GS-MAP</b>           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 30

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 30

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|---------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.60                      | 39.00                    | 152        |            |          | Seated on Bottom          |
| 1           | 1           | Opening            | Slots              | 32.90                      | 39.00                    | 152        |            | 1        | SL: 0mm;<br>A:<br>15.88mm |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 34.70                      | 36.50                    | 1.80                  | Consolidated      | 29.00     |               | 0.44  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC      | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|-----------|--------------|---------|
| 0.00  | 16.46 | 16.46     | Soil      |              |         |
| 16.46 | 39.01 | 22.55     | Sandstone | Water Supply |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW011066

### Works Details [\(top\)](#)

|                               |                      |
|-------------------------------|----------------------|
| <b>GROUNDWATER NUMBER</b>     | GW011066             |
| <b>LIC-NUM</b>                | 90BL004169           |
| <b>AUTHORISED-PURPOSES</b>    | STOCK                |
| <b>INTENDED-PURPOSES</b>      | STOCK                |
| <b>WORK-TYPE</b>              | Bore                 |
| <b>WORK-STATUS</b>            | (Unknown)            |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool           |
| <b>OWNER-TYPE</b>             | Private              |
| <b>COMMENCE-DATE</b>          |                      |
| <b>COMPLETION-DATE</b>        | 1954-12-01           |
| <b>FINAL-DEPTH (metres)</b>   | 47.90                |
| <b>DRILLED-DEPTH (metres)</b> | 47.90                |
| <b>CONTRACTOR-NAME</b>        |                      |
| <b>DRILLER-NAME</b>           |                      |
| <b>PROPERTY</b>               | GLENROE              |
| <b>GWMA</b>                   | 604 - GUNNEDAH BASIN |
| <b>GW-ZONE</b>                | -                    |
| <b>STANDING-WATER-LEVEL</b>   |                      |
| <b>SALINITY</b>               |                      |
| <b>YIELD</b>                  |                      |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-1S           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6595178.00        |
| <b>EASTING</b>          | 239607.00         |
| <b>LATITUDE</b>         | 30 44' 52"        |
| <b>LONGITUDE</b>        | 150 16' 48"       |
| <b>GS-MAP</b>           | 0028B3            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 30

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 30

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|---------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.80                      | 47.80                    | 152        |            |          | Seated on Bottom          |
| 1           | 1           | Opening            | Perforations       | 42.40                      | 47.90                    | 152        |            | 1        | SL: 0mm;<br>A:<br>15.88mm |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY   |
|----------------------------|--------------------------|-----------------------|-----------------------|-----------|---------------|-------|-------------------------------------|----------|------------|
| 42.70                      | 44.20                    | 1.50                  | Fractured             | 30.80     | 0.63          |       |                                     |          | Good Stock |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC  | GEO-MATERIAL       | COMMENT |
|-------|-------|-----------|-------|--------------------|---------|
| 0.00  | 20.42 | 20.42     | Soil  |                    |         |
| 20.42 | 47.85 | 27.43     | Shale | Black Water Supply |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW013284

### Works Details [\(top\)](#)

|                        |                                                                       |
|------------------------|-----------------------------------------------------------------------|
| GROUNDWATER NUMBER     | GW013284                                                              |
| LIC-NUM                | 90WA808995                                                            |
| AUTHORISED-PURPOSES    | STOCK                                                                 |
| INTENDED-PURPOSES      | NOT KNOWN                                                             |
| WORK-TYPE              | Bore                                                                  |
| WORK-STATUS            | (Unknown)                                                             |
| CONSTRUCTION-METHOD    | Cable Tool                                                            |
| OWNER-TYPE             | Private                                                               |
| COMMENCE-DATE          |                                                                       |
| COMPLETION-DATE        | 1920-01-01                                                            |
| FINAL-DEPTH (metres)   | 18.30                                                                 |
| DRILLED-DEPTH (metres) | 0.00                                                                  |
| CONTRACTOR-NAME        |                                                                       |
| DRILLER-NAME           |                                                                       |
| PROPERTY               | BROLGA                                                                |
| GWMA                   | 004 - UPPER NAMOI(U/S NARRABRI)                                       |
| GW-ZONE                | 004 - 004 - NAMOI VALLEY (KEEPIT DAM TO GINS LEAP) GROUNDWATER SOURCE |
| STANDING-WATER-LEVEL   |                                                                       |
| SALINITY               |                                                                       |
| YIELD                  |                                                                       |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-2N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6588017.00        |

EASTING 237892.00  
LATITUDE 30 48' 43"  
LONGITUDE 150 15' 37"  
GS-MAP 0028B4  
AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH BENTRY  
PORTION-LOT-DP It 2 dp 219575

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH BENTRY  
PORTION-LOT-DP 2 219575

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|-----------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | -0.30                    | 152        |            |          | (Unknown) |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW013369

### Works Details [\(top\)](#)

|                        |                                                                       |
|------------------------|-----------------------------------------------------------------------|
| GROUNDWATER NUMBER     | GW013369                                                              |
| LIC-NUM                | 90WA808994                                                            |
| AUTHORISED-PURPOSES    | STOCK                                                                 |
| INTENDED-PURPOSES      | NOT KNOWN                                                             |
| WORK-TYPE              | Bore                                                                  |
| WORK-STATUS            | (Unknown)                                                             |
| CONSTRUCTION-METHOD    | Cable Tool                                                            |
| OWNER-TYPE             | Private                                                               |
| COMMENCE-DATE          |                                                                       |
| COMPLETION-DATE        | 1946-01-01                                                            |
| FINAL-DEPTH (metres)   | 22.30                                                                 |
| DRILLED-DEPTH (metres) | 0.00                                                                  |
| CONTRACTOR-NAME        |                                                                       |
| DRILLER-NAME           |                                                                       |
| PROPERTY               | BROLGA                                                                |
| GWMA                   | 004 - UPPER NAMOI(U/S NARRABRI)                                       |
| GW-ZONE                | 004 - 004 - NAMOI VALLEY (KEEPIT DAM TO GINS LEAP) GROUNDWATER SOURCE |
| STANDING-WATER-LEVEL   |                                                                       |
| SALINITY               |                                                                       |
| YIELD                  |                                                                       |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-3N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6588545.00        |

EASTING 236815.00  
LATITUDE 30 48' 25"  
LONGITUDE 150 14' 57"  
GS-MAP 0028A4  
AMG-ZONE 56  
COORD-SOURCE  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH BENTRY  
PORTION-LOT-DP LT 2 DP 219575

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH BENTRY  
PORTION-LOT-DP 2 219575

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | 22.30                    | 152        |            |          | Suspended<br>in Clamps |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW016871

### Works Details [\(top\)](#)

|                               |                      |
|-------------------------------|----------------------|
| <b>GROUNDWATER NUMBER</b>     | GW016871             |
| <b>LIC-NUM</b>                | 90BL007353           |
| <b>AUTHORISED-PURPOSES</b>    | STOCK                |
| <b>INTENDED-PURPOSES</b>      | STOCK                |
| <b>WORK-TYPE</b>              | Bore                 |
| <b>WORK-STATUS</b>            | (Unknown)            |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool           |
| <b>OWNER-TYPE</b>             | Private              |
| <b>COMMENCE-DATE</b>          |                      |
| <b>COMPLETION-DATE</b>        | 1958-09-01           |
| <b>FINAL-DEPTH (metres)</b>   | 62.50                |
| <b>DRILLED-DEPTH (metres)</b> | 62.50                |
| <b>CONTRACTOR-NAME</b>        |                      |
| <b>DRILLER-NAME</b>           |                      |
| <b>PROPERTY</b>               | BELMONT              |
| <b>GWMA</b>                   | 604 - GUNNEDAH BASIN |
| <b>GW-ZONE</b>                | -                    |
| <b>STANDING-WATER-LEVEL</b>   |                      |
| <b>SALINITY</b>               |                      |
| <b>YIELD</b>                  |                      |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6594016.00        |
| <b>EASTING</b>          | 239981.00         |
| <b>LATITUDE</b>         | 30 45' 30"        |
| <b>LONGITUDE</b>        | 150 17' 1"        |
| <b>GS-MAP</b>           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 31

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 31

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.50                      | 62.50                    | 152        |            |          | Seated<br>on<br>Bottom |
| 1           | 1           | Opening            | Perforations       | 55.80                      | 62.50                    | 152        |            | 1        | SL:<br>0mm; A:<br>0mm  |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY  |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|-----------|
| 59.40                      | 62.40                    | 3.00                  | Consolidated      | 45.70     |               | 0.38  |                                     |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                        | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|-----------------------------|--------------|---------|
| 0.00  | 1.52  | 1.52      | Topsoil                     |              |         |
| 1.52  | 9.14  | 7.62      | Basalt                      |              |         |
| 9.14  | 42.06 | 32.92     | Clay Gravel                 |              |         |
| 42.06 | 59.44 | 17.38     | Sandstone Coarse            |              |         |
| 59.44 | 62.48 | 3.04      | Sandstone Grey Water Supply |              |         |

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice

should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW016874

### Works Details [\(top\)](#)

|                               |                      |
|-------------------------------|----------------------|
| <b>GROUNDWATER NUMBER</b>     | GW016874             |
| <b>LIC-NUM</b>                | 90BL007355           |
| <b>AUTHORISED-PURPOSES</b>    | DOMESTIC STOCK       |
| <b>INTENDED-PURPOSES</b>      | DOMESTIC STOCK       |
| <b>WORK-TYPE</b>              | Bore open thru rock  |
| <b>WORK-STATUS</b>            | (Unknown)            |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool           |
| <b>OWNER-TYPE</b>             | Private              |
| <b>COMMENCE-DATE</b>          |                      |
| <b>COMPLETION-DATE</b>        | 1958-03-01           |
| <b>FINAL-DEPTH (metres)</b>   | 53.90                |
| <b>DRILLED-DEPTH (metres)</b> | 54.00                |
| <b>CONTRACTOR-NAME</b>        |                      |
| <b>DRILLER-NAME</b>           |                      |
| <b>PROPERTY</b>               | BELMONT              |
| <b>GWMA</b>                   | 604 - GUNNEDAH BASIN |
| <b>GW-ZONE</b>                | -                    |
| <b>STANDING-WATER-LEVEL</b>   |                      |
| <b>SALINITY</b>               |                      |
| <b>YIELD</b>                  |                      |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6594022.00        |
| <b>EASTING</b>          | 238943.00         |
| <b>LATITUDE</b>         | 30 45' 29"        |
| <b>LONGITUDE</b>        | 150 16' 22"       |
| <b>GS-MAP</b>           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP LT 1 DP 787417

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 31

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.50                      | 51.30                    | 127        |            |          | Suspended<br>in Clamps |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY  |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|-----------|
| 45.10                      | 46.30                    | 1.20                  | Fractured         | 24.40     |               | 0.38  |                                     |          | (Unknown) |
| 51.80                      | 53.90                    | 2.10                  | Consolidated      |           |               | 0.88  |                                     |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                   | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|------------------------|--------------|---------|
| 0.00  | 1.52  | 1.52      | Soil                   |              |         |
| 1.52  | 6.71  | 5.19      | Clay Sandy             |              |         |
| 6.71  | 25.60 | 18.89     | Clay Gravel            |              |         |
| 25.60 | 29.26 | 3.66      | Boulders Loose         |              |         |
| 29.26 | 40.84 | 11.58     | Clay Gravel            |              |         |
| 40.84 | 46.33 | 5.49      | Coal Water Supply      |              |         |
| 46.33 | 51.82 | 5.49      | Shale Sandy            |              |         |
| 51.82 | 53.95 | 2.13      | Sandstone Water Supply |              |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources

(DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW017198

### Works Details [\(top\)](#)

|                        |                                                                       |
|------------------------|-----------------------------------------------------------------------|
| GROUNDWATER NUMBER     | GW017198                                                              |
| LIC-NUM                | 90WA808996                                                            |
| AUTHORISED-PURPOSES    | STOCK                                                                 |
| INTENDED-PURPOSES      | NOT KNOWN                                                             |
| WORK-TYPE              | Bore                                                                  |
| WORK-STATUS            | (Unknown)                                                             |
| CONSTRUCTION-METHOD    | Cable Tool                                                            |
| OWNER-TYPE             | Private                                                               |
| COMMENCE-DATE          |                                                                       |
| COMPLETION-DATE        | 1920-01-01                                                            |
| FINAL-DEPTH (metres)   | 37.50                                                                 |
| DRILLED-DEPTH (metres) | 0.00                                                                  |
| CONTRACTOR-NAME        |                                                                       |
| DRILLER-NAME           |                                                                       |
| PROPERTY               | BROLGA                                                                |
| GWMA                   | 004 - UPPER NAMOI(U/S NARRABRI)                                       |
| GW-ZONE                | 004 - 004 - NAMOI VALLEY (KEEPIT DAM TO GINS LEAP) GROUNDWATER SOURCE |
| STANDING-WATER-LEVEL   |                                                                       |
| SALINITY               |                                                                       |
| YIELD                  |                                                                       |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-3N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6589282.00        |

EASTING 236691.00  
LATITUDE 30 48' 1"  
LONGITUDE 150 14' 53"  
GS-MAP 0028A4  
AMG-ZONE 56  
COORD-SOURCE  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH BENTRY  
PORTION-LOT-DP 7

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH BENTRY  
PORTION-LOT-DP 7

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | 37.20                    | 152        |            |          | Suspended<br>in Clamps |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW017199

### Works Details [\(top\)](#)

|                               |                      |
|-------------------------------|----------------------|
| <b>GROUNDWATER NUMBER</b>     | GW017199             |
| <b>LIC-NUM</b>                | 90BL007679           |
| <b>AUTHORISED-PURPOSES</b>    | STOCK                |
| <b>INTENDED-PURPOSES</b>      | NOT KNOWN            |
| <b>WORK-TYPE</b>              | Bore                 |
| <b>WORK-STATUS</b>            | (Unknown)            |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool           |
| <b>OWNER-TYPE</b>             | Private              |
| <b>COMMENCE-DATE</b>          |                      |
| <b>COMPLETION-DATE</b>        | 1939-01-01           |
| <b>FINAL-DEPTH (metres)</b>   | 37.50                |
| <b>DRILLED-DEPTH (metres)</b> | 0.00                 |
| <b>CONTRACTOR-NAME</b>        |                      |
| <b>DRILLER-NAME</b>           |                      |
| <b>PROPERTY</b>               | BROLGA               |
| <b>GWMA</b>                   | 604 - GUNNEDAH BASIN |
| <b>GW-ZONE</b>                | -                    |
| <b>STANDING-WATER-LEVEL</b>   |                      |
| <b>SALINITY</b>               |                      |
| <b>YIELD</b>                  |                      |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-3N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6589835.00        |
| <b>EASTING</b>          | 234123.00         |
| <b>LATITUDE</b>         | 30 47' 41"        |
| <b>LONGITUDE</b>        | 150 13' 17"       |
| <b>GS-MAP</b>           | 0028A4            |

AMG-ZONE 56  
COORD-SOURCE  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH BRENTY  
PORTION-LOT-DP 7

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH BRENTY  
PORTION-LOT-DP 7

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | 36.30                    | 152        |            |          | Suspended<br>in Clamps |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

Print Report

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW020454

### Works Details [\(top\)](#)

|                        |            |
|------------------------|------------|
| GROUNDWATER NUMBER     | GW020454   |
| LIC-NUM                | 90BL013494 |
| AUTHORISED-PURPOSES    | STOCK      |
| INTENDED-PURPOSES      | NOT KNOWN  |
| WORK-TYPE              | Bore       |
| WORK-STATUS            | (Unknown)  |
| CONSTRUCTION-METHOD    | Cable Tool |
| OWNER-TYPE             | Private    |
| COMMENCE-DATE          |            |
| COMPLETION-DATE        | 1912-01-01 |
| FINAL-DEPTH (metres)   | 73.20      |
| DRILLED-DEPTH (metres) | 0.00       |
| CONTRACTOR-NAME        |            |
| DRILLER-NAME           |            |
| PROPERTY               | CARLTON    |
| GWMA                   | -          |
| GW-ZONE                | -          |
| STANDING-WATER-LEVEL   |            |
| SALINITY               |            |
| YIELD                  |            |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-2N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6589031.00        |
| EASTING          | 241539.00         |
| LATITUDE         | 30 48' 13"        |
| LONGITUDE        | 150 17' 55"       |
| GS-MAP           | 0028B4            |

AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH YARRARI  
PORTION-LOT-DP 171

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH YARRARI  
PORTION-LOT-DP 171

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

Print Report

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW020456

### Works Details [\(top\)](#)

|                        |            |
|------------------------|------------|
| GROUNDWATER NUMBER     | GW020456   |
| LIC-NUM                | 90BL013495 |
| AUTHORISED-PURPOSES    | STOCK      |
| INTENDED-PURPOSES      | NOT KNOWN  |
| WORK-TYPE              | Bore       |
| WORK-STATUS            | (Unknown)  |
| CONSTRUCTION-METHOD    | Cable Tool |
| OWNER-TYPE             | Private    |
| COMMENCE-DATE          |            |
| COMPLETION-DATE        | 1925-01-01 |
| FINAL-DEPTH (metres)   | 56.40      |
| DRILLED-DEPTH (metres) | 79.30      |
| CONTRACTOR-NAME        |            |
| DRILLER-NAME           |            |
| PROPERTY               | CARLTON    |
| GWMA                   | -          |
| GW-ZONE                | -          |
| STANDING-WATER-LEVEL   |            |
| SALINITY               |            |
| YIELD                  |            |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-2N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6588807.00        |
| EASTING          | 242502.00         |
| LATITUDE         | 30 48' 21"        |
| LONGITUDE        | 150 18' 31"       |
| GS-MAP           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH YARRARI  
 PORTION-LOT-DP 171

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH YARRARI  
 PORTION-LOT-DP 171

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.40                      | 41.70                    | 152        |            |          | Suspended<br>in Clamps |
| 1           | 1           | Casing             | Threaded Steel     | 39.60                      | 56.40                    | 127        |            |          | (Unknown)              |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                              | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|-----------------------------------|--------------|---------|
| 0.00  | 41.76 | 41.76     | Driller                           |              |         |
| 41.76 | 48.77 | 7.01      | Slate Green Hard                  |              |         |
| 48.77 | 49.99 | 1.22      | Slate Yellow Hard                 |              |         |
| 49.99 | 56.39 | 6.40      | Slate Green Soft Waterworn Traces |              |         |
| 56.39 | 79.25 | 22.86     | Slate Green Soft                  |              |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW020461

### Works Details [\(top\)](#)

|                        |                                                                       |
|------------------------|-----------------------------------------------------------------------|
| GROUNDWATER NUMBER     | GW020461                                                              |
| LIC-NUM                | 90WA809031                                                            |
| AUTHORISED-PURPOSES    | IRRIGATION                                                            |
| INTENDED-PURPOSES      | IRRIGATION                                                            |
| WORK-TYPE              | Bore                                                                  |
| WORK-STATUS            | (Unknown)                                                             |
| CONSTRUCTION-METHOD    | (Unknown)                                                             |
| OWNER-TYPE             | Private                                                               |
| COMMENCE-DATE          |                                                                       |
| COMPLETION-DATE        | 1963-04-01                                                            |
| FINAL-DEPTH (metres)   | 47.20                                                                 |
| DRILLED-DEPTH (metres) | 47.20                                                                 |
| CONTRACTOR-NAME        |                                                                       |
| DRILLER-NAME           |                                                                       |
| PROPERTY               | CARLTON                                                               |
| GWMA                   | 004 - UPPER NAMOI(U/S NARRABRI)                                       |
| GW-ZONE                | 004 - 004 - NAMOI VALLEY (KEEPIT DAM TO GINS LEAP) GROUNDWATER SOURCE |
| STANDING-WATER-LEVEL   |                                                                       |
| SALINITY               |                                                                       |
| YIELD                  |                                                                       |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-2N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6588429.00        |

**EASTING** 240862.00  
**LATITUDE** 30 48' 32"  
**LONGITUDE** 150 17' 29"  
**GS-MAP** 0028B4  
**AMG-ZONE** 56  
**COORD-SOURCE** GD.,ACC.MAP  
**REMARK**

### Form-A [\(top\)](#)

**COUNTY** NANDEWAR  
**PARISH** YARRARI  
**PORTION-LOT-DP** 171

### Licensed [\(top\)](#)

**COUNTY** NANDEWAR  
**PARISH** YARRARI  
**PORTION-LOT-DP** 171

### Water Bearing Zones [\(top\)](#)

| FROM-DEPTH<br>(metres) | TO-DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-DESC  | S-W-L | D-D-L | YIELD | TEST-HOLE-DEPTH<br>(metres) | DURATION | SALINITY  |
|------------------------|----------------------|-----------------------|----------------|-------|-------|-------|-----------------------------|----------|-----------|
| 6.10                   | 7.90                 | 1.80                  | Unconsolidated | 31.10 |       | 0.00  |                             |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                      | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|---------------------------|--------------|---------|
| 0.00  | 0.61  | 0.61      | Topsoil                   |              |         |
| 0.61  | 2.13  | 1.52      | Subsoil                   |              |         |
| 2.13  | 4.42  | 2.29      | Clay Fatty                |              |         |
| 4.42  | 9.14  | 4.72      | Clay Fine Gravel          |              |         |
| 9.14  | 15.85 | 6.71      | Clay Fatty                |              |         |
| 15.85 | 22.40 | 6.55      | Clay Matrix               |              |         |
| 15.85 | 22.40 | 6.55      | Gravel Red                |              |         |
| 22.40 | 34.90 | 12.50     | Clay Light                |              |         |
| 22.40 | 34.90 | 12.50     | Limestone Fused Traces    |              |         |
| 34.90 | 41.15 | 6.25      | Clay                      |              |         |
| 41.15 | 47.24 | 6.09      | Clay Light                |              |         |
| 41.15 | 47.24 | 6.09      | Traces Micaceous Feldspar |              |         |

---

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW022319

### Works Details [\(top\)](#)

|                        |                      |
|------------------------|----------------------|
| GROUNDWATER NUMBER     | GW022319             |
| LIC-NUM                | 90BL013922           |
| AUTHORISED-PURPOSES    | STOCK                |
| INTENDED-PURPOSES      | STOCK                |
| WORK-TYPE              | Bore                 |
| WORK-STATUS            | (Unknown)            |
| CONSTRUCTION-METHOD    | Cable Tool           |
| OWNER-TYPE             | Private              |
| COMMENCE-DATE          |                      |
| COMPLETION-DATE        | 1964-06-01           |
| FINAL-DEPTH (metres)   | 52.40                |
| DRILLED-DEPTH (metres) | 52.40                |
| CONTRACTOR-NAME        |                      |
| DRILLER-NAME           |                      |
| PROPERTY               | BELMONT              |
| GWMA                   | 604 - GUNNEDAH BASIN |
| GW-ZONE                | -                    |
| STANDING-WATER-LEVEL   |                      |
| SALINITY               |                      |
| YIELD                  |                      |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-2N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6592520.00        |
| EASTING          | 239299.00         |
| LATITUDE         | 30 46' 18"        |
| LONGITUDE        | 150 16' 34"       |
| GS-MAP           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 31

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 31

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.50                      | 47.10                    | 152        |            |          | Suspended<br>in Clamps |
| 1           | 1           | Opening            | Perforations       | 41.70                      | 47.20                    | 152        |            | 1        | SL: 0mm;<br>A: 0mm     |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY  |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|-----------|
| 3.00                       | 3.00                     | 0.00                  | Unconsolidated    |           |               | 0.00  |                                     |          | (Unknown) |
| 44.20                      | 46.00                    | 1.80                  | Unconsolidated    | 12.20     |               | 0.20  |                                     |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|---------------------|--------------|---------|
| 0.00  | 0.91  | 0.91      | Soil                |              |         |
| 0.91  | 44.20 | 43.29     | Gravel Clay         |              |         |
| 44.20 | 46.02 | 1.82      | Gravel Water Supply |              |         |
| 46.02 | 52.43 | 6.41      | Sandstone Grey      |              |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

Print Report

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW035706

### Works Details [\(top\)](#)

|                        |                     |
|------------------------|---------------------|
| GROUNDWATER NUMBER     | GW035706            |
| LIC-NUM                | 90BL029137          |
| AUTHORISED-PURPOSES    | DOMESTIC STOCK      |
| INTENDED-PURPOSES      | DOMESTIC STOCK      |
| WORK-TYPE              | Bore open thru rock |
| WORK-STATUS            | (Unknown)           |
| CONSTRUCTION-METHOD    | Cable Tool          |
| OWNER-TYPE             | Private             |
| COMMENCE-DATE          |                     |
| COMPLETION-DATE        | 1973-08-01          |
| FINAL-DEPTH (metres)   | 124.90              |
| DRILLED-DEPTH (metres) | 125.00              |
| CONTRACTOR-NAME        |                     |
| DRILLER-NAME           |                     |
| PROPERTY               | SURREY              |
| GWMA                   | -                   |
| GW-ZONE                | -                   |
| STANDING-WATER-LEVEL   |                     |
| SALINITY               |                     |
| YIELD                  |                     |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-2N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6593026.00        |
| EASTING          | 241070.00         |
| LATITUDE         | 30 46' 3"         |
| LONGITUDE        | 150 17' 41"       |
| GS-MAP           | 0028B4            |

AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 111

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP A 405391

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

| FROM   | TO     | THICKNESS | DESC                        | GEO-MATERIAL | COMMENT |
|--------|--------|-----------|-----------------------------|--------------|---------|
| 0.00   | 0.45   | 0.45      | Topsoil                     |              |         |
| 0.45   | 19.05  | 18.60     | Boulders Large Clay         |              |         |
| 19.05  | 33.22  | 14.17     | Basalt                      |              |         |
| 33.22  | 60.96  | 27.74     | Stones Grey Hard Soft Seams |              |         |
| 60.96  | 112.77 | 51.81     | Rock Grey Hard              |              |         |
| 112.77 | 124.96 | 12.19     | Rock Dark Grey Very Hard    |              |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW035706

### Works Details [\(top\)](#)

|                               |                     |
|-------------------------------|---------------------|
| <b>GROUNDWATER NUMBER</b>     | GW035706            |
| <b>LIC-NUM</b>                | 90BL029137          |
| <b>AUTHORISED-PURPOSES</b>    | DOMESTIC STOCK      |
| <b>INTENDED-PURPOSES</b>      | DOMESTIC STOCK      |
| <b>WORK-TYPE</b>              | Bore open thru rock |
| <b>WORK-STATUS</b>            | (Unknown)           |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool          |
| <b>OWNER-TYPE</b>             | Private             |
| <b>COMMENCE-DATE</b>          |                     |
| <b>COMPLETION-DATE</b>        | 1973-08-01          |
| <b>FINAL-DEPTH (metres)</b>   | 124.90              |
| <b>DRILLED-DEPTH (metres)</b> | 125.00              |
| <b>CONTRACTOR-NAME</b>        |                     |
| <b>DRILLER-NAME</b>           |                     |
| <b>PROPERTY</b>               | SURREY              |
| <b>GWMA</b>                   | -                   |
| <b>GW-ZONE</b>                | -                   |
| <b>STANDING-WATER-LEVEL</b>   |                     |
| <b>SALINITY</b>               |                     |
| <b>YIELD</b>                  |                     |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6593026.00        |
| <b>EASTING</b>          | 241070.00         |
| <b>LATITUDE</b>         | 30 46' 3"         |
| <b>LONGITUDE</b>        | 150 17' 41"       |
| <b>GS-MAP</b>           | 0028B4            |

AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 111

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP A 405391

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

| FROM   | TO     | THICKNESS | DESC                        | GEO-MATERIAL | COMMENT |
|--------|--------|-----------|-----------------------------|--------------|---------|
| 0.00   | 0.45   | 0.45      | Topsoil                     |              |         |
| 0.45   | 19.05  | 18.60     | Boulders Large Clay         |              |         |
| 19.05  | 33.22  | 14.17     | Basalt                      |              |         |
| 33.22  | 60.96  | 27.74     | Stones Grey Hard Soft Seams |              |         |
| 60.96  | 112.77 | 51.81     | Rock Grey Hard              |              |         |
| 112.77 | 124.96 | 12.19     | Rock Dark Grey Very Hard    |              |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW036484

### Works Details [\(top\)](#)

**GROUNDWATER NUMBER** GW036484  
**LIC-NUM**  
**AUTHORISED-PURPOSES**  
**INTENDED-PURPOSES** G/WATER XPLORE  
**WORK-TYPE** Bore  
**WORK-STATUS** Test Hole  
**CONSTRUCTION-METHOD** Cable Tool  
**OWNER-TYPE** NSW Office of Water  
**COMMENCE-DATE**  
**COMPLETION-DATE** 1983-12-01  
**FINAL-DEPTH (metres)** 40.00  
**DRILLED-DEPTH (metres)** 60.00  
**CONTRACTOR-NAME**  
**DRILLER-NAME**  
**PROPERTY**  
**GWMA**  
**GW-ZONE**  
**STANDING-WATER-LEVEL**  
**SALINITY**  
**YIELD**

### Site Details [\(top\)](#)

**REGION** 90 - BARWON  
**RIVER-BASIN** 419 - NAMOI RIVER  
**AREA-DISTRICT**  
**CMA-MAP** 8936-2N  
**GRID-ZONE** 56/1  
**SCALE** 1:25,000  
**ELEVATION**  
**ELEVATION-SOURCE** (Unknown)  
**NORTHING** 6587908.00  
**EASTING** 238480.00  
**LATITUDE** 30 48' 47"  
**LONGITUDE** 150 15' 59"  
**GS-MAP** 0028B4

AMG-ZONE 56  
 COORD-SOURCE SURV,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH YARRARI  
 PORTION-LOT-DP 134

### Licensed [\(top\)](#)

no details

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                                |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|---------------------------------------|
| 1           |             | Backfill           | Backfill           | 40.00                      | 60.00                    | 0          |            |          |                                       |
| 1           | 1           | Casing             | P.V.C.             | -1.00                      | 40.00                    | 101        |            |          | Seated on Bottom                      |
| 1           |             | Casing             | Casing Protector   | 0.00                       | 5.40                     | 203        |            |          | (Unknown)                             |
| 1           | 1           | Opening            | Slots - Horizontal | 34.00                      | 35.00                    | 101        |            | 1        | Mechanically Slotted; SL: 0mm; A: 3mm |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY  |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|-----------|
| 34.50                      | 35.00                    | 0.50                  | Unconsolidated    | 26.00     |               | 0.38  |                                     |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                     | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|--------------------------|--------------|---------|
| 0.00  | 1.00  | 1.00      | Topsoil                  |              |         |
| 1.00  | 7.00  | 6.00      | Clay Dark Brown          |              |         |
| 7.00  | 9.00  | 2.00      | Clay Light Brown         |              |         |
| 9.00  | 10.00 | 1.00      | Clay Gravel              |              |         |
| 10.00 | 18.00 | 8.00      | Clay Light Brown Sticky  |              |         |
| 18.00 | 30.00 | 12.00     | Clay Gravel              |              |         |
| 30.00 | 34.50 | 4.50      | Clay Light Brown         |              |         |
| 34.50 | 35.00 | 0.50      | Sand Gravel Water Supply |              |         |

|       |       |       |                                   |
|-------|-------|-------|-----------------------------------|
| 35.00 | 43.00 | 8.00  | Clay Light Brown Small Gravel     |
| 43.00 | 44.00 | 1.00  | Gravel Sandy Clay                 |
| 44.00 | 50.00 | 6.00  | Clay Light Brown Dark Brown Cored |
| 50.00 | 60.00 | 10.00 | Clay Red Bedrock                  |

---

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW044067

### Works Details [\(top\)](#)

|                        |                |
|------------------------|----------------|
| GROUNDWATER NUMBER     | GW044067       |
| LIC-NUM                | 90BL102846     |
| AUTHORISED-PURPOSES    | DOMESTIC STOCK |
| INTENDED-PURPOSES      | DOMESTIC STOCK |
| WORK-TYPE              | Bore           |
| WORK-STATUS            | (Unknown)      |
| CONSTRUCTION-METHOD    | Rotary Air     |
| OWNER-TYPE             | Private        |
| COMMENCE-DATE          |                |
| COMPLETION-DATE        | 1974-11-01     |
| FINAL-DEPTH (metres)   | 121.90         |
| DRILLED-DEPTH (metres) | 121.90         |
| CONTRACTOR-NAME        |                |
| DRILLER-NAME           |                |
| PROPERTY               | HIGHVIEW       |
| GWMA                   | -              |
| GW-ZONE                | -              |
| STANDING-WATER-LEVEL   |                |
| SALINITY               |                |
| YIELD                  |                |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-2N           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6594786.00        |
| EASTING          | 241213.00         |
| LATITUDE         | 30 45' 6"         |
| LONGITUDE        | 150 17' 48"       |
| GS-MAP           | 0028B4            |

AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 36

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 36 754950

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

| FROM   | TO     | THICKNESS | DESC                    | GEO-MATERIAL COMMENT |
|--------|--------|-----------|-------------------------|----------------------|
| 0.00   | 0.91   | 0.91      | Topsoil                 |                      |
| 0.91   | 4.88   | 3.97      | Clay Stoney             |                      |
| 4.88   | 10.97  | 6.09      | Clay                    |                      |
| 10.97  | 24.69  | 13.72     | Rock Soft               |                      |
| 24.69  | 40.23  | 15.54     | Rock Black Soft         |                      |
| 40.23  | 41.45  | 1.22      | Rock Black Hard         |                      |
| 41.45  | 74.07  | 32.62     | Rock Soft               |                      |
| 74.07  | 113.39 | 39.32     | Rock Black Soft         |                      |
| 113.39 | 121.92 | 8.53      | Shale Black Traces Coal |                      |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW044068

### Works Details [\(top\)](#)

|                               |                     |
|-------------------------------|---------------------|
| <b>GROUNDWATER NUMBER</b>     | GW044068            |
| <b>LIC-NUM</b>                | 90BL102845          |
| <b>AUTHORISED-PURPOSES</b>    | STOCK               |
| <b>INTENDED-PURPOSES</b>      | DOMESTIC STOCK      |
| <b>WORK-TYPE</b>              | Bore open thru rock |
| <b>WORK-STATUS</b>            | (Unknown)           |
| <b>CONSTRUCTION-METHOD</b>    | Rotary Air          |
| <b>OWNER-TYPE</b>             | Private             |
| <b>COMMENCE-DATE</b>          |                     |
| <b>COMPLETION-DATE</b>        | 1974-12-01          |
| <b>FINAL-DEPTH (metres)</b>   | 43.50               |
| <b>DRILLED-DEPTH (metres)</b> | 43.60               |
| <b>CONTRACTOR-NAME</b>        |                     |
| <b>DRILLER-NAME</b>           |                     |
| <b>PROPERTY</b>               | HIGHVIEW            |
| <b>GWMA</b>                   | -                   |
| <b>GW-ZONE</b>                | -                   |
| <b>STANDING-WATER-LEVEL</b>   |                     |
| <b>SALINITY</b>               |                     |
| <b>YIELD</b>                  |                     |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6594658.00        |
| <b>EASTING</b>          | 241030.00         |
| <b>LATITUDE</b>         | 30 45' 10"        |
| <b>LONGITUDE</b>        | 150 17' 41"       |
| <b>GS-MAP</b>           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 36

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 36 754950

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL           |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | 39.00                    | 152        |            |          | Driven into Hole |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 38.40                      | 39.00                    | 0.60                  | (Unknown)         | 18.50     |               | 0.32  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                                      | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|-------------------------------------------|--------------|---------|
| 0.00  | 0.61  | 0.61      | Topsoil                                   |              |         |
| 0.61  | 5.49  | 4.88      | Clay Sandstone                            |              |         |
| 5.49  | 9.45  | 3.96      | Clay Yellow                               |              |         |
| 9.45  | 26.52 | 17.07     | Sandstone Soft                            |              |         |
| 26.52 | 34.14 | 7.62      | Rock Black Soft                           |              |         |
| 34.14 | 38.40 | 4.26      | Rock Black                                |              |         |
| 38.40 | 39.01 | 0.61      | Rock Black Soft Stones White Water Supply |              |         |
| 39.01 | 43.59 | 4.58      | Rock Black                                |              |         |

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice

should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW044069

### Works Details [\(top\)](#)

|                               |                     |
|-------------------------------|---------------------|
| <b>GROUNDWATER NUMBER</b>     | GW044069            |
| <b>LIC-NUM</b>                | 90BL102847          |
| <b>AUTHORISED-PURPOSES</b>    | DOMESTIC STOCK      |
| <b>INTENDED-PURPOSES</b>      | DOMESTIC STOCK      |
| <b>WORK-TYPE</b>              | Bore open thru rock |
| <b>WORK-STATUS</b>            | (Unknown)           |
| <b>CONSTRUCTION-METHOD</b>    | Rotary Air          |
| <b>OWNER-TYPE</b>             | Private             |
| <b>COMMENCE-DATE</b>          |                     |
| <b>COMPLETION-DATE</b>        | 1974-12-01          |
| <b>FINAL-DEPTH (metres)</b>   | 47.80               |
| <b>DRILLED-DEPTH (metres)</b> | 47.90               |
| <b>CONTRACTOR-NAME</b>        |                     |
| <b>DRILLER-NAME</b>           |                     |
| <b>PROPERTY</b>               | HIGHVIEW            |
| <b>GWMA</b>                   | -                   |
| <b>GW-ZONE</b>                | -                   |
| <b>STANDING-WATER-LEVEL</b>   |                     |
| <b>SALINITY</b>               |                     |
| <b>YIELD</b>                  |                     |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6594934.00        |
| <b>EASTING</b>          | 240970.00         |
| <b>LATITUDE</b>         | 30 45' 1"         |
| <b>LONGITUDE</b>        | 150 17' 39"       |
| <b>GS-MAP</b>           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 36

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 36 754950

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL              |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|---------------------|
| 1           | 1           | Casing             | Threaded Steel     | -0.30                      | 41.70                    | 152        |            |          | Driven<br>into Hole |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 42.00                      | 42.90                    | 0.90                  | (Unknown)         | 19.80     |               | 0.38  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                    | GEO-MATERIAL | COMMENT |
|-------|-------|-----------|-------------------------|--------------|---------|
| 0.00  | 0.61  | 0.61      | Topsoil                 |              |         |
| 0.61  | 5.79  | 5.18      | Clay                    |              |         |
| 5.79  | 8.23  | 2.44      | Claystone               |              |         |
| 8.23  | 25.30 | 17.07     | Sandstone Clay          |              |         |
| 25.30 | 41.15 | 15.85     | Rock Soft               |              |         |
| 41.15 | 42.06 | 0.91      | Rock Black Soft         |              |         |
| 42.06 | 42.98 | 0.92      | Rock Black Water Supply | Stones White |         |
| 42.98 | 47.85 | 4.87      | Rock Black              |              |         |

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice

should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW045621

### Works Details [\(top\)](#)

|                               |                |
|-------------------------------|----------------|
| <b>GROUNDWATER NUMBER</b>     | GW045621       |
| <b>LIC-NUM</b>                | 90BL104367     |
| <b>AUTHORISED-PURPOSES</b>    | STOCK          |
| <b>INTENDED-PURPOSES</b>      | STOCK          |
| <b>WORK-TYPE</b>              | Bore           |
| <b>WORK-STATUS</b>            | Collapsed Bore |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool     |
| <b>OWNER-TYPE</b>             | Private        |
| <b>COMMENCE-DATE</b>          |                |
| <b>COMPLETION-DATE</b>        | 1930-01-01     |
| <b>FINAL-DEPTH (metres)</b>   | 10.00          |
| <b>DRILLED-DEPTH (metres)</b> | 0.00           |
| <b>CONTRACTOR-NAME</b>        |                |
| <b>DRILLER-NAME</b>           |                |
| <b>PROPERTY</b>               | KURIAL         |
| <b>GWMA</b>                   | -              |
| <b>GW-ZONE</b>                | -              |
| <b>STANDING-WATER-LEVEL</b>   |                |
| <b>SALINITY</b>               |                |
| <b>YIELD</b>                  |                |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-1S           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6595812.00        |
| <b>EASTING</b>          | 237808.00         |
| <b>LATITUDE</b>         | 30 44' 30"        |
| <b>LONGITUDE</b>        | 150 15' 41"       |
| <b>GS-MAP</b>           | 0028B3            |

AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH VICKERY  
PORTION-LOT-DP 18

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH VICKERY  
PORTION-LOT-DP 18

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|-----------|
| 1           | 1           | Casing             | Threaded Steel     | 0.00                       | 0.00                     | 600        |            |          | (Unknown) |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW050166

### Works Details [\(top\)](#)

|                               |                 |
|-------------------------------|-----------------|
| <b>GROUNDWATER NUMBER</b>     | GW050166        |
| <b>LIC-NUM</b>                | 90BL110883      |
| <b>AUTHORISED-PURPOSES</b>    | STOCK           |
| <b>INTENDED-PURPOSES</b>      | NOT KNOWN       |
| <b>WORK-TYPE</b>              | Well            |
| <b>WORK-STATUS</b>            | Supply Obtained |
| <b>CONSTRUCTION-METHOD</b>    | (Unknown)       |
| <b>OWNER-TYPE</b>             | Private         |
| <b>COMMENCE-DATE</b>          |                 |
| <b>COMPLETION-DATE</b>        | 1899-01-01      |
| <b>FINAL-DEPTH (metres)</b>   | 18.30           |
| <b>DRILLED-DEPTH (metres)</b> | 0.00            |
| <b>CONTRACTOR-NAME</b>        |                 |
| <b>DRILLER-NAME</b>           |                 |
| <b>PROPERTY</b>               | GLENROC         |
| <b>GWMA</b>                   | -               |
| <b>GW-ZONE</b>                | -               |
| <b>STANDING-WATER-LEVEL</b>   |                 |
| <b>SALINITY</b>               |                 |
| <b>YIELD</b>                  |                 |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-1S           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6595789.00        |
| <b>EASTING</b>          | 239379.00         |
| <b>LATITUDE</b>         | 30 44' 32"        |
| <b>LONGITUDE</b>        | 150 16' 40"       |
| <b>GS-MAP</b>           | 0028B3            |

AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 30

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 30

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                 |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|------------------------|
| 1           | 1           | Casing             | Timber             | 0.00                       | 0.00                     | 1829       |            |          | Suspended<br>in Clamps |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 16, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW050395

### Works Details [\(top\)](#)

|                        |                 |
|------------------------|-----------------|
| GROUNDWATER NUMBER     | GW050395        |
| LIC-NUM                | 90BL111536      |
| AUTHORISED-PURPOSES    | STOCK           |
| INTENDED-PURPOSES      | NOT KNOWN       |
| WORK-TYPE              | Bore            |
| WORK-STATUS            | Supply Obtained |
| CONSTRUCTION-METHOD    | (Unknown)       |
| OWNER-TYPE             | Private         |
| COMMENCE-DATE          |                 |
| COMPLETION-DATE        |                 |
| FINAL-DEPTH (metres)   | 36.60           |
| DRILLED-DEPTH (metres) | 0.00            |
| CONTRACTOR-NAME        |                 |
| DRILLER-NAME           |                 |
| PROPERTY               | N/A             |
| GWMA                   | -               |
| GW-ZONE                | -               |
| STANDING-WATER-LEVEL   |                 |
| SALINITY               |                 |
| YIELD                  |                 |

### Site Details [\(top\)](#)

|                  |                   |
|------------------|-------------------|
| REGION           | 90 - BARWON       |
| RIVER-BASIN      | 419 - NAMOI RIVER |
| AREA-DISTRICT    |                   |
| CMA-MAP          | 8936-1S           |
| GRID-ZONE        | 56/1              |
| SCALE            | 1:25,000          |
| ELEVATION        |                   |
| ELEVATION-SOURCE | (Unknown)         |
| NORTHING         | 6596450.00        |
| EASTING          | 239949.00         |
| LATITUDE         | 30 44' 11"        |
| LONGITUDE        | 150 17' 2"        |
| GS-MAP           | 0028B3            |

AMG-ZONE 56  
COORD-SOURCE GD.,ACC.MAP  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 30

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
PARISH TULCUMBA  
PORTION-LOT-DP 30

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|-----------|
| 1           | 1           | Casing             | (Unknown)          | 0.00                       | 0.00                     | 178        |            |          | (Unknown) |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW052958

### Works Details [\(top\)](#)

|                               |                |
|-------------------------------|----------------|
| <b>GROUNDWATER NUMBER</b>     | GW052958       |
| <b>LIC-NUM</b>                | 90BL107181     |
| <b>AUTHORISED-PURPOSES</b>    | DOMESTIC STOCK |
| <b>INTENDED-PURPOSES</b>      | DOMESTIC STOCK |
| <b>WORK-TYPE</b>              | Bore           |
| <b>WORK-STATUS</b>            | (Unknown)      |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool     |
| <b>OWNER-TYPE</b>             | Private        |
| <b>COMMENCE-DATE</b>          |                |
| <b>COMPLETION-DATE</b>        | 1980-11-01     |
| <b>FINAL-DEPTH (metres)</b>   | 53.00          |
| <b>DRILLED-DEPTH (metres)</b> | 53.00          |
| <b>CONTRACTOR-NAME</b>        |                |
| <b>DRILLER-NAME</b>           |                |
| <b>PROPERTY</b>               | SURREY         |
| <b>GWMA</b>                   | -              |
| <b>GW-ZONE</b>                | -              |
| <b>STANDING-WATER-LEVEL</b>   |                |
| <b>SALINITY</b>               |                |
| <b>YIELD</b>                  |                |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6589780.00        |
| <b>EASTING</b>          | 240669.00         |
| <b>LATITUDE</b>         | 30 47' 48"        |
| <b>LONGITUDE</b>        | 150 17' 23"       |
| <b>GS-MAP</b>           | 0028B4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 37

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH TULCUMBA  
 PORTION-LOT-DP 37

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE            | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                                              |
|-------------|-------------|--------------------|-------------------------------|----------------------------|--------------------------|------------|------------|----------|-----------------------------------------------------|
| 1           | 1           | Casing             | Corrugated<br>Galvanised Iron | -0.50                      | 42.00                    | 160        |            |          | Suspended<br>in Clamps                              |
| 1           | 1           | Casing             | Welded Steel                  | 41.00                      | 53.00                    | 130        |            |          | Seated on<br>Bottom                                 |
| 1           | 1           | Opening            | Slots - Vertical              | 36.00                      | 41.50                    | 160        |            | 1        | Oxy-<br>Acetylene<br>Slotted; SL:<br>0mm; A:<br>2mm |
| 1           | 1           | Opening            | Slots - Vertical              | 45.00                      | 48.00                    | 130        |            | 2        | Oxy-<br>Acetylene<br>Slotted; SL:<br>0mm; A:<br>2mm |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-------------------|-----------|---------------|-------|-------------------------------------|----------|----------|
| 45.00                      | 45.20                    | 0.20                  | (Unknown)         | 34.00     |               | 0.10  |                                     |          | Good     |

### Drillers Log [\(top\)](#)

| FROM | TO    | THICKNESS | DESC                   | GEO-MATERIAL | COMMENT |
|------|-------|-----------|------------------------|--------------|---------|
| 0.00 | 0.40  | 0.40      | Topsoil                |              |         |
| 0.40 | 6.30  | 5.90      | Clay Gravel            |              |         |
| 6.30 | 18.20 | 11.90     | Clay Sandy Some Gravel |              |         |

|       |       |       |                                          |
|-------|-------|-------|------------------------------------------|
| 18.20 | 21.60 | 3.40  | Clay Compacted Gravel                    |
| 21.60 | 33.10 | 11.50 | Clay Some Gravel                         |
| 33.10 | 34.90 | 1.80  | Clay Compacted Gravel                    |
| 34.90 | 41.50 | 6.60  | Clay Sandy                               |
| 41.50 | 42.10 | 0.60  | Rock Slightly Conglomerated              |
| 42.10 | 42.40 | 0.30  | Clay Gravel                              |
| 42.40 | 48.30 | 5.90  | Rock Slightly Conglomerated Water Supply |
| 48.30 | 51.00 | 2.70  | Clay Compacted Gravel                    |
| 51.00 | 52.00 | 1.00  | Clay                                     |
| 52.00 | 53.00 | 1.00  | Clay                                     |

---

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW060867

### Works Details [\(top\)](#)

|                               |                |
|-------------------------------|----------------|
| <b>GROUNDWATER NUMBER</b>     | GW060867       |
| <b>LIC-NUM</b>                | 90BL132319     |
| <b>AUTHORISED-PURPOSES</b>    | DOMESTIC STOCK |
| <b>INTENDED-PURPOSES</b>      | DOMESTIC STOCK |
| <b>WORK-TYPE</b>              | Bore           |
| <b>WORK-STATUS</b>            | (Unknown)      |
| <b>CONSTRUCTION-METHOD</b>    | Rotary Air     |
| <b>OWNER-TYPE</b>             | Private        |
| <b>COMMENCE-DATE</b>          |                |
| <b>COMPLETION-DATE</b>        | 1985-05-01     |
| <b>FINAL-DEPTH (metres)</b>   | 100.00         |
| <b>DRILLED-DEPTH (metres)</b> | 100.00         |
| <b>CONTRACTOR-NAME</b>        |                |
| <b>DRILLER-NAME</b>           |                |
| <b>PROPERTY</b>               | N/A            |
| <b>GWMA</b>                   | -              |
| <b>GW-ZONE</b>                | -              |
| <b>STANDING-WATER-LEVEL</b>   |                |
| <b>SALINITY</b>               |                |
| <b>YIELD</b>                  |                |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-1S           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6596082.00        |
| <b>EASTING</b>          | 237482.00         |
| <b>LATITUDE</b>         | 30 44' 21"        |
| <b>LONGITUDE</b>        | 150 15' 29"       |
| <b>GS-MAP</b>           | 0028B3            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH VICKERY  
 PORTION-LOT-DP 18

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH VICKERY  
 PORTION-LOT-DP 18

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE    | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                         |
|-------------|-------------|--------------------|-----------------------|----------------------------|--------------------------|------------|------------|----------|--------------------------------|
| 1           | 1           | Casing             | P.V.C.                | -0.50                      | 100.00                   | 130        |            |          | Seated<br>on<br>Bottom         |
| 1           | 1           | Opening            | Slots -<br>Horizontal | 82.00                      | 100.00                   | 130        |            | 1        | Plastic;<br>SL: 0mm;<br>A: 4mm |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-<br>CAT-<br>DESC | S-W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY  |
|----------------------------|--------------------------|-----------------------|-----------------------|-----------|---------------|-------|-------------------------------------|----------|-----------|
| 85.00                      | 86.00                    | 1.00                  | Fractured             |           |               | 1.00  |                                     |          | (Unknown) |
| 91.00                      | 92.00                    | 1.00                  | Fractured             | 40.00     |               | 1.25  |                                     |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM  | TO     | THICKNESS | DESC             | GEO-MATERIAL | COMMENT |
|-------|--------|-----------|------------------|--------------|---------|
| 0.00  | 1.00   | 1.00      | Soil Surface     |              |         |
| 1.00  | 15.00  | 14.00     | Shale            |              |         |
| 15.00 | 60.00  | 45.00     | Shale            |              |         |
| 60.00 | 85.00  | 25.00     | Basalt           |              |         |
| 85.00 | 100.00 | 15.00     | Basalt Fractured | Water Supply |         |

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources

(DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW062364

### Works Details [\(top\)](#)

|                               |                |
|-------------------------------|----------------|
| <b>GROUNDWATER NUMBER</b>     | GW062364       |
| <b>LIC-NUM</b>                | 90BL123440     |
| <b>AUTHORISED-PURPOSES</b>    | TEST BORE      |
| <b>INTENDED-PURPOSES</b>      | G/WATER XPLORE |
| <b>WORK-TYPE</b>              | Bore           |
| <b>WORK-STATUS</b>            | Test Hole      |
| <b>CONSTRUCTION-METHOD</b>    | Cable Tool     |
| <b>OWNER-TYPE</b>             | Private        |
| <b>COMMENCE-DATE</b>          |                |
| <b>COMPLETION-DATE</b>        | 1982-10-01     |
| <b>FINAL-DEPTH (metres)</b>   | 30.50          |
| <b>DRILLED-DEPTH (metres)</b> | 30.20          |
| <b>CONTRACTOR-NAME</b>        |                |
| <b>DRILLER-NAME</b>           |                |
| <b>PROPERTY</b>               | STRATFORD      |
| <b>GWMA</b>                   | -              |
| <b>GW-ZONE</b>                | -              |
| <b>STANDING-WATER-LEVEL</b>   |                |
| <b>SALINITY</b>               |                |
| <b>YIELD</b>                  |                |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-3N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> | (Unknown)         |
| <b>NORTHING</b>         | 6589356.00        |
| <b>EASTING</b>          | 234694.00         |
| <b>LATITUDE</b>         | 30 47' 57"        |
| <b>LONGITUDE</b>        | 150 13' 38"       |
| <b>GS-MAP</b>           | 0028A4            |

AMG-ZONE 56  
 COORD-SOURCE GD.,ACC.MAP  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH BENTRY  
 PORTION-LOT-DP 11

### Licensed [\(top\)](#)

COUNTY NANDEWAR  
 PARISH BENTRY  
 PORTION-LOT-DP 11

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE    | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                |
|-------------|-------------|--------------------|-----------------------|----------------------------|--------------------------|------------|------------|----------|-----------------------|
| 1           | 1           | Opening            | Slots -<br>Horizontal | 15.00                      | 22.00                    | 165        |            | 1        | SL:<br>0mm; A:<br>0mm |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-<br>W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY  |
|----------------------------|--------------------------|-----------------------|-------------------|---------------|---------------|-------|-------------------------------------|----------|-----------|
| 18.00                      | 19.00                    | 1.00                  | Unconsolidated    |               |               | 0.25  |                                     |          | (Unknown) |

### Drillers Log [\(top\)](#)

| FROM  | TO    | THICKNESS | DESC                    | GEO-MATERIAL COMMENT |
|-------|-------|-----------|-------------------------|----------------------|
| 0.00  | 3.00  | 3.00      | Clay                    |                      |
| 3.00  | 7.00  | 4.00      | Clay                    |                      |
| 7.00  | 11.00 | 4.00      | Clay Grey               |                      |
| 11.00 | 12.00 | 1.00      | Gravel Dry Clay         |                      |
| 12.00 | 19.00 | 7.00      | Clay Cream Water Supply |                      |
| 19.00 | 19.50 | 0.50      | Sand Small Gravel       |                      |
| 19.50 | 21.00 | 1.50      | Gravel Dry Clay         |                      |
| 21.00 | 22.00 | 1.00      | Rock Sharp              |                      |
| 22.00 | 28.00 | 6.00      | Basalt Grey             |                      |
| 28.00 | 28.50 | 0.50      | Clay Grey Sandy         |                      |
| 28.50 | 30.20 | 1.70      | Basalt Grey             |                      |

---

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW064948

### Works Details [\(top\)](#)

**GROUNDWATER NUMBER** GW064948  
**LIC-NUM**  
**AUTHORISED-PURPOSES**  
**INTENDED-PURPOSES** MONITORING BORE  
**WORK-TYPE** Bore  
**WORK-STATUS** (Unknown)  
**CONSTRUCTION-METHOD** Rotary Mud  
**OWNER-TYPE** Private  
**COMMENCE-DATE**  
**COMPLETION-DATE** 1985-12-01  
**FINAL-DEPTH (metres)** 49.00  
**DRILLED-DEPTH (metres)** 0.00  
**CONTRACTOR-NAME**  
**DRILLER-NAME**  
**PROPERTY**  
**GWMA**  
**GW-ZONE**  
**STANDING-WATER-LEVEL**  
**SALINITY**  
**YIELD**

### Site Details [\(top\)](#)

**REGION** 90 - BARWON  
**RIVER-BASIN** 419 - NAMOI RIVER  
**AREA-DISTRICT**  
**CMA-MAP** 8936-3N  
**GRID-ZONE** 56/1  
**SCALE** 1:25,000  
**ELEVATION**  
**ELEVATION-SOURCE**  
**NORTHING** 6590395.00  
**EASTING** 234322.00  
**LATITUDE** 30 47' 23"  
**LONGITUDE** 150 13' 25"  
**GS-MAP** 0028A4

AMG-ZONE 56  
 COORD-SOURCE  
 REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
 PARISH BRENTY  
 PORTION-LOT-DP 7

### Licensed [\(top\)](#)

no details

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
 ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                                    |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|-------------------------------------------|
| 1           | 1           | Casing             | (Unknown)          | 0.00                       | 0.00                     | 600        |            |          |                                           |
| 1           | 1           | Opening            | Screen             | 28.40                      | 33.60                    | 152        |            | 1        | Stainless<br>Steel; SL:<br>0mm; A:<br>0mm |
| 1           | 1           | Annulus            | (Unknown)          |                            | 0.00                     | 305        |            |          | GS: 5-<br>5mm                             |

### Water Bearing Zones [\(top\)](#)

| FROM-<br>DEPTH<br>(metres) | TO-<br>DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-<br>DESC | S-<br>W-<br>L | D-<br>D-<br>L | YIELD | TEST-<br>HOLE-<br>DEPTH<br>(metres) | DURATION | SALINITY |
|----------------------------|--------------------------|-----------------------|-------------------|---------------|---------------|-------|-------------------------------------|----------|----------|
| 28.40                      | 31.00                    | 2.60                  | Unconsolidated    |               |               |       |                                     |          |          |
| 32.00                      | 33.60                    | 1.60                  |                   |               |               |       |                                     |          |          |

### Drillers Log [\(top\)](#)

no details

---

**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)  
Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW064949

### Works Details [\(top\)](#)

**GROUNDWATER NUMBER** GW064949  
**LIC-NUM**  
**AUTHORISED-PURPOSES**  
**INTENDED-PURPOSES** MONITORING BORE  
**WORK-TYPE** Bore  
**WORK-STATUS** (Unknown)  
**CONSTRUCTION-METHOD** Rotary Mud  
**OWNER-TYPE** Private  
**COMMENCE-DATE**  
**COMPLETION-DATE** 1985-12-01  
**FINAL-DEPTH (metres)** 41.00  
**DRILLED-DEPTH (metres)** 0.00  
**CONTRACTOR-NAME**  
**DRILLER-NAME**  
**PROPERTY**  
**GWMA**  
**GW-ZONE**  
**STANDING-WATER-LEVEL**  
**SALINITY**  
**YIELD**

### Site Details [\(top\)](#)

**REGION** 90 - BARWON  
**RIVER-BASIN** 419 - NAMOI RIVER  
**AREA-DISTRICT**  
**CMA-MAP** 8936-3N  
**GRID-ZONE** 56/1  
**SCALE** 1:25,000  
**ELEVATION**  
**ELEVATION-SOURCE**  
**NORTHING** 6589964.00  
**EASTING** 234359.00  
**LATITUDE** 30 47' 37"  
**LONGITUDE** 150 13' 26"  
**GS-MAP** 0028A4

AMG-ZONE 56  
COORD-SOURCE  
REMARK

### Form-A [\(top\)](#)

COUNTY NANDEWAR  
PARISH BRENTY  
PORTION-LOT-DP 7

### Licensed [\(top\)](#)

no details

### Water Bearing Zones [\(top\)](#)

| FROM-DEPTH<br>(metres) | TO-DEPTH<br>(metres) | THICKNESS<br>(metres) | ROCK-CAT-DESC | S-W-L | D-D-L | YIELD | TEST-HOLE-DEPTH<br>(metres) | DURATION | SALINITY |
|------------------------|----------------------|-----------------------|---------------|-------|-------|-------|-----------------------------|----------|----------|
| 16.00                  | 18.00                | 2.00                  |               |       |       |       |                             |          |          |
| 30.20                  | 32.80                | 2.60                  |               |       |       |       |                             |          |          |

### Drillers Log [\(top\)](#)

no details

---

Warning To Clients: This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

# Groundwater Works Summary

For information on the meaning of fields please see [Glossary](#)

Document Generated on Tuesday, March 2, 2010

[Print Report](#)

[Works Details](#) [Site Details](#) [Form A](#) [Licensed](#) [Construction](#) [Water Bearing Zones](#) [Drillers Log](#)

## Work Requested -- GW968918

### Works Details [\(top\)](#)

|                               |                 |
|-------------------------------|-----------------|
| <b>GROUNDWATER NUMBER</b>     | GW968918        |
| <b>LIC-NUM</b>                | 90BL246117      |
| <b>AUTHORISED-PURPOSES</b>    | DOMESTIC STOCK  |
| <b>INTENDED-PURPOSES</b>      | DOMESTIC STOCK  |
| <b>WORK-TYPE</b>              | Bore            |
| <b>WORK-STATUS</b>            | Supply Obtained |
| <b>CONSTRUCTION-METHOD</b>    | (Unknown)       |
| <b>OWNER-TYPE</b>             | Private         |
| <b>COMMENCE-DATE</b>          |                 |
| <b>COMPLETION-DATE</b>        | 2008-09-15      |
| <b>FINAL-DEPTH (metres)</b>   | 103.00          |
| <b>DRILLED-DEPTH (metres)</b> | 103.00          |
| <b>CONTRACTOR-NAME</b>        |                 |
| <b>DRILLER-NAME</b>           |                 |
| <b>PROPERTY</b>               | YARRARI         |
| <b>GWMA</b>                   | -               |
| <b>GW-ZONE</b>                | -               |
| <b>STANDING-WATER-LEVEL</b>   | 40.00           |
| <b>SALINITY</b>               |                 |
| <b>YIELD</b>                  | 3.42            |

### Site Details [\(top\)](#)

|                         |                   |
|-------------------------|-------------------|
| <b>REGION</b>           | 90 - BARWON       |
| <b>RIVER-BASIN</b>      | 419 - NAMOI RIVER |
| <b>AREA-DISTRICT</b>    |                   |
| <b>CMA-MAP</b>          | 8936-2N           |
| <b>GRID-ZONE</b>        | 56/1              |
| <b>SCALE</b>            | 1:25,000          |
| <b>ELEVATION</b>        |                   |
| <b>ELEVATION-SOURCE</b> |                   |
| <b>NORTHING</b>         | 6594447.00        |
| <b>EASTING</b>          | 240917.00         |
| <b>LATITUDE</b>         | 30 45' 17"        |
| <b>LONGITUDE</b>        | 150 17' 37"       |
| <b>GS-MAP</b>           |                   |

**AMG-ZONE** 56  
**COORD-SOURCE** GIS - Geographic Information System  
**REMARK**

### Form-A [\(top\)](#)

**COUNTY** NANDEWAR  
**PARISH** TULCUMBA  
**PORTION-LOT-DP** 36//754950

### Licensed [\(top\)](#)

**COUNTY** NANDEWAR  
**PARISH** TULCUMBA  
**PORTION-LOT-DP** 36 754950

### Construction [\(top\)](#)

Negative depths indicate Above Ground Level;H-Hole;P-Pipe;OD-Outside Diameter;  
ID-Inside Diameter;C-Cemented;SL-Slot Length;A-Aperture;GS-Grain Size;Q-Quantity

| HOLE-<br>NO | PIPE-<br>NO | COMPONENT-<br>CODE | COMPONENT-<br>TYPE | DEPTH-<br>FROM<br>(metres) | DEPTH-<br>TO<br>(metres) | OD<br>(mm) | ID<br>(mm) | INTERVAL | DETAIL                  |
|-------------|-------------|--------------------|--------------------|----------------------------|--------------------------|------------|------------|----------|-------------------------|
| 1           |             | Hole               | Hole               | 0.00                       | 103.00                   | 125        |            |          | (Unknown)               |
| 1           | 1           | Casing             | Steel              | 0.00                       | 0.00                     | 125        |            |          | (Unknown);<br>(Unknown) |

### Water Bearing Zones [\(top\)](#)

no details

### Drillers Log [\(top\)](#)

| FROM  | TO     | THICKNESS | DESC             | GEO-MATERIAL | COMMENT |
|-------|--------|-----------|------------------|--------------|---------|
| 0.00  | 16.00  | 16.00     | Alluvium         |              |         |
| 16.00 | 37.00  | 21.00     | Basalt, flow     |              |         |
| 37.00 | 90.00  | 53.00     | Conglomerate     |              |         |
| 90.00 | 103.00 | 13.00     | Felsic Volcanics |              |         |

---


**Warning To Clients:** This raw data has been supplied to the Department of Infrastructure, Planning and Natural Resources (DIPNR) by drillers, licensees and other sources. The DIPNR does not verify the accuracy of this data. The data is presented for use by you at your own risk. You should consider verifying this data before relying on it. Professional hydrogeological advice should be sought in interpreting and using this data.

---

## Appendix E

---



- Drawing 1 – Location of Rocglen Mine
- Drawing 2 – Local Topography and Drainage
- Drawing 3 – Regional Geology
- Drawing 4 – Structure Contours – Base of Belmont Seam
- Drawing 5 – Monthly Average Rainfall and Evaporation – Gunnedah Area
- Drawing 6 – Locations of Faults – Rocglen Mine
- Drawing 7 – Lithostratigraphy at Rocglen Mine – Bore EVK110
- Drawing 8 – Local Geology – Alluvium North and South of the Mine
- Drawing 9 – Pre-mine Groundwater Levels (After RCA, 2007)
- Drawing 10 – Locations of Groundwater Monitoring Bores
- Drawing 11 – Locations of Private Groundwater Bores
- Drawing 12 – Model Predicted and Monitored Drawdown – Rocglen Pit



-  Major Road
-  Railway Line
-  Major Stream
-  Population Centre

Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)



|                                                                                                                                                        |  |                                                                                  |                   |                                                                                  |  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------|-------------------|----------------------------------------------------------------------------------|--|
|  <b>Douglas Partners</b><br>Geotechnics • Environment • Groundwater |  | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne |                   | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |  |
| TITLE LOCATION OF ROCGLLEN MINE<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales      |  |                                                                                  |                   |                                                                                  |  |
| CLIENT: GSS ENVIRONMENTAL                                                                                                                              |  |                                                                                  | OFFICE: NEWCASTLE |                                                                                  |  |
| DRAWN BY: AMP                                                                                                                                          |  | SCALE: 1:750000                                                                  |                   | PROJ NO: 49532.00                                                                |  |
| APPROVED BY: IDH                                                                                                                                       |  | DATE: Mar 2010                                                                   |                   | DRAWING NO: 1                                                                    |  |



Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)


|                                                                                                                                                        |                   |                                                                                  |                                                                                  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br>Geotechnics • Environment • Groundwater |                   | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| TITLE LOCAL TOPOGRAPHY & DRAINAGE<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales    |                   |                                                                                  |                                                                                  |
| CLIENT:                                                                                                                                                | GSS ENVIRONMENTAL |                                                                                  | OFFICE: NEWCASTLE                                                                |
| DRAWN BY: AMP                                                                                                                                          | SCALE: 1:60,000   | PROJ NO: 49532.00                                                                | DRAWING NO: 2                                                                    |
| APPROVED BY: IDH                                                                                                                                       | DATE: Mar 2010    |                                                                                  |                                                                                  |






Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)

|                                                                                                                                                                          |                 |                                                                                  |                      |                                                                                  |  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------------------------------------------------------------------------------|----------------------|----------------------------------------------------------------------------------|--|
|  <b>Douglas Partners</b><br>Geotechnics - Environment - Groundwater                   |                 | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne |                      | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |  |
| TITLE <b>STRUCTURE CONTOURS - BASE OF BELMONT SEAM</b><br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |                 |                                                                                  |                      |                                                                                  |  |
| CLIENT: <b>GSS ENVIRONMENTAL</b>                                                                                                                                         |                 | OFFICE: NEWCASTLE                                                                |                      |                                                                                  |  |
| DRAWN BY: AMP                                                                                                                                                            | SCALE: 1:17,500 | PROJ NO: 49532.00                                                                | DRAWING NO:        4 |                                                                                  |  |
| APPROVED BY:    IDH                                                                                                                                                      |                 | DATE:    Mar 2010                                                                |                      |                                                                                  |  |



 **Rainfall**  
 **Evaporation**



**Douglas Partners**  
Geotechnics • Environment • Groundwater

Brisbane, Cairns,  
Campbelltown, Canberra,  
Darwin, Gold Coast,  
Melbourne




Newcastle, Perth,  
Sunshine Coast, Sydney,  
Townsville, Wollongong,  
Wyong

**TITLE:** MONTHLY AVERAGE RAINFALL & EVAPORATION - GUNNEDAH AREA  
Hydrogeological Assessment for Rocglen Coal Mine Expansion  
Rocglen Coal Mine, via Gunnedah, New South Wales

**CLIENT:** GSS ENVIRONMENTAL **OFFICE:** NEWCASTLE


**DRAWN BY:** AMP **PROJECT NO:** 49532.00 **DRAWING NO:** 5

**APPROVED:** **DATE:** Mar 2010



Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)

|                                                                                                                                                           |                 |                                                                                  |                                                                                  |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br>Geotechnics • Environment • Groundwater    |                 | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyang |
| TITLE LOCATIONS OF FAULTS - ROGLEN MINE<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |                 |                                                                                  |                                                                                  |
| CLIENT: GSS ENVIRONMENTAL                                                                                                                                 |                 | OFFICE: NEWCASTLE                                                                |                                                                                  |
| DRAWN BY: AMP                                                                                                                                             | SCALE: 1:50,000 | PROJ NO: 49532.00                                                                | DRAWING NO: 6                                                                    |
| APPROVED BY: IDH                                                                                                                                          |                 | DATE: Mar 2010                                                                   |                                                                                  |



ROCGLLEN DEPOSIT



**Douglas Partners**  
Geotechnics • Environment • Groundwater

Brisbane, Cairns,  
Campbelltown, Canberra,  
Darwin, Gold Coast,  
Melbourne

Newcastle, Perth,  
Sunshine Coast, Sydney,  
Townsville, Wollongong,  
Wyong

TITLE LITHOSTRATIGRAPHY AT ROCGLLEN MINE - BORE EVK110  
Hydrogeological Assessment for Rocglen Coal Mine Expansion  
Rocglen Coal Mine, via Gunnedah, New South Wales

CLIENT: GSS ENVIRONMENTAL

OFFICE: NEWCASTLE

DRAWN BY: AMP



SCALE: N/A

PROJ NO: 49532.00

DRAWING NO: 7



APPROVED BY: IDH

DATE: Mar 2010



Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)

|                                                                                                                                                                        |                 |                                                                                  |                                                                                  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br>Geotechnics • Environment • Groundwater                 |                 | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| TITLE LOCAL GEOLOGY - ALLUVIUM NORTH & SOUTH OF MINE<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |                 |                                                                                  |                                                                                  |
| CLIENT: GSS ENVIRONMENTAL                                                                                                                                              |                 | OFFICE: NEWCASTLE                                                                |                                                                                  |
| DRAWN BY: AMP                                                                                                                                                          | SCALE: 1:50,000 | PROJ NO: 49532.00                                                                | DRAWING NO: 8                                                                    |
| APPROVED BY: IDH                                                                                                                                                       |                 | DATE: Mar 2010                                                                   |                                                                                  |






  
**Outline of ML1620**

  
**Extent of Mining at  
end December, 2009**

  
**Limit of proposed  
extension**


Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)

|                                                                                                                                                                         |                 |                                                                                  |                                                                                  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br>Geotechnics • Environment • Groundwater                  |                 | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| TITLE PRE-MINING GROUNDWATER LEVELS (After RCA, 2007)<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |                 |                                                                                  |                                                                                  |
| CLIENT: GSS ENVIRONMENTAL                                                                                                                                               |                 | OFFICE: NEWCASTLE                                                                |                                                                                  |
| DRAWN BY: AMP                                                                                                                                                           | SCALE: 1:60,000 | PROJ NO: 49532.00                                                                | DRAWING NO: 9                                                                    |
| APPROVED BY: IDH                                                                                                                                                        |                 | DATE: Mar 2010                                                                   |                                                                                  |




Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)

|                                                                                                                                                                   |                 |                                                                                  |                                                                                  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br><i>Geotechnics • Environment • Groundwater</i>     |                 | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyong |
| TITLE LOCATIONS OF GROUNDWATER MONITORING BORES<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |                 |                                                                                  |                                                                                  |
| CLIENT: GSS ENVIRONMENTAL                                                                                                                                         |                 | OFFICE: NEWCASTLE                                                                |                                                                                  |
| DRAWN BY: AMP                                                                                                                                                     | SCALE: 1:60,000 | PROJ NO: 49532.00                                                                | DRAWING NO: 10                                                                   |
| APPROVED BY: IDH                                                                                                                                                  |                 | DATE: Mar 2010                                                                   |                                                                                  |



Projection - GDA94 Zone 56  
Level Datum - Australian Height Datum (AHD)

|                                                                                                                                                                |                 |                                                                                  |                                                                                  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
|  <b>Douglas Partners</b><br><i>Geotechnics • Environment • Groundwater</i>  |                 | Brisbane, Cairns,<br>Campbelltown, Canberra,<br>Darwin, Gold Coast,<br>Melbourne | Newcastle, Perth,<br>Sunshine Coast, Sydney,<br>Townsville, Wollongong,<br>Wyang |
| TITLE LOCATIONS OF PRIVATE GROUNDWATER BORES<br>Hydrogeological Assessment for Rocglen Coal Mine Expansion<br>Rocglen Coal Mine, via Gunnedah, New South Wales |                 |                                                                                  |                                                                                  |
| CLIENT: GSS ENVIRONMENTAL                                                                                                                                      |                 | OFFICE: NEWCASTLE                                                                |                                                                                  |
| DRAWN BY: AMP                                                                                                                                                  | SCALE: 1:60,000 | PROJ NO: 49532.00                                                                | DRAWING NO: 11                                                                   |
| APPROVED BY: IDH                                                                                                                                               |                 | DATE: Mar 2010                                                                   |                                                                                  |



★ ★ ★ **Measured GW Level (WHM)**  
--- **Current Drawdown Trend**  
--- **Modelled Prediction - RCA (2007)**



**Douglas Partners**  
Geotechnics • Environment • Groundwater

Brisbane, Cairns,  
Campbelltown, Canberra,  
Darwin, Gold Coast,  
Melbourne

Newcastle, Perth,  
Sunshine Coast, Sydney,  
Townsville, Wollongong,  
Wyong

**TITLE:** MODEL PREDICTED & MONITORED DRAWDOWN - ROCGLLEN PIT  
Hydrogeological Assessment for Rocglen Coal Mine Expansion  
Rocglen Coal Mine, via Gunnedah, New South Wales

**CLIENT:** GSS ENVIRONMENTAL

**OFFICE:** NEWCASTLE

**DRAWN BY:** AP

**PROJECT NO:** 49532.00

**DRAWING NO:** 12

**APPROVED:**

**DATE:** Apr 2010