

Waste Management Plan

Prepared for: Meriton Apartments

Project Site: 131-138 Killeaton Street St Ives NSW

Date of Issue: 8th December 2010 rev1

Prepared by: Shane Johnson – Project Manager



WASTECH SERVICES PTY LTD

Free Call: 1800 465 465

Online: wastech.com.au

ABN: 52 059 404 152

CONTENTS

1.	INTRODUCTION	3
2.	SUMMARY	4
3.	WASTE MANAGEMENT PLAN	5
3.1	Inclusions	5
3.2	Exclusions.....	5
3.3	REFUSE ROOM DIMENSIONS	6
4.	GENERATED WASTE VOLUME ESTIMATE	8
5.	RESIDENTIAL WASTE MANAGEMENT	9
5.1	Waste Streams	9
5.2	Residential Garbage Disposal.....	9
5.3	Residential Recyclable Disposal.....	9
5.4	Residential Garbage & Recycling Collection.....	9
6.	RESIDENTIAL WASTE HANDLING EQUIPMENT	10
6.1	Residential Waste Calculations.....	11
7.	BIN SUMMARY	17
7.1	Residential Refuse Rooms	17
7.2	Bins Presented For Collection.....	18
8.	WASTE MINIMISATION STRATEGIES	19
9.	ADDITIONAL WASTE MANAGEMENT INFORMATION	20
10.	CONTACT INFORMATION	21

1. INTRODUCTION

Wastech Services Pty Ltd was commissioned by Meriton Apartments to prepare a waste and recycling plan associated with a proposed development to be located at 131-138 Killeaton Street St Ives New South Wales.

The project consists of:

- Six (6) Residential Apartment Buildings incorporating;
- 57 Residential Units to Building A
- 72 Residential Units to Building B
- 28 Residential Units to Building C
- 81 Residential Units to Building D
- 36 Residential Units to Building E
- 24 Residential Units to Building F

Scope: Wastech Services will review the building layout drawings and apartment details and provide a Waste Management Plan including the following:

- Calculation of weekly waste and recyclable volumes
- Provide recommendations for compaction, storage and transportation of waste and recyclables within the building
- Highlight relevant design issues that may affect the handling and movement of Waste and Recyclables within the development
- Include technical brochures and drawings for recommended equipment
- Provide recommendation for collection vehicle type
- Reference collection companies and/or council collection/disposal services
- Provide a bound, hard copy and electronic version of the report

All recommendations and equipment shall be in compliance with council codes, BCA, Australian Standards, and statutory requirements.

The results of the above analyses are outlined in the following sections.

2. SUMMARY

- Residents will be responsible for disposing of bagged garbage into the garbage chutes
- Residents will separate recyclable waste into paper/cardboard and containers for disposal into crates at each apartment level
- The building manager will collect recycling crates from each apartment level for emptying into the 240 litre paper/cardboard and container recycling collection bins located in the carpark level refuse rooms
- The building manager will be responsible for monitoring garbage bin levels ensuring clean empty bins are available to receive waste from the chutes
- The building manager will be responsible for transferring all full bins for collection from the refuse rooms to the collection point and return to the refuse rooms upon completion of collection
- All garbage and recycling waste collections shall be performed weekly by Ku-ring-gai Council. Collections shall be conducted at the carpark level loading dock with entry off Killeaton Street

3. WASTE MANAGEMENT PLAN

This waste management plan is based on the following conditions

3.1 Inclusions

- On-going use of the premises. Does not include demolition or construction stages.
- Figures and calculations are based on drawings and information supplied by Meriton Apartments.
- Waste volume figures are estimates only and will be influenced by the tenant, resident and operator's disposition toward waste disposal and recycling, and by the development's occupancy rate. Refer to the enclosed tables for rates and assumptions.

3.2 Exclusions

- Hard rubbish and green/garden wastes. Disposal shall be arranged by the building manager via appropriate contractors.

3.3 REFUSE ROOM DIMENSIONS

The residential refuse rooms, as shown on drawings DA 15 rev B and DA 16 rev B, are sufficient to accommodate the garbage equipment and bins specified within this report.

The bin holding room/collection zone at the loading dock collection point, as shown on drawing DA 16 rev B, is sufficient to accommodate the quantity of bins presented for collection.

BUILDING A REFUSE ROOM DIMENSIONS					
Bin Type	Length (mm)	Width (mm)	Quantity	Area Required (m ²)	
660 litre	1370	850	4	4.66	
240 litre	585	730	30	12.81	
(above figures do not allow for bin movements)					
Ecopack compactor over 660 litre bin			1	2.50	
TOTAL AREA REQUIRED				19.97	
TOTAL AREA PROVIDED				27.80	

BUILDING B REFUSE ROOM DIMENSIONS					
Bin Type	Length (mm)	Width (mm)	Quantity	Area Required (m ²)	
660 litre	1370	850	5	5.82	
240 litre	585	730	36	15.37	
(above figures do not allow for bin movements)					
Ecopack compactor over 660 litre bin			1	2.50	
TOTAL AREA REQUIRED				23.70	
TOTAL AREA PROVIDED				29.70	

BUILDING C REFUSE ROOM DIMENSIONS					
Bin Type	Length (mm)	Width (mm)	Quantity	Area Required (m ²)	
660 litre	1370	850	2	2.33	
240 litre	585	730	14	5.98	
(above figures do not allow for bin movements)					
Ecopack compactor over 660 litre bin			1	2.50	
TOTAL AREA REQUIRED				10.81	
TOTAL AREA PROVIDED				39.20	

BUILDING D REFUSE ROOM DIMENSIONS					
Bin Type	Length (mm)	Width (mm)	Quantity	Area Required (m ²)	
660 litre	1370	850	5	5.82	
240 litre	585	730	42	17.94	
(above figures do not allow for bin movements)					
Ecopack compactor over 660 litre bin			1	2.50	
TOTAL AREA REQUIRED				26.26	
TOTAL AREA PROVIDED				37.70	

BUILDING E REFUSE ROOM DIMENSIONS					
Bin Type	Length (mm)	Width (mm)	Quantity	Area Required (m ²)	
660 litre	1370	850	3	3.49	
240 litre	585	730	18	7.69	
(above figures do not allow for bin movements)					
Ecopack compactor over 660 litre bin			1	2.50	
TOTAL AREA REQUIRED				13.68	
TOTAL AREA PROVIDED				27.10	

BUILDING F REFUSE ROOM DIMENSIONS					
Bin Type	Length (mm)	Width (mm)	Quantity	Area Required (m ²)	
660 litre	1370	850	2	2.33	
240 litre	585	730	12	5.12	
(above figures do not allow for bin movements)					
Ecopack compactor over 660 litre bin			1	2.50	
TOTAL AREA REQUIRED				9.95	
TOTAL AREA PROVIDED				27.80	

BIN HOLDING ROOM / COLLECTION ZONE DIMENSIONS					
Bin Type	Length (mm)	Width (mm)	Quantity	Area Required (m ²)	
660 litre	1370	850	16	18.63	
240 litre	585	730	152	64.91	
(above figures do not allow for bin movements)					
TOTAL AREA REQUIRED				83.54	
TOTAL AREA PROVIDED				114.00	

4. GENERATED WASTE VOLUME ESTIMATE

The enclosed waste estimates, expressed in uncompacted cubic metres per week, are summarised as follows;

Refer to the enclosed waste generation calculations for further detail.

RESIDENTIAL WASTE	Garbage	Paper/Cardboard Recycling	Container Recycling
Building A Residential Apartments	6.84	3.42	3.42
Building B Residential Apartments	8.64	4.32	4.32
Building C Residential Apartments	3.36	1.68	1.68
Building D Residential Apartments	9.72	4.86	4.86
Building E Residential Apartments	4.32	2.16	2.16
Building F Residential Apartments	2.88	1.44	1.44
Total (m³/wk uncompacted)	35.76	17.88	17.88
Bin	660 litre bins	240 litre bins	240 litre bins

5. RESIDENTIAL WASTE MANAGEMENT

The following is recommended:

5.1 Waste Streams

Residential waste shall be sorted on-site by the residents into the following streams and associated bins:

- Garbage;
- Paper/Cardboard Recycling; and
- Container Recycling (PET, aluminium, steel, HDPE)

5.2 Residential Garbage Disposal

Residential apartments shall be furnished with plastic lined under bench storage bins, with a minimum capacity of 15 litres, for the temporary holding of garbage waste. Residents shall transfer bagged garbage to the garbage chutes for disposal. Each chute shall serve all apartment levels and discharge into a compactor with 660 litre bin at the carpark level refuse rooms. The building manager shall replace full bins with clean, empty ones as required.

5.3 Residential Recyclable Disposal

Residents shall transfer recyclables into the 120 or 240 litre bins located within the chute airlock at each apartment level for disposal. Cardboard shall be flattened and containers rinsed and cleaned prior to disposal.

Residential apartments shall be furnished with under bench storage bins for the temporary holding of recyclable waste with a minimum capacity of 10 litres. Residents shall sort recyclables into paper/cardboard and containers for disposal into crates located within the chute air lock / loading room at each apartment level. Residents shall flatten cardboard and rinse and clean containers prior to disposal.

The building manager shall collect crates, as required, from each apartment level and transfer recyclables to the 240 litre paper/cardboard and container recycling collection bins located in the carpark level refuse rooms. Note: recycling items must be separated into paper/cardboard and recyclable containers as per council requirements.

5.4 Residential Garbage & Recycling Collection

The building manager shall make 240 and 660 litre bin transfers between the refuse rooms and the bin store room/holding zone in building C at carpark level. The building manager shall prepare bins for collection and coordinate with collection vehicle arrivals so that bins do not impede vehicle access into the loading dock or carpark entry at building C. Full bins only are to be transferred to the bin store room/bin holding zone on day of collection, utilising a bin trailer/bin tug or similar, and returned to the refuse rooms upon completion of collection.

Weekly garbage and recycling collections are envisaged for all buildings.

The collection of waste and recycling bins is to be performed by Ku-ring-gai Council, to be confirmed by Meriton Apartments, from the designated collection point at the carpark level loading dock with entry off Killeaton Street. All collections shall be performed in accordance with local law requirements. The collection contractor shall transfer bins for collection from the bin store room/holding zone to the collection vehicle and return emptied bins to the bin store room/holding zone upon completion of collection.

The minimum overhead clearance height for a rear lift garbage collection truck is 2.5m. An overhead clearance height of 2.8m is provided at the carpark level loading dock and for the collection vehicle path of travel.

Attached drawings SP1 and SP2, provided by Transport and Traffic Planning Associates, and DA 16 rev B provided by Meriton Apartments, confirms sufficient area is provided for the collection vehicle turning circle and swept path from Killeaton Street to the loading dock collection point within the carpark level of building C.

6. RESIDENTIAL WASTE HANDLING EQUIPMENT

The following waste handling equipment is recommended:

Garbage Chute: 530mm diameter galvanised steel or Smoothubes® chute serving all apartment levels, as supplied by Wastech Engineering (or equivalent).

Quantity required five (5); one per building

Garbage Compactor: Automated EcoPack garbage-chute compactor to suit discharge into a single 660 litre bin, as supplied by Wastech Services (or equivalent).

Quantity required = five (5); one per building

Note: the Ecopack compactor does not compact waste into the collection bin. All compaction forces are contained within the compactor itself with waste then deposited into the collection bin below. Ku-Ring-Gai Council policy does not allow for compaction of garbage waste directly into collection bins. See attached diagram indicating compaction method for the Ecopack compactor.

Crates

Bin Type	50L Crate	70L Crate	90L Crate
Height	320 mm	395 mm	420 mm
Length	575 mm	575 mm	450 mm
Width	445 mm	445 mm	450 mm



* Crate type to be confirmed by building management. Minimum 1 crate per apartment level per building for paper/cardboard disposal and 1 crate per apartment level per building for container recycling collection. Crates to be emptied into 240 litre collection bins by the building manager. Crates are to be used for recyclables collection at the apartment levels to prevent less than full bins being transferred to the collection point. The building manager shall systematically empty recyclables into the 240 collection bins so that full bins only are presented for collection.

6.1 Residential Waste Calculations

Building A - 131-138 Killeaton Street St Ives		
GARBAGE		
Weekly Garbage Volume (Uncompacted)	6.84	cubic metres
Weekly Garbage Volume (Compacted 3:1)	2.28	cubic metres
Bin Type	660	litre
Frequency of collection	1	per week
Bins required for collection (volume / bin capacity)	3	
Spare Bins required	1	
Garbage Total bins required	4	

PAPER / CARDBOARD RECYCLING		
Weekly Paper/Cardboard Volume	3.42	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	15	
Paper/Cardboard Total bins required	15	

CONTAINER RECYCLING		
Weekly Container Volume	3.42	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	15	
Container Total bins required	15	

Building B - 131-138 Killeaton Street St Ives		
GARBAGE		
Weekly Garbage Volume (Uncompacted)	8.64	cubic metres
Weekly Garbage Volume (Compacted 3:1)	2.88	cubic metres
Bin Type	660	litre
Frequency of collection	1	per week
Bins required for collection (volume / bin capacity)	4	
Spare Bins required	1	
Garbage Total bins required	5	

PAPER / CARDBOARD RECYCLING		
Weekly Paper/Cardboard Volume	4.32	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	18	
Paper/Cardboard Total bins required	18	

CONTAINER RECYCLING		
Weekly Container Volume	4.32	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	18	
Container Total bins required	18	

Building C - 131-138 Killeaton Street St Ives		
GARBAGE		
Weekly Garbage Volume (Uncompacted)	3.36	cubic metres
Weekly Garbage Volume (Compacted 3:1)	1.12	cubic metres
Bin Type	660	litre
Frequency of collection	1	per week
Bins required for collection (volume / bin capacity)	1	
Spare Bins required	1	
Garbage Total bins required	2	

PAPER / CARDBOARD RECYCLING		
Weekly Paper/Cardboard Volume	1.68	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	7	
Paper/Cardboard Total bins required	7	

CONTAINER RECYCLING		
Weekly Container Volume	1.68	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	7	
Container Total bins required	7	

Building D - 131-138 Killeaton Street St Ives		
GARBAGE		
Weekly Garbage Volume (Uncompacted)	9.72	cubic metres
Weekly Garbage Volume (Compacted 3:1)	3.24	cubic metres
Bin Type	660	litre
Frequency of collection	1	per week
Bins required for collection (volume / bin capacity)	4	
Spare Bins required	1	
Garbage Total bins required	5	

PAPER / CARDBOARD RECYCLING		
Weekly Paper/Cardboard Volume	4.86	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	21	
Paper/Cardboard Total bins required	21	

CONTAINER RECYCLING		
Weekly Container Volume	4.86	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	21	
Container Total bins required	21	

Building E - 131-138 Killeaton Street St Ives		
GARBAGE		
Weekly Garbage Volume (Uncompacted)	4.32	cubic metres
Weekly Garbage Volume (Compacted 3:1)	1.44	cubic metres
Bin Type	660	litre
Frequency of collection	1	per week
Bins required for collection (volume / bin capacity)	2	
Spare Bins required	1	
Garbage Total bins required	3	

PAPER / CARDBOARD RECYCLING		
Weekly Paper/Cardboard Volume	2.16	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	9	
Paper/Cardboard Total bins required	9	

CONTAINER RECYCLING		
Weekly Container Volume	2.16	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	9	
Container Total bins required	9	

Building F - 131-138 Killeaton Street St Ives		
GARBAGE		
Weekly Garbage Volume (Uncompacted)	2.88	cubic metres
Weekly Garbage Volume (Compacted 3:1)	0.96	cubic metres
Bin Type	660	litre
Frequency of collection	1	per week
Bins required for collection (volume / bin capacity)	2	
Spare Bins required	1	
Garbage Total bins required	3	

PAPER / CARDBOARD RECYCLING		
Weekly Paper/Cardboard Volume	1.44	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	6	
Paper/Cardboard Total bins required	6	

CONTAINER RECYCLING		
Weekly Container Volume	1.44	cubic metres
Bin Type	240	litre
Frequency of collection	1	per week
Bins required for collection	6	
Container Total bins required	6	

7. BIN SUMMARY

7.1 Residential Refuse Rooms

Building A Refuse Room

660 litre Garbage bins	3
Spare 660 litre Garbage bins	1
240 litre Paper/Cardboard bins	15
240 litre Container bins	15
TOTAL BINS REQUIRED	19

Building B Refuse Room

660 litre Garbage bins	4
Spare 660 litre Garbage bins	1
240 litre Paper/Cardboard bins	18
240 litre Container bins	18
TOTAL BINS REQUIRED	23

Building C Refuse Room

660 litre Garbage bins	1
Spare 660 litre Garbage bins	1
240 litre Paper/Cardboard bins	7
240 litre Container bins	7
TOTAL BINS REQUIRED	16

Building D Refuse Room

660 litre Garbage bins	4
Spare 660 litre Garbage bins	1
240 litre Paper/Cardboard bins	21
240 litre Container bins	21
TOTAL BINS REQUIRED	47

Building E Refuse Room

660 litre Garbage bins	2
Spare 660 litre Garbage bins	1
240 litre Paper/Cardboard bins	9
240 litre Container bins	9
TOTAL BINS REQUIRED	21

Building F Refuse Room

660 litre Garbage bins	2
Spare 660 litre Garbage bins	1
240 litre Paper/Cardboard bins	6
240 litre Container bins	6
TOTAL BINS REQUIRED	15


7.2 Bins Presented For Collection

Buildings A B C D E and F

660 litre Garbage bins	16
240 litre Paper/Cardboard bins	76
240 litre Container bins	76
TOTAL BINS PRESENTED	168

8. WASTE MINIMISATION STRATEGIES

The operator (Body Corporate) will be responsible for the education of residential tenants in the practices of waste reduction/minimisation to divert waste from landfill. This will be achieved by the following:



- Document and distribute details of the waste management system that is in place on site to all residents
- Distribution of notices to all residents encouraging waste separation
- All bins to be labelled and colour coded stating types of waste that can be deposited i.e. paper/cardboard bins, container recycling bins, garbage bins
- Residents will be provided with a manual, upon residency, detailing items that can be disposed of via the garbage chute in accordance with the manufacturers recommendations
- Any future change to regulatory requirements or to the developments' waste generation rates will require the operator to conduct a waste audit and revise the waste management system that is in place accordingly

9. ADDITIONAL WASTE MANAGEMENT INFORMATION

As bins would be “wheeled” throughout the building, any ramps would require a maximum gradient of 1:14 to meet regulatory requirements. Steps are not permitted.

Items unsuitable for disposal via garbage or recycling bins would need to be disposed of with the assistance of the building manager. This would include: large, heavy, and liquid waste items.

To minimise security, vandalism, odour/visual impact, and health/safety issues, the following shall be implemented:

- Transferring waste and shifting bins shall require the minimum possible manual handling. The operator will assess manual handling risks as per regulatory requirements and provide appropriate documentation to the building manager;
- Signage and usage labels for the garbage and recycling bins will be provided by the operator;
- Bin stores will be secure and vermin proof and ventilated in accordance with Australian Standard AS 1668.2;
- A bin wash area comprising hot and cold water taps and floor drain with trap and sewer connection will be located within each bin store;
- The building manager shall keep clean the bin stores, keep bin lids closed and wash bins regularly;
- The operator shall consider providing 660 litre charity/donation bins for the collection of clothing, whitegoods etc to divert waste from landfill. Donation bins would be maintained and collected by the charity organisation;
- Keys to the security gates at the basement entry point, which shall be keyed alike to Ku-Ring-Gai Council’s master key, are to be provided to Ku-Ring-Gai council by the operator to ensure the collection vehicle has access to the collection point;
- A designated hard rubbish collection point shall be provided with a minimum footprint of 2m² to each building for residents to place hard rubbish for collection on specified days;
- The building manager will ensure prompt return of empty bins to the refuse rooms once collection has occurred;
- Use of the private road through the development results in indemnity issues for the collection providers. Indemnity resolution is required prior to waste collections being performed on site;
- The Body Corporate of the proposed development shall source and enter into service agreements for waste collection services. The Body Corporate will be responsible for all payments and costs associated with the waste collection service provided by Ku-Ring-Gai Council;
- The building manager shall prepare operational instructions and an operational health and safety procedure for site staff; and
- A traffic management plan and collection-vehicle safe operation procedure shall be prepared by the operator of the development in consultation with Ku-Ring-Gai Council prior to collections being performed on site.

10. CONTACT INFORMATION

Ku-ring-gai Council

818 Pacific Highway, Gordon NSW 2072
Locked Bag 1056, Pymble NSW 2073
Ph: 9424 0000
Fax: 9424 0001
E-mail: kmc@kmc.nsw.gov.au

SITA Environmental Solutions

(private waste collector)
201-205 Newton Road, Wetherill Park, NSW 2164
Ph: 9725 3255

Veolia Environmental Services

(private waste collector)
Cnr Unwin and Shirley Streets, Rosehill NSW 2142
Ph: 132 955

VISY Waste Management Integrated Solutions

(private waste collector)
6 Herbert Place, Smithfield, NSW 2164
Ph: 9794 3188

Electrodrive Pty Ltd

(tug manufacturer)
C/o Wastech Engineering

Eco-Safe Technologies

(odour control equipment supplier)
C/o Wastech Engineering

Wastech Engineering Pty. Ltd.

Waste Equipment Designer & Manufacturer
Valerie Collins
National Sales Executive
33 Wedgewood Road, Hallam VIC 3803
Ph 03 8787 1600
valerie@wastech.com.au



WASTE ESTIMATE Residential

Job:	Building A - 131-138 Killeaton Street St Ives		Date:	7-Dec-10
<u>No. OF RESIDENTIAL APARTMENTS</u>		57		
Garbage (m ³ /week uncompacted):	6.84	(Rate/apartment) ¹ :	0.120	
Paper/Cardboard Recycling (m ³ /week uncompacted):	3.42	(Rate/apartment) ¹ :	0.060	
Container Recycling (m ³ /week uncompacted):	3.42	(Rate/apartment) ¹ :	0.060	

<u>TOTAL RESIDENTIAL APARTMENT WASTE BLOCK A</u>	
Garbage (m ³ /week uncompacted):	6.84
Paper/Cardboard Recycling (m ³ /week uncompacted):	3.42
Container Recycling (m ³ /week uncompacted):	3.42

COMPACTOR DETAILS (garbage only - via refuse chute)				
Bin Size (litres)	Compaction Ratio	No. of Bins under compactor		No. of Bins Filled per Week
660	0.33	1		3.5

COLLECTIONS	Collections Per Week	No. of Bins Collected
Garbage Disposal	1 per week (660 litre bins)	3.5
Paper/Cardboard Recyc.	1 per week (240 litre bins)	14.3
Container Recyc.	1 per week (240 litre bins)	14.3

References/Notes:

- 1) Ku-Ring-Gai Council Development Control Plan (Town Centres) 2010



WASTE ESTIMATE Residential

Job:	Building B - 131-138 Killeaton Street St Ives	Date:	7-Dec-10
<u>No. OF 1 BEDROOM RESIDENTIAL APARTMENTS</u>		72	
Garbage (m ³ /week uncompacted):	8.64	(Rate/apartment) ¹ :	0.120
Paper/Cardboard Recycling (m ³ /week uncompacted):	4.32	(Rate/apartment) ¹ :	0.060
Container Recycling (m ³ /week uncompacted):	4.32	(Rate/apartment) ¹ :	0.060

<u>TOTAL RESIDENTIAL APARTMENT WASTE BLOCK B</u>	
Garbage (m ³ /week uncompacted):	8.64
Paper/Cardboard Recycling (m ³ /week uncompacted):	4.32
Container Recycling (m ³ /week uncompacted):	4.32

COMPACTOR DETAILS (garbage only - via refuse chute)				
Bin Size (litres)	Compaction Ratio	No. of Bins in Rotofeed		No. of Bins Filled per Week
660	0.33	1		4.4

COLLECTIONS	Collections Per Week	No. of Bins Collected
Garbage Disposal	1 per week (660 litre bins)	4.4
Paper/Cardboard Recyc.	1 per week (240 litre bins)	18.0
Container Recyc.	1 per week (240 litre bins)	18.0

References/Notes:

- 1) Ku-Ring-Gai Council Development Control Plan (Town Centres) 2010



WASTE ESTIMATE

Residential

Job:	Building C - 131-138 Killeaton Street St Ives		Date:	7-Dec-10
No. OF RESIDENTIAL APARTMENTS	28			
Garbage (m ³ /week uncompacted):	3.36	(Rate/apartment) ¹ :	0.120	
Paper/Cardboard Recycling (m ³ /week uncompacted):	1.68	(Rate/apartment) ¹ :	0.060	
Container Recycling (m ³ /week uncompacted):	1.68	(Rate/apartment) ¹ :	0.060	

<u>TOTAL RESIDENTIAL APARTMENT WASTE BLOCK C</u>			
Garbage (m ³ /week uncompacted):	3.36	-	-
Paper/Cardboard Recycling (m ³ /week uncompacted):	1.68		
Container Recycling (m ³ /week uncompacted):	1.68		

COMPACTOR DETAILS (garbage only - via refuse chute)				
Bin Size (litres)	Compaction Ratio	No. of Bins under compactor		No. of Bins Filled per Week
660	0.33	1		1.7

References/Notes:

COLLECTIONS	Collections Per Week	No. of Bins Collected
Garbage Disposal	1 per week (660 litre bins)	1.7
Paper/Cardboard Recyc.	1 per week (240 litre bins)	7.0
Container Recyc.	1 per week (240 litre bins)	7.0

References/Notes:

- 1) Ku-Ring-Gai Council Development Control Plan (Town Centres) 2010



WASTE ESTIMATE Residential

Job:	Building D - 131-138 Killeaton Street St Ives	Date:	7-Dec-10
<u>No. OF 1 BEDROOM RESIDENTIAL APARTMENTS</u>		81	
Garbage (m ³ /week uncompacted):	9.72	(Rate/apartment) ¹ :	0.120
Paper/Cardboard Recycling (m ³ /week uncompacted):	4.86	(Rate/apartment) ¹ :	0.060
Container Recycling (m ³ /week uncompacted):	4.86	(Rate/apartment) ¹ :	0.060
-	-	-	
<u>TOTAL RESIDENTIAL APARTMENT WASTE BLOCK D</u>			
Garbage (m ³ /week uncompacted):	9.72	-	-
Paper/Cardboard Recycling (m ³ /week uncompacted):	4.86		
Container Recycling (m ³ /week uncompacted):	4.86		

COMPACTOR DETAILS (garbage only - via refuse chute)				
Bin Size (litres)	Compaction Ratio	No. of Bins under compactor		No. of Bins Filled per Week
660	0.33	1		4.9

References/Notes:

COLLECTIONS	Collections Per Week	No. of Bins Collected
Garbage Disposal	1 per week (660 litre bins)	4.9
Paper/Cardboard Recyc.	1 per week (240 litre bins)	20.3
Container Recyc.	1 per week (240 litre bins)	20.3

References/Notes:

- 1) Ku-Ring-Gai Council Development Control Plan (Town Centres) 2010



WASTE ESTIMATE Residential

Job:	Building E - 131-138 Killeaton Street St Ives	Date:	7-Dec-10
<u>No. OF RESIDENTIAL APARTMENTS</u>	36		
Garbage (m ³ /week uncompacted):	4.32	(Rate/apartment) ¹ :	0.120
Paper/Cardboard Recycling (m ³ /week uncompacted):	2.16	(Rate/apartment) ¹ :	0.060
Container Recycling (m ³ /week uncompacted):	2.16	(Rate/apartment) ¹ :	0.060

<u>TOTAL RESIDENTIAL APARTMENT WASTE BLOCK E</u>	
Garbage (m ³ /week uncompacted):	4.32
Paper/Cardboard Recycling (m ³ /week uncompacted):	2.16
Container Recycling (m ³ /week uncompacted):	2.16

COMPACTOR DETAILS (garbage only - via refuse chute)				
Bin Size (litres)	Compaction Ratio	No. of Bins under compactor		No. of Bins Filled per Week
660	0.33	1		2.2

References/Notes:

COLLECTIONS	Collections Per Week	No. of Bins Collected
Garbage Disposal	1 per week (660 litre bins)	2.2
Paper/Cardboard Recyc.	1 per week (240 litre bins)	9.0
Container Recyc.	1 per week (240 litre bins)	9.0

References/Notes:

- 1) Ku-Ring-Gai Council Development Control Plan (Town Centres) 2010



**WASTE
ESTIMATE**
Residential

Job:	Building F - 131-138 Killeaton Street St Ives		Date:	7-Dec-10
<u>No. OF RESIDENTIAL APARTMENTS</u>	24			
Garbage (m ³ /week uncompacted):	2.88	(Rate/apartment) ¹ :	0.120	
Paper/Cardboard Recycling (m ³ /week uncompacted):	1.44	(Rate/apartment) ¹ :	0.060	
Container Recycling (m ³ /week uncompacted):	1.44	(Rate/apartment) ¹ :	0.060	

<u>TOTAL RESIDENTIAL APARTMENT WASTE BLOCK F</u>	
Garbage (m ³ /week uncompacted):	2.88
Paper/Cardboard Recycling (m ³ /week uncompacted):	1.44
Container Recycling (m ³ /week uncompacted):	1.44


COMPACTOR DETAILS (garbage only - via refuse chute)				
Bin Size (litres)	Compaction Ratio	No. of Bins under compactor		No. of Bins Filled per Week
660	0.33	1		1.5


References/Notes:


COLLECTIONS	Collections Per Week	No. of Bins Collected
Garbage Disposal	1 per week (660 litre bins)	1.5
Paper/Cardboard Recyc.	1 per week (240 litre bins)	6.0
Container Recyc.	1 per week (240 litre bins)	6.0

References/Notes:

- 1) Ku-Ring-Gai Council Development Control Plan (Town Centres) 2010







PROJECT NO.	131-138 KILLEATON STREET	DATE	14/06/2018
CLIENT	Meriton Residential Development	SCALE	1:100
DESIGNER	M. J. B. ARCHITECTS	PROJECT	131-138 KILLEATON STREET
CHECKED BY	M. J. B. ARCHITECTS	DATE	14/06/2018
APPROVED BY	M. J. B. ARCHITECTS	DATE	14/06/2018
<p>Meriton Residential Development Apartment 131-138 Killeaton Street St Ives NSW 2257</p>		<p>SECTION B-B</p>	





COMPACTION BLADE

Eco-Pack WASTE CHUTE COMPACTOR

Eco-Pack Waste Chute Compactor

The Patented Eco-Pack compactor has been specifically developed for compaction of waste delivered via an overhead chute in multi story apartments and entertainment venues.

Designed to suit tight room restraints, the Eco-Pack is a true hydraulic compactor that contains the high packing forces within itself to eliminate O,H&S issues and bin damage.



SPECIAL FEATURES

- High Compaction to reduce number of bins required thus reducing floor space.
- Compaction blade and ejection door constantly seal the waste chute to reduce odour and also eliminate the risk of fire transfer up the waste chute.
- Autocycle operation via 'photo cell' to reduce power consumption.
- Enclosed chamber design provides protection from glass explosion if bottles are dropped from upper levels.
- Ejection of compacted waste plugs into Bins sized from - 240 to 1,500 Ltr.
- Robust High tensile steel construction to Australian Standards AS4100.
- Compliance to all current O,H&S and WorkCover requirements.
- Quiet and efficient hydraulic system.
- Option of Roto Feed or Conveyor Feed to suit all installations.




Eco-Pack

APARTMENT COMPACTOR

Specifications

Compaction Ratio :	3:1 to 10:1 dependent on waste types.
Construction :	5mm and 20mm grade 350 high tensile steel plate.
Chamber dimensions :	560 wide x 600mm long.
Waste Capacity :	80 Ltr per 15 second cycle = 20m ³ /hr
Power requirements :	415v / 20A / 5pin power point .
Hydraulic Specs :	12 Lpm Pump, 5.5Kw Motor
Compaction Force :	62 kn or 6.3 tonnes force @ 14 Mpa
Waste bin Qty :	1 x 240 Ltr bin to 8 bins on Roto Feed and up to 660, 1500 litre bin Roto Feed.
Electric Control :	PLC control with electronic cycle control and photo cell monitoring.
Service :	Comprehensive fixed price service / inspection program available.
Warranty :	12 Month Warranty subject to our Standard Terms and Conditions.





Wastech Head Office
 21 Capital Drive,
 Dandenong Victoria 3175
 PO Box 4182
 Dandenong South 3164
Phone: (03) 9794 7155
Facsimile: (03) 9794 7636
 info@wastech.com.au
 www.wastech.com.au

FOR YOUR LOCAL AGENT
 IN YOUR STATE PLEASE CALL

FREE CALL:
1800 465 465

Your Local Agent:





WASTECH ENGINEERING

SPECIALISING IN: DESIGN, MANUFACTURE AND SERVICE OF WASTE DISPOSAL AND RECYCLING EQUIPMENT

21 CAPITAL STREET, DANBURY NSW 2170. PHONE (02) 92942150. FAX (02) 9294 0848

The details and design shown on this drawing are the property of WASTECH ENGINEERING PTY. LTD. and are not to be copied or reproduced without written approval of WASTECH ENGINEERING PTY. LTD.

DRN C.L.	TITLE		ECOPACK 100 ACTION	REV. 0
CKD C.G.	SCALE D.N.S	CAD FILE NAME		
APP S.F.	DATE 10-9-03	VEWS ---	EP-01-03663	

240 LITRE CONTAINER

Material

- **Polymer components:**
 - Injection moulded from specially designed HDPE
 - Resistant to decay, frost, heat and chemicals
 - Special UV-stabilisation provides excellent ageing characteristics
- **Corrosion resistant steel axle**
- **Noise reduction:**
 - Quiet-running solid rubber tyres
 - Tight-fitting axle
- **Long service life:**
 - High quality materials
 - Most advanced manufacturing processes
 - Withstands exposure to high mechanical stress levels
- **Recycling:**
 - All container parts are recyclable

Advantages

- Easy to manoeuvre
- Versatile, with a comprehensive accessories range
- Complies with EN840 and AS4123 quality requirements
- Particularly stable due to external position of wheels
- Safe and easy to handle
- Suitable for all DIN lifting equipment
- Double angle rail for greater safety when emptying
- Compatible with identification and weighing systems
- Special ribs prevent containers from becoming jammed when stacked

Imprints and markings

- Manufacturer, year of manufacture, material
- Nominal volume, max permitted total weight
- EN 840 and AS4123 markings
- Individual markings with imprints, hot-foil printing or adhesive labels*
- Customer specific serial numbers if required*

Accessories

- For accessories and special design variations such as lid apertures and locks please refer to the separate accessories sheet for 2-wheeled containers

SULO®

SULO MGB Australia Pty Ltd
123 Wisemans Ferry Road
Somersby NSW 2250
Australia
Tel: +61 (0) 2 - 4348 8188
Fax: +61 (0) 2 - 4348 8128
Internet: www.sulo.com.au
E-mail: info@sulo.com.au

SULO – Queensland Office
11 Argon Street
Sumner Park QLD 4074
Australia
Tel: +61 (0) 7 - 3725 5000
Fax: +61 (0) 7 - 3725 5099

Quality


- Certified according to EN840
- Manufactured in accordance with AS4123

Dimensions - Weights - Standards

- Nominal volume: 240 litres
- Net weight: approx 13 kg
- Max load: 96 kg
- Permitted total weight: 110 kg

- A 1060 mm ■ D 730 mm ■ G 550 mm
- B 990 mm ■ E 585 mm
- C 660 mm ■ F 400 mm

Measurements to be used as a guide only – variations will occur



Colours

- Standard colours: black, nature green, dark green, grey
- Special colours are available on request* – common colours include blue, yellow, red, brown, orange, purple



SULO – Victorian Office
1950 Hume Hwy
Campbellfield VIC 3061
Australia
Tel: +61 (0) 3 - 9357 7320
Fax: +61 (0) 3 - 9357 7340

SULO - New Zealand
PO Box 58 962
Greenmount, Manukau City 2141
New Zealand
Tel: +64 9 - 968 2180
Fax: +64 9 - 968 2188

©2009 Subject to technical amendments. *Minimum batch quantities required

SULO 209

660 litre container

Material


- **Polymer components:**
 - Injection moulded from specially designed HDPE
 - Resistant to decay, frost, heat and chemicals
 - Special UV-stabilisation provides excellent ageing characteristics
- **Corrosion resistant metal components:**
 - All metal components are galvanised
- **Noise reduction:**
 - Quiet-running tyres
- **Long service life:**
 - High quality materials
 - Most advanced manufacturing processes
 - Even if exposed to high mechanical stress levels
- **Recycling:**
 - All container parts are recyclable

Advantages

- Easy handling
 - Easy filling
 - Easy grip handles on front and sides of lid
 - Stable and light weight lid
- Safe manoeuvring
 - Easy grip handles on three sides
 - Wide handles, easy to use when wearing thick gloves
 - User-friendly handles
 - Handles available in alternative colours
- Complies fully with EN or RAL quality requirements
- Versatile, with a comprehensive accessories range
- Various wheel assembly configurations for different applications
 - Water drainage plug as standard
 - Compatible with identification and weighing systems
 - Suitable for all lifting equipment in accordance with EN 840
 - Rounded lid profile for improved rainwater dispersal

Dimensions and Weights

- Nominal volume: 660 litres
- Net weight: ca. 43 kg
- Permitted total weight: 310 kg



all dimensions according to EN 840

Colours

- Standard colours: grey, green, blue, yellow, brown, red
- Special colours are available on request
- All additives are cadmium free and environmentally friendly



Imprints and markings

- Manufacturer
- Month and year of manufacture
- Nominal volume, max. permitted total weight
- "No hot ashes" symbol
- Material
- EN 840, RAL markings
- Individual markings with imprints, screen printing, hot-foil printing or adhesive labels

Accessories

- For accessories and special design variations such as lid apertures, locks, towing brackets and fork lift sleeves, please refer to the separate accessories sheet for 4-wheeled containers



SULO

SULO Umwelttechnik GmbH & Co. KG
 Bündler Straße 85
 D-32051 Herford
 Telefon +49 (0) 52 21 598-207
 Telefax +49 (0) 52 21 598-579
 Internet: www.sulo.com
 e-mail: info@sulo.de

06-2004/ Subject to technical amendments

Specifications >>



Rear Lift Collection System

Container Specifications

Capacity	Plastic (polyethylene)				Metal (galvanised steel)	
	120l	240l	660l	1100l	1.5m ³	3.0m ³
Height	0.92m	1.075m	1.235m	1.485m	1.3m	1.3m
Width	0.54m	0.58m	1.36m	1.36m	2.4m	2.4m
Length	0.62m	0.715m	0.765m	1.07m	1.25m	2.25m
Weight	9.5kg	13.5kg	45kg	65kg	300kg	400kg

Vehicle Specifications

Overall length	8.0m
Overall width	2.5m
Height (travel)	3.4m
Height (in operation)	3.4m
Weight (vehicle only)	13.0t
Weight (payload)	9.5t
Turning circle	25.0m

Rear Lift Collection Operation



Containers are lifted automatically, emptied into vehicle and compacted.



Vehicle Safety Features

- On board reversing camera
- Hydraulic valves, lifting gear and doors
- Heated external mirrors
- Reversing lights and beepers

Container Options

- Foot operated lid
- Electronic chip provision
- Wheel locking device
- Divider system
- Size
- Flip top and roll top lids
- Colours (according to national standards) and decals

Container Accessories

- Wheel brakes
- Liners
- Security posts
- Padlocks and chains
- Cart cradle
- Waste ID labels
- Bin lifter

Note: Specifications are a guide only. Printed on recycled paper using environmentally friendly soy-based inks.









SITA's Range of Services include Small Business Waste, Commercial Waste, Industrial Waste, Recycling, Product Destruction, Waste Audits, Government, Domestic Waste, Liquid Waste, Medical Waste, Security Disposal, Builders Bins, Temporary Bins and Hygiene Services

Call 13 13 35 or visit sita.com.au



Electrodrive Waste Bin system

The Waste Bin System is an ideal solution for large facilities with centralised dumping points. Quickly and easily bring your waste bins to the one place for emptying. Safety features include: horn, flashing light, and back off button.

-  Features an Electrodrive Tug and a Waste Bin Mover
-  Carries up to 4 x 240L wheelie bins
-  Easy to manoeuvre with forward and reverse drive
-  Customised movers available to suit your facility
-  Electric powered: 24V deep cycle, sealed gel cell batteries
-  Easily traverses outdoor terrain and is weatherproof
-  Equipment training and servicing programs available
-  Simple to use, no driver's licence required

Specifications

Waste Bin Mover Dimensions:
Height: 1400
Length: 1600 (2 Bin), 2100 (3), 2600 (4)
Width: 715

Tug Dimensions:
Height: 890
Length: 1450 (Tiler handle down)
Width: 630
Capacity: 1000kg
Weight: 170kg
Voltage: 24V
Range: 12km

