

*with eaves boxed with Vee jointed timber linings. On the Kensington Street elevation the windows of the second floor addition are not aligned with those of the floors beneath as strictly as on the main facade. The double hung window assemblies along the eastern elevation at the boardroom are detailed with leadlight glazing.*

*Concurrent with the 1930 Second Floor addition, some modifications were made to the exterior of the original sections of the building, the most notable being the construction of the arched copper canopy over the main entrance, an inclusion that added focus to the Main Avenue administration precinct. Other alterations were mostly as a result of internal modifications, such as the removal of the private entrance to the Manager's office and the removal of the entrance directly leading to the basement. Changes are legible in the use of rendered faux rusticated sandstone at the base of the building along Main Avenue. The leadlight glazing of the first floor Show Room dates from this period.*



Figure 25. The main facade of the Administration Building faces what was originally the main brewery driveway and is now to be known as Carlton Street. The main phases of the development of the building are shown.



Figure 26. Eastern elevation of the Administration Building showing the major phases in its development. The upper level was added at the same time as the northern extension but noticeably less care was given to ensuring that the fenestration patterns are consistent with those on the lower levels on this side of the building, although the overall rhythms and disciplined character of the facade are retained.