

28 October 2025



ATT: Tia Mills
Department of Planning and Environment

24-28 Campbell St
Sydney NSW 2000
All mail to
GPO Box 4009
Sydney NSW 2001
T +61 2 13 13 65
ausgrid.com.au

Dear Tia,

In reference to State Significant Development application for The Boulevard, Punchbowl, Affordable Housing (SSD-83256463)

Ausgrid would like to thank you for seeking input and feedback regarding the Environmental Impact Statement (EIS). Ausgrid has undertaken a review of the EIS and associated information in relation to potential impacts or interfaces with Ausgrid's electricity infrastructure.

Ausgrid requires that due consideration be given to the compatibility of proposed development with existing Ausgrid infrastructure, particularly in relation to risks of electrocution, fire risks, Electric & Magnetic Fields (EMFs), noise, visual amenity and other matters that may impact on Ausgrid or the development.

Ausgrid has reviewed "Appendix X - Infrastructure Report" and advises the proponent must discuss any new connections and load requirements to the site directly with Ausgrid and submit a connection application to Ausgrid as soon as practicable.

We encourage the proponent to continue to discuss their requirements directly with Ausgrid as needed.

Ausgrid Underground Cables are in the vicinity of the development.

Special care should be taken to ensure that driveways and any other construction activities do not interfere with existing underground cables located in the footpath or adjacent roadways.

It is recommended that the developer locate and record the depth of all known underground services prior to any excavation in the area. Information regarding the position of cables along footpaths and roadways can be obtained by contacting Before You Dig Australia (BYDA)

In addition to BYDA the proponent should refer to the following documents to support safety in design and construction:

SafeWork Australia – Excavation Code of Practice.

Ausgrid's Network Standard NS156 which outlines the minimum requirements for working around Ausgrid's underground cables.

The following points should also be taken into consideration.

Ausgrid cannot guarantee the depth of cables due to possible changes in ground levels from previous activities after the cables were installed.

Should ground levels change above Ausgrid's underground cables in areas such as footpaths and driveways, Ausgrid must be notified, and written approval provided prior to the works commencing.

Should ground anchors be required in the vicinity of Ausgrid underground cables, the anchors must not be installed within 300mm of any cable, and the anchors must not pass over the top of any cable.

Ausgrid Overhead Powerlines are in the vicinity of the development.

The developer should refer to SafeWork NSW Document – Work Near Overhead Powerlines: Code of Practice. This document outlines the minimum separation requirements between electrical mains (overhead wires) and structures within the development site throughout the construction process. It is a statutory requirement that these distances be maintained throughout the construction phase.

Consideration should be given to the positioning and operating of cranes, scaffolding, and sufficient clearances from all types of vehicles that are expected be entering and leaving the site.

The “as constructed” minimum clearances to the mains must also be maintained. These distances are outlined in the Ausgrid Network Standard, NS220 Overhead Design Manual. This document can be sourced from Ausgrid’s website at www.ausgrid.com.au.

It is the responsibility of the developer to verify and maintain minimum clearances onsite. In the event where minimum safe clearances are not able to be met due to the design of the development, the Ausgrid mains may need to be relocated in this instance. Any Ausgrid asset relocation works will be at the developer’s cost.

New Driveways - Proximity to Existing Poles

Proposed driveways shall be located to maintain a minimum clearance of 1.5m from the nearest face of the pole to any part of the driveway, including the layback, this is to allow room for future pole replacements. Ausgrid should be further consulted for any deviation to this distance.

New or modified connection

To apply to connect or modify a connection for a residential or commercial premises. Ausgrid recommends the proponent to engage an Accredited Service Provider and submit a connection application to Ausgrid as soon as practicable. Visit the Ausgrid website for further details; <https://www.ausgrid.com.au/Connections/Get-connected>

Additional information can be found in the Ausgrid Quick Reference Guide for Safety Clearances “Working Near Ausgrid Assets - Clearances”. This document can be found by visiting the following Ausgrid website:

www.ausgrid.com.au/Your-safety/Working-Safe/Clearance-enquiries

Should you require further information please contact Ausgrid via email to Development@ausgrid.com.au

Please do not hesitate to contact me for further information.

Regards,



Paul Nakhle – Portfolio Manager - Asset Protection | Transmission Services