LEGEND

- COMBUSTIBLE STOCKPILE
- STORAGE NON-COMBUSTIBLE MATERIAL
- ACCESS AND EGRESS ROUTES/ SWEPT PATHS

NOTES

1. MIN. 6m ACCESS AROUND STOCK PILES.
2. NOT ALL STOCK PILES WILL BE FULLY OPERATIONAL OR UTILIZED AT THE SAME TIME.
3. DIMENSIONS INDICATED ARE APPROXIMATE ONLY.
4. STOCK PILES TO BE FURTHER ASSESSED TO CURRENT FRNSW FIRE SAFETY GUIDELINES FOR WASTE FACILITIES VERSION 02.02 DATED 27 FEBRUARY 2020. STOCKPILE VOLUMES AND SEPARATION DISTANCES SHOWN ARE AS PER PREVIOUSLY APPROVED METHODOLOGY FROM FRNSW.

PILE NO	TYPE	AVE HT (m)	SIZE (m3)	TONNES
1	INSPECTED SHREDDER FEED	4	1444	505
2	INSPECTED SHREDDER FEED	4	1008	353
3	INSPECTED SHREDDER FEED	4	576	202
4	AS DELIVERED SHREDDER FEED	4	624	218
5	AS DELIVERED SHREDDER FEED	4	1760	616
6	AS DELIVERED SHREDDER FEED	4	520	182
7	AS DELIVERED SHREDDER FEED	4	1288	451
8	AUTOMOTIVE	4	800	400
9	AUTOMOTIVE	4	1480	740
10a	PRE-SHREDDED AUTOMOTIVE	4	440	220
10b	PRE-SHREDDED AUTOMOTIVE	4	784	392
11a	PRE-SHREDDED AUTOMOTIVE	4	408	204
11b	PRE-SHREDDED AUTOMOTIVE	4	792	396
12	FLOC	3	600	200
		TOTAL	12524	5079

DEVELOPMENT DATA

SITE AREA	59,475 m²	
	FLOOR AREAS	
	WAREHOUSE	OFFICE/AMENITIES
BUILD 'A'	1278 m²	24 m²
BUILD 'B'	3162 m²	438 m²
BUILD 'C'	2981 m²	------
BUILD 'D'	415 m²	------
BUILD 'E'	984 m²	------
BUILD 'F'	494 m²	------
BUILD 'G'	81 m²	------
BUILD 'H'	25 m²	------
BUILD 'J'	17 m²	------
BUILD 'K'	47 m²	------
BUILD 'L'	593 m²	------
TOTAL	10,077 m²	462 m²

Issue	Description	By	Ckd	RPEQ	Date
02	AMENDED ISSUE FOR LEC	JCR			28/7/21
01	ORIGINAL ISSUE	JCR	-	-	26/7/21

100mm on Original

Scale: 1 : 750 (0 15 30 45 60 75m)

Surveyor

Urban Designer

Filename

Client

Status

Approved

R.P.E.Q No :

Scales: 1:750

Original Issue Signatures: Drawn --; Designed -; Project Manager -

Original Size: A1

Height Datum: AHD

Grid: MGA

© Copyright reserved

Project: SSD 5041 MOD 3 CONDITION B35D

Title: FINAL STOCKPILE PLAN APPROVED BY LEC PROCEEDING 2020/00365487