
# BURROWS INDUSTRIAL ESTATE 1-3 BURROWS ROAD, ALEXANDRIA

**Geotechnical Report** 

PSM2808-005R REV4

16 December 2024

Goodman Property Services (Aust) Pty Ltd



# **Table of Contents**

| 1. | Prea  | mble   | 4  |
|----|-------|--|----|
|    | 1.1   | Amended Project Description  | 4  |
|    | 1.2   | Change to the Proposal   |    |
| 2. | Intro | oduction   | _  |
|    |       |  |    |
| 3. | Revi  | ewed Documents   | 6  |
| 4. | Geo   | technical Investigation  | 6  |
|    | 4.1   | Fieldwork – 13 August 2015   | 6  |
|    | 4.2   | Geotechnical Laboratory Testing (August 2015)  | 6  |
|    | 4.3   | Fieldwork – 23 to 24 April 2019.   | 7  |
|    |       | 4.3.1 Standpipe Piezometers  | 7  |
| 5. | Site  | Conditions   | 7  |
|    | 5.1   | Geological Setting   | 7  |
|    | 5.2   | Surface Conditions   | 7  |
|    | 5.3   | Subsurface Conditions  | 7  |
|    | 5.4   | Groundwater  | 9  |
| 6. | Ass   | essment of SEARS – Geotechnical Items  | 9  |
|    | 6.1   | Introduction   | 9  |
|    | 6.2   | ITEM 1 – Assess potential impacts on soil resources and related infrastructure and riparian lands on a near the site, including soil erosion, salinity and acid sulfate soils  |    |
|    | 6.3   | ITEM 2a – Provide a surface and groundwater impact assessment that assess potential impacts of Surface water resources (quality and quantity) including related infrastructure, hydrology, dependences ecosystems, drainage lines, downstream assets and watercourses. | en |
|    | 6.4   | ITEM 2b – Provide a surface and groundwater impact assessment that assess potential impacts of Groundwater resources in accordance with the Groundwater Guidelines   |    |
| 7. | Disc  | ussion and Recommendations   | 10 |
|    | 7.1   | General  | 10 |
|    | 7.2   | Site Classification  | 10 |
|    | 7.3   | Permanent and Temporary Batters  | 10 |
|    | 7.4   | Excavation Support   |    |
|    | 7.5   | Slab on Ground   | 11 |
|    | 7.6   | Footings   | 11 |
|    |       | 7.6.1 Shallow Footings   | 11 |
|    |       | 7.6.2 Pile Footings  | 12 |
|    |       | 7.6.3 Differential Settlements   | 12 |
|    | 7.7   | Groundwater and Dewatering   | 12 |
|    | 7.8   | Pavements  | 14 |
|    | 7.9   | Earthquake Classification  | 14 |
|    | 7.10  | Site Suitability for Development   | 14 |



# **List of Tables**

| Table 1 - Overview of Key Numeric Amendments                           | .5  |
|--|-----|
| Table 2 – CBR Testing Results Summary                                  |     |
| Table 3 – Summary of Subsurface Units Encountered at CPT Locations     | .8  |
| Table 4 – Assessed Levels of Geotechnical Unit at CPT and BH Locations | 3.  |
| Table 5 – SEARs Requirements   | . 9 |
| Table 6 – Batter Slope Angles  | 11  |
| Table 7 – Engineering Parameters of Inferred Geotechnical Units        | 13  |

# **List of Figures**

| Figure 1 | Locality Plan                 |
|----------|-------------------------------|
| Figure 2 | Selected Site Photos (1 OF 2) |
| Figure 3 | Selected Site Photos (2 OF 2) |
| Figure 4 | Groundwater Monitoring – BH01 |
| Figure 5 | Groundwater Monitoring – BH02 |
| Figure 6 | Groundwater Monitoring – BH03 |

# **List of Appendices**

Appendix A CPT Results

Appendix B CBR Test Results

Appendix C Borehole logs

Appendix D Point Load Index Tests

Appendix E Piezometer Construction Records



#### 1. Preamble

#### 1.1 Amended Project Description

The project description is to be updated to reflect the following:

- Demolition of all existing structures and buildings on site
- Tree removal both on site and for a limited number of trees in the public domain and adjoining lot
- Site remediation, and establishment works, including minor excavation / bulk earthworks
- Design, construction and operation of a two-storey warehouse and distribution centre building with ancillary offices for each warehouse tenancy, including:
  - Approximately 34,051sqm of total GFA, comprising:
    - o 30,389sqm of warehouse and distribution centre GFA.
    - o 3,353sqm of GFA for ancillary office space; and
    - o End of Trip Facilities on the ground floor of 309 sqm GFA.
  - Maximum building height of RL 29.70 (maximum 25m from existing ground level).
  - Operation 24 hours per day seven days a week.
- Provision of on grade car parking accessed off Burrows Road which provides 145 tenant and visitor car
  parking spaces (including 8 accessible bays), 14 motorcycle spaces, and bicycle parking and end-of-trip
  facilities (including 66 bicycle parking spaces, showers, lockers and change rooms for occupants).
- New crossings to Burrows Road for truck and car access
- Single fire and utilities services ingress crossing off Canal Road
- Site landscaping works totalling approximately 6,856sqm (or 19.8% of the site), including
  - Two x 6-metre landscaped setback areas to both the Burrows Road and Canal Road site frontages.
  - 3,829sqm or 11.0% deep soil landscaping.
  - 3,027sqm or 8.7% of permeable paving; and
  - 5,450sqm or 15.7% tree canopy coverage.
- Provision of building / business identification and wayfinding signage.

#### 1.2 Change to the Proposal

The proposed design has been amended in response to issues relating to site contamination, potential flood impacts, assessment of the local logistics market and construction cost escalation. The intent of the proposal remains the same, however there have been changes to the physical layout/ built form of the warehouse and distribution facility as outlined below:

- Reduction of the proposed warehouse from 3 storeys (30.14m) to 2 storeys (25m). Despite the reduction of 1 storey, the building height has been reduced by approximately 5m. The remaining 2 storeys have increased in height to provide a more efficient warehouse facility.
- Re-orientation of the layout from an east-west central hardstand with smaller warehouse tenancies on the north and south, to a north-south central hardstand with larger/deeper warehouse tenancies on the east and west. This provides for more efficient warehouse layouts and truck access.
- Previously, truck access to the warehouse tenancies was facilitated via north and south spiral ramps from Burrows Road, connecting to a north-south hardstand on each level. Under the amended proposal, truck access will be provided directly to the ground level from Burrows Road, and upper level hardstand access will be provided via a northern ramp, also from Burrows Road.
- Previously, the offices associated with the warehouse tenancies were arranged over six levels in a separate
  block at the northern end of the site, featuring a shared rooftop garden terrace. The revised design situates
  the offices in a mezzanine layout within each warehouse tenancy, each having direct access to an elevated
  garden terrace along the building's east and west facade.
- Previously carparking was located in an under croft basement below the warehouse and accessed from Burrows Road. The amended design situates car parking at ground level, either externally to the building's footprint or within a ground-level under croft at the site's southern end.



- The facade has been redesigned to simplify the raked cladding panels, making them predominantly vertical
  while still maintaining a stepped appearance. The prominent corners of the development at the south-east
  and south-west extents of the building continue to feature expressive detailing.
- The proposal maintains a 6m landscaped setback to Burrows Road with a curved façade and a minimum 6m landscaped setback to Canal Road.
- The landscape design has been modified to reflect the revised site arrangement and orientation.
   However, the design concept retains the use of native and endemic species, as a key aspect of Connecting with Country.

The numerical changes to the proposal are detailed in Table 1 below.

**Table 1 - Overview of Key Numeric Amendments** 

| Element                    | Exhibited Proposal                                    | Amended Proposal                                     | Difference                        |  |
|----------------------------|---|--|-----------------------------------|--|
| Total Site Area            | 34,614sqm   | 34,614sqm  | Nil                               |  |
| Total Warehouse<br>Area    | 47,076sqm   | 30,389sqm  | Decrease of 16,687 sqm            |  |
| Total Office Area          | 5,014sqm  | 3,353sqm   | Decrease of 1,661sqm              |  |
| Total Café Area            | 60sqm   | 0sqm   | Decrease of 60ssqm                |  |
| Total GFA                  | 52,150sqm   | 34,051sqm  | Decrease of<br>18,099sqm          |  |
| Carparking                 | 241 car parking spaces (including 12 accessible bays) | 145 car parking spaces (including 8 accessible bays) | Decrease of 96 car parking spaces |  |
| Maximum Building<br>Height | 30.14m  | 25m  | Decrease of 5.14m                 |  |
| Landscaped Area            | 7,464 sqm (or 21.6% of the site)                      | 6,856sqm (or 19.8% of the site)                      | Decrease of 608sqm                |  |

#### 2. Introduction

This report presents the results of the geotechnical investigation undertaken by PSM in 2015 and 2019 for the proposed Burrows Industrial Estate Warehouse Development at 1-3 Burrows Road, Alexandria. The aim of the geotechnical investigation was to assess the subsurface conditions and to provide geotechnical design advice and recommendations for the proposed development.

The work has been undertaken in accordance with our proposals:

- PSM2808-001L dated 20 July 2015
- PSM2808-006L dated 18 March 2019.

This report was previously revised (ref. PSM2808-005R REV1 dated 13 May 2019) to include the results of the site investigation on the following dates:

- 1. 13 August 2015.
- 2. Between 23 April and 24 April 2019.



#### 3. Reviewed Documents

The following documents have been provided to inform the geotechnical report:

- Architectural Drawings by SBA (ref. 24132 DA000 to DA710 dated 13 September 2024)
- Civil Drawings by Costin Roe Consulting (ref. CO11035.05-SSDA100 to SSDA551 dated 17 October 2024)
- Structural Drawings by Costin Roe Consulting (ref. CO11035.05 S010 to S504 dated 30 July 2024)
- Email from Angus Harrold dated 14 May 2024.

Based on your email and drawings, we understand the following:

- The previous development, consisting of a three (3) storey commercial and industrial building with an external carpark has been revised to a two (2) storey scheme
- The current proposed redevelopment will comprise demolition of the existing buildings and pavements and construction of a double-storey warehouse
- The proposed floor level is at RL 4.4 m. No basement structure is proposed for the site.

### 4. Geotechnical Investigation

#### 4.1 Fieldwork – 13 August 2015

Fieldwork was undertaken on 13 August 2015 and comprised:

- 6 x Cone Penetrometer Tests (CPT 1 to CPT 6)
- 3 x Bulk samples (CBR1 to CBR 3).

The CPTs were carried out using a 15.5 tonne truck mounted testing rig. The CPTs were undertaken to a refusal depth between 12 and 14 m. CPT results and interpreted profiles are presented in Appendix A.

Prior to testing, on-site service location "scans" were undertaken by a service locator in the presence of a PSM geotechnical engineer to ensure the test locations were free from buried utilities. Coring through pavement was undertaken to allow the CPT cone to test the underlying material and also to recover bulk samples for testing.

The testing and sampling locations are shown in Figure 1. Testing and sampling locations were located with a GPS with the accuracy of +5 m.

#### 4.2 Geotechnical Laboratory Testing (August 2015)

Three (3) bulk samples (CBR 1, CBR 2 & CBR 3) recovered during the fieldwork using hand-auger were sent to a NATA registered geotechnical testing laboratory for California bearing ratio (CBR) testing. The test result sheets are attached in Appendix B and the results are tabulated in Table 2 below.

Table 2 - CBR Testing Results Summary

| CBR<br>SAMPLE ID | SAMPLE<br>DEPTH (m) | MATERIAL<br>DESCRIPTION | FIELD<br>MOISTURE<br>CONTENT<br>(%) | STANDARD<br>MAXIMUM<br>DRY<br>DENSITY<br>(t/m³) | OPTIMUM<br>MOISTURE<br>CONTENT<br>(%) | 4 DAY –<br>SOAKED<br>CBR (%) |
|------------------|---------------------|-------------------------|-------------------------------------|---|---------------------------------------|------------------------------|
| CBR 1            | 0.2 - ~0.5          | Clayey SAND             | 25.5                                | 1.63  | 20.1                                  | 15                           |
| CBR 2            | 0.2 - ~0.5          | Clayey SAND             | 30.8                                | 1.26  | 31.0                                  | 10                           |
| CBR 3            | 0.2 - ~0.5          | Clayey SAND             | 17.3                                | 1.69  | 17.5                                  | 50                           |



#### 4.3 Fieldwork – 23 to 24 April 2019

Additional fieldwork was undertaken on 23 to 24 April 2019 and comprised:

3 x Cored boreholes (BH01 to BH03).

The boreholes were drilled using a track mounted rig. All boreholes employed rotary auger drilling in soil, with NMLC coring used to recover bedrock. The boreholes were drilled to a depth of 15 m and piezometer were installed in each of the boreholes following completion of drilling. Point load index testing has been undertaken on the recovered rock cores at approximately 1 m intervals. Boreholes logs are presented in Appendix C and point load index testing results are presented in Appendix D.

Testing and sampling locations are shown in Figure 1.

#### 4.3.1 Standpipe Piezometers

Three standpipe piezometers were installed at the borehole locations. Appendix E presents the construction records of the piezometers. A water level logger was installed in each piezometer to record water level e.g. every hour (automatic data collection). This allows us to assess the effect of rainfall on the groundwater, etc.

#### 5. Site Conditions

#### 5.1 Geological Setting

The 1:100,000 Sydney Geological map indicates that the site is underlain by Quaternary alluvium being peat, sandy peat and mud.

#### 5.2 Surface Conditions

The site is currently occupied by single storey warehouses and up to two storey offices. The north west of the site is paved with asphalt overlying a concrete slab and the north east of the site is covered with a concrete slab. The pavement is up to 300 mm thick.

#### 5.3 Subsurface Conditions

The subsurface conditions encountered by the CPTs are summarised in Table 3 and Table 4.



Table 3 – Summary of Subsurface Units Encountered at CPT Locations

| UNIT NAME  | APPROXIMATE DEPTH<br>TO THE TOP OF UNIT<br>(m) | DESCRIPTION  |
|------------|--|--|
| PAVEMENT   | 0.0  | Pavement comprises asphalt and concrete slab or concrete slab only.  |
| FILL       | 0.2 to 0.3                                     | Gravelly SAND to Clayey SAND. Density index ranges from medium dense to very dense.  |
| UPPER SAND | 1.0 to 3.0                                     | Silty SAND. Density index ranges from loose to dense.  |
| UPPER CLAY | 2.8 to 5.2                                     | CLAY to Silty CLAY. Soft to firm clay.   |
| LOWER SAND | 4.0 to 8.7                                     | SAND to Silty Sand. Density index ranges from dense to very dense.  Grey, fine to medium grained.  |
| LOWER CLAY | 7.9 to 10.7                                    | CLAY to Silty Clay. Consistency stiff to very stiff.  Pale grey mottled brown and red to mottled dark grey and brown.  High Plasticity.                      |
| BEDROCK A  | 10.4 to 13.5                                   | SHALE: Dark grey with some brown stains to black, inferred to be very low strength. Extremely weathered to moderately weathered.  Inferred from CPT refusal. |
| BEDROCK B  |  | SHALE: Dark grey to black, inferred to be low to medium strength. Slightly weathered to Fresh.   |

Table 4 – Assessed Levels of Geotechnical Unit at CPT and BH Locations

| UNIT NAME                     | APPROXIMATE REDUCED LEVEL OF TOP OF UNIT (m AHD) |       |       |      |      |        |        |        |       |
|-------------------------------|--|-------|-------|------|------|--------|--------|--------|-------|
|                               | CPT1   | CPT2  | СРТ3  | CPT4 | CPT5 | СРТ6   | BH01   | BH02   | BH03  |
| Concrete PAVEMENT (COLLAR RL) | 2.8  | 2.3   | 3.75  | 2.9  | 3.5  | 3.45   | 2.05   | 2.3    | 3.5   |
| FILL                          | 2.6  | 2.1   | 3.55  | 2.7  | 3.2  | 3.25   | 1.75   | 2.1    | 3.25  |
| UPPER SAND                    | 1.2  | 1.3   | 2.25  | -0.1 | 0.5  | 1.45   | -2.35  | -1.7   | -1    |
| UPPER CLAY                    | -0.2   | -0.5  | -0.25 | -1.6 | -1.2 | -1.75  | NE     | NE     | NE    |
| LOWER SAND                    | -3   | -3.9  | -2.25 | -4.7 | -4   | -5.25  | NE     | NE     | NE    |
| LOWER CLAY                    | -5.1   | -8.4  | -5.85 | -6.1 | -6.7 | -5.95  | -5.95  | -6.5   | -5.5  |
| BEDROCK A                     | -9.2   | -10.1 | -9.05 | -11  | -9.8 | -10.65 | -8.35  | -10.9  | -8    |
| BEDROCK B                     | NE   | NE    | NE    | NE   | NE   | NE     | -9.75  | NE     | -9.3  |
| End of Hole                   | -9.2   | -10.1 | -9.05 | -11  | -9.8 | -10.65 | -12.97 | -12.88 | -11.5 |

NE = Not Encountered

The collar levels were estimated from the survey plan provided to PSM.



#### 5.4 Groundwater

Groundwater was encountered during drilling / augering between 0.6 and 1.8 m below the surface; (i.e. between RL 1.4 m and 1.7). We note that these levels were higher than those recorded in the water loggers below.

A PSM geotechnical engineer visited the site on 8 May 2019 to download the water level data from the loggers. The monitoring data from the piezometer is presented in Figure 4 to Figure 6. The data is consistent with dip measurement undertaken manually using a measuring tape.

PSM's groundwater assessment report is presented in PSM2808-019L REV3 dated 16 December 2024.

#### 6. Assessment of SEARS – Geotechnical Items

#### 6.1 Introduction

This section presents our response to some of Item 12 of the SEARs for warehouses and distribution centres from a geotechnical point of view. Table 5 reproduces Item 12 of the warehouse and distribution centre, Industry Specific Secretary's Environmental Assessment Requirements (SEARs). We have been provided with and used the following documents during our assessment:

- Architectural Drawings by SBA (ref. 24132 DA000 to DA710 dated 13 September 2024)
- Civil Drawings by Costin Roe Consulting (ref. CO11035.05-SSDA100 to SSDA551 dated 17 October 2024).

**Table 5 – SEARs Requirements** 

| Item             | Description of Requirement   |
|------------------|--|
| 12. Ground and   | <ul> <li>Assess potential impacts on soil resources and related infrastructure and riparian lands on and near the site, including soil erosion, salinity and acid sulfate soils.</li> <li>Provide a surface and groundwater impact assessment that assess potential impacts on:</li> </ul> |
| Water Conditions | <ul> <li>Surface water resources (quality and quantity) including related infrastructure, hydrology, dependent ecosystems, drainage lines, downstream assets and watercourses</li> <li>Groundwater resources in accordance with the Groundwater Guidelines</li> </ul>                      |

# 6.2 ITEM 1 – Assess potential impacts on soil resources and related infrastructure and riparian lands on and near the site, including soil erosion, salinity and acid sulfate soils

#### **PSM Response:**

PSM understands that the Site will either be in a net import or export balance depending on whether a piling platform is opted for across the site. From the cut fill plan, cut depths up to 1.25 m and fill depths up to 3.25 m are proposed with a final bulk earthworks level of RL 4.4 m AHD  $\pm$  1000 mm. The range in bulk earthworks level means that the site and design can be amended to achieve cut fill balance across the site.

We assess that from a geotechnical point of view, the proposed development will likely have close to no impact on the soil resource at the site as existing cut material from the site proposed to be reused. Imported fill is understood to be clean material which will have minimal impacts on the existing soil resource.

With regards to riparian lands, we understand that no riparian lands are present within the site boundary. It is expected that appropriate erosion control will be included during construction and the civil engineer will design the stormwater system, surface gradients and landscaping requirements to control surface flows and minimise soil erosion and the effects of soil erosion. We note that the vast majority of the site will be sealed by the proposed development and the appropriate surface runoff collection and disposal systems have been included in the design.



6.3 ITEM 2a – Provide a surface and groundwater impact assessment that assess potential impacts on: Surface water resources (quality and quantity) including related infrastructure, hydrology, dependent ecosystems, drainage lines, downstream assets and watercourses.

#### **PSM Response:**

We note that impacts on surface water resource (quality and quantity), impacts on dependent ecosystems, drainage lines, downstream assets and watercourses are not a geotechnical item. These items can be addressed by a suitably qualified person(s), (e.g., ecologist, drainage/civil designer and environmental consultant or other suitably qualified persons). These items are not considered by PSM.

6.4 ITEM 2b – Provide a surface and groundwater impact assessment that assess potential impacts on: *Groundwater resources in accordance with the Groundwater Guidelines.* 

Based on our geotechnical investigation and previous groundwater monitoring, we understand that groundwater levels vary between RL 0.5 m AHD and RL 0.7 m AHD. No significant excavation works or basements are proposed for the development with the site having a maximum cut depth of 1.25 m to a bulk earthwork level of RL 4.4 m AHD. As such we deem that impacts on the groundwater resource at the Site is negligible and will not be impacted by the proposed development.

#### 7. Discussion and Recommendations

#### 7.1 General

The design advice provided in the following sections has been prepared on the following basis:

- Earthworks will be undertaken on the site with the following depths:
  - Maximum cut depth: -1.25 m
  - Maximum Fill depth: 3.25 m
- Any proposed earthworks are to be completed in accordance with the Bulk Earthworks Specification (ref. PSM2808-023S dated 25 September 2024 in Appendix F)
- Further testing including plate load testing and additional CBR testing will be undertaken following demolition to confirm the advice provided in the following Sections.

If any of those bases are not applicable, PSM should be requested to confirm that the design advice below is still applicable.

#### 7.2 Site Classification

While the proposed development is out of scope of AS2870 (2011) Residential slabs and footings, we assess that, for the subgrade, the characteristic surface movement,  $y_s$ , would be less than 20 mm and thus would classify the site as Class S.

#### 7.3 Permanent and Temporary Batters

The batter slope angles shown in Table 6 are recommended for the design of batters up to 3 m height and above the groundwater table; subject to the following recommendations:

- 1. The batters shall be protected from erosion.
- 2. Permanent batters shall be drained.
- 3. Temporary batters shall not be left unsupported for more than 1 month without further advice, and inspection by a geotechnical engineer should be undertaken following significant rain events.

Where loads are imposed or structures/services are located within one batter height of the crest of the batter, further advice should be sought.



Table 6 - Batter Slope Angles

| UNIT   | TEMPORARY  | PERMANENT  |
|--|------------|------------|
| SOIL UNITS, eg. ENGINEERED<br>FILL, NATURAL SOIL | 2.0 H : 1V | 2.5 H : 1V |

Steeper batters may be possible subject to further advice, probably including inspection during construction.

#### 7.4 Excavation Support

Permanent cuts in the ENGINEERED FILL, NATURAL SOIL and BEDROCK units steeper than the recommended permanent batter slopes in Table 6 will need to be supported by some form of retaining structure.

The design of these structures should be based on the following:

- Effective soil strength parameters in Table 7 when assessing the earth pressure on retaining structures
- Water pressure (depending on the type of structure). Both water pressure acting directly on the structure, and the effect of water pressure on effective stresses within the retained ground
- Surcharge loads.

Note that design of retention systems may be based on either  $K_a$  or  $K_o$  earth pressures. Design using active earth pressures provides the minimum lateral earth pressure that must be supported to avoid failure and requires a wall that can rotate or translate to allow the pressures to reduce to these values (vertical and lateral movements up to 2% of height may occur, typical movements will be much less).

Where the design is based on  $K_0$  pressures, construction should be carefully controlled to avoid unwanted effects. It should be noted that designing for  $K_0$  pressures does not, of itself, ensure that movement does not occur. Movements are controlled by the construction method, especially sequence.

Both surface and sub-surface drainage needs to be designed and constructed properly to prevent pore water pressures from building up behind the retaining walls or appropriate water pressures must be included in the design.

#### 7.5 Slab on Ground

The design of slabs can be based on a subgrade with a Young's modulus (*E*) shown in Table 7 and subsurface profile discussed in Section 5.3. A short-term Young's modulus of 15 MPa can be adopted for slab founded on FILL or UPPER SAND unit.

We note that slabs will be affected by settlement of the deeper soil layers.

The structural designer or builder may wish to employ a surface layer of road base / crushed sandstone / concrete for trafficability or structural purposes. This is not required to achieve the properties provided in this design advice.

#### 7.6 Footings

#### 7.6.1 Shallow Footings

Pad footings can be founded on or within the FILL or UPPER SAND unit. They can be proportioned on the basis of an allowable bearing pressure (ABP) presented in Table 7. These pads are to have a minimum horizontal dimension of 1 m and an embedment depth of at least 0.5 m. Shallow footings should not be founded closer than their minimum plan dimension to the UPPER CLAY unit.

Please note that an allowable bearing pressure (ABP) is not a soil property. It depends on many factors such as the size of the footings, the embedment depth, the load direction and eccentricity, the stiffness of the footing, the adopted factor of safety (FOS), as well as the soil properties. As footings get bigger or deeper the capacity increases very quickly, as the load gets eccentric or inclined the capacity reduces very quickly.



Higher ABPs may be available but these depend on the size, depth, loads, etc. and would be subject to specific advice.

Settlement of footings should be assessed based on a foundation material with a long term Young's modulus shown in Table 7.

#### 7.6.2 Pile Footings

Piles should be designed in accordance with the requirements in AS 2159 (2009), Piling – Design and Installation.

Selection of the pile system depends on many considerations and should be undertaken by the designer in conjunction with the Principal and contractor / builder.

We envisage that piles to be founded within the BEDROCK unit. If piles need to be founded within SAND units, further advice should be sought, but we do not expect this to be practical.

With regards to the pile design we recommend that:

- A geotechnical strength reduction factor,  $\Phi g = 0.60$  (AS2159 CL. 4.3.2) be adopted for a high redundancy system for an assessed average risk rating (ARR) of 3.0. This should be reviewed to suit the specific design and construction methods proposed by the structural designers.
- It may be possible to increase the pile reduction factors, if the details of the proposed pile installation procedures indicate a high level of quality control with regards to concrete placement, base cleanliness etc.

Where the pile is sized using the allowable bearing capacity in Table 7 (i.e. assuming all the serviceability load is carried by the base), the settlement would be expected to be less than 1% of the pile diameter.

Any structural settlement due to shortening (or extension) of the footing element itself should be considered.

Where the founding or loading conditions between footings vary consideration should be given to the effects of differential settlements.

#### 7.6.3 Differential Settlements

Where adjacent foundation and slab details differ (e.g. between the remaining existing structure and new extension), differential settlement will need to be assessed.

#### 7.7 Groundwater

Assessment regarding groundwater is presented in our groundwater assessment letter (ref. PSM2808-019L REV3 dated 16 December 2024.



Table 7 – Engineering Parameters of Inferred Geotechnical Units

| INFERRED      | BULK UNIT<br>WEIGHT | SOIL EFFECTIVE<br>STRENGTH<br>PARAMETERS |             | ULTIMATE BEARING<br>PRESSURE UNDER   | ALLOWABLE BEARING<br>PRESSURE UNDER  | ULTIMATE<br>SHAFT | ELASTIC PARAMETERS     |                    |
|---------------|---------------------|--|-------------|--------------------------------------|--------------------------------------|-------------------|------------------------|--------------------|
| UNIT          | (kN/m³)             | c'<br>(kPa)                              | φ'<br>(deg) | CENTRIC VERTICAL<br>LOADING (kPa)    | CENTRIC VERTICAL<br>LOADING (kPa)    | ADHESION<br>(kPa) | Young<br>Modulus (MPa) | POISSON'S<br>RATIO |
| Fill          | 18                  | 0  | 25          | 250*                                 | 100*                                 | N/A               | 10                     | 0.3                |
| UPPER<br>SAND | 18                  | 0  | 25          | 250*                                 | 100*                                 | N/A               | 10                     | 0.3                |
| Upper clay    | 18                  | 0  | 20          | No footings anticipated in this unit |                                      | N/A               | 4                      | 0.3                |
| lower sand    | 18                  | 0  | 35          | No footings anticipated in the       | No footings anticipated in this unit |                   | 30                     | 0.3                |
| LOWER<br>CLAY | 18                  | 0  | 32          | No footings anticipated in this unit |                                      | N/A               | 20                     | 0.3                |
| bedrock A     | 22                  | N/A                                      | N/A         | 3000 1000**                          |                                      | 100               | 100                    | 0.3                |
| bedrock B     | 22                  | N/A                                      | N/A         | 6000 2500**                          |                                      | 350               | 500                    | 0.25               |

Note: \* Minimum footing dimensions: 1 m x 1 m in plan with an embedment depth at least = 0.5 m.



<sup>&</sup>lt;sup>3</sup> \*\* ABP in BEDROCK to cause settlement of <1% of minimum footing dimension.

#### 7.8 **Pavements**

Due to limited access to the subgrade underlying the concrete pavement, only three (3) CBR tests were undertaken. The CBR test results show a wide range of values.

For the purposes of preliminary structural pavement thickness design, a design CBR of 10% can be adopted for existing subgrade. Higher CBR values might be possible if testing is undertaken at specific areas. We recommend that specific CBR testing be undertaken at subgrade level when pavement layouts are finalised and after the demolition work is completed.

#### 7.9 **Earthquake Classification**

Given that the sub-surface conditions comprise material with an assessed consistency of soft, e.g. UPPER CLAY unit and that it is less than 20 m thick, we have classified the site sub-soil to be Class Ce in accordance with AS 1170.4-2007 Section 4.2.

#### 7.10 Site Suitability for Development

Based on the results of our geotechnical investigation and reviewed documents, PSM confirms that the site is geotechnically suitable for the development provided:

- The design of the development is undertaken in accordance with PSM advice provided in this report
- Any earthworks are undertaken in accordance with PSM bulk earthworks specification (ref. PSM2808-023S in Appendix F.

**HARLEY ZHENG** 

**GEOTECHNICAL ENGINEER** 

Should you have any queries, please do not hesitate to contact the undersigned.

**Yours Sincerely** 

**KEN TONG LEE** 

**GEOTECHNICAL ENGINEER** 

**AGUSTRIA SALIM PRINCIPAL** 

#### Brisbane

Level 6, 500 Queen Street Brisbane QLD 4000 +61 7 3220 8300

#### Sydney

G3-56 Delhi Road North Ryde NSW 2113 +61 2 9812 5000

#### Melbourne

Office 16 Level 4, 60 Moorabool Street Geelong VIC 3220 +61 3 7068 5699

#### Perth

Level 3 22 Delhi Street West Perth WA 6005 +61 8 9462 8400





#### Notes:

1. Plan obtained from Google Earth.




Previous site investigation on 13 August 2015 (Approx. only)



Cored Boreholes locations on 23 and 24 April 2019 (Approx. only)





1 - 3 Burrows Road, St Peters Geotechnical Investigation

**LOCALITY PLAN** 

PSM2808-005R

Figure 1



Photo 1 - General Site Conditions - Site Entrance



Photo 2 - General Site Conditions - View to the South from entrance



Photo 3 - General Site Conditions - North part of the site looking South

Goodman Limited
1 - 3 Burrows Road, St Peters
Geotechnical Investigation
SITE INVESTIGATION 23 and 24 April 2019
SELECTED SITE PHOTOS [1 OF 2]

**Pells Sullivan Meynink** 

PSM2808-005R

FIGURE 2



Photo 4 - General Site Conditions - View to the North from the South



Photo 5 - Drilling rig and exclusion zone


Goodman Limited
1 - 3 Burrows Road, St Peters
Geotechnical Investigation
SITE INVESTIGATION 23 and 24 April 2019
SELECTED SITE PHOTOS [2 OF 2]





Pells Sullivan Meynink

PSM2808-005R

FIGURE 3









# Appendix A CPT Results




















## CONE PENETRATION TEST - INFERRED SOIL TYPE




W:\2801-2900\PSM2808\Eng\CPT\NEW\[CPT4.xlsm]Subject test







## CONE PENETRATION TEST - INFERRED SOIL TYPE



W:\2801-2900\PSM2808\Eng\CPT\NEW\[CPT6.xlsm]Subject test

# **Appendix B CBR Test Results**



115 Wicks Road Macquarie Park, NSW 2113 PO Box 976 North Ryde, Bc 1670

02 9888 5000 Telephone: Facsimile: 02 9888 5001



ABN 43 002 145 173

# FOUR DAY SOAKED CALIFORNIA BEARING RATIO TEST REPORT

Client: Pells Sullivan Meynink Pty Ltd PSM Project No.: PSM2808-004L

Ref No: L3788E

Report: 1

Report Date: 25/08/2015

Page 1 of 1

| 1        | 2  | 3  |
|----------|--|--|
| 4.5      | 4.5  | 4.5  |
| 1.63 STD | 1.26 STD   | 1.69 STD   |
| 20.1     | 31.0   | 17.5   |
| 1.55     | 1.28   | 1.68   |
| 95       | 101  | 99   |
| 118      | 95   | 91   |
|          |  |  |
| 25.5     | 30.8   | 17.3   |
| 23.7     | 29.4   | 16.0   |
|          |  |  |
| 24.1     | 29.9   | 18.6   |
| 22.9     | 33.5   | 18.6   |
| 5*       | 7*   | 15*  |
| 0.0      | 0.0  | 0.0  |
|          |  |  |
| 15       | 10   | 50   |
|          | 1.63 STD<br>20.1<br>1.55<br>95<br>118<br>25.5<br>23.7<br>24.1<br>22.9<br>5*<br>0.0 | 4.5 4.5  1.63 STD 1.26 STD  20.1 31.0  1.55 1.28  95 101  118 95  25.5 30.8  23.7 29.4  24.1 29.9  22.9 33.5  5* 7*  0.0 0.0 |

#### **NOTES:**

- · Refer to appropriate notes for soil descriptions
- Test Methods: AS1289 6.1.1, 5.1.1 & 2.1.1.
- Date of receipt of sample: 14/08/2015.
- \* Denotes not used in test sample.



Accredited for compliance with ISO/IEC 17025. This document shall not be reproduced except

Authorised Signature / Date (D. Treweek)



# Appendix C Borehole logs





# Pells Sullivan Meynink Engineering Consultants

Rock-Soil-Water

# **EXPLANATION SHEET BOREHOLE LOG**

### **GENERAL**

#### Method

## **Coring Size**

| Non-Cored Borehole |
|--------------------|
| Auger              |
| Hand Auger         |
| Diamond Rotary     |
| Percussion         |
| Other              |

# **Testing**

| Symbol | Description                   |
|--------|-------------------------------|
| UCS    | Uniaxial Compressive Strength |
| TXL    | Triaxial Test                 |
| BT     | Brazilian Test                |
| DT     | Direct Tensile                |
| SD     | Slake Durability              |
| Packer | Rock Mass Permeability        |

| Cored Borehole | Nominal Core<br>Diameter (mm) |
|----------------|-------------------------------|
| NMLC           | 51.9                          |
| BQ             | 36.5                          |
| BQ3            | 33.5                          |
| NQ             | 47.6                          |
| NQ3            | 45.1                          |
| HQ             | 63.5                          |
| HQ3            | 61.1                          |
| PQ             | 85                            |
| PQ3            | 83.1                          |
| Diatube        | Variable                      |
| Other          | -                             |

## **Samples**

| Symbol | Description                   |
|--------|-------------------------------|
| U50    | 50 mm undisturbed tube sample |
| D      | Disturbed sample              |
| Bs     | Bulk sample                   |

#### Water

| Symbol     | Description         |
|------------|---------------------|
|            | Water level         |
| <b>)</b>   | Water inflow        |
| <b>-</b> ◀ | Complete water loss |
| <u> </u>   | Partial water loss  |

# SOIL DESCRIPTIONS

# **Unified Soil Classification System (USCS)**

| Major Divisions               |  |                       | Symbol | Typical Names  |
|-------------------------------|--|-----------------------|--------|--|
|                               |  | Clean                 | GW     | Well-graded gravels and gravel-sand mixtures, little or no fines.                                  |
| Coarse-                       | Gravels<br>(more than 50%                                  | Gravels               | GP     | Poorly graded gravels and gravel-sand mixtures, little or no fines.                                |
| Grained<br>Soils              | coarser than<br>2mm)                                       | Gravels<br>With Fines | GM     | Silty gravels, gravel-sand-silt mixtures.  |
| More<br>than                  | ,  |                       | GC     | Clayey gravels. gravel-sand-clay mixtures.   |
| 50%<br>coarser                | Sands  | Clean                 | SW     | Well-graded sands and gravelly sands, little or no fines.  |
| than<br>0.075mm               | (more than 50%<br>of coarse<br>fraction finer<br>than 2mm) | Sands                 | SP     | Poorly graded sands and gravelly sands, little or no fines.  |
|                               |  | Sand With<br>Fines    | SM     | Silty sands, sand-silt mixture.  |
|                               | ,  |                       | SC     | Clayey sands, sand-clay mixtures.  |
|                               | Silts and Clays Liquid limit<br>50% or less                |                       | ML     | Inorganic silts, very fine sands, rock flour silty or clayey fine sands.                           |
| Fine-<br>Grained              |  |                       | CL     | Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays. |
| Soils<br>50% or               |  |                       | OL     | Organic silts and silty clays of low plasticity.   |
| more<br>finer than<br>0.075mm | Silts and Clays<br>Liquid limit<br>greater than 50%        |                       | МН     | Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts.                     |
| 0.07011111                    |  |                       | СН     | Inorganic clays of high plasticity, fat clays.   |
|                               |  |                       | ОН     | Organic clays of medium to high plasticity.  |
|                               | Highly Organic Soils                                       |                       |        | Peat etc.  |

### **Moisture Condition**

| Term                 | Symbol |
|----------------------|--------|
| Dry                  | D      |
| Moist                | M      |
| Wet                  | W      |
| Wet at Plastic Limit | WP     |
| Wet at Liquid Limit  | WL     |



#### Strength

**COHESIVE SOILS** are described in terms of undrained shear strength, colour and structure with comments on minor constituents or apparent special features. Undrained shear strength is measured by hand penetrometer or determined by laboratory testing or estimated from experience. Classification in terms of undrained shear strength is as follows:

| Term       | Symbol | Description for Field Estimation   | Shear Strength<br>(kPa) | UCS<br>(kPa) |
|------------|--------|--|-------------------------|--------------|
| Very Soft  | VS     | Easily penetrated several centimetres by fist.   | <12                     | <25          |
| Soft       | S      | Easily penetrated several centimetres by thumb. Can be moulded by light finger pressure.   | 12-25                   | 25-50        |
| Firm       | F      | Can be penetrated by thumb with moderate effort. Can be moulded by strong finger pressure. | 25-50                   | 50-100       |
| Stiff      | ST     | Readily indented by thumb.   | 50-100                  | 100-200      |
| Very Stiff | VST    | Readily indented by thumbnail.   | 100-200                 | 200-400      |
| Hard       | Н      | Indented with difficulty by thumbnail  | >200                    | >400         |

**NON-COHESIVE SOILS** are described in terms of density, colour, with comments on minor constituents or special features. Density (density index) is generally based on standard penetration testing (AS1289 Method 6.3.1), or other forms of penetration testing. Terms used in describing density are set out below:

| Term         | Symbol | Density Index | SPT N Values |
|--------------|--------|---------------|--------------|
| Very Loose   | VL     | <15%          | <5           |
| Loose        | L      | 15-35 %       | 5-10         |
| Medium Dense | MD     | 35-65 %       | 10-30        |
| Dense        | D      | 65-85 %       | 30-50        |
| Very Dense   | VD     | >85 %         | >50          |



# **ROCK DESCRIPTIONS**

# Weathering

| Term                    | Symbol | Description   |
|-------------------------|--------|---|
| Fresh                   | FR     | Rock substance unaffected by weathering.  |
| Slightly<br>Weathered   | SW     | Rock substance affected by weathering to the extent that partial staining or partial discolouration of the rock substance usually by limonite has taken place. The colour and texture of the fresh rock is recognisable; strength properties are essentially those of the fresh rock substance.   |
| Moderately<br>Weathered | MW     | Rock substance affected by weathering to the extent staining extends throughout whole of the rock substance and the original colour of the fresh rock is no longer recognisable.  |
| Highly<br>Weathered     | HW     | Rock substance affected by weathering to the extent that limonite staining or bleaching affects the whole of the rock substance and signs of chemical or physical decomposition of individual minerals are usually evident. Porosity and strength may be increased or decreased when compared to the fresh rock substance, usually as a result of the leaching or deposition of iron. The colour and strength of the original fresh rock substance is no longer recognisable. |
| Extremely<br>Weathered  | EW     | Rock substance affected by weathering to the extent that the rock exhibits soil properties, i.e. it can be remoulded and can be classified according to the Unified Soil Classification System, but the texture of the original rock is still evident.  |

# Strength

| Term              | Symbol | Description for Field Estimation   | Point Load<br>Index I <sub>s</sub> 50<br>(MPa) |
|-------------------|--------|--|--|
| Very Low          | VL     | Material crumbles under firm blows with sharp end of pick; can be peeled with a knife; pieces up to 30 mm thick can be broken by finger pressure.  | <0.1   |
| Low               | L      | Easily scored with a knife; indentations 1 mm to 3 mm show with firm blows of a pick point; has a dull sound under hammer. Pieces of core 150 mm long by 50 mm diameter may be broken by hand. Sharp edges of core may be friable and break during handling. | 0.1 to 0.3                                     |
| Medium            | М      | Readily scored with a knife; a piece of core 150 mm long by 50 mm diameter can be broken by hand with difficulty.  | 0.3 to 1.0                                     |
| High              | Н      | A piece of core 150mm long by 50mm cannot be broken by hand but can be broken by a pick with a single firm blow; rock rings under hammer.  | 1 to 3   |
| Very High         | VH     | Hand specimen breaks after more than one blow of a pick; rock rings under hammer.  | 3 to 10  |
| Extremely<br>High | EH     | Specimen requires many blows with geological pick to break; rock rings under hammer.   | >10  |




## **Defect Description**

Order of description: type, inclination, shape, roughness, infill type, infill thickness, number

### **Defect Type**

| Symbol | Description  |
|--------|--|
| CL     | Clay Seam  |
| FL     | Fault - fracture along which displacement is recognisable.   |
| SR     | Shear - a fracture along which movement has taken place but no displacement is recognisable. Evidence for movement may be slickensides, polishing and/or clay gouge.   |
| SH     | Sheared Zone - zone of multiple closely spaced fracture planes with roughly parallel planar boundaries usually forming blocks of lenticular or wedge shaped intact material. Fractures are typically smooth, polished or slickensided; and curved. |
| BG     | Bedding parting - arrangement in layers of mineral grains or crystals parallel to surface of deposition along which a continuous observable parting occurs.  |
| BSH    | Bedding plane shear - a shear formed along a bedding plane   |
| JN     | Joint - a single fracture across which rock has little or no tensile strength and is not obviously related to rock fabric.   |
| CN     | Contact - surface between two lithologies.   |
| SC     | Schistosity - plane formed by the preferred orientation of<br>the constituent minerals in a parallel arrangement in a<br>coarse grained rock which has undergone regional<br>metamorphism (schist).  |
| CV     | Cleavage - plane of mechanical fracture in a rock<br>normally sufficiently closely spaced to form parallel-<br>sided slices.   |
| FO     | Foliation  |
| CZ     | Crushed Zone - zone with roughly parallel, planar boundaries (commonly slickensided) containing disoriented usually angular rock fragments of variable size often in a soil matrix.  |
| VN     | Vein - fracture in which a tabular or sheet-like body of minerals have been intruded.  |
| DK     | Dyke - Igneous intrusion - often weathered and altered to a clay like substance.   |
| DZ     | Decomposed Zone - zone of any shape but commonly with parallel planar boundaries containing moderately to gradational boundaries into fresher rock.  |
| FZ     | Fractured Zone - a zone of closely spaced defects (mainly joints, bedding, cleavage and/or schistosity) comprised of core lengths in the order of 50 mm or less.   |

### **Standard Defect Symbols**



# Roughness Colour Code (for summary log)





#### **Shape**

| Term       | Symbol | Description  |
|------------|--------|--|
| Planar     | PL     | Forms a continuous plane without variation in orientation. |
| Curved     | CU     | Has a gradual change in orientation.                       |
| Undulating | UN     | Has a wavy surface shape.                                  |
| Stepped    | ST     | Has one or more well defined steps                         |
| Irregular  | IR     | Many changes of orientation.                               |

#### Roughness

| Term                     | Symbol | Description   |
|--------------------------|--------|---|
| Slickensided or polished | Ro1    | Very smooth, reflects light.                          |
| Smooth                   | Ro2    | Roughness not detected with finger.                   |
| Defined<br>ridges        | Ro3    | Sandpaper feel (fine to medium sandpaper).            |
| Small steps              | Ro4    | Sandpaper feel<br>(medium to<br>coarse<br>sandpaper). |
| Very rough               | Ro5    | Very well defined ridges and/or steps.                |

# Infill Type

| Symbol | Description    |
|--------|----------------|
| KL     | Clean          |
| CA     | Calcite        |
| СВ     | Carbonaceous   |
| CHL    | Chlorite       |
| FE     | Iron oxide     |
| QZ     | Quartz         |
| MG     | Manganese      |
| SU     | Sulphides      |
| SE     | Sericite       |
| RF     | Rock fragments |
| G      | Gravel         |
| S      | Sand           |
| Z      | Silt           |
| CL     | Clay           |

#### **Infill Thickness**

Where infilling is present, the thickness of infill is recorded using the following convention:

ST Iron oxide staining of less than 1 mm VN Veneer coating of less than 1 mm

If the infilling is greater than 1 mm, the actual thickness of infill is recorded in millimeters.

If infill is not present, a dash (-) is recorded

#### Number

Number of defects with similar characteristics.





**BH01** 

Page 1 of 5

# **Engineering Log - Non Cored Borehole**

Goodman Group Client: Commenced: 23/04/2019 Project Name: **Burrows Road** Completed: 23/04/2019 1-3 Burrows Rd St Peters Logged By: Hole Location: JsR

Project No.:

PSM2808

Hole Position: 331557.0 m E 6245383.0 m N Checked By: AS

|                           |                 | Drilli                                 | ng Informati                              | on       |           |                                   |             |                          | Soil Description   |          |                                   | HD O                                 | Observations  |
|---------------------------|-----------------|--|---|----------|-----------|-----------------------------------|-------------|--------------------------|--|----------|-----------------------------------|--------------------------------------|---|
| Penetration               | Support         | Water                                  | Samples<br>Tests<br>Remarks               | Recovery | RL<br>(m) | Depth (m)                         | Graphic Log | Classification<br>Symbol | Material Description<br>SOIL NAME: Colour, structure,<br>plasticity, additional  | Moisture | Consistency /<br>Relative Density | Hand<br>Penetromete<br>UCS<br>(kPa)  | r Structure, Zoning, Origin,<br>Additional Observations   |
|                           | 1               |  |   |          |           |                                   |             |                          | Asphalt: 50 mm thick.  | 1        |                                   |                                      |   |
|                           | z               |  |   |          |           | -                                 |             |                          | Concrete: 250 mm thick.  |          |                                   |                                      |   |
|                           |                 | n standpipe                            |   |          | 0.1       | 1—                                |             |                          | Sandy Clayey GRAVEL: to 20 mm, sub-rounded to sub-angular, dark grey to black; clay non-plastic; sand fine to medium grained.  Silty CLAY: medium plasticity, black; some shale fragments, metal, rubber and plastic observed. | -        |                                   |                                      | 0.30: Inferred FILL.  |
|                           |                 | Observed at 1.76 m in standpipe        |   |          | -1.0      | 3-                                |             |                          |  | w        | L to F                            |                                      |   |
|                           |                 |  |   |          | -2.0      | 4                                 |             | SW-SM                    | Silty SAND with clay: fine to medium grained, grey; clay low plasticity.   | _        | D to VD                           |                                      | 4.40: Inferred alluvial soil.   |
| AD/T -<br>AD/V -<br>WB -V | Washt<br>Standa | er drill<br>er drill<br>oore<br>ard pe | ing TC bit<br>ing V bit<br>netration test | Pe       | throu     | tion<br>sistanc<br>ugh to<br>usal | -           | > Inflo<br>⊲ Par         | ater Samples and Tests ow U - Undisturbed Sample tial Loss plete Loss plete Loss TW - Thin Walled  |          | D<br>M                            | re Condition - Dry I - Moist / - Wet | Consistency/Relative Den  VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard |

Soil and rock descriptions in accordance with AS 1726:2017

Dense Very dense Cemented Compact



**BH01** 

Page 2 of 5

# **Engineering Log - Non Cored Borehole**

Client: Goodman Group Commenced: 23/04/2019 Project Name: **Burrows Road** Completed: 23/04/2019

Project No.:

PSM2808

1-3 Burrows Rd St Peters Hole Location: Logged By: JsR Hole Position: 331557.0 m E 6245383.0 m N Checked By: AS

|                           | Drill M<br>Hole D         |                |                                     | _  |          | ack Mo<br>0 mm | ounted                            | i           |                          | Inclination: -90° RL Surface<br>Bearing: Datum:   | ce:                   | 2.0<br>AF                         | 05 m<br>HD O                                 | perator: Rockwell   |
|---------------------------|---------------------------|----------------|-------------------------------------|--|----------|----------------|-----------------------------------|-------------|--------------------------|---|-----------------------|-----------------------------------|--|---|
| Ī                         |                           |                | Drilli                              | ng Informati                                       | on       |                |                                   |             |                          | Soil Description  |                       |                                   |  | Observations  |
| -                         | Method<br>Penetration     | Support        | Water                               | Samples<br>Tests<br>Remarks                        | Recovery | RL<br>(m)      | Depth<br>(m)                      | Graphic Log | Classification<br>Symbol | Material Description<br>SOIL NAME: Colour, structure,<br>plasticity, additional   | Moisture<br>Condition | Consistency /<br>Relative Density | Hand<br>Penetromete<br>UCS<br>(kPa)          | r Structure, Zoning, Origin,<br>Additional Observations   |
| rj; PSM 3.02.1 2019-03-06 | ADV                       | z              | Observed at 1.76 m in standpipe     |  |          | 7.0 -6.0 -6.0  |                                   |             | SW-SM<br>CH              |   | W                     | D to VD                           | 10 20 80 80 80 80 80 80 80 80 80 80 80 80 80 |   |
| BH NZ AL                  |                           |                |                                     |  |          |                |                                   |             |                          | Structure becomes visisble at 9.8m  |                       |                                   |  |   |
| 3.GLB Log PSM AU NONCORE  | AD/T -<br>AD/V -<br>WB -W | tanda<br>ush t | r drill<br>r drill<br>ore<br>ird pe | ing TC bit<br>ing V bit<br>enetration test<br>ving | Pe       | throu          | ion<br>sistance<br>ugh to<br>usal | _           | Inflo<br>Par             | water ow U - Undisturbed Sample D D D Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample |                       | D<br>M<br>W                       | re Condition<br>- Dry<br>- Moist<br>/ - Wet  | Consistency/Relative Density  VS - Very soft  S - Soft  F - Firm  St - Stiff  VSt - Very stiff  H - Hard  VL - Very loose  L - Loose  MD - Medium dense |

Soil and rock descriptions in accordance with AS 1726:2017

L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact



**BH01** 

Page 3 of 5

#### **Engineering Log - Non Cored Borehole**

Client: 23/04/2019 Goodman Group Commenced: 23/04/2019 Project Name: **Burrows Road** Completed:

Hole Location: 1-3 Burrows Rd St Peters Logged By: JsR Hole Position: 331557.0 m E 6245383.0 m N Checked By: AS

Drill Model and Mounting: RL Surface: Track Mounted Inclination: -90° 2.05 m

Hole Diameter: 100 mm Bearing: Datum: AHD Operator: Rockwell

Project No.:

PSM2808

| ļ  | -      | HOIE D      | ıam          | eter:                           |                             | 100      | ) mm              |                         |             |                          | Bearing: Datum:   |                       | Al                                | אט כ   | perator: Rockwell                                       |
|--|--------|-------------|--------------|---------------------------------|-----------------------------|----------|-------------------|-------------------------|-------------|--------------------------|---|-----------------------|-----------------------------------|--|---|
|  |        |             |              | Drilli                          | ing Informatio              | on       |                   |                         |             |                          | Soil Description  |                       |                                   |  | Observations  |
|  | Method | Penetration | Support      | Water                           | Samples<br>Tests<br>Remarks | Recovery | RL<br>(m)         | Depth<br>(m)            | Graphic Log | Classification<br>Symbol | Material Description<br>SOIL NAME: Colour, structure,<br>plasticity, additional   | Moisture<br>Condition | Consistency /<br>Relative Density | Hand<br>Penetromete<br>UCS<br>(kPa)          | r Structure, Zoning, Origin,<br>Additional Observations |
|  | AD/V   |             | N            | Observed at 1.76 m in standpipe |                             |          | -9.0              | 11 -                    |             | СН                       | CLAY: high plasticity, pale grey-brown and red. (continued)  SHALE: grey-brown, extremely weathered, very low to low strength | M<br>———              | H                                 | -  | 11.05° V-hit refusal                                    |
| ONCORE BH NZ AU PSM2808 GPJ < <drawingfile> 10/05/2019 1652 10.0.000 Datgel Fence and Map Tool   Lb: PSM 3.02.1.2019-03-06 Prj: PSM 3.02.1.2019-03-06 Prj: PSM 3.02.1.2019-03-06</drawingfile> |        |             |              |                                 |                             |          | -12.0 -11.0 -10.0 | 12                      |             |                          | Continued on cored borehole sheet   |                       |                                   |  | 11.05: V-bit refusal.                                   |
| NONCOR   | A      |             | etho<br>Auge |                                 | ing TC bit                  | Pe<br>⊘  | No re             | t <b>ion</b><br>sistanc | e [         | W<br>> Inflo             | /ater Samples and Tests low U - Undisturbed Sample still ass D - Disturbed Sample   | ٨                     | <b>rioistu</b><br>D<br>M          | <b>ıre Condition</b><br>  - Dry<br>  - Moist | Consistency/Relative Density  VS - Very soft  S - Soft  |

AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger Screwing

through to refusal

✓ Partial Loss Complete Loss U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

- Very soft
- Soft
- Soft
- Soft
- Siff
- Suff
- Very stiff
- Hard
- Very loose
- Loose
- Medium dense
- Wery dense
- Very dense
- Cemented
- Compact S F St VSt H VL MD D VD Ce C

Soil and rock descriptions in accordance with AS 1726:2017 See Explanatory Notes for details of abbreviations and basis of descriptions.





**BH01** 

Page 4 of 5

# **Engineering Log - Cored Borehole**

Client: Goodman Group Commenced: 23/04/2019 **Burrows Road** Completed: 23/04/2019 Project Name: JsR

Project No.:

PSM2808

1-3 Burrows Rd St Peters Hole Location: Logged By: Hole Position: 331557.0 m E 6245383.0 m N Checked By: AS

| L  | поіе           | F 05                                      | ILIOIT.  | 33                | 1337      | .0 111 E            | 0240                 | 363.0 III N   |   | Cite                 | ckeu   | Dy.                                     |   | AS                         |  |  |   |   |   |        |
|--|----------------|---|--|-------------------|-----------|---------------------|----------------------|---|---|----------------------|--|---|---|----------------------------|--|--|---|---|---|--------|
|  |                |   | el and M<br>pe and L   |                   | •         | Track<br>NML0       |                      |   | -90°  | RL S                 |  | ce:                                     | 2.0:<br>AH  |                            | 0  | nera                                   | ator:   | Rockwe                                    | ااد   |        |
| F  | Dani           |   | ling Info  |                   |           | 141112              | 0                    | Rock Sub  | stance  | Dutt                 |  |   | ,   |                            |  |  |   | ss Defe                                   |   |        |
| Method   | Water          | RQD (%)                                   | SAMPLES & FIELD TESTS  | WPT (Lugeons)     | RL<br>(m) | Depth<br>(m)        | Graphic Log          | Material Description<br>ROCK TYPE: Colour, grain size,<br>(texture, fabric, mineral composition<br>alteration, cementation, etc as ap<br>inclusions and minor compo | structure<br>n, hardness,<br>oplicable),  | Weath<br>≳ ≩ ≩       |  | 0.1                                     | rength s(50) - Axial Diametral  | S <sub>I</sub>             | efect<br>pacing<br>mm)   | 9                                      | Descrip   | otion, alp                                | ons / Comn<br>na/beta, inf<br>oe, roughno<br>s, other | illing |
|  |                |   | T1.15m<br>1 ls(50)<br>d=0.01   |                   | -9.0      | -<br>-<br>-<br>11-  |                      | Continued from non-cored borehole sl<br>SHALE: dark grey and brown, develop   | oed bedding.  |                      |  |   |   |                            |  |  |   |   |   |        |
| PSM 3.02.1 2019-03-06  | standpipe      | 86  | 11.95m<br>2 is(50)<br>4=0.01<br>a=0.3  |                   | -10.0     | 12-                 |                      | SHALE: dark grey, thinly laminated, w bedding.  | ell developed   |                      |  |   | <br>         <br>         <br>         <br>         <br>         <br> |                            |  |  | <sup>1</sup> IS, 0°,<br>−IS, 0°,<br>−IS, 0°,<br><sup>1</sup> JT, 20 | CL, PR,<br>CL, PR,<br>CL, PR,<br>°, FE SN | S, 10 mm  |        |
| el Fence and Map Tool   Lib: PSM 3.02.1 2019-03-06 Prj NMI C.  | m in           | G,  | 13.05m<br>3 Is(50)<br>d=0.2<br>a=0.3<br>MPa  |                   | -11.0     | 13-                 |                      |   |   |                      |  |   | 1                               |                            |  |  |   |   |   |        |
| Log PSM AU CORE BH PSMZ808 GPJ < <drawning*ie>&gt; 10/05/2019 16:51 10.0.000 Datgel Ferce and Map Total Lb: PSM 3.02.1 2019-03-06 Prj; PSM 3.02.1 2019-03-06 NSM I C</drawning*ie> |                | 66  | 13.95m<br>4 ls(50)<br>d=0.1<br>a=0.4<br>MPa  |                   | -12.0     | -<br>14 —<br>-<br>- |                      |   |   |                      |  | θ                                       |   |                            |  |  |   | °, KL, PF                                 |   |        |
| Log PSM AU CORE BH PS  | AD<br>WE<br>HQ | /T - Aug<br>/V - Aug<br>3 - Wa<br>33- Wir | dethod ger drilling \ | / bit<br>(63.5 mr |           | <                   | > Inflov<br>☐ Partia | XW - Ext<br>HW - Hig<br>al Loss MW - Mo<br>olete Loss SW - Slight<br>FR - Fre   | nthering<br>tremely Weathered<br>phly Weathered<br>derately Weathered<br>phtly Weathered<br>esh | SS<br>SZ<br>BF<br>SM | Defe<br>- Fau<br>3 - She<br>2 - She<br>2 - Beo<br>4 - Sea<br>- Infil | lt<br>ar Sur<br>ar Zon<br>Iding p<br>im | face<br>e<br>arting   | CI<br>SI<br>VI<br>CI<br>RI | Iing/C<br>N - Cle<br>N - Sta<br>N - Ver<br>O - Cor<br>F - Ror<br>- Gra | ean<br>iin<br>neer<br>ating<br>ck frag |   | SL -<br>POL<br>S -<br>RF -<br>VR -        | Slickensided - Polished Smooth Rough Very Rough       |        |

PQ3- Wireline core (85.0 mm) SPT- Standard penetration test PT - Push tube

See Explanatory Notes for details of abbreviations and basis of descriptions.

Graphic Log/Core Loss

Core recovered (hatching indicates material) No core recovery

| Strength | VL - Very Low | L - Low | M - Medium | H - High | VH - Very High | EH - Extremely High |

SM - Seam IS - Infilled Seam JT - Joint CO - Contact CZ - Crushed Zone VN - Vein FZ - Fracture Zone BSH - Bedding Shear DB - Drilling Break S - Sand
Z - Silt
CA - Calcite
CL - Clay
FE - Iron
QZ - Quartz
X - Carbonaceous

Shape
PR - Planar
CU - Curved
UN - Undulating
ST - Stepped
IR - Irregular



**BH01** 

Page 5 of 5

PSM2808

23/04/2019

23/04/2019

JsR

AS

Project No.:

Commenced:

Completed: Logged By:

Checked By:

#### **Engineering Log - Cored Borehole**

Client: Goodman Group Project Name: **Burrows Road** 

Hole Location: 1-3 Burrows Rd St Peters Hole Position: 331557.0 m E 6245383.0 m N

Drill Model and Mounting: Track Mounted Inclination: -90° RL Surface: 2.05 m

|  |        |       |         | e and L   |               | -                       | NML          |                        |   | Datum:                                   | AHD                                  |                           | ator: Rockwell  |
|--|--------|-------|---------|---|---------------|-------------------------|--------------|------------------------|---|--|--------------------------------------|---------------------------|---|
|  |        |       | Drill   | ing Info  | rmat          | ion                     |              |                        | Rock Substance  |  |                                      | R                         | ock Mass Defects  |
|  | Method | Water | RQD (%) | SAMPLES &<br>FIELD TESTS                        | WPT (Lugeons) | RL<br>(m)               | Depth<br>(m) | Graphic Log            | Material Description ROCK TYPE: Colour, grain size, structure (texture, fabric, mineral composition, hardness, alteration, cementation, etc as applicable), inclusions and minor components | Weathering O-                            | Strength Is(50)  - Axial - Diametral | Defect<br>Spacing<br>(mm) | Defect Descriptions / Comments  Description, alpha/beta, infilling or coating, shape, roughness, thickness, other |
| J CORE BH PSM2808.GPJ < <drawingfile>&gt; 10/05/2019 16:51 10.0.000 Datge Fence and Map Tool   Lb; PSM 3.02.1 2019-03-06 Pr; PSM 3.02.1 2019-03-06</drawingfile> |        |       |         |   |               | -17.0 -16.0 -15.0 -14.0 |              |                        | Hole Terminated at 15.02 m Target depth. Standpipe installed  |  |                                      |                           |   |
| CORE BH  |        | AD/   | T - Aug | e <b>thod</b><br>er drilling T<br>er drilling V | C bit         |                         |              | <b>W</b> a<br>≥ Inflow | ater Weathering  XW - Extremely Weathered  HW - Highly Weathered  Www. Moderately Weathered   | Perfect T<br>FT - Fault<br>SS - Shear St | urface                               | CN - Clean<br>SN - Stain  | ting Roughness SL - Slickensided POL - Polished S - Smooth  |

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
HQ3- Wireline core (63.5 mm)
PQ3- Wireline core (85.0 mm)
SPT- Standard penetration test
PT - Push tube

✓ Partial Loss Complete Loss

Graphic Log/Core Loss

Core recovered (hatching indicates material)
No core recovery See Explanatory Notes for details of abbreviations and basis of descriptions

HW - Highly Weathered MW - Moderately Weathered SW - Slightly Weathered FR - Fresh

| Strength | VL - Very Low | L - Low | M - Medium | H - High | VH - Very High | EH - Extremely High |

S - Shear Surface
SZ - Shear Zone
BP - Bedding parting
SM - Seam
IS - Infilled Seam
JT - Joint
CO - Contact
CZ - Crushed Zone
VN - Vein
FZ - Fracture Zone
BSH - Bedding Shear
DB - Drilling Break

| SN - Stain | VN - Veneer | CO - Coating | RF - Rock fragments | Gravel | S - Sand | Z - Slit | CA - Calcite | CL - Clay | FE - Iron | GZ - Quartz | X - Carbonaceous |

POL - Polished S - Smooth RF - Rough VR - Very Rough Shape PR - Planar CU - Curved UN - Undulating ST - Stepped IR - Irregular





1 - 3 Burrows Road, St Peters Geotechnical Investigation BOREHOLES CORE PHOTO

**Goodman Limited** 

BH01 From 11.1 m to 15.02 m

PSM2808-005R

Appendix C



**BH02** 

Page 1 of 5

# **Engineering Log - Non Cored Borehole**

Client: Goodman Group Commenced: 23/04/2019 Project Name: **Burrows Road** Completed: 23/04/2019

Project No.:

PSM2808

1-3 Burrows Rd St Peters Hole Location: Logged By: JsR Hole Position: 331729.0 m E 6245470.0 m N Checked By: AS

| Drill M<br>Hole D         |                |   | d Mounting:<br>:                                     |          | ck Mo<br>mm       | ounted                            | d           |                          | Inclination: -90°<br>Bearing:  | RL Surfa<br>Datum:                             | ice:                  | 2.3<br>Al-                        | 30 m<br><del>1</del> D     |                             | Oı   | perator: Rockwell   |
|---------------------------|----------------|---|--|----------|-------------------|-----------------------------------|-------------|--------------------------|--|--|-----------------------|-----------------------------------|----------------------------|-----------------------------|------|---|
|                           |                | Drill                                       | ing Informat   | ion      |                   |                                   |             |                          | Soil Descri  | ption  |                       |                                   |                            |                             |      | Observations  |
| Method<br>Penetration     | Support        | Water                                       | Samples<br>Tests<br>Remarks                          | Recovery | RL<br>(m)         | Depth<br>(m)                      | Graphic Log | Classification<br>Symbol | Material Description<br>SOIL NAME: Colour, stru<br>plasticity, additional  | cture,   | Moisture<br>Condition | Consistency /<br>Relative Density | Pene<br>(                  | land<br>trom<br>JCS<br>kPa) | eter | Structure, Zoning, Origin,<br>Additional Observations   |
| D                         | z              |   |  |          |                   | -                                 |             |                          | Concrete: 200 mm thick.  Sandy GRAVEL: to 30 mm, sub-agrey to black; sand coarse graine metal, rubber, ceramics, copper a observed.  | d; some  |                       |                                   |                            |                             |      | 0.20: Inferred FILL.  |
|                           |                |   |  |          | _ <del>1</del> .3 | 1—<br>-<br>-                      |             |                          |  |  |                       |                                   |                            |                             |      | 1.00: Numerous bricks observed  |
|                           |                | red at 3.84 m in standpipe                  |  |          | 0.3               | 2-                                |             |                          |  |  | w                     | L to F                            |                            |                             |      |   |
|                           |                | Observed at                                 |  |          | -0.7              | 3                                 |             |                          |  |  |                       |                                   |                            |                             |      |   |
|                           |                |   |  |          | -1.7              | 4                                 |             | SW-SM                    | Silty SAND with clay: fine to medii<br>grey; clay low plasticity.  | um grained,                                    | w                     | D to<br>VD                        |                            |                             |      | 4.00: Inferred alluvial soil. 4.20: Some shells observed  |
| AD/T -<br>AD/V -<br>WB -W | tanda<br>ush t | er dril<br>er dril<br>oore<br>ard pe<br>ube | ling TC bit<br>ling V bit<br>enetration test<br>wing |          | throu             | ion<br>sistance<br>ugh to<br>usal |             | > Inflo<br>✓ Par         | dater Samples al ow U - Undisturbed Samplet Loss SPT Standard F Sandre F Samplet Loss SPT Standard F Sandre F S | Sample<br>Imple<br>netration Test<br>al Sample |                       | loistu<br>D<br>M<br>W             | re Co<br>- D<br>- M<br>- W | ry<br>loist                 | ion  | Consistency/Relative Densite  VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose L - Loose MD - Medium dense D - Dense VD - Very dense |

Soil and rock descriptions in accordance with AS 1726:2017



**BH02** 

Page 2 of 5

# **Engineering Log - Non Cored Borehole**

Client: Goodman Group Commenced: 23/04/2019 Completed: 23/04/2019 Project Name: **Burrows Road** Hole Location: 1-3 Burrows Rd St Peters JsR

Project No.:

PSM2808

Logged By: Hole Position: 331729.0 m E 6245470.0 m N Checked By: AS

Drill Model and Mounting: Track Mounted RI Surface: Inclination: \_an° 2 30 m

|   | Drill M<br>Hole D  |   |   | _  |          | ack Mo    | ounted                     | i           |                          | Inclinati<br>Bearing                           |  | RL Surfa<br>Datum:                            | ce:                   | 2.3<br>AF                         | 30 m<br>HD            | 1                        | C              | Operator: Rockwell  |
|---|--|---|---|--|----------|-----------|----------------------------|-------------|--------------------------|--|--|---|-----------------------|-----------------------------------|-----------------------|--------------------------|----------------|---|
| ŀ   |  |   |   | ing Informati                                      |          |           |                            |             |                          |  | Soil Descrip   |   |                       |                                   |                       |                          |                | Observations  |
|   | Method<br>Penetration                                    | Support                                 | Water   | Samples<br>Tests<br>Remarks                        | Recovery | RL<br>(m) | Depth (m)                  | Graphic Log | Classification<br>Symbol | M<br>SOIL N<br>p                               | laterial Description<br>IAME: Colour, structilasticity, additional   |   | Moisture<br>Condition | Consistency /<br>Relative Density | Pen                   | Handetron<br>UCS<br>(kPa | nete<br>;<br>) | er Structure, Zoning, Origin,<br>Additional Observations                              |
| PSM AUNONCOCE BH NZ AU PSM2808 GPJ < <drawingfile>&gt; 10/05/2019 1652 10.0 000 Datgel Fence and Map Tool   Lb: PSM 3/02/1/2019-03-06 Pt; PSM 3/02/1/2019-03-06</drawingfile> | ADV  | Z                                       | Observed at 3.84 m in standpipe               |  | Pe       |           | 6— 7— 8— 9— -              |             | СН                       | GLAY: high pla                                 | sticity, pale grey-bro   | own.  | W                     | D to VD                           |                       |                          |                | n Consistency/Relative Density  |
| Log PSM AU NONCO  | AD/T -<br>AD/V -<br>WB -W<br>SPT - S<br>PT - P<br>AS - A | Auge<br>Auge<br>/asht<br>tanda<br>ush t | er drill<br>er drill<br>oore<br>ard pe<br>ube | ing TC bit<br>ing V bit<br>enetration test<br>wing |          | No re     | sistance<br>ugh to<br>usal |             | Inflo     ✓ Par          | ow L<br>tial Loss S<br>nplete Loss E<br>T<br>L | J - Undisturbed Sa<br>D - Disturbed Sal<br>SPT - Standard Per<br>SS - Environmenta<br>W - Thin Walled<br>B - Large Disturb | Sample mple etration Test Il Sample ed Sample | 10                    | D<br>M                            | - [<br>  - N<br>/ - V | Ory<br>Moist             |                | VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose |

VSt - Very stiff
H - Hard
VL - Very loose
L - Loose
MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact

Soil and rock descriptions in accordance with AS 1726:2017 See Explanatory Notes for details of abbreviations and basis of descriptions.



**BH02** 

Page 3 of 5

# **Engineering Log - Non Cored Borehole**

Client: 23/04/2019 Goodman Group Commenced: 23/04/2019 Project Name: **Burrows Road** Completed:

Logged By: Hole Location: 1-3 Burrows Rd St Peters JsR Hole Position: 331729.0 m E 6245470.0 m N Checked By: AS

Drill Model and Mounting: Track Mounted Inclination: -90° RL Surface: 2.30 m

Project No.:

PSM2808

|  | Hole D      | iam     | eter:                           | :                           | 100      | 0 mm       |                          |             |                          | Bearing: D   | atum: |                       | Αŀ                                | ID        |                              | (              | Op | perator: Rockwell   |
|--|-------------|---------|---------------------------------|-----------------------------|----------|------------|--------------------------|-------------|--------------------------|--|-------|-----------------------|-----------------------------------|-----------|------------------------------|----------------|----|---|
|  |             | ı       | Drilli                          | ing Informatio              | on       |            |                          |             |                          | Soil Description   | n     |                       |                                   |           |                              |                |    | Observations  |
| Method   | Penetration | Support | Water                           | Samples<br>Tests<br>Remarks | Recovery | RL<br>(m)  | Depth<br>(m)             | Graphic Log | Classification<br>Symbol | Material Description<br>SOIL NAME: Colour, structure<br>plasticity, additional |       | Moisture<br>Condition | Consistency /<br>Relative Density | Pen<br>01 | Hane<br>etror<br>UCS<br>(kPa | met<br>S<br>ı) |    | Structure, Zoning, Origin,<br>Additional Observations         |
| and Map Tod   Lb: PSM 3.02.1.2019.03.06 Ph; PSM 3.02.1.2019.03.06 Ph   |             | N       | Observed at 3.84 m in standpipe |                             |          | -10.7 -8.7 | 11                       |             | CH                       | CLAY: high plasticity, pale grey-brown. (continued)  Becomes dark grey         |       | M                     | St to<br>VSt                      |           |                              |                |    | 12.20: Becomes harder to drill                                |
| UNONCORE BH NZ AU PSM2808.GPJ <cdrawingfile>&gt; 10/05/2019 16:52 10.0.000 Datgel Fence and M</cdrawingfile> |             | detho   | d                               |                             | Pé       | 2:1-       | -<br>-<br>14 —<br>-<br>- |             | W                        | Continued on cored borehole sheet  ater Samples and To                         | ests  | M                     | loistu                            | re C      | ondi<br>Ory<br>Moist<br>Mat  | itio           | n  | Consistency/Relative Density VS - Very soft S - Soft F - Firm |

AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger Screwing

through to refusal

Partial Loss Complete Loss D - Disturbed Sample SPT - Standard Penetration Test ES - Environmental Sample TW - Thin Walled LB - Large Disturbed Sample

W - Wet

Soil and rock descriptions in accordance with AS 1726:2017 See Explanatory Notes for details of abbreviations and basis of descriptions



# P S M → ··· ×

**BH02**Page 4 of 5

PSM2808

Project No.:

# **Engineering Log - Cored Borehole**

Client: Goodman Group Commenced: 23/04/2019
Project Name: Burrows Road Completed: 23/04/2019
Hole Location: 1-3 Burrows Rd St Peters Logged By: JsR/NTH
Hole Position: 331729 0 m F 6245470 0 m N

|  | Hole                            | e Posi   | tion:                                   | 33            | 1729      | .0 m E              | 6245        | 470.0 m N   |  |  |     | heck  |  | -   | :  | /    | AS   |                        |  |        |  |
|--|---------------------------------|--|---|---------------|-----------|---------------------|-------------|---|--|--|-----|---|--|---|--|------|--|------------------------|--|--------|--|
| Г  |                                 |  | el and M                                |               | -         | Track               |             |   | lination:  | -90°                                   |     | L Sı  |  | ce:   |  | 2.30 |  |                        |  |        |  |
| $\vdash$   | Bar                             | rei iy   | oe and L                                | .engti        | n:<br>    | NML                 | 3 3m        | Ве  | aring:   |  | D   | atun  | n:   |   |  | AHD  | <u> </u>   | 0                      | pera   | ator:  | Rockwell   |
|  |                                 | Dril   | ling Info                               | rmat          | ion       |                     |             | F   | Rock Sub   | stance                                 |     |   |  |   |  |      |  |                        | R  | ock M  | lass Defects   |
| 14 O M   | Water                           | RQD (%)  | SAMPLES &<br>FIELD TESTS                | WPT (Lugeons) | RL<br>(m) | Depth<br>(m)        | Graphic Log | Material De<br>ROCK TYPE: Colour,<br>(texture, fabric, mineral c<br>alteration, cementatior<br>inclusions and mir | grain size,<br>composition<br>n, etc as ap   | n, hardness,<br>oplicable),            |     | eathe   |  | 0-1-0   | 0.3  | ))   | Sp<br>(  | efect<br>pacing<br>mm) | 9  | Desc   | t Descriptions / Comments<br>ription, alpha/beta, infilling<br>lating, shape, roughness,<br>thickness, other   |
| and Map Tool I Lib. PSM 3 02.1 2019-03-06 Prj: PSM 3 02.1 2019-03-06   |                                 |  |   |               | 10.7 -9.7 |                     |             | Continued from non-cored to   | porehole st  | neet                                   |     |   |  |   |  |      |  |                        |  |        |  |
| PSM AU CORE BH PSM2808.GPJ < <drawingfile>&gt; 10/05/2019 14:34 10.0.000 Datgel Fence and Map Tool   L. N. N. N. O</drawingfile> | Observed at 3.84 m in standpipe | 100  | 14.35m<br>1 ls(50)<br>d=0<br>a=0<br>MPa |               | -11.7     | -<br>14 —<br>-<br>- |             | SHALE: dark grey and brov<br>very low to low strength.  SHALE: dark grey, thinly lar<br>bedding.                  |  |  |     |   |  |   |  |      |  |                        |  | 10.20  | 0: V-bit refusal.  |
| M 3.02.1 LIB.GLB Log   | AI<br>W<br>H<br>P<br>SI<br>P    | HQ3- Wireline core (63.5 mm) PQ3- Wireline core (85.0 mm) SPT - Standard penetration test PT - Push tube |   |               |           |                     |             | al Loss plete Loss pg/Core Loss ecovered (hatching tes material) re recovery                                      | XW - Ext<br>HW - Hig<br>MW - Moo<br>SW - Slig<br>FR - Fre<br>Strei<br>VL - Ver<br>L - Lov<br>M - Meg<br>VH - Ver | <b>ngth</b><br>y Low<br>v<br>dium<br>h | 1 1 | SS -<br>SZ -<br>BP -<br>SM -<br>IS -<br>CO -<br>CZ -<br>VN -<br>FZ -<br>BSH | Sear<br>Infille<br>Join<br>Con<br>Crus<br>Vein<br>Frac | It ar Su ar Zo ding m ed Se t tact shed cture | urface<br>one<br>parting<br>eam<br>Zone<br>Zone<br>Shear | 1    | CN<br>SNN<br>CC<br>RF<br>G<br>S<br>Z<br>CA<br>CL<br>FE |                        | ean ain neer ating ck frag avel nd t lcite ay n artz | gments | Roughness SL - Slickensided POL - Polished S - Smooth RF - Rough VR - Very Rough Shape PR - Planar CU - Curved UN - Undulating ST - Stepped IR - Irregular |



**BH02** 

Page 5 of 5

PSM2808

Project No.:

#### **Engineering Log - Cored Borehole**

Client: 23/04/2019 Goodman Group Commenced: 23/04/2019 Project Name: **Burrows Road** Completed: Hole Location: 1-3 Burrows Rd St Peters JsR

Logged By: Hole Position: 331729.0 m E 6245470.0 m N Checked By: AS

Drill Model and Mounting: Track Mounted Inclination: -90° RL Surface: 2.30 m

|  | Barrel Type and Length: NMLC 3 m                                 |  |      |   |      | Datun   |                     |   | AHD  |   | rator:                         | Rockwell |   |     |  |              |
|--|--|--|------|---|------|---|---------------------|---|--|---|--------------------------------|----------|---|-----|--|--------------|
|  |  |  | Dril | ling Info                                   | rmat | ion   |                     |   | Rock Substance   |   |                                |          |   | F   | Rock N                                     | lass Defects |
|  | Method   |  |      |   |      | Material Description ROCK TYPE: Colour, grain size, structure (texture, fabric, mineral composition, hardness, alteration, cementation, etc as applicable), inclusions and minor components | Weather             |   | 0.1  | rength<br>s(50)<br>- Axial<br>Diametral | Defect<br>Spacing<br>(mm)      | Desc     | t Descriptions / Comments<br>cription, alpha/beta, infilling<br>pating, shape, roughness,<br>thickness, other |     |  |              |
| Ī  |  |  | 100  | 2 <sup>5.05m</sup><br>d=0.1<br>a=0.1<br>MPa |      |   |                     |   |  |   |                                |          |   |     |  |              |
| CORE BH PSM2808.GPJ <-Drawing-lie>> 10/05/2019 1651 10.0.000 Datgel Ferce and Map Tool   Lib. PSM 3.02.1.2019-03-03 Prj. PSM 3.02.1.2019-03-06 |  |  |      | a=0.1<br>MPa                                |      | -16.7 -13.7 -13.7   | 16—                 |   | Hole Terminated at 15.18 m Target depth. Standpipe installed |   |                                |          |   |     |  |              |
| CORE BI-   | Method  AD/T - Auger drilling TC bit AD/V - Auger drilling V bit |  |      |   |      |   | <b>W</b> ∂<br>Inflo | Weathering           XW - Extremely Weathered           W HW - Highly Weathered | FT -   | Fau                                     | <b>ct Ty</b><br>ilt<br>ear Sur | -        | Infilling/Coa<br>CN - Clean<br>SN - Stain   | ung | Roughness SL - Slickensided POL - Polished |              |

AD/T - Auger drilling TC bit
AD/V - Auger drilling V bit
WB - Washbore
HQ3- Wireline core (63.5 mm)
PQ3- Wireline core (85.0 mm)
SPT- Standard penetration test
PT - Push tube

 Complete Loss Graphic Log/Core Loss

✓ Partial Loss

Core recovered (hatching indicates material) No core recovery See Explanatory Notes for details of abbreviations and basis of descriptions

HW - Highly Weathered MW - Moderately Weathered SW - Slightly Weathered FR - Fresh

| Strength | VL - Very Low | L - Low | M - Medium | H - High | VH - Very High | EH - Extremely High |

FT - Fault
SS - Shear Surface
SZ - Shear Zone
BP - Bedding parting
SM - Seam
IS - Infilled Seam
JT - Joint
CO - Contact
CZ - Crushed Zone
VN - Vein
FZ - Fracture Zone
ESH - Bedding Shear
DB - Dnilling Break CN - Clean
SN - Stain
VN - Veneer
CO - Coating
RF - Rock fragments
G - Gravel
S - Sand
Z - Silt
CA - Calcite
CL - Clay
FE - Iron
QZ - Quartz
X - Carbonaceous SL - Slickensided
S - Smooth
RF - Rough
VR - Very Rough
Shape
PR - Planar
CU - Curved
UN - Undulating
ST - Stepped
IR - Irregular





**Goodman Limited** 

1 - 3 Burrows Road, St Peters Geotechnical Investigation BOREHOLES CORE PHOTO BH02 From 13.2 m to 15.18 m

PSM2808-005R

Appendix C



**BH03** 

Page 1 of 4

# **Engineering Log - Non Cored Borehole**

Client: Goodman Group Commenced: 24/04/2019 Project Name: **Burrows Road** Completed: 24/04/2019 Hole Location: 1-3 Burrows Rd St Peters JsR

Project No.:

PSM2808

Logged By: Hole Position: 331679.9 m E 6245385.0 m N Checked By: AS

| - 1  | Drill Model and Mounting: Track Mounted Hole Diameter: 100 mm  |   |                                 |              |     |           | ounted       | I           |                          | Inclination: -90° RL Surface: 3.50 m  Bearing: Datum: AHD Operator: Rockwell   |  |  |  |  |
|--|--|---|---------------------------------|--------------|-----|-----------|--------------|-------------|--------------------------|--|--|--|--|--|
|  |  | ı | Drilli                          | ing Informat | ion |           |              |             |                          | Soil Description Observations  |  |  |  |  |
| Method   | Method Penetration Support Water Water Support Water Water Water Symbol Classification Symbol  |   |                                 |              |     | RL<br>(m) | Depth<br>(m) | Graphic Log | Classification<br>Symbol | Material Description SOIL NAME: Colour, structure, plasticity, additional  Material Description SOIL NAME: Colour, structure, plasticity, additional  Material Description  USUBLE PROPRIED AND PROPRIED |  |  |  |  |
| Id   |  | Z |                                 |              |     | 2.5       | 1            |             |                          | Concrete: 250 mm thick.  Sandy GRAVEL: to 30 mm, sub-angular, black; sand fine to medium grained; some metal, ceramics observed.  M L to F  Silty SAND: fine to medium grained, grey.  |  |  |  |  |
| 0.0.000 Datgel Fence and Map Tool   Lib: PSM 3.02.1.2019-03-06 Prj: PSM 3.02.1.2019-03-06 AD/V   |  | Z | Observed at 2.87 m in standpipe |              |     | 0.5 1.5   | 2            |             |                          | Some clay with medium plasticity at 3.0m   |  |  |  |  |
| PSM 3.02.1.LIB.GLB Log PSM AU NONCORE BH NZ AU PSM2808.GPJ < <drawingflie>&gt; 10/05/2019 16:52 10.0.000 Da<br/><u>U</u></drawingflie> |  |   |                                 |              |     | -0.5      | 4            |             | SW-SM                    | Silty SAND with clay: fine to medium grained, grey; clay low plasticity.  W D to VD  |  |  |  |  |
| :1 LIB.GLB Log PSM AU NONCORE BH   | Method  AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger Screwing  Mo resistance through to refusal refusal  ✓ Parti ✓ Com |   |                                 |              |     |           |              | •           | > Inflo<br>✓ Par         | D. Digturbod Comple M. Moiet S Soff  |  |  |  |  |



**BH03** 

Page 2 of 4

# **Engineering Log - Non Cored Borehole**

Client: Goodman Group Commenced: 24/04/2019 Project Name: **Burrows Road** Completed: 24/04/2019

Project No.:

PSM2808

1-3 Burrows Rd St Peters Hole Location: Logged By: JsR Hole Position: 331679.9 m E 6245385.0 m N Checked By: AS

| Drill M<br>Hole [         |                         |   | _  |          | ick Mo    | ounted                                | d           |                          | Inclination: -90°<br>Bearing:  | RL Surfa<br>Datum:                                   | ce:                   | 3.t<br>Al-                        | 50 m<br>HD Ope                       | erator: Rockwell  |
|---------------------------|-------------------------|---|--|----------|-----------|---------------------------------------|-------------|--------------------------|--|--|-----------------------|-----------------------------------|--------------------------------------|---|
|                           |                         | Drill   | ing Informati                              | ion      |           |                                       |             | Soil Description Obse    |  |  |                       |                                   |                                      |   |
| Method<br>Penetration     | Support                 | Water   | Samples<br>Tests<br>Remarks                | Recovery | RL<br>(m) | Depth<br>(m)                          | Graphic Log | Classification<br>Symbol | Material Descriptio<br>SOIL NAME: Colour, str<br>plasticity, additiona   | ucture,  | Moisture<br>Condition | Consistency /<br>Relative Density | Hand<br>Penetrometer<br>UCS<br>(kPa) | Structure, Zoning, Origin,<br>Additional Observations   |
|                           |                         | .87 m in standpipe                            |  |          | -3.5      |                                       |             | SW-SM                    | Silty SAND with clay: fine to med grey; clay low plasticity. (continu  | ed) ¯  | W                     | D to<br>VD                        |                                      |   |
| ADN                       |                         | Observed at 2.87                              |  |          | -5.5      | 8                                     |             | SM-SC                    | Silty SAND: fine to medium grain   |  | W                     | D to<br>VD                        |                                      |   |
| AD/T -<br>AD/V -<br>WB -W | vashi<br>tanda<br>ush t | er drill<br>er drill<br>oore<br>ard pe<br>ube | ing TC bit<br>ing V bit<br>enetration test | Pe       | throu     | -<br>-<br>isistance<br>ugh to<br>usal |             | >> Inflo<br><□ Par       | ater Samples.  DW U - Undisturbe D - Disturbed S SPT - Standard P mplete Loss ES - Environme.  TW - Thin Walled LB - Large Distu | d Sample<br>Sample<br>enetration Test<br>ntal Sample | M                     | D<br>M                            | rre Condition - Dry - Moist / - Wet  | Consistency/Relative Density  VS - Very soft S - Soft F - Firm St - Stiff VSt - Very stiff H - Hard VL - Very loose |

Soil and rock descriptions in accordance with AS 1726:2017

MD - Medium dense
D - Dense
VD - Very dense
Ce - Cemented
C - Compact



**BH03** 

Page 3 of 4

#### **Engineering Log - Non Cored Borehole**

Client: 24/04/2019 Goodman Group Commenced: 24/04/2019 Project Name: **Burrows Road** Completed:

Hole Location: 1-3 Burrows Rd St Peters Logged By: JsR Hole Position: 331679.9 m E 6245385.0 m N Checked By: AS

Drill Model and Mounting: RL Surface: Track Mounted Inclination: -90° 3.50 m

Hole Diameter: 100 mm Bearing: Datum: AHD Operator: Rockwell

Project No.:

PSM2808

|        | Hole Diameter: 100 mm |         |                       |                             |          |           |              |             | Bearing: Datum: AHD (    |  |                       |                                   |                                      | Operator: Rockwell   |  |  |
|--------|-----------------------|---------|-----------------------|-----------------------------|----------|-----------|--------------|-------------|--------------------------|--|-----------------------|-----------------------------------|--------------------------------------|--|--|--|
|        |                       | ı       | Drilli                | ing Informatio              | on       |           |              |             |                          | Soil Description   |                       |                                   |                                      | Observations   |  |  |
| Method | Penetration           | Support | Water                 | Samples<br>Tests<br>Remarks | Recovery | RL<br>(m) | Depth<br>(m) | Graphic Log | Classification<br>Symbol | Material Description<br>SOIL NAME: Colour, structure,<br>plasticity, additional      | Moisture<br>Condition | Consistency /<br>Relative Density | Hand<br>Penetrometer<br>UCS<br>(kPa) | Structure, Zoning, Origin,<br>Additional Observations      |  |  |
| AD/V   |                       | Z       | : 2.87 m in standpipe |                             |          | <br>-7.5  | 11-          |             | СН                       | CLAY: high plasticity, pale grey-brown. (continued)  Becomes pale grey-brown and red | M                     | VSt<br>to H                       |                                      |  |  |  |
| A      |                       |         | Observed at 2.87      |                             |          | 5         | -<br>-<br>-  |             |                          |  |                       |                                   |                                      | 11.50: V-bit refusal.  11.90: Cleaning by washing borehole |  |  |
|        |                       |         |                       |                             |          | -9.5      | -            |             |                          | Continued on cored borehole sheet  |                       |                                   |                                      |  |  |  |
|        |                       |         |                       |                             |          | -10.5     | 14 —         |             |                          |  |                       |                                   |                                      |  |  |  |
|        |                       | etho    | d                     |                             | Pe       | netrat    | -<br>-       |             | w                        | ater Samples and Tests   |                       | Moistu                            | re Condition                         | Consistency/Relative Dens                                  |  |  |

AD/T - Auger drilling TC bit AD/V - Auger drilling V bit WB - Washbore SPT - Standard penetration test PT - Push tube AS - Auger Screwing

See Explanatory Notes for details of abbreviations and basis of descriptions.

through to refusal

Partial Loss Complete Loss U - Undisturbed Sample
D - Disturbed Sample
SPT - Standard Penetration Test
ES - Environmental Sample
TW - Thin Walled
LB - Large Disturbed Sample

S F St VSt H VL

- Very soft
- Soft
- Soft
- Soft
- Firm
- Stiff
- Very stiff
- Hard
- Very loose
- Loose
- Medium dense
- Dense
- Very dense
- Cemented
- Compact MD D VD Ce C

Soil and rock descriptions in accordance with AS 1726:2017



PSM2808

Project No.:

Project Name:

Client:

**BH03** Page 4 of 4

**Engineering Log - Cored Borehole** 

Goodman Group Commenced: 24/04/2019 **Burrows Road** Completed: 24/04/2019

Hole Location: 1-3 Burrows Rd St Peters Logged By: JsR

|        |                                       | Posi   | ition:<br>tion:   |   |                      |              |                  | eters<br>385.0 m N  | Logged I<br>Checked   | -   | JsR<br>AS  |   |  |
|--------|---------------------------------------|--|---|---|----------------------|--------------|------------------|---|---|---|--|---|--|
|        |                                       |  | el and M  |   | 0                    |              | Moun<br>3 m      | ted Inclination: -90°<br>Bearing:   | RL Surfa<br>Datum:  | ace: 3.50<br>AHD  |  | rator: Rockwell   |  |
|        |                                       | Drill  | ing Info  | ormat                                     | ion                  |              |                  | Rock Substance  | Rock Substance  |   |  |   |  |
| Method | Water                                 | RQD (%)  | SAMPLES &<br>FIELD TESTS  | WPT (Lugeons)                             | RL<br>(m)            | Depth<br>(m) | Graphic Log      | Material Description ROCK TYPE: Colour, grain size, structure (texture, fabric, mineral composition, hardness, alteration, cementation, etc as applicable), inclusions and minor components | Weathering  | O - Diametral   | Defect<br>Spacing<br>(mm)  | Defect Descriptions / Comment<br>Description, alpha/beta, infilling<br>or coating, shape, roughness,<br>thickness, other  |  |
| NMLC   | Observed at 2.87 m in standpipe       | 26   | 12.95m<br>1 is(50)<br>d=0.1 a=0.1<br>MPa<br>13.96m<br>2 is(50)<br>d=0.3<br>a=0.3<br>MPa<br>Is(50)<br>d=0.1<br>14.94m<br>MPa |   | -10.5 -9.5 -8.5 -7.5 |              |                  | Continued from non-cored borehole sheet SHALE: dark grey, thinly laminated, well developed bedding.  Hole Terminated at 15.00 m. Target depth. Standpipe installed                          |   |   |  | -IS, 0°, CL, PR, RF, 80 mm -IS, 0°, CL, PR, RF, 10 mm  -BP, 0°, CN, PR, RF -IS, 0°, CL, PR, RF, 50 mm -BP, 0°, FE SN, PR, RF -CZ, RF, PR, RF, 60 mm  -JT, 60°, RF, PR, RF |  |
|        | AD/\<br>WB<br>HQ3<br>PQ3<br>SPT<br>PT | F - Aug<br>- Aug<br>- Wa<br>- Win<br>- Star<br>- Pus | ethod ler drilling Ter drilling Vehicles shore eline core ( eline core ( ndard pene h tube                                  | / bit<br>63.5 mr<br>85.0 mr<br>etration t | n)<br>test           | Grap         | Core re indicate | XW - Extremely Weathered  | FT - Fau<br>SS - Shin<br>SZ - Shin<br>BP - Bee<br>SM - Sei<br>IS - Infi<br>JT - Joi<br>CO - Co<br>CZ - Cru<br>VN - Vei<br>FZ - Fra<br>BSH - Bee | ear Surface ear Zone dding parting am lled Seam nt ntact ushed Zone | Infilling/Coa CN - Clean SN - Clean SN - Stain VN - Veneer CO - Coating RF - Rock fr G - Gravel S - Sand Z - Silt CA - Calcite CL - Clay FE - Iron QZ - Quartz X - Carbon. | SL - Slickensided POL - Polished S - Smooth RF - Rough yagments VR - Very Rough Shape PR - Planar CU - Curved UN - Undulating ST - Stepped IR - Irregular                 |  |





**Goodman Limited** 

1 - 3 Burrows Road, St Peters Geotechnical Investigation BOREHOLES CORE PHOTO BH03 From 12.0 m to 15.0 m

PSM2808-005R

Appendix C

# **Appendix D Point Load Index Tests**





# **Pells Sullivan Meynink**

# POINT LOAD STRENGTH INDEX TEST RESULTS

|   | DOMASAA  |  |  | <u> </u>   |   |   |   |  |  |   |  |   |  | Obset  | _  | - £                                  |                          |
|---|--|--|--|--|---|---|---|--|--|---|--|---|--|--|--|--------------------------------------|--------------------------|
| Job No.   | PSM1541  |  |  |  |   |   |   |  |  |   |  |   |  | Sheet  | 1  | of                                   | 1                        |
| Project   | 1-3 Burrows Rd - S   | t Peters   |  |  |   |   |   |  |  |   |  |   |  |  |  |                                      |                          |
| Test Method  Test Machine Calibration Date                              | Purposes, Determinat<br>GSA 6500                                     |  |  | Festing Rocks for Engineering  Load Strength Index  Sampling Technique  NLMC  Storage History  North Ryde office indoor core storage area  Moisture Condition  Natural  Loading Rate  < 30 seconds |   |   |   |  |  | Sampling Date 23-24/04/2 Testing Date 04/2019 Tested By JsR |  |   | 19   |  |  |                                      |                          |
|   |  | Donth  |  |  | Dia   | ametral 1                                 | ests  |  |  | Axial, E  | Block, a   | and Irre                                    | gular Lu   | mp Tests   |  |                                      | AS 1726                  |
| Rock  | Type Location  | Depth (m)  | D<br>(mm)                                    | L<br>(mm)  | P<br>(kN)   | I <sub>s(50)</sub><br>(MPa)               | Failure Mode  | W<br>(mm)  | D<br>(mm)  | L<br>(mm)   | P<br>(kN)  | I <sub>s</sub><br>(MPa)                     | I <sub>s(50)</sub><br>(MPa)                        | Fail   | ıre M  | ode                                  | Strength Class           |
| Shale | BH01<br>BH01<br>BH01<br>BH01<br>BH02<br>BH02<br>BH03<br>BH03<br>BH03 | 11.05<br>11.95<br>13.05<br>13.95<br>14.90<br>14.35<br>15.05<br>12.95<br>13.96<br>14.94 | 50<br>50<br>50<br>50<br>50<br>50<br>50<br>50 | 62<br>100<br>101<br>96<br>82<br>121<br>76<br>70<br>74  | 0<br>0.1<br>0.5<br>0.2<br>0.1<br>0.2<br>0.2<br>0.8<br>0.4 | 0<br>0.2<br>0.1<br>0<br>0.1<br>0.3<br>0.1 | Parallel to bedding | 50<br>50<br>50<br>50<br>50<br>50<br>50<br>50<br>50 | 44<br>46<br>48<br>43<br>45<br>50<br>50<br>42<br>40<br>46 |   | 1<br>0.9<br>1<br>1.2<br>0.2<br>0.3<br>0.8<br>0.4 | 0.3<br>0.4<br>0.4<br>0<br>0.1<br>0.3<br>0.2 | 0.3<br>0.4<br>0.4<br>0<br>0.1<br>0.1<br>0.3<br>0.2 | Through Through Bad brea Bad brea Through Through Through Through Bad brea | subst<br>ak<br>subst<br>subst<br>subst<br>subst<br>subst | ance<br>ance<br>ance<br>ance<br>ance | VL/M L VL/M M VL VL VL L |
| Ву:   | JsR  |  | Check  | æd:  |   |   |   |  |  |   |  |   |  | Date:  |  | 1/5/20                               | )19                      |

# **Appendix E Piezometer Construction Records**





JOB no.: PSM2808

PROJECT: Burrows Road

### PIEZOMETER CONSTRUCTION RECORD

HOLE NUMBER: BH01 DRILLING CONTRACTOR: Rockwell Drilling

PIEZOMETER:

COLLAR EASTING:

COLLAR NORTHING:

DRILLING RIG: Hanjin
331557 DEPTH OF HOLE (m): 15 m
6245383 BOREHOLE INCLINATION: Vertical

COLLAR RL(m): 2.1
DATUM: MGA 56

SUPERVISED BY: JsR

PIEZO INSTALLATION DATE: 23/04/2019

#### Tick boxes

#### Complete dimensions if appropriate

| Steel protective  well cover   |                    | ↑ Height of stickup (m)     |       |
|--|--------------------|-----------------------------|-------|
| PVC cap X  |                    |                             |       |
| Concrete Colar   |                    | Diameter of PVC (mm)        | 50    |
| Back Fill type Cement bentonite Soil None X                          |                    |                             |       |
| Seal   |                    | Depth to top of seal        | 0.3 m |
| Bentonite Pellets Other  Gravel type: 2-5mm grave Gravel type: Other | el                 | Depth to top of gravel pack | 1.5 m |
| 2-5 mm gravel X Other  |                    | Depth to top of screen      | 6 m   |
| Perforation type: Drill holes Hack saw cuts                          | Monitored interval |                             | 40    |
| 40um machine slots L   | Monitored          | Depth to base of screen     | 12 m  |
|  |                    | Depth to base of piezo      | 15 m  |
|  |                    | Depth to base of gravel     | 15 m  |

| COMMENTS: | Gatic cover were used for the protection |  |
|-----------|--|--|
|           |  |  |
|           |  |  |
|           |  |  |
|           |  |  |
|           |  |  |



331729

JOB no.: PSM2808

PROJECT: Burrows Road

### PIEZOMETER CONSTRUCTION RECORD

HOLE NUMBER: BH02 DRILLING CONTRACTOR: Rockwell Drilling

PIEZOMETER: COLLAR EASTING: DRILLING RIG: Hanjin
DEPTH OF HOLE (m): 15 m
BOREHOLE INCLINATION: Vertical

COLLAR NORTHING: 6245470 COLLAR RL(m): 2.3

PIEZO INSTALLATION DATE: 24/04/2019

DATUM: MGA 56

SUPERVISED BY: JsR

#### Tick boxes

#### Complete dimensions if appropriate

|  | ^                  | Height of stickup (m)       |       |
|--|--------------------|-----------------------------|-------|
| Steel protective well cover  X               |                    |                             |       |
| PVC cap                                      |                    |                             |       |
| Concrete Colar                               |                    | Diameter of PVC (mm)        | 50    |
| Back Fill type Cement bentonite Soil None    |                    |                             |       |
| Cool   |                    | Depth to top of seal        | 0.3 m |
| Seal  Bentonite Pellets  Other  Gravel type: |                    |                             | 4.5   |
| Gravel type: 2-5mm grave Other               |                    | Depth to top of gravel pack | 1.5 m |
| 2-5 mm gravel X Other                        |                    | Depth to top of screen      | 6 m   |
| Perforation type: Drill holes Hack saw cuts  | Monitored interval |                             |       |
| 40um machine slots                           | mitored            | Depth to base of screen     | 12 m  |
|  | W                  | Depth to base of piezo      | 15 m  |
|  |                    | Depth to base of gravel     | 15 m  |

| COMMENTS: | Gatic cover were used for the protection |
|-----------|--|
|           |  |
|           |  |
|           |  |
|           |  |
|           |  |



JOB no.: PSM2808

PROJECT: Burrows Road

### PIEZOMETER CONSTRUCTION RECORD

HOLE NUMBER: BH03 DRILLING CONTRACTOR: Rockwell Drilling

PIEZOMETER:

COLLAR RL(m):

COLLAR EASTING:

COLLAR NORTHING:

DRILLING RIG: Hanjin
331680 DEPTH OF HOLE (m): 15 m
6245385 BOREHOLE INCLINATION: Vertical
3.5 PIEZO INSTALLATION DATE: 24/04/2019

DATUM: MGA 56 SUPERVISED BY: JsR

#### Tick boxes

#### Complete dimensions if appropriate

|  | <u> </u>                              | Height of stickup (m)        |      |
|--|---------------------------------------|------------------------------|------|
| Steel protective well cover                      |                                       |                              |      |
| PVC cap X  |                                       |                              |      |
| Concrete Colar                                   |                                       | Diameter of PVC (mm)         | 50   |
| Back Fill type Cement bentonite Soil None        |                                       |                              |      |
| Seal   |                                       | Depth to top of seal         | 5 m  |
| Bentonite Pellets Other  Gravel type:            |                                       | Double to top of wood on the | 7 m  |
| Gravel type: 2-5mm gravel Other                  |                                       | Depth to top of gravel pack  |      |
| 2-5 mm gravel X Other                            |                                       | Depth to top of screen       | 9 m  |
| Perforation type:  Drill holes  Hack saw cuts  X | Internal Interval  Monitored interval |                              |      |
| 40um machine slots                               | intored in                            | Depth to base of screen      | 15 m |
|  | Mon                                   | Depth to base of piezo       | 15 m |
|  |                                       | Depth to base of gravel      | 15 m |

| COMMENTS: | Gatic cover were used for the protection |  |
|-----------|--|--|
|           |  |  |
|           |  |  |
|           |  |  |
|           |  |  |
|           |  |  |

# Appendix F Bulk Earthworks Specification



# **Bulk Earthworks Specification**

1 - 3 Burrows Road, St Peters

PSM2808-023S 25 September 2024

Goodman Property Services (Aust) Pty Ltd



# **Table of Contents**

| 1.        | Scope4                             |   |    |  |  |
|-----------|------------------------------------|---|----|--|--|
| 2.        | 2. Site Preparation Works          |   |    |  |  |
| 3.        | Filli                              | Filling Works   |    |  |  |
|           | 3.1                                | 4   |    |  |  |
|           |                                    | 3.1.1 Subgrade - Existing Fill                                      | 5  |  |  |
|           |                                    | 3.1.2 Subgrade - Existing Pavement                                  | 5  |  |  |
|           | 3.2 Base Geometry                  |   |    |  |  |
|           | 3.3                                | Material  | 5  |  |  |
|           |                                    | 3.3.1 Site Won Material   | 5  |  |  |
|           |                                    | 3.3.2 Imported Fill   | 5  |  |  |
|           |                                    | 3.3.3 All Fill  | 6  |  |  |
|           | 3.4                                | 3.4 Fill Zonation and Placement                                     |    |  |  |
|           | 3.5 Compaction                     |   |    |  |  |
|           | 3.6                                | Moisture Control  | 7  |  |  |
| 4.        | Cutt                               | Cutting   |    |  |  |
|           | 4.1 Subgrade Condition             |   |    |  |  |
| 5. Survey |                                    |   |    |  |  |
|           | 5.1                                | Filling Areas   | 8  |  |  |
|           | 5.2 Cutting Areas                  |   |    |  |  |
| 6.        | Insp                               | 8   |    |  |  |
|           | 6.1                                | 6.1 Role of the GITA  |    |  |  |
|           | 6.2                                | 6.2 Level 1 Control   |    |  |  |
|           | 6.3                                | 9   |    |  |  |
|           | 6.4                                | 9   |    |  |  |
|           | 6.5                                | 9   |    |  |  |
|           | 6.6 Inspection, Testing and Survey |   |    |  |  |
| 7.        | Reporting and Certification        |   |    |  |  |
|           | 7.1                                | 7.1 Reporting   |    |  |  |
|           | 7.2                                | Certification   | 11 |  |  |
|           |                                    | 7.2.1 Weekly Certificates   |    |  |  |
|           |                                    | 7.2.2 Interim or Final Filling Certificate                          | 11 |  |  |
|           |                                    |   |    |  |  |
| Li        | st c                               | of Tables   |    |  |  |
| Tal       | ble 1 -                            | Requirements for Layer Thickness, Compaction and Moisture Variation | 7  |  |  |



# **List of Appendices**

Appendix A Site Locality Plan

Appendix B Subgrade Approval Report (Sample only)

Appendix C Lot Approval Report (Sample only)

Appendix D Daily Report (Sample only)

Appendix E Certification Letter (Sample only)



#### 1. Scope

This specification details the requirements for bulk earthworks to be undertaken for the proposed industrial warehouse development at 1-3 Burrows Road, St Peters. The area where this specification is applicable is shown in Appendix A. This includes areas where material is filled or cut to bulk earthworks level (BEL) within the extent of earthworks shown in Appendix A.

Fill placed in accordance with this specification is denoted as Engineered Fill.

This specification does not address any environmental, contamination or erosion issues or additional regulatory/approval requirements (e.g. Council Consent Conditions) associated with the earthworks.

There is a **HOLD POINT** on placing fill in Section 3.4 of this Specification.

# 2. Site Preparation Works

The following tasks shall be undertaken as part of the Site Preparation Works:

- 1. To prepare the site for the earthworks:
  - a. Removal of stockpiles and mounds
  - b. Clearing of the area including removal and disposal of all trees, stumps, roots, bush, other organic material, all vegetation both living and dead, all minor man-made structures (e.g. fences) and all rubbish
  - c. All trees and stumps, on or within the limits of clearing, unable to be removed by the clearing methods used by the Contractor shall be removed by grubbing
  - d. Stripping of topsoil
  - e. Demolition of structures as directed by the Principal. Extent of demolition works are not addressed by this Specification
  - f. Decommissioning the services from the pre-existing infrastructure. This is to include backfilling any voids such that they do not collapse or undergo excessive settlement under the weight of the filling and building loads. Backfilling is to be undertaken with one of the following materials:
    - i. Cement stabilised sand (min. 3% cement) placed in accordance with the supplier requirements or
    - ii. Mass concrete or grout as approved by PSM.
    - iii. Engineered fill placed in accordance with Clauses 3.5 and 3.6 of the Specification.

Where any excavation is required to complete the above tasks, the surface exposed at completion of the excavation shall be treated in accordance with the Subgrade Preparation requirements in Clause 3.1.

# 3. Filling Works

#### 3.1 Subgrade Preparation

The condition of the subgrade should be assessed immediately prior to filling commencing.

All Engineered Fill is to be placed on one of the following four (4) materials:

- 1. Bedrock.
- 2. Natural insitu material of at least stiff consistency.
- Engineered compacted fill placed in accordance with this or other approved specifications for which the Geotechnical Inspection and Testing Authority (GITA) has a Level 1 certificate certifying compliance with that approved specification AND of at least stiff consistency.
- 4. Other materials as approved by PSM, e.g. existing fill, existing pavement intended to be left in place.

Proof rolling shall only be undertaken under the direction of PSM. PSM may also direct a bridging layer of Engineered Fill be placed and compacted to a Dry or Hilf Density Ratio (Standard Compaction) of between 95% and 102%. Any such layer shall be a Lot under Clause 5.3.



The GITA should satisfy itself that the subgrade has not been desiccated, affected by rain or disturbed. If the GITA cannot so satisfy itself, then the subgrade should be moisture conditioned and compacted to be in accordance with Clauses 2.5 and 2.6 of this specification.

Engineered Fill shall be placed only on subgrade approved by the GITA as being in accordance with this specification.

#### 3.1.1 Subgrade - Existing Fill

The existing fill within the site can be approved by PSM as subgrade for filling following heavy proof rolling using an 825 compactor (or approved alternative by PSM) under the supervision of PSM. Where excessive deflection under the proof roll is observed the fill will require remediation i.e. remove and replace with engineered fill.

Additional inspections and testing of the in-situ existing fill may be required as directed by PSM, including plate load testing. The contractor is to make a suitable reaction (e.g. 20 tonne excavator) available for the plate load testing.

#### 3.1.2 Subgrade - Existing Pavement

Existing pavement comprising asphalt, road base and concrete can be approved by PSM as subgrade for filling if it satisfies all of the following requirements:

- 1. The pavement is located at least 1 m below the bulk earthworks levels (BELs).
- 2. The pavement has been proof-rolled using an 825 compactor (or approved alternative by PSM) under PSM supervision.

Core holes will need to be drilled through concrete pavements that are to be left in place at the direction of PSM to investigate voids underneath the concrete prior to approval as subgrade for filling.

Where the existing pavements are located within 1 m of the BEL, or are not approved by PSM, then the pavement shall be removed. It can be crushed and re-used as Engineered Fill if it meets the requirements in Clause 3.5 and 3.6 of this Specification.

#### 3.2 Base Geometry

The slope of any buried batter shall be less than 1H:1V unless otherwise directed by PSM.

The contractor shall remove or flatten any geometrical obstructions (e.g. protrusions or holes) such that subsequent Engineered Fill can be placed to achieve the requirements of this specification.

Engineered Fill shall be placed only on areas where the base geometry has been approved by the GITA.

#### 3.3 Material

#### 3.3.1 Site Won Material

Site Won Material is to meet the requirements of All Fill in Section 3.3.5 of this Specification. Site Won Material comprises either natural material or existing fill won from cut areas of excavations on site.

#### 3.3.2 Imported Fill

Imported Engineered Fill is to conform to the following definitions:

- 1. "Virgin excavated natural material" (**VENM**) as defined by the Protection of the Environment Operations Act 1997 No 156, Schedule 1, on Page 209: "Virgin excavated natural material (eg clay, gravel, sand, soil and rock) that is not mixed with any other waste and that:
  - a) Has been excavated from areas that are not contaminated, as a result of industrial, commercial, mining or agricultural activities, with manufactured chemicals and that does not contain sulphide ores or soils, or
  - b) Consists of excavated natural materials that meet such criteria as may be approved by the EPA".
- 2. "Excavated natural material" (ENM) as defined under Clause 93 of the Protection of the Environment Operations (Waste) Regulation 2014:

"Excavated natural material is naturally occurring rock and soil (including but not limited to materials such as sandstone, shale, clay and soil) that has:



- a) Been excavated from the ground, and
- b) Contains at least 98% (by weight) natural material, and
- Does not meet the definition of Virgin Excavated Natural Material in the Act.

Excavated Natural Material does not include material that has been located in a hotspot; that has been processed; or that contains asbestos, Acid Sulphate Soils (ASS), Potential Acid Sulphate soils (PASS) or sulfidic ores."

#### 3.3.3 All Fill

The Engineered Fill shall be approved by the GITA as suitable for use in a structural fill.

Engineered Fill shall not comprise unsuitable material that includes:

- Organic soils, such as many topsoils, severely root-affected subsoils and peat;
- Silts, or materials that have the deleterious engineering properties of silt;
- Other materials with properties that are unsuitable for the forming of structural fill; unless it is approved by PSM.

The GITA shall assess that the proportion of deleterious material in each Lot is not greater than 0.5% by weight. Deleterious material is defined by Table 3015.6 of the RMS QA Specification 3051 (Edition 7 June 2020) as:

Rubber, Plastic, Bitumen, Paper, Cloth, Paint, Wood and Other Vegetable Matter

If the GITA is not able to visually assess the above criterion, the GITA shall arrange appropriate testing.

All Engineered Fill particles shall be able to be incorporated within a single layer. Further, less than 30% of particles shall be retained on the 37.5 mm sieve.

Engineered Fill shall be able to be tested in accordance with the Standard Compaction method (AS1289.5.4.1) or Hilf test method (AS1289.5.7.1). These methods require less than 20% retained on the 37.5 mm sieve. Where between 20% and 30% of particles are retained on the 37.5 mm sieve the above test methods shall still be adopted and test reports annotated appropriately.

These requirements should be met by the material after placement and compaction.

Only material approved by the GITA shall be placed as Engineered Fill.

#### 3.4 Fill Zonation and Placement

#### **HOLD POINT**

| Process held          | Placing of fill   |
|-----------------------|---|
| Submission detail     | The Contractor / GITA submit to PSM a Weekly Certificate as defined in Clause 7.2.1 of this specification for the earthworks completed to the previous Saturday no later than 5 pm of the subsequent Wednesday.   |
| Release of Hold Point | PSM to confirm receipt of Weekly Certificate and recommend release of Hold Point if initial assessment of the Weekly Certificate indicates it complies with requirements of this specification. The contract superintendent should then release the Hold Point if it considers appropriate. |

Engineered Fill shall be placed in accordance with the following requirements:

- 1. In near horizontal, laterally extensive layers of uniform material and thickness, deposited systematically across the work area as determined by the GITA.
- 2. The compacted thickness of each layer shall be as per Table 1.

Engineered Fill shall only be placed on subgrade in accordance with this specification and approved by the GITA.



#### 3.5 Compaction

Engineered Fill shall be placed and compacted to a Dry or Hilf Density Ratios (Standard Compaction) of between 98% and 102%.

The insitu density shall be measured over the full depth of each layer placed.

#### 3.6 Moisture Control

The placement moisture variation or Hilf moisture variation shall be in accordance with Table 1 requirements.

Placement moisture content of the Engineered Fill shall be measured.

Table 1 - Requirements for Layer Thickness, Compaction and Moisture Variation

| Fill Type                             | Compacted Layer<br>Thickness (mm) | AS1289.5.1.1 and<br>AS1289.5.4.1 or<br>AS1289.5.7.1 | Moisture Variation  AS1289.5.1.1 and AS1289.5.4.1 or AS1289.5.7.1 |
|---------------------------------------|-----------------------------------|---|---|
| Site Won Material or<br>Imported Fill | 300                               | Between 98% and 102%                                | Between 2% Dry and 2%<br>Wet Std Comp                             |

#### Note:

- A single pass is defined as a forward and backwards in the same track.
- A Cat825 shall be used or other plant approved by PSM.
- <sup>3</sup> Compaction trials shall be undertaken onsite to confirm optimum number of passes:
  - a. In situ wet density measured after 4, 6, 8, 10 passes of Cat825.
  - b. Lab compactions to assess SMDD and OMC once 10 passes are completed.
  - c. GITA shall undertake a test roll with a 12 tonne smooth roller or PSM approved equivalent to confirm that no significant deformation/springing occurs.
  - d. Results shall be submitted to PSM for review and assessment.
- Each lot placed shall be tested as follows:
  - In situ wet density and moisture content measured at frequency as specified in Cl. 6.4 after nominated number of passes using the Nuclear Densometer.
  - b. 1 laboratory moisture content test shall be undertaken per lot using a small sample and strict protocols.
  - c. GITA shall undertake a test roll with a 12 tonne smooth drum roller or PSM approved equivalent on each completed Lot to confirm that no significant deformation/springing occurs and record this on the Lot Approval report. Should significant deformation/springing occur the layer may need additional compaction or moisture conditioning (typically drying).
  - d. Results reported as part of the Lot Approval Report and submitted to PSM.
  - e. GITA shall confirm in Lot Approval Report that minimum number of passes have been undertaken, confirm test roll indicates no significant deformation/springing, and report the in situ wet density test results.

# 4. Cutting

#### 4.1 Subgrade Condition

The subgrade is to comprise one of the following materials:

- 1. Bedrock.
- 2. Natural insitu material of at least stiff consistency.
- 3. Other materials as approved by PSM, e.g. existing fill intended to be left in place.

Proof rolling shall only be undertaken under the direction of PSM.

In areas of cut, any existing fill should be removed to a depth such that a minimum 1 m of engineered fill is to be placed on top of the existing fill to achieve the BEL.

The GITA should satisfy itself that the subgrade has not been desiccated, affected by rain or disturbed. If the GITA cannot so satisfy itself, then the subgrade should be excavated and filled to the BEL in accordance with this specification.



#### 5. Survey

#### 5.1 Filling Areas

The survey requirements are as follows:

- 1. Any approved subgrade shall be surveyed prior to first filling such that subgrade levels are established to within ± 0.1 m. The area subject to approval shall be assessed and shown on a plan drawing to an accuracy of at least +/- 5 m in plan.
- 2. The Lot boundaries shall be assessed and shown on a plan drawing to an accuracy of at least +/- 5 m in plan.
- 3. The location of the field density tests shall be assessed and shown on the Lot boundary plan drawing to an accuracy of at least +/-5 m in plan.
- 4. The elevation of the field density tests shall be surveyed to an accuracy of +/-0.05 m.

The plan drawing shall show at the boundaries of the site and other identifiable site features, so as to allow the location of the lots and the test to be recoverable.

#### **5.2** Cutting Areas

Any approved subgrade for cut areas shall be surveyed such that subgrade levels are established to within ± 0.1 m.

#### 6. Inspection and testing

#### 6.1 Role of the GITA

A NATA accredited Geotechnical Inspection and Testing Authority (GITA) shall be contracted to document and certify that the works undertaken by the contractor has been completed in accordance with the relevant design and specifications.

#### 6.2 Level 1 Control

The GITA shall adopt Level 1 responsibility as described in Section 8.2 of AS 3798-2007 "Guidelines on earthworks for commercial and residential developments":

"The primary objective of Level 1 Inspection and Testing is for the geotechnical inspection and testing authority (GITA) to be able to express an opinion on the compliance of the work. The GITA is responsible for ensuring that the inspection and testing are sufficient for this purpose.

The geotechnical inspection and testing authority needs to have competent personnel on site at all times while earthwork operations are undertaken. Such operations include:

- Completion of removal of top soil
- Placing of imported or cut material
- Compaction and adding/removal of moisture
- Trenching and backfilling
- Test rolling
- Testing

The superintendent should agree a suitable inspection and testing plan prior to commencement of the works.

"On completion of the earthworks, the GITA will usually be required to provide a report setting out the inspections, sampling and testing it has carried out, and the locations and results thereof. Unless very unusual conditions apply, the GITA should also be able to express an opinion that the works (as far as it has been able to determine) comply with the requirements of the specification and drawings."

For this particular contract, Level 1 responsibility includes:

- 1. Lot testing as per Clause 6.3 of this specification.
- 2. A frequency of compaction testing not less than that specified in Clause 6.4 of this specification.
- 3. The GITA documenting and reporting its activity in the terms required by Clause 7 of this specification.



4. The GITA undertaking adequate inspections and testing to comply with the above requirements and to be able to certify the fill in the terms required by Clause 7 of this specification.

#### 6.3 Lot Testing

This specification requires lot testing to be undertaken.

A Lot is defined as a single layer of Engineered Fill consisting of uniform material which has undergone similar treatment (both moisture conditioning and compaction) and that represents no more than one day's work.

Lot testing comprises the following:

- 1. A Lot shall be identified by the Contractor or the GITA with a Lot Number and presented for testing.
- 2. A Lot shall be deemed to be in accordance with the specification if all the tests undertaken within the Lot are in accordance with the specification, i.e. "a none to fail basis".
- If any one test undertaken within a Lot fails, the whole of the Lot shall be reworked and retested.

Any portion of the placed Engineered Fill must be part of a single lot and all Lots will require approval by the GITA.

#### 6.4 Testing Frequency (Compaction Testing)

The frequency of compaction testing for each lot shall not be less than the greater of:

- 1. 1 test per 500 m<sup>3</sup> of material placed.
- 2. 3 tests per lot.

A laboratory moisture content test shall be undertaken for each field density test.

Test locations shall be selected randomly by the GITA.

#### 6.5 Proof Rolling and Plate Load Testing

Proof rolling, together with minor boxing out and refilling, of the upper surface of the bulk earthworks will be undertaken as directed by PSM. The plant to be adopted depends upon the design loads adopted by the structural engineers for each section of the site.

Plate load testing shall be undertaken at the direction of PSM at final bulk earthworks level (BEL). Expected test frequency is approximately a day of testing for each building pad. The contractor is to make a suitable reaction (eg 20 tonne excavator) available for the tests.

#### 6.6 Inspection, Testing and Survey

The GITA shall at least undertake the following tasks:

#### Cut areas

- 1. Identify the subgrade as one of the three (3) subgrade types listed in Clause 4.1 of this specification and assess that the subgrade condition of cut areas is in accordance with the subgrade condition requirements of Clause 4.1 of this specification. Should the subgrade material comprise "Other materials as approved by PSM, eg. existing fill intended to be left in place.", PSM should be requested to inspect and provide approval.
- 2. Should Engineered Fill be required to fill overcut areas, assess that filling has been placed in accordance with this specification.

#### Fill areas

- 3. For fill areas, identify the subgrade as one of the four (4) subgrade types listed in Clause 3.1 of this specification and assess that the subgrade condition of any area prior to placement of fill material is in accordance with the subgrade preparation requirements of Clause 3.1 of this specification. Should the subgrade material comprise "Other materials as approved by PSM, eg. existing fill intended to be left in place.", PSM should be requested to inspect and provide approval prior to filling.
- 4. Assess that the base geometry of any area prior to placement of fill material is in accordance with the base geometry requirements of Clause 3.2 of this specification.



- 5. Assess that the material placed is in accordance with the fill material requirements of Clause 3.3 of this specification.
- 6. Assess that the Engineered Fill has been placed in accordance with the requirements for fill zonation and placement of Clause 3.4 of this specification.
- 7. Assess that each Lot as presented for approval by the contractor is in accordance with the requirements for Lot definition of Clause 6.3 of this specification.
- 8. Ensure that the survey requirements in Clause 5 of this specification have been completed.
- 9. Estimate the approximate volume of Engineered Fill placed in each Lot presented for approval.
- 10. Conduct Lot testing in accordance with the construction control testing requirements of Clauses 6.3 and 6.4 of this specification.
- 11. Assess that the compaction of each Lot is in accordance with the requirements of Clause 3.5 of this specification. The GITA shall select a depth of insitu density tests that allows the density of the full layer to be assessed.
- 12. Assess that the moisture variation of each Lot is in accordance with the requirements for moisture control in Clause 3.6 of this specification.
- 13. Conduct material property testing in accordance with the material testing requirements in this specification.

# 7. Reporting and Certification

#### 7.1 Reporting

The GITA shall produce at least the following reports:

- 1. Subgrade Approval Reports (a sample is attached). Such a report shall:
  - Document assessments undertaken for tasks 1 and 3 of Clause 6.6 including reporting the subgrade type.
  - o Document the subgrade survey that has been undertaken.
  - Approve or reject the subgrade condition and base geometry for filling, based on tasks 3 and 4 of Clause 6.6.
  - Approve or reject the subgrade condition for cut areas based on task 1.
- 2. Lot Approval Reports (a sample is attached). Such a report shall:
  - o Document assessments, testing and survey undertaken for tasks 3 to 13 of Clause 6.6.
  - o Report the results of testing undertaken for task 10 of Clause 6.6.
  - o Approve or reject lots based on tasks 11 and 12 of Clause 6.6.
- 3. Material Testing Reports. Such a report shall:
  - Report the results of material property testing undertaken for task 13 of Clause 6.6.
- 4. Daily Reports (a sample is attached). Such a report shall be completed daily and shall:
  - o Document time spent on site by the GITA personnel.
  - List subgrade assessments and approvals undertaken each day with reference to relevant Subgrade Approval Report(s).
  - List Lots presented, accepted and approved or rejected each day, with reference to relevant Lot Approval Report(s).
  - List survey undertaken each day as for task 8 of Clause 6.6 and not already documented in the Subgrade or Lot Approval Reports.
  - Document other relevant activities undertaken on site that day (site instructions, breakdowns, compaction equipment used, etc.)



#### 7.2 Certification

#### 7.2.1 Weekly Certificates

The GITA shall produce a Weekly Certificate for any week in which earthworks are undertaken in accordance with this specification. The Weekly Certificate will cover all works from the previous Weekly Certificate until the end of work on a Saturday.

The Weekly Certificate shall transmit the following:

- Copy or reference to the complete specification document(s)
- Subgrade Approval Reports
- Lot Approval Reports
- Material property testing reports
- Daily Reports
- Survey of subgrade geometry prior to filling or in cut areas
- Plan survey drawing showing lot boundaries and location of density tests
- Survey documenting filling undertaken to date and showing location of testing
- Provide an Excel spreadsheet presenting the results of the week's acceptance testing completed by the GITA.

#### And certify that:

"All the earthworks undertaken and the subgrade condition in the cut areas [in the stated period] are documented in the above reports and have been undertaken in accordance with the Specification (Ref. PSM4828-003S REV3)".

#### 7.2.2 Interim or Final Filling Certificate

At the completion of the bulk earthworks, or as requested by the Client, the GITA shall provide an Interim or Final Filling Certificate which shall:

- 1. Transmit a reference list of the Weekly Certificates.
- 2. Provide an Excel spreadsheet presenting the results of all the acceptance testing completed by the GITA.
- 3. Certify that "All the earthworks undertaken and the subgrade condition in the cut areas [in the stated period] are documented in the above reports and have been undertaken in accordance with the Specification (Ref. PSM2808-023S REVX)."



#### Brisbane

Level 6, 500 Queen Street GPO Box 3244 Brisbane QLD 4000 +61 7 3220 8300

#### **Sydney**

G3-56 Delhi Road North Ryde NSW 2113 +61 2 9812 5000


#### Perth

Level 3 22 Delhi Street West Perth WA 6005 +61 8 9462 8400



# Appendix A Site Locality Plan





These designs, plans & specifications and the copyright therein are the property of the Architect and must not be used, reproduced or copied wholly or in part without the written permission of this office.

Figured dimensions to be used in preference to scaling. All dimensions to be checked on site.

This document is not to be used for construction unless signed & issued for construction

NORTH



11/07/2024

23/07/2024

29/07/2024

REVISION REV DESCRIPTION DATE

1 ISSUED FOR INFORMATION 02/07/2024 Grid 18-20 revised

Fencing & Gates added ISSUE FOR REVIEW

ISSUE FOR REVIEW ISSUED FOR REVIEW

ARCHITECT



e info@sba.au w: www.sba.au CLIENT Goodmar



Multilevel Industrial Facility

1-3 Burrows Road, Alexandria

Site & Ground Floor Plan

SCALE 1:500 @ A1

PROJECT DRAWING 24132

**D**A200

Appendix B
Subgrade Approval Report (Sample only)



#### **GEOTECHNICAL INSPECTION AND TESTING AUTHORITY**

NATA accreditation number



#### SUBGRADE APPROVAL REPORT

| Client:     |                |                    |                      | Contractor:      |                         | The state of the s |                  |                      |  |
|-------------|----------------|--------------------|----------------------|------------------|-------------------------|--|------------------|----------------------|--|
| lob number: |                |                    |                      | Report number:   |                         |  |                  |                      |  |
| Project:    |                |                    |                      | Technician:      |                         | \  |                  |                      |  |
|             |                |                    |                      |                  |                         |  |                  |                      |  |
| Subgrade a  | reas assessed: | •                  |                      |                  |                         |  |                  |                      |  |
| Area ID     | Date           | Approximate extent | Subgrade description | Geometry summary | Specification reference | Compliance<br>(Pass/Fail)  | Survey reference | Approved<br>(Yes/No) |  |
|             |                | OMON               |                      |                  |                         | (r doon an)  | 1516151155       | (reente)             |  |
|             |                |                    |                      |                  |                         |  |                  |                      |  |
|             |                |                    |                      |                  |                         |  |                  |                      |  |
|             |                |                    |                      |                  |                         |  |                  |                      |  |
|             |                |                    |                      |                  |                         |  |                  |                      |  |
| COMMENT     | S:             |                    |                      |                  |                         |  |                  |                      |  |
| Signed:     |                |                    |                      | Date:            |                         |  |                  |                      |  |
|             |                |                    |                      |                  |                         |  |                  |                      |  |

# Appendix C Lot Approval Report (Sample only)





# **GEOTECHNICAL INSPECTION AND TESTING AUTHORITY**

NATA accreditation number

#### **LOT APPROVAL REPORT**

| Client:                                |                              |                               | Report number:          |                 |
|--|------------------------------|-------------------------------|-------------------------|-----------------|
| Job number:                            |                              |                               | Report date:            |                 |
| Project:                               |                              |                               | Technician:             |                 |
| Contractor:                            |                              |                               | Test methods:           |                 |
| LOT ID:                                |                              |                               | Sheet                   | of              |
| Retest (Yes/No)                        |                              |                               | Original test report no | umber:          |
| Specification reference                |                              |                               |                         |                 |
| Location:                              |                              |                               |                         |                 |
| Lot boundary survey reference/location | 1:                           |                               |                         |                 |
| Materials description:                 | (MATERIAL TYPE, colour, r    | minor components, maximum     | particle size)          |                 |
| Material identification:               |                              | ned in Clause 2.3.1, Clause 2 |                         | Specification ) |
| Deleterious material assessment:       | (Report proportion of delete | rious material)               |                         |                 |
| Layer thickness:                       |                              |                               |                         |                 |
| Accepted as Lot: (Yes/No)              |                              | -                             | Date:                   |                 |
| Approximate volume (m3)                |                              | <u>.</u>                      | Number of tests requ    | rired:          |
|  |                              |                               |                         |                 |
| Test ID No.                            |                              |                               | $M \sim 10^{-1}$        |                 |
| Test soil description                  |                              |                               | /                       |                 |
| Date tested:                           | Ko)\\                        |                               |                         |                 |
| Grid reference                         |                              |                               |                         |                 |
| Surveyed test locations (RL,E,N)       |                              |                               |                         |                 |
| Test depth (mm)                        |                              |                               |                         |                 |
| Max size (mm)                          |                              |                               |                         |                 |
| % Oversize material (wet)              |                              |                               |                         |                 |
| Field wet density (t/m³)               |                              |                               |                         |                 |
| Field moisture content (%)             |                              |                               |                         |                 |
| PWCD (t/m <sup>3</sup> )               |                              |                               |                         |                 |
| Compactive effort                      |                              |                               |                         |                 |
| Moisture variation (%)                 |                              |                               |                         |                 |
| HILF density ratio (%)                 |                              |                               |                         |                 |
| TEST (Pass/Fail)                       |                              |                               |                         |                 |
|  |                              |                               |                         |                 |
| LOT APPROVAL                           | (Pass/Fail)                  | Signed:                       | Date                    | e:              |

# Appendix D Daily Report (Sample only)





# **GEOTECHNICAL INSPECTION AND TESTING AUTHORITY**

**NATA** accreditation number

# **DAILY REPORT**

| Client: Job number: Project:                                    | Report number:<br>Report date:        |
|---|---------------------------------------|
| Location:<br>Contractor   | Level of testing: Level 1 Technician: |
| Time on site:<br>Time off site:                                 |                                       |
| 1. Subgrade Approval  |                                       |
| Areas ID Subgrade Approval Report No: Comments                  |                                       |
| 2. Lot Approval   |                                       |
| Lot ID Lot Approval Report No: Comments                         |                                       |
| 3. Survey   |                                       |
| Type of survey Survey undertaken by: Reference                  |                                       |
|   |                                       |
| 4. Instructions received on site                                |                                       |
| 4. Instructions received on site                                |                                       |
| 4. Instructions received on site  5. Instructions given on site |                                       |
|   |                                       |
|   |                                       |

# Appendix E Certification Letter (Sample only)



| Our Ref:   |
|--|
| Date:  |
| Addressed to: Earthwork Contractor   |
| Attention: Earthwork Contractor Representative   |
| Dear   |
| RE: SAMPLE INTERIM (OR FINAL) FILLING CERTIFICATE INDUSTRIAL DEVELOPMENT, BULK EARTHWORKS CERTIFICATION OF EARTHWORKS BETWEEN [DATE OF COMMENCEMENT] AND [DATE OF COMPLETION]  |
| In the period between [date start] and [date finish] the contractor has undertaken earthworks in areas $XXX$ and $XXX$ .   |
| During the above period:   |
| <ul> <li>The GITA has prepared the following Subgrade Approval Reports:</li> <li>1. Subgrade Approval Report No 1</li> <li>2</li> </ul>  |
| <ul> <li>The GITA has prepared the following Lot Approval Reports:</li> <li>1. Lot Approval Report No 1</li> <li>2</li> </ul>  |
| <ul> <li>The GITA has prepared the following Daily Reports:</li> <li>Daily Report No 1</li> <li>The following subgrade survey was undertaken:</li> </ul>   |
| 1 Subgrade Survey reference  |
| The following weekly survey was undertaken:  |
| <ol> <li>Weekly survey of week endingreference</li> <li></li> </ol>  |
| Copies of all the above documents are attached.  |
| The GITA certifies that all the earthworks undertaken in the above stated period are documented in the above reports and have been undertaken in accordance with the Specifications (ref. PSM2808-023S, dated XXX) a copy of which is attached, with the exception of: |
| 1. List outstanding issues (not approved subgrade, lots, unsuitable material, failed tests etc.)   |
| 2  |
| Signed   |
| GITA   |