


Appendix A

DRAWINGS BY COSTIN ROE CONSULTING

STATE SIGNIFICANT DEVELOPMENT APPLICATION
YIRIBANA LOGISTICS ESTATE
754-770 & 784-786 MAMRE ROAD, KEMPS CREEK, NSW, 2178

DRAWING LIST

DRAWING NO.	DRAWING TITLE
C013874.06-SSDA100	DRAWING LIST AND LOCALITY PLAN
C013874.06-SSDA110	GENERAL NOTES
C013874.06-SSDA200	EROSION AND SEDIMENT CONTROL PLAN - STAGE 1
C013874.06-SSDA201	EROSION AND SEDIMENT CONTROL PLAN - STAGE 2
C013874.06-SSDA250	EROSION AND SEDIMENT CONTROL DETAILS
C013874.06-SSDA300	BULK EARTHWORKS PLAN
C013874.06-SSDA310	CUT/FILL PLAN
C013874.06-SSDA350	BULK EARTHWORKS SECTIONS - SHEET 1
C013874.06-SSDA351	BULK EARTHWORKS SECTIONS - SHEET 2
C013874.06-SSDA400	STORMWATER DRAINAGE MASTER PLAN
C013874.06-SSDA401	PRE-DEVELOPMENT STORMWATER CATCHMENT PLAN
C013874.06-SSDA402	POST-DEVELOPMENT STORMWATER CATCHMENT PLAN
C013874.06-SSDA411	WAREHOUSE 1 - STORMWATER DRAINAGE PLAN
C013874.06-SSDA413	WAREHOUSE 3 - STORMWATER DRAINAGE PLAN
C013874.06-SSDA420	E2 CORRIDOR GENERAL ARRANGEMENT PLAN
C013874.06-SSDA421	E2 CORRIDOR CENTRELINE LONGSECTION
C013874.06-SSDA431	OSD BASIN 1 PLAN
C013874.06-SSDA432	OSD BASIN 2 PLAN
C013874.06-SSDA451	STORMWATER DRAINAGE DETAILS - SHEET 1
C013874.06-SSDA452	STORMWATER DRAINAGE DETAILS - SHEET 2
C013874.06-SSDA453	STORMWATER DRAINAGE DETAILS - SHEET 3
C013874.06-SSDA454	STORMWATER DRAINAGE DETAILS - SHEET 4
C013874.06-SSDA460	TYPICAL SECTIONS - SHEET 1
C013874.06-SSDA461	TYPICAL SECTIONS - SHEET 2
C013874.06-SSDA500	ROADWORKS MASTER PLAN
C013874.06-SSDA510	ROADWORKS TYPICAL SECTIONS & DETAILS
C013874.06-SSDA521	ROADWORKS LONG SECTIONS - SHEET 1
C013874.06-SSDA600	RETAINING WALL SETOUT PLAN
C013874.06-SSDA651	RETAINING WALL DETAILS



LOCALITY PLAN
NTS



FOR DEVELOPMENT APPLICATION

			ARCHITECT		CLIENT		PROJECT		CONSULTING ENGINEERS		DRAWING TITLE	
			SB ARCHITECTS		GPT The GPT Group		YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW		Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Windmill Street Wahia Bay, Sydney NSW 2000 Tel: (02) 8551-7699 Fax: (02) 8541-3721 email: mail@costinroe.com.au		DRAWING LIST AND LOCALITY PLAN	
			DESIGNED DS		CHECKED DS		DATE APRIL '21		SCALE AS SHOWN		PRECISION COMMUNICATION ACCOUNTABILITY	
			ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION		ISSUED FOR PRELIMINARY ONLY		AMENDMENTS		AMENDMENTS		DRAWING No C013874.06-SSDA100	
			21/05/21		09/04/21		DATE		DATE		ISSUE	
			B		A		ISSUE		ISSUE		B	

GENERAL NOTES:

- THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS' DRAWINGS AND SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK
- ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE RELEVANT AND CURRENT STANDARDS AUSTRALIA CODES AND WITH THE BY-LAWS AND ORDINANCES OF THE RELEVANT BUILDING AUTHORITIES EXCEPT WHERE VARIED BY THE PROJECT SPECIFICATION.
- ALL DIMENSIONS SHOWN SHALL BE VERIFIED BY THE BUILDER ON SITE. ENGINEER'S DRAWINGS SHALL NOT BE SCALED FOR DIMENSIONS. ENGINEER'S DRAWINGS ISSUED IN ANY ELECTRONIC FORMAT MUST NOT BE USED FOR DIMENSIONAL SETOUT.
- REFER TO THE ARCHITECT'S DRAWINGS FOR ALL DIMENSIONAL SETOUT INFORMATION. DURING CONSTRUCTION THE STRUCTURE SHALL BE MAINTAINED IN A STABLE CONDITION AND NO PART SHALL BE OVERSTRESSED. TEMPORARY BRACING SHALL BE PROVIDED BY THE BUILDER TO KEEP THE WORKS AND EXCAVATIONS STABLE AT ALL TIMES.
- UNLESS NOTED OTHERWISE ALL LEVELS ARE IN METRES AND ALL DIMENSIONS ARE IN MILLIMETRES.
- ALL WORKS SHALL BE UNDERTAKEN IN ACCORDANCE WITH ACCEPTABLE SAFETY STANDARDS & APPROPRIATE SAFETY SIGNS SHALL BE INSTALLED AT ALL TIMES DURING THE PROGRESS OF THE JOB.

SURVEY NOTE:

- EXISTING SITE LEVELS AND DETAILS BASED ON A PLAN OF SURVEY '11019-001' BY 'BOXALL SURVEYORS PTY. LTD.' DATED 23.07.2020.

SITE PREPARATION NOTES:

- ALL EARTHWORKS SHALL BE COMPLETED GENERALLY IN ACCORDANCE WITH THE GUIDELINES SPECIFIED BY THE GEOTECHNICAL REPORT 'PSM3959-004L' PROVIDED BY PSM DATED 17.10.2019.
- EXISTING LEVELS ARE BASED ON INFORMATION PROVIDED BY BOXALL SURVEYORS TITLED 11019-001 DATED 23.07.2020.
- STRIP ANY TOP SOIL OR DELETERIOUS MATERIAL AND DISPOSE OF FROM SITE OR STORE AS DIRECTED.
- COMPLETE CUT TO FILL EARTHWORKS TO ACHIEVE THE REQUIRED LEVELS AS INDICATED ON THE DRAWINGS WITHIN A TOLERANCE OF +0mm/-10mm THROUGH BUILDING PADS/PAVEMENTS AND +0mm/-20mm ELSEWHERE.
- PREPARE STEEP BATTERS TO RECEIVE FILL BY CONSTRUCTING BENCHING TO FACILITATE FILL PLACEMENT AND COMPACTION.
- AREAS TO RECEIVE FILL (THAT ARE NOT ON BENCHED BATTERS) AND AREAS IN CUT SHALL BE PROOF ROLLED TO IDENTIFY ANY SOFT HEAVING MATERIAL. SOFT MATERIAL SHALL BE BOXED OUT AND REMOVED PRIOR TO FILL PLACEMENT. PROOF ROLLING TO BE INSPECTED BY A GEOTECHNICAL ENGINEER OR THE EARTHWORKS DESIGNER.
- SITE WON FILL SHALL BE COMPACTED IN MAXIMUM 300mm LAYERS AND TO DRY OR HALF DENSITY RATIOS (STANDARD COMPACTION) OF BETWEEN 98% AND 103%. THE PLACEMENT MOISTURE VARIATION OR HALF MOISTURE VARIATION SHALL BE CONTROLLED TO BE BETWEEN 2% DRY AND 2% WET.
- IMPORTED FILL SHALL BE COMPACTED IN MAXIMUM 300mm LAYERS AND TO DRY OR HALF DENSITY RATIOS (STANDARD COMPACTION) OF BETWEEN 98% AND 103%. THE PLACEMENT MOISTURE VARIATION OR HALF MOISTURE VARIATION SHALL BE CONTROLLED TO BE BETWEEN 2% DRY AND 2% WET.
- ALL ENGINEERED FILL PARTICLES SHALL BE ABLE TO BE INCORPORATED WITHIN A SINGLE LAYER. FURTHER, LESS THAN 30% OF PARTICLES SHALL BE RETAINED ON THE 37.5 mm SIEVE. ENGINEERED FILL SHALL BE ABLE TO BE TESTED IN ACCORDANCE WITH THE STANDARD COMPACTION METHOD (AS1289.5.4.1) OR HALF TEST METHOD (AS1289.5.7.1). THESE METHODS REQUIRE LESS THAN 20% RETAINED ON THE 37.5 mm SIEVE. WHERE BETWEEN 20% AND 30% OF PARTICLES ARE RETAINED ON THE 37.5 mm SIEVE THE ABOVE TEST METHODS SHALL STILL BE ADOPTED AND TEST REPORTS ANNOTATED APPROPRIATELY. THESE REQUIREMENTS SHOULD BE MET BY THE MATERIAL AFTER PLACEMENT AND COMPACTION.
- ALL THE EARTHWORKS UNDERTAKEN AND THE SUBGRADE CONDITION IN THE CUT AREAS (IN THE STATED PERIOD) ARE DOCUMENTED IN THE REPORTS AND HAVE BEEN UNDERTAKEN IN ACCORDANCE WITH THE SPECIFICATION (EG. COSTIN ROE SITE PREPARATION NOTES IN DWG C014021.00-DA100)
- PRIOR TO ANY EARTHWORKS, EROSION CONTROL AS OUTLINED IN THE EROSION AND SEDIMENTATION CONTROL PLAN SHALL BE COMPLETED.
- EXISTING ROCK, IF ANY, SHALL BE REMOVED BY HEAVY ROCK BREAKING OR RIPPING.
- MATCH EXISTING LEVELS AT BATTER INTERFACE.
- CONTRACTOR TO MATCH EXISTING LEVELS AT THE INTERFACE OF EARTHWORKS AND EXISTING SURFACE AT BATTER LOCATIONS OR WHERE NO RETAINING WALLS ARE PRESENT. ANY DISCREPANCY BETWEEN DESIGN AND EXISTING LEVELS TO BE REFERRED TO THE ENGINEER FOR DIRECTION OR ADJUSTMENTS TO DESIGN LEVELS.
- DURING EARTHWORKS THE CONTRACTOR IS TO ENSURE ALL AREAS ARE FREE DRAINING & WILL NOT RETAIN WATER DURING RAINFALL. PROVIDE TEMPORARY MEASURES AS REQUIRED TO ENSURE FREE FLOWING RUNOFF THROUGH MANAGED DRAINAGE PATHS, DIVERSION DRAINS OR OTHER SUITABLE DISPOSAL METHOD AS AGREED DURING THE WORKS. REFER ANY CONCERNS TO THE ENGINEER. REFER TO EROSION AND SEDIMENT CONTROL DRAWINGS AND NOTES.

ELECTRONIC INFORMATION NOTES:

- THE ISSUED DRAWINGS IN HARD COPY OR PDF FORMAT TAKE PRECEDENCE OVER ANY ELECTRONICALLY ISSUED INFORMATION, LAYOUTS OR DESIGN MODELS.
- THE CONTRACTOR'S DIRECT AMENDMENT OR MANIPULATION OF THE DATA OR INFORMATION THAT MIGHT BE CONTAINED WITHIN AN ENGINEER-SUPPLIED DIGITAL TERRAIN MODEL AND ITS SUBSEQUENT USE TO UNDERTAKE THE WORKS WILL BE SOLELY AT THE DISCRETION OF AND THE RISK OF THE CONTRACTOR.
- THE CONTRACTOR IS REQUIRED TO HIGHLIGHT ANY DISCREPANCIES BETWEEN THE DIGITAL TERRAIN MODEL AND INFORMATION PROVIDED IN THE CONTRACT AND/OR DRAWINGS AND IS REQUIRED TO SEEK CLARIFICATION FROM THE SUPERINTENDENT.
- THE ENGINEER WILL NOT BE LIABLE OR RESPONSIBLE FOR THE POSSIBLE ON-GOING NEED TO UPDATE THE DIGITAL TERRAIN MODEL, SHOULD THERE BE ANY AMENDMENTS OR CHANGES TO THE DRAWINGS OR CONTRACT INITIATED BY THE CONTRACTOR.

EROSION CONTROL NOTES:

ALL CONTROL WORK INCLUDING DIVERSION BANKS AND CATCH DRAINS, V-DRAINS AND SILT FENCES SHALL BE COMPLETED DIRECTLY FOLLOWING THE COMPLETION OF THE EARTHWORKS.

- SILT FENCES AND SILT FENCE RETURNS SHALL BE ERECTED CONVEX TO THE CONTOUR TO POND WATER.
- HAY BALE BARRIERS AND GEOTEXTILE FENCES ARE TO BE CONSTRUCTED TO TOE OF BATTER, PRIOR TO COMMENCEMENT OF EARTHWORKS, IMMEDIATELY AFTER CLEARING OF VEGETATION AND BEFORE REMOVAL OF TOP SOIL.
- ALL TEMPORARY EARTH BERMS, DIVERSION AND SILT DAM EMBANKMENTS ARE TO BE MACHINE COMPACTED, SEEDED AND MULCHED FOR TEMPORARY VEGETATION COVER AS SOON AS THEY HAVE BEEN FORMED.
- CLEAR WATER IS TO BE DIVERTED AWAY FROM DISTURBED GROUND AND INTO THE DRAINAGE SYSTEM.
- THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND PROVIDING ON GOING ADJUSTMENT TO EROSION CONTROL MEASURES AS REQUIRED DURING CONSTRUCTION.
- ALL SEDIMENT TRAPPING STRUCTURES AND DEVICES ARE TO BE INSPECTED AFTER STORMS FOR STRUCTURAL DAMAGE OR CLOGGING, TRAPPED MATERIAL IS TO BE REMOVED TO A SAFE, APPROVED LOCATION.
- ALL FINAL EROSION PREVENTION MEASURES INCLUDING THE ESTABLISHMENT OF GRASSING ARE TO BE MAINTAINED UNTIL THE END OF THE DEFECTS LIABILITY PERIOD.
- ALL EARTHWORKS AREAS SHALL BE ROLLED ON A REGULAR BASIS TO SEAL THE EARTHWORKS.
- ALL FILL AREAS ARE TO BE LEFT WITH A BUND AT THE TOP OF THE SLOPE AT THE END OF EACH DAYS EARTHWORKS. THE HEIGHT OF THE BUND SHALL BE A MINIMUM OF 200mm.
- ALL CUT AND FILL SLOPES ARE TO BE SEEDED AND HYDROMULCHED WITHIN 10 DAYS OF COMPLETION OF FORMATION.
- AFTER REVEGETATION OF THE SITE IS COMPLETE AND THE SITE IS STABLE IN THE OPINION OF A SUITABLY QUALIFIED PERSON ALL TEMPORARY WORK SUCH AS SILT FENCE, DIVERSION DRAINS ETC SHALL BE REMOVED.
- ALL TOPSOIL STOCKPILES ARE TO BE SUITABLY COVERED TO THE SATISFACTION OF THE SITE MANAGER TO PREVENT WIND AND WATER EROSION.
- ANY AREA THAT IS NOT APPROVED BY THE CONTRACT ADMINISTRATOR FOR CLEARING OR DISTURBANCE BY THE CONTRACTOR'S ACTIVITIES SHALL BE CLEARLY MARKED AND SIGN POSTED, FENCED OFF OR OTHERWISE APPROPRIATELY PROTECTED AGAINST ANY SUCH DISTURBANCE.
- ALL STOCKPILE SITES SHALL BE SITUATED IN AREAS APPROVED FOR SUCH USE BY THE SITE MANAGER. A 6m BUFFER ZONE SHALL EXIST BETWEEN STOCKPILE SITES AND ANY STREAM OR FLOW PATH. ALL STOCKPILES SHALL BE ADEQUATELY PROTECTED FROM EROSION AND CONTAMINATION OF THE SURROUNDING AREA BY USE OF THE MEASURES APPROVED IN THE EROSION AND SEDIMENTATION CONTROL PLAN.
- ACCESS AND EXIT AREAS SHALL INCLUDE SHAKE-DOWN OR OTHER METHODS APPROVED BY THE SITE MANAGER FOR THE REMOVAL OF SOIL MATERIALS FROM MOTOR VEHICLES.
- THE CONTRACTOR IS TO ENSURE RUNOFF FROM ALL AREAS WHERE THE NATURAL SURFACE IS DISTURBED BY CONSTRUCTION, INCLUDING ACCESS ROADS, DEPOT AND STOCKPILE SITES, SHALL BE FREE OF POLLUTANTS BEFORE IT IS EITHER DISPERSED TO STABLE AREAS OR DIRECTED TO NATURAL WATERCOURSES.
- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN SLOPES, CROWNS AND DRAINS ON ALL EXCAVATIONS AND EMBANKMENTS TO ENSURE SATISFACTORY DRAINAGE AT ALL TIMES. WATER SHALL NOT BE ALLOWED TO POND ON THE WORKS UNLESS SUCH PONDING IS PART OF AN APPROVED ESCP / SWMP.

EXISTING SERVICES NOTES:

- DURING THE EXECUTION OF WORKS, THE CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF EXISTING SERVICES. THE CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED TO THE EXISTING SERVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE RELEVANT SERVICE AUTHORITY, AT NO COST TO THE PRINCIPAL.
- WHERE IT IS NECESSARY TO REMOVE, DIVERT OR CUT INTO ANY EXISTING SERVICE, THE CONTRACTOR SHALL GIVE AT LEAST THREE (3) DAYS NOTICE OF ITS REQUIREMENTS TO THE SUPERINTENDENT, WHO WILL ADVISE WHAT ARRANGEMENTS SHOULD BE MADE FOR THE ALTERATION OF SUCH EXISTING SERVICES.
- EXISTING SERVICES HAVE BEEN PLOTTED FROM SUPPLIED DATA. THE ACCURACY IS NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ESTABLISH THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO COMMENCING WORK. ALL CLEARANCES AND APPROVALS SHALL ALSO BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY PRIOR TO THE COMMENCEMENT OF WORK.
- ALL NEW AND EXHUMED SERVICES THAT CROSS EXISTING AND FUTURE ROADS/PAVEMENTS WITHIN THE SITE SHALL BE BACKFILLED WITH DGB20 MATERIAL TO SUBGRADE LEVEL AND COMPACTED TO 98% STANDARD DENSITY RATIO. SUBJECT TO PRIOR APPROVAL FROM RELEVANT AUTHORITY.
- ON COMPLETION OF SERVICES INSTALLATION, ALL DISTURBED AREAS SHALL BE RESTORED TO ORIGINAL, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AREAS, GRASSED AREAS AND ROAD PAVEMENTS.
- CARE TO BE TAKEN WHEN EXCAVATING NEAR UTILITY SERVICES. NO MECHANICAL EXCAVATION TO BE UNDERTAKEN OVER SERVICES. LIAISE WITH RELEVANT AUTHORITY.
- THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION AND REMOVAL IF REQUIRED OF ALL EXISTING SERVICES IN AREAS AFFECTED BY THE WORKS WITHIN THE CONTRACT AREA AS SHOWN ON THE DRAWINGS UNLESS DIRECTED OTHERWISE BY THE SUPERINTENDENT. ALL TO REGULATORY AUTHORITY STANDARDS AND APPROVAL.
- THE CONTRACTOR IS TO MAINTAIN EXISTING STORMWATER DRAINAGE FLOWS THROUGH THE ROADS AT ALL TIMES. MAKE DUE ALLOWANCE FOR ALL SUCH FLOWS AT ALL TIMES.
- PRIOR TO COMMENCEMENT OF ANY WORKS THE CONTRACTOR SHALL OBTAIN THE SUPERINTENDENT'S APPROVAL OF THE PROGRAM FOR THE RELOCATION/CONSTRUCTION OF TEMPORARY SERVICES.
- CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES AS REQUIRED TO MAINTAIN EXISTING SUPPLY TO BUILDINGS REMAINING IN OPERATION DURING WORKS TO THE SATISFACTION AND APPROVAL OF THE SUPERINTENDENT. ONCE DIVERSION IS COMPLETE AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND MAKE GOOD TO THE SATISFACTION OF THE SUPERINTENDENT.
- INTERRUPTION TO SUPPLY OF EXISTING SERVICES SHALL BE DONE SO AS NOT TO CAUSE ANY INCONVENIENCE OR DAMAGE TO THE ADJACENT RESIDENCES. CONTRACTOR TO GAIN APPROVAL OF THE SUPERINTENDENT FOR TIME OF INTERRUPTION.
- THE CONTRACTOR SHALL UNDERTAKE A DIAL BEFORE YOU DIG (DBYD 1100) SERVICES SEARCH BEFORE THE COMMENCEMENT OF ANY WORKS.

TRAFFIC CONTROL NOTES:

- TRAFFIC CONTROLS TO COMPLY WITH AS 1742.3-2002
- TRAFFIC CONTROL PLANS TO BE SUBMITTED AND CERTIFIED BY AN ACCREDITED WORK SITE OPERATIVE.
- AS PART OF THE TRAFFIC CONTROL PLAN ENSURE THAT PEDESTRIANS ARE CATERED FOR.
- AFTER-HOURS TRAFFIC CONTROL THROUGH THE WORKSITE HAVE TO BE CATERED FOR.

PCC NOTES:

ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH PENRITH CITY COUNCIL STANDARDS AND SPECIFICATIONS.

STORMWATER DRAINAGE NOTES:

- ALL STORMWATER WORKS TO BE COMPLETED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS3500.3:2003 PLUMBING AND DRAINAGE, PART 3: STORMWATER DRAINAGE.
- THE MINOR (PIPED) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 20 YEAR ARI STORM EVENT AND THE MAJOR (OVERLAND) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 100 YEAR ARI STORM EVENT.
- PIT SIZES SHALL BE AS INDICATED IN THE SCHEDULE WHILE PIPE SIZES AND DETAILS ARE PROVIDED ON PLAN.
- EXISTING STORMWATER PIT LOCATIONS AND INVERT LEVELS TO BE CONFIRMED BY SURVEY PRIOR TO COMMENCING WORKS ON SITE.
- ALL STORMWATER PIPES Ø375 OR GREATER SHALL BE CLASS 2 (WITH HS2 SUPPORT) REINFORCED CONCRETE WITH RUBBER RING JOINTS UNLESS NOTED OTHERWISE.
- ALL PIPES UP TO AND INCLUDING Ø300 TO BE UPVC GRADE S8B UNO.
- PIPE CLASS NOMINATED ARE FOR IN-SERVICE LOADING CONDITIONS ONLY. CONTRACTOR IS TO MAKE ANY NECESSARY ADJUSTMENTS REQUIRED FOR CONSTRUCTION CONDITIONS.
- ALL CONCRETE PITS GREATER THAN 1000mm DEEP SHALL BE REINFORCED USING N12-200 EACH WAY CENTERED IN WALL AND BASE. LAP MINIMUM 300mm WHERE REQUIRED. ALL CONCRETE FOR PITS SHALL BE F'c<25 MPa. PRECAST PITS MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
- IN ADDITION TO ITEM 9 ABOVE, ALL CONCRETE PITS GREATER THAN 3000mm DEEP SHALL HAVE WALLS AND BASE THICKNESS INCREASED TO 200mm.
- PIPES SHALL BE LAID AS PER PIPE LAYING DETAILS. PARTICULAR CARE SHALL BE TAKEN TO ENSURE THAT THE PIPE IS FULLY AND EVENLY SUPPORTED. NARROW PACK FILLING AROUND AND UNDER BACK OF PIPES AND PIPE FAUCETS, WITH RAMP EDGED RAMMERS OR OTHER SUITABLE TAMPING DETAILS.
- CONCRETE PIPES UNDER, OR WITHIN THE ZONE OF INFLUENCE OF PAVED AREAS SHALL BE LAID USING HS2 TYPE SUPPORT, AS A MINIMUM, IN ACCORDANCE WITH AS 3725. AGGREGATE BACKFILL SHALL NOT BE USED FOR PIPE BEDDING AND OR HAUNCH/SIDE SUPPORT.
- WHERE PIPE LINES ENTER PITS, PROVIDE 2m LENGTH OF STOCKING WRAPPED SLOTTED Ø100 UPVC TO EACH SIDE OF PIPE.
- ALL SUBSOIL DRAINAGE LINES SHALL BE Ø100 SLOTTED UPVC WITH APPROVED FILTER WRAP LAID IN 300mm WIDE GRANULAR FILTER UNLESS NOTED OTHERWISE. LAY SUBSOIL LINES TO MATCH FALLS OF LAND AND/OR 1 IN 200 MINIMUM. PROVIDE CAPPED CLEANING EYE (RODDING POINT) AT UPSTREAM END OF LINE AND AT 30m MAX. CTS. PROVIDE SUBSOIL LINES TO ALL PAVEMENT/ LANDSCAPED INTERFACES, TO REAR OF RETAINING WALLS (AS NOMINATED BY STRUCTURAL ENGINEER) AND AS SHOWN ON PLAN.
- ALL PIPE GRADES 1 IN 200 MINIMUM UNO.
- PROVIDE STEP IRONS IN PITS DEEPER THAN 1000mm.
- MIN. 600 COVER TO PIPE OBVERT BENEATH ROADS & MIN. 400 COVER BENEATH LANDSCAPED AND PEDESTRIAN AREAS.
- PIT COVERS IN TRAFFICABLE PAVEMENT SHALL BE CLASS D 'HEAVY DUTY', THOSE LOCATED IN NON-TRAFFICABLE AREAS SHALL BE CLASS B 'MEDIUM DUTY' U.N.O.
- PROVIDE CLEANING EYES (RODDING POINTS) TO PIPES AT ALL CORNERS AND T-JUNCTIONS WHERE NO PITS ARE PRESENT.
- DOWN PIPES (DP) TO BE AS PER HYDRAULIC ENGINEERS DETAILS WITH CONNECTOR TO MATCH DP SIZE U.N.O. ON PLAN. PROVIDE CLEANING EYE AT GROUND LEVEL.
- PIPE LENGTHS NOMINATED ON PLAN OR LONGSECTIONS ARE MEASURED FROM CENTER OF PITS TO THE NEAREST 0.5m AND DO NOT REPRESENT ACTUAL LENGTH. THE CONTRACTOR IS TO ALLOW FOR THIS.

FINISHED LEVELS PLAN NOTES:

- LEVELS DATUM IS AUSTRALIAN HEIGHT DATUM (A.H.D.).
- GRADING REQUIREMENTS TO BE COMPLETED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS2890.1, AS2890.2 AND AS2890.6.
- ALL CONTOUR LINES & SPOT LEVELS INDICATE FINISHED PAVEMENT LEVELS U.N.O. ON PLAN.
- CONTOUR INTERVALS
 - THE MINOR CONTOUR INTERVAL IS 0.1m.
 - THE MAJOR CONTOUR INTERVAL IS 0.5m.
- HARDSTAND GRADING
 - MINIMUM PAVEMENT GRADE IS TO BE 1:100 (1%).
 - GRADING OF ON-GRADE DOCKS TO BE 1:100 (1%) FALL AWAY FROM THE DOCK FACE FOR A LENGTH OF 15m U.N.O.
 - GRADING OF TRUCK CIRCULATION ZONES TO BE MINIMUM AS NOTED ABOVE, 3-4% NOMINAL AND MAX. 5%.
- CAR PARKING AREA GRADES
 - MINIMUM PAVEMENT GRADE IS TO BE 1:100 (1%), DESIRABLE MINIMUM GRADE 1:50 (2%).
 - MAXIMUM PAVEMENT GRADE IS TO BE 1:20 (5%) IN CARPARKING AREAS AND 1:25 (4%) ELSEWHERE.
 - DISABLED ACCESS PARKING ZONES AND SHARED SPACE TO BE MAXIMUM OF 1:33 (3%) IN ASPHALT PAVEMENT AND MAXIMUM OF 1:40 (2.5%) IN CONCRETE PAVEMENT.
 - CARPARK RAMP GRADES TO BE MAX 1:5 WITH 2.5m SMOOTH TRANSITION AT TOP AND BOTTOM U.N.O.
- TRUCK RAMP GRADES
 - MAXIMUM B-DOUBLE OR 19.0m AV RAMP GRADES ARE TO BE 1:8.3 (12%) U.N.O. ON PLAN.
 - PROVIDE MINIMUM 4.0m LONG TRANSITION WHERE CHANGES OF GRADE EXCEED 1:20 (5%) AT A CREST U.N.O.
 - PROVIDE MINIMUM 3.0m LONG TRANSITION WHERE CHANGE OF GRADE EXCEED 1:20 (5%) AT A SAG U.N.O.
 - TRANSITIONS ARE TO PROVIDE A SMOOTH CONTINUOUS CIRCULAR AND TANGENTIAL CHANGE IN GRADE TO ENSURE NO SHARP OR ACUTE CHANGES IN GRADE ARE PRESENT.
- WHERE FIRE BRIGADE ACCESS IS REQUIRED, MAXIMUM RAMP GRADIENTS ARE TO BE 1:6 (16.6%), DESIRABLE RAMP GRADIENTS ARE TO BE 1:8 (12.5%) WITH 7m TRANSITION TOP AND BOTTOM U.N.O. ON PLAN.
- PERMANENT BATTER SLOPES ARE TO HAVE A MAXIMUM GRADE OF 1V:3H U.N.O. BASED ON GEOTECHNICAL ASSESSMENT. PROVIDE MINIMUM 0.5m BERM BETWEEN THE BACK OF KERB OR PAVEMENT EDGES AND THE TOP OR TOE OF A BATTER.
- ALL BATTER SLOPE WITH GRADES AT OR EXCEEDING 1V:6H ARE TO BE TURED IMMEDIATELY OR APPROPRIATE EROSION CONTROL IS TO BE PROVIDED TO THE SATISFACTION OF THE ENGINEER.
- ALL FOOTPATHS ARE TO FALL AWAY FROM THE BUILDING AT 2.5% NOMINAL GRADE.
- ALL PAVEMENTS ARE TO BE SET AT 30mm BELOW THE FINISHED FLOOR LEVEL OF THE WAREHOUSE AND OFFICE AREAS. PROVIDE LOCAL FEATHERING AT DOORWAYS OR ROLLER SHUTTERS TO PROVIDE FLUSH FINISH AS REQUIRED.
- WHERE NEW AND EXISTING INTERFACING IS REQUIRED, MATCH EXISTING LEVELS AND PROVIDE SMOOTH INTERFACE BETWEEN NEW AND EXISTING GRADIENTS. REFER ANY CONCERNS TO THE ENGINEER.

REINFORCED EARTH RETAINING WALL NOTES:


- ALL COMPONENTS AND INSTALLATION SHALL COMPLY WITH AS4678 AND THE STANDARDS REFERRED TO THEREIN.
- MINIMUM HEIGHT (H) TO GEOGRID REINFORCEMENT LENGTH (L) TO BE 1.0.
- MINIMUM BEARING CAPACITY OF FOUNDATION (BASED ON MINIMUM H/L RATIO OF 1.0) TO BE AS FOLLOWS:
 - a. H MAX. 2.0m = 100 kPa
 - b. H MAX. 3.5m = 150 kPa
 - c. H MAX. 5.0m = 200 kPa
- BEFORE COMMENCEMENT OF CONSTRUCTION THE FOUNDATION SHALL BE INSPECTED AND VERIFIED BY A QUALIFIED GEOTECHNICAL ENGINEER.
- WHERE MINIMUM BEARING IS NOT ACHIEVABLE OR NOT MEETING DESIGN REQUIREMENT, THE FOUNDATION MATERIAL IS TO BE EXCAVATED AND REPLACED WITH APPROVED MATERIAL PLACED IN ACCORDANCE WITH THE FILLING SPECIFICATION TO A MINIMUM COMPACTION OF 100% SMD AND PLACED WITHIN 2% OF OMC.
- MINIMUM SURCHARGE LOADS TO BE APPLIED AS FOLLOWS U.N.O. ON PLAN:
 - a. LIVE LOAD = 20 kPa
 - b. DEAD LOAD = 5 kPa
 - c. CONSTRUCTION TRAFFIC LIVE LOAD = 10 kPa
- THE GEOGRIDS SHALL BE OF THE TYPE AND INDEX STRENGTH NOMINATED ON THE DRAWINGS. THE MINIMUM GEOGRIDS SHALL BE A SINGLE LENGTH IN THE DIRECTION OF DESIGN TENSION, NOT LAPPED, MAKING PROVISION FOR CONNECTION TO THE FACING ACROSS THE WHOLE WIDTH OF THE FACING AND PROVIDING FOR THE SPECIFIED ANCHORAGE WITHIN THE DESIGNATED ANCHORAGE ZONE. GEOGRIDS SHALL COVER THE WHOLE OF THE PLAN AREA BEHIND THE WALL FOR THE SPECIFIED ANCHORAGE LENGTH AND SHALL BE LAPPED WITH ADJACENT SECTIONS IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
- MINIMUM WALL EMBEDMENT AT THE TOE OF THE WALL TO BE 300mm.
- DESIGN LIFE OF STRUCTURE IS TO BE 100 YEARS.
- SELECT BACKFILL MATERIAL WITHIN THE REINFORCED SOIL BLOCK SHALL BE SOUND GRANULAR MATERIAL OF NATURAL OR INDUSTRIAL ORIGIN, NON-EXPANSIVE, FREE FROM ORGANIC OR OTHER DELETERIOUS MATERIAL CONFORMING TO THE PHYSICAL, CHEMICAL AND ELECTROCHEMICAL LIMITS AS SPECIFIED AND SHALL NOT BE SUBJECT TO BREAKDOWN UNDER COMPACTION. THE SELECT BACKFILL MATERIAL IS TO HAVE THE FOLLOWING PARAMETERS:
 - a. MINIMUM INTERNAL FRICTION, Ø = 34°
 - b. EFFECTIVE COHESION, C' = 0 kPa
 - c. UNIT WEIGHT = 21 kN/m³
 - d. PH BETWEEN 4 AND 9
- SELECT BACKFILL IS TO BE PLACED AND COMPACTED IN LAYERS NOT MORE THAN 300mm (LOOSE) COMPACTION TO NOT LESS THAN 100% SMD WILL BE ACHIEVED AND MATERIAL PLACED WITHIN 2% OF OMC. DENSITY TESTING SHALL BE PERFORMED IN EACH COMPACTED LIFT IN ACCORDANCE WITH AS3798.
- PROVIDE A DRAINAGE LAYER DIRECTLY BEHIND THE FACING UNITS IN A MINIMUM 300mm WIDE 12-20mm AGGREGATE LAYER. FACING UNIT VOIDS TO BE FILLED WITH AGGREGATE. PROVIDE 100mm MINIMUM AG. DRAIN IN GEOTEXTILE SOCK AT TOE OF WALL FACING AND CONNECT TO DRAINAGE SYSTEM AT 30m MAX. SPACING.
- THE NEED FOR A CHIMNEY DRAIN OR DRAINAGE AT THE REAR OF THE MASS SOIL BLOCK IS TO BE CONFIRMED ON SITE BY THE GEOTECHNICAL ENGINEER AND DESIGNER FOLLOWING PREPARATION OF THE FOUNDATION AND PRIOR TO CONSTRUCTION OF THE MASS SOIL BLOCK.
- CONSTRUCTION EQUIPMENT WEIGHING MORE THAN 500KG STATIC WEIGHT IS TO BE KEPT BACK 1.5m FROM THE REAR FACE OF THE WALL FACING UNITS. COMPACTION OF THE SELECT FILL MATERIAL WITHIN THE 1.5m STRIP ADJACENT TO THE WALL SHALL BE ACHIEVED BY LIGHT MECHANICAL TAMPERS (VIBRATING PLATE, TRENCH COMPACTOR OR SIMILAR) TO GIVE THE SAME DENSITY AS IN THE REMAINDER OF THE SELECT FILL.
- ALL DESIGN AND CONSTRUCT WALL SYSTEM TO BE COMPLETED IN ACCORDANCE WITH THESE NOTES.
- TOP OF WALL HEIGHTS ARE NOTED TO ALIGN WITH FINISHED PAVEMENT HEIGHTS. THE CONTRACTOR AND THEIR DESIGN AND CONSTRUCT WALLING CONTRACTORS ARE TO ENSURE THAT ALL WALL STRAPS ARE INSTALLED BELOW THE DESIGN EARTHWORKS SUBGRADE. CONTRACTOR TO ALLOW FOR WALL STRAPS TO BE GRADED AWAY FROM THE FACE OF THE WALL OR OTHERWISE INSTALLED TO SUIT EARTHWORKS DESIGN LEVELS AND GRADES.

DIFFERENTIAL SETTLEMENT NOTE:


FUTURE BUILDING AND SERVICE DESIGNERS TO CONSIDER DIFFERENTIAL SETTLEMENT OF REINFORCED EARTH WALL BLOCK AND GENERAL FILL AREAS. PARTICULAR ATTENTION TO BE DRAWN TO HEAVILY LOADED AREAS, OR DEFERRING LOADED AREAS (INCLUDING SPRINKLER TANK AND TRUCK PAVEMENT AREAS) AND WHERE SIGNIFICANT CHANGES IN OVERALL WALL HEIGHT OR FILL AMOUNTS ARE EXPERIENCED. IT IS THE RESPONSIBILITY OF THE FUTURE DESIGNERS TO ENSURE APPROPRIATE DESIGN CONSIDERATION TO DIFFERENTIAL SETTLEMENT ARE MADE DEPENDING ON THE DESIGN ELEMENT AND INTERACTION WITH RETAINED ELEMENTS AND GENERAL FILL MATERIAL.

RETAINING WALL NOTES:


- ALL COMPONENTS AND INSTALLATION SHALL COMPLY WITH AS4678 AND THE STANDARDS REFERRED TO THEREIN.
- MINIMUM BEARING CAPACITY OF FOUNDATION TO BE AS FOLLOWS :
 - a. H MAX. 2.0m = 100 kPa
 - b. H MAX. 3.5m = 150 kPa
 - c. H MAX. 5.0m = 200 kPa
- BEFORE COMMENCEMENT OF CONSTRUCTION THE FOUNDATION SHALL BE INSPECTED AND VERIFIED BY A QUALIFIED GEOTECHNICAL ENGINEER.
- WHERE MINIMUM BEARING IS NOT ACHIEVABLE OR NOT MEETING DESIGN REQUIREMENT, THE FOUNDATION MATERIAL IS TO BE EXCAVATED AND REPLACED WITH APPROVED MATERIAL PLACED IN ACCORDANCE WITH THE FILLING SPECIFICATION TO A MINIMUM COMPACTION OF 100% SMD AND PLACED WITHIN 2% OF OMC.
- MINIMUM SURCHARGE LOADS TO BE APPLIED AS FOLLOWS U.N.O.
- ON PLAN :
 - a. LIVE LOAD = 20 kPa
 - b. DEAD LOAD = 5 kPa
 - c. CONSTRUCTION TRAFFIC LIVE LOAD = 10 kPa
- MINIMUM WALL EMBEDMENT AT THE TOE OF THE WALL TO BE 300mm MINIMUM UNLESS NOTED OTHERWISE.
- DESIGN LIFE OF STRUCTURE IS TO BE 100 YEARS.
- TIED WALLS ARE TO BE TEMPORARILY PROPPED AT TOP UNTIL SUCH TIME THE TOP OF WALL IS TIED TO THE SLAB AND 28-DAY CONCRETE STRENGTH HAS BEEN ACHIEVED.
- CONSTRUCTION EQUIPMENT WEIGHING MORE THAN 500KG STATIC WEIGHT IS TO BE KEPT BACK 1.5m FROM THE REAR FACE OF THE WALL FACING UNITS. COMPACTION OF THE SELECT FILL MATERIAL WITHIN THE 1.5m STRIP ADJACENT TO THE WALL SHALL BE ACHIEVED BY LIGHT MECHANICAL TAMPERS (VIBRATING PLATE, TRENCH COMPACTOR OR SIMILAR) TO GIVE THE SAME DENSITY AS IN THE REMAINDER OF THE SELECT FILL.
- ALL DESIGN AND CONSTRUCT WALL SYSTEMS TO BE COMPLETED IN ACCORDANCE WITH THESE NOTES.



SILT FENCE WITH STRAW BALE DETAIL
N.T.S.




TYPICAL SILT FENCE DETAIL
N.T.S.
PROVIDE 1m RETURNS AT 30m INTERVALS.
TYPICAL



TYPICAL STOCKPILE DETAIL
N.T.S.

STOCKPILE NOTES


1. PLACE ALL STOCKPILES IN LOCATIONS MORE THAN 5m FROM EXISTING VEGETATION, ROADS & HAZARD AREAS.
2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT ELONGATED MOUNDS. SIDE SLOPE TO BE 1 V: 2 H MAX.
3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT.
4. WHERE STOCKPILES ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE USING WOOD CHIP MULCH - 16 TONNE/Ha
5. CONSTRUCT SILT FENCE WITH CATCH DRAIN ON UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES & SILT FENCE ONLY 1 TO 2m DOWNSLOPE AS SHOWN.




SEDIMENT STORAGE MARKER
SCALE 1:20

NOTES:


- ALL EROSION & SEDIMENT CONTROL MEASURES TO BE INSPECTED & MAINTAINED DAILY BY SITE MANAGER.
- MINIMISE DISTURBED AREAS.
- ROADS & FOOTPATHS TO BE SWEEPED DAILY.
- 12m TURF TO BE PLACED BEHIND KERBS.
- DUST MINIMISATION CONTROL BY WATERING TO BE IMPLEMENTED BY SITE MANAGER AS REQUIRED OR AS DIRECTED BY THE EPA.




TYPE 1 DIVERSION DRAIN SECTION
SCALE 1:20





TYPE 2 DIVERSION DRAIN SECTION
SCALE 1:20



TYPE 3 DIVERSION DRAIN SECTION
SCALE 1:20




TYPE 4 DIVERSION DRAIN SECTION
SCALE 1:20




TYPICAL SEDIMENT CONTROL POND PLAN
SCALE 1:250

SPILLWAY DETAIL & SCHEDULE


CATCHMENT (Ha)	FLOW (m³/s)	WIDTH (mm)	FLOW DEPTH (mm)	ROCK SIZE (mm)	BUND HEIGHT ABOVE SPILLWAY (mm)
0.20	0.14	1000	200	-	600
0.5	0.2	2000	200	-	600
1	0.3	2000	200	-	700
2	0.6	4000	200	-	700
5	1.4	5000	300	200	800
10	2.8	8000	350	200	850
20	5.5	14000	400	250	900
40	11.0	20000	500	250	1000



TYPICAL SEDIMENT CONTROL BASIN SECTION
SCALE 1:50



PRELIMINARY ONLY



LEGEND

NOTE:
LEVELS DATUM IS AHD.
ALL LEVELS ARE ±1000 mm

— 10.00 — - EXISTING CONTOUR
— 13.00 — - B.E.L. CONTOUR (MAJOR 1.0m)
— 13.25 — - B.E.L. CONTOUR (MINOR 0.25m)

PAVEMENT PFL
DEPTH OF PAVEMENT.
REFER TO STRUCTURAL PLANS FOR DETAILS.

PAVEMENT
BASE/ SUBBASE COURSES
SUBGRADE
NOMINATED B.E. LEVEL

NOMINATED B.E.L. DETAIL
N.T.S.

DEPTH RANGE				
No.	FROM DEPTH	TO DEPTH	COLOUR	DEPTH RANGE VOLUME
1	-18.000	-16.000		44m
2	-16.000	-14.000		2222m
3	-14.000	-12.000		7802m
4	-12.000	-10.000		15344m
5	-10.000	-8.000		25120m
6	-8.000	-6.000		38872m
7	-6.000	-4.000		60199m
8	-4.000	-2.000		101518m
9	-2.000	0.000		176985m
10	0.000	2.000		342971m
11	2.000	4.000		167543m
12	4.000	6.000		53626m
13	6.000	8.000		15454m
14	8.000	10.000		1426m

ADJACENT PROPERTY LEVELS NOTE:
FUTURE DEVELOPMENT LEVELS FOR NEIGHBOURING PROPERTIES TO NORTH AND EAST NOT CURRENTLY KNOWN. INTERFACING CURRENTLY SHOWN ON PLAN IS TO EXISTING LEVELS. FINAL INTERFACING ARRANGEMENT SUBJECT TO FURTHER DISCUSSION & COORDINATION WITH ADJOINING LANDOWNERS/DEVELOPERS.

LEVELS NOTE:
LEVELS SHOWN TO BE ±1000mm FROM THOSE SHOWN FINAL LEVELS SUBJECT TO FINAL GEOTECHNICAL INVESTIGATIONS, ARCHITECTURAL LAYOUT AND ACHIEVING A CUT TO FILL EARTHWORKS BALANCE OVER THE PROPERTY.

EARTHWORKS VOLUMES
SITE AREA = 33.1 Ha

TOPSOIL STRIP (200 mm) = (- 66,200 m³)
CUT MATERIAL = - 428,100 m³
FILL MATERIAL = + 580,000 m³

DETAILED EXCAVATION (2,000m³/Ha OVER 33.1 Ha) = - 66,200 m³


BALANCE = + 86,700 m³


NOTE:
EARTHWORKS VALUES ARE APPROXIMATE ONLY.
NO ALLOWANCE HAS BEEN MADE IN THE ABOVE VOLUMES FOR EROSION & SEDIMENT CONTROL BACKFILLING, BULKING OR COMPACTION OF FILLED SOILS, THE REMOVAL OF UNCONTROLLED OR CONTAMINATED MATERIAL, TEMPORARY DRAINAGE SWALES WITHIN BUILDING PADS, OR ANY OTHER UNSPECIFIED EXCAVATION RELATED TO WAREHOUSE CONSTRUCTION.

MIRVAC SITE
ANTICIPATED PAD LEVELS AS SHOWN
SITE LAYOUT PER MIRVAC SSDA_10448 EIS


BULK EARTHWORKS PLAN
SCALE 1:1000

FOR DEVELOPMENT APPLICATION







SECTION 1
HORIZONTAL SCALE 1:1000
VERTICAL SCALE 1:200




SECTION 2
HORIZONTAL SCALE 1:1000
VERTICAL SCALE 1:200




SECTION 3
HORIZONTAL SCALE 1:1000
VERTICAL SCALE 1:200




SECTION 4
HORIZONTAL SCALE 1:1000
VERTICAL SCALE 1:200



FOR DEVELOPMENT APPLICATION




SECTION 6
HORIZONTAL SCALE 1:1000
VERTICAL SCALE 1:200




Costin Roe Consulting

[illegible]




STORMWATER DRAINAGE MASTER PLAN
SCALE 1:1000

FOR DEVELOPMENT APPLICATION




ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION				ARCHITECT				CLIENT				PROJECT				Costin Roe Consulting Pty Ltd.			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION				SB ARCHITECTS				GPT The GPT Group				YIRIBANA LOGISTICS ESTATE				Consulting Engineers			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION				26.05.21				754-770 & 784-786 MAMRE ROAD				Level 1, 8 Windmill Street				Wahib Bay, Sydney NSW 2000			
ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION				21.05.21				KEMPS CREEK NSW				Tel: (02) 8551-7699 Fax: (02) 8541-3721				email: mail@costinroe.com.au			
ISSUED FOR PRELIMINARY ONLY				09.04.21				DESIGNED (DRAWN) DS				CHECKED DS				DATE APRIL '21			
AMENDMENTS				DATE				SIZE A0				SCALE AS SHOWN				CNO REF: C01871.01-SSDA4.00			
DATE				ISSUE				AMENDMENTS				PRECISION COMMUNICATION ACCOUNTABILITY				DRAWING TITLE			
												STORMWATER DRAINAGE MASTERPLAN				DRAWING No			
												C013874.06-SSDA4.00				ISSUE			
												E							




PRE-DEVELOPMENT CATCHMENT PLAN
SCALE 1:2000

FOR DEVELOPMENT APPLICATION




ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION			AMENDMENTS			AMENDMENTS			AMENDMENTS			AMENDMENTS			AMENDMENTS			AMENDMENTS		
2105.21	A																			
DATE	ISSUE		DATE	ISSUE		DATE	ISSUE		DATE	ISSUE		DATE	ISSUE		DATE	ISSUE		DATE	ISSUE	

ARCHITECT		CLIENT		PROJECT		CONSULTANT		DRAWING TITLE	
SB ARCHITECTS		GPT The GPT Group		YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW		Costin Roe Consulting Pty Ltd. Consulting Engineers		PRE-DEVELOPMENT STORMWATER CATCHMENT PLAN	
Basis: 752, 83 Mount Street, North Sydney NSW 2060 Tel: (02) 9551-7000 Fax: (02) 9551-7001 Email: info@sbarchitects.com.au		Level 1, 8 Windmill Street, Wahbi Bay, Sydney NSW 2000 Tel: (02) 9551-7000 Fax: (02) 9551-7001 Email: mail@costinroe.com.au		DESIGNED (DRAWN) DS		CHECKED (DS)		DATE (APRIL '21)	
SIZE (A0)		SCALE (AS SHOWN)		CADD REF: (C01874.06-SSDA4.01)		PRECISION COMMUNICATION ACCOUNTABILITY		DRAWING No C013874.06-SSDA4.01	
ISSUE		ISSUE		ISSUE		ISSUE		ISSUE	




 **POST DEVELOPMENT
STORMWATER CATCHMENT PLAN**
SCALE 1:2000



FOR DEVELOPMENT APPLICATION

ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION			ARCHITECT			CLIENT			PROJECT			CONSULTANT			DRAWING TITLE		
2105.21									YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW						POST-DEVELOPMENT STORMWATER CATCHMENT PLAN		
AMENDMENTS			DATE			DATE			DESIGNED (DRAWN)			PRECISION COMMUNICATION ACCOUNTABILITY			DRAWING No		
DATE			ISSUE			DATE			DS			C013874.06-SSDA402			C013874.06-SSDA402		
AMENDMENTS			DATE			DATE			DS			C013874.06-SSDA402			C013874.06-SSDA402		
AMENDMENTS			DATE			DATE			DS			C013874.06-SSDA402			C013874.06-SSDA402		



LEGEND:
LEVELS DATUM IS AHD.

EXISTING SITE LEVELS AND DETAILS BASED ON A PLAN OF SURVEY 20119 DE-01 BY STATIKER 26/09/20.

- SGGP, SINGLE GRATED GULLY PIT
- SJP, SEALED JUNCTION PIT
- GD, GRATED DRAIN (300W x 225D UNO)
- PROPOSED DRAINAGE LINE
- EXISTING ESTATE DRAINAGE LINE
- ROOFWATER DOWNPIPE (INDICATIVE)
- OVERLAND FLOW DIRECTION
- FINISHED PAVEMENT CONTOUR (MAJOR) 0.5m INTERVALS
- FINISHED PAVEMENT CONTOUR (MINOR) 0.1m INTERVALS
- EXISTING ESTATE CONTOUR

- STORMWATER DRAINAGE NOTES:**
- ALL STORMWATER WORKS TO BE COMPLETED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS3500.3:2003 PLUMBING AND DRAINAGE, PART 3: STORMWATER DRAINAGE.
 - THE MINOR (PIPED) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 20 YEAR ARI STORM EVENT AND THE MAJOR (OVERLAND) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 100 YEAR ARI STORM EVENT.
 - ALL FINISHED PAVEMENT LEVELS SHALL BE AS INDICATED ON FINISHED LEVELS PLANS SSDA11.
 - PIT SIZES SHALL BE AS INDICATED IN THE SCHEDULE WHILE PIPE SIZES AND DETAILS ARE PROVIDED ON PLAN.
 - EXISTING STORMWATER PIT LOCATIONS AND INVERT LEVELS TO BE CONFIRMED BY SURVEY PRIOR TO COMMENCING WORKS ON SITE.
 - ALL STORMWATER PIPES Ø375 OR GREATER SHALL BE CLASS 2 (WITH HS2 SUPPORT) REINFORCED CONCRETE WITH RUBBER RING JOINTS UNLESS NOTED OTHERWISE.
 - ALL PIPES UP TO AND INCLUDING Ø300 TO BE UPVC GRADE SN8 UNO.
 - PIPE CLASS NOMINATED ARE FOR IN-SERVICE LOADING CONDITIONS ONLY. CONTRACTOR IS TO MAKE ANY NECESSARY ADJUSTMENTS REQUIRED FOR CONSTRUCTION CONDITIONS.
 - ALL CONCRETE PITS GREATER THAN 1000mm DEEP SHALL BE REINFORCED USING N12-200 EACH WAY CENTERED IN WALL AND BASE. LAP MINIMUM 300mm WHERE REQUIRED. ALL CONCRETE FOR PITS SHALL BE F_{cd}≥25 MPa. PRECAST PITS MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
 - IN ADDITION TO ITEM 6 ABOVE, ALL CONCRETE PITS GREATER THAN 3000mm DEEP SHALL HAVE WALLS AND BASE THICKNESS INCREASED TO 200mm.
 - PIPES SHALL BE LAID AS PER PIPE LAYING DETAILS. PARTICULAR CARE SHALL BE TAKEN TO ENSURE THAT THE PIPE IS FULLY AND EVENLY SUPPORTED. RAM AND PACK FILLING AROUND AND UNDER BACK OF PIPES AND PIPE FAUCETS, WITH NARROW EDGED RAMMERS OR OTHER SUITABLE TAMPING DETAILS.
 - CONCRETE PIPES UNDER, OR WITHIN THE ZONE OF INFLUENCE OF PAVED AREAS SHALL BE LAID USING HS2 TYPE SUPPORT, AS A MINIMUM, IN ACCORDANCE WITH AS 3725. AGGREGATE BACKFILL SHALL NOT BE USED FOR PIPE BEDDING AND OR HAUNCH/SIDE SUPPORT.
 - WHERE PIPE LINES ENTER PITS, PROVIDE 2m LENGTH OF STOCKING WRAPPED SLOTTED Ø100 UPVC TO EACH SIDE OF PIPE.
 - ALL SUBSOIL DRAINAGE LINES SHALL BE Ø100 SLOTTED UPVC WITH APPROVED FILTER WRAP LAID IN 300mm WIDE GRANULAR FILTER UNLESS NOTED OTHERWISE. LAY SUBSOIL LINES TO MATCH FALLS OF LAND AND/OR 1 IN 200 MINIMUM. PROVIDE CAPPED CLEANING EYE (RODDING POINT) AT UPSTREAM END OF LINE AND AT 30m MAX. CTS. PROVIDE SUBSOIL LINES TO ALL PAVEMENT / LANDSCAPED INTERFACES, TO REAR OF RETAINING WALLS (AS NOMINATED BY STRUCTURAL ENGINEER) AND AS SHOWN ON PLAN.
 - ALL PIPE GRADES 1 IN 200 MINIMUM UNO.
 - PROVIDE STEP IRONS IN PITS DEEPER THAN 1000mm.
 - MIN 600 COVER TO PIPE OBVERT BENEATH ROADS & MIN 400 COVER BENEATH LANDSCAPED AND PEDESTRIAN AREAS.
 - PIT COVERS IN TRAFFICABLE PAVEMENT SHALL BE CLASS D 'HEAVY DUTY'. THOSE LOCATED IN NON-TRAFFICABLE AREAS SHALL BE CLASS B 'MEDIUM DUTY' UNO.
 - PROVIDE CLEANING EYES (RODDING POINTS) TO PIPES AT ALL CORNERS AND T-JUNCTIONS WHERE NO PITS ARE PRESENT.
 - DOWN PIPES (DP) TO BE AS PER HYDRAULIC ENGINEERS DETAILS WITH CONNECTOR TO MATCH DP SIZE UNO ON PLAN. PROVIDE CLEANING EYE AT GROUND LEVEL.
 - PIPE LENGTHS NOMINATED ON PLAN OR LONGSECTIONS ARE MEASURED FROM CENTER OF PITS TO THE NEAREST 0.5m AND DO NOT REPRESENT ACTUAL LENGTH. THE CONTRACTOR IS TO ALLOW FOR THIS.

LEVELS NOTE:
LEVELS SHOWN TO BE +/- 1000mm FROM THOSE SHOWN. FINAL LEVELS SUBJECT TO FINAL GEOTECHNICAL INVESTIGATIONS, ARCHITECTURAL LAYOUT AND ACHIEVING A CUT TO FILL EARTHWORKS BALANCE OVER THE PROPERTY.


PIT SCHEDULE - NETWORK A					
PIT No.	GRATE RL	DEPTH	TYPE	GRATE SIZE	COMMENT
PIT WH1-A01	56.00		SGGP	900x900	
PIT WH1-A02	56.00		SGGP	900x900	
PIT WH1-A03	56.00		SGGP	900x900	
PIT WH1-A04	56.00		SGGP	900x900	
PIT WH1-A05	56.00		SGGP	900x900	
PIT WH1-A06	56.00		SGGP	900x900	
PIT WH1-A07	56.00		SGGP	900x900	
PIT WH1-A08	56.00		SGGP	900x900	
PIT WH1-A09	56.00		SGGP	900x900	
PIT WH1-A010	56.00		SGGP	900x900	
PIT WH1-A11	56.00		SGGP	900x900	
PIT WH1-A12	56.00		SGGP	900x900	
PIT WH1-A13	54.20		SGGP	900x900	

PIT SCHEDULE - NETWORK B					
PIT No.	GRATE RL	DEPTH	TYPE	GRATE SIZE	COMMENT
PIT WH1-B01	56.00		SGGP	900x900	
PIT WH1-B02	56.00		SGGP	900x900	
PIT WH1-B03	56.00		SGGP	900x900	
PIT WH1-B04	56.00		SGGP	900x900	
PIT WH1-B04A	56.00		SGGP	900x900	
PIT WH1-B05	56.00		SGGP	900x900	
PIT WH1-B06	56.00		SGGP	900x900	
PIT WH1-B06A	56.45		SJP	900x900	
PIT WH1-B06B	56.45		SJP	900x900	
PIT WH1-B07	56.00		SGGP	900x900	
PIT WH1-B08	56.00		SGGP	900x900	
PIT WH1-B09	56.00		SGGP	900x900	
PIT WH1-B10	56.00		SGGP	900x900	
PIT WH1-B11	56.00		SGGP	900x900	
PIT WH1-B12	56.00		SGGP	900x900	
PIT WH1-B13	56.00		SGGP	900x900	
PIT WH1-B14	56.00		SGGP	900x900	
PIT WH1-B15	56.00		SGGP	900x900	
PIT WH1-B16	56.00		SGGP	900x900	

PIT SCHEDULE - NETWORK C					
PIT No.	GRATE RL	DEPTH	TYPE	GRATE SIZE	COMMENT
PIT WH1-C01	56.45		SJP	900x900	
PIT WH1-C02	56.45		SJP	900x900	
PIT WH1-C03	56.45		SJP	900x900	
PIT WH1-C04	56.45		SJP	900x900	

PIT SCHEDULE - NETWORK X				
PIT No.	GRATE RL	DEPTH	TYPE	GRATE SIZE
PIT WH1-X01	54.45		SGGP	900x900
PIT WH1-X02	56.45		SGGP	900x900
PIT WH1-X03	56.45		SGGP	900x900
PIT WH1-X04	56.45		SGGP	900x900

FOR DEVELOPMENT APPLICATION



LEGEND:
LEVELS DATUM IS AHD.

EXISTING SITE LEVELS AND DETAILS BASED ON A PLAN OF SURVEY 20119 DE-01 BY STATIKER 26/09/20

- SGGP, SINGLE GRATED GULLY PIT
- SJP, SEALED JUNCTION PIT
- GD, GRATED DRAIN (300W x 2250 UNO)
- PROPOSED DRAINAGE LINE
- EXISTING ESTATE DRAINAGE LINE
- ROOFWATER DOWNPIPE (INDICATIVE)
- OVERLAND FLOW DIRECTION
- FINISHED PAVEMENT CONTOUR (MAJOR) 0.5m INTERVALS
- FINISHED PAVEMENT CONTOUR (MINOR) 0.1m INTERVALS
- EXISTING ESTATE CONTOUR

- STORMWATER DRAINAGE NOTES:**
- ALL STORMWATER WORKS TO BE COMPLETED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS3500.3:2003 PLUMBING AND DRAINAGE, PART 3: STORMWATER DRAINAGE.
 - THE MINOR (PIPED) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 20 YEAR ARI STORM EVENT AND THE MAJOR (OVERLAND) SYSTEM HAS BEEN DESIGNED FOR THE 1 IN 100 YEAR ARI STORM EVENT.
 - ALL FINISHED PAVEMENT LEVELS SHALL BE AS INDICATED ON FINISHED LEVELS PLANS SSDA511
 - PIT SIZES SHALL BE AS INDICATED IN THE SCHEDULE WHILE PIPE SIZES AND DETAILS ARE PROVIDED ON PLAN.
 - EXISTING STORMWATER PIT LOCATIONS AND INVERT LEVELS TO BE CONFIRMED BY SURVEY PRIOR TO COMMENCING WORKS ON SITE.
 - ALL STORMWATER PIPES Ø375 OR GREATER SHALL BE CLASS 2 (WITH HS2 SUPPORT) REINFORCED CONCRETE WITH RUBBER RING JOINTS UNLESS NOTED OTHERWISE.
 - ALL PIPES UP TO AND INCLUDING Ø300 TO BE uPVC GRADE SN8 UNO.
 - PIPE CLASS NOMINATED ARE FOR IN-SERVICE LOADING CONDITIONS ONLY. CONTRACTOR IS TO MAKE ANY NECESSARY ADJUSTMENTS REQUIRED FOR CONSTRUCTION CONDITIONS.
 - ALL CONCRETE PITS GREATER THAN 1000mm DEEP SHALL BE REINFORCED USING M2-200 EACH WAY CENTERED IN WALL AND BASE LAP MINIMUM 300mm WHERE REQUIRED. ALL CONCRETE FOR PITS SHALL BE F'c=25 MPa. PRECAST PITS MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
 - IN ADDITION TO ITEM 6 ABOVE, ALL CONCRETE PITS GREATER THAN 3000mm DEEP SHALL HAVE WALLS AND BASE THICKNESS INCREASED TO 200mm.
 - PIPES SHALL BE LAID AS PER PIPE LAYING DETAILS. PARTICULAR CARE SHALL BE TAKEN TO ENSURE THAT THE PIPE IS FULLY AND EVENLY SUPPORTED. RAM AND PACK FILLING AROUND AND UNDER BACK OF PIPES AND PIPE FAUCETS, WITH NARROW EDGED RAMMERS OR OTHER SUITABLE TAMPING DETAILS.
 - CONCRETE PIPES UNDER, OR WITHIN THE ZONE OF INFLUENCE OF PAVED AREAS SHALL BE LAID USING HS2 TYPE SUPPORT, AS A MINIMUM, IN ACCORDANCE WITH AS 3725. AGGREGATE BACKFILL SHALL NOT BE USED FOR PIPE BEDDING AND OR HAUNCH/SIDE SUPPORT.
 - WHERE PIPE LINES ENTER PITS, PROVIDE 2m LENGTH OF STOCKING WRAPPED SLOTTED Ø100 uPVC TO EACH SIDE OF PIPE.
 - ALL SUBSOIL DRAINAGE LINES SHALL BE Ø100 SLOTTED uPVC WITH APPROVED FILTER WRAP LAID IN 300mm WIDE GRANULAR FILTER UNLESS NOTED OTHERWISE. LAY SUBSOIL LINES TO MATCH FALLS OF LAND AND/OR 1 IN 200 MINIMUM. PROVIDE CAPPED CLEANING EYE (RODDING POINT) AT UPSTREAM END OF LINE AND AT 30m MAX. CTS. PROVIDE SUBSOIL LINES TO ALL PAVEMENT/ LANDSCAPED INTERFACES, TO REAR OF RETAINING WALLS (AS NOMINATED BY STRUCTURAL ENGINEER) AND AS SHOWN ON PLAN.
 - ALL PIPE GRADES 1 IN 200 MINIMUM UNO.
 - PROVIDE STEP IRONS IN PITS DEEPER THAN 1000mm.
 - MIN. 600 COVER TO PIPE OBVERT BENEATH ROADS & MIN. 400 COVER BENEATH LANDSCAPED AND PEDESTRIAN AREAS.
 - PIT COVERS IN TRAFFICABLE PAVEMENT SHALL BE CLASS D 'HEAVY DUTY'. THOSE LOCATED IN NON-TRAFFICABLE AREAS SHALL BE CLASS B 'MEDIUM DUTY' UNO.
 - PROVIDE CLEANING EYES (RODDING POINTS) TO PIPES AT ALL CORNERS AND T-JUNCTIONS WHERE NO PITS ARE PRESENT.
 - DOWN PIPES (DP) TO BE AS PER HYDRAULIC ENGINEERS DETAILS WITH CONNECTOR TO MATCH DP SIZE UNO ON PLAN. PROVIDE CLEANING EYE AT GROUND LEVEL.
 - PIPE LENGTHS NOMINATED ON PLAN OR LONGSECTIONS ARE MEASURED FROM CENTER OF PITS TO THE NEAREST 0.5m AND DO NOT REPRESENT ACTUAL LENGTH. THE CONTRACTOR IS TO ALLOW FOR THIS.


PIT SCHEDULE - NETWORK A					
PIT No.	GRATE RL	DEPTH	TYPE	GRATE SIZE	COMMENT
PIT WH3-A01	65.00		SGGP	900x900	
PIT WH3-A02	65.00		SGGP	900x900	
PIT WH3-A03	65.00		SGGP	900x900	
PIT WH3-A04	65.00		SGGP	900x900	
PIT WH3-A05	65.00		SGGP	900x900	
PIT WH3-A06	65.00		SGGP	900x900	
PIT WH3-A07	65.00		SGGP	900x900	
PIT WH3-A08	65.00		SGGP	900x900	
PIT WH3-A09	65.00		SGGP	900x900	
PIT WH3-A10	65.00		SGGP	900x900	
PIT WH3-A10A	65.00		SGGP	900x900	
PIT WH3-A11	65.00		SGGP	900x900	
PIT WH3-A11A	65.00		SGGP	900x900	
PIT WH3-A12	65.00		SGGP	900x900	
PIT WH3-A13	65.00		SGGP	900x900	
PIT WH3-A14A	65.00		SGGP	900x900	
PIT WH3-A15	65.00		SGGP	900x900	
PIT WH3-A15A	65.00		SGGP	900x900	
PIT WH3-A16	65.00		SGGP	900x900	
PIT WH3-A17	65.00		SGGP	900x900	

PIT SCHEDULE - NETWORK B					
PIT No.	GRATE RL	DEPTH	TYPE	GRATE SIZE	COMMENT
PIT WH3-B01	65.00		SGGP	900x900	
PIT WH3-B02	65.00		SGGP	900x900	
PIT WH3-B03	65.00		SGGP	900x900	
PIT WH3-B04	65.00		SGGP	900x900	
PIT WH3-B05	65.00		SGGP	900x900	
PIT WH3-B06	65.00		SGGP	900x900	
PIT WH3-B07	65.00		SGGP	900x900	
PIT WH3-B08	65.00		SGGP	900x900	
PIT WH3-B09	65.00		SGGP	900x900	
PIT WH3-B10	65.00		SGGP	900x900	
PIT WH3-B10A	65.00		SGGP	900x900	
PIT WH3-B11	65.00		SGGP	900x900	
PIT WH3-B12	65.00		SGGP	900x900	
PIT WH3-B12A	65.45		SJP	900x900	
PIT WH3-B12B	65.45		SJP	900x900	
PIT WH3-B13	65.00		SGGP	900x900	
PIT WH3-B13A	65.00		SGGP	900x900	
PIT WH3-B14	65.00		SGGP	900x900	


PIT SCHEDULE NETWORK C					
PIT No.	GRATE RL	DEPTH	TYPE	GRATE SIZE	COMMENT
PIT WH3-C01	65.45		SJP	900x900	
PIT WH3-C02	65.45		SJP	900x900	
PIT WH3-C03	65.45		SJP	900x900	
PIT WH3-C04	65.45		SJP	900x900	

NOTE:
PITS TO BE FITTED WITH OCEAN PROTECT OCEAN GUARD OG200 PIT INSERTS SHOWN THUS TOTAL NO OF PIT INSERTS = 42 REFER TO PIT SCHEDULE ABOVE


LEVELS NOTE:
LEVELS SHOWN TO BE +/-1000mm FROM THOSE SHOWN. FINAL LEVELS SUBJECT TO FINAL GEOTECHNICAL INVESTIGATIONS, ARCHITECTURAL LAYOUT AND ACHIEVING A CUT TO FILL EARTHWORKS BALANCE OVER THE PROPERTY.




FOR DEVELOPMENT APPLICATION



E2 CORRIDOR ALIGNMENT PLAN
SCALE 1:500




- LEGEND:**
LEVELS DATUM IS AHD.
- SW - DENOTES PROPOSED INFRASTRUCTURE STORMWATER
 - FW - DENOTES FUTURE WAREHOUSE STORMWATER
 - E2 - E2 CORRIDOR/WAREHOUSE BOUNDARY
 - LOW - INDICATIVE LOW-FLOW MEANDER
 - OSD - APPROXIMATE 100 YEAR OSD STORAGE AREA



FOR DEVELOPMENT APPLICATION

ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION			ARCHITECT			CLIENT			PROJECT			Costin Roe Consulting Pty Ltd.			DRAWING TITLE		
AMENDMENTS			SB ARCHITECTS			GPT The GPT Group			YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW			Consulting Engineers			E2 CORRIDOR ALIGNMENT PLAN		
21.05.21			21.05.21			21.05.21			Level 1, 8 Windmill Street Wahib Bay, Sydney NSW 2000			Tel: (02) 8551-7669 Fax: (02) 8541-3721			PRECISION COMMUNICATION ACCOUNTABILITY		
DATE			DATE			DATE			DESIGNED (DRAWN) DS			CHECKED (DS) APRIL '21			SCALE 1:500 AT A0 SIZE SHEET		
ISSUE			ISSUE			ISSUE			SIZE A0			SCALE AS SHOWN			SCALE 1:500 AT A0 SIZE SHEET		
AMENDMENTS			AMENDMENTS			AMENDMENTS			CNO REP: C01871.01-SSDA4.20			C01871.01-SSDA4.20			C01871.01-SSDA4.20		







LONGITUDINAL SECTION - GPT E2 CHANNEL

HORIZONTAL SCALE 1:500


VERTICAL SCALE 1:100

FOR DEVELOPMENT APPLICATION






- LEGEND:**
LEVELS DATUM IS AHD.
- EXISTING SITE LEVELS AND DETAILS BASED ON SURVEY INFORMATION PROVIDED BY BOXALL SURVEYORS (REF: 11017-001, DATED 23.07.2020)
- SGGP, SINGLE GRATED GULLY PIT
 - SJP, SEALED JUNCTION PIT
 - KIP, KERB INLET PIT
 - PROPOSED DRAINAGE LINE
 - FUTURE WAREHOUSE DRAINAGE LINE
 - 2 YEAR ARI TOP WATER LEVEL
 - 20 YEAR ARI TOP WATER LEVEL
 - 100 YEAR ARI TOP WATER LEVEL
 - OVERLAND FLOW DIRECTION
 - FINISHED PAVEMENT CONTOUR (MAJOR) 0.5m INTERVALS
 - FINISHED PAVEMENT CONTOUR (MINOR) 0.10m INTERVALS



ESTATE BASIN 2 PLAN
SCALE 1:250



FOR DEVELOPMENT APPLICATION





DEPTH 'H'	WALL THICKNESS 'TW'	WALL REINFORCEMENT	BASE THICKNESS 'TB'	BASE REINFORCEMENT
< 1.0m	150mm	-	150mm	-
1.0m-3.0m	150mm	N12-200 EACH WAY	150mm	N12-200 EACH WAY
3.0m-4.5m	200mm	N12-200 EACH WAY	200mm	N12-200 EACH WAY
4.5-6.0	200mm	N16-200 EACH WAY	200mm	N16-200 EACH WAY

ELEMENT	SLUMP	AGGREGATE (MAX. SIZE)	CEMENT TYPE	ADMIXTURE	F/C (MPa)
PIT	80	20	GP	NIL	32


- NOTES:**
- WHERE GULLY PIT IS LOCATED ON KERB RETURNS OR BULB OF CUL-DE-SACS PROVIDE CURVED PRECAST CONCRETE LINTELS.
 - SAG PITS SHALL HAVE LINTEL PLACED CENTRALLY ABOUT THE GRATE.
 - ALL REINFORCING TO HAVE 30 MIN. CLAR CONCRETE COVER.
 - FOR PITS DEEPER THAN 1200mm CLIMB RAILS SHALL BE PROVIDED.



SINGLE GRATED GULLY PIT - SGGP




SEALED PIT - SJP



SIEVE SIZE (mm)	WEIGHT PASSING (%)
19.0	100
2.36	100 TO 50
0.60	90 TO 50
0.30	60 TO 10
0.15	25 TO 0
0.075	10 TO 0

PIPE SIZE (mm)	l _c (mm)
≤ 900φ	150
1050φ	175
1200φ	200
1350φ	225
1500φ	250
1650φ	275
1800φ	300


ENGINEER TO SPECIFY TRENCH WIDTHS FOR PIPE SIZES GREATER THAN 1800φ



SIEVE SIZE (mm)	WEIGHT PASSING (%)
19.0	100
2.36	100 TO 50
0.60	90 TO 50
0.30	60 TO 10
0.15	25 TO 0
0.075	10 TO 0


PIPE SIZE (mm)	l _c (mm)
≤ 900φ	150
1050φ	175
1200φ	200
1350φ	225
1500φ	250
1650φ	275
1800φ	300

ENGINEER TO SPECIFY TRENCH WIDTHS FOR PIPE SIZES GREATER THAN 1800φ




SIEVE SIZE (mm)	WEIGHT PASSING (%)
75.0	100
9.5	100 TO 50
2.36	100 TO 50
0.60	50 TO 15
0.075	25 TO 0

SELECT FILL MATERIAL IN ACCORDANCE WITH TABLE 1 AS 3725




**SJP/CIS & SGGP/CIS (CAST IN SLAB) PIT DETAIL
GRATE/COVER SUPPORT
CAST-INTO PAVEMENT SLAB**

(ADOPT IN CONCRETE PAVEMENTS FOR SGGP's & SJP's, WHERE JOINTS ARE NOT LOCATED WITHIN PROXIMITY OF THE GRATE)




**SJP/CIS & SGGP/CIS (CAST IN SLAB) PIT DETAIL
GRATE/COVER SUPPORT
CAST-INTO PAVEMENT SLAB**

(ADOPT IN CONCRETE PAVEMENT FOR SGGP's & SJP's, WHERE PITS ARE LOCATED IN THE CORNER OF SLAB PANELS OR ADJACENT TO SLAB PANEL JOINTS)



SIEVE SIZE (mm)	WEIGHT PASSING (%)
19.0	100
9.5	100 TO 50
2.6	100 TO 30
0.60	50 TO 15
0.075	25 TO 0



200mm 0 500 1000 1500 2000mm
SCALE 1:20 AT A0 SIZE SHEET



FOR DEVELOPMENT APPLICATION




NOTES:


1. WHERE GULLY PIT IS LOCATED ON KERB RETURNS OR BULB OF CUL-DE-SACS PROVIDE CURVED PRECAST CONCRETE LINTELS.
2. SAG PITS SHALL HAVE LINTEL PLACED CENTRALLY ABOUT THE GRATE.
3. ALL REINFORCING TO HAVE 30 MIN. CLEAR CONCRETE COVER.
4. FOR PITS DEEPER THAN 1200mm STEP IRONS SHALL BE PROVIDED.
5. FOR ALL PITS IN ITV PAVEMENT AREAS, PIT WALLS ARE TO BE INCREASED IN THICKNESS BY 50mm AND REINFORCEMENT TO BE N16 BARS IN LIEU OF N12

DEPTH 'H'	WALL THICKNESS 'TW'	WALL REINFORCEMENT	ROOF THICKNESS 'TR'	ROOF REINFORCEMENT	BASE THICKNESS 'TB'	BASE REINFORCEMENT
~15m	150mm	N12-200 EACH WAY	150mm	N12-200 EACH WAY	150mm	N12-200 EACH WAY
1.5m–3.0m	150mm	N12-200 EACH WAY	150mm	N12-200 EACH WAY	150mm	N12-200 EACH WAY
3.0m–4.5m	200mm	N16-200 EACH WAY	200mm	N16-200 EACH WAY	200mm	N12-200 EACH WAY
4.5–6.0	250mm	N16-200 EACH WAY	250mm	N16-200 EACH WAY	250mm	N16-200 EACH WAY






PLAN VIEW AT PIPE OUTLET



DISSIPATER NOTES:


- PIPE TO REST ON, AND BE PACKED IN, BY RIP-RAP (SIZE AS NOTED).
- DISCHARGE INTO STREAM WHERE BEDROCK IS PRESENT, OTHERWISE SCOUR PROTECT AS REQUIRED.
- SCOUR PROTECT THE OPPOSITE BANK AS REQUIRED. SCOUR PROTECTION TO BE PROVIDED WHERE OPPOSITE BANK IS WITHIN 12-14 TIMES THE PIPE DIAMETER.
- RIP-RAP TO CONSIST OF ANGULAR RUN-OF-QUARRY ROCK (d50= 150mm MINIMUM) AS NOTED IN THE SCHEDULE. RIP-RAP TO BE MINIMUM THICKNESS OF LAYER TO BE 1.6x AVERAGE ROCK SIZE (d50).
- RIP-RAP IS TO BE PLACED OVER A 200mm LAYER OF MASS CONCRETE OVER NEEDLE-PUNCHED GEOTEXTILE A44.
- PLACE ROCK SO THAT IT FORMS A DENSE, WELL-GRADED MASS OF ROCK WITH A MINIMUM OF VOIDS. THE FINISHED RIP-RAP SURFACE SHOULD BE FREE OF POCKETS OF SMALL ROCK OR CLUSTERS OF LARGE ROCKS.
- GAPS IN RIP-RAP TO BE HAND PACKED WITH TOPSOIL & PLANTED WITH NATIVE SEDGES & RUSHES TO PROVIDE. THE INTENT IS FOR THERE TO BE NO VOIDS BETWEEN RIP-RAP BOULDERS.
- ENSURE THE FINISHED ROCK SURFACE BLENDS WITH THE SURROUNDING GROUND LEVELS. NO OVERFALL OR PROTRUSION OF ROCK SHOULD BE APPARENT.
- ENSURE THAT STORMWATER FROM SURROUNDING GROUND IS FREE TO ENTER THE STRUCTURE WITHOUT CAUSING UNDESIRABLE PONDING OR SCOUR.



ELEVATION AT PIPE OUTLET


BASIN OUTLET STRUCTURES

SCALE 1:50




TYPICAL SECTION - PLUNGE POOL

SCALE 1:50




TYPICAL DETAIL - PLUNGE POOL AND WEIR

SCALE 1:50




TYPICAL PLAN - PLUNGE POOL

SCALE 1:100




TYPICAL DETAIL - MAINTENANCE ACCESS DRIVE PAVEMENT CONSTRUCTION

SCALE 1:50




TYPICAL DETAIL - BATTER STABILISATION SCOUR PROTECTION


SCALE 1:50




FOR DEVELOPMENT APPLICATION




TYPICAL PLAN - BASIN 5 DISCHARGE ROCK DROP SILL
SCALE 1:100



TYPICAL DETAIL - COIR FIBRE LOG PLACEMENT ANY LOCATION
SCALE 1:20




TYPICAL DETAIL - ROCK DROP SILL AND WEIR
SCALE 1:20




APPLICABILITY:

- 1) ALL PROPOSED OR FUTURE PIPED DRAINAGE CONNECTIONS TO THE PROPOSED CREEK WORKS SHOULD HAVE A SIMILAR OUTLET TREATMENT TO THOSE SHOWN HERE.
- 2) MIN. ROCK SIZE IN OUTLET DEPRESSED APRON SHOULD BE 500-600mm.


TYPICAL STACKED ROCK HEADWALL TREATMENT
SCALE 1:20



TYPICAL DETAIL - ROCK DROP SILL AND WEIR
SCALE 1:20



SECTION B-B
SCALE 1:20



FOR DEVELOPMENT APPLICATION

ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION			21.05.21	A	AMENDMENTS			DATE	ISSUE	AMENDMENTS			DATE	ISSUE
AMENDMENTS					AMENDMENTS					AMENDMENTS				

ARCHITECT

SBA
ARCHITECTS

Studio 101, 81 Midvale Street, North Ryde NSW 1595
Tel: (02) 9551-7000 Fax: (02) 9551-7001
Email: info@sbaarchitects.com.au

CLIENT

GPT
The GPT Group

PROJECT

YIRIBANA LOGISTICS ESTATE
754-770 & 784-786 MAMRE ROAD
KEMPS CREEK NSW

DESIGNED: [] DRAWN: [] DATE: APRIL '21 CHECKED: [] DATE: [] SIZE: A0 SCALE: AS SHOWN CAD REF: C013874.06-SSDA455


Costin Roe Consulting Pty Ltd.
Consulting Engineers
Level 1, 8 Windmill Street
Wahia Bay, Sydney NSW 2000
Tel: (02) 9551-7000 Fax: (02) 9551-7001
Email: mail@costinroe.com.au


Costin Roe Consulting

PRECISION | COMMUNICATION | ACCOUNTABILITY

DRAWING TITLE
STORMWATER DRAINAGE DETAILS
SHEET 5


DRAWING No C013874.06-SSDA455 ISSUE A

[illegible]








ROADWORKS MASTER PLAN
SCALE 1:1000



FOR DEVELOPMENT APPLICATION



ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION		21.05.21	B	AMENDMENTS		DATE	ISSUE	AMENDMENTS	DATE	ISSUE	ARCHITECT	CLIENT	PROJECT	DESIGNED	DRAWN	CHECKED	DATE	SCALE	AS SHOWN	CAD REPLY	C013874.06-SSDA500	Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Windmill Street Wahib Bay, Sydney NSW 2000 Tel: (02) 8551-7669 Fax: (02) 8541-3721 email: mail@costinroe.com.au ©		PRECISION COMMUNICATION ACCOUNTABILITY		DRAWING TITLE ROADWORKS MASTER PLAN	DRAWING No C013874.06-SSDA500	ISSUE B
ISSUED FOR PRELIMINARY ONLY		09.04.21	A	AMENDMENTS		DATE	ISSUE	AMENDMENTS	DATE	ISSUE	ARCHITECT	CLIENT	PROJECT	DESIGNED	DRAWN	CHECKED	DATE	SCALE	AS SHOWN	CAD REPLY	C013874.06-SSDA500	Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Windmill Street Wahib Bay, Sydney NSW 2000 Tel: (02) 8551-7669 Fax: (02) 8541-3721 email: mail@costinroe.com.au ©		PRECISION COMMUNICATION ACCOUNTABILITY		DRAWING TITLE ROADWORKS MASTER PLAN	DRAWING No C013874.06-SSDA500	ISSUE B




PEDESTRIAN SLAB DETAILS




ROAD PAVEMENT DETAIL

SCALE 1:10
DESIGN TRAFFIC 1x10⁷ ESA's
DESIGN CBR VALUE OF 2%
NOTE: FINAL DESIGN SUBJECT TO FURTHER TESTING TO CONFIRM CBR VALUE



TYPICAL NEW / EXISTING PAVEMENT INTERFACE DETAIL



FOR DEVELOPMENT APPLICATION


ISSUED FOR STATE SIGNIFICANT DEVELOPMENT APPLICATION			AMENDMENTS			AMENDMENTS			AMENDMENTS		
21.05.21	A										
DATE	ISSUE		DATE	ISSUE		DATE	ISSUE		DATE	ISSUE	
ARCHITECT			CLIENT			PROJECT			DRAWING TITLE		
SB ARCHITECTS			GPT The GPT Group			YIRIBANA LOGISTICS ESTATE 754-770 & 784-786 MAMRE ROAD KEMPS CREEK NSW			ROADWORKS TYPICAL SECTIONS AND DETAILS		
Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Windmill Street Wahia Bay, Sydney NSW 2000 Tel: (02) 8551-7699 Fax: (02) 8541-3721 email: mail@costinroe.com.au			DESIGNED [] DRAWN [] DATE [] CHECKED [] SIZE [] SCALE [] CNO REF: []			PRECISION COMMUNICATION ACCOUNTABILITY			DRAWING No C013874.06-SSDA510		
ISSUE			ISSUE			ISSUE			ISSUE		




HORIZONTAL SCALE 1:500
VERTICAL SCALE 1:100



HORIZONTAL SCALE 1:500
VERTICAL SCALE 1:100




HORIZONTAL SCALE 1:500
VERTICAL SCALE 1:100




FOR DEVELOPMENT APPLICATION

[illegible]




TIERED REINFORCED EARTH WALL DETAILS
SCALE 1:50




REINFORCED EARTH WALL DETAILS
SCALE 1:20

NOTE:
INDICATIVE REINFORCEMENT LENGTHS SHOWN.
DESIGN TO BE CONFIRMED / PROVIDED BY D-C CONTRACTOR.




TYPICAL THRU' KEYSTONE RETAINING WALL
(1000 TO 3000 MAXIMUM RETAINED HEIGHT)


NOTE:
INDICATIVE REINFORCEMENT LENGTHS SHOWN.
DESIGN TO BE CONFIRMED / PROVIDED BY D-C CONTRACTOR.




TYPICAL ROCK BATTER WITH SHOTCRETE
SCALE 1:100



DETAIL 1:5




DETAIL 1:10



CONTIGUOUS PILE WALL TYPICAL SECTION
SCALE 1:50

NOTE:
SOCKET DEPTH NOTED IS MINIMUM INTO CLASS IV ROCK OR HIGHER. THIS IS TO BE CONFIRMED BY GEOTECHNICAL ENGINEER DURING INSTALLATION. IF SOFTER ROCK IS ENCOUNTERED, ENGINEER TO BE NOTIFIED IMMEDIATELY AND WILL ADVISE OF ADJUSTED SOCKET DEPTH.




CONTIGUOUS PILE WALL
SCALE 1:20


CONTIGUOUS PILE WALL SCHEDULE

PILE TYPE	MAX. HEIGHT "H" (m)	PILE DIA. (mm)	PILE SPACING (mm)	SOCKET DEPTH "S" (mm)	PILE REINFORCEMENT	CLOSED TIES	CAPPING BEAM
-	-	-	-	-	-	-	-


CONCRETE QUALITY					
ELEMENT	SLUMP	AGGREGATE (MAX. SIZE)	CEMENT TYPE	ADMIXTURE	F'c (MPa)
PILES	80	20	SL	NIL	32
SHOT CRETE	230	10	SL	NIL	32
CAPPING	80	20	GP	NIL	32




DETAIL OF 700x550 CAPPING BEAM
SCALE 1:20



FOR DEVELOPMENT APPLICATION



SWEPT PATH PLAN
SCALE 1:500



FUNCTIONAL LAYOUT PLAN
SCALE 1:250

10m 0 10 20 30 40 50 60 70 80 90 100m
SCALE 1:1000 AT A0 SIZE SHEET

FOR INFORMATION

ISSUED FOR INFORMATION ONLY				AMENDMENTS				AMENDMENTS				AMENDMENTS			
21.05.21				A				A				A			
DATE				ISSUE				DATE				DATE			
AMENDMENTS				AMENDMENTS				AMENDMENTS				AMENDMENTS			
ARCHITECT				CLIENT				PROJECT				DRAWING TITLE			
SBA ARCHITECTS				GPT The GPT Group				YIRIBANA LOGISTICS ESTATE				FUNCTIONAL LAYOUT PLAN			
754-770 & 784-786 MAMRE ROAD				KEMPS CREEK NSW				Level 1, 8 Windmill Street				TEMP ACCESS ROAD			
DESIGNED: DS				CHECKED: DS				CNO: REP: C01874.06-SK02				STAGE 2 - ULTIMATE			
DRAWN: JB				DATE: APRIL '21				COSTIN ROE CONSULTING PTY LTD.				DRAWING No			
CNO: REP: C01874.06-SK02				COSTIN ROE CONSULTING PTY LTD.				CONSULTING ENGINEERS				C013874.06-SK02			
CONSULTING ENGINEERS				PRECISION COMMUNICATION ACCOUNTABILITY				ISSUE				A			

Appendix B

MUSIC MODEL CONFIGURATION & PARAMETERS

B.1 Introduction

The MUSIC model was chosen to model water quality. This model, released by the Cooperative Research Centre for Catchment Hydrology (CRCCH), is a standard industry model for this purpose. MUSIC (the Model for Urban Stormwater Improvement Conceptualisation) is suitable for simulating catchment areas of up to 100 km² and utilises a continuous simulation approach to model water quality.

By simulating the performance of stormwater management systems, MUSIC can be used to predict if the proposed systems and changes to land use are appropriate for their catchments and capable of meeting specified water quality objectives (CRC 2002). The water quality constituents modelled in MUSIC, of relevance to this report, include Total Suspended Solids (TSS), Total Phosphorus (TP) and Total Nitrogen (TN).

The pollutant retention criteria set out in Section C3 of Council *DCP 2014* and nominated in **Section 7.1** of this report were used as a basis for assessing the effectiveness of the selected treatment trains.

The MUSIC model “13874.06-Rev1.sqz” was set up to examine the effectiveness of the water quality treatment train and to predict if Council’s requirements have been achieved.

Modelling parameters used are based on those nominated in the Sydney Catchment Management Authority (SCA) document *Using Music in Sydney’s Drinking Water Catchment – A Sydney Catchment Authority Standard (2012)* and *Draft NSW MUSIC Modelling Guidelines (2011)*.

B.2 Rainfall Data

As per the recommendation of Table 3-1 of *Draft NSW MUSIC Modelling Guidelines (2011)*, six-minute pluviographic data for the Sydney Meteorological Office Station was sourced from the Bureau of Meteorology (BOM) as nominated below. Evapo-transpiration data for the period was sourced from the Sydney Monthly Areal PET data set supplied with the MUSIC software.

Input	Data Used
Rainfall Station	67113 Penrith Lakes AWS
Rainfall Period	1999 – 2008 (10 years)
Mean Annual Rainfall (mm)	712
Evapo- transpiration	Sydney Monthly Areal PET
Model Time step	6 minutes

B.3 Rainfall Runoff Parameters

Parameter	Value
Rainfall Threshold	1.40
Soil Storage Capacity (mm)	105
Initial Storage (% capacity)	30
Field Capacity (mm)	70
Infiltration Capacity Coefficient a	150

Infiltration Capacity exponent b	3.5
Initial Depth (mm)	10
Daily Recharge Rate (%)	25
Daily Baseflow Rate (%)	10
Daily Seepage Rate (%)	0

B.4 Pollutant Concentrations & Source Nodes

Pollutant concentrations for source nodes are based on parameters adopted by the SCA as per **Table B.1**.

Flow Type	Surface Type	TSS (log ₁₀ values)		TP (log ₁₀ values)		TN (log ₁₀ values)	
		Mean	Std Dev.	Mean	Std Dev.	Mean	Std Dev.
Baseflow	Roof	NA	NA	NA	NA	NA	NA
	Roads	1.20	0.17	-0.85	0.19	0.11	0.12
Stormflow	Roof	1.30	0.32	-0.89	0.25	0.30	0.19
	Roads	2.43	0.32	-0.30	0.25	0.34	0.19

Table B.1. Pollutant Concentrations

The MUSIC model has been setup with a treatment train approach based on the pollutant concentrations in **Table B.1** above.

The relevant stormwater catchment sizes are listed below in **Table B.2** and their configuration within the MUSIC model.

Catchment	Area (Ha)	Source Node	% Impervious	Stormwater Treatment
Roof	15.53	Roof	100	Bio-Retention
Carpark	2.57	Sealedroad	90	GPT & Bio-Retention
Hardstand	5.57	Sealedroad	100	GPT & Bio-Retention
Firetrail	2.53	Sealedroad	100	GPT & Bio-Retention
On-Site Detention Basin	2.06	Revegetatedland	0	-
Landscaping	1.73	Revegetatedland	0	GPT & Bio-Retention
Road Network	2.51	Sealedroad	90	Bio-Retention
Bypass (Landscaping)	1.06	Revegetatedland	0	-
Total	33.56			

Table B.2. Music Model Source Nodes

B.5 Treatment Nodes

Bio-Retention system and Ocean Protect OceanGuard (GPT) nodes have been used in the modelling of the development.

It is noted that the bio-retention node, within the flood storage basin, has been modelled in MUSIC to simulate treatment during low flow and non-flood scenario. The bio-retention node allows for a high flow bypass which would operate when flows from the site are greater than 100 l/s. This flow is based on the 1 in 3-month flow from the site and would simulate a conservative model for the site during the period when the flood basin operates and would not provide treatment to the site. It is noted that the model is conservative in that the flood basin is not expected to operate until flood events which are greater than 1 in 5-year ARI which would mean that possible higher treatment of stormwater from the site. This is considered a suitable and conservative modelling approach for the treatment of stormwater from this site.

B.6 Results

Table B.3 shows the results of the MUSIC analysis. The reduction rate is expressed as a percentage and compares the post-development pollutant loads without treatment versus post-development loads with treatment.

	Source	Residual Load	% Reduction
Total Suspended Solids (kg/yr)	22900	3270	85.7
Total Phosphorus (kg/yr)	48.3	17.7	63.5
Total Nitrogen (kg/yr)	374	178	52.3
Gross Pollutants (kg/yr)	4550	96.1	97.9

Table B.3. MUSIC analysis results

The model results indicate that, through the use of the STM in the treatment train, pollutant load reductions for Total Suspended Solids, Total Phosphorous, Total Nitrogen and Gross Pollutants will meet the requirements of Section C3 of Council's *DCP 2014* on an overall catchment basis.

B.7 Modelling Discussion

MUSIC modelling has been performed to assess the effectiveness of the selected treatment trains and to ensure that the pollutant retention requirements of C3 of PCC's DCP2014 have been met.

The MUSIC modelling has shown that the proposed treatment train of STM will provide stormwater treatment which will meet PCC requirements in an effective and economical manner.

Hydrocarbon and oil & grease removal cannot be modelled with MUSIC software. As an industrial estate with users for individual development sites not known, the exact levels of hydrocarbons would not be known however given the expected use of the site as a warehouse distribution centre these pollutants would not be expected to be large. Potential sources of hydrocarbons and/or oil & grease which drain to the stormwater system would be limited to leaking engine sumps or for accidental fuel spills/leaks and leaching of bituminous pavements (car parking only). The potential for these pollutants is low and published data from the CSIRO indicates that average concentrations from industrial sites are in the order of 10mg/L and we would expect source loading from this site to be near to or below this concentration.

Given the expected low source loadings of hydrocarbons and oil/grease and removal efficiencies of the treatment devices and bio-retention systems we consider that the requirements of the Penrith City Council have been met.

Appendix C

DRAFT

CONSTRUCTION SOIL AND WATER MANAGEMENT PLAN

C.1 Introduction

An erosion and sediment control plan (ESCP) is shown on drawing **Co13874.06-DA200** with details on **DA250**. These are conceptual plans only providing sufficient detail to clearly show that the works can proceed without undue pollution to receiving waters. A detailed plan will be prepared once consent is given and before works start.

C.2 General Conditions

1. The ESCP will be read in conjunction with the engineering plans, and any other plans or written instructions that may be issued in relation to development at the subject site.
2. Contractors will ensure that all soil and water management works are undertaken as instructed in this specification and constructed following the guidelines stated in *Managing Urban Stormwater, Soils and Construction (1998) "The Blue Book"* and Penrith City Council specifications.
3. All subcontractors will be informed of their responsibilities in minimising the potential for soil erosion and pollution to down slope areas.

C.3 Land Disturbance

1. Where practicable, the soil erosion hazard on the site will be kept as low as possible and as recommended in Table C.1.

Land Use	Limitation	Comments
Construction areas	Limited to 5 (preferably 2) metres from the edge of any essential construction activity as shown on the engineering plans.	All site workers will clearly recognise these areas that, where appropriate, are identified with barrier fencing (upslope) and sediment fencing (downslope), or similar materials.
Access areas	Limited to a maximum width of 5 metres	The site manager will determine and mark the location of these zones onsite. They can vary in position so as to best conserve existing vegetation and protect downstream areas while being considerate of the needs of efficient works activities. All site workers will clearly recognise these boundaries.
Remaining lands	Entry prohibited except for essential management works	

Table C.1 Limitations to access

C.4 Erosion Control Conditions

1. Clearly visible barrier fencing shall be installed as shown on the plan and elsewhere at the discretion of the site superintendent to ensure traffic control and prohibit unnecessary site disturbance. Vehicular access to the site shall be limited to only those essential for construction work and they shall enter the site only through the stabilised access points.
2. Soil materials will be replaced in the same order they are removed from the ground. It is particularly important that all subsoils are buried and topsoils remain on the surface at the completion of works.
3. Where practicable, schedule the construction program so that the time from starting land disturbance to stabilisation has a duration of less than six months.
4. Notwithstanding this, schedule works so that the duration from the conclusion of land shaping to completion of final stabilisation is less than 20 working days.
5. Land recently established with grass species will be watered regularly until an effective cover has properly established and plants are growing vigorously. Further application of seed might be necessary later in areas of inadequate vegetation establishment.
6. Where practical, foot and vehicular traffic will be kept away from all recently established areas
7. Earth batters shall be constructed in accordance with the Geotechnical Engineers Report or with as low a gradient as practical but not steeper than:
 - 2H:1V where slope length is less than 7 metres
 - 2.5H:1V where slope length is between 7 and 10 metres
 - 3H:1V where slope length is between 10 and 12 metres
 - 4H:1V where slope length is between 12 and 18 metres
 - 5H:1V where slope length is between 18 and 27 metres
 - 6H:1V where slope length is greater than 27 metres
8. All earthworks, including waterways/drains/spillways and their outlets, will be constructed to be stable in at least the design storm event.
9. During windy weather, large, unprotected areas will be kept moist (not wet) by sprinkling with water to keep dust under control. In the event water is not available in sufficient quantities, soil binders and/or dust retardants will be used or the surface will be left in a cloddy state that resists removal by wind.

C.5 Pollution Control Conditions

1. Stockpiles will not be located within 5 metres of hazard areas, including likely areas of high velocity flows such as waterways, paved areas and driveways. Silt/ sediment fences and appropriate stabilisation of stockpiles are to be provided as detailed on the drawings.
2. Sediment fences will:
 - a) Be installed where shown on the drawings, and elsewhere at the discretion of the site superintendent to contain the coarser sediment fraction (including aggregated fines) as near as possible to their source.
 - b) Have a catchment area not exceeding 720 square meters, a storage depth (including both settling and settled zones) of at least 0.6 meters, and internal dimensions that provide maximum surface area for settling, and
 - c) Provide a return of 1 metre upslope at intervals along the fence where catchment area exceeds 720 square meters, to limit discharge reaching each section to 10 litres/second in a maximum 20-year t_c discharge.
3. Sediment removed from any trapping device will be disposed in locations where further erosion and consequent pollution to down slope lands and waterways will not occur.
4. Water will be prevented from directly entering the permanent drainage system unless it is relatively sediment free (i.e. the catchment area has been permanently landscaped and/or likely sediment has been treated in an approved device). Nevertheless, stormwater inlets will be protected.
5. Temporary soil and water management structures will be removed only after the lands they are protecting are stabilised.

C.6 Waste Management Conditions

Acceptable bind will be provided for any concrete and mortar slurries, paints, acid washings, lightweight waste materials and litter. Clearance service will be provided at least weekly.

C.7 Site Inspection and Maintenance

1. A self-auditing program will be established based on a Check Sheet. A site inspection using the Check Sheet will be made by the site manager:
 - At least weekly.
 - Immediately before site closure.
 - Immediately following rainfall events in excess of 5mm in any 24-hour period.

The self-audit will include:

- Recording the condition of every sediment control device
- Recording maintenance requirements (if any) for each sediment control device

- Recording the volumes of sediment removed from sediment retention systems, where applicable
 - Recording the site where sediment is disposed
 - Forwarding a signed duplicate of the completed Check Sheet to the project manager/developer for their information
2. In addition, a suitably qualified person will be required to oversee the installation and maintenance of all soil and water management works on the site. The person shall be required to provide a short monthly written report. The responsible person will ensure that:
- The plan is being implemented correctly
 - Repairs are undertaken as required
 - Essential modifications are made to the plan if and when necessary

The report shall carry a certificate that works have been carried out in accordance with the plan.

3. Waste bins will be emptied as necessary. Disposal of waste will be in a manner approved by the Site Superintendent.
4. Proper drainage will be maintained. To this end drains (including inlet and outlet works) will be checked to ensure that they are operating as intended, especially that,
- No low points exist that can overtop in a large storm event
 - Areas of erosion are repaired (e.g. lined with a suitable material) and/or velocity of flow is reduced appropriately through construction of small check dams or installing additional diversion upslope.
 - Blockages are cleared (these might occur because of sediment pollution, sand/soil/spoil being deposited in or too close to them, breached by vehicle wheels, etc.).
5. Sand/soil/spoil materials placed closer than 2 meters from hazard areas will be removed. Such hazard areas include and areas of high velocity water flows (e.g. waterways and gutters), paved areas and driveways.
6. Recently stabilised lands will be checked to ensure that erosion hazard has been effectively reduced. Any repairs will be initiated as appropriate.
7. Excessive vegetation growth will be controlled through mowing or slashing.
8. All sediment detention systems will be kept in good, working condition. In particular, attention will be given to:
- a) Recent works to ensure they have not resulted in diversion of sediment laden water away from them
 - b) Degradable products to ensure they are replaced as required, and
 - c) Sediment removal, to ensure the design capacity or less remains in the settling zone.
9. Any pollutants removed from sediment basins or litter traps will be disposed of in areas where further pollution to down slope lands and waterways should not occur.

10. Additional erosion and/or sediment control works will be constructed as necessary to ensure the desired protection is given to down slope lands and waterways, i.e. make ongoing changes to the plan where it proves inadequate in practice or is subjected to changes in conditions at the work site or elsewhere in the catchment.
11. Erosion and sediment control measures will be maintained in a functioning condition until all earthwork activities are completed and the site stabilised
12. Litter, debris and sediment will be removed from the gross pollutant traps and trash racks as required.

EROSION AND SEDIMENT CONTROL WEEKLY SITE INSPECTION SHEET

LOCATION
 INSPECTION OFFICER DATE
 SIGNATURE

Legend: ☐ OK ☐ Not OK N/A Not applicable

Item	Consideration	Assessment
1	Public roadways clear of sediment.
2	Entry/exit pads clear of excessive sediment deposition.
3	Entry/exit pads have adequate void spacing to trap sediment.
4	The construction site is clear of litter and unconfined rubbish.
5	Adequate stockpiles of emergency ESC materials exist on site.
6	Site dust is being adequately controlled.
7	Appropriate drainage and sediment controls have been installed prior to new areas being cleared or disturbed.
8	Up-slope "clean" water is being appropriately diverted around/through the site.
9	Drainage lines are free of soil scour and sediment deposition.
10	No areas of exposed soil are in need of erosion control.
11	Earth batters are free of "rill" erosion.
12	Erosion control mulch is not being displaced by wind or water.
13	Long-term soil stockpiles are protected from wind, rain and stormwater flow with appropriate drainage and erosion controls.
14	Sediment fences are free from damage.
15	Sediment-laden stormwater is not simply flowing "around" the sediment fences or other sediment traps.
16	Sediment controls placed up-slope/around stormwater inlets are appropriate for the type of inlet structure.
17	All sediment traps are free of excessive sediment deposition.
18	The settled sediment layer within a sediment basin is clearly visible through the supernatant prior to discharge such water.
19	All reasonable and practicable measures are being taken to control sediment runoff from the site.
20	All soil surfaces are being appropriately prepared (i.e. pH, nutrients, roughness and density) prior to revegetation.
21	Stabilised surfaces have a minimum 70% soil coverage.
22	The site is adequately prepared for imminent storms.
23	All ESC measures are in proper working order.