

**A-92-01 - INTERNAL FINISHES SCHEDULE**

## REVIEW RECORD

Issue Status	<input type="checkbox"/> Preliminary	<input checked="" type="checkbox"/> Tender	<input type="checkbox"/> Construction
--------------	--------------------------------------	--	---------------------------------------

*Check box field→*

Author	Interior Designer	Pascale de Guio	10.08.2020
--------	-------------------	-----------------	------------

Checked	Project Architect	Leanne Mitchell	10.08.2020
---------	-------------------	-----------------	------------

Approved	Project Director	Russell Lee	10.08.2020
----------	------------------	-------------	------------

## REVISIONS RECORD OF THIS DOCUMENT

Rev	Date	Revision Description
A	10.07.2020	Issue for Tender
B	10.08.2020	Tender Addendum

## **A-92-01 - INTERNAL FINISHES SCHEDULE**

### **EDITIONS AND REVISIONS FORMAT OF THIS DOCUMENT**

#### **Revision indicators**

This document may be issued in one or more editions. Each edition, whether original or revised, is identified by matching revision indicators in the file name and in the document footer.

Revision indicators are either numerical series or alphabetical series according to the status of each edition as follows:

- Numerical series: Rev 1 begins the initial tender issue before advancing to the formal numerical series.
- Alphabetical series: Rev A begins the formal approved for construction (AFC) series on signing of the contract, then advances through B, C etc when revised and re-issued.

Changes within revised editions

Changes that are made in the latest and/or previous editions are indicated and identified as follows:

- If an item is added or amended in the latest edition, it is marked by the latest revision indicator appearing in the Rev column (e.g. T01).
- Changes of the legend in the latest edition are displayed as follows☺
  - Refer to bold red text for all revisions
- When changes are made, the whole document is reissued as a revised latest edition.
- Changes in formatting, punctuation, spelling corrections and other minor matters are not identified unless substantive.
- Changes should always be fully comprehended by comparison with previous editions.

#### **REVISIONS & ISSUES**

Revisions are a means of identifying and tracking changes in red to the document and a copy of every revision is kept for audit purposes.

Issues are points in the process when the document is provided to an external party.




An issue therefore can contain a number of revisions; similarly a single (unamended) revision can be part of several issues. Revisions and issues should therefore not be confused with each other.

All lead times indicating “in stock” was confirmed on the date of issue. Contractor to confirm lead times prior to ordering and notify Cox Architecture of any discrepancies

Nominated Architects: Joe Agius (No 6491) & Russell Lee (No 6367)

© Copyright 2005 Cox Architecture Pty Limited



## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
ACP01	Ground Floor Function room	Martini acoustic panels	<b>Product:</b> Martini Absorb XHD75 <b>Size:</b> 75mm <b>Finish:</b> P05 <b>Fire Rating:</b> Group 01 <b>Note:</b> To be fixed directly to u/s of slab, 10mm shadowline <b>Refer to RCP</b>		CSR or equivalent	-	B
ACS01	First floor Function room	Acoustic Ceiling Slatted	<b>Type:</b> Supaslat <b>Series:</b> Profile 5 <b>Finish:</b> Supafinish White SF <b>Dimensions:</b> 18x70 <b>Spacing/Configuration:</b> 57mm <b>Backing:</b> Grey FRIAT integrated acoustic textile  <b>Fire Rating Class:</b> Group 3 <b>Fixing:</b> SST200 concealed fixing system <b>Notes:</b> Concept Veneer and matching edges on MR MDF	 <p>60mm WIDE CROSS BATTEN @ 800 MAX CENTRES, INSET UP TO 400mm</p> <p>IF SPECIFIED (SHOWN WHITE FOR CLARITY)</p> <p>HP50 INSULATION IF SPECIFIED</p> <p>END VIEW SCALE 1:4</p>	<b>Supawood</b> Vanessa Lesniak <a href="mailto:Vanessa@supawood.com.au">Vanessa@supawood.com.au</a> 0414 876 277	TBC	A
COF01/SE01	Columns and exposed beams.	Concrete: Off form	<b>Class 2C –</b> Colour controlled concrete – natural <b>Applied finish:</b> Clear sealer		Off form finish.		A

## INTERIOR SCHEDULES

.10.08.2020



## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
CPT01	Ground floor halls	Carpet tiles	<b>Product:</b> Tractionback modular carpet <b>Range:</b> TBC <b>Tile Size:</b> 1000 x 1000mm <b>Yarn Type:</b> Milliken WearOn BCF Nylon Type 6,6 <b>Tile Backing:</b> Tractionback, PVC-Free Comfort Plus® ES Cushion Secondary with Synthetic Woven/Non-Woven Composite. A high friction coating applied <b>Fire Rating:</b> TBC <b>Trolley Storage:</b> Provide custom sized trolleys 2 x 1m. <b>Notes:</b> Allow to order additional 10% spare  <b>Price:</b> \$60 + GST supply and install.	 TBC	<b>Milliken Ontera</b> Daniella Savian <a href="mailto:Daniella.Savian@Milliken.com">Daniella.Savian@Milliken.com</a> 0455 333 634		A
CPT02	Level one halls	Broadloom carpet	<b>Product:</b> Heavy duty commercial woven Axminster carpet – Custom design <b>Composition:</b> 80% Wool 20% Nylon <b>Underlay:</b> Commercial dual bonded grade underlay to appropriate commercial standards. <b>Colour and design:</b> custom – TBC <b>Note:</b> Hand trial sample and artwork to be approved. Image is indicative only Allow for 5% additional for spares <b>Fire Rating:</b> <b>Notes:</b> Allow to order additional 10% spare  Allow for angle at threshold and ensure carpet sits flush with tile.  <b>Price:</b> \$79.50 /sqm supply and install by Briton's preferred supplier		<b>BRINTONS</b> Maggie <a href="mailto:maggie@questforfloors.com">maggie@questforfloors.com</a>	14 weeks	A





## INTERIOR SCHEDULES

.10.08.2020

## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
CTF01	Along glazing Ground floor and level one	Blockout Curtains to Ground floor and Level one halls	<b>Product:</b> Silent gliss 5600 curtain  <b>Fabric</b> Zepel Range: Allusion Colour: TBC James Dunlop solar line Block out lining polyester Dry cleanable  <b>Notes:</b> Block out curtains with sheer layer, track to be recessed into pelmet detail.		Silent Gliss	-	A
EPX01	Refer to finishes plans	Epoxy sealed concrete flooring	<b>Product:</b> Metz 33-SL Sip resistance epoxy topping. <b>Notes:</b> Create falls using Metz 10 epoxy concrete with Metz 33-SL applied to top. Allow to form coved skirting at 150mm		<b>Metz</b> Louise Mychael louise@metztiles.com.au 0425 314 845		A
FB01	Operable wall	Acoustic Fabric lining	<b>Product:</b> Metric <b>Code:</b> 466014 <b>Colour:</b> TBC <b>Cost:</b> \$45/m2 of finish material. <b>Acoustic rating:</b> 0.90NRC		<b>Fabric</b> <b>Kvdrat Maharam</b> Carly Tyrell 0409800932		A

## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
LAM01	Amenities Toilet Partitions	High Pressure Laminate	<b>Product:</b> Compact Laminate (13mm) <b>Colour:</b> Raw Birchply <b>Code:</b> 8910 <b>Finish:</b> Natural finish <b>Size:</b> <b>Fire Rating:</b>		<b>Laminex</b> Naomi Ide <a href="mailto:naomi.ide@laminex.com.au">naomi.ide@laminex.com.au</a> 0407 750 080	3 days if in stock	A
LAM02	Joinery where noted. Sick Bay	High Pressure Laminate	<b>Product:</b> High Pressure Laminate – Absolute Matte <b>Colour:</b> White <b>Finish:</b> Matte <b>Size:</b> 3600mm x 1200mm <b>Fire Rating:</b> <b>Notes:</b> Fingerprint resistant surface		<b>Laminex</b> Naomi Ide <a href="mailto:naomi.ide@laminex.com.au">naomi.ide@laminex.com.au</a> 0407 750 080	TBC	A
LAM03	Lift car ceiling finish	Laminate	<b>Product:</b> Laminex Laminate <b>Colour:</b> Black <b>Finish:</b> Matte <b>Size:</b> 3600mm x 1200mm <b>Fire Rating:</b> Group 1		<b>Laminex</b> Naomi Ide <a href="mailto:naomi.ide@laminex.com.au">naomi.ide@laminex.com.au</a> 0407 750 080	TBC	B
MAT01	Ground floor along glazing.	Entrance Matting	<b>Product:</b> Recessed Duramat entry mat <b>Size:</b> Refer to drawings Approx 1.5m x 100m L (cos) can be tailored to meet width and length requirements with neat butt join <b>Colour:</b> Midnight Black extrusion. <b>Thickness:</b> 10mm <b>Construction:</b> Closed <b>Fire Rating:</b> <b>Note:</b> Allow for metal angle around all		<b>Birrus</b> Melissa McRae <a href="mailto:melissa@birrusmatting.com.au">melissa@birrusmatting.com.au</a> 0419 377 184	TBC	A





## INTERIOR SCHEDULES

.10.08.2020

## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
			sides to recess.				
MIR01	Amenities and Lift car	Mirror	<b>Product:</b> MirraEcho on Toughened Glass <b>Finish:</b> Safety back mirror Polished edge (frameless) <b>Colour:</b> Clear <b>Size:</b> 6mm thick 3660 x 2440mm TBC <b>Fire Rating:</b> <b>Notes:</b> to Australian Standards		<b>Viridian</b> Maria Murace <a href="mailto:mamurace@csr.com.au">mamurace@csr.com.au</a> 0427 369 322	Usually in stock	A
MIR02	Ground floor Back bar	Mirror	<b>Product:</b> MirraEcho on Toughened Smoked grey Glass <b>Finish:</b> Safety back mirror Polished edge (frameless) <b>Colour:</b> grey <b>Size:</b> 6mm thick <b>Fire Rating:</b> <b>Notes:</b> to Australian Standards		<b>Viridian</b> Maria Murace <a href="mailto:mamurace@csr.com.au">mamurace@csr.com.au</a> 0427 369 322		A
MIR03	Level one Back bar	Mirror	<b>Product:</b> MirraEcho on Toughened <b>Finish:</b> Safety back mirror Polished edge (frameless) <b>Colour:</b> Bronze <b>Size:</b> 6mm thick <b>Fire Rating:</b> <b>Notes:</b> to Australian Standards		<b>Viridian</b> Maria Murace <a href="mailto:mamurace@csr.com.au">mamurace@csr.com.au</a> 0427 369 322		A
MT01	Canopy bar. Ground Floor	Metal	<b>Product:</b> 20 x 20 SHS <b>Colour:</b> PC01 <b>Finish:</b> Powdercoat			TBC	A

## A-92-01 - INTERNAL FINISHES SCHEDULE





CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
MT02	Canopy bar Level 1	Metal	<b>Product:</b> 20 x 20 SHS <b>Colour:</b> PC02 <b>Finish:</b> Powdercoat <b>Note:</b> image is indicative – refer to 3D visuals			TBC	A
MT03	Ground Floor: And Level one Bar canopy	Metal mesh	<b>Product:</b> Expanded perforated metal <b>Code:</b> R07962 <b>Thickness:</b> 1mm <b>Finish:</b> Powdercoated PC01 to ground floor and PC02 to level one. <b>Open area:</b> 62% <b>Diameter:</b> 7.94 <b>Centres:</b> 9.55 <b>Standard sheet size:</b> 2440mm x 1220mm TBC		Locker Group  <b>Sample to be provided to Cox for approval prior to ordering</b>		A
MT04	Stainless steel finish to mirror edge <b>and lift car</b>	Coloured Stainless steel	<b>Product:</b> Rimex stainless steel <b>Finish:</b> Granex or satin TBC <b>Colour:</b> Black <b>Thickness:</b> 3mm		Rimex Metals (02) 4340 5599	8-10 weeks	B
MT05	Stainless steel finish to mirror edge.	Coloured Stainless steel	<b>Product:</b> Rimex stainless steel <b>Finish:</b> Granex or satin TBC <b>Colour:</b> Quartz Champagne <b>Thickness:</b> 3mm		Rimex Metals (02) 4340 5599	8-10 weeks	A



## INTERIOR SCHEDULES

.10.08.2020





## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
MT05	Kick plate to entry doors.	Stainless steel	<b>Product:</b> Rimex stainless steel <b>Finish:</b> Granex or satin TBC <b>Colour:</b> Platinum Brush <b>Thickness:</b> 1.5mm <b>Size:</b> 200mm high		Rimex Metals (02) 4340 5599		A
MT06	End cap to bathroom walls.		<b>Product:</b> Metal plate <b>Finish:</b> Powdercoated <b>Colour:</b> to match wall tile				A
P01	Entry doors	Wall Paint	<b>Product:</b> Dulux Wash and Wear Paint <b>Type:</b> Acrylic <b>Finish:</b> Matt <b>Colour:</b> TBC <b>Notes:</b> Low Sheen		<b>Dulux</b> Christine Kotsis 0412 805 654	Usually in stock	A
P02	General Ceilings	Ceiling Paint	<b>Product:</b> Dulux Wash and Wear Paint <b>Finish:</b> Matt <b>Colour:</b> TBC <b>Fire Rating:</b> <b>Notes:</b> Flat		<b>Dulux</b> Christine Kotsis 0412 805 654	Usually in stock	A





## INTERIOR SCHEDULES

.10.08.2020

## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
P03	Amenities and kitchen Ceilings	Ceiling Paint	<b>Product:</b> Dulux Wash and Wear Paint <b>Finish:</b> Flat Anti-Mould Resistant <b>Colour:</b> TBC <b>Notes:</b> Flat		<b>Dulux</b> Christine Kotsis 0412 805 654		A
P04	Walls Level one Ground floor where noted	Wall Paint	<b>Product:</b> Porters Paint French wash <b>Finish:</b> Low Sheen Acrylic <b>Colour:</b> Popcorn and French Wash in Elysian combination <b>Fire Rating:</b> <b>Notes:</b> Sample to be provided <b>To be applied as per manufacturers recommendation.</b>		<b>Porters Paint</b> Gema Beneitez-Martinez gema.beneitez@porters.com.au 0414 598 448		A
P05	Ground floor ceiling, services and wall	Wall Paint	<b>Product:</b> Dulux Wash and Wear Paint <b>Finish:</b> Flat Anti-Mould Resistant <b>Colour:</b> TBC <b>Notes:</b> Flat		<b>Dulux</b> Christine Kotsis 0412 805 654		A
PC01	Bar canopy Level one	Powdercoat	<b>Product:</b> Electro powdercoat <b>Finish:</b> Flat <b>Colour:</b> Black Ace <b>Code:</b> 9069116F <b>Notes:</b>		<b>Dulux</b> Christine Kotsis 0412 805 654		A



## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
PC02	Bar canopy Level one	Powdercoat	<b>Product:</b> Electro powdercoat <b>Finish:</b> Flat <b>Colour:</b> Medium Bronze <b>Code:</b> 9068183K <b>Fire Rating:</b> <b>Notes:</b>		<b>Dulux</b> Christine Kotsis 0412 805 654		A
PC03	Level one halls.	Powdercoat	<b>Product:</b> Powdercoat <b>Finish:</b> Mat <b>Colour:</b> TBC <b>Notes:</b> Colour to match the slatted ceilings for the metal service channels		<b>Dulux</b> Christine Kotsis 0412 805 654		A
PB01	Change room, Function Rooms	Plasterboard Ceiling	<b>Product:</b> 10mm Standard Plasterboard <b>Finish:</b> Painted – refer to P02 <b>Fire Rating:</b>		<b>Boral or equivalent</b>	Usually in stock	A
PB02	Amenities and kitchens	Moisture resistant plasterboard Ceiling	<b>Product:</b> 13mm Fire Wetstop™ <b>Finish:</b> Painted – refer to P02 <b>Fire Rating:</b> <b>Note:</b> allow for concealed LED lighting, refer to detail		<b>Boral or equivalent</b>	Usually in stock	A




## INTERIOR SCHEDULES

.10.08.2020

## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
PB03	Walls in Ground Halls	Acoustic panels	<b>Product:</b> Rigitone Gyprock Perforated Panel with 50mm backing insulation behind as per CSR manual to achieve NRC rating of .7 <b>Pattern:</b> Astral TBC Pattern to align. <b>Modular Dimension:</b> Approx 2400 x 1200mm Seamless effect with butt joins <b>Thickness:</b> 13mm <b>Perforation:</b> 6mm round 15mm centres <b>Fire Rating:</b> Group 1 <b>Supply Cost:</b> Trade \$53m2 +GST <b>Finish:</b> To specified Paint finish		CSR Himmel Gavin Bernardino 0418 200 281		A
PV1	Ground floor Halls	Concrete	<b>Class 2 Concrete slab</b> Exposed aggregate finish <b>Finish:</b> Honed <b>Colour:</b> Natural <b>Sealer:</b> Aquaron 3000				A
SE01	BOH As noted	Clear Penetrating Sealer (Concrete)	<b>Aquron 2000</b> <b>Fire Rating:</b>		Markham Global Ph: (07) 4153 6286		A
SE02	BOH As noted	Clear Penetrating Sealer (blockwork)	<b>Aquron 3000</b> <b>Fire Rating:</b>		Markham Global Ph: (07) 4153 6286		A



## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
SKT01	Skirting Ground Floor	Tile	<b>Range:</b> Core <b>Colour:</b> TBC <b>Finish:</b> Matt <b>Slip Rating:</b> P4 <b>Edge:</b> Rectified <b>Dimensions:</b> 400mm x 400mm <b>Thickness:</b> 15mm <b>Grout:</b> Epoxy tbc. Gaps 1.5mm <b>Fire Rating:</b> TBC		<b>Skheme</b> Mark Bridges <a href="mailto:markb@skheme.com">markb@skheme.com</a> 02 8755 2305	TBC	A
SKT02	Skirting Level 1	Terrazzo Floor tile	<b>Product:</b> Italian Terrazzo Tile – Special Order Items <b>Colour:</b> 26 Honed <b>Dimensions:</b> TBC <b>Thickness:</b> TBC <b>Fire Rating:</b> TBC  <b>Price:</b> \$110 /sqm + GST		<b>Surface Gallery</b> Scott Marrant <a href="mailto:Scott@surfacegallery.com.au">Scott@surfacegallery.com.au</a> 9566 2002	TBC	A
STN01	Vanity benchtop and bar benchtop Ground Floor	Reconstituted stone	<b>Product:</b> Caesarstone <b>Colour:</b> Piatto Black <b>Finish:</b> TBC <b>Code:</b> 3101 <b>Dimensions:</b> 3050 x 1440mm <b>Thickness:</b> 13mm <b>Fire Rating:</b> Fire Certification Provided <b>Notes:</b> Image is indicative only  <b>Price:</b> \$280 /sqm + GST for a single slab (project pricing applies for 20+ slabs)		<b>Caesarstone</b> Barbe Dolan <a href="mailto:barbe.dolan@caesarstone.com.au">barbe.dolan@caesarstone.com.au</a> 0400 493 647	Currently In Stock	A

## INTERIOR SCHEDULES

.10.08.2020





## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
STN02	bar benchtop Level One	Reconstituted stone	<b>Product:</b> Caesarstone <b>Colour:</b> Sleek Concrete <b>Finish:</b> TBC <b>Code:</b> 400 <b>Dimensions:</b> 3050 x 1440mm <b>Thickness:</b> 13mm <b>Fire Rating:</b> Fire Certification Provided <b>Notes:</b> Image is indicative only		<b>Caesarstone</b> Barbe Dolan barbe.dolan@caesarstone.com.au 0400 493 647	Currently In Stock	A
STN03	Amenities Vanities	Terrazzo slab	<b>Product:</b> Terrazzo Australian Marble slab <b>Colour:</b> Custom to match TL08 <b>Dimensions:</b> 2650 x 1250mm <b>Thickness:</b> 30mm  <b>Price:</b> \$450 /sqm + GST		<b>Terrazzo Australian Marble</b> Mark Donati mark@terrazzo.net.au 02 9672 1277		A
TL01	Amenities	Ceramic Floor Tile	<b>Range:</b> Core <b>Colour:</b> Warm grey <b>Finish:</b> Matt <b>Slip Rating:</b> P4 <b>Edge:</b> Rectified <b>Dimensions:</b> 300mm x 300mm <b>Grout:</b> Mapei Kerapoxy Colout 112 Grigio Medio (Medium Grey) <b>Fire Rating:</b> TBC  <b>Price:</b> \$23.90 /sqm + GST (over 200 sqm) \$19.90 /sqm + GST (over 500 sqm)		<b>Skheme</b> Mark Bridges markb@skheme.com 02 8755 2305	Currently in stock, 8-10 weeks if not	A

## INTERIOR SCHEDULES

.10.08.2020

## A-92-01 - INTERNAL FINISHES SCHEDULE




CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
TL02	Amenities	Large wall tile	<b>Colour:</b> Cool White <b>Finish:</b> Matt <b>Matt Size:</b> 900 x 300mm <b>Thickness:</b> 9mm <b>Grout:</b> White <b>Fire Rating:</b> N/A  <b>Price:</b> \$35 /sqm + GST		<b>Skheme</b> Mark Bridges <a href="mailto:markb@skheme.com">markb@skheme.com</a> 02 8755 2305	Currently in stock, 8 weeks if not	A
TL03	Bar BOH Ground	Wall tile	<b>Series:</b> Basics <b>Colour:</b> Black TBC <b>Finish:</b> matt with rectified edges <b>Size:</b> 300 x 600 x 10mm <b>Fire Rating:</b> N/A  <b>Price:</b> \$16.90 /sqm + GST		<b>Skheme</b> Mark Bridges <a href="mailto:markb@skheme.com">markb@skheme.com</a> 02 8755 2305	Currently in stock, 8-10 weeks if not	A
TL04a	Ground floor Level one bar	3D Wall Tile	<b>Product:</b> Stripes (Stripes Strip, Stripes Transition & Stripes Liso) <b>Colour:</b> Graphite Stone <b>Finish:</b> Matt <b>Edge:</b> Non-Rectified <b>Dimensions:</b> 300 x 75mm <b>Fire Rating:</b> N/A  <b>Price:</b> 2 x rows of Stripes Strip: \$145 /sqm +GST 1 x row of Stripes Transition: \$145 /sqm +GST	 (Stripes Strip) (Stripes Transition)	<b>Earp Bros</b> Jullanar Obeid <a href="mailto:jullanaro@earp.com.au">jullanaro@earp.com.au</a> 0422 025 626  <b>Refer to Bar drawing</b>	Approximately 10 weeks	A
TL04b	Ground floor Level one bar	3D Wall Tile	<b>Product:</b> Stripes (Stripes Strip, Stripes Transition & Stripes Liso) <b>Colour:</b> Ice White <b>Finish:</b> Matt <b>Edge:</b> Non-Rectified <b>Dimensions:</b> 300 x 75mm	 (Stripes Strip)	<b>Earp Bros</b> Jullanar Obeid <a href="mailto:jullanaro@earp.com.au">jullanaro@earp.com.au</a> 0422 025 626  <b>Refer to Bar drawing</b>	Approxim	A



## INTERIOR SCHEDULES





.10.08.2020

## A-92-01 - INTERNAL FINISHES SCHEDULE



CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
			<b>Fire Rating:</b> N/A  <b>Price:</b> 2 x rows of Stripes Strip: \$145 /sqm +GST 1 x row of Stripes Transition: \$145 /sqm +GST	 (Stripes Transition)		at least 10 weeks	
TL05	Level one bar / Bridge Link	Terrazzo Floor tile	<b>Product:</b> Italian Terrazzo Tile – Special Order Items <b>Colour:</b> 26 Honed <b>Dimensions:</b> 600 x 600mm <b>Thickness:</b> 20mm <b>Slip rating:</b> Custom honed to suit <b>Fire Rating:</b> TBC  <b>Price:</b> \$110 /sqm + GST		<b>Surface Gallery</b> Scott Marrant Scott@surfacegallery.com.au 9566 2002	TBC	B
TL06	Male Amenities	Wall tile	<b>Range:</b> Core <b>Colour:</b> Warm grey <b>Finish:</b> Matt <b>Slip Rating:</b> P4 <b>Edge:</b> Rectified <b>Dimensions:</b> 300mm x 600mm <b>Grout:</b> Mapei Kerapoxy Colout 112 Grigio Medio (Medium Grey) <b>Fire Rating:</b> N/A		<b>Skheme</b> Mark Bridges markb@skheme.com 02 8755 2305		A



## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
TL07	Lift car floor finish. To match external paving.	Floor Tile	<b>TBC TO MATCH CONCRETE FLOOR</b> <b>Range:</b> Core <b>Colour:</b> TBC <b>Finish:</b> Matt <b>Slip Rating:</b> P4 <b>Edge:</b> Rectified <b>Dimensions:</b> 400mm x 400mm <b>Thickness:</b> 15mm <b>Grout:</b> Mapei Kerapoxy Colour <b>Fire Rating:</b> TBC		<b>Skheme</b> Mark Bridges <a href="mailto:markb@skheme.com">markb@skheme.com</a> 02 8755 2305		A
TL08	Wall behind amenity vanities	Terrazzo tile	<b>Product:</b> Italian Terrazzo Tile – Special Order Items <b>Colour:</b> 26 Honed <b>Dimensions:</b> 600 x 600mm check <b>Thickness:</b> TBC <b>Fire Rating:</b> TBC  <b>Price:</b> \$110 /sqm + GST		<b>Surface Gallery</b> Scott Marrant <a href="mailto:Scott@surfacegallery.com.au">Scott@surfacegallery.com.au</a> 9566 2002	TBC	A
TL09	Bar BOH Level one	Wall tile	<b>Series:</b> Basics <b>Colour:</b> White <b>Finish:</b> White matt with rectified edges <b>Size:</b> 300 x 600 x 10mm <b>Fire Rating:</b> N/A  <b>Price:</b> \$16.90 /sqm + GST		<b>Skheme</b> Mark Bridges <a href="mailto:markb@skheme.com">markb@skheme.com</a> 02 8755 2305	Currently in stock, 8-10 weeks if not	A
TRM01	Tile Trim Angle	Where required	<b>Type:</b> L-Angle Tile Trim <b>Size:</b> To suite tile thickness <b>Code:</b> AA- (TBC)-3-(custom colour) <b>Colour:</b> To match wall tile <b>Fire Rating:</b>		<b>B.A.T Trims</b> Ph: 9797 7900		A

## A-92-01 - INTERNAL FINISHES SCHEDULE

CODE	LOCATION	PRODUCT	FINISH	IMAGE	SUPPLIER	LEAD TIMES	REV
TRM02	Tile Trim Corner	Tiled corner	<b>Type:</b> Birds mouth corner Angle Tile Trim <b>Size:</b> To suite tile thickness <b>Colour:</b> To match wall tile <b>Fire Rating:</b>		<b>B.A.T Trims</b> Ph: 9797 7900		
VN01	Comms Room	Vinyl Resilient Flooring – Anti Static	<b>Type:</b> Anti Static Flooring Series: Safeguard R10 with coved skirting <b>Colour:</b> Mid grey <b>Composition:</b> Slip resistance: R10 <b>Roll width:</b> 2m <b>Thickness:</b> 2mm <b>Code:</b> 4D100012 <b>Fire Rating:</b>		<b>Armstrong Flooring</b> Cathryn Bensley 0412 332 14		A