

PROPOSED TREE PLANTING					
CODE	BOTANICAL NAME	COMMON NAME	CENTRES	POT SIZE	QUANTITY
BIT	Banksia integrifolia	Coastal Banksia	As shown	75L	22
CSA	Callistemon salignus	Willow Bottlebrush	As shown	200mm	6
ERO	Eucalyptus robusta	Swamp mahogany	As shown	200mm	5
ETE	Eucalyptus tereticornis	Forest Red Gum	As shown	200L	7
SOFF Mix	An even mix of - Acmena smithii Callistemon salignus Casuarina glauca Cupaniopsis anacardioides Eucalyptus amplifolia Eucalyptus crebra Eucalyptus tereticornis Melaleuca styphelioides Waterhousea floribunda	Lilly Pilly Bottlebrush Swamp Oak Tuckeroo Cabbage Gum Narrow-Leaved Ironbark Forest Red Gum Prickly Paperbark Weeping Lilly Pilly	As shown	200mm	720

NOTE: CURRENT NUMBER OF TREES REMOVED = 380.
2 FOR 1 REPLACEMENT STRATEGY = 760 PROPOSED TREES REQUIRED
(400 TREES TO BE PLANTED IN PHASE 1; 360 TO BE PLANTED IN PHASE 2.)

Legend
SOFF Mix Proposed (other) Existing (retained)



Notes:

- Suggest contact Tree Impact - Ross Clark for large tree stocks 02 4234 2700
- General landscape turf to be Sir Walter Buffalo. Sportfields, practice nets and performance areas turf as specified by specialist consultant.
- All plant species specified above may not be readily available in specified quantities and pot sizes. A lead time of 18 months from date of purchase may apply to some species. A **pre-grow contract** is required as soon as practicable.
- The head contractor must place the plant order for the whole site within 2 weeks of signing the head contract to ensure the plant nursery has enough time to source and grow on plant stock
- Contractor to submit the final nursery delivery schedule for approval prior to installation. Schedule must include botanical names and pot size.
- Contractor to organise a visual inspection of plants at time of delivery on site with Landscape Architect prior to installation.
- The Genus and Species nominated must be delivered to site in the total quantity specified. Varieties and hybrids of the same genus are not a suitable substitute.
- Unapproved substitutes will be detected and require replacement.
- Unapproved reductions to the specified pot sizes will be detected and require replacement, or where approved by client, a cost credit will be applied.
- Acceptance of plant stock is wholly at the discretion of the client. Plants deemed to be unsuitable for any reason (damage, root girdling, poor health, no vigorous, yellowing leaves, insect predation, water stress... etc) can be rejected by the client and will require replacement at the contractors expense.
- Plants that are deemed too small for the pot size nominated (as determined by the client and/or the clients representative) will be detected and require replacement.
- It is incumbent upon the contractor to maintain appropriate quality controls to minimise costly and timely defects rectification.
- Liaison with the plant nursery, inspecting and receiving plant stock must be undertaken by a qualified horticulturist with a minimum of 5 years practical experience on construction projects. The name and qualifications of the horticulturist must be submitted for approval within 2 weeks of the head contract being award. The client may accept or reject the submission and the contractor must seek an alternative horticulturist to the satisfaction of the client. Where not under the employ of the contractor, the contractor must hire a horticulturist for the project. The horticulturist must liaise with the client and clients representative on all plant related issues and be present at any site inspection during soil, irrigation, and plant installation.

PROPOSED UNDERSTOREY PLANTING						
CODE	SPECIES	COMMON NAME	CENTRES (mm)	POT SIZE	QUANTITY	TOTAL AREA
Ca	Carex appressa	Tall Sedge	700	140mm	78	38 m²
Cp	Crinum pedunculatum	Swamp Lily	700	140mm	68	33 m²
Di	Dianella caerulea	Blue flax-lily	700	140mm	88	43 m²
Hi	Hibbertia scandens	Snake vine	500	140mm	21	5 m²
MIX 1	An even mix of - Correa alba Ficinia nodosa Pennisetum Nafray	White correa Knotted club-rush Chinese Fountaingrass Nafray	700	140mm	126	62 m²
MIX 2	An even mix of - Lomandra longifolia Crinum pedunculatum Cordylne stricta Myoporum parvifolium	Spiny-head rush Swamp lily Slender Palm Lily Creeping Boobialla	700	140mm	296	145 m²
MIX 3	An even mix of - Acacia binervia Melaleuca 'Snowstorm' Westringia fruticosa Dodonaea viscosa Myoporum parvifolium	Coast Myall Melaleuca Snowstorm Coastal Rosemary Sticky Hop Bush Creeping Boobialla	700	140mm	1197	587 m²
MIX 4	An even mix of - Myoporum parvifolium Lomandra longifolia Crinum pendunculatum Dianella caerulea	Creeping Boobialla Spiny-head rush Swamp Lily Blue flax-lily	700	140mm	2876	1409 m²
MIX 5	An even mix of - Myoporum parvifolium Lomandra longifolia Crinum pendunculatum Banksia robur Dianella caerulea Cordylne stricta Dodonaea viscosa Acmena smithii Minor Westringia fruticosa Mundi	Creeping Boobialla Spiny-head rush Swamp Lily Swamp Banksia Blue flax-lily Slender Palm Lily Sticky Hop Bush Dwarf Lilly Pilly Mundi Coastal Rosemary	700	140mm	2372	1162 m²
MIX 7	An even mix of - Correa alba Pennisetum Nafray	Spiny-head rush Pennisetum Nafray	700	140mm	108	53 m²
MIX 8	An even mix of - Lomandra longifolia Westringia fruticosa Correa alba Leptospermum flavesces 'Cardwell'	Spiny-head rush Coastal Rosemary White correa Tea Tree	700	140mm	1961	961 m²
MIX 9	An even mix of - Pelargonium australe Scaevola aemula Hibbertia scandens Dianella caerulea Myoporum parvifolium	Native Storksbill Fan-flower Snake Flower Blue Flax-lily Creeping Boobialla	700	140mm	105	51 m²
MIX 10	An even mix of - Callistemon 'Hannah Ray' Indigofera australis Dodonaea viscosa	Hannah Ray Bottlebrush Australian indigo Hopbush	700	140mm	383	188 m²
MIX 11	An even mix of - Correa alba Kunzea ambigua Acacia longifolia	White correa White Kunzea Sydney Golden Wattle	700	140mm	352	172 m²
MIX 12	An even mix of - Myoporum parvifolium Lomandra longifolia	Hop Goodenia Spiny-head rush	700	140mm	83	40 m²
Sc	Scaevola albida 'Mauve Clusters'	Fan-flower	700	140mm	367	180 m²

GENERAL NOTES

- THIS DRAWING IS COPYRIGHT AND IS THE PROPERTY OF TURF DESIGN STUDIO AND MUST NOT BE USED WITHOUT PERMISSION.
- THIS DRAWING IS AN UNCONTROLLED COPY UNLESS STAMPED WITH STATUS. THE CONTRACTOR MUST VERIFY ALL DIMENSIONS AND LEVELS ON SITE AS THIS IS NOT A SHOP DRAWING.
- THE CONTRACTOR MUST REFER ANY DISCREPANCIES TO THE SUPERINTENDENTS REPRESENTATIVE BEFORE PROCEEDING WITH THE WORK.
- THE CONTRACTOR MUST NOT SCALE FROM THESE DRAWINGS. USE NOMINATED DIMENSIONS AND LEVELS.
- THIS DRAWING MUST BE READ IN CONJUNCTION WITH THE TOTAL CONTRACT PACKAGE INCLUDING DRAWINGS AND SPECIFICATIONS OF ALL CONSULTANTS.
- IF THE CONTRACTOR INTENDS TO UNDERTAKE ANY EXCAVATION WORK, IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT 1100 - DIAL BEFORE YOU DIG OR WWW.1100.COM.AU
- SITE BOUNDARY AND PHASE 2 HATCHED AREA IS NOT THE LEASE BOUNDARY

SURVEY INFORMATION

- TURF DESIGN STUDIO DO NOT WARRANT THE ACCURACY OF SURVEY INFORMATION.

5	06.04.22	CC4	CO	SJ
4	18.03.22	For CC4	CO	SJ
3	08.03.22	For Approval	CO	SJ
2	09.07.21	For CC3 Construction Certificate	CO	SJ
1	01.10.20	Tender Addendum	DB	JN
Rev	Date	Description	Drawn	Checked

REV. NOTES:
- TREE AND PLANTING NUMBERS
UPDATED.

Author



Turf Design Studio - 35 Wellington St, Chippendale NSW 2008
Phone (+61 2) 8394 9990, Fax (+61 2) 9527 2307
Email: sydney@turfdesign.com

Client



Project
Cricket NSW COE

Drawing Title

Planting Schedules

Drawing Status

CC4

Scale: @A1

Project No.

1910

Drawing No.

L-500

Revision

5