

2. ALL STOCKPILE INDICATED ARE DIAGRAMMATIC ONLY AND SHALL BE CONFIRMED ON SITE PRIOR TO INSTALLATION.

DEVELOPMENT DATA		
SITE AREA	59,475 m2	
	FLOOR AREAS	
	WAREHOUSE	OFFICE/AMENITIES
BUILD 'A'	1278 m2	24 m2
BUILD 'B'	3162 m2	438 m2
BUILD 'C'	2981 m2	-----
BUILD 'D'	415 m2	-----
BUILD 'E'	984 m2	-----
BUILD 'F'	494 m2	-----
BUILD 'G'	81 m2	-----
BUILD 'H'	25 m2	-----
BUILD 'J'	17 m2	-----
BUILD 'K'	47 m2	-----
BUILD 'L'	593 m2	-----
TOTAL	10,077 m2	462 m2

STOCK PILE NOTES

1. MIN 6m ACCESS AROUND STOCK PILES
2. NOT ALL STOCK PILES WILL BE FULLY OPERATIONAL OR UTILISED AT THE SAME TIME
3. DIMENSIONS INDICATED ARE APPROXIMATE ONLY.
4. STOCKPILES TO BE FURTHER ASSESSED TO CURRENT FRNSW FIRE SAFETY GUIDELINES FOR WASTE FACILITIES VERSION 02.02 DATED 27 FEBRUARY 2020. STOCKPILE VOLUMES AND SEPARATION DISTANCES SHOWN ARE AS PER PREVIOUSLY APPROVED METHODOLOGY FROM FRNSW.

PILE NO.	TYPE	AVE. HT. (m)	SIZE (m3)	TONNES
1	INSPECTED SHREDDER FEED	4	14.44	505
2	INSPECTED SHREDDER FEED	4	1008	353
3	INSPECTED SHREDDER FEED	4	536	202
4	AS DELIVERED SHREDDER FEED	4	624	218
5	AS DELIVERED SHREDDER FEED	4	1760	616
6	AS DELIVERED SHREDDER FEED	4	520	182
7	AS DELIVERED SHREDDER FEED	4	1288	451
8	AUTOMOTIVE	4	800	400
9	AUTOMOTIVE	4	1480	740
10	PRE-SHREDDED AUTOMOTIVE	4	1224	612
11	PRE-SHREDDED AUTOMOTIVE	4	1200	600
12	FLOC	3	600	200
	TOTAL		12524	5079

