

Development Consent

Section 4.38 of the *Environmental Planning and Assessment Act 1979*

As delegate of the Minister for Planning under delegation executed on 9 March 2022, I determine:

- a) to grant consent to the Staged Development Application referred to in Schedule 1, subject to the Concept Proposal conditions and Stage 1 Development Application conditions in Schedule 2;
- b) that pursuant to section 4.37 of the *Environmental Planning and Assessment Act 1979* (NSW), any subsequent development under the Concept Proposal is only considered to be State Significant Development should the development meet the relevant criteria in Schedule 1 of State Environmental Planning Policy (Planning Systems) 2021 (or any substituted SEPP).

These conditions are required to:

- prevent, minimise, or offset adverse environmental impacts;
- set standards and performance measures for acceptable environmental performance;
- require regular monitoring and reporting; and
- provide for the ongoing environmental management of the development.

Chris Ritchie
Director
Industry Assessments

Sydney

24 May 2022

The Department has prepared a consolidated version of the consent which is intended to include all modifications to the original determination instrument.

The consolidated version of the consent has been prepared by the Department with all due care. This consolidated version is intended to aid the consent holder by combining all consents relating to the original determination instrument, but it does not relieve a consent holder of its obligation to be aware of and fully comply with all consent obligations as they are set out in the legal instruments, including the original determination instrument and all subsequent modification instruments.

CONSOLIDATED CONSENT

SCHEDULE 1

Application Number:	SSD-10448
Applicant:	Mirvac Projects Pty Ltd
Consent Authority:	Minister for Planning
Site:	<p><u>Aspect Industrial Estate</u></p> <p>Lots 54-58 DP 259135 Lots 1, 2 and 5 DP 1285305 and Lots 6 and 7 DP 1291562</p> <p>Lots 301 and 305 DP 1305254, Lots 104 and 105 DP 1305965</p> <p>788-882-788-882 Mamre Road, Kemps Creek NSW 2178</p> <p><u>Elizabeth Enterprise Precinct</u></p> <p>Lot 100 DP 1283398 and Lot 741 DP 810111</p> <p>1669A and 1669-1723 Elizabeth Drive, Badgerys Creek NSW 2555</p> <p>1669-1723 Elizabeth Drive, Badgerys Creek NSW 2555</p>
Development:	<p>The Staged Development Application for the Aspect Industrial Estate comprised of:</p> <ul style="list-style-type: none">• a Concept Proposal for the staged development of an industrial estate comprising of 9 buildings with a total GFA of up to 247,646 square metres (m²) for industrial, warehousing and distribution centres, and café uses• Stage 1 development comprising site preparation works, vegetation clearing, realignment of the existing creek, construction of access roads and eastern half of Mamre Road/ Access Road 1 intersection works, construction, fit out, and operation of one warehouse and one industrial building with ancillary offices, car parks, landscaping, signage, construction and operation of services and utilities, and subdivision of the site into three lots.; and• inclusion of the Elizabeth Enterprise Precinct site for stormwater management purposes only.

FOR INFORMATION

CONSOLIDATED CONSENT

SUMMARY OF MODIFICATIONS

Application Number	Determination Date	Decider	Modification Description
SSD-10448-MOD-1	25 August 2022	Principal Planning Officer, Industry Assessments	Modification to include additional conditions required by TfNSW for SSD-10448
SSD-10448-MOD-2	30 November 2022	Team Leader, Industry Assessments	Modification to Concept Plan and Stage 1 Development layouts
SSD-10448-MOD-3	2 March 2023	Director, Industry Assessments	Modification to Concept Plan and Stage 1 Development
SSD-10448-MOD-5	12 December 2023	Director, Industry Assessments	Use of the temporary left-in/left-out construction access on Mamre Road by Warehouse 1 operational vehicles.
SSD-10448-MOD-4	21 December 2023	Director, Industry Assessments	Modification to amend the Concept Proposal and Stage 1 stormwater management strategy
SSD-10448-MOD-7	15 July 2024	Team Leader, Industry Assessments	Use of the temporary left-in/left-out construction access on Mamre Road by Warehouses 1 and 9 operational vehicles.
SSD-10448-MOD-8	7 May 2025	Team Leader, Industry Assessments	Modification to Concept and Stage 1 stormwater management strategy
SSD-10448-MOD-9	27 June 2025	Acting Executive Director, Industry Assessments	Modification to the Concept Plan to include a revised building layout
SSD-10448-MOD-10	25 September 2025	Acting Executive Director, Industry Assessments	Modification to the Concept Plan to amend carparking, noise limits and tree canopy for warehouse 8
SSD-10448-Mod-11	6 May 2026	Team Leader, Industry Assessments	Modification to Concept and Stage 1 stormwater management strategy

TABLE OF CONTENTS

DEFINITIONS	6
PART A CONDITIONS FOR CONCEPT PROPOSAL	10
Terms of consent	10
Future Development Applications	10
Limits of Consent	10
Staging Plan	11
Traffic.....	12
Future infrastructure requirements.....	12
Noise Limits	12
Mamre Road Precinct Working Group	12
Evidence of consultation	13
Staging, Combining and Updating Strategies, Plans or Programs	13
PART B CONDITIONS FOR FUTURE DEVELOPMENT APPLICATIONS	14
Traffic and Access	14
Future Freight Network	14
Stormwater Management	14
Development Contributions	15
Noise and Vibration	15
Visual Amenity	15
Bushfire Protection	16
Endeavour Energy	16
Sydney water	16
External Walls and Cladding	16
PART C STAGE 1 DEVELOPMENT GENERAL CONDITIONS	17
Obligation to Minimise Harm to the Environment.....	17
Terms of Consent	17
Limits of Consent	17
Notification of Commencement.....	18
Evidence of Consultation	18
Staging, Combining and Updating Strategies, Plans or Programs	18
Protection of Public Infrastructure	18
Demolition.....	18
Structural Adequacy	18
Subdivision	19
Compliance.....	19
Development Contributions	19
Operation of Plant and Equipment.....	19
External Walls and Cladding.....	19
Utilities and Services	20
Works as Executed Plans	20
Environmental Representative.....	20
Mamre Road Precinct Working Group	21
Applicability of Guidelines	21
PART D STAGE 1 DEVELOPMENT SPECIFIC ENVIRONMENTAL CONDITIONS	23
Traffic and Access	23
Soils, Water Quality and Hydrology	27
Visual Amenity	28
Noise	29
Air Quality	31
Aboriginal Heritage	31
Historic Heritage	32
Biodiversity	32
Hazards and Risk	32
Waste Management.....	33
PART E STAGE 1 DEVELOPMENT ENVIRONMENTAL MANAGEMENT, REPORTING AND AUDITING.....	34
Environmental Management.....	34
Construction Environmental Management Plan.....	34

CONSOLIDATED CONSENT

Operational Environmental Management Plan	35
Revision of Strategies, Plans and Programs	35
Reporting and Auditing	35
Access to Information	36
APPENDIX 1 CONCEPT PROPOSAL	37
APPENDIX 2 STAGE 1 DA PLANS	40
APPENDIX 3 NOISE MONITORING LOCATIONS.....	59
APPENDIX 4 NOISE MITIGATION ELIGIBLE RECEIVERS LOCATIONS.....	60
APPENDIX 5 APPLICANT'S MANAGEMENT AND MITIGATION MEASURES	61
APPENDIX 6 INCIDENT NOTIFICATION AND REPORTING REQUIREMENTS	69

FOR INFORMATION

DEFINITIONS

ADR	Amended Development Report titled 'SSD-10448 Aspect Industrial Estate Amended Development Report', prepared by Urbis and dated 5 May 2022
Applicant	Mirvac Projects Pty Ltd, or any person carrying out any development to which this consent applies
BCA	Building Code of Australia
BC Act	<i>Biodiversity Conservation Act 2016</i> (NSW)
Calendar year	A period of 12 months commencing on 1 January
CAQMP	Construction Air Quality Management Plan
Carrier	Operator of a telecommunication network and/ or associated infrastructure, as defined in s 7 of the <i>Telecommunications Act 1997</i> (Cth)
CDWMP	Construction and Demolition Waste Management Plan
Certifier	A council or an accredited certifier (including principal certifiers) who is authorised under s 6.5 of the EP&A Act to issue Part 6 certificates
CEMP	Construction Environmental Management Plan
CNMP	Construction Noise Management Plan
Conditions of this consent	Conditions contained in Schedule 2 of this consent
Concept Proposal	Concept layout of 44 9 buildings and ancillary offices for industrial, warehousing and distribution centres, and café uses, as described in the EIS, Response to Submissions and ADR
Construction	The demolition and removal of buildings or works, the carrying out of works for the purpose of the development, including bulk earthworks and erection of buildings and other infrastructure permitted by this consent
Council	Penrith City Council
Day	The period from 7 am to 6 pm on Monday to Saturday, and 8 am to 6 pm on Sundays and Public Holidays
Decommissioning	The controlled process of safely retiring a facility from service, including decontamination, dismantling, and disposal after the cessation of operations
Demolition	The deconstruction and removal of buildings, sheds, and other structures on the site
Department	Department of Planning and Environment
Development	The development described in Schedule 1, the EIS, Response to Submissions, and ADR, including the construction and operation of 44 9 buildings, ancillary offices and associated infrastructure for industrial, warehousing and distribution centres, and café uses, as shown on the plans in Appendix 1, and as modified by the conditions of this consent
Development layout	The Plans at Appendix 1 of this consent
DPE	Has the same meaning of the Department
Earthworks	Bulk earthworks, site levelling, import and compaction of fill materials, excavation for installation of drainage and services, to prepare the site for construction
EEP	Elizabeth Enterprise Precinct (Lot 100 DP 1283398 and Lot 741 DP 810111), (1669A and 1669-1723 Elizabeth Drive, Badgerys Creek NSW 2555) as described in the Modification Report titled AIE Concept Plan and Stage 1 Modification (SSD-10448 MOD 4) Modification Report, prepared by Urbis, dated September 2023 and shown in Figure 5A in Appendix 2 of this consent
E&H	Environment and Heritage Group, DPE
EIS	The Environmental Impact Statement titled Aspect Industrial Estate Environmental Impact Statement, prepared by Urbis, dated November 2020, submitted with the application for consent for the development
ENM	Excavated Natural Material
Environment	As defined in section 1.4 of the EP&A Act

EPA	NSW Environment Protection Authority
EP&A Act	<i>Environmental Planning and Assessment Act 1979</i> (NSW)
EP&A Regulation	Environmental Planning and Assessment Regulation 2000 (NSW)
ER	Environmental Representative
Evening	The period from 6 pm to 10 pm
Fibre-ready facility	As defined in s 372W of the <i>Telecommunication Act 1997</i> (Cth)
Heritage	Encompasses both Aboriginal and historic heritage including sites that predate European settlement, and a shared history since European settlement
Heritage item	An item as defined under the <i>Heritage Act 1977</i> (NSW), and assessed as being of local, State and/ or National heritage significance, and/or an Aboriginal Object or Aboriginal Place as defined under the <i>National Parks and Wildlife Act 1974</i> (NSW), the World Heritage List, or the National Heritage List or Commonwealth Heritage List under the <i>Environment Protection and Biodiversity Conservation Act 1999</i> (Cth), or anything identified as a heritage item under the conditions of this consent
Incident	An occurrence or set of circumstances that causes or threatens to cause material harm and which may or may not be or cause a non-compliance <i>Note: 'material harm' is defined in this consent</i>
IWCM	Integrated Water Cycle Management
Land	Has the same meaning as the definition of the term in section 1.4 of the EP&A Act
Material harm	Is harm that: (a) involves actual or potential harm to the health or safety of human beings or to the environment that is not trivial, or (b) results in actual or potential loss or property damage of an amount, or amounts in aggregate, exceeding \$10,000, (such loss includes the reasonable costs and expenses that would be incurred in taking all reasonable and practicable measures to prevent, mitigate or make good harm to the environment)
Minister	New South Wales Minister for Planning (or delegate)
Mitigation	Activities associated with reducing the impacts of the development prior to or during those impacts occurring
Modification Assessments	<p>The document assessing the environmental impacts of a proposed modification of this consent and any other information submitted with the following modification application made under the EP&A Act:</p> <ul style="list-style-type: none"> a) Section 4.55(1) Application to Amend SSD-10448, Aspect Industrial Estate, prepared by Urbis, dated 19 July 2022. b) Section 4.55(1A) Application to Amend SSD-10448, Aspect Industrial Estate, prepared by Urbis, dated June 2022. c) AIE Concept Plan and Stage 1 Modification (SSD-10448 MOD 3) and Stage 2 Development Application (SSD-46516461) Environmental Impact Statement, prepared by Urbis, dated 21 September 2022. d) AIE Concept Plan and Stage 1 Modification (SSD-10448 MOD 5) Modification Report, prepared by Urbis, dated September 2023. e) AIE Concept Plan and Stage 1 Modification (SSD-10448 MOD 4) Modification Report, prepared by Urbis, dated September 2023. f) AIE Concept Plan, Stage 1 and Stage 2 Modification SSD-10448 MOD 7 SSD-46516461 MOD 2, prepared by Urbis, dated May 2024. g) SSD-10448-Mod-8: Modification Report titled "AIE Concept Plan, Stage 1, 2, 3 and 4 Modification SSD-10448 MOD 8 SSD-46516461 MOD 3 SSD-58257960 MOD 1 SSD-60513208 MOD 1 Modification Report", prepared by Urbis, dated December 2024 and all accompanying documents. h) SSD-10448-Mod-9: Modification Report titled 'Aspect Industrial Estate Concept Plan, Stage 1 (SSD10448) & Stage 4 (SSD-60513208) Modification', prepared by Urbis dated 5 February 2025.

	<p>i) SSD—10448-Mod-10: 'Aspect Industrial Estate Concept Plan, Stage 1 (SSD-10448 Mod 10) & WH8 Fit-Out and Use Application (SSD-80331959), prepared by Urbis dated June 2025.</p> <p>j) SSD-10448-Mod-11 'AIE Stormwater Management Modification Report' SSD-10448 Mod 11, SSD-46516461 Mod 4, SSD-58257960 Mod 3, SSD-60513208 Mod 3 prepared by Urbis dated December 2025</p>
Modification 5	The temporary use of the left-in/left-out construction access on Mamre Road by Warehouse 1 operational vehicles until the signalised Mamre Road/Access Road 1 intersection is constructed and commissioned as described in AIE Concept Plan and Stage 1 Modification (SSD-10448 MOD 5) Modification Report, prepared by Urbis, dated September 2023
Modification 7	The temporary use of the left-in/left-out construction access on Mamre Road by Warehouses 1 and 9 operational vehicles until the signalised Mamre Road/Access Road 1 intersection is constructed and commissioned as described in AIE Concept Plan, Stage 1 and Stage 2 Modification SSD-10448 MOD 7 SSD-46516461 MOD 2, prepared by Urbis, dated May 2024.
Monitoring	Any monitoring required under this consent must be undertaken in accordance with section 9.40 of the EP&A Act
MRP	Mamre Road Precinct
MRP DCP	Mamre Road Precinct Development Control Plan (NSW Government, 2021)
Night	The period from 10 pm to 7 am on Monday to Saturday, an 10 pm to 8 am on Sundays and Public Holidays
Non-compliance	An occurrence, set of circumstances or development that is a breach of this consent
Night	The period from 10 pm to 7 am on Monday to Saturday, and 10 pm to 8 am on Sundays and Public Holidays
NML	Noise Monitoring Locations
Non-compliance	An occurrence, set of circumstances or development that is a breach of this consent
NRAR	Natural Resources Access Regulator, DPE
OEMP	Operational Environmental Management Plan
Operation	The use of warehouse and industrial buildings for storage, distribution or manufacture of goods upon completion of construction as described in the EIS and ADR
PA	Means a planning agreement within the meaning of the term in section 7.4 of the EP&A Act.
Planning Secretary	Planning Secretary under the EP&A Act, or nominee
POEO Act	<i>Protection of the Environment Operations Act 1997</i> (NSW)
Precinct-Wide Stormwater Infrastructure	Refers to future regional stormwater infrastructure for the MRP to be operated by a stormwater management authority
Principal Certifier	The certifier appointed as the principal certifier for the building work under s 6.6(1) of the EP&A Act or for the subdivision work under s 6.12(1) of the EP&A Act
Reasonable	Means applying judgement in arriving at a decision, taking into account: mitigation benefits, costs of mitigation versus benefits provided, community views, and the nature and extent of potential improvements
Registered Aboriginal Parties	Means the Aboriginal persons identified in accordance with the document entitled 'Aboriginal cultural heritage consultation requirements for proponents 2010' (DECCW)
Registered Surveyor	Means registered surveyor within the meaning of the term in the <i>Surveying and Spatial Information Act 2002</i> (NSW)
Response to Submissions (RtS)	The Applicant's response to issues raised in submissions received in relation to the application for consent for the development under the EP&A Act and includes the document titled Aspect Industrial Estate Response to Submissions SSD-10448, prepared by Urbis, dated 5 March 2021
Roads authority	As defined in dictionary of the <i>Roads Act 2003</i> (NSW)
Sensitive receivers	A location where people are likely to work, occupy or reside, including a dwelling, school, hospital, office, or public recreational area

Site	The land defined in Schedule 1
Stage 1 development	Sitewide bulk earthworks, retaining walls, estate basin, riparian corridor realignment, construction of access roads and the Mamre Road / Access Road 1 intersection construction and operation of buildings 1 and 3, café, landscaping services and utilities installation and subdivision, as described in the EIS, Response to Submissions and ADR
Stage 1 Phase 1 Road Works	Involves construction and operation of a signalised intersection at Mamre Road, Access Road 1 between Mamre Road and Access Road 2, and Access Road 2 as identified in Figure 1 at Appendix 1
Stage 1 Phase 2 Road Works	Involves construction and operation of a roundabout at Access Roads 1 and 3 intersection, the remaining portion of Access Road 1 between Access Road 2 and the roundabout, and Access Road 3 to the south of the roundabout (excludes Access Road 3 - North)
TfNSW	Transport for New South Wales
Traffic control facilities	Has the same meaning as the definition of the term in <i>Dictionary of the Roads Act 1993 (NSW)</i> .
VENM	Virgin Excavated Natural Material
WAD	Works Authorisation Deed
WSUD	Water Sensitive Urban Design

SCHEDULE 2

PART A CONDITIONS FOR CONCEPT PROPOSAL

TERMS OF CONSENT

- A1. The development may only be carried out:
- (a) in compliance with the conditions of this consent;
 - (b) in accordance with all written directions of the Planning Secretary;
 - (c) in accordance with the EIS, Response to Submissions (RtS), and Amended Development Report (ADR);
 - (d) **in accordance with the Modification Assessments;**
 - (e) in accordance with the Development Layout in Appendix 2; and
 - (f) in accordance with the management and mitigation measures in Appendix 5.
- A2. Consistent with the requirements in this consent, the Planning Secretary may make written directions to the Applicant in relation to:
- (a) the content of any strategy, study, system, plan, program, review, audit, notification, report or correspondence submitted under or otherwise made in relation to this consent, including those that are required to be, and have been, approved by the Planning Secretary; and
 - (b) the implementation of any actions or measures contained in any such document referred to in condition A2(a).
- A3. The conditions of this consent and directions of the Planning Secretary prevail to the extent of any inconsistency, ambiguity or conflict between them and a document listed in condition A1(c) or A1(f). In the event of an inconsistency, ambiguity or conflict between any of the documents listed in condition A1(c) or A1(f), the most recent document prevails to the extent of the inconsistency, ambiguity or conflict.

FUTURE DEVELOPMENT APPLICATIONS

- A4. In accordance with section 4.22 of the EP&A Act, each subsequent stage of the Concept Proposal (excluding Stage 1 development) is to be subject to future development applications (DAs). Future DAs are to be consistent with the terms of this consent.

MODIFICATIONS TO THE CONCEPT PROPOSAL

- A4A. This consent does not approve the concept stormwater management strategy described in:
- Section 3.3 of the AIE Concept Plan and Stage 1 Modification (SSD-10448 MOD 4) Modification Report, prepared by Urbis Ltd, dated September 2023;
 - Section 3.2 of the SSD-10448 MOD 4 Response to Submissions, prepared by Urbis Ltd, dated 6 December 2023; and
 - Section 5.1 of the Aspect Industrial Estate Water and Stormwater Management Plan, prepared by AT&L, dated 6 December 2023.
- A4B. Any development applications for future stages of the AIE must be accompanied with a revised site-wide stormwater management strategy demonstrating compliance with the Integrated Water Cycle Management (IWCM) controls in the MRP DCP in accordance with the *Technical Guidance for achieving Wianamatta South Creek Stormwater Management Targets* (NSW Government, 2022).

LIMITS OF CONSENT

- A5. This consent lapses five years after the date from which it operates unless the development has physically commenced on the land to which the consent applies before that date.
- A6. The Applicant must ensure any future development of the site is consistent with the *Mamre Road Precinct Development Control Plan 2021* (NSW Government, 2021) (MRP DCP).
- A7. The maximum GFA for future development on the site for the land uses described in **Table 1** must not exceed the limits described in that table.

Table 1 Maximum GFA of the Concept Proposal

Land Use	Maximum GFA (m ²)
Warehouse and distribution centres and general industrial	234,035
Ancillary offices	11,136
Total	245,296

- A8. A future road widening corridor along the western boundary must not be developed and must be maintained and preserved for the future Mamre Road widening works as shown in **Figure 1** in **Appendix 1**.
- A9. The largest vehicle permitted to access the site is a 30 m Performance Based Standards (PBS) Level 2 Type B.
- A9A. The maximum height for future development on the site described in Table 1A must not be exceeded.

Table 1A Maximum Building Height of the Concept Proposal

Land Use	Height (m)
Warehouse 1	<ul style="list-style-type: none"> • 16.0 m (excluding rooftop plant) • 18.4 m (including rooftop plant)
Warehouse 9	<ul style="list-style-type: none"> • 14.6 m
All other warehouses	13.7 m

Elizabeth Enterprise Precinct

- A9B. Under this consent, the EEP site must **only** be used for stormwater management purposes as required by Condition A9E and as shown on Figure 5 and 5A, until the Precinct-Wide Stormwater Infrastructure becomes available for the AIE to connect into.

Note: Any future use of the EEP site other than for stormwater management purposes may be considered by the Department as part of a separate future modification and/or application should alternative stormwater management strategies become available.

- ~~A9C. This consent does not permit the use of the EEP site for any other development or use and must be preserved as undeveloped land for the purposes described in Condition A9E.~~
- A9D. The conditions in Part B, Schedule 2 of this consent do not apply to the EEP site as described in Schedule 1 of this consent.

STORMWATER MANAGEMENT

- A9E. The site and the EEP must collectively achieve compliance with the Integrated Water Cycle Management (IWCM) controls in the MRP DCP in accordance with the *Technical Guidance for achieving Wianamatta South Creek Stormwater Management Targets* (NSW Government, 2022).

STAGING PLAN

- A10. Prior to the commencement of construction of any stage of the Concept Proposal, the Applicant shall prepare a Staging Plan for the Development, to the satisfaction of the Planning Secretary. The plan shall:
- (a) be prepared in consultation with Council, utility and service providers and other relevant stakeholders;
 - (b) describe how the implementation of the Concept Proposal, would be staged to ensure it is carried out in an orderly and economic way and minimises construction impacts;
 - (c) show the likely sequence of DAs that will be lodged to develop the Site, with the estimated timing for each Stage and identification of any overlapping construction and operational activities;
 - (d) include concept design for the staged delivery of landscaping, focusing on early implementation of screen planting to minimise the visual impact of subsequent development stages; and
 - (e) include conceptual design for the provision of services, utilities and infrastructure to the Site, including stormwater management infrastructure and any future road upgrades.
- A11. The Applicant must:
- (a) not commence construction of any stage of the Development until the Staging Plan required by Condition A12 is approved by the Planning Secretary; and
 - (b) implement the most recent version of the Staging Plan approved by the Planning Secretary.
- A12. The Planning Secretary may require the Applicant to address certain matters identified in the Staging Plan. The Applicant must comply with any such requirements of the Planning Secretary given as part of the Staging Plan approval.

Notes:

- *The Applicant may amend the Staging Plan as desired, with the approval of the Planning Secretary.*
- *The Staging Plan is intended to broadly describe the development sequence for the Site and the delivery of infrastructure for all stages. It is not required to provide detailed design for latter Stages.*

TRAFFIC

- A13. The Applicant must monitor operational traffic for all developments in the concept proposal for a period of 12 months following commencement of operation of each development under the relevant stage. This must include, but not be limited to:
- (a) details of the number and frequency of truck numbers generated by the relevant stage of the Concept Proposal along with any approved developments under the concept proposal;
 - (b) verification of the predicted traffic numbers and level of service against the relevant stage of the Concept Proposal, and analyse the potential cause of any significant discrepancies; and
 - (c) consideration of the current capacity and efficiency of the existing road network including Mamre Road.

FUTURE INFRASTRUCTURE REQUIREMENTS

- A14. The Applicant must prepare an Infrastructure Review to support each future stage of the Concept Proposal. The Infrastructure Review must demonstrate the surrounding road infrastructure can accommodate the relevant stage and other approved developments in the MRP. The Infrastructure Review must:
- (a) detail traffic volumes from all operating stages of the Concept Proposal;
 - (b) include background traffic volumes from key roads within the MRP, including Mamre Road;
 - (c) assess the operating performance of key intersections in the MRP, including Mamre Road and Access Road 1;
 - (d) detail the current level of approved development within the MRP, including total approved GFA;
 - (e) consider consistency with the latest approved Concept Proposal traffic volumes;
 - (f) demonstrate the road network has sufficient capacity to accommodate the proposed stage of the Concept Proposal, and if the proposed stage would trigger the need for any road upgrades, including those identified in the traffic modelling for the MRP;
 - (g) if road upgrades are required to support the proposed stage, identify the timing and mechanisms to contribute to the delivery of the required road upgrades.
- A15. The outcomes of the Infrastructure Review must be used to inform the Staging Plan required by Condition A10.

NOISE LIMITS

- A16. The Applicant must:
- (a) ensure the cumulative noise emission of fixed external mechanical plant for each warehouse building does not exceed a sound power level (SWL) of 90 dB(A) (except Warehouse 8 whose fixed external mechanical plant must not exceed a cumulative sound power level (SWL) of 98dB(A)) and do not exhibit tonal characteristics or strong low frequency content; and
 - (b) ensure the noise generated by the operation of the Development does not exceed the noise limits in Table 2.

Table 2 Operational Noise Limits for Concept Proposal dB(A)

Location	Day	Evening	Night
	L _{Aeq} (15 minute)	L _{Aeq} (15 min)	L _{Aeq} (15 min)
Residential receivers near Medinah Avenue (Luddenham), Mount Vernon Road (Mont Vernon) and Kerrs Road (Mont Vernon)	39	34	29
BAPS Temple – Outdoor Use Area (Except Car Parking Area)	36 (when in use)		

Note:

- Noise generated by the development is to be measured in accordance with the relevant procedures and exemptions (including certain meteorological conditions) of the NSW Noise Policy for Industry (EPA, 2017) (as may be updated or replaced from time to time). Refer to the plan in Appendix 3 for the location of residential sensitive receivers.

- A16A. Prior to the commencement of operation of any part of the Development, the Applicant must prepare and submit an Operational Noise Management Plan to the satisfaction of the Planning Secretary. The Operational Noise Management Plan must:
- (a) describe the noise performance monitoring method established in accordance with the following guidelines and standards (as may be updated or replaced from time to time) to analyse compliance with the limits specified in condition A16:

- (i) the Australian Standard AS 1055:2018 Acoustics – Description and measurement of environmental noise (Standards Australia, 2018);
- (ii) the EPA Approved Methods for the Measurement and Analysis of Environmental Noise in NSW (EPA, 2022);
- (iii) Section 7 of the Noise Policy for Industry (EPA, 2017);
- (b) identify the allowable noise contribution level of each warehouse at compliance locations identified in Table 2;
- (c) identify the nominated intermediate monitoring locations, reference noise levels at each intermediate location, and noise level relationship between each intermediate location and compliance locations identified in Table 2;
- (d) include:
 - (i) an outline of at-source and transmission path mitigation measures required to ensure compliance with the limits specified in condition A16;
 - (ii) a description of operational procedures to minimise noise, including load dock management practices and driver code of conduct;
 - (iii) a description of contingency measures (including the cessation of non-compliant noise generating activities during the night-time period) in the event mitigation measures and operational procedures are ineffective at reducing operational noise to comply with limits specified in condition A16;
- (e) be updated within three months of the approval of any modification of the Development Layout or determination of future DAs.

MAMRE ROAD PRECINCT WORKING GROUP

A17. For the duration of construction works for each development under the Concept Proposal, and until all components of the development under the Concept Proposal are operational, the Applicant must participate in the Mamre Road Precinct Working Group with relevant consent holders in the MRP to the satisfaction of the Planning Secretary (see Condition C34 in Schedule 2).

EVIDENCE OF CONSULTATION

- A18. Where conditions of this consent require consultation with an identified party, the Applicant must:
- (a) consult with the relevant party prior to submitting the subject document to the Planning Secretary for approval; and
 - (b) provide details of the consultation undertaken including:
 - (i) the outcome of that consultation, matters resolved and unresolved; and
 - (ii) details of any disagreement remaining between the party consulted and the Applicant and how the Applicant has addressed the matters not resolved.

STAGING, COMBINING AND UPDATING STRATEGIES, PLANS OR PROGRAMS

- A19. With the approval of the Planning Secretary, the Applicant may:
- (a) prepare and submit any strategy, plan or program required by this consent on a staged basis (if a clear description is provided as to the specific stage and scope of the development to which the strategy, plan or program applies, the relationship of the stage to any future stages and the trigger for updating the strategy, plan or program);
 - (b) combine any strategy, plan or program required by this consent (if a clear relationship is demonstrated between the strategies, plans or programs that are proposed to be combined); and
 - (c) update any strategy, plan or program required by this consent (to ensure the strategies, plans and programs required under this consent are updated on a regular basis and incorporate additional measures or amendments to improve the environmental performance of the development).
- A20. If the Planning Secretary agrees, a strategy, plan or program may be staged or updated without consultation being undertaken with all parties required to be consulted in the relevant condition in this consent.
- A21. If approved by the Planning Secretary, updated strategies, plans, or programs supersede the previous versions of them and must be implemented in accordance with the condition that requires the strategy, plan, or program.

ADVISORY NOTES

AN1. All licences, permits, approvals and consents as required by law must be obtained and maintained as required for the development. No condition of this consent removes any obligation to obtain, renew or comply with such licences, permits, approvals and consent.

PART B CONDITIONS FOR FUTURE DEVELOPMENT APPLICATIONS**TRAFFIC AND ACCESS****Traffic Impact Assessment**

- B1. Future DAs shall be accompanied by a traffic impact assessment (TIA). The TIA must:
- assess the impacts on the safety and capacity of the surrounding road network and access points during construction and operation of the relevant stage in accordance with relevant TfNSW guidelines;
 - include traffic monitoring data collected under Condition D3 and incorporate the relevant findings into this assessment;
 - demonstrate internal roads and car parking complies with relevant Australian Standards and the car parking rates in Condition B2;
 - demonstrate the Mamre Road/Access Road 1 intersection can accommodate operational traffic associated with the relevant stage;
 - detail the scope and timing of any required road or intersection upgrades to service the relevant stage if the assessment under sub-clause (d) identifies that additional upgrades are required; and
 - detail measures to promote non-car travel modes, including a Sustainable Travel Plan identifying pedestrian and cyclist facilities to service the relevant stage of the development.

Car Parking

- B2. Car parking must be provided in accordance with the RMS Guide to Traffic Generating Developments and at the following rates:
- warehouse and distribution centre: 1 space per 300 m²
 - office: 1 space per 40 m²
 - café: 1 space per 10 m².

Access

- B3. Future developments on the site must meet the following requirements:
- internal roads, driveways and parking (including grades, turn paths, sight distance requirements, aisle widths, aisle lengths and parking bay dimensions) associated with the development are constructed and maintained in accordance with the latest version of Australian Standards *AS 1428.1 Design for Access and Mobility - General Requirements for Access - New Building Work*, AS 2890.1, AS 2890.2 and AS 2890.6;
 - the swept path of the longest vehicle entering and exiting the site, as well as manoeuvrability through the site, is in accordance with the relevant Austroads guidelines;
 - vehicles must not queue on the public road network;
 - heavy vehicles and bins associated with the development are not parked on local roads or footpaths in the vicinity of the site;
 - all vehicles are wholly contained on site before being required to stop;
 - all loading and unloading of materials is carried out on-site;
 - all vehicles enter and exit the site in a forward direction;
 - all trucks entering or leaving the site with loads have their loads covered and do not track dirt onto the public road network; and
 - the proposed turning areas in the car park are kept clear of any obstacles, including parked cars, at all times.

Bicycle Parking and End-of-Trip Facilities

- B4. Bicycle parking and end-of-trip facilities is to be provided with suitable pedestrian connections linking these facilities with the offices/ warehouses in accordance with relevant guidelines and standards.

FUTURE FREIGHT NETWORK

- B5. Future DAs must make appropriate provision for the freight network identified in the MRP DCP, including the alignment and width of the corridor and access to the network within the site, to the satisfaction of TfNSW.

STORMWATER MANAGEMENT

- B6. Future development on the site must achieve compliance with the Integrated Water Cycle Management (IWCM) controls in the MRP DCP in accordance with the *Draft Technical Guidance for achieving Wianamatta South Creek*

Stormwater Management Targets (NSW Government, 2022). The Applicant must ensure sufficient land is reserved for stormwater management purposes, unless the Applicant provides evidence that an agreement is in place to demonstrate that the development is integrated into the regional stormwater system.

- B7. Development application for each future stage must include a Stormwater Management Strategy (SMS) incorporating the relevant stage and all preceding stages of the AIE. The Strategy must:
- (a) be prepared by a suitably qualified chartered professional engineer with experience in modelling, design, and supervision of WSUD systems in consultation with the relevant stormwater management authority;
 - (b) consider the approved or as modified stormwater management system for preceding stages of the development, including compliance of this system with the IWCM controls of the MRP DCP (refer to Condition D30);
 - (c) outline any stormwater infrastructure required to be upgraded, installed, or removed consistent with the site-wide stormwater management strategy for the AIE as required by Condition A4B;
 - (d) demonstrate the relevant stage can comply with the IWCM controls of the MRP DCP;
 - (e) include an assessment of any impacts on salinity and sodic soils from the future development including any proposed WSUD infrastructure; and
 - (f) detail what infrastructure may be required to connect to a precinct-wide stormwater management system for the relevant stage.

DEVELOPMENT CONTRIBUTIONS

- B8. Prior to the issue of a Construction Certificate (or at a time otherwise permitted by the contributions plan or agreed by Council) for any future stage of the Development, the Applicant must pay contributions to Council as required in accordance with the Penrith City Mamre Road Precinct Development Contributions Plan 2022, or any other contributions plan as in force when the later consent takes effect.

Note: Subject to agreement between Council and the Applicant, local contributions may be satisfied by a planning agreement or works-in-kind agreement between Council and the Applicant.

- B9. *The Environmental Planning and Assessment (Special Infrastructure Contribution – Western Sydney Aerotropolis) Determination 2022* requires special infrastructure contributions to be made for development on rezoned land within the Western Sydney Aerotropolis Special Infrastructure Contributions Area (within the meaning of that Determination). Accordingly, any special infrastructure contribution imposed by a condition of consent to a subsequent development application in relation to the site to which this consent applies is to be determined in accordance with that Determination, or any subsequent determination of the Minister under section 7.23 of the *Environmental Planning and Assessment Act 1979* (NSW), as in force when the later consent takes effect.

NOISE AND VIBRATION

- B10. Future DAs must be accompanied by a Noise and Vibration Impact Assessment. The assessment must:
- (a) identify the noise and vibration impacts during construction and operation;
 - (b) demonstrate compliance with the noise limits in Condition A16;
 - (c) provide an analysis of all external plant and equipment, including but not limited to, forklifts, air conditioners and refrigeration systems and on-site vehicle movements;
 - (d) incorporate noise mitigation measures, such as increased building setbacks, building insulation, noise barriers, layout of truck loading areas or source controls, to demonstrate the noise limits in Condition A16 can be achieved;
 - (e) recommend mitigation and management measures (excluding measures at receivers) to be implemented to minimise noise during construction and operation.

VISUAL AMENITY

Landscaping

- B11. Landscaping design for future developments must comply with the relevant requirements under the MRP DCP.
- B12. Future development must be accompanied by a Landscape Plan consistent with the key principles and plant species described in the Landscape Plans titled *Aspect Industrial Estate, Mamre Road, Kemps Creek Landscape Masterplan*, Dated October 2020.

Outdoor Lighting

- B13. Future development must ensure compliance with Australian Standards *AS/NZS 1158.3.1:2005 Pedestrian Area (Category P) Lighting* and *AS/NZS 4282:2019 Control of Obtrusive Effects of Outdoor Lighting*.

Signage

B14. Future development must include details of any external advertising signage and demonstrate compliance with the requirements of Condition D40 and Chapter 3 of the State Environmental Planning Policy (Industry and Employment) 2021 (or any substituted SEPP).

Glazing

B15. The visible light reflectivity from building materials used in façades along Mamre Road and the internal road frontages must meet the minimum requirements of the MRP DCP.

BUSHFIRE PROTECTION

B16. The Applicant shall ensure future DAs comply with:

- (a) the relevant provisions of *Planning for Bushfire Protection* (NSW RFS, 2019);
- (b) the construction standards and asset protection zone requirements recommended in the Bushfire Assessment for the Proposed Aspect Industrial Estate, prepared by Australian Bushfire Protection Planners Pty Limited, dated 6 October 2020; and
- (c) Australian Standard *AS2419.1-2005 Fire hydrant installations System design, installation, and commissioning*.

ENDEAVOUR ENERGY

B17. The Applicant must obtain relevant approvals from Endeavour Energy, or relevant service provider, prior to the construction of any electricity utility works to service each stage of the development.

SYDNEY WATER

B18. Before the commencement of operation of any future developments, the Applicant must obtain a Compliance Certificate for water and sewerage infrastructure servicing of the site under section 73 of the *Sydney Water Act 1994* (NSW).

EXTERNAL WALLS AND CLADDING

B19. The external walls of all future buildings must comply with the relevant requirements of the BCA.

B20. Future development involving the construction of external walls must ensure that the products and systems proposed for use or used in the construction of external walls (including finishes and claddings such as synthetic or aluminium composite panels) comply with the requirements of the BCA.

Note: Documentary evidence that these comply with the BCA will need to be provided to the Certifier prior to the issue of any construction certificate for these works and prior to the Occupation Certificate. A copy of the documentation given to the Certifier will also be required to be provided to the Planning Secretary within seven days after the Certifier accepts it.

PART C STAGE 1 DEVELOPMENT GENERAL CONDITIONS

OBLIGATION TO MINIMISE HARM TO THE ENVIRONMENT

- C1. In addition to meeting the specific performance measures and criteria in this consent, all reasonable and feasible measures must be implemented to prevent, and if prevention is not reasonable and feasible, minimise, any material harm to the environment that may result from the construction and operation of the Stage 1 Development, and any rehabilitation required under this consent.

TERMS OF CONSENT

- C2. The Stage 1 development may only be carried out:
- (a) in compliance with the conditions of this consent;
 - (b) in accordance with all written directions of the Planning Secretary;
 - (c) in accordance with the EIS, RtS, and ADR;
 - (d) in accordance with the Modification Assessments;
 - (e) in accordance with the Development Layout in Appendix 3; and
 - (f) in accordance with the management and mitigation measures in Appendix 5.
- C3. Consistent with the requirements in this consent, the Planning Secretary may make written directions to the Applicant in relation to:
- (a) the content of any strategy, study, system, plan, program, review, audit, notification, report or correspondence submitted under or otherwise made in relation to this consent, including those that are required to be, and have been, approved by the Planning Secretary; and
 - (b) the implementation of any actions or measures contained in any such document referred to in condition C2(a).
- C4. The conditions of this consent and directions of the Planning Secretary prevail to the extent of any inconsistency, ambiguity or conflict between them and a document listed in condition C2(c) or C2(f). In the event of an inconsistency, ambiguity or conflict between any of the documents listed in condition C2(c) or C2(f), the most recent document prevails to the extent of the inconsistency, ambiguity or conflict.

LIMITS OF CONSENT

Lapsing

- C5. This consent lapses five years after the date from which it operates unless the Stage 1 Development has physically commenced on the land to which the consent applies before that date.

Maximum GFA

- C6. The maximum GFA for the Stage 1 Development must not exceed the limits described in **Table 3**.

Table 3 Maximum GFA for the Stage 1 Development

Land Use	Maximum GFA (m ²)
Warehouse 1	
Warehouse and distribution centres and general industrial	32,686
Ancillary offices	1,200
Subtotal	33,886
Warehouse 3	
Warehouse and distribution centres and general industrial	20,735
Ancillary offices	800
Subtotal	21,535
Total	55,421

Stage 1 Development Operational Vehicles

- C6A. The Applicant must ensure no vehicles associated with the operation of Stage 1 accesses Bakers Lane, Aldington Road, and Abbots Road.

Note: Any future use of Bakers Lane, Aldington Road, and Abbots Road may be considered by the Department as part of a separate future application should future road infrastructure upgrades become available

NOTIFICATION OF COMMENCEMENT

- C7. The date of commencement of each of the following phases of the Stage 1 Development must be notified to the Department in writing, at least one month before that date:
- (a) construction; and
 - (b) operation.

EVIDENCE OF CONSULTATION

- C8. Where conditions of this consent require consultation with an identified party, the Applicant must:
- (a) consult with the relevant party prior to submitting the subject document to the Planning Secretary for approval; and
 - (b) provide details of the consultation undertaken including:
 - (i) the outcome of that consultation, matters resolved and unresolved; and
 - (ii) details of any disagreement remaining between the party consulted and the Applicant and how the Applicant has addressed the matters not resolved.

STAGING, COMBINING AND UPDATING STRATEGIES, PLANS OR PROGRAMS

- C9. With the approval of the Planning Secretary, the Applicant may:
- (a) prepare and submit any strategy, plan or program required by this consent on a staged basis (if a clear description is provided as to the specific stage and scope of the development to which the strategy, plan or program applies, the relationship of the stage to any future stages and the trigger for updating the strategy, plan or program);
 - (b) combine any strategy, plan or program required by this consent (if a clear relationship is demonstrated between the strategies, plans or programs that are proposed to be combined); and
 - (c) update any strategy, plan or program required by this consent (to ensure the strategies, plans and programs required under this consent are updated on a regular basis and incorporate additional measures or amendments to improve the environmental performance of the development).
- C10. If the Planning Secretary agrees, a strategy, plan or program may be staged or updated without consultation being undertaken with all parties required to be consulted in the relevant condition in this consent.
- C11. If approved by the Planning Secretary, updated strategies, plans, or programs supersede the previous versions of them and must be implemented in accordance with the condition that requires the strategy, plan or program.

PROTECTION OF PUBLIC INFRASTRUCTURE

- C12. Before the commencement of construction, the Applicant must:
- (a) consult with the relevant owner and provider of services that are likely to be affected by the Stage 1 Development to make suitable arrangements for access to, diversion, protection, and support of the affected infrastructure;
 - (b) prepare a dilapidation report identifying the condition of all public infrastructure in the vicinity of the site (including roads, gutters, and footpaths); and
 - (c) submit a copy of the dilapidation report to the Planning Secretary and TfNSW.
- C13. Unless the Applicant and the applicable authority agree otherwise, the Applicant must:
- (a) repair, or pay the full costs associated with repairing, any public infrastructure that is damaged by carrying out the development; and
 - (b) relocate, or pay the full costs associated with relocating, any public infrastructure that needs to be relocated as a result of the development.

DEMOLITION

- C14. All demolition must be carried out in accordance with *Australian Standard AS 2601-2001 The Demolition of Structures* (Standards Australia, 2001).

STRUCTURAL ADEQUACY

- C15. All new buildings and structures, and any alterations or additions to existing buildings and structures, that are part of the development, must be constructed in accordance with the relevant requirements of the Building Code of Australia (BCA).

Note:

- Under Part 6 of the EP&A Act, the Applicant is required to obtain construction and occupation certificates for the proposed building works.

- *Part 8 of the EP&A Regulation sets out the requirements for the certification of the development.*

SUBDIVISION

- C16. Prior to the issuing of a Subdivision Certificate for any stage of the development, detailed work-as-executed drawings shall be prepared and signed by a Registered Surveyor, which show the finished surface levels of the access road, internal roads, drainage, and any areas of fill, carried out under this consent. The work-as-executed drawing must be submitted to the Certifier and Council prior to the issue of a Subdivision Certificate.
- C17. Prior to the issuing of a Subdivision Certificate for any stage of the development, the Applicant must provide to the Certifier evidence that all matters required to be registered on title, including easements, have been lodged for registration or registered at the Land Registry Services.
- C18. Prior to the issuing of a Subdivision Certificates for any stage of the development, a certificate from an electricity and telecommunications provider must be submitted to the Certifier certifying that satisfactory service arrangements to the site have been established.

COMPLIANCE

- C19. The Applicant must ensure that all of its employees, contractors (and their sub-contractors) are made aware of, and are instructed to comply with, the conditions of this consent relevant to activities they carry out in respect of the development.

DEVELOPMENT CONTRIBUTIONS

- C20. Prior to the issue of a Construction Certificate (or at a time otherwise permitted by the contributions plan or otherwise agreed by Council) for any building in the Stage 1 Development, the Applicant must pay contributions to Council in accordance with the Penrith City Mamre Road Precinct Development Contributions Plan 2022.

Note: subject to agreement between Council and the Applicant, local contributions may be satisfied by a planning agreement or works-in-kind agreement between Council and the Applicant.

- C21. A special infrastructure contribution must be made in accordance with the Environmental Planning and Assessment (Special Infrastructure Contribution – Western Sydney Aerotropolis) Determination 2022 (2022 Determination) as in force when this development consent takes effect, for the first stage of development to which this consent applies.

A person may not apply for a subdivision certificate or construction certificate (as the case may require, having regard to the 2022 Determination) in relation to the first stage of development unless the person provides, with the application, written evidence from the Department of Planning and Environment that the special infrastructure contribution for the first stage of development (or that part of the development for which the certificate is sought) has been made or that arrangements are in force with respect to the making of the contribution.

A special infrastructure contribution may also be required to be made for further development that consists of, or involves, development on rezoned land within the meaning of the 2022 Determination on the site to which this consent applies.

Any special infrastructure contribution imposed by a condition of consent to a subsequent development application is to be determined in accordance with the 2022 Determination, or any subsequent determination of the Minister under section 7.23 of the Environmental Planning and Assessment Act 1979, as in force when that later consent takes effect.

More information

A request for assessment by the Department of Planning and Environment of the amount of the contribution that is required under this condition can be made through the NSW planning portal (<https://www.planningportal.nsw.gov.au/development-assessment/contributions/sic-online-service>). Please refer enquiries to SIContributions@planning.nsw.gov.au.

OPERATION OF PLANT AND EQUIPMENT

- C22. All plant and equipment used on site, or to monitor the performance of the Stage 1 Development, must be:
- (a) maintained in a proper and efficient condition;
 - (b) noise amelioration featured; and
 - (c) operated in a proper and efficient manner.

EXTERNAL WALLS AND CLADDING

- C23. The external walls of all buildings including additions to existing buildings must comply with the relevant requirements of the BCA.
- C24. Prior to the issue of:
- (a) any Construction Certificate relating to the construction of external walls (including the installation of finishes and claddings such as synthetic or aluminium composite panels); and

- (b) an Occupation Certificate, the Applicant must provide the Certifier with documented evidence that the products and systems proposed for use or used in the construction of external walls (including finishes and claddings such as synthetic or aluminium composite panels) comply with the requirements of the BCA.
- C25. The Applicant must provide a copy of the documentation given to the Certifier to the Planning Secretary within seven days after the Certifier accepts it.

UTILITIES AND SERVICES

- C26. Before the construction of any utility works associated with the Stage 1 Development, the Applicant must obtain relevant approvals from service providers.
- C27. Before the commencement of operation of the development, the Applicant must obtain a Compliance Certificate for water and sewerage infrastructure servicing of the site under section 73 of the *Sydney Water Act 1994* (NSW).
- C28. Before the issue of a Subdivision or Construction Certificate for any stage of the development, the Applicant (whether or not a constitutional corporation) is to provide evidence, satisfactory to the Certifier, that arrangements have been made for:
- (a) the installation of fibre-ready facilities to all individual lots and/or premises in a real estate development project to enable fibre to be readily connected to any premises that is being or may be constructed on those lots; and
 - (b) the provision of fixed-line telecommunications infrastructure in the fibre-ready facilities to all individual lots and/or premises in a real estate development project demonstrated through an agreement with a carrier.
- C29. Before the issue of the final Occupation Certificate the Applicant must demonstrate that the carrier has confirmed in writing they are satisfied that the fibre ready facilities are fit for purpose.

WORKS AS EXECUTED PLANS

- C30. Before the issue of the final Occupation Certificate, works-as-executed drawings signed by a registered surveyor demonstrating that the stormwater drainage and finished ground levels have been constructed as approved, must be submitted to the Principal Certifier.

ENVIRONMENTAL REPRESENTATIVE

- C31. The Applicant must engage an Environmental Representative (ER) to oversee construction of the Stage 1 Development. Unless otherwise agreed to by the Planning Secretary, construction of the Stage 1 development must not commence until an ER has been approved by the Planning Secretary and engaged by the Applicant. The approved ER must:
- (a) be a suitably qualified and experienced person who was not involved in the preparation of the EIS, RtS, ADR, and any additional information for the Stage 1 Development and is independent from the design and construction personnel for the Stage 1 Development;
 - (b) receive and respond to communication from the Planning Secretary in relation to the environmental performance of the Stage 1 development;
 - (c) consider and inform the Planning Secretary on matters specified in the terms of this consent;
 - (d) consider and recommend to the Applicant any improvements that may be made to work practices to avoid or minimise adverse impact to the environment and to the community;
 - (e) review the CEMP required in Condition E2 and any other documents that are identified by the Planning Secretary, to ensure they are consistent with requirements in or under this consent and if so:
 - (i) make a written statement to this effect before submission of such documents to the Planning Secretary (if those documents are required to be approved by the Planning Secretary); or
 - (ii) make a written statement to this effect before the implementation of such documents (if those documents are required to be submitted to the Planning Secretary/Department for information or are not required to be submitted to the Planning Secretary/Department);
 - (f) regularly monitor the implementation of the CEMP to ensure implementation is being carried out in accordance with the document and the terms of this consent;
 - (g) as may be requested by the Planning Secretary, help plan, attend or undertake audits of the development commissioned by the Department including scoping audits, programming audits, briefings, and site visits;
 - (h) as may be requested by the Planning Secretary, assist the Department in the resolution of community complaints;
 - (i) provide advice to the Applicant on the management and coordination of construction works on the site with adjoining sites in the Mamre Road Precinct in relation to construction traffic management, earthworks and sediment control and noise;

- (j) attend the Mamre Road Precinct Working Group (see Condition C34) in a consultative role in relation to the environmental performance of the Stage 1 development; and
 - (k) prepare and submit to the Planning Secretary and other relevant regulatory agencies, for information, an **Environmental Representative Quarterly Report** providing the information set out in the Environmental Representative Protocol under the heading 'Environmental Representative Quarterly Reports'. The **Environmental Representative Quarterly Report** must be submitted within seven calendar days following the end of each quarter for the duration of the ER's engagement for the development, or as otherwise agreed with the Planning Secretary.
- C32. The Applicant must provide the ER with all documentation requested by the ER in order for the ER to perform their functions specified in condition C31 (including preparation of the ER monthly report), as well as:
- (a) the complaints register (to be provided on a daily basis); and
 - (b) a copy of any assessment carried out by the Applicant of whether proposed work is consistent with the consent (which must be provided to the ER before the commencement of the subject work).
- C33. The Planning Secretary may at any time commission an audit of an ER's exercise of its functions under condition E16. The Applicant must:
- (a) facilitate and assist the Planning Secretary in any such audit; and
 - (b) make it a term of their engagement of an ER that the ER facilitate and assist the Planning Secretary in any such audit.

MAMRE ROAD PRECINCT WORKING GROUP

- C34. Within three months of the commencement of construction of the Stage 1 Development and until all components of the Stage 1 development are constructed and operational, the Applicant must establish and participate in a working group with relevant consent holders in the MRP, to the satisfaction of the Planning Secretary. The purpose of the working group is to consult and coordinate construction works within the MRP to assist with managing and mitigating potential cumulative environmental impacts. The working group must:
- (a) comprise at least one representative of the Applicant, the Applicant's ER, and relevant consent holders in the MRP;
 - (b) meet periodically throughout the year to discuss, formulate and implement measures or strategies to improve monitoring, coordination of the approved industrial developments in the MRP;
 - (c) regularly inform Council, TfNSW, Sydney Water and the Planning Secretary of the outcomes of these meetings and actions to be undertaken by the working group;
 - (d) review the performance of approved industrial developments in the MRP and identify trends in the data with respect to cumulative construction traffic, erosion and sediment control, noise, stormwater management and waterway health objectives under the MRP DCP;
 - (e) review community concerns or complaints with respect to environmental management;
 - (f) identify interim traffic safety measures to manage construction traffic and how these measures will be coordinated, communicated, funded and monitored in the MRP; and
 - (g) provide the Planning Secretary with an update and strategies, if a review under subclause (d) and (e) identifies additional measures and processes are required to be implemented by the working group.
- C35. Three (3) months prior to completion of construction of all components of the Stage 1 development, the Applicant is eligible to exit the working group required under condition C34. The Applicant must:
- (a) consult with the Planning Secretary;
 - (b) provide confirmation that all components of the Stage 1 development are operational; and
 - (c) advise on the date of the proposed exit.

APPLICABILITY OF GUIDELINES

- C36. References in the conditions of this consent to any guideline, protocol, Australian Standard, or policy are to such guidelines, protocols, standards, or policies in the form they are in as at the date of this consent.
- C37. However, consistent with the conditions of this consent and without altering any limits or criteria in this consent, the Planning Secretary may, when issuing directions under this consent in respect of ongoing monitoring and management obligations, require compliance with an updated or revised version of such a guideline, protocol, Standard or policy, or a replacement of them.

ADVISORY NOTES

CONSOLIDATED CONSENT

AN1. All licences, permits, approvals and consents as required by law must be obtained and maintained as required for the development. No condition of this consent removes any obligation to obtain, renew or comply with such licences, permits, approvals and consents.

FOR INFORMATION

PART D STAGE 1 DEVELOPMENT SPECIFIC ENVIRONMENTAL CONDITIONS

TRAFFIC AND ACCESS

Construction Traffic Management Plan

- D1. Prior to the commencement of construction of the Stage 1 Development, the Applicant must prepare a Construction Traffic Management Plan (CTMP) for the development to the satisfaction of the Planning Secretary. The plan must form part of the CEMP required by condition E2 and must:
- (a) be prepared by a suitably qualified and experienced person(s);
 - (b) be prepared in consultation with Council and TfNSW;
 - (c) detail the traffic management and contingency measures that are to be implemented for the site, particularly during the construction works for the Mamre Road/Access Road 1 intersection, to ensure access to the site and road safety and network efficiency is maintained, including interim traffic safety controls and management measures;
 - (d) detail heavy vehicle routes, access, and parking arrangements;
 - (e) include a Driver Code of Conduct to:
 - (i) minimise the impacts of earthworks and construction on the local and regional road network;
 - (ii) minimise conflicts with other road users;
 - (iii) minimise road traffic noise; and
 - (iv) ensure truck drivers use specified routes;
 - (f) include a program to monitor the effectiveness of these measures; and
 - (g) if necessary, detail procedures for notifying residents and the community (including local schools), of any potential disruptions to routes.
- D2. The Applicant must:
- (a) not commence construction until the CTMP required by condition D1 is approved by the Planning Secretary; and
 - (b) implement the most recent version of the CTMP approved by the Planning Secretary for the duration of construction.

Operational Traffic Monitoring Program

- D3. Prior to commencement of operation of Building 1 or 3 and for a minimum period of 12 months of operation, the Applicant must establish an Operational Traffic Monitoring Program. The program must verify light and heavy vehicle traffic numbers, including the heavy vehicle volumes limited by Condition D3A, against the prediction in the Aspect Industrial Estate, Mamre Road Precinct – Modification 2 to State Significant Development Application (SSD-10448) Traffic Impact Assessment prepared by Ason Group, dated 25 July 2022. The Program must also monitor the effectiveness of the traffic management measures to the satisfaction of the Planning Secretary and include but not be limited to the following:
- (a) detail the numbers and frequency of truck movements, sizes of trucks, vehicle routes and hours of operation;
 - (b) queue monitoring at the Mamre Road/Access Road 1 intersection and background travel counts on Mamre Road;
 - (c) verify the predicted traffic numbers and level of service against the actual impacts of the Stage 1 Development, and analyse the potential cause of any significant discrepancies;
 - (d) consider the current capacity and efficiency of the existing road network including Mamre Road; and
 - (e) include procedures for the reporting and monitoring of results to evaluate the traffic performance of the Stage 1 Development.
- D3A. The Applicant must ensure the total number of hourly heavy vehicles entering Warehouse 1 from Access Road 1 does not exceed 22 or is in line with Part 6 of Austroads Standards Guide to Traffic Management, whichever is lesser.

Internal Access Roads

- D4. Prior to the commencement of any construction works for Building 1 or 3 (excluding site-wide bulk earthworks) as described in the ADR, the Applicant must:
- (a) prepare a concept design of the Stage 1 Phase 2 road works in accordance with the design requirements in the MRP DCP and in consultation with the relevant roads authority, to the satisfaction of the Planning Secretary; and

- (b) consult with the relevant roads authority concerning the processes for dedication of the lands for the internal Access Roads 1 and 3 (North and South) including the roundabout shown in Figure 1: in Appendix 1.
- D5. Within one month of registration of lot(s) for internal Access Roads 1 and 3 including the roundabout at the Land Registry Services, the Applicant must notify the Planning Secretary that the lands for the internal Access Roads 1 and 3 (North and South) has been dedicated.
- D6. Prior to issue of an Occupation Certificate for Building 3, the Applicant must construct and operate the Stage 1 Phase 1 road works shown in **Figure 4** in Appendix 3 to the satisfaction of relevant road authority.
- D6A. Within six months of the issuing of an Occupation Certificate for Warehouse 9 and prior to the issuing of an Occupation Certificate for Warehouse 3, the Applicant must construct and operate the Stage 1 Phases 1 and 2 road works, including completing construction of Mamre Road/Access Road 1 intersection and the installation of the traffic signals to the satisfaction of TfNSW.
- D7. Within six months of the approval of this consent or as otherwise agreed by the Planning Secretary, the Applicant must prepare and submit the following plans to facilitate the construction and delivery of Access Road 3 – North, in consultation with Council and landowner of 784-786 Mamre Road, Kemps Creek (Lot 59 DP259135), and to the satisfaction of the Planning Secretary:
- (a) a Staging Plan for the riparian corridor realignment works and Access Road 3 – North construction, including:
- details of the scope of works to be undertaken on the site and the adjoining site at 784-786 Mamre Road, Kemps Creek (Lot 59 DP259135) (see **Figure 4**);
 - details of how the further riparian corridor realignment and road construction works at the junction between the site and 784-786 Mamre Road, Kemps Creek (Lot 59 DP259135) will be coordinated and delivered;
 - an arrangement on timing of the works; and
- (b) a detailed design plan of Access Road 3 – North prepared in accordance with the design requirements under the MRP DCP.
- Note: The detailed design of Access Road 3 - North and any changes to the approved riparian corridor alignment may require modification(s) to SSD-10448 or separate DA(s).*
- D8. Prior to issue of an Occupation Certificate for any other buildings or warehouses in the Development, the Applicant must ensure the Stage 1 Phase 2 road works are constructed and operational.
- D9. The Applicant must ensure that the portion of Access Road 3 – North to be located on the site is constructed and operational in accordance with the design plans required under Condition D7.

Access Arrangements

- D10. Prior to the commencement of construction of any works (excluding bulk earthworks) for Buildings 1 or 3, the Applicant must submit design plans to the satisfaction of the relevant roads authority, which demonstrates the proposed accesses to the development are designed to accommodate the turning path of a 30 m PBS Level 2 vehicle.
- D11. Prior to the commencement of any construction works (excluding bulk earthworks) for Warehouse 1 as described in the EIS, the Applicant must prepare and submit design plans in consultation with TfNSW, FRNSW, and Council, and to the satisfaction of the Planning Secretary, demonstrating access to the development from Access Road 1 complies with relevant FRNSW and TfNSW access requirements.
- D11A. The Applicant must ensure:
- Warehouse 1 driveway on Access Road 1 is used by inbound heavy vehicles only;
 - Warehouse 3 driveway on Access Road 1 adjacent Warehouse 2 is used by inbound heavy vehicles only;
 - Warehouse 3 driveway on Access Road 1 opposite Warehouse 8 car park driveway is used by fire engines only; and
 - Warehouse 3 driveway on Access Road 2 is used by outbound heavy vehicles, inbound and outbound light vehicles.
- D11B. Prior to the commencement of operation of Warehouse 3, the Applicant must:
- install stop signs at Warehouse 3 where the loading area adjoins the private driveway to the north of the Warehouse 3 building; and
 - finish line-marking of the private driveway to the north of the Warehouse 3 building.
- D11C. Prior to the Mamre Road/Access Road 1 intersection being completed and commissioned, the Applicant must ensure only vehicles associated with Warehouses 1 and 9 operations are permitted to use the temporary left-in/left-out construction access on Mamre Road shown in Figure 6 and Figure 7 as described in Modification 5 in addition to vehicles relating to construction activities.

- D11D. Prior to the commencement of operation of Warehouse 1, the Applicant must submit details of all traffic control facilities including but not limited to line-marking and safety control for Stages 1 and 2 temporary access roads shown in purple in **Figure 6** and **Figure 7** in Appendix 3. These traffic control facilities are to be prepared in consultation with Council and to the satisfaction of the Planning Secretary.
- D11E. Prior to the commencement of operation of Warehouse 1, the Applicant must submit a pre-opening Road Safety Audit (RSA) prepared by an accredited Road Safety Auditor for the Stages 1 and 2 temporary access roads shown in purple in **Figure 6** and **Figure 7** in Appendix 3. The RSA is to be prepared in consultation with Council and to the satisfaction of the Planning Secretary and must outline any recommendations for road safety improvements and demonstrate the improvements have been implemented.
- D11F. Prior to the commencement of operation of Warehouse 1, the Applicant must install all traffic control facilities shown in **Figure 8** to **Figure 12** in Appendix 3, including any amendments to the facilities made following consultation with Council.
- D11G. The Applicant must remove the Stage 1 temporary access road shown in **Figure 6** in Appendix 3 and all temporary traffic control facilities for that road at the completion and commissioning of Access Road 4.
- D11H. Prior to the commissioning of Access Road 4, the Applicant must install all traffic control facilities shown in **Figure 13** to **Figure 17** in Appendix 3, including any amendments to the facilities made following consultation with Council.
- D11I. The Applicant must remove the Stage 2 temporary construction access roads shown in **Figure 7**, **Figure 12**, **Figure 13**, **Figure 15**, and **Figure 17** in Appendix 3 and all temporary traffic control facilities at the completion and commissioning of Mamre Road/Access Road 1 intersection.
- D11J. The Applicant must ensure all vehicles including those associated with the operation of Stage 1 development utilise the washdown area shown in **Figure 6** and **Figure 7** to ensure all vehicles do not track dirt onto the public road network before leaving the site as required by Condition D21(g).
- D11K. The Applicant must monitor construction and operational traffic volumes using the temporary left-in/left-out access off Mamre Road for the period that the temporary construction access is being used. Traffic volumes must be reported to TfNSW and the Planning Secretary on a monthly basis.
- D11L. Within three months of approval of Modification 7, the Applicant must install a 60 kilometre per hour (km/hr) road works speed limit on Mamre Road between Bakers Lane and Abbots Road to the satisfaction of TfNSW. The road works speed limit must remain in operation 24 hours a day, seven days a week, unless otherwise instructed by TfNSW.

Mamre Road/Access Road 1 intersection works

- D12. Prior to the Applicant entering into a Works Authorisation Deed (WAD) required by condition D13, or otherwise agreed by the Planning Secretary, the Applicant must:
- obtain landowners consent and enter into an agreement with the owner(s) of 833B Mamre Road, Kemps Creek (Lot 28, DP258414) to relocate or remove an existing gated driveway on that property outside of the footprint of the Mamre Road/Access Road 1 intersection signals to the satisfaction of Council and the Planning Secretary;
 - provide a copy of the landowner's consent and signed agreement described under condition D12(a) to TfNSW and the Planning Secretary; and
 - remove and relocate the driveway in accordance with the agreement.
- D13. The Applicant must enter into a Works Authorisation Deed for the **Mamre Road/Access Road 1** intersection works with TfNSW. The WAD must be executed prior to the submission of the detailed design required by condition D12 to TfNSW for approval.
- D13A. The Applicant must enter into a WAD with TfNSW for establishing a temporary left in/left out construction access and left-turn lane on Mamre Road to be used by vehicles during Stage 1 construction. The WAD must:
- include details of the removal of the temporary left in/left out construction access and left-turn lane on Mamre Road; and
 - be executed prior to commencement of construction of the temporary left in/left out construction access and left-turn lane on Mare Road.
- D13B. The Applicant must:
- ensure the temporary left in/left out construction access and left-turn lane are maintained at no cost to TfNSW;
 - remove the temporary left in/left out construction access and left-turn lane at the completion and commissioning of the Mamre Road/Access Road 1 intersection, at no cost to TfNSW; and
 - reinstate shoulder along Mamre Road within three months of satisfying Condition D6, at cost to TfNSW.

- D14. Prior to the issue of a construction certificate for the Mamre Road/Access Road 1 intersection (the intersection) construction, the Applicant must finalise and submit the detailed design of the intersection works, including an endorsed Traffic Signal Plan (TSP) to TfNSW for approval. The TSP must:
- (a) demonstrate the proposed traffic control light at the intersection is designed in accordance with Austroads Guide to Road Design, RMS Signal Design Manual, and Australian Codes of Practice; and
 - (b) be approved and endorsed by a suitably qualified practitioner.
- D15. The Applicant must obtain a Road Occupancy Licence (ROL) from TfNSW Transport Management Centre for any works that may impact on traffic flows on Mamre Road during construction.

Redundant Driveways on Mamre Road

- D16. The Applicant must remove redundant driveways on Mamre Road within the site's boundaries and replace with kerb and gutter to match existing in accordance with TfNSW requirements. Detailed design plans of the proposed kerb and gutter are to be submitted to TfNSW for approval prior to the issue of a Construction Certificate and commencement of any road works within Mamre Road.

Structural integrity of road infrastructure

- D17. Prior to commencement of any works on Mamre Road, the Applicant must prepare and submit detailed design plans and hydraulic calculations of any changes to the stormwater drainage system to TfNSW for approval.
- D18. At least six weeks prior to commencement of bulk earthworks within Mamre Road, the Applicant must submit design drawings and documents relating to the excavation of the site and support structures in accordance with TfNSW Technical Direction GTD2012/001.
- D19. Should the Applicant propose to excavate below the level of the base of the footings of the adjoining roads and driveways, at least seven days prior to commencement of excavation, the Applicant must provide notice of the intention to excavate below the base of the footings to owner(s) of that roads and driveways. The notice must include complete details of the proposed excavation including but not limited to the extent and duration of works.

Parking

- D20. The Applicant must provide sufficient parking facilities on-site, including for heavy vehicles and for site personnel, to ensure that traffic associated with the development does not utilise public and residential streets or public parking facilities.

Operating Conditions

- D21. The Applicant must ensure:
- (a) internal roads, driveways and parking (including grades, turn paths, sight distance requirements, aisle widths, aisle lengths and parking bay dimensions) associated with the development are constructed and maintained in accordance with the latest version of *AS 2890.1:2004 Parking facilities Off-street car parking* (Standards Australia, 2004) and *AS 2890.2:2002 Parking facilities Off-street commercial vehicle facilities* (Standards Australia, 2002);
 - (b) the swept path of the longest vehicle entering and exiting the site, as well as manoeuvrability through the site, is in accordance with the relevant AUSTROADS guidelines;
 - (c) the development does not result in any vehicles queuing on the public road network;
 - (d) heavy vehicles and bins associated with the development are not parked on local roads or footpaths in the vicinity of the site;
 - (e) all vehicles are wholly contained on site before being required to stop;
 - (f) all loading and unloading of materials is carried out on-site;
 - (g) all trucks entering or leaving the site with loads have their loads covered and do not track dirt onto the public road network; and
 - (h) the proposed turning areas in the car park are kept clear of any obstacles, including parked cars, at all times.

Workplace Travel Plan

- D22. Prior to the commencement of operation of any part of the development, the Applicant must prepare a Workplace Travel Plan and submit a copy to the Planning Secretary. The Workplace Travel Plan must form part of the OEMP required by condition E5 and must:
- (a) be prepared in consultation with TfNSW and Council;
 - (b) outline facilities and measures to promote public transport usage, such as car share schemes and employee incentives; and
 - (c) describe pedestrian and bicycle linkages and end of trip facilities available on-site.

D23. The Applicant must implement the most recent version of the Workplace Travel Plan for the duration of the development.

SOILS, WATER QUALITY AND HYDROLOGY

Imported Soil

D24. The Applicant must:

- (a) ensure that only VENM, ENM, or other material approved in writing by the EPA is brought onto the site;
- (b) keep accurate records of the volume and type of fill to be used; and
- (c) make these records available to the Planning Secretary upon request.

Erosion and Sediment Control

D25. Prior to the commencement of any construction or other surface disturbance, the Applicant must design and detail the erosion and sediment control measures for the site to ensure the construction phase IWCM controls in the MRP DCP are achieved. Detailed Erosion and Sediment Control Plans (ESCP) and drawings must:

- (a) be prepared by a Chartered Professional Erosion and Sediment Control (CPESC) specialist;
- (b) be prepared in accordance with *Managing Urban Stormwater: Soils and Construction – Volume 1: Blue Book* (Landcom, 2004) and with the WSUD design principles set out in the *Draft Technical Guidance for achieving Wianamatta South Creek Stormwater Management Targets* (NSW Government, 2022);
- (c) demonstrate the construction approach and timing to ensure the construction phase stormwater quality targets can be met; and
- (d) be included in the CEMP required by condition E2.

D26. The Applicant must ensure delivery and operation of all construction phase erosion and sediment controls on the site is supervised and certified by a CPESC. Monthly audits are to be completed by CPESC and kept on record for the duration of the construction and an additional 12 months following completion of construction works. Discharge Limits

Discharge Limits

D27. The development must comply with section 120 of the POEO Act, which prohibits the pollution of waters, except as expressly provided for in an EPL.

Stormwater Management System

D28. Prior to the commencement of operation of the development, the Applicant must implement the Stormwater Management System described in the ADR amended by Modification Assessments and as shown in [Figure 2 Figures 5 and 5A in Appendix 2](#). The design and subsequent construction and establishment of the WSUD systems must be supervised and certified by a suitably qualified chartered professional engineer with experience in modelling, design, and supervision of WSUD systems.

D29. All stormwater infrastructure, including bio-retention basins, shall remain under the ownership, control, and care of the registered proprietor of the lots. Upstream drainage catchment pipes are to be located outside of the public road reserve and remain in private ownership, in accordance with Council requirements.

Stormwater Management Plan

D30. Within three (3) months prior to the commencement of operation of either Building 1 or 3 of the Stage 1 Development, the Applicant must prepare a Stormwater Management Plan (SMP) to the satisfaction of the Planning Secretary. The SMP must:

- (a) be prepared by a suitably qualified chartered professional engineer with experience in modelling, design, and supervision of WSUD systems whose appointment has been endorsed by the Planning Secretary;
- (b) be prepared in consultation with the Environment and Heritage, Sydney Water, DPE, and Council;
- (c) [address the requirements under the heading 'Water and Stormwater Management Plan' outlined in the Environment and Heritage's letter dated 18 December 2023;](#)
- (d) describe the baseline soil, surface water and groundwater conditions at the site;
- (e) detail a monitoring program to monitor:
 - (i) surface water flows and quality;
 - (ii) surface water storage and use;
 - (iii) sediment basin operation;
 - (iv) the performance of the Stage 1 stormwater management system to demonstrate compliance with the IWCM controls in the MRP DCP;

- (f) detail a stormwater management strategy and designs of each WSUD system, including:
 - (i) description of how the requirements and objectives of the IWCM controls of the DCP will be achieved, including provisions for how stormwater will be managed and monitored;
 - (ii) details of how the Stage 1 Development will be designed and developed so it can potentially connect to precinct-wide stormwater infrastructure, if required
 - (iii) engineering drawings completed and certified by a chartered professional engineer with experience in modelling, design, and supervision of WSUD systems that detail the WSUD measures;
 - (iv) landscape drawings that include planting and hardscape details of the WSUD systems;
- (g) include a protocol for investigation of any non-compliances of the IWCM controls in the MRP DCP controls described in condition D30(f) and contingency measures that would be implemented should issues arise;
- (h) include evidence that the design and mix of WSUD infrastructure has considered ongoing operation and maintenance, including a detailed lifecycle cost assessment (including capital, operation/maintenance, and renewal costs over 30 years); and
- (i) include a Maintenance Plan for WSUD measures.

D31. The Applicant must:

- (a) not commence the operation of the development until the SMP required by condition D30 is approved by the Planning Secretary;
- (b) implement the most recent version of the SMP approved by the Planning Secretary for the duration of the development; and
- (c) ensure all WSUD systems are constructed under the supervision of a suitably qualified chartered professional engineer with experience in modelling, design, and supervision of WSUD systems.

Easements and Maintenance

D32. Prior to the issue of any Occupation Certificate, a restriction on the use of land and positive covenant relating to the:

- (a) stormwater management system (including on-site detention and water sensitive urban design)
- (b) trunk drainage

shall be registered on the title of the property. The restriction on the use of land and positive covenant shall be in Council's standard wording as detailed in Council's Stormwater Specification for Building Developments - Appendix F, available on Council's Website.

D33. The stormwater management system must continue to be operated and maintained in perpetuity for the life of the development in accordance with the final operation and maintenance management plan. Regular inspection records are required to be maintained and made available Council on request. All necessary improvements are required to be made immediately upon awareness of any deficiencies in the stormwater management systems.

Dam Decommissioning Strategy

D34. Prior to commencement of construction of the Stage 1 Development, the Applicant must implement the Dam Decommissioning Strategy included in the EIS. The Applicant must implement the most recent version of the Dam Decommissioning Strategy for the duration of construction.

Groundwater Management Plan

D35. Prior to commencement construction of the Stage 1 Development, the Applicant must implement the Groundwater Management Plan included in the EIS. The Applicant must implement the most recent revision of the Groundwater Management Plan for the duration of the development.

Salinity Management

D36. The Applicant must prepare a Salinity Management Plan, which must form part of the CEMP in accordance with Condition E2, that addresses all aspects of the Stage 1 development. The Applicant must implement the most recent revision of the Salinity Management Plan for the duration of construction.

VISUAL AMENITY

Landscaping

D37. Prior to the commencement of operation, the Applicant must prepare a Landscape Management Plan to manage the revegetation and landscaping works on-site, to the satisfaction of the Planning Secretary. The plan must form part of an OEMP in accordance with condition E5. The plan must:

- (a) detail the species to be planted on-site;

- (b) demonstrate the species are suitable in relation to wildlife management in proximity to the future Western Sydney Airport;
- (c) describe the monitoring and maintenance measures to manage revegetation and landscaping works; and
- (d) be consistent with the Applicant’s Management and Mitigation Measures detailed at Appendix 6.

D38. The Applicant must:

- (a) not commence operation until the Landscape Management Plan is approved by the Planning Secretary.
- (b) must implement the most recent version of the Landscape Management Plan approved by the Planning Secretary; and
- (c) maintain the landscaping and vegetation on the site in accordance with the approved Landscape Management Plan required by condition D37 for the life of the development.

D38A. The Applicant must ensure street trees on all Access Roads are planted at a spacing of 10 m or less.

Lighting

D39. The Applicant must ensure the lighting associated with the development:

- (a) complies with the latest version of AS 4282-1997 - *Control of the obtrusive effects of outdoor lighting* (Standards Australia, 1997); and
- (b) is mounted, screened, and directed in such a manner that it does not create a nuisance to surrounding properties or the public road network.

Signage and Fencing

D40. All signage and fencing must be erected in accordance with the development plans included in the ADR.

Note: *This condition does not apply to temporary construction and safety related signage and fencing.*

NOISE

Hours of Work

D41. The Applicant must comply with the hours detailed in **Table 4**, unless otherwise agreed in writing by the Planning Secretary.

Table 4 *Hours of Work*

Activity	Day	Time
Earthworks and construction	Monday – Friday	7 am to 6 pm
	Saturday	8 am to 1 pm
Operation	Monday – Sunday	24 hours

D42. Works outside of the hours identified in condition D41 may be undertaken in the following circumstances:

- (a) works that are inaudible at the nearest sensitive receivers;
- (b) works agreed to in writing by the Planning Secretary;
- (c) for the delivery of materials required outside these hours by the NSW Police Force or other authorities for safety reasons; or
- (d) where it is required in an emergency to avoid the loss of lives, property or to prevent environmental harm.

Construction Noise Limits

D43. The development must be constructed to achieve the construction noise management levels detailed in *the Interim Construction Noise Guideline* (DECC, 2009) (as may be updated or replaced from time to time). All feasible and reasonable noise mitigation measures must be implemented and any activities that could exceed the construction noise management levels must be identified and managed in accordance with the management and mitigation measures in the Appendix 5.

Construction Noise Management Plan

D44. The Applicant must prepare a Construction Noise Management Plan (CNMP) for the development to the satisfaction of the Planning Secretary. The Plan must form part of a CEMP in accordance with condition E2 and must:

- (a) be prepared by a suitably qualified and experienced noise expert whose appointment has been endorsed by the Planning Secretary;

- (b) be approved by the Planning Secretary prior to the commencement of construction of each phase of the development;
- (c) describe procedures for achieving the noise management levels in EPA's *Interim Construction Noise Guideline* (DECC, 2009) (as may be updated or replaced from time to time);
- (d) describe the measures to be implemented to manage high noise generating works, in close proximity to sensitive receivers, particularly for noise mitigation eligible receivers shown in **Figure 19**: in Appendix 5, including but not limited to the following:
 - (i) details of a real-time noise monitoring system to identify occurrence of highly noise affected levels as defined in the *Interim Construction Noise Guideline*; and
 - (ii) describe procedures for implementing respite periods and temporary relocation following identification of highly noise affected levels.
- (e) include a complaints management system that would be implemented for the duration of the development.

D45. The Applicant must:

- (a) not commence construction of any relevant stage until the CNMP required by condition D44 is approved by the Planning Secretary; and
- (b) implement the most recent version of the CNMP approved by the Planning Secretary for the duration of construction.

Noise Agreement

- D46. Prior to the commencement of operation of the Stage 1 development an, the Applicant must enter into an agreement with the noise mitigation eligible receivers shown in **Figure 19**: in Appendix 5.
- D47. Prior to the commencement of operation of the Stage 1 development, the Applicant must submit copies of the noise agreements required under Condition D46 to the Planning Secretary.
- D48. The noise agreement required under Condition D46 must be in force until the existing residential use ceases on the land subject to the agreement or a development application for general industrial or other employment uses applies to the land, whichever is the sooner.

Vibration Criteria

- D49. Vibration caused by construction at any residence or structure outside the site must be limited to:
- (a) for structural damage, the criteria set in the latest version of *DIN 4150-3:2016-12 Vibration in Buildings – Part 3: Effects on Structures* (German Institute for Standardisation, 2016); and
 - (b) for human exposure, the acceptable vibration values set out in the *Environmental Noise Management Assessing Vibration: a technical guideline* (DEC, 2006) (as may be updated or replaced from time to time).
- D50. The Applicant must offer and, if the offer is accepted, implement monitoring of vibration levels during construction at 884-902 Mamre Road (Lot 53 DP259135), to the satisfaction of the Planning Secretary. Any vibration monitoring must be undertaken during the entirety of the construction period. If the criteria in Condition D49 are exceeded, management and mitigation measures must be developed and implemented to address any exceedances.

Dilapidation Reporting

- D51. Prior to commencement of construction, the Applicant must offer and prepare (if the offer is accepted) a pre-construction dilapidation report at 884-902 Mamre Road (Lot 53 DP259135). The report must be submitted to the Planning Secretary and the relevant property owner(s) prior to construction works commencing on the site.

Operational Noise Limits

D52. The Applicant must:

- (a) establish intermediate noise monitoring locations in accordance with the Operational Noise Management Plan (refer to condition A16A) prior to commencement of operation of the Stage 1 Development;
- (b) ensure the cumulative noise emission of fixed external mechanical plant for each warehouse building do not exceed 90 dB(A) and do not exhibit tonal characteristics or strong low frequency content; and
- (c) ensure the noise generated by operation of the Stage 1 Development does not exceed the noise limits in condition A16.

Noise Verification Report

- D53. Within three months of the commencement of operation of the Stage 1 Development, the Applicant must submit a noise verification report to the satisfaction of the Planning Secretary. The report must be prepared by a suitably qualified and experienced acoustic consultant and include:
- (a) an analysis of compliance with noise limits specified in condition D52;

- (b) an outline of mitigation and management measures to reduce any exceedances of the limits specified in condition D52 (excluding measures to be implemented at the receivers); and
- (c) a description of contingency measures in the event management actions are not effective in reducing noise levels to an acceptable level.

AIR QUALITY

Dust Minimisation

- D54. The Applicant must take all reasonable steps to minimise dust generated during all works authorised by this consent.
- D55. During construction, the Applicant must ensure that:
- (a) exposed surfaces and stockpiles are suppressed by regular watering;
 - (b) all trucks entering or leaving the site with loads have their loads covered;
 - (c) trucks associated with the development do not track dirt onto the public road network;
 - (d) public roads used by these trucks are kept clean; and
 - (e) land stabilisation works are carried out progressively on site to minimise exposed surfaces.

Construction Air Quality Management Plan

- D56. Prior to the commencement of construction, the Applicant must prepare a Construction Air Quality Management Plan (CAQMP) to the satisfaction of the Planning Secretary. The CAQMP must form part of the CEMP required by condition E2 and must:
- (a) be prepared by a suitably qualified and experienced person(s);
 - (b) detail and rank all emissions from all sources during construction of the development, including particulate emissions;
 - (c) describe a program that is capable of evaluating the performance of the construction and determining compliance with key performance indicators;
 - (d) identify the control measures that will be implemented for each emission source; and
 - (e) nominate the following for each of the proposed controls:
 - (i) key performance indicator;
 - (ii) monitoring method;
 - (iii) location, frequency, and duration of monitoring;
 - (iv) record keeping;
 - (v) complaints register;
 - (vi) response procedures; and
 - (vii) compliance monitoring.
- D57. The Applicant must:
- (a) not commence construction until the CAQMP required by condition D56 is approved by the Planning Secretary; and
 - (b) implement the most recent version of the CAQMP approved by the Planning Secretary for the duration of the development.

Odour Management

- D58. The Applicant must ensure the development does not cause or permit the emission of any offensive odour (as defined in the POEO Act).

ABORIGINAL HERITAGE

Statutory Requirements

- D59. Prior to the commencement of construction of Stage 1 development, the Applicant must register identified Aboriginal items or objects on the Heritage NSW Aboriginal Heritage Information Management System (AHIMS) Aboriginal Sites Register.

Archaeological Salvage

- D60. Prior to the commencement of construction of Stage 1, the Applicant must engage a suitably qualified and experienced expert to undertake an archaeological salvage excavation of the MAM AS 1901. The Applicant must undertake the salvage excavation in accordance with the requirements of Heritage NSW, and must:
- (a) implement the methodology for the reburial of all salvaged Aboriginal objects within the site detailed in the Reburial Methodology, prepared by artefact, dated 26 February 2021; and
 - (b) provide the Registered Aboriginal Parties (RAPs) an opportunity to collect Aboriginal objects across the site.
- D61. The Applicant must prepare an archaeological report of the salvage excavation undertaken in accordance with Condition D60. An interim report of the salvage excavation must be provided to the satisfaction of the Planning Secretary within one month of completion of the salvage work and a final report provided within 12 months of completion of the salvage work.

Unexpected Finds Protocol

- D62. If any item or object of Aboriginal heritage significance is identified on site:
- (a) all work in the immediate vicinity of the suspected Aboriginal item or object must cease immediately;
 - (b) a 10 m wide buffer area around the suspected item or object must be cordoned off; and
 - (c) Heritage NSW must be contacted immediately.
- D63. Work in the immediate vicinity of the Aboriginal item or object may only recommence in accordance with the provisions of Part 6 of the *National Parks and Wildlife Act 1974* (NSW).

HISTORIC HERITAGE

Unexpected Finds Protocol

- D64. If any archaeological relics are uncovered during the course of the work, then all works must cease immediately in that area. Unexpected finds must be evaluated and recorded in accordance with the requirements of Heritage NSW and details included in the salvage excavation report required under Condition D60(b).

BIODIVERSITY

- D65. Prior to any clearing or construction works the Applicant must purchase and retire 1 ecosystem credit to offset the removal of *Grey Box – Forest Red Gum grassy woodland on flats of the Cumberland Plain, Sydney Basin Bioregion* and 3 species credits to offset the removal of *Myotis macropus* at the site. The ecosystem and species credits must be retired in accordance with the requirements of the E&H Group's Biodiversity Offsets Scheme and the *Biodiversity Conservation Act 2016* (NSW).
- D66. The requirement to retire ecosystem and species credits (see Condition D65) may be satisfied by payment to the Biodiversity Conservation Fund of an amount equivalent to the number and classes of ecosystem and species credits, as calculated by the E&H Group's Biodiversity Offsets Payment Calculator.
- D67. The Applicant must provide the Planning Secretary with evidence that:
- (a) the retirement of ecosystem credits has been completed (see Condition D65); or
 - (b) a payment has been made to the Biodiversity Conservation Fund (see Condition D66),
- prior to undertaking any clearing of native vegetation and *Myotis macropus* habitat.
- D68. Prior to commencement of dam dewatering and construction of the Stage 1 Development, the Applicant must implement the Flora and Fauna Management Plan included in the RtS. The Applicant must implement the most recent revision of the Flora and Fauna Management Plan for the duration of construction works.

Vegetation Management Plan – Riparian Corridor

- D69. Within six (6) months of the commencement of operation, the Applicant must complete the revegetation of the realigned riparian corridor in accordance with the Vegetation Management Plan (VMP) included in the RTS and ensure that the realigned riparian corridor provides for a full hierarchy of appropriate ground cover, shrubs and trees. The Applicant must implement the most recent version of the VMP for a maintenance period of up to five years following the completion of the establishment phase of the VMP.

HAZARDS AND RISK

Dangerous Goods

- D70. The quantities of dangerous goods stored and handled at the site must be below the threshold quantities listed in the Department of *Planning's Hazardous and Offensive Development Application Guidelines – Applying SEPP 33* at all times.

Bunding

D71. The Applicant must store all chemicals, fuels and oils used on-site in appropriately banded areas in accordance with the requirements of all relevant Australian Standards, and/or EPA's *Storing and Handling of Liquids: Environmental Protection – Participants Manual* (Department of Environment and Climate Change, 2007).

WASTE MANAGEMENT

Pests, Vermin and Noxious Weed Management

D72. The Applicant must:

- (a) implement suitable measures to manage pests, vermin and declared noxious weeds on the site; and
- (b) inspect the site on a regular basis to ensure that these measures are working effectively, and that pests, vermin or noxious weeds are not present on site in sufficient numbers to pose an environmental hazard or cause the loss of amenity in the surrounding area.

Note: For the purposes of this condition, noxious weeds are those species subject to an order declared under the Biosecurity Act 2015 (NSW).

Waste Storage and Processing

D73. Prior to the commencement of construction of Building 1 and 2, the Applicant must obtain agreement from Council for the design of the waste storage area for each warehouse.

D74. Waste must be secured and maintained within designated waste storage areas at all times and must not leave the site onto neighbouring public or private properties.

Waste Management Plan

D75. The Applicant must implement the Waste Management Plan (WMP) prepared by MRA Consulting Group, dated 30 September 2020 in the EIS for the duration and construction and operation of Stage 1 of the development.

Statutory Requirements

D76. All waste materials removed from the site must only be directed to a waste management facility or premises lawfully permitted to accept the materials.

Unexpected Finds

D77. Prior to the commencement of earthworks, the Applicant must prepare an unexpected contamination procedure to ensure that potentially contaminated material is appropriately managed. The procedure must form part of the of the CEMP in accordance with condition E2 and must ensure any material identified as contaminated and is required to be removed from the site must be disposed off-site, with the disposal location and results of testing submitted to the Planning Secretary, prior to its removal.

PART E STAGE 1 DEVELOPMENT ENVIRONMENTAL MANAGEMENT, REPORTING AND AUDITING

ENVIRONMENTAL MANAGEMENT

Management Plan Requirements

- E1. Management plans required under this consent must be prepared in accordance with relevant guidelines, and include:
- (a) detailed baseline data;
 - (b) details of:
 - (i) the relevant statutory requirements (including any relevant approval, licence or lease conditions);
 - (ii) any relevant limits or performance measures and criteria; and
 - (iii) the specific performance indicators that are proposed to be used to judge the performance of, or guide the implementation of, the development or any management measures;
 - (c) a description of the measures to be implemented to comply with the relevant statutory requirements, limits, or performance measures and criteria;
 - (d) a program to monitor and report on the:
 - (i) impacts and environmental performance of the development; and
 - (ii) effectiveness of the management measures set out pursuant to paragraph (c) above;
 - (e) a contingency plan to manage any unpredicted impacts and their consequences and to ensure that ongoing impacts reduce to levels below relevant impact assessment criteria as quickly as possible;
 - (f) a program to investigate and implement ways to improve the environmental performance of the development over time;
 - (g) a protocol for managing and reporting any:
 - (i) incident and any non-compliance (specifically including any exceedance of the impact assessment criteria and performance criteria);
 - (ii) complaint;
 - (iii) failure to comply with statutory requirements; and
 - (h) a protocol for periodic review of the plan.

Note: *the Planning Secretary may waive some of these requirements if they are unnecessary or unwarranted for particular management plans*

CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN

- E2. The Applicant must prepare a Construction Environmental Management Plan (CEMP) in accordance with the requirements of condition E1 and to the satisfaction of the Planning Secretary.
- E3. As part of the CEMP required under condition E2 of this consent, the Applicant must include the following:
- (a) Construction Traffic Management Plan (see condition D1);
 - (b) Erosion and Sediment Control Plan (see condition D25);
 - (c) Salinity Management Plan (see condition D33);
 - (d) Construction Noise Management Plan (see condition D44);
 - (e) Construction Air Quality Management Plan (see condition D56);
 - (f) Vegetation Management Plan (see Condition D69);
 - (g) Contamination Unexpected finds procedure (see Condition D77);
 - (h) Waste Management Plan (see condition D75); and
 - (i) Community Consultation and Complaints Handling.
- E4. The Applicant must:
- (a) not commence construction of the development until the CEMP is approved by the Planning Secretary; and
 - (b) carry out the construction of the development in accordance with the CEMP approved by the Planning Secretary and as revised and approved by the Planning Secretary from time to time.

OPERATIONAL ENVIRONMENTAL MANAGEMENT PLAN

- E5. The Applicant must prepare an Operational Environmental Management Plan (OEMP) in accordance with the requirements of condition E1 and to the satisfaction of the Planning Secretary.
- E6. As part of the OEMP required under condition E5 of this consent, the Applicant must include the following:
- (a) describe the role, responsibility, authority, and accountability of all key personnel involved in the environmental management of the development;
 - (b) describe the procedures that would be implemented to:
 - (i) keep the local community and relevant agencies informed about the operation and environmental performance of the development;
 - (ii) receive, handle, respond to, and record complaints;
 - (iii) resolve any disputes that may arise;
 - (iv) respond to any non-compliance;
 - (v) respond to emergencies; and
 - (c) include the following environmental management plans:
 - (i) [Operational Noise Management Plan \(see condition A16A\)](#);
 - (ii) Operational Traffic Monitoring Program (see condition D3);
 - (iii) Workplace Travel Plan (see condition D22);
 - (iv) Landscape Management Plan (see condition D37);
 - (v) Stormwater Management Plan (see condition D30);
 - (vi) Vegetation Management Plan (see Condition D69); and
 - (vii) Waste Management Plan (see condition D75).
- E7. The Applicant must:
- (a) not commence operation until the OEMP is approved by the Planning Secretary; and
 - (b) operate the development in accordance with the OEMP approved by the Planning Secretary (and as revised and approved by the Planning Secretary from time to time).

REVISION OF STRATEGIES, PLANS AND PROGRAMS

- E8. Within three months of:
- (a) the submission of a Compliance Report under condition E14;
 - (b) the submission of an incident report under condition E10;
 - (c) the approval of any modification of the conditions of this consent; or
 - (d) the issue of a direction of the Planning Secretary under condition C2(b) which requires a review,
- the strategies, plans and programs required under this consent must be reviewed, and the Planning Secretary must be notified in writing that a review is being carried out.
- E9. If necessary to either improve the environmental performance of the development, cater for a modification or comply with a direction, the strategies, plans and programs required under this consent must be revised, to the satisfaction of the Planning Secretary. Where revisions are required, the revised document must be submitted to the Planning Secretary for approval within six weeks of the review.

Note: *This is to ensure strategies, plans and programs are updated on a regular basis and to incorporate any recommended measures to improve the environmental performance of the development.*

REPORTING AND AUDITING

Incident Notification, Reporting and Response

- E10. The Planning Secretary must be notified in writing via the Major Projects website immediately after the Applicant becomes aware of an incident. The notification must identify the development (including the development application number and the name of the development if it has one) and set out the location and nature of the incident. Subsequent notification requirements must be given, and reports submitted in accordance with the requirements set out in Appendix 7.

Non-Compliance Notification

- E11. The Planning Secretary must be notified in writing to the Major Projects website within seven days after the Applicant becomes aware of any non-compliance.
- E12. A non-compliance notification must identify the development and the application number for it, set out the condition of consent that the development is non-compliant with, the way in which it does not comply and the reasons for the non-compliance (if known) and what actions have been, or will be, undertaken to address the non-compliance.
- E13. A non-compliance which has been notified as an incident does not need to also be notified as a non-compliance.

Compliance Reporting

- E14. Within three months after the commencement of construction of the Stage 1 Development, and in the same month each subsequent year (or such other timing as agreed by the Planning Secretary) for the duration of construction works, the Applicant must submit a Compliance Report to the Department reviewing the environmental performance of the development to the satisfaction of the Planning Secretary. Compliance Reports must be prepared in accordance with the Compliance Reporting Post Approval Requirements (Department 2020) and must also:
- (a) identify any trends in the monitoring data over the life of the development;
 - (b) identify any discrepancies between the predicted and actual impacts of the development, and analyse the potential cause of any significant discrepancies; and
 - (c) describe what measures will be implemented over the next year to improve the environmental performance of the development.
- E15. The Applicant must make each Compliance Report publicly available no later than 60 days after submitting it to the Planning Secretary and notify the Planning Secretary in writing at least 7 days before this is done.

Monitoring and Environmental Audits

- E16. Any condition of this consent that requires the carrying out of monitoring or an environmental audit, whether directly or by way of a plan, strategy or program, is taken to be a condition requiring monitoring or an environmental audit under Division 9.4 of Part 9 of the EP&A Act. This includes conditions in respect of incident notification, reporting and response, non-compliance notification, compliance reporting and independent auditing.

Note: For the purposes of this condition, as set out in the EP&A Act, "monitoring" is monitoring of the development to provide data on compliance with the consent or on the environmental impact of the development, and an "environmental audit" is a periodic or particular documented evaluation of the development to provide information on compliance with the consent or the environmental management or impact of the development.

ACCESS TO INFORMATION

- E17. At least 48 hours before the commencement of construction until the completion of all works under this consent, the Applicant must:
- (a) make the following information and documents (as they are obtained or approved) publicly available on its website:
 - (i) the documents referred to in condition C2 of this consent;
 - (ii) all current statutory approvals for the development;
 - (iii) all approved strategies, plans and programs required under the conditions of this consent;
 - (iv) the proposed staging plans for the development if the construction, operation or decommissioning of the development is to be staged;
 - (v) regular reporting on the environmental performance of the development in accordance with the reporting requirements in any plans or programs approved under the conditions of this consent;
 - (vi) a comprehensive summary of the monitoring results of the development, reported in accordance with the specifications in any conditions of this consent, or any approved plans and programs;
 - (vii) a summary of the current stage and progress of the development;
 - (viii) contact details to enquire about the development or to make a complaint;
 - (ix) a complaints register, updated monthly;
 - (x) the Compliance Report of the development;
 - (xi) audit reports prepared as part of any Independent Audit of the development and the Applicant's response to the recommendations in any audit report;
 - (xii) any other matter required by the Planning Secretary; and
 - (b) keep such information up to date, to the satisfaction of the Planning Secretary.

APPENDIX 1 CONCEPT PROPOSAL

Table 5 *Schedule of Approved Plans – Concept Proposal*

Drawing No	Title	Issue	Date
Architectural Plan prepared by SBA Architects			
MP01	Aspect Industrial Estate Lots 1-5 (DP 1285305) Mamre Road, Kemps Creek – SSDA-MOD 10 Estate Masterplan	B	03/04/2025
Landscape Plan prepared by Site Image Landscape Architects			
003	Aspect Industrial Estate Kemps Creek Landscape Masterplan IVE Fitout	A	08/04/2025
Tree Canopy Plan prepared by Site Image Landscape Architects			
2001	Kemps Creek Lots 1,2 & 5 DP 1285305 & Lots 6 & 7 DP 1291562 Mamre Road Kemps Creek Tree Canopy Plan	02	15/04/2025

FOR INFORMATION

OVERALL DEVELOPMENT DATA	
Field Area	898,323 m ²
Mains Rd Reserve Area	143,034 m ²
Road Boundary Area	544,216 m ²
Access Road Area	39,076 m ²
Future Road Area	3,575 m ²
Carpark Area	20,717 m ²
Residential Area	4,042 m ²
Shop Lot Area	18,719 m ²
Total Development Area	1,419,702 m ²
Total Office Area (incl. access)	11,158 m ²
Total Warehouse Area	234,025 m ²
Gate	126 m ²
Total Site Area	245,126 m ²
Residential Use Area	4,013 m ²

WAREHOUSE 1	
Site Area	25,217 m ²
Office	600 m ²
Warehouse	50,000 m ²
Shop Office	300 m ²
Total GFA	50,900 m ²
Carpark Provision	141

WAREHOUSE 2	
Site Area	43,172 m ²
Office	1,500 m ²
Warehouse	32,000 m ²
Shop Office	300 m ²
Total GFA	34,200 m ²
Carpark Provision	150

WAREHOUSE 3	
Site Area	49,708 m ²
Office	700 m ²
Warehouse	28,720 m ²
Shop Office	180 m ²
Total GFA	29,600 m ²
Carpark Provision	89

WAREHOUSE 4	
Site Area	41,385 m ²
Office	700 m ²
Warehouse	18,000 m ²
Shop Office	180 m ²
Total GFA	18,980 m ²
Carpark Provision	53

WAREHOUSE 5	
Site Area	38,180 m ²
Office	600 m ²
Warehouse	11,872 m ²
Shop Office	300 m ²
Total GFA	12,772 m ²
Carpark Provision	50


WAREHOUSE 6	
Site Area	18,435 m ²
Office	600 m ²
Warehouse	8,074 m ²
Shop Office	300 m ²
Total GFA	9,074 m ²
Carpark Provision	71

WAREHOUSE 7	
Site Area	27,120 m ²
Office	500 m ²
Warehouse	14,388 m ²
Shop Office	180 m ²
Gate	126 m ²
Total GFA	15,194 m ²
Carpark Provision	54

WAREHOUSE 8	
Site Area	35,718 m ²
Office	2,000 m ²
Warehouse	30,708 m ²
Shop Office	370 m ²
Store	400 m ²
Handover Office	300 m ²
Total GFA	42,878 m ²
Carpark 1 Provision	94
Carpark 2 Provision	58

WAREHOUSE 9	
Site Area	155,362 m ²
Office	1,000 m ²
Warehouse	84,908 m ²
Shop Office	300 m ²
Total GFA	86,214 m ²
Carpark Provision	208

*Areas are reserved to future Mains Rd boundary in red
 **Areas subject to survey



REV	DESCRIPTION	DATE
A	ISSUED FOR SDA	06/03/2025
B	ISSUED FOR SDA	03/04/2025

sba Aspect Industrial Estate
 789-882 Mains Road Kempsey Creek

- LEGEND**
- Landscape Setback
 - - - Building Setback
 - SS Substation Indicative Location
 - RW Retaining Wall
 - FS Fire Services
 - FB Fire Brigade Truck Parking
 - LB Landscape Block
 - RWT Rainwater Tank
 - AC Plant Indicative Location



**ESTATE MASTERPLAN
 SSD-10448-MOD10**
 AIE. EST. DA.1090
 Date: 03/04/2025 Scale: 1:4000@A3, 1:2000@A1 Project No: 25107 **MP01 B**

Figure 1: Concept Layout – MOD - 10



commencing work. Do not scale this drawing. Any required dimensions not shown shall be referred to the Landscape Architect for confirmation.

02	Response to Comment	CS	NM	15/04/2024
01	Preliminary	CS	NM	07/04/2024
Issue	Revision Description	Drawn	Checked	Date

Client:
Mirvac

Project:
840-882 Mamre Road Kemp Creek
NSW 2178. Lots 1, 2 & 5 DP1285305
& Lots 6 & 7 DP1291562

Level 1, 3-6 Skipton Street
Sydney NSW 2016
Australia
Tel: 01 21 8332 6600
Fax: 01 21 8336 8877
www.sitimage.com.au
Site Image (2023) Pty Ltd
ABN 64 607 382 380



PRELIMINARY

Drawing Name:
Tree Canopy Plan_IV E Fitout

Scale: 1:2000 @ A1
Job Number: SS24-5421_IV E
Drawing Number: 2001_02

WAREHOUSE RIVE FITOUT - CANOPY COVER				
	Area (m ²)	30% Canopy Cover	Current Canopy Cover	Current % Canopy Cover
Warehouse 1	61,217	6,122	6225.2	10%
Warehouse 2	40,112	4,011	3516	9%
Warehouse 3	42,755	4,276	4222.7	10%
Warehouse 4	41,965	4,197	5121.1	12%
Warehouse 5	28,190	2,819	2844.4	10%
Warehouse 6	19,439	1,944	593.5	3%
Warehouse 7	27,120	2,712	3930.9	14%
Warehouse 8	75,710	7,571	11977.14	16%
Warehouse 9	113,082	11,308	8449.5	7%
Sub total (Warehouse allotments)	449,020	44902	46888.44	10.44%
Non-warehouse lot	38157	1,816	7382.3	41%
Riparian Zone (Less C2 Area)	20,968	2,099	14264.1	67%
Total (Excluding public roads and C2 Land)	475,383	47539.3	61,969	13%
C2 Land	12,772	1,277	6386	50%
Public Roads	43,446	4,738	5903.1	14%
Site Land	16,004			
Total (Including public roads and C2 Land)	558,323	55,832.30	73,856	13.2%

NOT FOR CONSTRUCTION

Figure 1A: Tree Canopy Plan

APPENDIX 2 STAGE 1 DA PLANS

Table 6 Schedule of Approved Plans – Stage 1 DA Plans

Drawing No	Title	Issue	Date
Architectural Plan prepared by SBA Architects			
DA100	Aspect Industrial Estate Lots 54-58 (DP 259135) Mamre Road, Kemps Creek – Overall Site Plan	W	30/11/2022
DA101	Aspect Industrial Estate Lots 54-58 (DP 259135) Mamre Road, Kemps Creek – Signage Plan	G	05/08/2022
DA110	Aspect Industrial Estate Lots 54-58 (DP 259135) Mamre Road, Kemps Creek – Lot 1 Site & Warehouse Floor Plan	DD	19/10/2022
DA310	Aspect Industrial Estate Lots 54-58 (DP 259135) Mamre Road, Kemps Creek – Lot 3 Site & Warehouse Floor Plan	M	19/10/2022



OVERALL DEVELOPMENT DATA

Total Site Area	558,323 m ²
Mamre Rd Reserve Area	14,004 m ²
Rev. Boundary Site Area	544,319 m ²
Access Roads Area	43,856 m ²
Future Roads Area	3,570 m ²
Creek Riparian Area	29,718 m ²
Retained Riparian Area	4,042 m ²
Basin Lot Area	18,157 m ²
Total Developable Area	445,027 m²
Restriction on User Area	4,613 m ²

WAREHOUSE 1


Site Area	61,170 m ²
Offices	900 m ²
Warehouse	32,886 m ²
Dock Office	300 m ²
Total GFA	33,886 m²
Carpark Provided	141

WAREHOUSE 3

Site Area	42,755 m ²
Offices	700 m ²
Warehouse	20,735 m ²
Dock Office	100 m ²
Total GFA	21,535 m²
Carpark Provided	89



Figure 2: Stage 1 Plan



	01 9438 2000 01 9438 2001 01 9438 2002 01 9438 2003 01 9438 2004 01 9438 2005 01 9438 2006 01 9438 2007 01 9438 2008 01 9438 2009 01 9438 2010 01 9438 2011 01 9438 2012 01 9438 2013 01 9438 2014 01 9438 2015 01 9438 2016 01 9438 2017 01 9438 2018 01 9438 2019 01 9438 2020 01 9438 2021 01 9438 2022 01 9438 2023 01 9438 2024 01 9438 2025 01 9438 2026 01 9438 2027 01 9438 2028 01 9438 2029 01 9438 2030 01 9438 2031 01 9438 2032 01 9438 2033 01 9438 2034 01 9438 2035 01 9438 2036 01 9438 2037 01 9438 2038 01 9438 2039 01 9438 2040 01 9438 2041 01 9438 2042 01 9438 2043 01 9438 2044 01 9438 2045 01 9438 2046 01 9438 2047 01 9438 2048 01 9438 2049 01 9438 2050 01 9438 2051 01 9438 2052 01 9438 2053 01 9438 2054 01 9438 2055 01 9438 2056 01 9438 2057 01 9438 2058 01 9438 2059 01 9438 2060 01 9438 2061 01 9438 2062 01 9438 2063 01 9438 2064 01 9438 2065 01 9438 2066 01 9438 2067 01 9438 2068 01 9438 2069 01 9438 2070 01 9438 2071 01 9438 2072 01 9438 2073 01 9438 2074 01 9438 2075 01 9438 2076 01 9438 2077 01 9438 2078 01 9438 2079 01 9438 2080 01 9438 2081 01 9438 2082 01 9438 2083 01 9438 2084 01 9438 2085 01 9438 2086 01 9438 2087 01 9438 2088 01 9438 2089 01 9438 2090 01 9438 2091 01 9438 2092 01 9438 2093 01 9438 2094 01 9438 2095 01 9438 2096 01 9438 2097 01 9438 2098 01 9438 2099 01 9438 2100 01 9438 2101 01 9438 2102 01 9438 2103 01 9438 2104 01 9438 2105 01 9438 2106 01 9438 2107 01 9438 2108 01 9438 2109 01 9438 2110 01 9438 2111 01 9438 2112 01 9438 2113 01 9438 2114 01 9438 2115 01 9438 2116 01 9438 2117 01 9438 2118 01 9438 2119 01 9438 2120 01 9438 2121 01 9438 2122 01 9438 2123 01 9438 2124 01 9438 2125 01 9438 2126 01 9438 2127 01 9438 2128 01 9438 2129 01 9438 2130 01 9438 2131 01 9438 2132 01 9438 2133 01 9438 2134 01 9438 2135 01 9438 2136 01 9438 2137 01 9438 2138 01 9438 2139 01 9438 2140 01 9438 2141 01 9438 2142 01 9438 2143 01 9438 2144 01 9438 2145 01 9438 2146 01 9438 2147 01 9438 2148 01 9438 2149 01 9438 2150 01 9438 2151 01 9438 2152 01 9438 2153 01 9438 2154 01 9438 2155 01 9438 2156 01 9438 2157 01 9438 2158 01 9438 2159 01 9438 2160 01 9438 2161 01 9438 2162 01 9438 2163 01 9438 2164 01 9438 2165 01 9438 2166 01 9438 2167 01 9438 2168 01 9438 2169 01 9438 2170 01 9438 2171 01 9438 2172 01 9438 2173 01 9438 2174 01 9438 2175 01 9438 2176 01 9438 2177 01 9438 2178 01 9438 2179 01 9438 2180 01 9438 2181 01 9438 2182 01 9438 2183 01 9438 2184 01 9438 2185 01 9438 2186 01 9438 2187 01 9438 2188 01 9438 2189 01 9438 2190 01 9438 2191 01 9438 2192 01 9438 2193 01 9438 2194 01 9438 2195 01 9438 2196 01 9438 2197 01 9438 2198 01 9438 2199 01 9438 2200 01 9438 2201 01 9438 2202 01 9438 2203 01 9438 2204 01 9438 2205 01 9438 2206 01 9438 2207 01 9438 2208 01 9438 2209 01 9438 2210 01 9438 2211 01 9438 2212 01 9438 2213 01 9438 2214 01 9438 2215 01 9438 2216 01 9438 2217 01 9438 2218 01 9438 2219 01 9438 2220 01 9438 2221 01 9438 2222 01 9438 2223 01 9438 2224 01 9438 2225 01 9438 2226 01 9438 2227 01 9438 2228 01 9438 2229 01 9438 2230 01 9438 2231 01 9438 2232 01 9438 2233 01 9438 2234 01 9438 2235 01 9438 2236 01 9438 2237 01 9438 2238 01 9438 2239 01 9438 2240 01 9438 2241 01 9438 2242 01 9438 2243 01 9438 2244 01 9438 2245 01 9438 2246 01 9438 2247 01 9438 2248 01 9438 2249 01 9438 2250 01 9438 2251 01 9438 2252 01 9438 2253 01 9438 2254 01 9438 2255 01 9438 2256 01 9438 2257 01 9438 2258 01 9438 2259 01 9438 2260 01 9438 2261 01 9438 2262 01 9438 2263 01 9438 2264 01 9438 2265 01 9438 2266 01 9438 2267 01 9438 2268 01 9438 2269 01 9438 2270 01 9438 2271 01 9438 2272 01 9438 2273 01 9438 2274 01 9438 2275 01 9438 2276 01 9438 2277 01 9438 2278 01 9438 2279 01 9438 2280 01 9438 2281 01 9438 2282 01 9438 2283 01 9438 2284 01 9438 2285 01 9438 2286 01 9438 2287 01 9438 2288 01 9438 2289 01 9438 2290 01 9438 2291 01 9438 2292 01 9438 2293 01 9438 2294 01 9438 2295 01 9438 2296 01 9438 2297 01 9438 2298 01 9438 2299 01 9438 2300 01 9438 2301 01 9438 2302 01 9438 2303 01 9438 2304 01 9438 2305 01 9438 2306 01 9438 2307 01 9438 2308 01 9438 2309 01 9438 2310 01 9438 2311 01 9438 2312 01 9438 2313 01 9438 2314 01 9438 2315 01 9438 2316 01 9438 2317 01 9438 2318 01 9438 2319 01 9438 2320 01 9438 2321 01 9438 2322 01 9438 2323 01 9438 2324 01 9438 2325 01 9438 2326 01 9438 2327 01 9438 2328 01 9438 2329 01 9438 2330 01 9438 2331 01 9438 2332 01 9438 2333 01 9438 2334 01 9438 2335 01 9438 2336 01 9438 2337 01 9438 2338 01 9438 2339 01 9438 2340 01 9438 2341 01 9438 2342 01 9438 2343 01 9438 2344 01 9438 2345 01 9438 2346 01 9438 2347 01 9438 2348 01 9438 2349 01 9438 2350 01 9438 2351 01 9438 2352 01 9438 2353 01 9438 2354 01 9438 2355 01 9438 2356 01 9438 2357 01 9438 2358 01 9438 2359 01 9438 2360 01 9438 2361 01 9438 2362 01 9438 2363 01 9438 2364 01 9438 2365 01 9438 2366 01 9438 2367 01 9438 2368 01 9438 2369 01 9438 2370 01 9438 2371 01 9438 2372 01 9438 2373 01 9438 2374 01 9438 2375 01 9438 2376 01 9438 2377 01 9438 2378 01 9438 2379 01 9438 2380 01 9438 2381 01 9438 2382 01 9438 2383 01 9438 2384 01 9438 2385 01 9438 2386 01 9438 2387 01 9438 2388 01 9438 2389 01 9438 2390 01 9438 2391 01 9438 2392 01 9438 2393 01 9438 2394 01 9438 2395 01 9438 2396 01 9438 2397 01 9438 2398 01 9438 2399 01 9438 2400 01 9438 2401 01 9438 2402 01 9438 2403 01 9438 2404 01 9438 2405 01 9438 2406 01 9438 2407 01 9438 2408 01 9438 2409 01 9438 2410 01 9438 2411 01 9438 2412 01 9438 2413 01 9438 2414 01 9438 2415 01 9438 2416 01 9438 2417 01 9438 2418 01 9438 2419 01 9438 2420 01 9438 2421 01 9438 2422 01 9438 2423 01 9438 2424 01 9438 2425 01 9438 2426 01 9438 2427 01 9438 2428 01 9438 2429 01 9438 2430 01 9438 2431 01 9438 2432 01 9438 2433 01 9438 2434 01 9438 2435 01 9438 2436 01 9438 2437 01 9438 2438 01 9438 2439 01 9438 2440 01 9438 2441 01 9438 2442 01 9438 2443 01 9438 2444 01 9438 2445 01 9438 2446 01 9438 2447 01 9438 2448 01 9438 2449 01 9438 2450 01 9438 2451 01 9438 2452 01 9438 2453 01 9438 2454 01 9438 2455 01 9438 2456 01 9438 2457 01 9438 2458 01 9438 2459 01 9438 2460 01 9438 2461 01 9438 2462 01 9438 2463 01 9438 2464 01 9438 2465 01 9438 2466 01 9438 2467 01 9438 2468 01 9438 2469 01 9438 2470 01 9438 2471 01 9438 2472 01 9438 2473 01 9438 2474 01 9438 2475 01 9438 2476 01 9438 2477 01 9438 2478 01 9438 2479 01 9438 2480 01 9438 2481 01 9438 2482 01 9438 2483 01 9438 2484 01 9438 2485 01 9438 2486 01 9438 2487 01 9438 2488 01 9438 2489 01 9438 2490 01 9438 2491 01 9438 2492 01 9438 2493 01 9438 2494 01 9438 2495 01 9438 2496 01 9438 2497 01 9438 2498 01 9438 2499 01 9438 2500 01 9438 2501 01 9438 2502 01 9438 2503 01 9438 2504 01 9438 2505 01 9438 2506 01 9438 2507 01 9438 2508 01 9438 2509 01 9438 2510 01 9438 2511 01 9438 2512 01 9438 2513 01 9438 2514 01 9438 2515 01 9438 2516 01 9438 2517 01 9438 2518 01 9438 2519 01 9438 2520 01 9438 2521 01 9438 2522 01 9438 2523 01 9438 2524 01 9438 2525 01 9438 2526 01 9438 2527 01 9438 2528 01 9438 2529 01 9438 2530 01 9438 2531 01 9438 2532 01 9438 2533 01 9438 2534 01 9438 2535 01 9438 2536 01 9438 2537 01 9438 2538 01 9438 2539 01 9438 2540 01 9438 2541 01 9438 2542 01 9438 2543 01 9438 2544 01 9438 2545 01 9438 2546 01 9438 2547 01 9438 2548 01 9438 2549 01 9438 2550 01 9438 2551 01 9438 2552 01 9438 2553 01 9438 2554 01 9438 2555 01 9438 2556 01 9438 2557 01 9438 2558 01 9438 2559 01 9438 2560 01 9438 2561 01 9438 2562 01 9438 2563 01 9438 2564 01 9438 2565 01 9438 2566 01 9438 2567 01 9438 2568 01 9438 2569 01 9438 2570 01 9438 2571 01 9438 2572 01 9438 2573 01 9438 2574 01 9438 2575 01 9438 2576 01 9438 2577 01 9438 2578 01 9438 2579 01 9438 2580 01 9438 2581 01 9438 2582 01 9438 2583 01 9438 2584 01 9438 2585 01 9438 2586 01 9438 2587 01 9438 2588 01 9438 2589 01 9438 2590 01 9438 2591 01 9438 2592 01 9438 2593 01 9438 2594 01 9438 2595 01 9438 2596 01 9438 2597 01 9438 2598 01 9438 2599 01 9438 2600 01 9438 2601 01 9438 2602 01 9438 2603 01 9438 2604 01 9438 2605 01 9438 2606 01 9438 2607 01 9438 2608 01 9438 2609 01 9438 2610 01 9438 2611 01 9438 2612 01 9438 2613 01 9438 2614 01 9438 2615 01 9438 2616 01 9438 2617 01 9438 2618 01 9438 2619 01 9438 2620 01 9438 2621 01 9438 2622 01 9438 2623 01 9438 2624 01 9438 2625 01 9438 2626 01 9438 2627 01 9438 2628 01 9438 2629 01 9438 2630 01 9438 2631 01 9438 2632 01 9438 2633 01 9438 2634 01 9438 2635 01 9438 2636 01 9438 2637 01 9438 2638 01 9438 2639 01 9438 2640 01 9438 2641 01 9438 2642 01 9438 2643 01 9438 2644 01 9438 2645 01 9438 2646 01 9438 2647 01 9438 2648 01 9438 2649 01 9438 2650 01 9438 2651 01 9438 2652 01 9438 2653 01 9438 2654 01 9438 2655 01 9438 2656 01 9438 2657 01 9438 2658 01 9438 2659 01 9438 2660 01 9438 2661 01 9438 2662 01 9438 2663 01 9438 2664 01 9438 2665 01 9438 2666 01 9438 2667 01 9438 2668 01 9438 2669 01 9438 2670 01 9438 2671 01 9438 2672 01 9438 2673 01 9438 2674 01 9438 2675 01 9438 2676 01 9438 2677 01 9438 2678 01 9438 2679 01 9438 2680 01 9438 2681 01 9438 2682 01 9438 2683 01 9438 2684 01 9438 2685 01 9438 2686 01 9438 2687 01 9438 2688 01 9438 2689 01 9438 2690 01 9438 2691 01 9438 2692 01 9438 2693 01 9438 2
--	---

Landscape Concept Masterplan Stage 1



-  Estate Entry Feature
-  Streetscape
-  Riparian Zone
-  Stormwater Basin
-  Boundary Planting
-  On Lot Landscape



Aspect Industrial Estate Kemp's Creek | Landscape Masterplan MOD2

Drawing Number	004
Issue	E
Date	25.07.2022

Figure 3: Stage 1 Landscape Plan



OVERALL DEVELOPMENT DATA

Total Site Area	558,323 m ²
Mamre Rd Reserve Area	14,004 m ²
Rev. Boundary Site Area	546,319 m ²
Access Roads Area	39,876 m ²
Future Roads Area	3,573 m ²
Creek Riparian Area	29,718 m ²
Retained Riparian Area	4,042 m ²
Basin Lot Area	18,157 m ²
Total Developable Area	448,956 m ²
Total Office Area (incl dock off)	1,834 m ²
Total Warehouse Area	64,973 m ²
Total Building Area	66,812 m ²

WAREHOUSE 9	
Site Area	113,082 m ²
Office	1,265 m ²
Warehouse	64,742 m ²
Dock Office	243 m ²
Total GFA	66,350 m ²
Carpark Provided	257



*Areas are measured to future Mamre Rd boundary in red
 **All areas subject to survey

	PREPARED FOR: SSSDA-MOD 3 DRAWN BY: SSSDA-MOD 3 CHECKED BY: SSSDA-MOD 3 DATE: 07.02.2023	ASPECT INDUSTRIAL ESTATE LOTS 54-58 (DP259135) MAMRE ROAD, KEMPS CREEK	SETOUT TO GDA2020	SSDA-MOD 3 STAGING PLAN DATE: 07.02.2023 1:4000 @ A3 21250 MP3-03 D
	SCALE: 1:4000			

Figure 4: Stage 1 Development Road Works Phasing Plan





Figure 5: Stormwater Management AIE Site






Figure 7: AIE Stage 1 Development Temporary Operational Access Arrangement Phase 2




Figure 8: AIE Temporary Operational Access Stage 1 Sheet 1




Figure 9: AIE Temporary Operational Access Stage 1 Sheet 2




Figure 10: AIE Temporary Operational Access Stage 1 Sheet 3






Figure 12: AIE Temporary Operational Access Stage 1 Sheet 5



Issue	Description	Date
P1	ISSUED FOR INFORMATION	25-10-23



THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L



Scales	1:500	Drawn	MH
		Designed	MH
Grid	GDA2020	Checked	DS
Height Datum	AHD	Approved	DS

Project: ASPECT INDUSTRIAL ESTATE
MAMRE ROAD,
KEMPS CREEK

Title: AIE TEMPORARY OPERATIONAL ACCESS
STAGE 2
SHEET 1

Civil Engineers and Project Managers

Level 7, 153 Walker Street
North Sydney NSW 2060
ABN 96 130 862 405
Fax: 02 9439 1777
02 9662 1056
www.atl.nsw.au
info@atl.nsw.au

Scale	FOR INFORMATION ONLY	A1
Project - Drawing No.	8-596-SK190A	Issue
		P1

F:\18-596 Mamre Road\6.0 Drgs\Civil\Sketches\18-596-SK190A AIE TEMPORARY OPERATIONAL ACCESS STAGE 2 SHEET 1.dwg

Figure 13: AIE Temporary Operational Access Stage 2 Sheet 1




Figure 14: AIE Temporary Operational Access Stage 2 Sheet 2




Figure 15: AIE Temporary Operational Access Stage 2 Sheet 3




Figure 16: AIE Temporary Operational Access Stage 2 Sheet 4




Figure 17: AIE Temporary Operational Access Stage 2 Sheet 5

APPENDIX 3 NOISE MONITORING LOCATIONS




Figure 18: Noise Monitoring Locations Plan

APPENDIX 4 NOISE MITIGATION ELIGIBLE RECEIVERS LOCATIONS



Figure 19: Noise mitigation eligible receivers to the west of Mamre Road

APPENDIX 5 APPLICANT'S MANAGEMENT AND MITIGATION MEASURES

Issue	SSD DA Component	Mitigation and Management
Construction Management		
General Construction Management	Stage 1 Development	<ul style="list-style-type: none"> ▪ A CEMP to be prepared for the AIE Stage 1 Development capturing standard and specific management and mitigation measures as described in the SSD DA, EIS and supporting technical documents.
Operational Management		
General Operational Management	Concept Masterplan Stage 1 Development	<ul style="list-style-type: none"> ▪ An OEMP to be prepared for the AIE capturing standard and specific operational management and mitigation measures as described in the SSD DA, EIS and supporting technical documents.
Transport		
Construction Traffic	Stage 1 Development	<ul style="list-style-type: none"> ▪ Preparation of a CTMP to form part of the CEMP addressing issues such as: <ul style="list-style-type: none"> – Track haul routes, delivery schedules and curfews; – Protocols for the management of construction traffic moving onto and off the site.
Urban Design and Visual		
Site Layout and Design	Concept Masterplan	<ul style="list-style-type: none"> ▪ Future development of the AIE to proceed in accordance with the approved Concept Proposal and DCP.
Development Controls	Concept Masterplan	<ul style="list-style-type: none"> ▪ Design and development controls to be established for

Issue	SSD DA Component	Mitigation and Management
		<p>the AIE in the form of a DCP to guide future development on the site.</p>
Visual Impact	<p>Concept Masterplan Stage 1 Development</p>	<ul style="list-style-type: none"> ▪ Design and development controls to be established for the AIE in the form of a DCP to guide future development on the site. ▪ Landscaping of key interfaces including western boundary to minimise visual impact.
Soils and Water		
Water Usage	Stage 1 Development	<ul style="list-style-type: none"> ▪ Rainwater tanks to be provided for each development site with size determined in accordance with the Penrith City Council DCP requirements. ▪ Irrigation and toilet flushing for development to be plumbed to rainwater tanks. ▪ Consideration to be given to other possible rainwater reuse opportunities such as truck washing. ▪ Measures and considerations for the minimisation of water use during construction and operation to be incorporated into CEMP and OEMP as relevant.
Soils	Stage 1 Development	<ul style="list-style-type: none"> ▪ Mitigation measures inherent to the civil design of the proposal. ▪ Sediment and erosion control measures are proposed as detailed in Appendix F and Appendix G.
Salinity	Stage 1 Development	<ul style="list-style-type: none"> ▪ A Salinity Management Plan to be prepared for the proposed development.

Issue	SSD DA Component	Mitigation and Management
Contamination	Stage 1 Development	<ul style="list-style-type: none"> ▪ Management measures described in the Salinity Management Plan to be adopted in the CEMP and OEMP as relevant.
Earthworks	Stage 1 Development	<ul style="list-style-type: none"> ▪ Identified areas of potential contamination to be subject to further investigation prior to the development of affected land. ▪ Adoption of unexpected finds procedure for hazardous and contaminated materials management and removal during demolition and excavation.
Mineral Resources	Concept Masterplan	<ul style="list-style-type: none"> ▪ Civil design achieves appropriate site levels with minimal impact on hydrology. ▪ Import of fill to be managed in accordance with CEMP. ▪ Erosion and sediment control measures included in SSD DA package (Appendix F and Appendix G).
Surface Water	Stage 1 Development	<ul style="list-style-type: none"> ▪ No mitigation required. Proposed development does not impact existing mining leases in the area.
		<ul style="list-style-type: none"> ▪ Stormwater issues addressed through design measures incorporated into proposed development. ▪ Stormwater management system designed to meet the requirements of Penrith City Council's Engineering Works and WSUD guidelines, and relevant NOW guidelines. ▪ Detailed on-lot stormwater for future stages of the AIE to be

Issue	SSD DA Component	Mitigation and Management
Groundwater	Stage 1 Development	<p>designed and assessed under future applications.</p> <ul style="list-style-type: none"> ▪ Methods and management of any required dam dewatering required, as outlined in Appendix W, during construction works to be detailed in the CEMP.
Flooding	Stage 1 Development	<ul style="list-style-type: none"> ▪ OSD designed to ensure that development does not increase stormwater peak flows in downstream areas for events up to and including 1:100 year ARI. ▪ OSD designed to mitigate post-development flows to pre-development flows for peak ARI events. ▪ Finished floor levels to have a minimum 500mm freeboard to 100 year overland flows.
Water Quality	Stage 1 Development	<ul style="list-style-type: none"> ▪ Erosion and sediment controls as detailed in Appendix F and Appendix G to be implemented through CEMP. ▪ Stormwater to be treated to compliant levels prior to discharge. ▪ Gross Pollutant Trap (GPT) to be installed within each development site on the final downstream stormwater pit prior to discharge. ▪ WSUD measures adopted to achieve target reductions for the AIE: <ul style="list-style-type: none"> – 85% Total Suspended Solids – 60% Total Phosphorus – 45% Total Nitrogen – 90% Gross Pollutants

Issue	SSD DA Component	Mitigation and Management
Infrastructure		
Capacity and Upgrades	Concept Masterplan	<ul style="list-style-type: none"> ▪ Management of issues in respect of infrastructure capacity and upgrades is in the form of design responses described in Section 2.5.6 of the EIS.
Delivery and Staging	Concept Masterplan Stage 1 Development	<ul style="list-style-type: none"> ▪ Management of issues in respect of infrastructure capacity and upgrades is in the form of design responses described in Sections 2.4.7 and 2.5.6. ▪ Staging of development of the AIE would be aligned with infrastructure and services delivery.
Other Environmental Issues		
Flora and Fauna	Concept Masterplan Stage 1 Development	<ul style="list-style-type: none"> ▪ Implementation of the Biodiversity Offset Strategy for the site. ▪ Preparation of a Biodiversity Management Plan for the site to inform the CEMP and OEMP as relevant to manage potential impacts to biodiversity during construction and operation. ▪ Restoration of retained areas of vegetation including riparian corridors and the Biodiversity Offset Area; ▪ Native grassland restoration to other areas of the site including road batters and outside batters of bio-retention basins; and ▪ Ongoing maintenance and management of these areas in accordance with the provisions of the Biodiversity Offset Strategy.

Issue	SSD DA Component	Mitigation and Management
Waterways and Riparian Lands	Concept Masterplan Stage 1 Development	<ul style="list-style-type: none"> ▪ Realignment of creek to occur in accordance with design and management measures described in Appendix P including: <ul style="list-style-type: none"> – Revegetation to use appropriate native aquatic macrophyte and River-flat Eucalypt-forest species within the riparian area. – Ongoing management of riparian lands on the site to be in accordance with the Vegetation Management Plan (Appendix P).
Construction Noise	Stage 1 Development	<ul style="list-style-type: none"> ▪ Construction hours to be limited to 7:00am – 6:00pm Monday to Friday and 8:00am – 1:00pm Saturdays. ▪ Where construction noise levels are predicted to be above the NMLs, all feasible and reasonable work practices are investigated to minimise noise emissions. ▪ If construction noise levels are still predicted to exceed the NMLs, potential noise impacts would be managed via site specific construction noise management plans. ▪ Construction works should be conducted during standard construction hours, with OOHW minimised as far as reasonable and feasible. ▪ Locations for vibration intensive equipment should be reviewed during the preparation of the site specific Construction Noise and Vibration Management Plans (CNVMP) for construction works adjacent to sensitive receivers.

Issue	SSD DA Component	Mitigation and Management
Operational Noise	Stage 1 Development	<ul style="list-style-type: none"> ▪ Further noise management measures to be incorporated into the CEMP as appropriate.
Air Quality and Odour – Construction	Stage 1 Development	<ul style="list-style-type: none"> ▪ CEMP to include standard air quality control measures, contingency plans and response procedure and suitable reporting and performance monitoring procedures. ▪ CEMP to include standard odour mitigation measures for construction including keeping excavation surfaces moist, covering excavation faces and/or stockpiles, use of soil vapour extraction systems and regular monitoring of discharges as appropriate.
Air Quality and Odour – Operational	Stage 1 Development	<ul style="list-style-type: none"> ▪ Further assessment of potential air quality impacts to be undertaken in respect of any specific operations proposed within the AIE with an atypical air emissions profile. ▪ Specific operations proposed within the AIE with the potential for generation of odour would be subject to further assessment.
Indigenous Heritage	Stage 1 Development	<ul style="list-style-type: none"> ▪ Archaeological salvage excavation and monitoring to be undertaken in the presence of relevant Aboriginal stakeholders prior to ground disturbance and

Issue	SSD DA Component	Mitigation and Management
Non-Indigenous Heritage	Stage 1 Development	<p>excavation work in identified areas.</p> <ul style="list-style-type: none"> ▪ Result of detailed archaeological excavation and any suitable salvaged materials to be managed in accordance with the NPW Act and direction from relevant Aboriginal stakeholders. ▪ Implementation of Unexpected Finds Protocol.
Greenhouse Gas and Energy Efficiency	Stage 1 Development	<ul style="list-style-type: none"> ▪ Future stages of development within the AIE would be subject to assessment in relation to energy efficiency and greenhouse gas emissions.
Waste Management – Construction	Stage 1 Development	<ul style="list-style-type: none"> ▪ Detailed construction waste minimisation and management measures to be included in the CEMP as described in Appendix Y.
Waste Management – Operations	Stage 1 Development	<ul style="list-style-type: none"> ▪ Detailed construction waste minimisation and management measures to be included in the OEMP as described in Appendix Y.

APPENDIX 6 INCIDENT NOTIFICATION AND REPORTING REQUIREMENTS

WRITTEN INCIDENT NOTIFICATION REQUIREMENTS

1. A written incident notification addressing the requirements set out below must be submitted to the Planning Secretary via the Major Projects website within seven days after the Applicant becomes aware of an incident. Notification is required to be given under this condition even if the Applicant fails to give the notification required under condition E10 or, having given such notification, subsequently forms the view that an incident has not occurred.
2. Written notification of an incident must:
 - a. identify the development and application number;
 - b. provide details of the incident (date, time, location, a brief description of what occurred and why it is classified as an incident);
 - c. identify how the incident was detected;
 - d. identify when the applicant became aware of the incident;
 - e. identify any actual or potential non-compliance with conditions of consent;
 - f. describe what immediate steps were taken in relation to the incident;
 - g. identify further action(s) that will be taken in relation to the incident; and
 - h. identify a project contact for further communication regarding the incident.

INCIDENT REPORT REQUIREMENTS

3. Within 30 days of the date on which the incident occurred or as otherwise agreed to by the Planning Secretary, the Applicant must provide the Planning Secretary and any relevant public authorities (as determined by the Planning Secretary) with a detailed report on the incident addressing all requirements below, and such further reports as may be requested.
4. The Incident Report must include:
 - a. a summary of the incident;
 - b. outcomes of an incident investigation, including identification of the cause of the incident;
 - c. details of the corrective and preventative actions that have been, or will be, implemented to address the incident and prevent recurrence; and
 - d. details of any communication with other stakeholders regarding the incident.