



Consulting.TM
an Elephants Foot Company

North Sydney Public School
182 Pacific Highway, North Sydney
Public School Development

OPERATIONAL WASTE MANAGEMENT PLAN

19/08/2021
Report No. 3383
Revision D

Client

School Infrastructure NSW

Level 8, 259 George Street, North Sydney
www.schoolinfrastructure.nsw.gov.au



REVISION REFERENCE

Revision	Date	Prepared by	Reviewed by	Description
A	27/07/2021	J. Parker	A. Armstrong	Draft
B	18/08/2021	J. Parker	A. Armstrong	Final
C	19/08/2021	J. Parker	A. Armstrong	Amendment
D	19/08/2021	J. Parker	A. Armstrong	Amendment

The information contained in this document produced by Elephants Foot Recycling Solutions (EFRS) is solely for the use of the client identified on the cover sheet for the purpose for which it has been prepared for. EFRS undertakes no duty, nor accepts any responsibility for any third party who may rely upon this document. Reproduction, publication or distribution of this document without written permission from EFRS is strictly prohibited.

TABLE OF CONTENTS

OPERATIONAL WASTE MANAGEMENT PLAN	i
TABLE OF FIGURES	iv
LIST OF TABLES.....	iv
GLOSSARY OF ABBREVIATIONS AND TERMS	i
1 INTRODUCTION	3
1.1 SCOPE OF REPORT	3
1.2 REPORT CONDITIONS.....	4
2 LEGISLATION & GUIDANCE	5
2.1 COUNCIL OBJECTIVES	5
2.1.1 SEAR 18 - WASTE.....	6
3 DEVELOPMENT OVERVIEW.....	7
3.1 SITE LOCATION	8
4 SCHOOL WASTE MANAGEMENT.....	9
4.1 WASTE GENERATION ESTIMATES	9
4.2 BIN SUMMARY.....	9
4.3 WASTE DISPOSAL PROCEDURES	9
4.4 WASTE COLLECTION PROCEDURES	10
4.5 OTHER WASTE MANAGEMENT CONSIDERATIONS.....	10
4.5.1 KITCHEN AND FOOD PREPARATION AREAS	10
4.5.2 BATHROOMS.....	10
4.5.3 PRINTING & PHOTOCOPYING ROOMS	10
4.5.4 BULKY WASTE AND RE-USABLE ITEMS	11
4.5.5 LIQUID WASTE	11
4.5.6 PROBLEM WASTE.....	11
5 STAKEHOLDER ROLES & RESPONSIBILITIES	12
6 SOURCE SEPARATION	13
7 BIN STORAGE AREAS.....	14
7.1 SIGNAGE	14
7.2 POLLUTION PREVENTION	14
8 BIN MOVING PATHS	15
9 USEFUL CONTACTS	16
APPENDIX A: ARCHITECTURAL PLANS.....	17
APPENDIX: A.1 SITE PLAN	18
APPENDIX B: PRIMARY WASTE MANAGEMENT PROVISIONS.....	19
APPENDIX: B.1 TYPICAL BIN SPECIFICATIONS	20
APPENDIX: B.2 SIGNAGE FOR WASTE AND RECYCLING BINS	21
APPENDIX: B.3 TYPICAL COLLECTION VEHICLE INFORMATION	23

APPENDIX C: SECONDARY WASTE MANAGEMENT PROVISIONS	25
APPENDIX: C.1 TYPICAL WORM FARM SPECIFICATIONS.....	26
APPENDIX: C.2 TYPICAL SOURCE SEPARATION BINS	27

TABLE OF FIGURES

Figure 1. Site Location.....	8
------------------------------	---

LIST OF TABLES

Table 1: SEARs Items	6
Table 2: Bin Quantities	9
Table 3: Stakeholder Roles and Responsibilities	12
Table 4: Operational Waste Streams.....	13

GLOSSARY OF ABBREVIATIONS AND TERMS

TERM	DESCRIPTION
<i>Baler</i>	A device that compresses waste into a mould to form bales which may be self-supporting or retained in shape by strapping
<i>Bin-carting Route</i>	Travel route for transferring bins from the storage area to a nominated collection point
<i>Collection Area/Point</i>	The identified position or area where general waste or recyclables are loaded onto the collection vehicle
<i>Compactor</i>	A machine for compressing waste into disposable or reusable containers
<i>Composter</i>	A container/machine used for composting specific food scraps
<i>Crate</i>	A plastic box used for the collection of recyclable materials
<i>DA</i>	Development Application
<i>DCP</i>	Development Control Plan
<i>EPA</i>	Environmental Protection Authority
<i>HRV</i>	Heavy Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities
<i>L</i>	Litre(s)
<i>LEP</i>	Local Environmental Plans guide planning decisions for local government areas
<i>Liquid Waste</i>	Non-hazardous liquid waste generated by commercial premises that must be connected to sewer or collected for treatment and disposal by a liquid waste contractor (including grease trap waste)
<i>Mixed Use Development</i>	A development comprised of two or more different uses
<i>Mobile Garbage Bin(s) (MGB)</i>	A waste container generally constructed of plastic with wheels with a capacity in litres of 120, 240, 360, 660, 1000 or 1100
<i>MRV</i>	Medium Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities
<i>Onsite Collection</i>	When the collection vehicle enters the property and services the development within the property boundary from a designated loading area
<i>Owners Corporation</i>	An organisation or group of persons that is identified by a particular name and acts, or may act, as an entity
<i>SEAR</i>	Secretary's Environmental Assessment Requirements
<i>SRV</i>	Small Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities
<i>SSDA</i>	State Significant Development Application
<i>WHS</i>	Workplace Health and Safety

Wheel-in wheel-out service

A type of waste collection service offered by local councils where the council waste collection personnel enter the premises to collect the bins and returns them to the property

1 INTRODUCTION

Elephants Foot Recycling Solutions (EFRS) has been engaged to prepare the following waste management plan for the operational management of waste generated by the North Sydney Public School development located at 182 Pacific Highway, North Sydney.

This report has been prepared in response to the Secretary's Environmental Assessment Requirements, specifically SEAR 18, dated 24 December 2020 in support of a State Significant Development Application (SSDA).

SEAR 18 is included below:

18. Waste

- Identify, quantify and classify the likely waste streams to be generated during construction and operation.
- Provide the measures to be implemented to manage, reuse, recycle and safely dispose of this waste.
- Identify appropriate servicing arrangements (including but not limited to, waste management, loading zones, mechanical plant) for the site.
- Provide a hazardous materials survey of existing aboveground buildings that are proposed to be demolished or altered.

Relevant Policies and Guidelines:

Waste Classification Guidelines (EPA, 2014).

1.1 SCOPE OF REPORT

This operational waste management plan (OWMP) only applies to the **operational** phase of the proposed development; therefore, the requirements outlined in this OWMP must be implemented during the operational phase of the site and may be subject to review upon further expansion of, and/or changes to the development.

The waste management of the **construction** and **demolition** phases of the development are not addressed in this report. A construction and demolition WMP will be provided separately.

1.2 REPORT CONDITIONS

The purpose of this report is to document an OWMP as part of a State Significant Development Application (SSDA), which is supplied by EFRS with the following limitations:

- Drawings, estimates and information contained in this OWMP have been prepared by analysing the information, plans and documents supplied by the client and third parties including Department of Planning, Industry and Environment and other government agencies. The assumptions based on the information contained in the OWMP is outside the control of EFRS,
- The figures presented in the report are an estimate only – the actual amount of waste generated will be dependent on the occupancy rate of the building/s and waste generation intensity as well as the building management's approach to educating tenants regarding waste management operations and responsibilities,
- The building manager will adjust waste management operations as required based on actual waste volumes (e.g. if waste is greater than estimated) and increase the number of bins and collections accordingly,
- The report will not be used to determine or forecast operational costs or prepare any feasibility study or to document any safety or operational procedures,
- The report has been prepared with all due care; however no assurance is made that the OWMP reflects the actual outcome of the proposed waste facilities, services, and operations, and EFRS will not be liable for plans or results that are not suitable for purpose due to incorrect or unsuitable information or otherwise,
- EFRS offer no warranty or representation of accuracy or reliability of the OWMP unless specifically stated,
- Any manual handling equipment recommended in this OWMP should be provided at the recommendation of the appropriate equipment provider who will assess the correct equipment for supply,
- Design of waste management equipment and systems must be approved by the supplier,
- EFRS cannot be held accountable for late changes to the design after the OWMP has been submitted,
- EFRS will provide specifications and recommendations on bin access and travel paths within the OWMP, however it is the architect's responsibility to ensure the architectural drawings meet these provisions,
- EFRS are not required to provide information on collection vehicle swept paths, head heights, internal manoeuvring or loading requirements. It is assumed this information will be provided by a traffic consultant,
- Council are subject to changing waste and recycling policies and requirements at their own discretion.

2 LEGISLATION & GUIDANCE

Waste management and resource recovery regulation in Australia is administered by the Australian Constitution, Commonwealth laws, and international agreements. State and territory governments maintain primary responsibility for controlling development and regulating waste. The following legislation has been enacted in New South Wales, and provides the lawful underpinnings of this OWMP.

- NSW Environmental Planning & Assessment Act 1979
- NSW Protection of the Environment Operations Act 1997
- NSW Waste Avoidance & Resource Recovery Act 2001

At the local level, councils or Local Government Areas (LGAs) require OWMPs to be included in new development applications. This OWMP is specifically required by:

- North Sydney Development Control Plan 2013
- North Sydney Local Environmental Plan 2013

The primary purpose of a development control plan (DCP) is to guide development according to the aims of the corresponding local environmental plan (LEP). The DCP must be read in conjunction with the provisions of the relevant LEP.

Information provided in this OWMP comes from a wide range of waste management guidance at the local, state, and federal levels. The primary sources of guidance include:

- North Sydney Development Control Plan 2013
- NSW Better Practice Guidelines for Waste Management and Recycling in Commercial and Industrial Facilities 2012
- NSW Better Practice Guide for Resource Recovery in Residential Developments 2019
- NSW Waste Avoidance and Resource Recovery (WARR) Strategy 2014-2021
- NSW Waste Classification Guidelines 2014
- Australia's National Waste Policy 2018

2.1 COUNCIL OBJECTIVES

North Sydney Council aims to be a leader in local government for waste management by minimising the amount of waste taken to landfill sites and introducing efficient, cost effective and convenient collection and disposal methods. As such, Council expects:

- Minimal material usage and waste during building, construction and demolition;
- Minimal levels of waste during operation to reduce new building material usage and minimise volume of demolition materials;
- The building to be designed to encourage waste minimisation such as source separation, reuse and recycling;
- Adequate recycling systems to be provided in the design of the waste storage area;
- Materials with long lives and low maintenance are encouraged to be incorporated;
- Contractors and sub-contractors employed to undertake proposed construction works and waste removal to be educated about the waste objectives of the development; and
- The storage of any hazardous waste materials to be adequately secured.

2.1.1 SEAR 18 - WASTE

The following table identifies the relevant SEARs items and where these are addressed in this report and the accompanying Construction and Demolition Waste Management Plan:

Table 1: SEARs Items

Item	Corresponding Section
Identify, quantify and classify the likely waste streams to be generated during construction and operation.	Section 4 of the OWMP and Section 3 of the C&D WMP.
Provide the measures to be implemented to manage, reuse, recycle and safely dispose of this waste.	Sections 4-8 of the OWMP and Sections 2-3 of the C&D WMP.
Identify appropriate servicing arrangements (including but not limited to, waste management, loading zones, mechanical plant) for the site.	Section 4.4 of the OWMP and Section 3.5 of the C&D WMP.
Provide a hazardous materials survey of existing aboveground buildings that are proposed to be demolished or altered.	This is outside of the scope of EFRS and should be provided by an appropriate contractor.

3 DEVELOPMENT OVERVIEW

This SSDA seeks consent for alterations and additions to the existing North Sydney Public School. The proposal entails:

- Demolition of the existing hall (building B), haven building (building C) and 6 temporary buildings;
- Construction of a three storey building comprising:
 - staff administration rooms;
 - 16 homebases
 - a new library;
 - hall;
 - out of school hours care facilities;
 - covered outdoor learning area;
 - bicycle parking and end of trip facilities for staff; and
 - services, amenities and access.
- New entry gate and forecourt from Bay Road;
- Internal refurbishment of building G ground floor from the existing library to 3 homebases;
- Capacity for an increase in student numbers from 869 to 1,012; and
- Associated tree removal, landscaping and excavation.


The proposal maintains:

- The gates and fence of former Crows Nest House including the entrance from Pacific Highway and Bay Road;
- Existing gate along McHatton Street;
- The outdoor play area to the east of Building A;
- Existing covered outdoor learning area adjacent to Building A;
- The basketball courts and staff carpark in the western portion of the site;
- The significant tree planting on all school boundaries;
- Buildings A, D and F noting minor internal refurbishments are being undertaken outside of the SSDA scope of work (exempt development) to improve student amenities and canteen; and
- Building G noting ground floor internal refurbishment is proposed in the SSDA.

3.1 SITE LOCATION

The site is located at 182 Pacific Highway, North Sydney, as shown in Figure.1. The site has frontages to Bay Road, McHatton Street and Pacific Highway, with vehicle access via McHatton Street.

Figure 1. Site Location



Source: Google Maps

4 SCHOOL WASTE MANAGEMENT

The following section outlines best practice waste management for the development, including waste generation estimates and waste disposal and collection procedures.

4.1 WASTE GENERATION ESTIMATES

The school has provided information on the amount of waste currently generated in operation, to help guide waste generation estimates following the proposed works.

The site currently has a total of 869 students, with 4 x 1100L bins collected 2 x weekly for general waste; and 4 x 1100L bins collected 1 x weekly for recycling. Assuming that all bins are full at the time of collection to cater for a worst-case scenario, this equates to 8,800L/week for general waste and 4,400L/week for recycling.

4.2 BIN SUMMARY

The proposed number of students following these works is 1012. This represents an increase of 16.46% ($1,012 - 869 = 143$ $143 \div 869 = 0.1646$ $0.1646 \times 100 = 16.46$).

This percentage increase can be applied to the site's current figures of generated waste and recycling as follows:

General Waste – $8,800 \times 1.1646 = 10,248$ L

Recycling – $4,400 \times 1.1646 = 5,126$ L

Using the collection frequencies the site currently uses and the anticipated waste figures for the increased numbers of students, the current and proposed bin quantities are as follows:

Table 2: Bin Quantities

Current	Proposed
<u>General Waste:</u> 4 x 1100L bins collected 2 x weekly	<u>General Waste:</u> 5 x 1100L bins collected 2 x weekly
<u>Recycling:</u> 4 x 1100L bins collected 1 x weekly	<u>Recycling:</u> 5 x 1100L bins collected 1 x weekly

Bin sizes, quantities, and/or collection frequencies may be modified by management in operation. Management will be required to negotiate any changes to bins or collections with the collection service provider. Seasonal peak periods such as public and school holidays should also be considered.

4.3 WASTE DISPOSAL PROCEDURES

Suitably labelled general waste and recycling receptacles will be placed throughout each building as required for the collection of general waste and recycling generated in each space. Receptacles should be provided in convenient locations and areas of high waste generation.

The students, staff and visitors will be responsible for placing their general waste and recycling into the correct receptacle. The capacity of the source separation bins will be monitored by the caretaker and cleaners.

The cleaners will circulate throughout the building after hours and empty the general waste and recycling receptacles situated throughout the school. The cleaners will then transport the

general waste and recycling to the collection bins in the bin storage areas and deposit into the appropriate bins.

All operations within the school will share bins, bin storage areas and collection services.

The bin storage areas will be located on either side of the carpark off McHatton Street as per the current arrangement (see APPENDIX: A.1 for storage area locations). The caretaker, waste collection staff and cleaners will be the only personnel expected to access the collection bins. All transportation of waste and recycling must be co-ordinated with the caretaker or cleaners.

4.4 WASTE COLLECTION PROCEDURES

A private waste collection contractor will continue to service the waste and recycling bins as per the current arrangement. This report assumes that collections will follow the current schedule of twice weekly collections for general waste and once weekly collections for recycling.

On the day of service, a private waste collection vehicle will enter the site from McHatton Street and pull-up on the Western side of the carpark adjacent to the bin storage area. Collection staff will leave the vehicle and service the bins directly from the holding area. Once the bins have been serviced, the collection vehicle will exit the site onto McHatton Street in a forward direction. The caretaker will be responsible for transferring bins between the two storage areas, ensuring that on collection days, the required bins are located in the Western storage area for ease of servicing.

4.5 OTHER WASTE MANAGEMENT CONSIDERATIONS

Based on the uses anticipated for this development, the following waste management practices are recommended.

4.5.1 KITCHEN AND FOOD PREPARATION AREAS

Any food preparation area will be provided with dedicated source separation bins including a general waste bin and a recycling bin. Cleaners or nominated staff will be responsible for monitoring these bins and emptying them as required.

Recycling organic waste, such as food scraps and garden materials, dramatically reduces the quantity of waste being diverted to land fill and thus reduces the school's ecological footprint. Compost material can also be returned to the soil as a rich fertilizer and improve plant growth and the overall health of surrounding vegetation. The school may wish to pursue the use of worm farms or a communal composting facility. Composting facilities are to be sited on an unpaved area with soil depth of at least 300mm.

4.5.2 BATHROOMS

Washroom facilities should be supplied with collection bins for paper towels (if used). Sanitary bins for female restroom facilities must also be arranged with an appropriate contractor.

4.5.3 PRINTING & PHOTOCOPYING ROOMS

It is recommended that printing rooms and photocopying rooms are supplied with bins for the collection of paper, as well as separate receptacles for ink toner cartridges for recycling. The cleaners or nominated staff are responsible for monitoring these bins and ensuring the items are collected and recycled by an appropriate contractor.

4.5.4 BULKY WASTE ANDRE-USABLE ITEMS

A dedicated room is allocated on Level 1 for the storage of bulky waste items such as discarded furniture, eWaste, etc.

The caretaker will be responsible the management of the bulky goods area and storage of reusable items. School staff will need liaise with the caretaker for assistance with disposing of bulky items.

4.5.5 LIQUID WASTE

Liquid wastes such cleaning products, chemicals, paints, and cooking oil, etc., will be stored in a secure space that is bunded and drained to a grease trap in accordance with State government authorities and legislation.

4.5.6 PROBLEM WASTE

The caretaker will be responsible for making arrangements for the disposal and recycling of problem waste streams with an appropriate contractor. Problem wastes cannot be placed in general waste as they can have adverse impacts to human health and the environment if disposed of in landfill.

Problem waste streams include:

- Chemical Waste
- Liquid wastes
- Toner cartridges
- Lightbulbs
- eWaste
- Batteries

5 STAKEHOLDER ROLES & RESPONSIBILITIES

The following table demonstrates the primary roles and responsibilities of the respective stakeholders:

Table 3: Stakeholder Roles and Responsibilities

Roles	Responsibilities
Management	- Ensuring that all waste service providers submit monthly reports on all equipment movements and waste quantities/weights; - Organising internal waste audits/visual assessments on a regular basis; and - Manage any non-compliances/complaints reported through waste audits.
Site Caretaker	- Ensuring effective signage, communication and education is provided to occupants, tenants and cleaners; - Providing staff/contractors with equipment manuals, training, health and safety procedures, risk assessments, and PPE to control hazards associated with all waste management activities; - Ensuring site safety for residents, children, visitors, staff and contractors; - Abiding by all relevant OH&S legislation, regulations, and guidelines; - Assessing any manual handling risks and prepare a manual handling control plan for waste and bin transfers; - Preventing storm water pollution by taking necessary precautions (securing bin storage areas, preventing overfilling of bins) - Cleaning and transporting of bins as required; - Organising, maintaining and cleaning the general and recycled waste holding area; - Organising both garbage and recycled waste pick-ups as required; - Organising replacement or maintenance requirements for bins; - Organising bulky goods collection when required; and - Investigating and ensuring prompt clean-up of illegally dumped waste materials.
Staff/Students	- Dispose of all garbage and recycling in the allocated MGBs provided; - Ensure adequate separation of garbage and recycling; and - Compliance with the provisions of Council and the WMP.
Waste Contractor	- Provide a reliable and appropriate waste collection service; - Provide feedback to staff/students in regards to contamination of recyclables; and - Work with management/site caretaker to customise waste systems where possible.
Gardening/Landscaping Contractor	Removal of all garden organic waste generated during gardening maintenance activities for recycling at an offsite location.

6 SOURCE SEPARATION

Better practice waste management includes the avoidance, reuse, and recovery of unwanted items, which can be achieved through source separation. The table below outlines what is typically included in various waste streams and how they can be managed. Refer to the local council for a list of accepted materials. Planet Ark can be accessed online to find other facilities that recover unwanted items.

Table 4: Operational Waste Streams

Waste Stream	Description	Typical Destination	Waste Stream Management
General Waste	The remaining portion of the waste stream that is not recovered for re-use, processing, or recycling. May include soft plastics, food scraps, polystyrene, etc.	Landfill	Waste should be bagged before placing in the designated waste bins.
Recycling	A mixture of items that are commonly recycled usually segregated through a MRF. Typically include food and beverage containers (e.g. aluminium, glass, steel, hard plastics, cartons). Also included cardboard and paper products.	Resource Recovery Centre	Recycling must not be bagged, and instead should be placed loosely in the designated recycling bins. Cardboard should be flattened before placing in the recycling bins.
Secure Documents	Secure documents are printed paper materials that contain sensitive information.	Recycling Facility	Secure documents are placed in allocated secure document bins. Private contractor removes bins from site.
Green Waste	Green waste consists of unwanted organic materials that are easily biodegradable and/or compostable (e.g. lawn clippings, branches)	Resource Recovery Centre	Landscape Maintenance Contractors will remove the green waste from site during scheduled maintenance.
Food Waste	Food waste consists of unwanted or uneaten kitchen scraps that are easily compostable/biodegradable (e.g. vegetable peels, fruit rinds, coffee grounds).	Composting facility or Landfill	Food waste can be composted on-site, off-site, or else included in the general waste stream.
Electronic Waste	Discarded e-waste, electronic components and materials such as computers, mobile phones, keyboards, etc.	Resource Recovery Centre	Management to arrange for recycling and collections of e-waste.
Bulky Items	Items that are too large to place into general rubbish collection. This includes disused and/or broken furniture, white goods, etc.	Resource Recovery Centre or Landfill	Management responsible for arranging for storage and removal of bulky waste items.
Sanitary Waste	Feminine hygiene waste generated from female bathrooms.	Incineration or Landfill	Sanitary bins are serviced by sanitary waste contractor.
Other	Other recyclable items that require special recovery may include ink cartridges, batteries, chemical waste, fluorescent tubes, etc.	Resource Recovery Facility	Management responsible for arranging collections by appropriate recycling services when required.

7 BIN STORAGE AREAS

The total number of bins proposed for the site is as follows:

General Waste: 5 x 1100L bins collected **2 x weekly**

Recycling: 5 x 1100L bins collected **1 x weekly**

Bins will be stored in the two existing bin storage areas on either side of the carpark, with 6 x 1100L bins in the Western storage area adjacent to the gates, and 4 x 1100L bins in the Eastern storage area adjacent to Building F (see APPENDIX: A.1 for storage area locations). The Western storage area is large enough to accommodate the additional 2 x 1100L bins required by this proposal.

7.1 SIGNAGE

Signage and education are essential components to support best practice waste management including resource recovery, source separation, and diversion of waste from landfill.

Signage should include:

- Clear and correctly labelled waste and recycling bins,
- Instructions for separating and disposing of waste items. Different languages should be considered,
- Locations of, and directions to, the waste storage points with directional signs, arrows, or lines,
- The identification of all hazards or potential dangers associated with the waste facilities, and
- Emergency contact information should there be issues with the waste systems or services.

All signage should conform to the relevant Australian Standards.

7.2 POLLUTION PREVENTION

The caretaker shall be responsible for the following to minimise dispersion of site litter and prevent stormwater pollution to avoid impact to the environment and local amenity:

- Promoting adequate waste disposal into the bins
- Prevent overfilling of bins, keep all bin lids closed and bungs leak-free
- Taking action to prevent dumping or unauthorised use of waste areas
- Require collection contractor/s to clean up any spillage when clearing bins

8 BIN MOVING PATHS

The building caretaker will be responsible for any movement of bins that occurs at this site.

Transfer of bins should minimise manual handling where possible, as bins become heavy when full. Management must assess manual handling risks and provide any relevant documentation to key personal.

The routes along any bin moving paths should;

- Allow for a continuous route that is wholly within the property boundary.
- Be free from obstruction and obstacles such as steps and kerbs.
- Be constructed of solid materials with a non-slip surface
- Be A minimum of 300mm wider than the largest bin used onsite.
- If bins are moved manually, the route must not exceed a grade of 1:14.
- If a bin moving device is used, the route cannot exceed the maximum operating grade of the device. This is typically a grade of 1:4, however this will vary depending on the model of bin moving device acquired for the site.

9 USEFUL CONTACTS

EFRS does not warrant or make representation for goods or services provided by suppliers.

LOCAL COUNCIL

North Sydney Council Customer Service Ph: 02 9330 6400 E: council@northsydney.nsw.gov.au

PRIVATE WASTE COLLECTION PROVIDER

Capital City Waste Services	Ph: 02 9599 9999	E: service@ccws.net.au
Remondis	Ph: 02 9032 7100	
Suez Environmental	Ph: 13 13 35	
Wastewise NSW	Ph: 1300 550 408	E: admin@wastewise.com.au

BIN MOVING DEVICE SUPPLIERS

Electrodrive	Ph: 1800 333 002	E: sales@electrodrive.com.au
Sitecraft	Ph: 1300 363 152	E: sales@sitecraft.com.au
Spacepac	Ph: 1300 763 444	

ORGANIC DIGESTERS AND DEHYDRATORS

Closed Loop	Ph: 1300 762 166	
Orca		E: contact.australia@feedtheorca.com
Soil Food	Ph: 1300 556 628	
Waste Master	Ph: 1800 614 272	E: hello@wastemasterpacific.com.au

COOKING OIL CONTAINERS AND DISPOSAL

Auscol	Ph: 1800 629 476	E: sales@auscol.com
--------	------------------	---

ODOUR CONTROL

Purifying Solutions	Ph: 1300 636 877	E: sales@purifyingsolutions.com.au
---------------------	------------------	---

SOURCE SEPARATION BINS

Source Separation Systems	Ph: 1300 739 913	E: info@sourceseparationsystems.com.au
---------------------------	------------------	---

MOBILE GARBAGE BINS, BULK BINS AND BIN EQUIPMENT


SULO	Ph: 1300 364 388	E: sales@sulo.com.au
OTTO Australia	Ph: 02 9153 6999	

CHUTES, COMPACTORS AND EDIVERTER SYSTEMS

Elephants Foot Recycling Solutions	Ph: 1800 025 073	E: info@elephantsfoot.com.au
------------------------------------	------------------	---

APPENDIX A: ARCHITECTURAL PLANS

APPENDIX: A.1 SITE PLAN



Source: Fulton Trotter Architects, Drawing No. SD-1002, Rev.E, 13/08/21 – Proposed Site Plan

APPENDIX B: PRIMARY WASTE MANAGEMENT PROVISIONS

APPENDIX: B.1 TYPICAL BIN SPECIFICATIONS

All bins and containers allocated must conform with *AS4123.1-2008 Mobile waste containers* and be fitted with the correct colour lid for the waste contained as per *AS4123.7-2006 Mobile waste containers: colours, markings and designation requirements*.

The most common bin sizes are provided below, although not all sizes are shown. The dimensions are a guide only and differ slightly between manufacturers. Some bins have flat or domed lids and are used with different lifting devices. Refer to *AS4123.6-2006* for further details.

Table G1.2: Average dimension ranges for four-wheel bulk bins



Bin capacity	660L	770L	1100L	1300L	1700L
Height (mm)	1250	1425	1470	1480	1470
Depth (mm)	850	1100	1245	1250	1250
Width (mm)	1370	1370	1370	1770	1770
Approx footprint (m ²)	0.86–1.16	1.51	1.33–1.74	2.21	2.21
Approx weight (kg)	45	Not known	65	Not known	Not known
Approx maximum load (kg)	310	Not known	440	Not known	Not known

Dome or flat lid container

Sources include Sulo, Signal Waste, Cleanaway, SUEZ, Just Wheelie Bins and Perth Waste

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

APPENDIX: B.2 SIGNAGE FOR WASTE AND RECYCLING BINS

Waste signs

Signs and educational materials perform several functions including:

- informing residents why it is important to recover resources and protect the environment
- providing clear instructions on how to use the bins and services provided
- alerting people to any dangers or hazards within the bin storage areas.

All waste, recycling and organic bins should be Australian Standard colours and clearly and correctly labelled, such as by a sticker on the lid and/or the body of the bin.

Communal bin storage areas should be clearly signposted with signs outlining how to correctly separate waste into the bins provided. The local council responsible for waste services may be a good source of signs and posters and can advise on what signs are suitable.

Information on who to contact to find out more about the recycling and/or other resource recovery services in the building should also be displayed in communal areas, such as on a noticeboard.

The Planet Ark website also has resources available free of charge for use by businesses and councils. These signs can be found at businessrecycling.com.au/research/signage.cfm

Figure I1.1: Examples of waste wall posters (EPA supplied)



Figure I1.2: Examples of bin lid stickers (EPA supplied)



Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

Problem waste signs

The EPA has also produced a range of images and signs that can be used for problem wastes, such as fluoro globes and tubes, household and car batteries, e-waste and smoke detectors. To access these resources, contact the NSW EPA. Some examples are shown below.

Figure I2.1: Problem waste signs



Safety signs

The use of safety signs for waste resource recovery rooms must comply with *AS1319 Safety signs for occupational environments*. Safety signs must be used to regulate and control safety related to behaviour, warn of hazards and provide emergency information, including fire protection information. Suitable signs should be decided for each development as required.

Figure I3.1: Example safety signs



Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

APPENDIX: B.3 TYPICAL COLLECTION VEHICLE INFORMATION

General

Appropriate heavy rigid vehicle standards should be incorporated into the road and street designs in new developments where onsite collections are proposed. Road and street designs must comply with relevant Acts, regulations, guidelines, and codes administered by Austroads, Standards Australia, NSW Roads and Maritime Services, WorkSafe NSW and any local council traffic requirements.

Applicants and building designers should consult with councils and other relevant authorities before designing new roads or streets and access points for waste collection vehicles to establish specific design requirements.

Table H4.1: Australian Standards for turning circles for medium and heavy rigid class vehicles

Vehicle class	Overall length (m)	Design width (m)	Design turning radius (m)	Swept circle (m)	Clearance (travel) height (m)
Medium rigid vehicle	8.80	2.5	10.0	21.6	4.5
Heavy rigid vehicle	12.5	2.5	12.5	27.8	4.5

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

Large collection vehicles

Waste collection vehicles may be side-loading, rear-loading, front-lift-loading, hook or crane lift trucks. Vehicle dimensions vary by collection service, manufacturer, make and model. It is not possible to provide definitive dimensions, so architects and developers should consult with the local council and/or contractors.

The following characteristics represent typical collection vehicles and are provided for guidance only. Reference to *AS2890.2 Parking facilities: off-street commercial vehicle facilities* for detailed requirements, including vehicle dimensions, is recommended.

Table B2.1: Collection vehicle dimensions


Vehicle type	Rear-loading	Side-loading*	Front-lift-loading	Hook truck	Crane truck
Length overall (m)	10.5	9.6	11.8	10.0	10.0
Width overall (m)	2.5	2.5	2.5	3.0	2.5
Travel height (m)	3.9	3.6	4.8	4.7	3.8
Operational height for loading (m)	3.9	4.2	6.5	3.0	8.75
Vehicle tare weight (t)	13.1	11.8	16.7	13.0	13.0
Maximum payload (t)	10.0	10.8	11.0	14.5	9.5
Turning circle (m)	25.0	21.4	25.0	25.0	18

* The maximum reach of a side arm is 3 m.

Sources: JJ Richards, SUEZ, MacDonald Johnson, Cleanaway, Garwood, Ros Roca, Bingo and Edbro. Figures shown represent the maximum dimensions for each vehicle type.

Rear-loading collection vehicles


These vehicles are commonly used for domestic waste collections from MUDs and RFBs and sometimes for recycling. They can be used to collect waste stored in mobile bins or bulk bins, particularly where bins are not presented at the kerbside. They are also used for collecting bulky waste.



Rear-loading waste collection vehicle

Side-loading collection vehicles

This is the most commonly used vehicle for domestic waste, recycling and organics collections. It is only suitable for collecting mobile bins up to 360L in capacity.



Side-loading waste collection vehicle

Front-lift-loading collection vehicles

These vehicles are commonly used for collecting commercial and industrial waste. They can only collect specially designed front-lift bulk bins and not mobile bins.



Front-lift-loading waste collection vehicle

Small collection vehicles

Typically, councils and their contractors operate with large collection vehicles (heavy rigid class vehicles) because they carry greater payloads and allow for more cost-effective collection services. Some councils, or their contractors, may have smaller collection vehicles in their fleet. Early discussion with the council is important to confirm this, but it should not be assumed that the council will have access to small collection vehicles.

The waste management systems and the location of the collection point should always be designed so that the council can provide the standard domestic waste service.

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

APPENDIX C: SECONDARY WASTE MANAGEMENT PROVISIONS

APPENDIX: C.1 TYPICAL WORM FARM SPECIFICATIONS

Worm farms



Worm farms or vermiculture systems transform food and other organic material into vermicast (worm compost) and vermi-liquid (liquid extraction from a worm farm). Seafood, seafood shells, meat or bones, and dairy products are not an acceptable part of the worms' diet and should not be applied to these systems. Worm farms can occupy a small footprint and be located on balconies or in gardens. The worm farm should be placed in a sheltered position to avoid getting too hot in summer.

Worm farms come in different sizes and designs and are sold through hardware stores and often at local government offices. Medium and large-scale worm farms can service many households and commercial activities. These larger systems need a management process to ensure they are properly maintained.

Onsite composting



Compost tumblers and bins and compost bays transform food and other organic material into useful soil enhancer (compost). They are more versatile than worm farms as they can generally process a wider range of materials, including woody garden organics and can be placed in the sun. A variety of compost bins and tumblers are available from hardware stores or some local councils. There are also various online resources on how to construct them using recycling materials such as timber pallets. The footprint area requirement for a typical single household compost bin is about 1m x 1m x 1m.

Before setting up an onsite composter or worm-farm system, check with council for any local requirements such as setback distances from property boundaries.

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

APPENDIX: C.2 TYPICAL SOURCE SEPARATION BINS



Source: <https://www.sourceseparationsystems.com.au/>