Hastings Secondary College, Port Macquarie

Private and Public Views - Visual Impact Photomontage and Methodology Report

VIRTUAL IDEAS



and constants in

1 25 33115 5

1. INTRODUCTION

This document was prepared by Virtual Ideas to demonstrate the visual impact of the proposed development at Hastings Secondary College, Port Macquarie NSW with respect to the existing built form and site conditions.

2. VIRTUAL IDEAS EXPERTISE

Virtual Ideas is an architectural visualisation company that has over 15 years experience in preparing visual impact assessment content and reports on projects of major significance that meet the requirements for relevant local and state planning authorities.

Our reports have been submitted as evidence in proceedings in both the Land and Environment Court and the Supreme Court of NSW. Our director, Grant Kolln, has been an expert witness in the field of visual impact assessment in the Supreme Court of NSW.

Virtual Ideas' methodologies and outcomes have been inspected by various court appointed experts in relation to previous visual impact assessment submissions, and have always been found to be accurate and acceptable.

3. PHOTOMONTAGE METHODOLOGY

The following describes the process that we undertake to create the photomontage renderings that form the basis of this report.

3.1 DIGITAL 3D SCENE CREATION

The first step in our process is the creation of an accurate, real world scale digital 3D scene that is positioned at a common reference point using the MGA 56 co-ordinates system.

We have used a variety of data from various sources to create the 3D scene including a building 3D model and a site survey. A detailed description of the various data sources used in this report can be found in Appendix A.

point. This common reference point is established by using the MGA-56 co-ordinates system. in the data sources that can be aligned to points in other data sources that are positioned at MGA-56. This can be data such as site boundaries and building outlines.

Descriptions of how we have aligned each data source can also be found in Section 3.4.

3.2 SITE PHOTOGRAPHY

The site photography was captured from locations that were nominated by Ethos Urban, School Infrastructure NSW and DFP Planning.

Camera lenses for each photograph were selected taking a variety of factors into consideration including the distance from the site and the size of the proposed development with respect to the existing built form and landscape.

In some cases, a specific lens requirement set by planning authorities may not produce a photomontage that is effective for visual impact assessment. In the cases where we are required to satisfy a specific lens stipulation and we consider that this is not effective for assessment of visual impact, we will outline the extent of the longer lens on the photomontage.

Full metadata of the photographs was recorded during the site photography. The critical data we extracted was date, time and lens width or field of view.

- All data has been imported into the 3D scene at real world scale and positioned to a common reference When we receive data sources that are not positioned to MGA-56 co-ordinates, we use common points

3.3 SITE AND PHOTOGRAPHY LOCATION SURVEY

To correctly adjust the digital cameras in our 3D scenes to match the positions of the site photography, we used the relevant information provided in the site survey drawing (at MGA 56 co-ordinates) and a 3D model was created from drawings provided from FJMT.

3.4 ALIGNMENT OF 3D SCENE TO PHOTOGRAPHY

To align the 3D scene to the photograph, we first imported the site and photography location survey data into the 3D scene.

We then loaded the photograph into the background of the corresponding 3D scene camera view, ensuring that the aspect ratio and lens setting match.

The 3D scene camera was moved to the correct position and rotated so that the surveyed feature locations match the same features in the photograph.




Image showing proposed survey drawing(in red lines) aligned to architectural drawing(in yellow lines)

3.5 RENDERING AND PHOTOMONTAGE CREATION

After the completing the camera alignment, we add lighting to the 3D scene.

A digital sunlight system was added in the 3D scene to match the lighting direction of the sun in the photograph. This was done using the software sunlight system that matches the angle of the sun using location data and time and date information. This data was extracted from the metadata of the site photographs.

For the photomontages, we were requested to apply a basic white material to the proposed development.

Trees being proposed for removal were also removed from the photography where this was achievable and trees easily identifiable. We referenced the supplied documentation included as Appendix E and F to ascertain the locations of such trees.

We also placed future proposed trees into the 3D model referring the proposed tree manangment plan included as Appendix G. Proposed trees are shown in the images as semi-transparent with a green overlay.

Images were then rendered from the software and layered over the photograph. Additional linework was added to show where built form occurs behind existing built form and landscape.




Image showing building model aligned to survey and architectural drawings

3.6 COMPARISON OF FORMER PROPOSED DESIGN OF JULY 2021 TO CURRENT PROPOSED DESIGN OF OCTOBER 2022

The images on this page present a comparison of the former proposed designs from July 2021 to that of the updated proposal from October 2022. In the images the proposed buildings are presented in beige, trees in green and the existing buildings and site in grey.

In the Updated Proposed Design October 2022 image a blue overlay represents changes for the PCYC subject to this approval application.



Former Proposed Design July 2021



Updated Proposed Design October 2022

4.1 MAP OF PHOTOGRAPHY LOCATIONS

PLAN ILLUSTRATING PRIVATE VIEW CAMERA LOCATIONS FOR VISUAL IMPACT PHOTOGRAPHY OF HASTING SECONDARY SCHOOL, PORT MACQUARIE NSW



4.2 MAP OF PHOTOGRAPHY LOCATIONS

PLAN ILLUSTRATING PUBLIC VIEW CAMERA LOCATIONS FOR VISUAL IMPACT PHOTOGRAPHY OF HASTING SECONDARY SCHOOL, PORT MACQUARIE NSW



5.1 PRIVATE CAMERA POSITION 01 - 21 OWEN ST

AS APPROVED



AS PROPOSED




| Photo Date: | 22nd July 2021 |
|----------------------------|------------------------------|
| Camera Used: | Canon EOS 80D |
| Camera Lens: | EF-S18-55mm f/3.5-5.6 IS STM |
| Focal length in 35mm Film: | 33.6mm |

5.1 PRIVATE CAMERA POSITION 01 - 21 OWEN ST



5.1 PRIVATE CAMERA POSITION 01 - 21 OWEN ST

AS PROPOSED



Proposed landscape

Proposed building design



5.2 PRIVATE CAMERA POSITION 02 - LA MER UNIT 4

AS APPROVED



AS PROPOSED




| Photo Date: | 23rd July 2021 |
|----------------------------|------------------------------|
| Camera Used: | Canon EOS 80D |
| Camera Lens: | EF-S18-55mm f/3.5-5.6 IS STM |
| Focal length in 35mm Film: | 33.6mm |

5.2 PRIVATE CAMERA POSITION 02 - LA MER UNIT 4



5.2 PRIVATE CAMERA POSITION 02 - LA MER UNIT 4

AS PROPOSED



Proposed landscape

Proposed building design



5.3 PRIVATE CAMERA POSITION 03 - LA MER UNIT 6

AS APPROVED




AS PROPOSED




| Photo Date: | 23rd July 2021 |
|----------------------------|------------------------------|
| Camera Used: | Canon EOS 80D |
| Camera Lens: | EF-S18-55mm f/3.5-5.6 IS STM |
| Focal length in 35mm Film: | 33.6mm |

5.3 PRIVATE CAMERA POSITION 03 - LA MER UNIT 6



5.3 PRIVATE CAMERA POSITION 03 - LA MER UNIT 6

AS PROPOSED



Proposed landscape

Proposed building design

5.4 PRIVATE CAMERA POSITION 04 - LA MER UNIT 14

AS APPROVED



AS PROPOSED




| Photo Date: | 21st July 2021 |
|----------------------------|------------------------------|
| Camera Used: | Canon EOS 80D |
| Camera Lens: | EF-S10-18mm f/4.5-5.6 IS STM |
| Focal length in 35mm Film: | 24mm |

5.4 PRIVATE CAMERA POSITION 04 - LA MER UNIT 14



5.4 PRIVATE CAMERA POSITION 04 - LA MER UNIT 14

AS PROPOSED



Proposed landscape

Proposed building design

5.5 PRIVATE CAMERA POSITION 05 - MAINSAIL UNIT 9

AS APPROVED



AS PROPOSED



| Photo Date: | 23rd July 2021 |
|----------------------------|------------------------------|
| Camera Used: | Canon EOS 5DS R |
| Camera Lens: | EF-S10-18mm f/4.5-5.6 IS STM |
| Focal length in 35mm Film: | 24mm |

5.5 PRIVATE CAMERA POSITION 05 - MAINSAIL UNIT 9



5.5 PRIVATE CAMERA POSITION 05 - MAINSAIL UNIT 9

AS PROPOSED



Proposed landscape

Proposed building design

5.6 PRIVATE CAMERA POSITION 06 - MAINSAIL UNIT 10

AS APPROVED



AS PROPOSED



| Photo Date: | 21st July 2021 |
|----------------------------|------------------------------|
| Camera Used: | Canon EOS 5DS R |
| Camera Lens: | EF-S10-18mm f/4.5-5.6 IS STM |
| Focal length in 35mm Film: | 20.8mm |

5.6 PRIVATE CAMERA POSITION 06 - MAINSAIL UNIT 10



5.6 PRIVATE CAMERA POSITION 06 - MAINSAIL UNIT 10

AS PROPOSED



Proposed landscape

Proposed building design

5.7 PRIVATE CAMERA POSITION 07 - MAINSAIL UNIT 11

AS APPROVED



AS PROPOSED



| Photo Date: | 21st July 2021 |
|----------------------------|--------------------------|
| Camera Used: | Canon EOS 5DS R |
| Camera Lens: | EF-S10-18mm f/4.5-5.6 IS |
| Focal length in 35mm Film: | 24mm |

5.7 PRIVATE CAMERA POSITION 07 - MAINSAIL UNIT 11



5.7 PRIVATE CAMERA POSITION 07 - MAINSAIL UNIT 11

AS PROPOSED



Proposed landscape

Proposed building design

5.8 PUBLIC CAMERA POSITION 01

AS APPROVED



AS PROPOSED



| Photo Date: | 11th May 2021 |
|----------------------------|------------------------|
| Camera Used: | Canon EOS 5DS R |
| Camera Lens: | EF24-105mm f/4L IS USM |
| Focal length in 35mm Film: | 24mm |

5.8 PUBLIC CAMERA POSITION 01





5.8 PUBLIC CAMERA POSITION 01

AS PROPOSED



Proposed landscape

Proposed building design



5.9 PUBLIC CAMERA POSITION 02

AS APPROVED



AS PROPOSED



| Photo Date: | 11th May 2021 |
|----------------------------|------------------------|
| Camera Used: | Canon EOS 5DS R |
| Camera Lens: | EF24-105mm f/4L IS USM |
| Focal length in 35mm Film: | 24mm |

5.9 PUBLIC CAMERA POSITION 02



5.9 PUBLIC CAMERA POSITION 02

AS PROPOSED



Proposed landscape

Proposed building design

5.10 PUBLIC CAMERA POSITION 03

AS APPROVED




AS PROPOSED




| Photo Date: | 11th May 2021 |
|----------------------------|------------------------|
| Camera Used: | Canon EOS 5DS R |
| Camera Lens: | EF24-105mm f/4L IS USM |
| Focal length in 35mm Film: | 24mm |

5.10 PUBLIC CAMERA POSITION 03



5.10 PUBLIC CAMERA POSITION 03

AS PROPOSED



Proposed landscape

Proposed building design

5.11 PUBLIC CAMERA POSITION 04

AS APPROVED



AS PROPOSED



PHOTOGRAPH DETAILS

| Photo Date: | 11th May 2021 |
|----------------------------|------------------------|
| Camera Used: | Canon EOS 5DS R |
| Camera Lens: | EF24-105mm f/4L IS USM |
| Focal length in 35mm Film: | 24mm |

5.11 PUBLIC CAMERA POSITION 04

AS APPROVED



5.11 PUBLIC CAMERA POSITION 04

AS PROPOSED



Proposed landscape

Proposed building design



5.12 PUBLIC CAMERA POSITION 05

AS APPROVED



AS PROPOSED




PHOTOGRAPH DETAILS

| Photo Date: | 11th May 2021 | |
|----------------------------|------------------------|--|
| Camera Used: | Canon EOS 5DS R | |
| Camera Lens: | EF24-105mm f/4L IS USM | |
| Focal length in 35mm Film: | 24mm | |

5.12 PUBLIC CAMERA POSITION 05


AS APPROVED





5.12 PUBLIC CAMERA POSITION 05

AS PROPOSED



Proposed landscape

Proposed building design

Hastings Secondary College, Port Macquarie NSW - Private and Public Views - Visual Impact Photomontage and Methodology Report - 2nd November 2022



6.1 APPENDIX A: 3D SCENE DATA SOURCES

A.1 - 3D Model of the proposed development

| File Name: | HSPM Hastings Schools Port Macquarie Model |
|------------------|--|
| Author: | FJMT |
| Format: | DIN3D |
| Scene Alignment: | MGA GDA2020 |

A.2 - 3D Model updated September 2022 of the proposed development

| File Name: | HSPM Hastings CAPA Model |
|------------------|--------------------------|
| Author: | FJMT |
| Format: | DIN3D |
| Scene Alignment: | MGA GDA2020 |

A.2 - 3D Model updated October 2022 of the proposed development

| File Name: | 4662.530.01 Hastings PCYC 3D model |
|------------------|------------------------------------|
| Author: | SHAC |
| Format: | DIN3D |
| Scene Alignment: | MGA GDA2020 |


A.4 - Site Survey - refer to Appendix B for details

| File Name: | 55819-2B DETAIL.dwg |
|------------|---------------------|
| Author: | YSCO GEOMATICS |
| Format: | Autocad DWG |
| Alignment: | MGA GDA2020 |

A.5 - Survey of camera location and alignment positions - refer to Appendix C for details

6661_Survey.dwg King & Campbell File Name: Author: Format: Autocad DWG Alignment: MGA GDA2020





6.2 APPENDIX B: SITE SURVEY SUPPLIED BY YSCO GEOMATICS

6.3 APPENDIX C: PHOTOGRAPHY SURVEY FOR PRIVATE VIEWS SUPPLIED BY KING & CAMPBELL

Project: HASTINGS SECONDARY COLLEGE, PORT MACQUARIE VISUAL IMPACT ASSESSMENT - Survey & Coordination of Photo Control Points

KING & CAMPBELL Ref: 6661 (rev A) Dates of Survey: 21-23 JULY 2021

Notes:

- Coordinates have been shown in MGA2020 coordinates (ground coordinates related to PM11959)

- Reduced Levels (RL) are related to Australian Height Datum (AHD)

- Points surveyed using total station observations

-This table to be used in conjunction with the .dwg file (Ref 6661_Survey), and the data contained in this hard copy table takes precedence over any co-ordinate interpolated from the CAD file or EXCEL spreadsheet

| Point ID | Easting MGA 2020 grou | Northing nd coordinates | REDUCED LEVEL | Description |
|----------|--------------------------|----------------------------|---------------|-------------------------------------|
| | (origin Pl | | A.H.D. | |
| CAM 4 | 492356.58 | 6522461.73 | 15.69 | CAMERA VIEW UNIT 4 (11 OWEN ST) |
| CAM 6 | 492356.55 | 6522461.71 | 18.34 | CAMERA VIEW UNIT 6 (11 OWEN ST) |
| CAM 14 | 492356.53 | 6522461.76 | 28.96 | CAMERA VIEW UNIT 14 (11 OWEN ST) |
| CAM 21 | 492363.88 | 6522346.91 | 16.62 | CAMERA VIEW UNIT 21 OWEN ST |
| CAM 9A | 492361.03 | 6522361.41 | 22,50 | CAMERA VIEW A UNIT 9 (17-19 OWEN ST |
| CAM 9B | 492362.10 | 6522360.28 | 22,44 | CAMERA VIEW B UNIT 9 (17-19 OWEN ST |
| CAM 9C | 492362.72 | 6522358.79 | 22,49 | CAMERA VIEW C UNIT 9 (17-19 OWEN ST |
| CAM 10 | 492361.66 | 6522369,58 | 22,43 | CAMERA VIEW UNIT 10 (17-19 OWEN ST |
| CAM 11 | 492356.70 | 6522383.75 | 22,42 | CAMERA VIEW UNIT 11 (17-19 OWEN ST |
| 0.07.11 | | COLLOGO NO | LLIL | |
| 900 | 492578.42 | 6522631.09 | 20.66 | ROOF RIDGE |
| 901 | 492403.26 | 6522578.94 | 17.74 | CORNER OF PARAPET |
| 902 | 492388.35 | 6522537.26 | 17.84 | TOP OF FLAG POLE |
| 903 | 492361.14 | 6522520.07 | 19.81 | TOP OF POWER POLE |
| 904 | 492438.13 | 6522510.20 | 13.14 | CORNER OF BUILDING GUTTER |
| 905 | 492363.78 | 6522477.77 | 20.77 | TOP OF POWER POLE |
| 906 | 492364.38 | 6522448.79 | 21.57 | TOP OF POWER POLE |
| 907 | 492376.41 | 6522469.01 | 11.60 | TOP OF SIGN IN MEDIAN |
| 908 | 492428.46 | 6522432.82 | 14.92 | CORNER OF BUILDING GUTTER |
| 909 | 492403.45 | 6522462.73 | 13.68 | CORNER OF GOAL POST (SOUTH) |
| 910 | 492403.34 | 6522463.58 | 16.70 | TOP OF GOAL POST (SOUTH) |
| 911 | 492403.03 | 6522469.27 | 16.70 | TOP OF GOAL POST (NORTH) |
| 912 | 492403.04 | 6522470.23 | 13.67 | CORNER OF GOAL POST (NORTH) |
| 913 | 492490.17 | 6522470.25 | 16.20 | TOP OF GOAL POST (SOUTH) |
| 914 | 492517.65 | 6522396.50 | 22.32 | CORNER OF BUILDING GUTTER |
| 915 | 492465.73 | 6522421.41 | 20.98 | ROOF RIDGE |
| 916 | 492395.57 | 6522411.57 | 14.98 | TOP OF FENCE POST |
| 917 | 492395.84 | 6522407.47 | 15.15 | TOP OF FENCE POST |
| 918 | 492416.17 | 6522406.58 | 21.68 | TOP OF DOME |
| 919 | 492416.65 | 6522399.15 | 21.72 | TOP OF DOME |
| 920 | 492416.71 | 6522394.44 | 21.41 | ROOF RIDGE |
| 921 | 492397.75 | 6522378.77 | 16.35 | TOP OF FENCE POST |
| 922 | 492398.85 | 6522361.73 | 18.29 | CORNER OF ROOF GUTTER |
| 923 | 492399.28 | 6522354.89 | 18.28 | CORNER OF ROOF GUTTER |
| 924 | 492395.98 | 6522352.17 | 18.12 | TOP OF SIGN POST |
| 925 | 492380.60 | 6522359.35 | 14.92 | END OF LINEMARKING |
| 926 | 492381.49 | 6522346.41 | 15.64 | END OF LINEMARKING |
| 927 | 492371.59 | 6522355.25 | 17.16 | CORNER OF CABLE CLAMP |
| 928 | 492362.57 | 6522372.52 | 22.06 | CORNER OF BALUSTRADE |

6.3 APPENDIX C: PHOTOGRAPHY SURVEY FOR PUBLIC VIEWS SUPPLIED BY YSCO GEOMATICS

Project: HASTINGS SECONDARY SCHOOL DEVELOPMENT PORT MACQUARIE

Survey and Coordination of Photo Control Points YSCO GEOMATICS Ref: 5819 Photo Points (amendment A) Date of Survey: 13 MAY 2021

Notes:

- Points surveyed relate to the brief provided on 12 MAY 2021

- Coordinates have been shown in MGA2020 coordinates (ground coordinates related to PM11959)

Reduced Levels (RL) are related to Australian Height Datum (AHD)
Points surveyed using combination of GNSS and total station observations

-This table to be used in conjunction with the .dwg file provided, and the data contained in this hard copy table takes precedence over any co-ordinate interpolated from the CAD file or EXCEL spreadsheet

| Point Number | Easting MGA 2020 grou (origin PN | | REDUCED LEVEL AH.D. | Description |
|--------------|--|------------|------------------------|------------------------------------|
| 1 | 492358.20 | 6522536.09 | 9.22 | CAMERA VIEW 01 |
| 101 | 492384.83 | 6522524.70 | 11.81 | CORNER OF STREET SIGN |
| 102 | 492386.02 | 6522503.61 | 18.64 | TOP OF LIGHT POLE |
| 103 | 492414.55 | 6522427.12 | 21.39 | RIDGE POINT |
| 104 | 492360.22 | 6522526.90 | 11.86 | TOP OF STREET SIGN POST |
| 2 | 492376.26 | 6522269.14 | 18.66 | CAMERA VIEW 02 |
| 201 | 492386.12 | 6522274.18 | 18.89 | REFLECTOR IN ROAD |
| 202 | 492417.84 | 6522299.93 | 22.78 | CORNER OF BUILDING GUTTER |
| 203 | 492376.67 | 6522278.14 | 21.31 | TOP OF STREET SIGN POST |
| 204 | 492400.33 | 6522282.58 | 29.21 | TOP OF POWER POLE |
| 205 | 492399.27 | 6522354.91 | 18.28 | CORNER OF GUTTER OF ENTRY BUILDING |
| 3 | 492482.23 | 6522202.07 | 22.94 | CAMERA VIEW 03 |
| 301 | 492477.65 | 6522206.44 | 22.83 | JOINT IN CONCRETE KERB |
| 302 | 492481.99 | 6522253.98 | 24.82 | CORNER OF BUILDING GUTTER (MIDDLE) |
| 303 | 492489.16 | 6522254.48 | 24.72 | CORNER OF BUILDING GUTTER (EAST) |
| 304 | 492472.38 | 6522298.45 | 26.20 | CORNER OF BUILDING GUTTER (WEST) |
| 305 | 492423.19 | 6522250.96 | 21.59 | BOTTOM CORNER OF BUILDING |
| 306 | 492477.59 | 6522228.14 | 24.75 | TOP OF FENCE POST |
| 307 | 492480.07 | 6522228.30 | 24.78 | TOP OF FENCE POST |
| 4 | 492615.32 | 6522533.37 | 12.03 | CAMERA VIEW 04 |
| 401 | 492507.22 | 6522512.53 | 35.97 | TOP OF RIGHT HAND LIGHT POLE |
| 402 | 492507.89 | 6522439.55 | 36.50 | TOP OF LEFT HAND LIGHT POLE |
| 403 | 492569.54 | 6522436.67 | 14.85 | CORNER GOAL POST (EAST) |
| 404 | 492563.84 | 6522436.69 | 14.81 | CORNER GOAL POST (WEST) |
| 405 | 492482.60 | 6522439.21 | 19.03 | CORNER GUTTER BASKETBALL STADIUM |

| Point Number | - | Northing and coordinates M11959) | REDUCED LEVEL AH.D. |
|--------------|-----------|--|------------------------|
| 5 | 492362.91 | 6522464.91 | 10.36 |
| 501 | 492376.41 | 6522469.01 | 11.60 |
| 502 | 492403.03 | 6522469.27 | 16.70 |
| 503 | 492403.34 | 6522463.58 | 16.70 |
| 504 | 492389.37 | 6522454.82 | 13.70 |
| 505 | 492465.73 | 6522421.41 | 20.98 |

Description

CAMERA VIEW 05


TOP OF SIGN IN MEDIAN TOP OF GOAL POST (NORTH) TOP OF GOAL POST (SOUTH) TOP OF PARKING SIGN RIDGE OF BASKETBALL STADIUM

6.4 APPENDIX D: ARCHITECTURAL PLANS SUPPLIED BY FJMT



| tstudi | С |
|--|---|
| 0 20m | \bigcirc |
| es sions and existing condi ind verified by the contr g with the work. elative to Yuustralian He ale drawings. ed dimensions only. | itions shall be actor before ight Datum'. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| For Construction For Construction | SEH AC |
| name hools Port Macquarie condary College | by chk |
| rie NSW 2444 | Scale 1:500 @ A1 |
| e | First Issued |
| R-0-12001 | 00/00/2021 Rev B |
| | |

6.5 APPENDIX E: TREE REMOVAL PLAN SUPPLIED BY FJMT



Hastings Secondary College, Port Macquarie NSW - Private and Public Views - Visual Impact Photomontage and Methodology Report - 2nd November 2022

| 1.1 | |
|-----|--|
| 100 | |

5

KED AND VERIFIED BY THE FORE PROCEEDING WITH THE WORK. ATME TO WUSTRALIAN HIEG HT DATUM'. RAWINGS. MENSIONS ONLY.


STEBOUNDARY EXISTING SPOTLEVEL PROPOSEDSPOTLEVEL

EXISTING TREE TO BE RETAINED IN ACCORDANCE WITH ARBORICLL TURAL AS SESSMENT


EXISTING TREE TO BE

| | Mi Ki by chik |
|--------------------------------|---------------------|
| tan connuntly Mijetabetacan | fjmt |
| Macquarie | |
| Man - Tree R | emoval |
| that issued | 96/3/21 |
| eet no. | revision |
| SDA-800002 | 02 |
| | |

6.6 APPENDIX F: TREE REMOVAL PLAN CREATED BY THE TREE MD PTY LTD



6.7 APPENDIX G: TREE MANAGEMENT PLAN - PROPOSED SUPPLIED BY FJMT



Hastings Secondary College, Port Macquarie NSW - Private and Public Views - Visual Impact Photomontage and Methodology Report - 2nd November 2022

EXISTING SPOTLEVE

EXISTING TREE TO B RETAINED IN ACCORDANCE WITH ARBORICULTURAL

EXISTING TREE TO BE

TREE

KI KI fjmt first lanued 23/2/2 03