

YPI2B OWNERSHIP TRUST NO 6



Geotechnical Investigation



175-177 Cleveland St & 6-8 Woodburn Street, Redfern,
NSW

Document Control

Report Title: Geotechnical Investigation, 175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW

Report No: E25342.G03

Copies	Recipient
1 Soft Copy (PDF – Secured, issued by email)	James McBride YPI2B Ownership Trust No 6 Level 12, 179 Elizabeth Street, SYDNEY NSW 2000
2 Original (Saved to Digital Archives) (\\Pahlei-au\$07 - Projects\E25342_YPI2B Ownership_Redfern_GI_PSI_DSI_RAP_AQI\05_Deliverables\Work in Progress\G03 - GI\E25342.G03 - Geotechnical Investigation Report.docx)	EI Australia Suite 6.01, 55 Miller Street, PYRMONT NSW 2009

Author		Technical Reviewer	
			
Anthony Camillos Geotechnical Engineer		Stephen Kim Senior Geotechnical Engineer	
Revision	Details	Date	Amended By
	Original	3 August 2022	

© 2022 EI Australia (EI) ABN: 42 909 129 957

This report is protected by copyright law and may only be reproduced, in electronic or hard copy format, if it is copied and distributed in full and with prior written permission by EI.

Table of Contents

	Page Number
1. INTRODUCTION	1
1.1 Background	1
1.2 Proposed Development	1
1.3 Objectives	1
1.4 Scope of Works	2
1.5 Constraints	3
2. SITE DESCRIPTION	4
2.1 Site Description and Identification	4
2.2 Local Land Use	5
2.3 Regional Setting	5
3. INVESTIGATION RESULTS	7
3.1 Stratigraphy	7
3.2 Groundwater Observations	8
3.3 Test Results	8
4. RECOMMENDATIONS	10
4.1 Geotechnical Issues	10
4.2 Dilapidation Surveys	10
4.3 Existing Footings	10
4.4 Excavation Methodology	10
4.4.1 <i>Excavation Assessment</i>	10
4.4.2 <i>Excavation Monitoring</i>	11
4.5 Groundwater Considerations	11
4.6 Excavation Retention	12
4.6.1 <i>Support Systems</i>	12
4.6.2 <i>Retaining Wall Design Parameters</i>	13
4.7 Foundations	16
4.8 Basement Floor Slab	16
5. FURTHER GEOTECHNICAL INPUTS	17
6. STATEMENT OF LIMITATIONS	18
REFERENCES	19
ABBREVIATIONS	19

Schedule of Figures

Plate 1: Aerial photograph of the site (source: SIX Maps, accessed 7/12/21)

Plate 2: Excerpt of geological map showing location of site.

Schedule of Tables

Table 1-1	Augering and Rock Coring Depths	2
Table 2-1	Summary of Site Information	4
Table 2-2	Summary of Local Land Use	5
Table 2-3	Topographic and Geological Information	5
Table 3-1	Summary of Subsurface Conditions	7
Table 3-3	Summary of Soil Laboratory Test Results	9
Table 4-1	Geotechnical Design Parameters	15

Appendices

FIGURES

Figure 1 Site Locality Plan

Figure 2 Borehole Location Plan

APPENDIX A – BOREHOLE LOGS AND EXPLANATORY NOTES

APPENDIX B – LABORATORY CERTIFICATES

APPENDIX C – IMPORTANT INFORMATION

1. Introduction

1.1 Background

At the request of James McBride on behalf of YPI2B Ownership Trust No 6 (the Client), EI Australia (EI) has carried out a Geotechnical Investigation (GI) for the proposed development at 175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW (the Site).

This GI report has been prepared to provide advice and recommendations to assist in the preparation of designs for the proposed development. The investigation has been carried out in accordance with the agreed scope of works outlined in EI's proposals referenced;

- P19736.1, dated 24 August 2021, with the Client's signed authorisation to proceed, dated 24 August 2021; and
- P19736.2, dated 31 March 2022, with the Client's authorisation to proceed emailed on 23 March 2022.

1.2 Proposed Development

The following documents, supplied by the Client, were used to assist with the preparation of this GI report:

- Architectural Drawings prepared by Mark Shapiro Architects – Project No. 21022, Drawing Numbers SK00 to SK14, latest revision P2, Dated 4 November 2021, was supplied by the Client, and
- Stage 1 and Stage 2 Environmental Site Assessment, prepared by geo-environmental engineering – Project number E14002RED (Appendix I).

Based on the provided documents, EI understands that the proposed development involves the demolition of the existing site structures and the construction of a five to six-storey mixed-use boarding house development overlying a common single-level basement. The basement level is proposed to have a finished floor level (FFL) of RL 16.1m. A Bulk Excavation Level (BEL) of RL 15.8m is assumed, which includes allowance for the construction of the basement slab. To achieve the BEL, excavation depths from 1.6m to 7.1m Below Existing Ground Level (BEGL) have been estimated. Locally deeper excavations may be required for footings, lift overrun pits, crane pads, and service trenches. The basement extends up to all boundaries, except the western boundary which has an irregular shape ranging between none to 20m set back.

1.3 Objectives

The objective of the GI was to assess site surface and subsurface conditions at five borehole locations, and to provide geotechnical advice and recommendations addressing the following:

- Dilapidation Surveys;
- Excavation methodologies and monitoring requirements;
- Groundwater considerations;
- Vibration considerations;
- Excavation support requirements, including geotechnical design parameters for retaining walls and shoring systems;

- Building foundation options, including;
 - Design parameters.
 - Earthquake loading factor in accordance with AS1170.4:2007.
- The requirement for additional geotechnical works.

1.4 Scope of Works

The scope of works for the GI included:

- Preparation of a Work Health and Safety Plan;
- Review of relevant geological maps for the project area;
- Site walkover inspection by a Geotechnical Engineer to assess topographical features and site conditions;
- Auger drilling of six boreholes (BH1, BH2M, BH3M, BH4, BH201M and BH202M) by a portable hand rig using solid flight augers equipped with a 'Tungsten-Carbide' (T-C) bit. The boreholes were auger drilled to depths as shown in **Table 1-1** below:

Table 1-1 Augering and Rock Coring Depths

Borehole ID	Augering		Rock Coring	
	Depth (m)	RL (m AHD)	Depth (m)	RL (m AHD)
BH1	1.00	16.40	7.43	9.97
BH2M	9.00	11.40	13.52	6.88
BH3M	5.50	12.00	8.86	8.64
BH4	0.60	21.60	13.63	8.57
BH201M	0.50	16.90	10.22	7.18
BH202M	0.50	20.30	13.33	7.47

- Measurements of groundwater seepage/levels, where possible, in the augered sections of the boreholes during and shortly after completion of auger drilling;
- The strength of the bedrock in the augered sections of the boreholes was assessed by observation of the auger penetration resistance using a T-C drill bit and examination of the recovered rock cuttings. It should be noted that rock strengths assessed from augered boreholes are approximate and strength variances can be expected.
- Continuation of BH1, BH2M, BH3M, BH4, BH201M and BH202M using NMLC diamond coring techniques to termination depths shown above in **Table 1-1**. The rock core photographs are presented in **Appendix A**;
- One Dynamic Cone Penetrometer (DCP) tests (DCP1) was carried out adjacent to BH1 and were carried out to a refusal depth of 1.6m BEGL;
- Boreholes BH2M, BH3M, BH201M and BH202M were converted into groundwater monitoring well with a depth of 10.8m (RL 9.6m), 6.8m (RL 10.75m), 3.3m (RL 14.1m) and 6.0m (RL 11.4m) BEGL respectively, to allow for long-term groundwater monitoring;

- Boreholes BH1, and BH4 were backfilled with spoils and capped with concrete upon completion;
- Soil and rock samples were sent to STS Geotechnics Pty Ltd (STS) and SGS Australia (SGS), which are National Australian Testing Authority (NATA) accredited laboratories, for testing and storage.
- Preparation of this GI report.

EI's Geotechnical Engineer was present full-time onsite to set out the borehole locations, direct the testing and sampling, log the subsurface conditions and record groundwater levels.

1.5 Constraints

The GI was limited by the intent of the investigation and presence of the existing structure. The discussions and advice presented in this report are intended to assist in the preparation of designs for the proposed development. Further geotechnical inspections should be carried out during construction to confirm the geotechnical and groundwater models, and the preliminary design parameters provided in this report.

2. Site Description

2.1 Site Description and Identification

The site identification details and associated information are presented in **Table 2-1** below while the site locality is shown on **Figure 1**. An aerial photograph of the site is presented in **Plate 1** below.

Table 2-1 Summary of Site Information

Information	Detail
Street Address	175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW
Lot and Deposited Plan (DP) Identification	Lot 1 DP 724328 Lot 1 DP1093304 Lot 15 DP 57107 Lot 10 DP 809537 Lot 3 Section 2 DP 977379 Lot 4 Section 2 DP 977379 Lot 5 DP68798 Lot 1 in DP 780307 Lot1 in DP 121029
Brief Site Description	At the time of our investigation, the site was occupied by four, two to four-storey brick and brick rendered buildings. An asphalt-paved ground-floor carpark is located on the north-eastern corner of the site. 6-8 Woodburn Street had a single basement carpark level in the south-western portion of the site, accessed from Eveleigh Street.
Site Area	The site area is approximately 2020m ² (based on the provided Architectural Drawings referenced above).



Plate 1: Aerial photograph of the site (source: SIX Maps, accessed 7/12/21)

2.2 Local Land Use

The site is situated within an area of a mixed commercial and residential use. Current uses on surrounding land at the time of our presence on site are described in **Table 2-2** below. For the sake of this report, the site boundary adjacent to Woodburn Street shall be adopted as the eastern site boundary.

Table 2-2 Summary of Local Land Use

Direction Relative to Site	Land Use Description
North	Cleveland Street a six-lane asphalt road with no parking on either side of the roadway. Cleveland Street is a TfNSW asset road. Beyond Cleveland Street are two to three-storey commercial and residential buildings, and a basement car park was noted for the residential apartment building.
West	Eveleigh Street a single lane asphalt road with a dedicated timed parking lane along the western boundary of the site. The road is one way with traffic able to travel south to north. Beyond Eveleigh Street is a three storey residential apartment building with at least one basement level, the building is offset from the site boundary by approximately 10.0m
South	13-31 Eveleigh Street a three storey commercial building of brick construction, with no apparent basement levels. The building abuts the site boundary. 9 Woodburn Street a two storey residential dwelling of brick rendered construction. The dwelling abuts the site boundary. 10 Woodburn Street a two storey residential dwelling of brick rendered construction with a common wall with 9 Woodburn Street. The building is offset approximately 4.5m from the site boundary.
East	Woodburn Street is a two lane asphalt road with a dedicated parking lane on the eastern side of the road. Woodburn Street is a “no through road”. Beyond Woodburn Street is a retaining wall, set back about 8m from the site that is approximately 1.2m high, which leads into a rail corridor. The rail corridor adjoins Redfern and Central Station and the closest track lies about 12m from the closest site boundary. An overhead wire gantry is located approximately 8.5m from the site. Additionally a mix use (residential and commercial) building is located to the north east of the site, which is three-storey high, with a partially underground car park.

2.3 Regional Setting

The site topography and geological information for the locality is summarised in **Table 2-3** below.

Table 2-3 Topographic and Geological Information

Attribute	Description
Topography	The site is located on the low south side of Cleveland Street within gently (3° to 5°), southwest dipping topography.
Regional Geology	Information on regional sub-surface conditions, referenced from the Department of Mineral Resources Geological Map Sydney 1:100,000 Geological Series Sheet 9130 (DMR 1983) indicates the site to be underlain by Ashfield Shale, which consists of black to dark grey shale and laminite. It should be noted that the site lies close to a geological boundary with Cainozoic Holocene material (Qhd) which comprises medium to fine grained “marine” sands with podsols to north and a Dyke is located approximately 70m to the south of the site.




Plate 2: Excerpt of geological map showing location of site.

3. Investigation Results

3.1 Stratigraphy

For the development of a site-specific geotechnical model, the stratigraphy observed in the GI has been grouped into four geotechnical units. A summary of the subsurface conditions across the site, interpreted from the assessment results, is presented in **Table 3-1** below. More detailed descriptions of subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**. The details of the methods of soil and rock classifications, explanatory notes and abbreviations adopted on the borehole logs are also presented in **Appendix A**.

Table 3-1 Summary of Subsurface Conditions

Unit	Material ²	Depth to Top of Unit (m BEGL) ¹	RL of Top of Unit (m AHD) ¹	Observed Thickness (m)	Comments
1	Fill	Surface	17.4 to 22.2	0.5 to 1.3	Concrete pavements of 100mm to 350mm thickness, underlain by gravelly sands, sand and silty clay. DCP's within this material range in value from 0 to 11 indicating that the material is poorly compacted. Fill was not encountered in BH1, BH3, BH202M beneath the pavements.
2	Residual Soil	0.2 to 1.3	16.1 to 21.6	3.9 to 8.32	Silty and sandy clay low to medium plasticity, of firm to hard consistency, grading in to extremely weathered shale with depth. DCP within this material range from 2 to refusal, and SPT values of 8 to 30. Bands of very low strength shale and ironstone was encountered in the boreholes.
3	Very Low to Low Strength Shale / Sandstone	4.2 to 9.32	10.5 to 17.7	0.12 to 2.6	Distinctly weathered, very low to low strength shale and sandstone. The core consists of closely spaced defects including gentle to steep joints, sub-horizontal bedding partings, and fractured/decomposed zones. core loss was observed in boreholes between 50mm to 920mm thickness, which are inferred to be zones of extremely weathered or highly fractured rock.
4	Medium to High Strength Shale / Sandstone	6.22 to 10.05	10.05 to 15.42	- ³	Slightly weathered to fresh sandstone/shale of medium to high strength sandstone. The sandstone/shale generally consisted of moderately spaced defects consisting of gentle to sub-vertical joints, sub-horizontal bedding partings, and fractured/decomposed seams.

Note 1 Approximate depth and level at the time of our assessment. Depths and levels may vary across the site.

Note 2 For more detailed descriptions of the subsurface conditions, reference should be made to the borehole logs attached to **Appendix A**.

Note 3 Observed up to termination depth in all boreholes.

3.2 Groundwater Observations

Following completion of auger drilling, the boreholes were left open and free standing groundwater levels were then measured within the boreholes after a period of time. No groundwater or significant seepage was observed during or after auger drilling of the boreholes.

Groundwater monitoring wells were installed in the location of BH2M, BH3M, BH201M and BH202M. However, water circulation due to coring within the boreholes prevented further observations of groundwater levels within the wells.

A return visit for groundwater monitoring in borehole BH2M was conducted on 13 October 2021 and 29 June 2022. A summary of the encountered groundwater upon the return visit is summarised below in **Table 3-2** below. Additionally, groundwater data from geo-environmental (GE) engineering report has also been included and measured during our site works.

Table 3-2 Groundwater Levels

Borehole ID	Measurement Date	Depth to Groundwater (m BEGL)	Groundwater RL (m AHD)
GE BH1	1/5/2014	4.20	18.6
GE BH1	29/6/2022	4.20	18.6
GE BH3	1/5/2014	4.15	18.25
BH2M	13/10/2019	3.95	16.45
BH2M	29/6/2022	4.30	16.1
BH201M	8/7/2022	1.5	15.9
BH202M	8/7/2022	2.7	18.1

3.3 Test Results

Three soil samples were selected for laboratory testing to assess the following:

- Atterberg Limits and Linear Shrinkage
- Soil aggressivity (pH, chloride and sulfate content and electrical conductivity).
- Moisture Content.

A summary of the soil test results is provided in **Table 3-2** below. Laboratory test certificates are presented in **Appendix B**.

Table 3-3 Summary of Soil Laboratory Test Results

Test/ Sample ID		BH2M_1.5- 1.95	BH3M_3.0- 3.45	BH3M_4.5- 4.95	BH201M_1.4 -1.5	BH202M_1.1-1.2	BH202M_1.5-1.6
Unit		2	2	2	2	2	2
Material Description ¹		Silty Clay	Silty Clay	Silty Clay	Silty Clay	Silty Clay	Silty Clay
Aggressivity	Chloride Cl (ppm)	12	-	22	22	14	-
	Sulfate SO ₄ (ppm)	66	-	58	590	140	-
	pH	7.5	-	6.0	6.8	5.1	-
	Electrical Conductivity (μS/cm)	160	-	44	390	140	-
Moisture Content (%)		14.3	16.1	15.1	14	15.3	23.6
Atterberg Limits	Liquid Limit (%)	-	44	-	-	-	42
	Plastic Limit (%)	-	21	-	-	-	15
	Plasticity Index (%)	-	23	-	-	-	27
	Linear Shrinkage (%)	-	11	-	-	-	12.5

Note 1 More detailed descriptions of the subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**.

The Atterberg Limits result on the selected clay samples indicated clays to be of medium plasticity and of moderate shrink-swell potential.

The assessment indicated low permeability soil was present above the groundwater table. In accordance with Tables 6.4.2(C) and 6.5.2(C) of AS 2159:2009 'Piling – Design and Installation', the results of the pH, chloride and sulfate content and electrical conductivity of the soil provided the following exposure classifications:

- 'Mild' for buried concrete structural elements; and
- 'Non-Aggressive' for buried steel structural elements.

29 selected rock core samples were tested by STS to estimate the Point Load Strength Index (I_{s50}) values to assist with rock strength assessment. The results of the testing are summarised on the attached borehole logs.

The point load strength index tests correlated reasonably well with our field assessments of rock strength. The approximate Unconfined Compressive Strength (UCS) of the rock core, estimated from correlations with the point load strength index test results, varied from <1 MPa to 44 MPa.

4. Recommendations

4.1 Geotechnical Issues

Based on the results of the assessment, we consider the following to be the main geotechnical issues for the proposed development:

- Basement excavation and retention to limit lateral deflections and ground loss as a result of excavations, resulting in damage to nearby structures;
- Deepening of existing basement in south-eastern portion of the site.
- Rock excavation;
- Foundation design for building loads.

4.2 Dilapidation Surveys

Prior to excavation and construction, we recommend that detailed dilapidation surveys be carried out on all structures and infrastructures surrounding the site that falls within the zone of influence of the excavation to allow assessment of the recommended vibration limits and protect the client against spurious claims of damage. The zone of influence of the excavation is defined by a distance back from the excavation perimeter of twice the total depth of the excavation. The reports would provide a record of existing conditions prior to commencement of the work. A copy of each report should be provided to the adjoining property owner who should be asked to confirm that it represents a fair assessment of existing conditions. The reports should be carefully reviewed prior to demolition and construction.

4.3 Excavation Methodology

4.3.1 Excavation Assessment

Prior to any excavation commencing, we recommend that reference be made to the Safe Work NSW Excavation Work Code of Practice, dated January 2020.

EI assumes that the proposed development will require a BEL of RL 15.8m for the basement, or an excavation depth of about 1.6m to 7.1m BEGL. Locally deeper excavations for footings, service trenches, crane pads and lifts overrun pits may be required.

Based on the borehole logs, the proposed basement excavations will therefore extend through Units 1, 2 and possibly Unit 3 as outlined in **Table 3-1** above. As such, an engineered retention system must be installed prior to excavation commencing.

Units 1 and 2 (and 3 if encountered) could be excavated using buckets of large earthmoving Hydraulic Excavators, particularly if fitted with 'Tiger Teeth'. Should rock hammers be required for the excavation of the high strength bedrock, further advice should be sought from EI regarding vibration mitigation and monitoring.

Groundwater seepage monitoring should be carried out during bulk excavation works and prior to finalising the design of a pump out facility. Outlets into the stormwater system will require Council approval.

Furthermore, any existing buried services, which run below the site, will require diversion prior to the commencement of excavation or alternatively be temporarily supported during excavation, subject to permission or other instructions from the relevant service authorities.

Enquiries should also be made for further information and details, such as invert levels, on the buried services.

4.3.2 Excavation Monitoring

Consideration should be made to the impact of the proposed development upon neighbouring structures, roadways and services. Basement excavation retention systems should be designed so as to limit lateral deflections.

Contractors should also consider the following limits associated with carrying out excavation and construction activities:

- Limit lateral deflection of temporary or permanent retaining structures;
- Limit vertical settlements of ground surface at common property boundaries and services easement; and
- Limit Peak Particle Velocities (PPV) from vibrations, caused by construction equipment or excavation, experienced by any nearby structures and services.

Monitoring of deflections of retaining structures and surface settlements should be carried out by a registered surveyor at agreed points along the excavation boundaries and along existing building foundations / services/ pavements and other structures located within or near the zone of influence of the excavation. Owners of existing services adjacent to the site should be consulted to assess appropriate deflection limits for their infrastructures. Measurements should be taken in the following sequence:

- Before commencing installation of retaining structures where appropriate to determine the baseline readings. Two independent sets of measurements must be taken confirming measurement consistency;
- After installation of the retaining structures, but before commencement of excavation;
- After excavation to the first row of supports or anchors, but prior to installation of these supports or anchors;
- After excavation to any subsequent rows of supports or anchors, but prior to installation of these supports or anchors;
- After excavation to the base of the excavation;
- After de-stressing and removal of any rows of supports or anchors; and
- One month after completion of the permanent retaining structure or after three consecutive measurements not less than a week apart showing no further movements, whichever is the latter.

4.4 Groundwater Considerations

Groundwater was encountered as detailed in **Table 3-2**, which are both above or just below the BEL. EI recommends that long-term monitoring and a pump out test are conducted to assess the expected seepage during construction and the long-term.

Based on the encountered subsurface conditions, due to the low permeability of the soil and bedrock profile any groundwater inflows into the excavation should not have an adverse impact on the proposed development or on the neighbouring sites and should be manageable. However, we expect that some groundwater inflows into the excavation along the soil/rock interface and through any defects within the shale bedrock (such as jointing, and bedding planes, etc.) particularly following a period of heavy rainfall. The initial flows into the excavation

may be locally high, but would be expected to decrease considerably with time as the bedding seams/joints are drained. We recommend that monitoring of seepage be implemented during the excavation works to confirm the capacity of the drainage system.

We expect that any seepage that does occur will be able to be controlled by a conventional sump and pump system. We recommend that a sump-and-pump system be used both during construction and for permanent groundwater control below the basement floor slab. In the long term, drainage should be provided behind all basement retaining walls, around the perimeter of the basement and below the basement slab. The completed excavation should be inspected by the hydraulic engineer to confirm that adequate drainage has been allowed for. Drainage should be connected to the sump-and-pump system and discharging into the stormwater system. The permanent groundwater control system should take into account any possible soluble substances in the groundwater which may dictate whether or not groundwater can be pumped into the stormwater system.

The design of drainage and pump systems should take the above issues into account along with careful ongoing inspections and maintenance programs.

4.5 Excavation Retention

4.5.1 Support Systems

From a geotechnical perspective, it is critical to maintain the stability of all adjacent structures and infrastructures during demolition, excavation and construction works.

Based on the provided architectural plans, the proposed basement outline abuts all boundaries and has a maximum setback 21.4m from the western boundary.

Based on the above, the encountered subsurface conditions, the depth of excavation, temporary batters of no steeper than a safe angle of 1 Vertical (V) to 1 Horizontal (H) may be feasible in the central portion of the western boundary of the proposed basement, where the offsets to the boundary is larger, which allows space allows for the fill and residual soil profile. The above temporary batters should remain stable provided that all surcharge loads, including construction loads, are kept at a distance of at least $2h$ (where 'h' is the height of the batter in metres) from the crest of the batter. If steeper batters are to be used, then these must be supported by shotcrete and soil nail system designed by a suitable structural or geotechnical engineer. The stability of these batters can be assessed using computer slope stability analysis software such as Slope/W. we can complete such analysis, if commissioned to do so.

Where batters are used, the space between the batters and the permanent retaining walls will need to be carefully backfilled to reduce future settlement of the backfill. Only light compaction equipment should be used for compaction behind retaining walls so that excessive lateral pressures are not placed on the walls. This will require the backfill to be placed in thin layers, say 100mm loose thickness, appropriate to the compaction equipment being used. The compaction specification for the backfill will depend on whether paving or structures are to be supported on the fill. If the fill is to support paved areas it should be compacted to a density of at least 98% of Standard Maximum Dry Density (SMDD) for granular fill materials, but if it is only to support landscaped areas of lower compaction specification, say 95% of SMDD, may be appropriate, provided the risk of future settlement and maintenance can be accepted. An alternative for backfill would also be to use a uniform granular material, wrapped in a geofabric.

Where space for temporary batters is not available, a suitable retention system will be required for the support of the entire depth of the excavation. For this site, we consider that an anchored and/or propped soldier pile wall with mass concrete in between the piles installed to below BEL to be the most suitable. Anchors/props and shotcrete panels must be installed progressively as excavation proceeds.

Due to the presence of the basement structures adjacent to the site, anchors installation may not be possible and internal props may be required. Details of nearby basements, shoring pile walls and anchors must be obtained prior to final design.

EI also notes the presence of the existing basement walls in the south-eastern portion of the site. Whether the boundary walls along the southern and eastern boundaries are being retained or replaced, these walls must be assessed by a structural engineer and possible internal bracing or anchors may be required for additional lateral restraint prior to demolition of the ground floor slab. Removal or replacement of the existing retaining wall should be completed with a set sequence, say in a hit-one-miss-three sequence, and EI can provide further comment and geotechnical advice.

Bored piles are considered to be the most suitable for this site. Tremie pumps may be required where high groundwater seepage inflows are present during the drilling of the bored piles. However, relatively large capacity piling rigs will be required for drilling through the sandstone or shale bedrock. The proposed pile locations should take into account the presence of buried services. Further advice should be sought from prospective piling contractors who should be provided with a copy of this report.

4.5.2 Retaining Wall Design Parameters

The following parameters may be used for static design of temporary and permanent retaining walls at the subject site:

- Conventional free-standing cantilever walls which support areas where movement is of little concern (i.e. where only gardens or open areas are to be retained), may be designed using a triangular lateral earth pressure distribution and an 'active' earth pressure coefficient, K_a , as shown in **Table 4-1**;
- Cantilevered walls, where the tops of which are restrained by the floor slabs of the permanent structure or which support movement sensitive elements, should be designed using a triangular lateral earth pressure distribution and an 'at rest' earth pressure coefficient, K_o , as shown in **Table 4-1** below.
- For progressively anchored or propped walls where minor movements can be tolerated (provided there are no buried movement sensitive services), we recommend the use of a trapezoidal earth pressure distribution of $5H$ kPa for soil, where H is the retained height in meters. These pressures should be assumed to be uniform over the central 50% of the support system, tapering to nil at top and bottom;
- For progressively anchored or propped walls which support areas which are highly sensitive to movement (such as areas where movement sensitive structures or infrastructures or buried services are located in close proximity), we recommend the use of a trapezoidal earth pressure distribution of $8H$ kPa for soil, where 'H' is the retained height in meters. These pressures should be assumed to be uniform over the central 50% of the support system, tapering to nil at top and bottom;
- All surcharge loading affecting the walls (including from construction equipment, construction loads, adjacent high level footings, etc.) should be adopted in the retaining wall design as an additional surcharge using an 'at rest' earth pressure coefficient, K_o .
- The retaining walls should be designed as drained and measures are to be taken to provide complete and permanent drainage behind the walls. Strip drains protected with a non-woven geotextile fabric should be used behind the shotcrete infill panels for soldier pile walls. Alternatively, for the contiguous pile walls, weepholes comprising 20mm diameter,

slotted PVC pipes installed into holes or gaps between adjacent piles at 1.2m centres (horizontal and vertical), may be used. The embedded pipes must, however, be wrapped with a non-woven geotextile fabric (such as Bidim A34) to act as a filter against subsoil erosion;

- For piles embedded into Unit 4 or better, the allowable lateral toe resistance values outlined in **Table 4-1** below may be adopted. These values assume excavation is not carried out within the zone of influence of the wall toe and the rock does not contain adverse defects etc. The upper 0.3m depth of the socket should not be taken into account to allow for tolerance and disturbance effects during excavation.
- If temporary anchors extend beyond the site boundaries, then permission from the neighbouring properties would need to be obtained prior to installation. Also, the presence of neighbouring basements and/or services and their levels must be confirmed prior to finalising anchor design.
- Anchors should have their bond length within Unit 3 or better. For the design of anchors bonded into Unit 3 or better, the allowable bond stress value outlined in **Table 4-1** below may be used, subject to the following conditions:
 1. Anchor bond lengths of at least 3m behind the 'active' zone of the excavation (taken as a 45 degree zone above the base of the excavation) is provided;
 2. Overall stability, including anchor group interaction, is satisfied;
 3. All anchors should be proof loaded to at least 1.33 times the design working load before locked off at working load. Such proof loading is to be witnessed by an engineer independent of the anchoring contractor. We recommend that only experienced contractors be considered for anchor installation with appropriate insurances;
 4. If permanent anchors are to be used, these must have appropriate corrosion provisions for longevity.

Table 4-1 Geotechnical Design Parameters

Material ¹		Unit 1 Fill	Unit 2 Residual Soil	Unit 3 Very Low To Low Strength Shale	Unit 4 Medium to High Strength Shale/ Sandstone
RL of Top of Unit (m AHD) ²		17.4 to 22.2	16.1 to 21.6	10.5 to 17.7	10.05 to 15.42
Bulk Unit Weight (kN/m ³)		20	19	24	24
Friction Angle, ϕ' (°)		30	27	35	40
Earth Pressure Coefficients	At rest, K_o ³	0.5	0.55	0.43	-
	Active, K_a ³	0.33	0.38	0.27	-
	Passive, K_p ³	-	2.66	3.69	-
Allowable Bearing Pressure (kPa) ⁵		-	-	700	3000
Allowable Shaft Adhesion (kPa) ^{4, 5}	in Compression	-	-	70	300
	in Uplift	-	-	35	150
Allowable Toe Resistance (kPa)		-	-	-	300
Allowable Bond Stress (kPa)		-	-	50	250
Earthquake Site Risk Classification		<ul style="list-style-type: none"> AS 1170.4:2007 indicates an earthquake subsoil class of Class C_e (Shallow Soil) AS 1170.4:2007 indicates that the hazard factor (z) for Sydney is 0.09. 			

Notes:

- 1 More detailed descriptions of subsurface conditions are available on the borehole logs presented in **Appendix A**.
- 2 Earth pressures are provided on the assumption that the ground behind the retaining walls is horizontal.
- 3 Side adhesion values given assume there is intimate contact between the pile and foundation material and should achieve a clean socket roughness category R2 or better. Design engineer to check both 'piston pull-out' and 'cone liftout' mechanics in accordance with AS4678-2002 Earth Retaining Structures.
- 4 To adopt these parameters we have assumed that:
 - Footings have a nominal socket of at least 0.3m, into the relevant founding material;
 - For piles, there is intimate contact between the pile and foundation material (a clean socket roughness category of R2 or better);
 - Potential soil and groundwater aggressivity will be considered in the design of piles and footings;
 - Piles should be drilled in the presence of a Geotechnical Engineer prior to pile construction to verify that ground conditions meet design assumptions. Where groundwater ingress is encountered during pile excavation, concrete is to be placed as soon as possible upon completion of pile excavation. Pile excavations should be pumped dry of water prior to pouring concrete, or alternatively a tremmie system could be used;
 - The bases of all pile, pad and strip footing excavations are cleaned of loose and softened material and water is pumped out prior to placement of concrete;
 - The concrete is poured on the same day as drilling, inspection and cleaning.
 - The allowable bearing pressures given above are based on serviceability criteria of settlements at the footing base/pile toe of less than or equal to 1% of the minimum footing dimension (or pile diameter).

4.6 Foundations

Upon reaching the BEL of the basement, it is expected that Unit 2 will be exposed at this level.

In view of the expected loads and moderate depths to the bedrock, we recommend that building is supported on pile footings founded into Unit 4 (Medium to High Strength bedrock).

For piles founded Unit 4 bedrock, these must be embedded a minimum of 0.5m, and can be designed for a maximum allowable bearing pressure of 3000kPa. The allowable shaft adhesion in Unit 4 bedrock may be designed as 10% of the allowable bearing pressure (or 5% for uplift) for the socket length in excess of 0.5m.

At least the initial drilling of piles should be completed in the presence of a geotechnical engineer to verify that ground conditions meet design assumptions.

Where groundwater ingress is encountered during pile excavation, concrete is to be placed as soon as possible upon completion of pile excavation. Pile excavations should be pumped dry of water prior to pouring concrete, or alternatively a tremmie system could be used. Concrete must be poured on the same day as drilling, inspection and drilling.

The aggressivity of natural soils and groundwater (if encountered) should be taken into consideration in the design.

4.7 Basement Floor Slab

Following bulk excavations for the proposed basement, residual soil is expected to be exposed at the basement floor BEL.

Following the removal of all loose and softened materials, we recommend that underfloor drainage be provided and should comprise a strong, durable, single sized washed aggregate such as 'blue metal gravel'. Joints in the concrete floor slab should be designed to accommodate shear forces but not bending moments by using dowelled and keyed joints. The basement floor slab should be isolated from columns. The completed excavation should be inspected by the hydraulic engineer to confirm the extent of the drainage required.

In addition, a system of sub-soil drains comprising a durable single sized aggregate with perforated drains/pipes leading to sumps should be provided. The basement floor slab should be isolated from columns.

Permission may need to be obtained from the NSW Department of Primary Industries (DPI) and possibly Council for any permanent discharge of seepage into the drainage system. Given the subsurface conditions, we expect that seepage volumes would be low and within the DPI limits. However, if permission for discharge is not obtained, the basement may need to be designed as a tanked basement.

5. Further Geotechnical Inputs

Below is a summary of the previously recommended additional work that needs to be carried out:

- Long term groundwater monitoring and seepage modelling;
- Stability assessment of temporary batters using computer modelling, if required;
- Dilapidation surveys;
- Classification of all excavated material transported off site;
- Witnessing installation of support measures and proof-testing of anchors (if required).
- Geotechnical inspections of all new footings/piles by an experienced geotechnical professional before concrete or steel are placed to verify their bearing capacity and the in-situ nature of the founding strata; and
- Ongoing monitoring of groundwater inflows into the bulk excavation;

We recommend that a meeting be held after initial structural design has been completed to confirm that our recommendations have been correctly interpreted. We also recommend a meeting at the commencement of construction to discuss the primary geotechnical issues and inspection requirements.

6. Statement of Limitations

This report has been prepared for the exclusive use of James McBride and YPI2B Ownership Trust No 6 who is the only intended beneficiary of EI's work. The scope of the assessment carried out for the purpose of this report is limited to those agreed with James McBride and YPI2B Ownership Trust No 6

No other party should rely on the document without the prior written consent of EI, and EI undertakes no duty, or accepts any responsibility or liability, to any third party who purports to rely upon this document without EI's approval.

EI has used a degree of care and skill ordinarily exercised in similar investigations by reputable members of the geotechnical industry in Australia as at the date of this document. No other warranty, expressed or implied, is made or intended. Each section of this report must be read in conjunction with the whole of this report, including its appendices and attachments.

The conclusions presented in this report are based on a limited investigation of conditions, with specific sampling and test locations chosen to be as representative as possible under the given circumstances.

EI's professional opinions are reasonable and based on its professional judgment, experience, training and results from analytical data. EI may also have relied upon information provided by the Client and other third parties to prepare this document, some of which may not have been verified by EI.

EI's professional opinions contained in this document are subject to modification if additional information is obtained through further investigation, observations, or validation testing and analysis during construction. In some cases, further testing and analysis may be required, which may result in a further report with different conclusions.

We draw your attention to the document "Important Information", which is included in **Appendix C** of this report. The statements presented in this document are intended to advise you of what your realistic expectations of this report should be. The document is not intended to reduce the level of responsibility accepted by EI, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in so doing.

Should you have any queries regarding this report, please do not hesitate to contact EI.

References

- AS1289.6.3.1:2004, *Methods of Testing Soils for Engineering Purposes*, Standards Australia.
- AS1726:2017, *Geotechnical Site Investigations*, Standards Australia.
- AS2159:2009, *Piling – Design and Installation*, Standards Australia.
- AS3600:2009, *Concrete Structures*, Standards Australia
- Safe Work NSW Excavation Work Code of Practice, dated January 2020 – WorkCover NSW
- NSW Department of Finance and Service, Spatial Information Viewer, maps.six.nsw.gov.au.
- NSW Department of Mineral Resources (1983) Sydney 1:100,000 Geological Series Sheet 9130 (Edition 1). Geological Survey of New South Wales, Department of Mineral Resources.


Abbreviations


AHD	Australian Height Datum
AS	Australian Standard
BEL	Bulk Excavation Level
B EGL	Below Existing Ground Level
BH	Borehole
DBYD	Dial Before You Dig
DP	Deposited Plan
EI	EI Australia
GI	Geotechnical Investigation
NATA	National Association of Testing Authorities, Australia
RL	Reduced Level
SPT	Standard Penetration Test
T-C	Tungsten-Carbide
UCS	Unconfined Compressive Strength

Figures

Figure 1 Site Locality Plan

Figure 2 Borehole Location Plan





LEGEND (All Locations are Approximate)

- Site boundary
- Basement boundary
- Borehole locations
- Monitoring Well Borehole locations
- Test Pit locations



Contamination | Remediation | Geotechnical
Suite 6.01, 55 Miller Street, PYRMONT 2009
Ph (02) 9516 0722 Fax (02) 9518 5088

Drawn:	J.O.
Approved:	X.X
Date:	25-07-22

YP12B Ownership Trust No 6
Geotechnical Investigation
6-8 Woodburn Street, Redfern, NSW
Borehole Location Plan

Figure:

2

Project: E25342.G03

Appendix A – Borehole Logs And Explanatory Notes

Project	Boarding House Development										Sheet	1 of 2	
Location	6-8 Woodburn Street, Redfern NSW										Date Started	05/10/2021	
Position	Refer to Figure 2										Date Completed	05/10/2021	
Job No.	E25342.G03										Logged By	DS	Date 05/10/2021
Client	YPI2B Ownership Trust No 6										Reviewed By	SK	Date 01/08/2022
Drilling Contractor		BG Drilling					Surface RL		≈17.40 m AHD				
Drill Rig		Hand Portable Rig					Inclination		-90°				
Drilling				Sampling			Field Material Description						
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	GROUP SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION		MOISTURE CONDITION	CONSISTENCY REL. DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
DT	-		0	17.40 0.23 17.17				-	CONCRETE: 230mm.	-	-	PAVEMENT	
AD/T	-	GWNE			BH1 0.30-0.40 m			CI	Silty CLAY: medium plasticity, pale grey and red-brown.	M (<PL)	S - F St	RESIDUAL	
			1	1.00	BH1 0.90-1.00 m				Continued as Cored Borehole		VSt		
			2										
			3										
			4										
			5										
			6										
			7										
			8										
			9										
			10										

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH1

Project	Boarding House Development	Sheet	2 OF 2
Location	6-8 Woodburn Street, Redfern NSW	Date Started	05/10/2021
Position	Refer to Figure 2	Date Completed	05/10/2021
Job No.	E25342.G03	Logged By DS	Date 05/10/2021
Client	YPI2B Ownership Trust No 6	Reviewed By SK	Date 01/08/2022

Drilling Contractor	BG Drilling	Surface RL	≈17.40 m AHD
Drill Rig	Hand Portable Rig	Inclination	-90°

Drilling					Field Material Description				Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations		Average Defect Spacing (mm)
									$V_{0.1}$ $M_{0.3}$ H_1 $V_{0.3}$ E_{10}			30 100 300 1000 3000
NMLC	80% RETURN				0							
					1	1.00 16.40		Continuation from non-cored borehole CORE LOSS: 920mm.				
		33	0		2	1.92 15.48		Silty CLAY: medium plasticity, pale grey/orange-brown.	RS			
						2.37						
		88	0			14.98		CORE LOSS: 50mm. Silty CLAY: medium plasticity, pale grey/orange-brown.	RS			
						2.80 2.93		CORE LOSS: 130mm.				
		90	0		3	14.47		Silty CLAY; medium plasticity, grey with iron stone bands (EXTREMELY WEATHERED)	XW	2.95-3.04: XWS, 90 mm 3.09-3.14: XWS, 50 mm 3.16: JT, 45°, Fe SN, IR, RO 3.21-3.29: XWS, 80 mm 3.34-3.62: XWZ, 280 mm 3.53: JT, 30°, Clay VNR, IR, RO 3.64: JT, 15°, Fe SN, PL, RO		
					4	4.20				3.83-3.85: XWS, 20 mm 3.93-4.03: XWZ, 100 mm 4.05-4.10: XWS, 50 mm 4.13: JT, 60°, Fe SN, IR, RO 4.13-4.14: XWS, 10 mm 4.17-4.31: XWZ, 140 mm		
		75	0			4.38 13.02		SHALE: pale grey and red, thinly bedded, with iron stained bands.	DW			
						4.64		CORE LOSS: 260mm.				
						12.76		SHALE: dark grey/ red-brown, very thinly bedded with sub-horizontal siltstone laminations and ironstaining.	XW DW	4.64-4.73: XWS, 90 mm 4.78: JT, 30°, Fe SN, PL, RO 4.86-5.08: XWZ, 220 mm		
					5	5.08 12.32		CORE LOSS: 440mm.				
						5.52						
		60	0			11.88		SHALE: dark grey/ red-brown, very thinly bedded with sub-horizontal siltstone laminations and ironstaining.	DW	5.52-5.72: XWZ, 200 mm		
					6					5.77: JT, 75°, PL 5.80-5.82: XWS, 20 mm 5.93-5.95: XWS, 20 mm 6.12-6.17: XWS, 50 mm 6.18-6.22: XWS, 40 mm 6.24: JT, 30 - 40°, Fe SN, CU, RO		
						6.49		CORE LOSS: 100mm.	SW			
		92	44			10.81 6.80 10.60		SANDSTONE: fine-grained, pale grey, laminated. From 6.80m, thickly to medium bedded.	DW FR	6.61-6.67: XWZ, 60 mm		
				7								
					7.43 9.97		Hole Terminated at 7.43 m Target Depth Reached.					
				8								
				9								

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

DYNAMIC CONE PENETROMETER TEST RESULTS


DCP NO. BH1

Project Boarding House Development
Location 6-8 Woodburn Street, Redfern NSW
Position Refer to Figure 2
Job No. E25342.G03
Client YPI2B Ownership Trust No 6

Sheet 1 of 3
Date Started 05/10/2021
Date Completed 05/10/2021
Logged By DS **Date** 05/10/2021
Reviewed By SK **Date** 01/08/2022

Drilling Contractor BG Drilling **Surface RL** ≈17.40 m AHD
Drill Rig Hand Portable **Inclination** -90°

DEPTH (m)	NO OF BLOWS PER 100 mm
0.20-0.3	1 / 200 mm.
0.30-0.4	0
0.40-0.5	2
0.50-0.6	4
0.60-0.7	4
0.70-0.8	3
0.80-0.9	6
0.90-1	11
1.00-1.1	10
1.10-1.2	12
1.20-1.3	16
1.30-1.4	20
1.40-1.5	23
1.50-1.59	25 / 90 mm HB.




Termination Remark
Target Depth Reached.

Final Depth (m)

1.59

CORE PHOTOGRAPH OF BOREHOLE: BH1

Project	Proposed Boarding House Development	Depth Range	1.0m to 7.43m BEGL	
Location	175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW	Contractor	BG Drilling	
Position	See Figure 2	Drill Rig	Hand Portable Rig	
Job No.	E25342.G03	Logged	DS	Date 5 / 10 / 2021
Client	YPI2B Ownership Trust No 6	Box	1 & 2 of 2	Checked SK Date 2 / 8 / 2022
		Surface RL	≈ 17.40m	
		Inclination	-90°	



Project		Boarding House Development					Sheet		1 of 3				
Location		6-8 Woodburn Street, Redfern NSW					Date Started		05/10/2021				
Position		Refer to Figure 2					Date Completed		05/10/2021				
Job No.		E25342.G03					Logged By		DS				
Client		YPI2B Ownership Trust No 6					Date		05/10/2021				
							Reviewed By		SK				
							Date		01/08/2022				
Drilling Contractor		BG Drilling			Surface RL		≈20.40 m AHD						
Drill Rig		Rig CE 180			Inclination		-90°						
Drilling		Sampling			Field Material Description								
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	GROUP SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION		MOISTURE CONDITION	CONSISTENCY REL. DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
DT	-		0	0.19				-	CONCRETE: 190mm.	-			PAVEMENT
				0.35				-	BRICK: 360mm.	-			BRICK
			20.05					-	FILL: SAND: fine to coarse-grained, dark.	-			FILL
				1.00	BH2M 0.50-0.60 m								
			1	19.40	BH2M 1.10-1.20 m			CI	Sandy CLAY: medium plasticity, pale grey mottled orange brown, sand is fine to medium-grained.				RESIDUAL
					SPT 1.50-1.95 m 3,4,5 N=9					M (<PL)	St		
			2										
				2.40				CI	Silty CLAY: medium plasticity, pale grey/red-brown with fine to medium ironstone gravels.				
			3	18.00									
					SPT 3.00-3.45 m 4,7,10 N=17								
				3.50					From 3.50m, less ironstone gravels.				
			4	16.90							VSt		
					SPT 4.50-4.95 m 5,11,15 N=26								
			5										
				6.00					From 6.0m, grading to extremely weathered shale.	M (<PL)			
			6	14.40	SPT 6.00-6.45 m 11,13,17 N=30								
			7										
											H		
			8										
				9.00									
			9						Continued as Cored Borehole				
			10										

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH2M

Project	Boarding House Development	Sheet	3 OF 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	05/10/2021
Position	Refer to Figure 2	Date Completed	05/10/2021
Job No.	E25342.G03	Logged By DS	Date 05/10/2021
Client	YPI2B Ownership Trust No 6	Reviewed By SK	Date 01/08/2022

Drilling Contractor	BG Drilling	Surface RL	≈20.40 m AHD
Drill Rig	Rig CE 180	Inclination	-90°

Drilling				Field Material Description				Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations	Average Defect Spacing (mm)
								VL L L M H H VH ¹⁰ EH			20 100 300 1000 3000
NMLC	90-95% RETURN	79	26	10	10.99		SANDSTONE: fine to medium-grained, grey, very thinly to thinly bedded, with pale orange-brown ironstaining and dark grey sub horizontal siltstone laminations. From 10.38m, no iron staining.	SW		9.99-10.05: XWS, 60 mm	
				10.38	10.02					10.73-10.76: XWS, 30 mm	
90-95% RETURN	100	65		11			From 11.93m, medium to thickly bedded.	FR		11.02-11.07: XWS, 50 mm	
				11.93	8.47					11.31: JT, 10°, CN, IR, RO 11.38-11.44: XWS, 60 mm	
90-95% RETURN	100	96		12						11.69: JT, 45 - 80°, CN, ST, RO 11.89-11.90: XWS, 10 mm	
				13						12.26-12.27: XWS, 10 mm	
				13.52	6.88		Hole Terminated at 13.52 m Target Depth Reached.				
				14							
				15							
				16							
				17							
				18							
				19							
				20							

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH2M

Project	Boarding House Development	Sheet	2 OF 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	05/10/2021
Position	Refer to Figure 2	Date Completed	05/10/2021
Job No.	E25342.G03	Logged By	DS
Client	YPI2B Ownership Trust No 6	Date	05/10/2021
		Reviewed By	SK
		Date	01/08/2022

Drilling Contractor	BG Drilling	Surface RL	≈20.40 m AHD
Drill Rig	Rig CE 180	Inclination	-90°

Drilling						Field Material Description				Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations	Average Defect Spacing (mm)		
									VL 0.1 L 0.3 M 0.5 H 1 VH 10 EH		20 100 200 1000 3000		
				0									
				1									
				2									
				3									
				4									
				5									
				6									
				7									
				8									
				9	9.00		Continuation from non-cored borehole						
					11.40		CORE LOSS: 320mm.	-					
					9.32								
					11.08		SHALE; dark grey, very thinly laminated to laminated.	DW		9.32-9.94: XWZ, 580 mm			
				10									

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

[illegible]

CORE PHOTOGRAPH OF BOREHOLE: BH2M

Project	Proposed Boarding House Development	Depth Range	9.0m to 13.52m BEGL	
Location	175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW	Contractor	BG Drilling	
Position	See Figure 2	Drill Rig	Rig CE 180	
Job No.	E25342.G03	Logged	DS	Date 5 / 10 / 2021
Client	YPI2B Ownership Trust No 6	Inclination	-90°	Date 2 / 8 / 2022
		Box	1 & 2 of 2	
		Checked	SK	



BOREHOLE LOG

BH NO. BH3M

Project		Boarding House Development				Sheet		1 of 2	
Location		6-8 Woodburn Street, Redfern NSW				Date Started		07/11/2021	
Position		Refer to Figure 2				Date Completed		07/11/2021	
Job No.		E25342.G03				Logged By		EM	
Client		YPI2B Ownership Trust No 6				Reviewed By		SK	
Drilling Contractor		BG Drilling		Surface RL		≈17.50 m AHD			
Drill Rig		Rig CE 180		Inclination		-90°			

Drilling			Sampling		Field Material Description						
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED GRAPHIC LOG	GROUP SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY REL. DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
DT	-		0	17.50			-	CONCRETE: 240mm.	-	-	PAVEMENT
				0.24							
				17.26	BH3M 0.30-0.40 m BH3M 0.40-0.50 m		CI	Silty CLAY: medium plasticity, pale grey/red brown.			RESIDUAL
			1							St	
					SPT 1.50-1.95 m 4,8,12 N=20						
			2	2.00 15.50				From 2.0m, pale grey with angular to sub angular.			
			3		SPT 3.00-3.45 m 6,13,13 N=26				M (<PL)		
										VSt	
			4								
					SPT 4.50-4.95 m 5,13,12 N=25						
			5	5.20 12.30 5.50				From 5.20m, with very low strength, distinctly weathered shale gravel bands.			
			6					Continued as Cored Borehole			
			7								
			8								
			9								
			10								

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH3M

Project	Boarding House Development	Sheet	2 OF 2
Location	6-8 Woodburn Street, Redfern NSW	Date Started	07/11/2021
Position	Refer to Figure 2	Date Completed	07/11/2021
Job No.	E25342.G03	Logged By	EM
Client	YPI2B Ownership Trust No 6	Date	07/11/2021
		Reviewed By	SK
		Date	01/08/2022

Drilling Contractor	BG Drilling	Surface RL	≈17.50 m AHD
Drill Rig	Rig CE 180	Inclination	-90°

Drilling						Field Material Description				Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations	Average Defect Spacing (mm)		
								VL 0.1 L 0.3 M 0.5 H 1.0 VH 1.5 EH 2.0			20 100 300 1000 3000		
				0									
				1									
				2									
				3									
				4									
				5									
				5.50			Continuation from non-cored borehole						
				12.00			CORE LOSS: 600mm.						
			0	6									
			0	6.10									
				11.40			SANDSTONE: fine to coarse-grained pale grey, thinly to medium bedded with sub-horizontal dark grey siltstone laminations.	DW SW		6.14-6.22: XWS, 80 mm			
			100	7				FR		7.19-7.26: XWS, 70 mm			
				8						8.40: JT, 20°, CN, PL, RO 8.42: JT, 20°, CN, PL, RO			
			100	8									
				8.86									
				8.64			Hole Terminated at 8.86 m Target Depth Reached.						
				9									
				10									

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

[illegible]

CORE PHOTOGRAPH OF BOREHOLE: BH3M

Project	Proposed Boarding House Development	Depth Range	6.10m to 8.86m BEGL	
Location	175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW	Contractor	BG Drilling	
Position	See Figure 2	Drill Rig	Rig CE 180	
Job No.	E25342.G03	Logged	EM	Date 07 / 11 / 2021
Client	YPI2B Ownership Trust No 6	Box	1 of 1	Checked SK Date 2 / 8 / 2022
Surface RL		≈ 17.50m		
Inclination		-90°		



BOREHOLE LOG

BH NO. BH4

Project	Boarding House Development	Sheet	1 of 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	29/06/2022
Position	Refer to Figure 2	Date Completed	29/06/2022
Job No.	E25342.G03	Logged By	LL
Client	YPI2B Ownership Trust No 6	Date	29/06/2022
		Reviewed By	SK
		Date	01/08/2022

Drilling Contractor	Geosense Drilling Pty Ltd	Surface RL	≈22.20 m AHD
Drill Rig	Comacchio Geo 205	Inclination	-90°

Drilling				Sampling		Field Material Description						
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	GROUP SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY REL. DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
AD/T	VL	GWNE	0	0.10	DS 0.20-0.30 m			-	ASPHALT PAVEMENT: 100mm.	-	-	ASPHALT PAVEMENT
			22.10	FILL: Gravelly SAND; fine to coarse-grained, gravel is angular, dark grey/grey.							FILL	
			0.50	SPT 0.50-0.95 m 4,5,7 N=12				-	M	-		
			21.70									From 0.50m, pale grey.
			1	1.20	SPT 1.50-1.95 m 1,3,5 N=8			CI	Silty CLAY; medium plasticity, pale grey/yellow-brown, with ironstaining.		St	RESIDUAL SOIL
			21.00									
			3	3.00	SPT 3.00-3.45 m 10,12,15 N=27				-	M (<PL)	VSt	
			19.20	From 3.0m, trace ironstone band.								
			4	4.50	SPT 4.50-4.94 m 3,15,30/140mm HB				-		-	BEDROCK
			17.70									
5		DS 5.20-5.40 m										
6	6.00	SPT 5.80-6.00 m 3,4/50mm HB										

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH4

Project	Boarding House Development	Sheet	2 OF 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	29/06/2022
Position	Refer to Figure 2	Date Completed	29/06/2022
Job No.	E25342.G03	Logged By LL	Date 29/06/2022
Client	YPI2B Ownership Trust No 6	Reviewed By SK	Date 01/08/2022

Drilling Contractor	Geosense Drilling Pty Ltd	Surface RL	≈22.20 m AHD
Drill Rig	Comacchio Geo 205	Inclination	-90°

Drilling						Field Material Description				Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH Is ₅₀ MPa	DEFECT DESCRIPTION & Additional Observations		Average Defect Spacing (mm)	
									V _{0.1} M _{0.3} H ₁ VH ₃ EH ₁₀			30 100 300 1000 3000	
				0									
				1									
				2									
				3									
				4									
				5									
				6	6.00 16.20		Continuation from non-cored borehole SHALE; dark grey, laminated.	DW		6.16: JT, 45°, CN, PL, RO			
	95% RETURN	100	81	7	6.78 15.42		From 6.78m, thinly to medium bedded.	FR		6.57-6.70: CZ, 130mm 6.87-6.90: CS, 30mm 7.06: BP, 0°, Sand infill PL, RO 7.37-7.41: CS, 40mm 7.58: BP, 0°, Sand infill PL, RO 7.86-7.91: CS, 50mm 8.15: JT, 20°, CN, PL, RO 8.19: JT, 10°, Healed RL 8.29: JT, 10°, Healed PL			
NMLC	79% RETURN	100	85	8						8.94-9.00: CS, 60mm 9.29: JT, 10°, CN, IR, RO 9.48: JT, 85°, CN, ST, RO			
				9									
				10									

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH4

Project	Boarding House Development	Sheet	3 OF 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	29/06/2022
Position	Refer to Figure 2	Date Completed	29/06/2022
Job No.	E25342.G03	Logged By	LL Date 29/06/2022
Client	YPI2B Ownership Trust No 6	Reviewed By	SK Date 01/08/2022

Drilling Contractor	Geosense Drilling Pty Ltd	Surface RL	≈22.20 m AHD
Drill Rig	Comacchio Geo 205	Inclination	-90°

Drilling						Field Material Description		Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations	Average Defect Spacing (mm)
								VL L M H VH ¹⁰ EH			20 100 200 1000 3000
NMILC	80% RETURN	100	96	10			SHALE; dark grey, laminated.	FR		9.95: JT, 80°, CN, PL, RO 10.08-10.13: BP, 50mm 10.15: JT, 50°, CN, PL, RO	
										10.58: BP, 0°, CN, PL, RO 10.65-10.69: CS, 40mm	
				11	11.00 11.20		SANDSTONE; fine to medium-grained, pale grey, medium to thickly bedded.			10.95-11.00: XWS, 50mm Clay 11.16: BP, 50°, CN, PL, RO 11.42: JT, 50°, Healed ST 11.72-11.74: XWS, 20mm	
				12	12.40 9.80		From 12.40m, coarse-grained.				
				13						13.02: BP, 0°, PL, RL 13.03: BP, 0°, PL, RL	
				13.63	8.57		Hole Terminated at 13.63 m Target Depth Reached.				
				14							
				15							
				16							
				17							
				18							
				19							
				20							

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORE PHOTOGRAPH OF BOREHOLE: BH4

Project	Proposed Boarding House Development			Depth Range	6.0m to 13.63m BEGL		
Location	175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW			Contractor	Geosense Drilling Pty Ltd		
Position	See Figure 2	Surface RL	≈ 22.20m	Drill Rig	Comacchio Geo 205		
Job No.	E25342.G03	Inclination	-90°	Logged	LL	Date	07 / 11 / 2021
Client	YPI2B Ownership Trust No 6	Box	1 & 2 of 2	Checked	SK	Date	2 / 8 / 2022



Project	Boarding House Development				Sheet	1 of 3							
Location	6-8 Woodburn Street, Redfern NSW				Date Started	05/07/2022							
Position	Refer to Figure 2				Date Completed	08/07/2022							
Job No.	E25342.G03				Logged By	DD	Date 08/07/2022						
Client	YPI2B Ownership Trust No 6				Reviewed By	SK	Date 02/08/2022						
Drilling Contractor		Tight Site Drilling		Surface RL		≈17.40 m AHD							
Drill Rig		Hand Portable Rig		Inclination		-90°							
Drilling			Sampling		Field Material Description								
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	GROUP SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY REL. DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS	
AD/T	-	GWNE	0	17.40	DS 1.40-1.50 m DS 1.60-1.70 m DS 1.90-2.00 m			-	CONCRETE; 350mm thickness.	-	-	PAVEMENT	
			0.35	17.05				-	FILL: Silty CLAY; medium plasticity, orange-grey and red, with brick tile, concrete fragments.	M (=PL)	-	FILL	
			1	1.30				16.10	CI	Silty CLAY; medium plasticity, red-grey, trace fine to medium shale gravel.	M (<PL)	St	RESIDUAL SOIL
			2	2.12									
			3										
			4										
			5										
			6										
			7										
			8										
			9										
			10										

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH201M

Project	Boarding House Development	Sheet	2 OF 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	05/07/2022
Position	Refer to Figure 2	Date Completed	08/07/2022
Job No.	E25342.G03	Logged By DD	Date 08/07/2022
Client	YPI2B Ownership Trust No 6	Reviewed By SK	Date 02/08/2022

Drilling Contractor	Tight Site Drilling	Surface RL	≈17.40 m AHD
Drill Rig	Hand Portable Rig	Inclination	-90°

Drilling						Field Material Description				Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations		Average Defect Spacing (mm)	
									VL 0.1 L 0.3 M 0.5 H 1 VH 10 EH			20 100 200 1000 3000	
				0									
				1									
				2	2.12		Continuation from non-cored borehole						
				15.28			Silty CLAY; medium plasticity, red-grey, trace fine to medium-grained Siltstone gravel.	RS					
		100	100	3									
		68	68	4									
				5	5.30		From 5.30m, iron stained shale bands (EXTREMELY WEATHERED SHALE)	XW			5.83: JT, 10°, PR, RO, CN		
		100	38	6	12.10								
				7	6.95		SANDSTONE; fine to medium-grained, orange-grey, thinly bedded.	DW			7.17: JT, 90°, PR, CN		
				10.45									
				7.35			From 7.35m, grey.	SW					
				10.05									
		100	63	8									
				8.60			From 8.60m, coarse-grained, medium to thickly bedded.	FR			8.42-8.43: XWS, 10mm		
				8.80									
		98	89	9									
				10									

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

Project	Boarding House Development				Sheet	3 OF 3					
Location	6-8 Woodburn Street, Redfern NSW				Date Started	05/07/2022					
Position	Refer to Figure 2				Date Completed	08/07/2022					
Job No.	E25342.G03				Logged By	DD	Date 08/07/2022				
Client	YPI2B Ownership Trust No 6				Reviewed By	SK	Date 02/08/2022				
Drilling Contractor		Tight Site Drilling		Surface RL		≈17.40 m AHD					
Drill Rig		Hand Portable Rig		Inclination		-90°					
Drilling				Field Material Description			Defect Information				
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH IS ₍₅₀₎ MPa	DEFECT DESCRIPTION & Additional Observations	Average Defect Spacing (mm)
								V _{0.1} L _{0.3} L _{0.5} L ₁ L ₃ L ₁₀			30 100 300 1000 3000
		98	89	10	10.22 7.18			FR			
							Hole Terminated at 10.22 m Target Depth Reached.				
				11							
				12							
				13							
				14							
				15							
				16							
				17							
				18							
				19							
				20							

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

MONITORING WELL LOG

MW NO. BH201M



Project Boarding House Development
Location 6-8 Woodburn Street, Redfern NSW
Position Refer to Figure 2
Job No. E25342.G03
Client YPI2B Ownership Trust No 6

Sheet 1 of 2
Date Started 05/07/2022
Date Completed 08/07/2022
Logged By DD **Date** 08/07/2022
Reviewed By SK **Date** 02/08/2022

Drilling Contractor Tight Site Drilling **Surface RL** ≈17.40 m AHD
Drill Rig Hand Portable Rig **Inclination** -90°

PIEZOMETER CONSTRUCTION DETAILS

ID Type Stick Up & RL Tip Depth & RL Installation Date Static Water Level
BH201M Standpipe Piezometer 0.00 m 17.40 m 3.30 m 14.10 m 08/07/2022



This well log should be read in conjunction with EI Australia's accompanying standard notes.

CORE PHOTOGRAPH OF BOREHOLE: BH201M

Project	Proposed Boarding House Development	Depth Range	2.12m to 10.22m BEGL	
Location	175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW	Contractor	Tight Site Drilling	
Position	See Figure 2	Drill Rig	Hand Portable Rig	
Job No.	E25342.G03	Logged	DD	Date 07 / 07 / 2022
Client	YPI2B Ownership Trust No 6	Inclination	-90°	Date 2 / 8 / 2022
		Box	1 & 2 of 2	
		Checked	SK	



BOREHOLE LOG

BH NO. BH202M

Project	Boarding House Development	Sheet	1 of 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	06/07/2022
Position	Refer to Figure 2	Date Completed	08/07/2022
Job No.	E25342.G03	Logged By	DD
Client	YPI2B Ownership Trust No 6	Date	08/07/2022
		Reviewed By	SK
		Date	02/08/2022

Drilling Contractor	Tight Site Drilling	Surface RL	≈20.80 m AHD
Drill Rig	Hand Portable Rig	Inclination	-90°

Drilling				Sampling		Field Material Description						
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	GROUP SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY REL. DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
AD/T	-	GWNE	0	20.76	DS 0.90-1.00 m DS 1.10-1.20 m DS 1.50-1.60 m			-	TILE & GROUT; 40mm thickness.	M (=PL)	St	TILE
			-	CONCRETE; 460mm thickness.				CONCRETE				
			CI	Silty CLAY; medium plasticity, grey-brown.				RESIDUAL SOIL				
			1.71						Continued as Cored Borehole			
			2									
			3									
			4									
			5									
			6									
			7									
			8									
			9									
			10									

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH202M

Project	Boarding House Development	Sheet	2 OF 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	06/07/2022
Position	Refer to Figure 2	Date Completed	08/07/2022
Job No.	E25342.G03	Logged By DD	Date 08/07/2022
Client	YPI2B Ownership Trust No 6	Reviewed By SK	Date 02/08/2022

Drilling Contractor	Tight Site Drilling	Surface RL	≈20.80 m AHD
Drill Rig	Hand Portable Rig	Inclination	-90°

Drilling					Field Material Description				Defect Information			
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations		Average Defect Spacing (mm)
									V _{0.1} M _{0.3} H ₁ VH ₃ EH ₁₀			30 100 300 1000 3000
				0								
				1								
				1.71	19.09		Continuation from non-cored borehole					
		100	0	2			Silty CLAY; medium plasticity, orange-red and grey, trace fine-grained sand.					
				3								
		100	0	4								
				4.70	16.10		From 4.70m, with iron stained shale bands (EXTREMELY WEATHERED SHALE)	HW				
		100	0	5								
				5.87	14.93		CORELOSS; 470mm.					
		63	0	6.34	14.46		Silty CLAY; medium plasticity, grey and red, with iron stained shale bands (EXTREMELY WEATHERED SHALE)	HW				
				7								
		109	0	7.14	13.66		SHALE; grey to dark grey, very thinly bedded.	MW		7.60-7.65: CS, 50mm		
				8						8.07-8.13: CS, 60mm		
		100	0	8.93	11.87		From 8.93m, thinly bedded.	SW		8.27-8.28: CS, 10mm 8.35-8.44: CS, 90mm 8.46: JT, 80°, IR, CN 8.48-8.51: CS, 30mm 8.78: JT, 80°, IR, CN 8.85-8.91: CS, 60mm		
				9.63	11.17		SANDSTONE; fine to medium-grained, grey to pale grey, medium to thickly bedded.	FR		9.62-9.62: XWS, 2mm 9.72-9.72: XWS, 3mm		

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

CORED BOREHOLE LOG

BH NO. BH202M

Project	Boarding House Development	Sheet	3 OF 3
Location	6-8 Woodburn Street, Redfern NSW	Date Started	06/07/2022
Position	Refer to Figure 2	Date Completed	08/07/2022
Job No.	E25342.G03	Logged By DD	Date 08/07/2022
Client	YPI2B Ownership Trust No 6	Reviewed By SK	Date 02/08/2022

Drilling Contractor	Tight Site Drilling	Surface RL	≈20.80 m AHD
Drill Rig	Hand Portable Rig	Inclination	-90°

Drilling						Field Material Description				Defect Information		
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPTH RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	INFERRED STRENGTH $I_{s(50)}$ MPa	DEFECT DESCRIPTION & Additional Observations	Average Defect Spacing (mm)	
								VL 0.1 L 0.3 M 0.5 H 1 VH 10 EH			20 100 500 1000 3000	
NMLC	10% RETURN	101	95	10			SANDSTONE; fine to medium-grained, grey to pale grey, medium to thickly bedded.	FR				
	50% RETURN	100	79	11								
				12								
				13								
				13.33	7.47		Hole Terminated at 13.33 m Target Depth Reached.					
				14								
				15								
				16								
				17								
				18								
				19								
				20								

This borehole log should be read in conjunction with EI Australia's accompanying standard notes.

MONITORING WELL LOG

MW NO. BH202M


Project Boarding House Development
Location 6-8 Woodburn Street, Redfern NSW
Position Refer to Figure 2
Job No. E25342.G03
Client YPI2B Ownership Trust No 6

Sheet 1 of 2
Date Started 06/07/2022
Date Completed 08/07/2022
Logged By DD **Date** 08/07/2022
Reviewed By SK **Date** 02/08/2022

Drilling Contractor Tight Site Drilling **Surface RL** ≈20.80 m AHD
Drill Rig Hand Portable Rig **Inclination** -90°

PIEZOMETER CONSTRUCTION DETAILS

ID Type Stick Up & RL Tip Depth & RL Installation Date Static Water Level
BH202M Standpipe Piezometer 0.09 m 20.71 m 6.00 m 14.80 m 08/07/2022



This well log should be read in conjunction with EI Australia's accompanying standard notes.

CORE PHOTOGRAPH OF BOREHOLE: BH202M

Project	Proposed Boarding House Development	Depth Range	1.71m to 13.33m BEGL	
Location	175-177 Cleveland St & 6-8 Woodburn Street, Redfern, NSW	Contractor	Tight Site Drilling	
Position	See Figure 2	Drill Rig	Hand Portable Rig	
Job No.	E25342.G03	Logged	DD	Date 07 / 07 / 2022
Client	YPI2B Ownership Trust No 6	Box	1, 2 & 3 of 3	Checked SK Date 2 / 8 / 2022



DYNAMIC CONE PENETROMETER TEST RESULTS


DCP NO. TP1

Project Boarding House Development
Location 6-8 Woodburn Street, Redfern NSW
Position Refer to Figure 2
Job No. E25342.G03
Client YPI2B Ownership Trust No 6

Sheet 1 of 1
Date 07/11/2021
Logged By DS **Date** 07/11/2021
Reviewed By AC **Date** 01/08/2022

Contactors BG Drilling **Surface RL** ≈18.80 m AHD
Machine Rig CE 180 **Bucket Size**

DEPTH (m)	NO OF BLOWS PER 100 mm
0.40-0.5	0 / 1000 mm.
0.50-0.6	0
0.60-0.7	0
0.70-0.8	0
0.80-0.9	0
0.90-1	0
1.00-1.1	0
1.10-1.2	0
1.20-1.3	0
1.30-1.4	0
1.40-1.5	2
1.50-1.6	3
1.60-1.7	7
1.70-1.8	7
1.80-1.9	9
1.90-2	17
2.00-2.1	13
2.10-2.2	13
2.20-2.3	14
2.30-2.4	14
2.40-2.5	15
2.50-2.6	11
2.60-2.7	14
2.70-2.8	25 / HB (>25/100 mm)



Termination Remark
Target Depth Reached.

Final Depth (m)

2.80

DYNAMIC CONE PENETROMETER TEST RESULTS


DCP NO. TP2

Project Boarding House Development
Location 6-8 Woodburn Street, Redfern NSW
Position Refer to Figure 2
Job No. E25342.G03
Client YPI2B Ownership Trust No 6

Sheet 1 of 1
Date 07/11/2021
Logged By DS **Date** 07/11/2021
Reviewed By AC **Date** 01/08/2022

Contactor BG Drilling **Surface RL** ≈17.50 m AHD
Machine Rig CE 180 **Bucket Size**

DEPTH (m)	NO OF BLOWS PER 100 mm
0.40-0.5	2
0.50-0.6	3
0.60-0.7	5
0.70-0.8	5
0.80-0.9	8
0.90-1	8
1.00-1.1	12
1.10-1.2	14
1.20-1.3	10
1.30-1.4	10
1.40-1.5	10
1.50-1.6	14
1.60-1.7	19
1.70-1.8	18
1.80-1.89	25 / 90 mm HB.



Termination Remark
Target Depth Reached.

Final Depth (m)

1.89

DYNAMIC CONE PENETROMETER TEST RESULTS


DCP NO. TP3

Project Boarding House Development
Location 6-8 Woodburn Street, Redfern NSW
Position Refer to Figure 2
Job No. E25342.G03
Client YPI2B Ownership Trust No 6

Sheet 1 of 1
Date 07/11/2021
Logged By DS **Date** 07/11/2021
Reviewed By AC **Date** 01/08/2022

Contactor BG Drilling **Surface RL** ≈17.40 m AHD
Machine Rig CE 180 **Bucket Size**

DEPTH (m)	NO OF BLOWS PER 100 mm
0.30-0.4	2
0.40-0.5	2
0.50-0.6	5
0.60-0.7	5
0.70-0.8	5
0.80-0.9	6
0.90-1	8
1.00-1.1	6
1.10-1.2	6
1.20-1.3	5
1.30-1.4	6
1.40-1.5	5
1.50-1.6	5
1.60-1.7	8
1.70-1.8	10
1.80-1.9	12
1.90-2	17
2.00-2.1	14
2.10-2.2	14
2.20-2.3	14
2.30-2.4	13
2.40-2.5	16
2.50-2.6	16
2.60-2.7	14
2.70-2.8	17
2.80-2.9	16
2.90-3	17 / Terminated.



Termination Remark
Target Depth Reached.

Final Depth (m)

3.00

DYNAMIC CONE PENETROMETER TEST RESULTS


DCP NO. TP4

Project Boarding House Development
Location 6-8 Woodburn Street, Redfern NSW
Position Refer to Figure 2
Job No. E25342.G03
Client YPI2B Ownership Trust No 6

Sheet 1 of 1
Date 07/11/2021
Logged By DS **Date** 07/11/2021
Reviewed By AC **Date** 01/08/2022

Contact BG Drilling **Surface RL** ≈20.20 m AHD
Machine Rig CE 180 **Bucket Size**

DEPTH (m)	NO OF BLOWS PER 100 mm
0.10-0.2	2
0.20-0.3	3
0.30-0.4	3
0.40-0.5	7
0.50-0.6	1
0.60-0.7	1 / 200 mm.
0.70-0.8	0
0.80-0.9	1 / 200 mm.
0.90-1	0
1.00-1.1	1
1.10-1.2	1 / 200 mm.
1.20-1.3	0
1.30-1.4	2
1.40-1.5	4
1.50-1.6	6
1.60-1.7	6
1.70-1.8	8
1.80-1.9	10
1.90-2	14
2.00-2.1	11
2.10-2.2	16
2.20-2.3	19
2.30-2.4	17
2.40-2.5	19
2.50-2.6	20
2.60-2.7	21
2.70-2.8	20
2.80-2.9	17 / Terminated.



Termination Remark
Target Depth Reached.

Final Depth (m)

2.90

EXPLANATION OF NOTES, ABBREVIATIONS & TERMS USED ON BOREHOLE AND TEST PIT LOGS

DRILLING/EXCAVATION METHOD





HA	Hand Auger	ADH	Hollow Auger	NQ	Diamond Core - 47 mm
DT	Diatube Coring	RT	Rotary Tricone bit	NMLC	Diamond Core - 52 mm
NDD	Non-destructive digging	RAB	Rotary Air Blast	HQ	Diamond Core - 63 mm
AD*	Auger Drilling	RC	Reverse Circulation	HMLC	Diamond Core - 63 mm
*V	V-Bit	PT	Push Tube	EX	Tracked Hydraulic Excavator
*T	TC-Bit, e.g. AD/T	WB	Washbore	HAND	Excavated by Hand Methods

PENETRATION RESISTANCE

L	Low Resistance	Rapid penetration/ excavation possible with little effort from equipment used.
M	Medium Resistance	Penetration/ excavation possible at an acceptable rate with moderate effort from equipment used.
H	High Resistance	Penetration/ excavation is possible but at a slow rate and requires significant effort from equipment used.
R	Refusal/Practical Refusal	No further progress possible without risk of damage or unacceptable wear to equipment used.

These assessments are subjective and are dependent on many factors, including equipment power and weight, condition of excavation or drilling tools and experience of the operator.

WATER

	 Standing Water Level	 Partial water loss
	 Water Seepage	 Complete Water Loss
GWNO	GROUNDWATER NOT OBSERVED - Observation of groundwater, whether present or not, was not possible due to drilling water, surface seepage or cave-in of the borehole/ test pit.	
GWNE	GROUNDWATER NOT ENCOUNTERED - Borehole/ test pit was dry soon after excavation. However, groundwater could be present in less permeable strata. Inflow may have been observed had the borehole/ test pit been left open for a longer period.	

SAMPLING AND TESTING

SPT	Standard Penetration Test to AS1289.6.3.1-2004
4,7,11 N=18	4,7,11 = Blows per 150mm. N = Blows per 300mm penetration following a 150mm seating drive
30/80mm	Where practical refusal occurs, the blows and penetration for that interval are reported, N is not reported
RW	Penetration occurred under the rod weight only, N<1
HW	Penetration occurred under the hammer and rod weight only, N<1
HB	Hammer double bouncing on anvil, N is not reported
Sampling	
DS	Disturbed Sample
ES	Sample for environmental testing
BDS	Bulk disturbed Sample
GS	Gas Sample
WS	Water Sample
U50	Thin walled tube sample - number indicates nominal sample diameter in millimetres
Testing	
FP	Field Permeability test over section noted
FVS	Field Vane Shear test expressed as uncorrected shear strength (sv= peak value, sr= residual value)
PID	Photoionisation Detector reading in ppm
PM	Pressuremeter test over section noted
PP	Pocket Penetrometer test expressed as instrument reading in kPa
WPT	Water Pressure tests
DCP	Dynamic Cone Penetrometer test
CPT	Static Cone Penetration test
CPTu	Static Cone Penetration test with pore pressure (u) measurement

GEOLOGICAL BOUNDARIES

————— = Observed Boundary (position known)	- - - - - = Observed Boundary (position approximate)	- - ? - - ? - - ? - - = Boundary (interpreted or inferred)
-----------------------------------------------	---------------------------------------------------------	---------------------------------------------------------------

ROCK CORE RECOVERY








TCR=Total Core Recovery (%)

$$= \frac{\text{Length of core recovered}}{\text{Length of core run}} \times 100$$

RQD = Rock Quality Designation (%)

$$= \frac{\sum \text{Axial lengths of core} > 100\text{mm}}{\text{Length of core run}} \times 100$$

METHOD OF SOIL DESCRIPTION USED ON BOREHOLE AND TEST PIT LOGS

	FILL		ORGANIC SOILS (OL, OH or Pt)		CLAY (CL, CI or CH)
	COUBLES or BOULDERS		SILT (ML or MH)		SAND (SP or SW)
	GRAVEL (GP or GW)	Combinations of these basic symbols may be used to indicate mixed materials such as sandy clay			

CLASSIFICATION AND INFERRED STRATIGRAPHY

Soil is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS 1726:2017, Section 6.1 – Soil description and classification.


PARTICLE SIZE CHARACTERISTICS

Fraction	Components	Sub Division	Size mm
Oversize	BOULDERS		>200
	COBBLES		63 to 200
Coarse grained soil	GRAVEL	Coarse	19 to 63
		Medium	6.7 to 19
		Fine	2.36 to 6.7
	SAND	Coarse	0.6 to 2.36
		Medium	0.21 to 0.6
		Fine	0.075 to 0.21
Fine grained soil	SILT		0.002 to 0.075
	CLAY		<0.002

GROUP SYMBOLS

Major Divisions		Symbol	Description
COARSE GRAINED SOILS More than 65% of soil excluding oversize fraction is greater than 0.075mm	GRAVEL More than 50% of coarse fraction is >2.36mm	GW	Well graded gravel and gravel-sand mixtures, little or no fines, no dry strength.
		GP	Poorly graded gravel and gravel-sand mixtures, little or no fines, no dry strength.
		GM	Silty gravel, gravel-sand-silt mixtures, zero to medium dry strength.
		GC	Clayey gravel, gravel-sand-clay mixtures, medium to high dry strength.
	SAND More than 50% of coarse fraction is <2.36 mm	SW	Well graded sand and gravelly sand, little or no fines, no dry strength.
		SP	Poorly graded sand and gravelly sand, little or no fines, no dry strength.
		SM	Silty sand, sand-silt mixtures, zero to medium dry strength.
		SC	Clayey sand, sandy-clay mixtures, medium to high dry strength.
FINE GRAINED SOILS More than 35% of soil excluding oversized fraction is less than 0.075mm	Liquid Limit less < 50%	ML	Inorganic silts of low plasticity, very fine sands, rock flour, silty or clayey fine sands, zero to medium dry strength.
		CL, CI	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, medium to high dry strength.
		OL	Organic silts and organic silty clays of low plasticity, low to medium dry strength.
	Liquid Limit > 50%	MH	Inorganic silts of high plasticity, high to very high dry strength.
		CH	Inorganic clays of high plasticity, high to very high dry strength.
		OH	Organic clays of medium to high plasticity, medium to high dry strength.
	Highly Organic soil		PT

PLASTICITY PROPERTIES



MOISTURE CONDITION

Symbol	Term	Description
D	Dry	Non-cohesive and free-running.
M	Moist	Soils feel cool, darkened in colour. Soil tends to stick together.
W	Wet	Soils feel cool, darkened in colour. Soil tends to stick together, free water forms when handling.

Moisture content of cohesive soils shall be described in relation to plastic limit (PL) or liquid limit (LL) for soils with higher moisture content as follows: Moist, dry of plastic limit ($w < PL$); Moist, near plastic limit ($w \approx PL$); Moist, wet of plastic limit ($w < PL$); Wet, near liquid limit ($w \approx LL$); Wet, wet of liquid limit ($w > LL$).

CONSISTENCY

Symbol	Term	Undrained Shear Strength (kPa)	SPT "N" #
VS	Very Soft	≤ 12	≤ 2
S	Soft	>12 to ≤ 25	>2 to ≤ 4
F	Firm	>25 to ≤ 50	>4 to ≤ 8
St	Stiff	>50 to ≤ 100	>8 to ≤ 15
VSt	Very Stiff	>100 to ≤ 200	>15 to ≤ 30
H	Hard	>200	>30
Fr	Friable	-	-

DENSITY

Symbol	Term	Density Index %	SPT "N" #
VL	Very Loose	≤ 15	0 to 4
L	Loose	>15 to ≤ 35	4 to 10
MD	Medium Dense	>35 to ≤ 65	10 to 30
D	Dense	>65 to ≤ 85	30 to 50
VD	Very Dense	>85	Above 50

In the absence of test results, consistency and density may be assessed from correlations with the observed behaviour of the material. # SPT correlations are not stated in AS1726:2017, and may be subject to corrections for overburden pressure, moisture content of the soil, and equipment type.

MINOR COMPONENTS

Term	Assessment Guide	Proportion by Mass
Add 'Trace'	Presence just detectable by feel or eye but soil properties little or no different to general properties of primary component	Coarse grained soils: $\leq 5\%$ Fine grained soil: $\leq 15\%$
Add 'With'	Presence easily detectable by feel or eye but soil properties little or no different to general properties of primary component	Coarse grained soils: 5 - 12% Fine grained soil: 15 - 30%
Prefix soil name	Presence easily detectable by feel or eye in conjunction with the general properties of primary component	Coarse grained soils: $>12\%$ Fine grained soil: $>30\%$

TERMS FOR ROCK MATERIAL STRENGTH AND WEATHERING

CLASSIFICATION AND INFERRED STRATIGRAPHY

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 – 2017, Section 6.2 – Rock identification, description and classification.

ROCK MATERIAL STRENGTH CLASSIFICATION

Symbol	Term	Point Load Index, $Is_{(50)}$ (MPa) [#]	Field Guide
VL	Very Low	0.03 to 0.1	Material crumbles under firm blows with sharp end of pick; can be peeled with knife; too hard to cut a triaxial sample by hand. Pieces up to 30 mm can be broken by finger pressure.
L	Low	0.1 to 0.3	Easily scored with a knife; indentations 1 mm to 3 mm show in the specimen with firm blows of pick point; has dull sound under hammer. A piece of core 150 mm long by 50 mm diameter may be broken by hand. Sharp edges of core may be friable and break during handling.
M	Medium	0.3 to 1	Readily scored with a knife; a piece of core 150 mm long by 50 mm diameter can be broken by hand with difficulty.
H	High	1 to 3	A piece of core 150 mm long by 50 mm diameter cannot be broken by hand but can be broken with pick with a single firm blow; rock rings under hammer.
VH	Very High	3 to 10	Hand specimen breaks with pick after more than one blow; rock rings under hammer.
EH	Extremely High	>10	Specimen requires many blows with geological pick to break through intact material; rock rings under hammer.

[#] Rock Strength Test Results



Point Load Strength Index, $Is_{(50)}$, Axial test (MPa)



Point Load Strength Index, $Is_{(50)}$, Diametral test (MPa)

Relationship between rock strength test result ($Is_{(50)}$) and unconfined compressive strength (UCS) will vary with rock type and strength, and should be determined on a site-specific basis. However UCS is typically 20 x $Is_{(50)}$.

ROCK MATERIAL WEATHERING CLASSIFICATION

Symbol	Term	Field Guide
RS	Residual Soil	Soil developed on extremely weathered rock; the mass structure and substance fabric are no longer evident; there is a large change in volume but the soil has not been significantly transported.
XW	Extremely Weathered	Rock is weathered to such an extent that it has soil properties - i.e. it either disintegrates or can be remoulded, in water.
DW	Distinctly Weathered	Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching, or may be decreased due to deposition of weathering products in pores. In some environments it is convenient to subdivide into Highly Weathered and Moderately Weathered, with the degree of alteration typically less for MW.
SW	Slightly Weathered	Rock slightly discoloured but shows little or no change of strength relative to fresh rock.
FR	Fresh	Rock shows no sign of decomposition or staining.

ABBREVIATIONS AND DESCRIPTIONS FOR ROCK MATERIAL AND DEFECTS

CLASSIFICATION AND INFERRED STRATIGRAPHY

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 – 2017, Section 6.2 – Rock identification, description and classification.

DETAILED ROCK DEFECT SPACING

Defect Spacing			Bedding Thickness (Stratification)	
Spacing/width (mm)	Descriptor	Symbol	Term	Spacing (mm)
<20	Extremely Close	EC	Thinly laminated	<6
20-60	Very Close	VC	Laminated	6 – 20
60-200	Close	C	Very thinly bedded	20 – 60
200-600	Medium	M	Thinly bedded	60 – 200
600-2000	Wide	W	Medium bedded	200 – 600
2000-6000	Very Wide	VW	Thickly bedded	600 – 2,000
			Very thickly bedded	> 2,000

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT TYPES

Defect Type	Abbr.	Description
Joint	JT	Surface of a fracture or parting, formed without displacement, across which the rock has little or no tensile strength. May be closed or filled by air, water or soil or rock substance, which acts as cement.
Bedding Parting	BP	Surface of fracture or parting, across which the rock has little or no tensile strength, parallel or sub-parallel to layering/ bedding. Bedding refers to the layering or stratification of a rock, indicating orientation during deposition, resulting in planar anisotropy in the rock material.
Contact	CO	The surface between two types or ages of rock.
Sheared Surface	SSU	A near planar, curved or undulating surface which is usually smooth, polished or slickensided.
Sheared Seam/ Zone (Fault)	SS/SZ	Seam or zone with roughly parallel almost planar boundaries of rock substance cut by closely spaced (often <50 mm) parallel and usually smooth or slickensided joints or cleavage planes.
Crushed Seam/ Zone (Fault)	CS/CZ	Seam or zone composed of disoriented usually angular fragments of the host rock substance, with roughly parallel near-planar boundaries. The brecciated fragments may be of clay, silt, sand or gravel sizes or mixtures of these.
Extremely Weathered Seam/ Zone	XWS/XWZ	Seam of soil substance, often with gradational boundaries, formed by weathering of the rock material in places.
Infilled Seam	IS	Seam of soil substance, usually clay or clayey, with very distinct roughly parallel boundaries, formed by soil migrating into joint or open cavity.
Vein	VN	Distinct sheet-like body of minerals crystallised within rock through typically open-space filling or crack-seal growth.

NOTE: Defects size of <100mm SS, CS and XWS. Defects size of >100mm SZ, CZ and XWZ.

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT SHAPE AND ROUGHNESS

Shape	Abbr.	Description	Roughness	Abbr.	Description
Planar	PR	Consistent orientation	Polished	POL	Shiny smooth surface
Curved	CU	Gradual change in orientation	Slickensided	SL	Grooved or striated surface, usually polished
Undulating	UN	Wavy surface	Smooth	SM	Smooth to touch. Few or no surface irregularities
Stepped	ST	One or more well defined steps	Rough	RO	Many small surface irregularities (amplitude generally <1mm). Feels like fine to coarse sandpaper
Irregular	IR	Many sharp changes in orientation	Very Rough	VR	Many large surface irregularities, amplitude generally >1mm. Feels like very coarse sandpaper

Orientation:

Vertical Boreholes – The dip (inclination from horizontal) of the defect.

Inclined Boreholes – The inclination is measured as the acute angle to the core axis.

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT COATING

Coating	Abbr.	Description	Aperture	Abbr.	Description
Clean	CN	No visible coating or infilling	Closed	CL	Closed.
Stain	SN	No visible coating but surfaces are discoloured by staining, often limonite (orange-brown)	Open	OP	Without any infill material.
Veneer	VNR	A visible coating of soil or mineral substance, usually too thin to measure (< 1 mm); may be patchy	Infilled	-	Soil or rock i.e. clay, silt, talc, pyrite, quartz, etc.

Appendix B – Laboratory Certificates

CLIENT DETAILS

Contact David Saw
Client EI AUSTRALIA
Address SUITE 6.01
 55 MILLER STREET
 PYRMONT NSW 2009

Telephone 61 2 9516 0722
Facsimile (Not specified)
Email david.saw@eiaustralia.com.au

Project **E25342.G03 6-8 Woodburn St, Redfern**
Order Number **E25342.G03**
Samples 2

LABORATORY DETAILS

Manager Huong Crawford
Laboratory SGS Alexandria Environmental
Address Unit 16, 33 Maddox St
 Alexandria NSW 2015

Telephone +61 2 8594 0400
Facsimile +61 2 8594 0499
Email au.environmental.sydney@sgs.com

SGS Reference **SE224457 R0**
Date Received 11/10/2021
Date Reported 18/10/2021

COMMENTS

Accredited for compliance with ISO/IEC 17025 - Testing. NATA accredited laboratory 2562(4354).

SIGNATORIES



Dong LIANG
 Metals/Inorganics Team Leader



Shane MCDERMOTT
 Inorganic/Metals Chemist



ANALYTICAL RESULTS

SE224457 R0

Soluble Anions (1:5) in Soil/Solids by Ion Chromatography [AN245] Tested: 11/10/2021

			BH2M_1.5-1.95	BH3M_4.5-4.95
			SOIL	SOIL
			-	-
			10/10/2021	10/10/2021
			SE224457.001	SE224457.002
PARAMETER	UOM	LOR		
Chloride	mg/kg	0.25	12	22
Sulfate	mg/kg	5	66	58

pH in soil (1:5) [AN101] Tested: 11/10/2021

			BH2M_1.5-1.95	BH3M_4.5-4.95
			SOIL	SOIL
			-	-
			10/10/2021	10/10/2021
			SE224457.001	SE224457.002
PARAMETER	UOM	LOR		
pH	pH Units	0.1	7.5	6.0



ANALYTICAL RESULTS

SE224457 R0

Conductivity and TDS by Calculation - Soil [AN106] Tested: 11/10/2021

			BH2M_1.5-1.95	BH3M_4.5-4.95
			SOIL	SOIL
			-	-
			10/10/2021	10/10/2021
			SE224457.001	SE224457.002
PARAMETER	UOM	LOR		
Conductivity of Extract (1:5 as received)	µS/cm	2	160	44

Moisture Content [AN002] Tested: 14/10/2021

			BH2M_1.5-1.95	BH3M_4.5-4.95
			SOIL	SOIL
			-	-
			10/10/2021	10/10/2021
			SE224457.001	SE224457.002
PARAMETER	UOM	LOR		
% Moisture	%w/w	1	14.3	15.1

METHOD

METHODOLOGY SUMMARY

AN002

The test is carried out by drying (at either 40°C or 105°C) a known mass of sample in a weighed evaporating basin. After fully dry the sample is re-weighed. Samples such as sludge and sediment having high percentages of moisture will take some time in a drying oven for complete removal of water.

AN101

pH in Soil Sludge Sediment and Water: pH is measured electrometrically using a combination electrode and is calibrated against 3 buffers purchased commercially. For soils, sediments and sludges, an extract with water (or 0.01M CaCl₂) is made at a ratio of 1:5 and the pH determined and reported on the extract. Reference APHA 4500-H+.

AN106

Conductivity and TDS by Calculation: Conductivity is measured by meter with temperature compensation and is calibrated against a standard solution of potassium chloride. Conductivity is generally reported as µmhos/cm or µS/cm @ 25°C. For soils, an extract of as received sample with water is made at a ratio of 1:5 and the EC determined and reported on the extract, or calculated back to the as-received sample. Salinity can be estimated from conductivity using a conversion factor, which for natural waters, is in the range 0.55 to 0.75. Reference APHA 2510 B.

AN245

Anions by Ion Chromatography: A water sample is injected into an eluent stream that passes through the ion chromatographic system where the anions of interest ie Br, Cl, NO₂, NO₃ and SO₄ are separated on their relative affinities for the active sites on the column packing material. Changes to the conductivity and the UV-visible absorbance of the eluent enable identification and quantitation of the anions based on their retention time and peak height or area. APHA 4110 B

FOOTNOTES

*	NATA accreditation does not cover the performance of this service.	-	Not analysed.	UOM	Unit of Measure.
**	Indicative data, theoretical holding time exceeded.	NVL	Not validated.	LOR	Limit of Reporting.
***	Indicates that both * and ** apply.	IS	Insufficient sample for analysis.	↑↓	Raised/lowered Limit of Reporting.
		LNR	Sample listed, but not received.		

Unless it is reported that sampling has been performed by SGS, the samples have been analysed as received.
Solid samples expressed on a dry weight basis.

Where "Total" analyte groups are reported (for example, Total PAHs, Total OC Pesticides) the total will be calculated as the sum of the individual analytes, with those analytes that are reported as <LOR being assumed to be zero. The summed (Total) limit of reporting is calculated by summing the individual analyte LORs and dividing by two. For example, where 16 individual analytes are being summed and each has an LOR of 0.1 mg/kg, the "Totals" LOR will be 1.6 / 2 (0.8 mg/kg). Where only 2 analytes are being summed, the "Total" LOR will be the sum of those two LORs.

Some totals may not appear to add up because the total is rounded after adding up the raw values.

If reported, measurement uncertainty follow the ± sign after the analytical result and is expressed as the expanded uncertainty calculated using a coverage factor of 2, providing a level of confidence of approximately 95%, unless stated otherwise in the comments section of this report.

Results reported for samples tested under test methods with codes starting with ARS-SOP, radionuclide or gross radioactivity concentrations are expressed in becquerel (Bq) per unit of mass or volume or per wipe as stated on the report. Becquerel is the SI unit for activity and equals one nuclear transformation per second.

Note that in terms of units of radioactivity:

- 1 Bq is equivalent to 27 pCi
- 37 MBq is equivalent to 1 mCi

For results reported for samples tested under test methods with codes starting with ARS-SOP, less than (<) values indicate the detection limit for each radionuclide or parameter for the measurement system used. The respective detection limits have been calculated in accordance with ISO 11929.

The QC and MU criteria are subject to internal review according to the SGS QAQC plan and may be provided on request or alternatively can be found here: www.sgs.com.au/en-gb/environment-health-and-safety.

This document is issued by the Company under its General Conditions of Service accessible at www.sgs.com/en/Terms-and-Conditions.aspx. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.

Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client only. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

This report must not be reproduced, except in full.

Atterberg Limits and Linear Shrinkage Report

Project: E25342.G04.2 - 6 - 7 WOODBURN STREET, REDFERN

Project No.: 31380

Client: El Australia

Report No.: 22/2659

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 19/07/2022

Test Method: AS1289.3.1.2, .3.2.1, .3.4.1,2.1.1

Page: 1 of 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	6669D-L/1					
Sample Location	Borehole 202M					
Material Description	Silty Clay, grey/orange, trace of sand					
Depth (m)	1.5 - 1.6					
Sample Date	7/07/2022					
Sample History	Oven Dried					
Method of Preparation	Dry Sieved					
Liquid Limit (%)	42					
Plastic Limit (%)	15					
Plasticity Index	27					
Linear Shrinkage (%)	12.5					
Mould Size (mm)	254					
Crumbing	N					
Curling	N					

Remarks:

Approved Signatory.....


Technician: DH

Orlando Mendoza - Laboratory Manager

Moisture Content of Soil and Aggregate Samples

Project: E25342.G04.2 - 6 - 7 WOODBURN STREET, REDFERN

Project No.: 31380

Client: El Australia

Report No.: 22/2659

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 19/07/2022

Test Method: AS1289.2.1.1


Page: 2 of 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	6669D-L/1					
Sample Location	Borehole 202M					
Material Description	Silty Clay, grey/orange, trace of sand					
Depth (mm)	1.5 - 1.6					
Sample Date	7/07/2022					
Moisture Content (%)	23.6					

Remarks:

Approved Signatory.....



Technician: DH

Orlando Mendoza - Laboratory Manager

Atterberg Limits and Linear Shrinkage Report

Project: E25342: 6 - 9 Woodburn Street, Redfern

Project No.: 31380

Client: El Australia Pty Ltd

Report No.: 21/3054

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 27/10/2021

Test Method: AS1289.3.1.2, 3.2.1, 3.1.1, 3.4.1, 2.1.1

Page: 1 of 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	5679D-L/1					
Sample Location	Borehole 3M					
Material Description	Silty Clay, pale grey trace of gravel					
Depth (m)	3.0 - 3.45					
Sample Date	7/10/2021					
Sample History	Air Dried					
Method of Preparation	Dry Sieved					
Liquid Limit (%)	44					
Plastic Limit (%)	21					
Plasticity Index	23					
Linear Shrinkage (%)	11					
Mould Size (mm)	128					
Crumbing	N					
Curling	N					

Remarks:

Approved Signatory.....

Technician: LL

David Ly - Senior Geotechnician

Moisture Content of Soil and Aggregate Samples

Project: E25342: 6 - 9 Woodburn Street, Redfern

Project No.: 31380

Client: El Australia Pty Ltd

Report No.: 21/3054

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 27/10/2021

Test Method: AS1289.2.1.1

Page: 2 of 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	5679D-L/1					
Sample Location	Borehole 3M					
Material Description	Silty Clay, pale grey trace of gravel					
Depth (mm)	3.0 - 3.45					
Sample Date	7/10/2021					
Moisture Content (%)	16.1					

Remarks:


 Approved Signatory.....

Technician: LL

David Ly - Senior Geotechnician

Point Load Strength Index Report

Project: 6-8 WOODBURN STREET, REDFERN NSW - E25342

Project No.: 31380/5679D-L

Client: El Australia Pty Ltd

Report No.: 21/2980

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 21/10/2021

Test Method: AS4133.4.1

Page: 1 OF 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Date Samples Drilled / Taken: 07/10/2021

Date Samples Drilled / Taken: 07/10/2021

Borehole No. 1

Borehole No. 2M

Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture	Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture
3.35	A	0.019	TS	3	M	9.37	A	0.046	TS	3	W
3.76	A	0.220	SS	3	M	10.13	A	0.660	SS	3	D
4.20	A	0.085	TS	3	M	10.77	A	0.970	SS	3	D
5.70	A	0.190	SS	3	M	11.82	A	0.600	SS	3	D
6.35	A	0.510	SH	3	D	12.50	A	1.400	SS	3	D
6.82	A	0.310	SS	3	D	13.42	A	1.200	SS	3	D
7.35	A	0.910	SS	3	D						

FAILURE TYPE

- 1= FRACTURE THROUGH BEDDING OR WEAK PLANE
- 2= FRACTURE ALONG BEDDING
- 3= FRACTURE THROUGH ROCK MASS
- 4= FRACTURE INFLUENCED BY NATURAL DEFECT OR DRILLING
- 5= PARTIAL FRACTURE OR CHIP (INVALID RESULT)

TEST TYPE

- A= AXIAL
- D= DIAMETRAL
- I= IRREGULAR
- C= CUBE

MOISTURE CONDITION

- W= WET
- M= MOIST
- D= DRY

ROCK TYPE

- SS= SANDSTONE
- ST= SILTSTONE
- SH= SHALE
- YS= CLAYSTONE
- IG= IGNEOUS

Remarks:

Technician: ZW

Approved Signatory.....

Orlando Mendoza - Laboratory Manager

Point Load Strength Index Report

Project: 6-8 WOODBURN STREET, REDFERN NSW - E25342

Project No.: 31380/5679D-L

Client: El Australia Pty Ltd

Report No.: 21/2980

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 21/10/2021

Test Method: AS4133.4.1

Page: 2 OF 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Date Samples Drilled / Taken: 07/10/2021

Date Samples Drilled / Taken:

Borehole No. 3M

Borehole No.

Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture	Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture
6.25	A	3.700	SS	3	D						
7.03	A	0.920	SS	3	D						
7.58	A	1.200	SS	3	D						
8.06	A	1.300	SS	3	D						

FAILURE TYPE

- 1= FRACTURE THROUGH BEDDING OR WEAK PLANE
- 2= FRACTURE ALONG BEDDING
- 3= FRACTURE THROUGH ROCK MASS
- 4= FRACTURE INFLUENCED BY NATURAL DEFECT OR DRILLING
- 5= PARTIAL FRACTURE OR CHIP (INVALID RESULT)

TEST TYPE

- A= AXIAL
- D= DIAMETRAL
- I= IRREGULAR
- C= CUBE

MOISTURE CONDITION

- W= WET
- M= MOIST
- D= DRY

ROCK TYPE

- SS= SANDSTONE
- ST= SILTSTONE
- SH= SHALE
- YS= CLAYSTONE
- IG= IGNEOUS

Remarks:


Technician: ZW

Approved Signatory.....

Orlando Mendoza - Laboratory Manager



Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Failure Type	Test Type	Moisture Condition	Rock Type
1 = Fracture through bedding or weak plane	A = Axial	W = Wet	SS = Sandstone
2 = Fracture along bedding	D = Diametrial	M = Moist	ST = Siltstone
3 = Fracture through rock mass	I = Irregular	D = Dry	SH = Shale
4 = Fracture influenced by natural defect or drilling	C = Cube		YS = Claystone
5 = Partial fracture or chip (invalid result)			IG = Igneous
Remarks:			
Technician: LL			Approved Signatory.....  Philip Ihnativ - Senior Geotechnical

Appendix C – Important Information

SCOPE OF SERVICES

The geotechnical report ("the report") has been prepared in accordance with the scope of services as set out in the contract, or as otherwise agreed, between the Client And EI Australia ("EI"). The scope of work may have been limited by a range of factors such as time, budget, access and/or site disturbance constraints.

RELIANCE ON DATA

EI has relied on data provided by the Client and other individuals and organizations, to prepare the report. Such data may include surveys, analyses, designs, maps and plans. EI has not verified the accuracy or completeness of the data except as stated in the report. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations ("conclusions") are based in whole or part on the data, EI will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to EI.

GEOTECHNICAL ENGINEERING

Geotechnical engineering is based extensively on judgment and opinion. It is far less exact than other engineering disciplines. Geotechnical engineering reports are prepared for a specific client, for a specific project and to meet specific needs, and may not be adequate for other clients or other purposes (e.g. a report prepared for a consulting civil engineer may not be adequate for a construction contractor). The report should not be used for other than its intended purpose without seeking additional geotechnical advice. Also, unless further geotechnical advice is obtained, the report cannot be used where the nature and/or details of the proposed development are changed.

LIMITATIONS OF SITE INVESTIGATION

The investigation programme undertaken is a professional estimate of the scope of investigation required to provide a general profile of subsurface conditions. The data derived from the site investigation programme and subsequent laboratory testing are extrapolated across the site to form an inferred geological model, and an engineering opinion is rendered about overall subsurface conditions and their likely behaviour with regard to the proposed development. Despite investigation, the actual conditions at the site might differ from those inferred to exist, since no subsurface exploration program, no matter how comprehensive, can reveal all subsurface details and anomalies. The engineering logs are the subjective interpretation of subsurface conditions at a particular location and time, made by trained personnel. The actual interface between materials may be more gradual or abrupt than a report indicates.

SUBSURFACE CONDITIONS ARE TIME DEPENDENT

Subsurface conditions can be modified by changing natural forces or man-made influences. The report is based on conditions that existed at the time of subsurface exploration. Construction operations adjacent to the site, and natural events such as floods, or ground water fluctuations, may also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. EI should be kept apprised of any such events, and should be consulted to determine if any additional tests are necessary.

VERIFICATION OF SITE CONDITIONS

Where ground conditions encountered at the site differ significantly from those anticipated in the report, either due to natural variability of subsurface conditions or construction activities, it is a condition of the report that EI be notified of any variations and be provided with an opportunity to review the recommendations of this report. Recognition of change of soil and rock conditions requires experience and it is recommended that a suitably experienced geotechnical engineer be engaged to visit the site with sufficient frequency to detect if conditions have changed significantly.

REPRODUCTION OF REPORTS

This report is the subject of copyright and shall not be reproduced either totally or in part without the express permission of this Company. Where information from the accompanying report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimize the likelihood of misinterpretation from logs.

REPORT FOR BENEFIT OF CLIENT

The report has been prepared for the benefit of the Client and no other party. EI assumes no responsibility and will not be liable to any other person or organisation for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organisation arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of EI or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own inquiries and obtain independent advice in relation to such matters.

OTHER LIMITATIONS

EI will not be liable to update or revise the report to take into account any events or emergent circumstances or fact occurring or becoming apparent after the date of the report.