



NSW RURAL FIRE SERVICE

Thomas Bertwistle
Locked Bag 5022, Parramatta NSW 2124

Our reference: DA20220414007112-EIS & DA
Exhibition-1

ATTENTION: Thomas Bertwistle

Date: Wednesday 29 June 2022

Dear Sir/Madam,

Development Application

Other - Other Assessment - Commercial Premises

5 Skyline Crescent Horningsea Park NSW 2171, 1//DP1266533, B//DP406516

I refer to your correspondence regarding the above proposal which was received by the NSW Rural Fire Service on 27/05/2022.

The NSW Rural Fire Service (NSW RFS) has considered the information submitted and provides the following recommended conditions:

Asset Protection Zones

Intent of measures: to minimise the risk of bush fire attack and provide protection for emergency services personnel, residents and others assisting firefighting activities.

1. From the commencement of building works and in perpetuity, the entire property must be managed as an inner protection area in accordance with the following requirements of Appendix 4 of *Planning for Bush Fire Protection 2019*:

- tree canopy cover should be less than 15% at maturity;
- trees at maturity should not touch or overhang the building;
- lower limbs should be removed up to a height of 2m above the ground;
- tree canopies should be separated by 2 to 5m;
- preference should be given to smooth-barked and evergreen trees.
- create large discontinuities or gaps in the vegetation to slow down or break the progress of fire towards buildings should be provided;
- shrubs should not be located under trees;
- shrubs should not form more than 10% ground cover; and
- clumps of shrubs should be separated from exposed windows and doors by a distance of at least twice the height of the vegetation.
- grass should be kept mown (as a guide, grass should be kept to no more than 100mm in height); and
- leaves and vegetation debris should be removed.

2. Landscaping within the required asset protection zone must comply with Appendix 4 of *Planning for Bush Fire Protection 2019*. In this regard, the following principles are to be incorporated:

Postal address

NSW Rural Fire Service
Locked Bag 17
GRANVILLE NSW 2142

Street address

NSW Rural Fire Service
4 Murray Rose Ave
SYDNEY OLYMPIC PARK NSW 2127

T (02) 8741 5555
F (02) 8741 5550
www.rfs.nsw.gov.au

- A minimum 1 metre wide area (or to the property boundary where the setbacks are less than 1 metre), suitable for pedestrian traffic, must be provided around the immediate curtilage of the building;
- Planting is limited in the immediate vicinity of the building;
- Planting does not provide a continuous canopy to the building (i.e. trees or shrubs are isolated or located in small clusters);
- Landscape species are chosen to ensure tree canopy cover is less than 15% (IPA), and less than 30% (OPA) at maturity and trees do not touch or overhang buildings;
- Avoid species with rough fibrous bark, or which retain/shed bark in long strips or retain dead material in their canopies;
- Use smooth bark species of trees species which generally do not carry a fire up the bark into the crown;
- Avoid planting of deciduous species that may increase fuel at surface/ ground level (i.e. leaf litter);
- Avoid climbing species to walls and pergolas;
- Locate combustible materials such as woodchips/mulch, flammable fuel stores away from the building;
- Locate combustible structures such as garden sheds, pergolas and materials such as timber garden furniture away from the building; and
- Low flammability vegetation species are used.

Construction Standards

Intent of measures: to minimise the risk of bush fire attack and provide protection for emergency services personnel, residents and others assisting firefighting activities.

3. The building must comply with the construction recommendations as set out in the bush fire report prepared by Blackash Bushfire Consulting, project ref. Lot 1 Bringelly Road Business Hub, ver. 1.2, dated 11 May 2022.

Property Access

Intent of measures: to minimise the risk of bush fire attack and provide protection for emergency services personnel, residents and others assisting firefighting activities.

4. Property access roads must comply with the following requirements of Table 7.4a of *Planning for Bush Fire Protection 2019*:

- property access roads are two-wheel drive, all-weather roads;
- the capacity of road surfaces and any bridges/causeways is sufficient to carry fully loaded firefighting vehicles (up to 23 tonnes); bridges and causeways clearly, indicate load rating.
- there is suitable access for a Category 1 fire appliance to within 4m of the static water supply where no reticulated supply is available;
- minimum 4m carriageway width;
- a minimum vertical clearance of 4m to any overhanging obstructions, including tree branches;
- property access must provide a suitable turning area in accordance with Appendix 3;
- curves have a minimum inner radius of 6m and are minimal in number to allow for rapid access and egress;
- the minimum distance between inner and outer curves is 6m;
- the cross fall is not more than 10 degrees; and
- maximum grades for sealed roads do not exceed 15 degrees and not more than 10 degrees for unsealed roads.

Water and Utility Services

Intent of measures: to minimise the risk of bush fire attack and provide protection for emergency services personnel, residents and others assisting firefighting activities.

5. The provision of water, electricity and gas must comply with Table 7.4a of *Planning for Bush Fire Protection 2019*.

For any queries regarding this correspondence, please contact Simon Derevnin on 1300 NSW RFS.

Yours sincerely,

Alastair Patton

Supervisor Development Assessment & Plan
Built & Natural Environment