



Consulting.TM
an Elephants Foot Company

Marsden Park High School & Melonba Public School
Elara Boulevard, Melonba (Lot 30 DP 1237735) NSW

OPERATIONAL WASTE MANAGEMENT PLAN

19/09/2022
SSD-41372302
Report No. 3990
Revision H

Client

NSW Department of Education
Sydney NSW

Architect

NBRS Architecture
<https://nbrs.com.au/>



REVISION REFERENCE

Revision	Date	Prepared by	Description
A	14/06/2022	H Wilkes	Draft
B	20/06/2022	H Wilkes	Amendment
C	4/07/2022	H Wilkes	Amendment
D	18/07/2022	H Wilkes	Amendment
E	28/07/2022	H Wilkes	Amendment
F	15/08/2022	H Wilkes	Amendment
G	8/09/2022	H Wilkes	Final Draft
H	19/09/2022	H Wilkes	Final

The information contained in this document produced by Elephants Foot Consulting (EFC) is solely for the use of the client identified on the cover sheet for the purpose for which it has been prepared for. EFC undertakes no duty, nor accepts any responsibility for any third party who may rely upon this document. Reproduction, publication or distribution of this document without written permission from EFC is strictly prohibited.

TABLE OF CONTENTS

OPERATIONAL WASTE MANAGEMENT PLAN	i
TABLE OF FIGURES	iv
LIST OF TABLES.....	iv
GLOSSARY OF ABBREVIATIONS AND TERMS	i
1 INTRODUCTION	2
1.1 SCOPE OF REPORT	2
1.2 REPORT CONDITIONS.....	3
2 LEGISLATION & GUIDANCE	4
2.1 PLANNING SECRETARY'S ENVIRONMENTAL ASSESSMENT REQUIREMENTS – 18. WASTE.....	5
3 DEVELOPMENT OVERVIEW.....	6
3.1 SITE LOCATION	7
4 WASTE MANAGEMENT	8
4.1 WASTE GENERATION ESTIMATES	8
4.2 BIN SUMMARY.....	9
4.3 WASTE DISPOSAL PROCEDURES	10
4.4 WASTE COLLECTION PROCEDURES	10
4.5 OTHER WASTE MANAGEMENT CONSIDERATIONS.....	11
4.5.1 BATHROOMS.....	11
4.5.2 CANTEEN.....	11
4.5.3 LIQUID WASTE	11
4.5.4 PROBLEM WASTE.....	11
4.5.5 FUTURE WASTE AND RECYCLING STREAM SEPARATION.....	12
5 STAKEHOLDER ROLES & RESPONSIBILITIES	14
6 SOURCE SEPARATION	15
7 EDUCATION	16
7.1 SIGNAGE	16
7.2 POLLUTION PREVENTION	16
9 WASTE ROOMS	17
10 BIN MOVING PATHS	18
11 CONSTRUCTION REQUIREMENTS.....	19
11.1 ADDITIONAL CONSIDERATIONS	19
12 USEFUL CONTACTS.....	20
APPENDIX A: ARCHITECTURAL PLANS.....	21
APPENDIX: A.1 GROUND FLOOR PLAN – WASTE FACILITIES.....	22
APPENDIX B: PRIMARY WASTE MANAGEMENT PROVISIONS.....	23
APPENDIX: B.1 TYPICAL BIN SPECIFICATIONS	24

APPENDIX: B.2	SIGNAGE FOR WASTE AND RECYCLING BINS	25
APPENDIX: B.3	TYPICAL COLLECTION VEHICLE INFORMATION	27

TABLE OF FIGURES

Figure 1. Site Location.....	7
------------------------------	---

LIST OF TABLES

Table 1: SEARs Items	5
Table 2: Estimated Volumes of General Waste and Recycling – Primary School	8
Table 3: Estimated Volumes of General Waste and Recycling – High School	9
Table 4: Stakeholder Roles and Responsibilities	14
Table 5: Operational Waste Streams.....	15
Table 6: Waste Room Areas.....	17
Table 7: Waste Room Requirements.....	17

GLOSSARY OF ABBREVIATIONS AND TERMS

TERM	DESCRIPTION
<i>Bin-carting Route</i>	Travel route for transferring bins from the storage area to a nominated collection point
<i>Collection Area/Point</i>	The identified position or area where general waste or recyclables are loaded onto the collection vehicle
<i>Compactor</i>	A machine for compressing waste into disposable or reusable containers
<i>Composter</i>	A container/machine used for composting specific food scraps
<i>Crate</i>	A plastic box used for the collection of recyclable materials
<i>DA</i>	Development Application
<i>DCP</i>	Development Control Plan
<i>EPA</i>	Environmental Protection Authority
<i>HRV</i>	Heavy Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities
<i>L</i>	Litre(s)
<i>LEP</i>	Local Environmental Plans guide planning decisions for local government areas
<i>Liquid Waste</i>	Non-hazardous liquid waste generated by commercial premises that must be connected to sewer or collected for treatment and disposal by a liquid waste contractor (including grease trap waste)
<i>Mobile Garbage Bin(s) (MGB)</i>	A waste container generally constructed of plastic with wheels with a capacity in litres of 120, 240, 360, 660, 1000 or 1100
<i>MRV</i>	Medium Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities
<i>Onsite Collection</i>	When the collection vehicle enters the property and services the development within the property boundary from a designated loading area
<i>SRV</i>	Small Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities
<i>WHS</i>	Workplace Health and Safety
<i>Wheel-in wheel-out service</i>	A type of waste collection service offered by local councils where the council waste collection personnel enter the premises to collect the bins and returns them to the property

1 INTRODUCTION

Elephants Foot Consulting (EFC) has been engaged to prepare the following waste management plan for the operational management of waste generated by Marsden Park new high school and Melonba new primary school.

Waste management strategies and audits are required for new developments in order to support the design and sustainable performance of the building. It is EFC's belief that a successful waste management strategy contains three key objectives:

- i. **Promote responsible source separation** to reduce the amount of waste that goes to landfill by implementing convenient and efficient waste management systems.
- ii. **Ensure adequate waste provisions and robust procedures** that will cater for potential changes during the operational phase of the development.
- iii. **Comply** with all relevant council codes, policies, and guidelines.

To achieve these objectives, this operational waste management plan (OWMP) identifies the different waste streams likely to be generated during the operational phase of the development, as well as how the waste will be handled and disposed, details of bin sizes/quantities and waste rooms, descriptions of the proposed waste management equipment used, and information on waste collection points and frequencies.

It is essential that this OWMP is integrated into the overall management of the building and is clearly communicated to all relevant stakeholders.

1.1 SCOPE OF REPORT

This operational waste management plan (OWMP) only applies to the **operational** phase of the proposed development; therefore, the requirements outlined in this OWMP must be implemented during the operational phase of the site and may be subject to review upon further expansion of, and/or changes to the development.

The waste management of the **construction** and **demolition** phases of the development are not addressed in this report. A construction and demolition WMP will be provided separately.

1.2 REPORT CONDITIONS

The purpose of this report is to document an OWMP as part of a state significant development application, which is supplied by EFC with the following limitations:

- Drawings, estimates and information contained in this OWMP have been prepared by analysing the information, plans and documents supplied by the client and third parties including Council and other government agencies. The assumptions based on the information contained in the OWMP is outside the control of EFC,
- The figures presented in the report are an estimate only – the actual amount of waste generated will be dependent on the occupancy rate of the building/s and waste generation intensity as well as the building management's approach to educating tenants regarding waste management operations and responsibilities,
- The building manager will adjust waste management operations as required based on actual waste volumes (e.g. if waste is greater than estimated) and increase the number of bins and collections accordingly,
- The report will not be used to determine or forecast operational costs or prepare any feasibility study or to document any safety or operational procedures,
- The report has been prepared with all due care; however no assurance is made that the OWMP reflects the actual outcome of the proposed waste facilities, services, and operations, and EFC will not be liable for plans or results that are not suitable for purpose due to incorrect or unsuitable information or otherwise,
- EFC offer no warranty or representation of accuracy or reliability of the OWMP unless specifically stated,
- Any manual handling equipment recommended in this OWMP should be provided at the recommendation of the appropriate equipment provider who will assess the correct equipment for supply,
- Design of waste management equipment and systems must be approved by the supplier,
- EFC cannot be held accountable for late changes to the design after the OWMP has been submitted to Council,
- EFC will provide specifications and recommendations on bin access and travel paths within the OWMP, however it is the architect's responsibility to ensure the architectural drawings meet these provisions,
- EFC are not required to provide information on collection vehicle swept paths, head heights, internal manoeuvring or loading requirements. It is assumed this information will be provided by a traffic consultant,
- Council are subject to changing waste and recycling policies and requirements at their own discretion.

This OWMP is only finalised once the Draft Watermark has been removed. If the Draft Watermark is present, the information in the OWMP is not confirmed.

2 LEGISLATION & GUIDANCE

Waste management and resource recovery regulation in Australia is administered by the Australian Constitution, Commonwealth laws, and international agreements. State and territory governments maintain primary responsibility for controlling development and regulating waste. The following legislation has been enacted in New South Wales, and provides the lawful underpinnings of this OWMP.

- NSW Environmental Planning & Assessment Act 1979
- NSW Protection of the Environment Operations Act 1997
- NSW Waste Avoidance & Resource Recovery Act 2001

At the local level, councils or Local Government Areas (LGAs) require OWMPs to be included in new development applications. This OWMP is specifically required by:

- SEPP (Precincts - Central River City) 2021 Appendix 11
- Blacktown City Council Growth Centre Precincts DCP
- Blacktown Development Control Plan 2015 – Part 5 – Site Waste Management and Minimisation

The primary purpose of a development control plan (DCP) is to guide development according to the aims of the corresponding local environmental plan (LEP). The DCP must be read in conjunction with the provisions of the relevant LEP.

Information provided in this OWMP comes from a wide range of waste management guidance at the local, state, and federal levels. The primary sources of guidance include:

- Blacktown Council's *Guidelines For Waste Management In New Developments* 2021
- NSW Department of Education's *Educational Facilities Standards and Guidelines Requirement DG02 (2.7.2)*
- NSW Better Practice Guide for Resource Recovery in Residential Developments 2019
- NSW Waste Avoidance and Resource Recovery (WARR) Strategy 2014-2021
- NSW Waste Classification Guidelines 2014
- Australia's National Waste Policy 2018

2.1 PLANNING SECRETARY'S ENVIRONMENTAL ASSESSMENT REQUIREMENTS – 18. WASTE

The following table identifies the relevant SEARs items and where these are addressed in this report and the accompanying Construction and Demolition Waste Management Plan:

Table 1: SEARs Items

Item	Corresponding Section
Identify, quantify and classify the likely waste streams to be generated during construction and operation.	Section 4 of the OWMP and Section 3 of the C&D WMP.
Provide the measures to be implemented to manage, reuse, recycle and safely dispose of this waste.	Sections 6-of the OWMP and Sections 2-3 of the C&D WMP.
Identify appropriate servicing arrangements (including but not limited to, waste management, loading zones, mechanical plant) for the site.	Section 4.4 of the OWMP and Section 3.5 of the C&D WMP.
Provide a hazardous materials survey of existing aboveground buildings that are proposed to be demolished or altered.	Site is Vacant and no demolitions is proposed.

3 DEVELOPMENT OVERVIEW

Construction of two new schools, new high school in Marsden Park and new primary school in Melonba, located at 20 Kaluta Avenue and 10 Swallowtail Street, Melonba.

Marsden Park new high school is a new secondary school comprising:

- 97 general learning spaces (GLS) and specialist teaching spaces;
- Three supported education learning unit (SELU) rooms;
- School hall, and lecture and movement studio;
- Administration spaces;
- Staff and student facilities;
- Library;
- Canteen;
- Sports courts;
- Playing field;
- Landscaping and outdoor learning areas;
- Covered outdoor learning area (COLA); and
- Car parking (shared with Melonba new primary school).

Melonba new primary school will comprise:


- 44 GLS;
- Three SELU rooms;
- Administration and staff facilities;
- Canteen;
- Multi-purpose hall;
- Library;
- Out of School Hours Care (OSHC);
- COLA;
- Outdoor play areas including sports courts; and
- Landscaped outdoor learning areas.

The new high school in Marsden Park will cater for high school for 2000 students and Melonba new primary school' will cater for 1000 primary school students.

3.1 SITE LOCATION

The site is located at 20 Kaluta Avenue and 10 Swallowtail Street, Melonba, which is within the Central River City Precinct and Blacktown Local Government Area (LGA). The site is irregular in shape and is sited between two tributaries of Little Creek. The site is generally level but has a gentle fall from the south-eastern corner (RL23) to the north western corner (RL19.5). The site contains no vegetation other than grass and is currently fenced to prevent unauthorised access.

Figure 1. Site Location



Source: Google Maps

4 WASTE MANAGEMENT

The following section outlines best practice waste management for the primary and high schools, including waste generation estimates and waste disposal and collection procedures.

4.1 WASTE GENERATION ESTIMATES

The NSW *Better Practice Guide For Resource Recovery In Residential Developments* 2019 has been referenced to calculate the total number of bins required for the schools. It is assumed that the waste and recycling generation rates from the NSW EPA's *Better Practice Guide For Resource Recovery In Residential Developments* 2019 for educational facilities actually reflects weekly generation per student.

Calculations are based on generic waste and recycling rates. Actual volumes of waste and recycling generated in operation may differ according to the schools' actual waste management practice.

The following table shows the estimated volume in litres of general waste and recyclables that will be generated by schools as well as the recommended number of bins for the site.

It is assumed that all operations within the site will share a bin storage area and collection services but the bins will be kept separate.

Table 2: Estimated Volumes of General Waste and Recycling – Primary School

Waste Generation Rate Type	Students	General Waste Generation Rates (L/student/week)	Generated Garbage (L/week)	Recycling Generation Rate (L/student/week)	Generated Recycling (L/week)
Schools: Primary	1000	15	15000	20	20000
TOTAL	1000		15000		20000
Equipment and Collections	General Waste Bin Size (L)		1100	Recycling Bin Size (L)	1100
	General Waste Bins Per Week		14	Recycling Bins Per Week	19
	General Waste Collections per Week		3	Recycling Collections per Week	3
	Total General Waste Bins Required		5	Total Recycling Bins Required	7

Table 3: Estimated Volumes of General Waste and Recycling – High School

Waste Generation Rate Type	Students	General Waste Generation Rates (L/student/week)	Generated Garbage (L/week)	Recycling Generation Rate (L/student/week)	Generated Recycling (L/week)
Schools: Secondary	2000	20	40000	15	30000
TOTAL	2000		40000		30000
Equipment and Collections	General Waste Bin Size (L)		1100	Recycling Bin Size (L)	1100
	General Waste Bins Per Week		37	Recycling Bins Per Week	28
	General Waste Collections per Week		3	Recycling Collections per Week	3
	Total General Waste Bins Required		<u>13</u>	Total Recycling Bins Required	<u>10</u>

4.2 BIN SUMMARY

The estimates above reflect the total volumes of waste and recycling and the bins required to handle these volumes between collections. For the purposes of sizing the waste rooms, the bins have been calculated as general waste and general recycling.

The recommended bin quantities and collection frequencies are as follows:

Primary School

General Waste: 5 x 1100L MGBs collected **3 times weekly (approx. every 2 days)**

General Recycling: 7 x 1100L MGBs collected **3 times weekly (approx. every 2 days)**

High School

General Waste: 13 x 1100L MGBs collected **3 times weekly (approx. every 2 days)**

General Recycling: 10 x 1100L MGBs collected **3 times weekly (approx. every 2 days)**

During operation, bin sizes, quantities, and/or collection frequencies may be modified by the building manager. Building management will be required to negotiate any changes to bins or collections with the collection service provider. Seasonal peak periods such as school terms should also be considered.

The general waste and general recycling can be further divided into more specific waste and recycling streams to increase recovery. The general waste stream can be separated into landfill waste, food waste and soft plastics recycling. The general recycling can be divided into co-mingled recycling, glass recycling and refundable containers. It is recommended that the further separation of waste streams is conducted once the site is operational to best reflect the operations of the site and the proportion of each waste stream generated. It is recommended that annual waste audits are conducted to help understand the composition and total volumes of each waste stream generated during operation.

4.3 WASTE DISPOSAL PROCEDURES

All operations within the site share Bin Storage Area and collection services, however each school will have their own bins.

The Bin Storage Area for the schools will be located on the ground level, near the loading area. The Bin Storage Area will contain 1100L mobile garbage bins (MGBs) for the collection of the waste and recycling. The groundskeeper, waste collection staff and cleaners will be the only personnel with access to the waste storage areas. All transportation of waste and recycling must be co-ordinated with the groundskeeper or cleaners.

Suitably labelled waste and recycling receptacles or bins approx. 20L in size will be placed in each room and throughout the campus grounds. Garbage and recycling receptacles should be provided in convenient locations and areas of high waste generation.

The students, staff and visitors will be responsible for placing their waste and recycling into the correct receptacle. The fullness of the source separation bins will be monitored by groundskeeper and cleaners.

The cleaners will circulate throughout the campus after hours and empty the waste and recycling receptacles situated throughout the school. The cleaners will then transport the waste and recycling to the bulk bins in the Bin Storage Area and dispose of the waste and recycling into the appropriate bins.

4.4 WASTE COLLECTION PROCEDURES

A private waste collection contractor will be engaged to service the waste and recycling bins per an agreed schedule. The collections will be in accordance with the Department of Education's contracts with a private waste collection service.

On the day of service, a private waste collection vehicle will enter the site from Galah St and park in the loading bay adjacent to the bin storage area, (see Appendix A.1).

The waste collection staff will collect the bins from the Bin Storage Area.

Once the bins are serviced, the collection vehicle will exit the site onto Galah St in a forward direction.

4.5 OTHER WASTE MANAGEMENT CONSIDERATIONS

4.5.1 BATHROOMS

Washroom facilities should be supplied with collection bins for paper towels (if used). The cleaners will empty the washroom bins as required.

Sanitary bins for female restroom facilities must also be arranged with an appropriate contractor.

4.5.2 CANTEEN

The canteen staff will be responsible for their own storage of garbage and recycling back of house (BOH) during daily operations. On completion of each day or as required, nominated staff or cleaners will transport their garbage and recycling to the waste areas and place garbage and recycling into the appropriate collection bins.

A high density of waste and recycling bins should be placed around the canteen dining areas as this area will be a hotspot for waste and recycling generation.

4.5.3 LIQUID WASTE

Liquid wastes such as cleaning products, chemicals, paints, and cooking oil, etc., will be stored in a secure space that is bunded and drained to a grease trap in accordance with State government authorities and legislation.

4.5.4 PROBLEM WASTE

The building manager is responsible for making arrangements for the disposal and recycling of problem waste streams with an appropriate contractor. Problem wastes cannot be placed in general waste as they can have adverse impacts to human health and the environment if disposed of in landfill. School staff will need to liaise with the building manager when disposing of problem waste streams.

Problem waste streams include:

- Chemical Waste
- Liquid wastes
- Toner cartridges
- Lightbulbs
- eWaste
- Batteries

4.5.5 FUTURE WASTE AND RECYCLING STREAM SEPARATION

To design the Bin Storage Area and waste facilities in the site, all possible waste and recycling streams have been grouped together into 'general waste' and 'general recycling'. This is to ensure the waste facilities have adequate capacity to manage total volumes of waste and recycling streams, regardless of the management of waste and recycling during operation.

Once the school is operational, the school management can choose to separate the general recycling stream and the general waste stream into more specific recyclable waste streams. This allows the site's waste management system to have greater potential to divert waste from landfill and contribute to wider environmental sustainability.

The more waste streams that are separated, the more complex the waste management strategy becomes. In turn, it is likely to increase operational cost, manual input of building caretaker and cleaners as well as the level of engagement required by all stakeholders involved in waste management. Therefore, it is recommended that the decision to separate and manage any additional waste streams comes from the school management, once the school is operational, and is directed by the operational experience and needs of the school.

As identified in NSW Department of Education *Educational Facilities Standards and Guidelines Requirement DG02 (2.7.2)* the waste streams that can be managed at schools are as follows;

- Food Organics and Garden Organics
- Co-Mingled Container Recycling
- Paper & Cardboard Recycling
- Container Deposit Scheme Recycling
- Soft Plastic Recycling
- General Waste
- Other waste streams such as batteries, e-waste, coffee cups

The school management can choose which waste streams are handled in the waste management strategy at any time by assessing the composition of waste and recycling generated in operation as well as the costs/benefits at that time.

The successful separation of the waste streams is significantly impacted by the behaviours of the waste generators and the key personnel who look after the waste management systems. At this site, most of the waste generators will be high school aged children/teenagers. The managers of the waste system will be the building manager and grounds keeper.

The following are the key responsibilities required for successful ongoing source separation. These responsibilities should be taken into consideration when assessing whether to introduce the separation and management of more waste streams.

Responsibilities of the waste stream generator:

- Correctly identify the waste type.
- Place the waste item into the correct bin.
- Pending on waste item, partially dismantle waste item into different stream types (e.g. empty food waste into organics, lid into recycling and main container into landfill)

Responsibilities of the key staff managing the waste systems:

- Provide source separation bins in convenient locations.
- Monitor contamination of waste streams.
- Organise contracts with collection and recycling services of all waste streams.
- Educate waste stream generators on a ongoing basis
- Provide signage on all bins.
- Monitor and correct any issues.

If the management of any additional waste stream is introduced during operation, the school management would be responsible for setting up and maintaining the waste stream management procedures. Including;

- The provision of appropriate source separation bins around the campus.
- The update all waste related signage and waste management education material.
- The introduction of the collection bins of the waste stream in the Bin Storage Area.
- The reduction to the number of bins(or size of bins) for the general waste or general recycling stream being diverted.
- Engaging a specialist contractor to collect the bins and recycle the waste stream.
- Ensuring the collection timetables minimise conflicts with the loading area.
- Educating all staff and students on the new procedures, including which items are accepted in each bin.

Separation of food waste and soft plastic recycling streams will reduce the volume of general waste. Therefore, it is assumed that the number of general waste bins would go down by the corresponding number of food waste bins and or/soft plastic bins.

Separation of co-mingled recycling, paper & cardboard recycling and items refundable under the container deposit scheme will reduce the volume of general recycling. Therefore, it is assumed that the number of general recycling bins would go down by the corresponding number of co-mingled, paper & cardboard and refundable container bins introduced.

In addition, as identified in NSW Department of Education's *Educational Facilities Standards and Guidelines Requirement DG02 (2.7.2)*, during operation the school management can implement measures to reduce the volumes of waste generated by;

- Examining all processes to determine where wastes are produced and to devise measure for waste prevention or reduction.
- Devising ways of recycling waste with students so they too can share in the savings (for example rewards for students who reduce waste).
- Partnering with other organisations to assist with waste minimisation.
- Keep track of changes and improvements
- Reusing drums, cartridges and containers where possible
- Selling or donating usable waste materials to other organisations.

5 STAKEHOLDER ROLES & RESPONSIBILITIES

The following table demonstrates the primary roles and responsibilities of the respective stakeholders:

Table 4: Stakeholder Roles and Responsibilities

Roles	Responsibilities
Site Management	- Ensuring that all waste service providers submit regular (i.e monthly) reports on all equipment movements and waste quantities/weights; - Organising internal waste audits/visual assessments on a regular basis; and - Manage any non-compliances/complaints reported through waste audits.
School Management or Groundskeeper	- Ensuring effective signage, communication and education is provided to students, staff and cleaners; - Providing staff/contractors with equipment manuals, training, health and safety procedures, risk assessments, and PPE to control hazards associated with all waste management activities; - Ensuring site safety for students, visitors, staff and contractors; - Abiding by all relevant OH&S legislation, regulations, and guidelines; - Assessing any manual handling risks and prepare a manual handling control plan for waste and bin transfers; - Preventing storm water pollution by taking necessary precautions (securing bin storage area, preventing overfilling of bins) - Cleaning and transporting of bins as required; - Organising, maintaining and cleaning the general and recycled waste holding area; - Organising both garbage and recycled waste pick-ups as required; - Organising replacement or maintenance requirements for bins; - Organising bulky goods collection when required; and - Investigating and ensuring prompt clean-up of illegally dumped waste materials.
Cleaners, Staff and Students	- Dispose of all garbage and recycling in the allocated MGBs provided; - Ensure adequate separation of garbage and recycling; and - Compliance with the provisions of Council and the WMP.
Private Waste Contractor	- Provide a reliable and appropriate waste collection service; - Provide feedback to School Caretaker in regards to contamination of recyclables; and - Work with building managers to customise waste systems where possible.
Gardening/Landscaping Contractor	Removal of all garden organic waste generated during gardening maintenance activities for recycling at an offsite location.
Building Contractors	Removing all construction related waste offsite in a manner that meets all authority requirements.

6 SOURCE SEPARATION

Better practice waste management includes the avoidance, reuse, and recovery of unwanted items, which can be achieved through source separation. The table below outlines what is typically included in various waste streams and how they can be managed. Refer to your local council for a list of accepted materials. Planet Ark can be accessed online to find other facilities that recover unwanted items.

Table 5: Operational Waste Streams

Waste Stream	Description	Typical Destination	Waste Stream Management
General Waste	The remaining portion of the waste stream that is not recovered for re-use, processing, or recycling. May include soft plastics, food scraps, polystyrene, etc.	Landfill	Waste should be bagged before placing in the designated waste bins.
Recycling	A mixture of items that are commonly recycled usually segregated through a MRF. Typically include food and beverage containers (e.g. aluminium, glass, steel, hard plastics, cartons). Also included cardboard and paper products.	Resource Recovery Centre	Recycling must not be bagged, and instead should be placed loosely in the designated recycling bins. Cardboard should be flattened before placing in the designated cardboard bin.
Secure Documents	Secure documents are printed paper materials that contain sensitive information.	Recycling Facility	Secure documents are placed in allocated secure document bins. Private contractor removes bins from site.
Green Waste	Green waste consists of unwanted organic materials that are easily biodegradable and/or compostable (e.g. lawn clippings, branches)	Resource Recovery Centre	Landscape Maintenance Contractors will remove the green waste from site during scheduled maintenance.
Food Waste	Food waste consists of unwanted or uneaten kitchen scraps that are easily compostable/biodegradable (e.g. vegetable peels, fruit rinds, coffee grounds).	Composting facility or Landfill	Food waste can be composted on-site, off-site, or else included in the general waste stream.
Electronic Waste	Discarded e-waste, electronic components and materials such as computers, mobile phones, keyboards, etc.	Resource Recovery Centre	A location should be dedicated to the storage of e-waste. When a suitable amount has been accumulated, the Grounds Keeper or school management is responsible for arranging the collection of e-waste with an appropriate recycling service.
Bulky Items	Items that are too large to place into general rubbish collection. This includes disused and/or broken furniture, mattresses, white goods, etc.	Resource Recovery Centre or Landfill	A location should be dedicated to the storage of bulky waste. When a suitable amount has been accumulated, the Grounds Keeper or school management is responsible for arranging the collection of bulky waste with an appropriate recycling service.
Sanitary Waste	Feminine hygiene waste generated from female bathrooms.	Incineration or Landfill	Sanitary bins are serviced by sanitary waste contractor.
Other	Other recyclable items that require special recovery may include ink cartridges, batteries, chemical waste, fluorescent tubes, etc.	Resource Recovery Facility	Grounds Keeper or school management arranges collection by appropriate recycling services when required.

7 EDUCATION

The school management is responsible for creating and implementing the waste management education process.

Educational material encouraging the correct separation of garbage and recycling items must be provided to each staff member, cleaners and students to ensure the correct disposal of waste and minimise the possibility of contamination in the waste and recycling bins.

It is recommended that the school investigates programs to teach students about recycling and resource recovery. These programs can be implemented into the operation of the school to reduce overall waste generation.

7.1 SIGNAGE

Signage and education are essential components to support best practice waste management including resource recovery, source separation, and diversion of waste from landfill.

Signage should include:

- Clear and correctly labelled waste and recycling bins,
- Instructions for separating and disposing of waste items. Different languages should be considered,
- Locations of, and directions to, the waste storage areas with directional signs, arrows, or lines,
- The identification of all hazards or potential dangers associated with the waste facilities, and
- Emergency contact information should there be issues with the waste systems or services in the building.

The school management is responsible for waste room signage including safety signage. Appropriate signage must be prominently displayed on doors, walls and above all bins, clearly stating what type of waste or recyclables is to be placed in each bin.

All signage should conform to the relevant Australian Standards.

7.2 POLLUTION PREVENTION

The Groundskeeper shall be responsible for the following to minimise dispersion of site litter and prevent stormwater pollution to avoid impact to the environment and local amenity:

- Promoting adequate waste disposal into the bins
- Securing all bin storage areas (whilst affording access to staff/contractors)
- Prevent overfilling of bins, keep all bin lids closed and bungs leak-free
- Taking action to prevent dumping or unauthorised use of waste areas
- Require collection contractor/s to clean up any spillage when clearing bins

9 WASTE ROOMS

The areas allocated for waste management are detailed in the table below, and are estimates only. Final areas will depend on room and bin layouts.

To design the school's Bin Storage Area, all possible waste and recycling streams have been grouped together into 'general waste' and 'general recycling', as detailed in the table below. This is to ensure the waste facilities have adequate capacity to manage total volumes of waste and recycling streams, regardless of the management of waste and recycling during operation. At Any time during the operation of the school, at the school management's discretion, the waste streams separated from the 'general waste' or 'general recycling streams can be adjusted General waste and general recycling can be separated into any of the following waste streams;

General Waste:

- Food waste and Garden Organics
- Soft Plastic Recycling
- Waste (landfill disposal only)

General Recycling:

- Food waste and Garden Organics
- Soft Plastic Recycling
- General Waste (landfill disposal only)

As further separation of waste streams will reduce the volume of general waste or general recycling, it is assumed that the number of general waste bins or general recycling bins would go down by the corresponding number of bins. Thus, the space within Bin Storage Area required to store the bins should remain consistent.

Table 6: Waste Room Areas

Level	Waste Room Type	Equipment	Estimated Area Required (m ²)
G	Bin Storage Area (collection area)	<i>Primary School</i> 5x 1100L MGBs (waste) 7x 1100L MGBs (recycling) <i>High School</i> 13x 1100L MGBs (waste) 10x 1100L MGBs (recycling)	>95

The waste room areas have been calculated based on equipment requirements and/or bin dimensions with an additional 70% of bin GFA factored in for manoeuvrability. The following table provides further waste room requirements.

Table 7: Waste Room Requirements

Waste Room Type	Waste Room Requirements
Bin Storage Area	• In order to ensure staff safety, all bins should be arranged so they can be accessed without moving another bin

	• All doorways and passageways facilitating the movement of bins and/or bulky waste items must be at least 1700mm
Bulky Goods Waste Storage Room	• May be a dedicated room or screened area within another waste room • Must be in close proximity to the collection area • Area must also be allocated for the segregation of e-waste, gas bottles, cardboard, etc. • Doorway should be a minimum of 1500mm wide

10 BIN MOVING PATHS

The cleaners are responsible for the transportation of bins from their designated operational locations to the collection area when full and returning them once emptied to resume operational use. Typically waste and recycling is transported using trollies containing other cleaning equipment.

Transfer of bins should minimise manual handling where possible, as bins become heavy when full. The building manager must assess manual handling risks and provide any relevant documentation to key personnel.

The routes along the bin moving path should;

- Allow for a continuous route that is wholly within the property boundary.
- Be free from obstruction and obstacles such as steps and kerbs.
- Be constructed of solid materials with a non-slip surface
- Be A minimum of 300mm wider than the largest bin used onsite.
- If bins are moved manually, the route must not exceed a grade of 1:14.
- If a bin moving device is used, the route cannot exceed the maximum operating grade of the device. This is typically a grade of 1:4, however this will vary depending on the model of bin moving device acquired for the site.

Bin moving devices maybe needed to aid the movement of waste and recycling over longer distances.

11 CONSTRUCTION REQUIREMENTS

Waste room construction must comply with the minimum standards as outlined in the *Blacktown Development Control Plan 2015*, in order to minimise odours, deter vermin, protect surrounding areas, and make it a user-friendly and safe area.

The *NSW Better practice guide for resource recovery in residential developments (2019)* also states that better practice bin storage areas should achieve more than the minimum compliance requirements, which are as follows:

- Ensuring BCA compliance, including ventilation. Where required, ventilation system must comply with AS1668.4-2012 The use of ventilation and air conditioning in buildings.
- Ensuring storage areas are well lit (sensor lighting preferred) and have lighting available 24 hours a day.
- Provision of bin washing facilities, including taps for hot and cold water provided through a centralised mixing valve. The taps must be protected from bins and be located where they can be easily accessed even when the area is at bin capacity.
- Floor constructed of concrete at least 75mm thick.
- Floor graded so that any water is directed to a sewer authority approved drainage connection to ensure washing bins and/or waste storage areas do not discharge flow into the stormwater drain.
- Provision of smooth, cleanable and durable floor and wall surfaces that extend up the wall to a height equivalent to any bins held in the area.
- Ensuring ceilings are finished with a smooth-faced non-absorbent material capable of being cleaned.
- All surfaces (walls, ceiling and floors) finished in a light colour.

11.1 ADDITIONAL CONSIDERATIONS

- Waste room floor to be sealed with a two-pack epoxy;
- All corners coved and sealed 100mm up, this is to eliminate build-up of dirt;
- Tap height and light switch height of 1.6m;
- Storm water access preventatives (grate);
- All walls painted with light colour and washable paint;
- Equipment electric outlets to be installed 1700mm above finished floor level;
- Optional automatic odour and pest control system installed
- If 660L or 1100L bins are utilised, 2 x 820mm (minimum) double-doors must be used;
- All personnel doors are hinged, lockable and self-closing;
- Conform to the Building Code of Australia, Australian standards and local laws; and
- Childproofing and public/operator safety shall be assessed and ensured
- Waste and recycling rooms must have their own exhaust ventilation system either;
 - Mechanically - exhausting at a rate of 5L/m² floor area, with a minimum rate of 100L/s minimum; Mechanical exhaust systems shall comply with AS1668.4.2012 and not cause any inconvenience, noise or odour problem or
 - Naturally - permanent, unobstructed, and opening direct to the external air, not less than one-twentieth (1/20) of the floor area.

12 USEFUL CONTACTS

EFC does not warrant or make representation for goods or services provided by suppliers.

PRIVATE WASTE COLLECTION PROVIDER

Capital City Waste Services	Ph: 02 9599 9999	E: service@ccws.net.au
Remondis	Ph: 02 9032 7100	
Suez Environmental	Ph: 13 13 35	
Wastewise NSW	Ph: 1300 550 408	E: admin@wastewise.com.au

BIN MOVING DEVICE SUPPLIERS

Electrodrive	Ph: 1800 333 002	E: sales@electrodrive.com.au
Sitecraft	Ph: 1300 363 152	E: sales@sitecraft.com.au
Spacepac	Ph: 1300 763 444	

ORGANIC DIGESTERS AND DEHYDRATORS

Closed Loop	Ph: 1300 762 166	
Orca		E: contact.australia@feedtheorca.com
Soil Food	Ph: 1300 556 628	
Green Eco Technologies	Ph: 1800 614 272	E: equires@greenecotec.com

COOKING OIL CONTAINERS AND DISPOSAL

Auscol	Ph: 1800 629 476	E: sales@auscol.com
--------	------------------	---

ODOUR CONTROL

EF Neutralizer	Ph: 1300 435 374	E: info@elephantsfoot.com.au
----------------	------------------	---

SOURCE SPERATION BINS

Source Separation Systems	Ph: 1300 739 913	E: info@sourceseparationsystems.com.au
---------------------------	------------------	---

MOBILE GARBAGE BINS, BULK BINS AND BIN EQUIPMENT


SULO	Ph: 1300 364 388	E: sales@sulo.com.au
OTTO Australia	Ph: 02 9153 6999	

CHUTES, COMPACTORS AND EDIVERTER SYSTEMS

Elephants Foot	Ph: 1800 025 073	E: info@elephantsfoot.com.au
----------------	------------------	---

APPENDIX A: ARCHITECTURAL PLANS

APPENDIX: A.1 GROUND FLOOR PLAN – WASTE FACILITIES



Source: NBR Architecture, Drawing No 21466-NBR-DR-A-0201, Rev 3, Aug2022 – Site Plan

APPENDIX B: PRIMARY WASTE MANAGEMENT PROVISIONS

APPENDIX: B.1 TYPICAL BIN SPECIFICATIONS

Mobile bins

Mobile bins come in a variety of sizes and are designed for lifting and emptying by purpose-built equipment.

Mobile bins with capacities of up to 1700L must comply with *AS4123.6-2006 Mobile waste containers* which specifies standard sizes and sets out the colour designations for the bodies and lids of mobile waste containers indicating the type of materials they are used to collect.

The most common bin sizes are provided below, although not all sizes are shown. The dimensions are a guide only and differ slightly between manufacturers. Some bins have flat or domed lids and are used with different lifting devices. Refer to *AS4123.6-2006* for further details.

Table G1.1: Average dimension ranges for two-wheel mobile bins



Bin capacity	80L	120L	140L	240L	360L
Height (mm)	870	940	1065	1080	1100
Depth (mm)	530	530	540	735	820
Width (mm)	450	485	500	580	600
Approximate footprint (m ²)	0.24	0.26–0.33	0.27–0.33	0.41–0.43	0.49
Approximate weight (kg)	8.5	9.5	10.4	15.5	23
Approximate maximum load (kg)	32	48	56	96	Not known

Wheelie bin

Sources include Sulo, Single Waste, Cleanaway, SUEZ, just wheelie bins and Perth Waste for two-wheel mobile bins

Table G1.2: Average dimension ranges for four-wheel bulk bins



Bin capacity	660L	770L	1100L	1300L	1700L
Height (mm)	1250	1425	1470	1480	1470
Depth (mm)	850	1100	1245	1250	1250
Width (mm)	1370	1370	1370	1770	1770
Approx footprint (m ²)	0.86–1.16	1.51	1.33–1.74	2.21	2.21
Approx weight (kg)	45	Not known	65	Not known	Not known
Approx maximum load (kg)	310	Not known	440	Not known	Not known

Dome or flat lid container

Sources include Sulo, Signal Waste, Cleanaway, SUEZ, Just Wheelie Bins and Perth Waste

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

APPENDIX: B.2 SIGNAGE FOR WASTE AND RECYCLING BINS

Waste signs

Signs and educational materials perform several functions including:

- informing residents why it is important to recover resources and protect the environment
- providing clear instructions on how to use the bins and services provided
- alerting people to any dangers or hazards within the bin storage areas.

All waste, recycling and organic bins should be Australian Standard colours and clearly and correctly labelled, such as by a sticker on the lid and/or the body of the bin.

Communal bin storage areas should be clearly signposted with signs outlining how to correctly separate waste into the bins provided. The local council responsible for waste services may be a good source of signs and posters and can advise on what signs are suitable.

Information on who to contact to find out more about the recycling and/or other resource recovery services in the building should also be displayed in communal areas, such as on a noticeboard.

The Planet Ark website also has resources available free of charge for use by businesses and councils. These signs can be found at businessrecycling.com.au/research/signage.cfm

Figure I1.1: Examples of waste wall posters (EPA supplied)



Figure I1.2: Examples of bin lid stickers (EPA supplied)



Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

Problem waste signs

The EPA has also produced a range of images and signs that can be used for problem wastes, such as fluoro globes and tubes, household and car batteries, e-waste and smoke detectors. To access these resources, contact the NSW EPA. Some examples are shown below.

Figure I2.1: Problem waste signs



Safety signs

The use of safety signs for waste resource recovery rooms must comply with *AS1319 Safety signs for occupational environments*. Safety signs must be used to regulate and control safety related to behaviour, warn of hazards and provide emergency information, including fire protection information. Suitable signs should be decided for each development as required.

Figure I3.1: Example safety signs



Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

APPENDIX: B.3 TYPICAL COLLECTION VEHICLE INFORMATION

General

Appropriate heavy rigid vehicle standards should be incorporated into the road and street designs in new developments where onsite collections are proposed. Road and street designs must comply with relevant Acts, regulations, guidelines, and codes administered by Austroads, Standards Australia, NSW Roads and Maritime Services, WorkSafe NSW and any local council traffic requirements.

Applicants and building designers should consult with councils and other relevant authorities before designing new roads or streets and access points for waste collection vehicles to establish specific design requirements.

Table H4.1: Australian Standards for turning circles for medium and heavy rigid class vehicles

Vehicle class	Overall length (m)	Design width (m)	Design turning radius (m)	Swept circle (m)	Clearance (travel) height (m)
Medium rigid vehicle	8.80	2.5	10.0	21.6	4.5
Heavy rigid vehicle	12.5	2.5	12.5	27.8	4.5

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

Large collection vehicles

Waste collection vehicles may be side-loading, rear-loading, front-lift-loading, hook or crane lift trucks. Vehicle dimensions vary by collection service, manufacturer, make and model. It is not possible to provide definitive dimensions, so architects and developers should consult with the local council and/or contractors.

The following characteristics represent typical collection vehicles and are provided for guidance only. Reference to *AS2890.2 Parking facilities: off-street commercial vehicle facilities* for detailed requirements, including vehicle dimensions, is recommended.

Table B2.1: Collection vehicle dimensions


Vehicle type	Rear-loading	Side-loading*	Front-lift-loading	Hook truck	Crane truck
Length overall (m)	10.5	9.6	11.8	10.0	10.0
Width overall (m)	2.5	2.5	2.5	3.0	2.5
Travel height (m)	3.9	3.6	4.8	4.7	3.8
Operational height for loading (m)	3.9	4.2	6.5	3.0	8.75
Vehicle tare weight (t)	13.1	11.8	16.7	13.0	13.0
Maximum payload (t)	10.0	10.8	11.0	14.5	9.5
Turning circle (m)	25.0	21.4	25.0	25.0	18

* The maximum reach of a side arm is 3 m.

Sources: JJ Richards, SUEZ, MacDonald Johnson, Cleanaway, Garwood, Ros Roca, Bingo and Edbro. Figures shown represent the maximum dimensions for each vehicle type.

Rear-loading collection vehicles

These vehicles are commonly used for domestic waste collections from MUDs and RFBs and sometimes for recycling. They can be used to collect waste stored in mobile bins or bulk bins, particularly where bins are not presented at the kerbside. They are also used for collecting bulky waste.



Rear-loading waste collection vehicle

Side-loading collection vehicles

This is the most commonly used vehicle for domestic waste, recycling and organics collections. It is only suitable for collecting mobile bins up to 360L in capacity.



Side-loading waste collection vehicle

Front-lift-loading collection vehicles

These vehicles are commonly used for collecting commercial and industrial waste. They can only collect specially designed front-lift bulk bins and not mobile bins.



Front-lift-loading waste collection vehicle

Small collection vehicles

Typically, councils and their contractors operate with large collection vehicles (heavy rigid class vehicles) because they carry greater payloads and allow for more cost-effective collection services. Some councils, or their contractors, may have smaller collection vehicles in their fleet. Early discussion with the council is important to confirm this, but it should not be assumed that the council will have access to small collection vehicles.

The waste management systems and the location of the collection point should always be designed so that the council can provide the standard domestic waste service.

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority