Birds Tree Consultancy

Consulting Arborist AQF5/8 • Expert Witness • Environmental Arboriculture • Resistograph Testing



ARBORICULTURAL DEVELOPMENT IMPACT ASSESSMENT REPORT

4-6 Bligh Street Sydney NSW

REVISION A 22nd of December 2022

Prepared for

Holdmark

Prepared by

Birds Tree Consultancy Glenn Bird Grad Cert Arboriculture Uni Melb (AQF8) Dip. Hort (Arboriculture) (AQF5) PO Box 6048 DURAL NSW 2158 PH 0438 892 634 glenn@birdstrees.com.au www.birdstrees.com.au ABN 31 105 006 657



Executive Summary

This Arboricultural Development Impact Assessment Report has been commissioned by Holdmark to report on trees within the site of 4-6 Bligh Street Sydney NSW. The subject trees are located within the public domain adjacent to the western boundary of this site. This site is currently an existing commercial building. The site is proposed for redevelopment including the demolition of the existing building and construction of new commercial building, basement car parking, driveway entry, and associated landscape works. This report has been commissioned to outline the health, condition and stability of these trees as well as their viability for retention within the scope of the proposed development. The scope of this report includes all trees within areas that may be impacted by the proposed development.

The subject Trees are preserved under Section 3 of City of Sydney Development Control Plan 2012 and are in good health and condition.

The proposed development will encroach the Tree Protection Zone (TPZ) of trees 2 and 3 by a minor encroachment in accordance with AS 4970-2009 Protection of Trees on Development Sites, however the proposed awning at a height of 25.91 will impact the crown of these trees at a height of between 4.5m and 5m. The impact of the awning and required scaffolding and hoarding will require crown reduction pruning which will remove 30-40% of the crown of these trees. These trees will remain viable to be retained under the proposed development however the crown reduction pruning required will significantly impact the crowns of these trees leaving the crown unbalanced and with an atypical form.

The current existing tree species are a mixture of *Lophostemon confertus* and *Celtis Australia*, both of which are within the Primary Tree Species Palette of the Northern Financial and Alfred Street Precinct within the current City of Sydney Street Tree Masterplan 2011 however the nominated street tree species for Bligh Street in this current Masterplan is *Lophostemon confertus*. Trees 1, 2, and 3 are viable to be retained however due to the anticipated impact of the awning, scaffolding and hoarding of the proposed development, consideration should be made to the opportunity to remove the existing trees and replace with species that meet the requirements of the current Street Tree Masterplan (*Lophostemon confertus*) or the Draft Street Tree Masterplan 2022 (*Waterhousea floribunda*).

The proposed landscape design as shown in 360 Landscape Plan – Ground Floor Rev D 15/12/2022 proposes to replace the existing street trees with Lophostemon confertus. Replacement of the existing trees with new planting of Lophostemon confertus would meet the objectives of the current City of Sydney Street Tree Masterplan 2011. Replacement of the existing trees would also allow formative pruning of the new trees to accommodate the proposed awning.

Contents

	utive Summary						
	ents						
1.0	Scope of Works						
2.0	Site Analysis	.4					
2.1	Site	.4					
2.2	Documentation	.4					
2.3	Topography	.4					
2.4	Identification	.4					
2.5	Soils	.4					
3.0	Existing Trees	. 5					
4.0	Landscape Significance of Trees						
4.1	Landscape Significance						
4.2	Methodology of Determining Landscape Significance						
4.3	Landscape Significance of Subject Trees						
5.0	Subject Tree Retention Value						
5.1	Tree Retention Value Methodology						
5.2	Retention Value of Subject Trees						
6.0	Impact of Development						
6 .1	Tree Protection Zone						
6.2	Structural Root Zone						
-							
6.3	Development Impact						
7.0	Recommendations						
8.0	Pre-Construction Tree Protection Measures						
8.1	General						
8.2	Identification						
8.3	Site Arborist						
8.4	Protective Fence						
8.5	Mulching						
8.6	Signage						
8.7	Trunk and Branch Protection	10					
9.0	Site Management Issues	10					
9.1	Soil Compaction	10					
9.2	Site Access	10					
9.3	Excavation within Tree Protection Area	11					
9.4	Possible Contamination / Storage of Materials	11					
10.0	Tree Protection Measures During Construction	11					
10.1	Maintenance of Pre-Construction Tree Protection Measures						
10.2	Possible Contaminants						
	Physical Damage						
	Compaction						
	Trenching						
	Irrigation/Watering						
	Site Sheds / Amenities/ Storage						
	Environmental / Heritage/ Legislative Considerations						
	References						
	Disclaimer						
	Appendix ALandscape Significance						
	ndix C - Tree Inspection Data						
мрре	ndix D - Tree Location Plan – Retention Value Plan	17					

1.0 Scope of Works

This Arboricultural Development Impact Assessment Report has been commissioned by Holdmark to report on trees within the site of 4-6 Bligh Street Sydney NSW. It has been commissioned to outline the health, condition and stability of these trees as well as their viability for retention within the scope of the proposed development. The scope of this report includes all trees within areas that may be impacted by the proposed development.

On the 2nd of December 2022, Glenn Bird of Birds Tree Consultancy attended site and inspected the subject trees from the ground. There was no aerial inspection carried out. A Visual Tree Assessment was undertaken in accordance with Visual Tree Assessment (VTA) guidelines (Mattheck and Breloer, 1994). Tree heights were measured using a Nikon Forestry 550 Heightmeter.

2.0 Site Analysis

2.1 Site

The subject site is the proposed 4-6 Bligh Street Sydney NSW. The subject trees are located within the public domain adjacent to the western boundary of this site. This site is currently an existing commercial building. The site is proposed for redevelopment including the demolition of the existing building and construction of new commercial building, basement car parking, driveway entry, and associated landscape works.

2.2 Documentation

This Development Impact Assessment Report has been compiled based on the following documentation provided:

- 1. CMS Surveyors Detail Survey Dated 27/04/2017.
- 2. Woods Bagot Floor Plan Basement level 1 Rev A 19/12/2022.
- 3. Woods Bagot Floor Plan Basement level 2 Rev A 19/12/2022.
- 4. Woods Bagot Floor Plan Basement level 3 Rev A 19/12/2022.
- 5. Woods Bagot Floor Plan Basement level 4 Rev A 19/12/2022.
- 6. Woods Bagot Floor Plan Basement level 5 Rev A 19/12/2022.
- 7. Woods Bagot Floor Plan Ground Floor Rev A 19/12/2022.
- 8. Woods Bagot Floor Plan Level 01 Rev A 19/12/2022.
- 9. Woods Bagot Northeast & Northwest Elevation Rev A 19/12/2022.
- 10. 360 Landscape Plan Ground Floor Rev D 15/12/2022

2.3 Topography

The site is relatively flat. Refer to detailed survey for detailed levels.

2.4 Identification

Trees are as identified in the attached inspection forms in Appendix C and shown in Tree location Plan A01 in Appendix D.

2.5 Soils

Soil material and horizons were not tested for this report.

3.0 Existing Trees

The following trees were inspected from the ground and the following items identified. Please refer also to the attached inspection data in Appendix C.

3.1. Tree 1. Lophostemon confertus

This semi-mature tree is approximately 6m tall with a canopy spread of 2m. It has a single trunk with a diameter at breast height (DBH) of 50mm. This tree is in good health and condition with minimal deadwood and epicormic growth.

3.2. Tree 2. Celtis australis This mature tree is approximately 9m tall with a canopy spread of 8m. It has a single trunk with a DBH of 290mm. This tree is in good health and condition with minimal deadwood and epicormic growth.

3.3. Tree 3. Celtis australis

This mature tree is approximately 10m tall with a canopy spread of 9m. It has a single trunk with a DBH of 270mm. This tree is in good health and condition with minimal deadwood and epicormic growth.

4.0 Landscape Significance of Trees

4.1 Landscape Significance

The significance of a tree within the landscape is a factor of the health and condition of the tree, vitality, the form of the tree, environmental, cultural, amenity and heritage value.

4.2 Methodology of Determining Landscape Significance

For the purpose of this report, the Significance of a Tree, Assessment Rating System (STARS) as developed by the Institute of Australian Consulting Arborists (IACA) has been implemented. Please refer to Appendix A for greater detail of this assessment system. This system defines Landscape Significance for individual trees as High, Medium or Low Significance.

4.3 Landscape Significance of Subject Trees

Based on our assessment of the subject trees and implementation of the IACA Significance of a Tree, Assessment Rating System, the Landscape Significance of the Subject Trees was determined as shown in Table 1.

Tree no.	Species	Landscape Significance
1.	Lophostemon confertus	Medium
2.	Celtis australis	Medium
3.	Celtis australis	Medium

Table 1 - Landscape Significance

5.0 Subject Tree Retention Value

5.1 Tree Retention Value Methodology

For the purpose of this report, the Tree Retention Values have been assessed by incorporating Landscape Significance Values as determined in 4.0 with the Useful Life Expectancy of the subject trees and assessing the retention values based on the Tree Retention Value Priority Matrix as developed by the Institute of Australian Consulting Arborists (IACA). Please refer to Appendix B for greater detail on this Tree Retention Value Priority Matrix. This matrix defines Landscape Significance for individual trees as High, Medium or Low Retention Value as well as Priority for Removal.

5.2 Retention Value of Subject Trees

Based on our assessment of the subject trees and implementation of the IACA Tree Retention Value Priority Matrix, the Retention Values of the Subject Trees were determined as shown in Table 2.

Tree no.	Species	Retention Value
1.	Lophostemon confertus	High
2.	Celtis australis	Medium
3.	Celtis australis	Medium

 Table 2 – Tree Retention Value

6.0 Impact of Development

6.1 Tree Protection Zone

Tree Protection Zones (TPZs) have been defined for the subject trees in order to define the encroachment of the proposed development in accordance with *AS4970-2009*. The TPZs required have been taken as a circular area with a radius 12 x the diameter at breast height of the tree. This requirement is in line with Australian Standard AS 4970-2009 Protection of Trees on Development Sites. This standard defines a maximum of 10% encroachment to be minimal encroachment. Any encroachment over 10% requires the site arborist to give consideration as to the viability of the tree due to the proposed development.

6.2 Structural Root Zone

Structural Root Zone (SRZs) are defined by AS4970-2009 as the area of root development required for the structural stability of the tree. The SRZ is required to be assessed only when an encroachment greater than 10% is considered.

Tree no.	Species	TPZ Radius (m)	Encroachment (%)	SRZ Radius (m) Encroached / Not Encroached
1.	Lophostemon confertus	2	5	1.20
2.	Celtis australis	3.48	5	2.18

3.	Celtis australis	3.24	0	2.08

6.3 Development Impact

6.3.1. Tree 1. Lophostemon confertus

The Tree Protection Zone (TPZ) of this tree in accordance with AS 4970-2009 Protection of Trees on Development Sites will not be further encroached by the proposed development. This tree will remain viable to be retained under the proposed development.

6.3.2. Tree 2. Celtis australis

At ground level, the Tree Protection Zone (TPZ) of this tree, in accordance with AS 4970-2009 Protection of Trees on Development Sites, will be encroached by the proposed development by a minor encroachment as defined by AS 4970-2009 however the proposed awning at a height of 25.91 will impact the crown of this tree at a height of between 4.5m and 5m. The impact of the awning and required scaffolding and hoarding will require crown reduction pruning which will remove 30-40% of the crown of this tree. This tree will remain viable to be retained under the proposed development however the crown of this tree leaving the crown unbalanced and with an atypical form.

6.3.3. Tree 3. Celtis australis

At ground level, the Tree Protection Zone (TPZ) of this tree, in accordance with AS 4970-2009 Protection of Trees on Development Sites, will be encroached by the proposed development by a minor encroachment as defined by AS 4970-2009 however the proposed awning at a height of 25.91 will impact the crown of this tree at a height of between 4.5m and 5m. The impact of the awning and required scaffolding and hoarding will require crown reduction pruning which will remove 30-40% of the crown of this tree. This tree will remain viable to be retained under the proposed development however the crown of this tree leaving the crown unbalanced and with an atypical form.

7.0 Recommendations

The subject Trees are preserved under Section 3 of City of Sydney Development Control Plan 2012 and are in good health and condition.

The proposed development will encroach the Tree Protection Zone (TPZ) of trees 2 and 3 at ground level by a minor encroachment in accordance with AS 4970-2009 Protection of Trees on Development Sites, however the proposed awning at a height of 25.91 will impact the crown of these trees at a height of between 4.5m and 5m. The impact of the awning and required scaffolding and hoarding will require crown reduction pruning which will remove 30-40% of the crown of these trees. These trees will remain viable to be retained under the proposed development however the crown

reduction pruning required will significantly impact the crowns of these trees leaving the crown unbalanced and with an atypical form.

The current tree species are a mixture of *Lophostemon confertus* and *Celtis Australia*, both of which are within the Primary Tree Species Palette of the Northern Financial and Alfred Street Precinct within the current City of Sydney Street Tree Masterplan 2011 however the nominated street tree species for Bligh Street in this current Masterplan is *Lophostemon confertus*. Trees 1, 2, and 3 are viable to be retained however due to the anticipated impact of the awning, scaffolding and hoarding of the proposed development, consideration should be made to the opportunity to remove the existing trees and replace with species that meet the requirements of the current Street Tree Masterplan (*Lophostemon confertus*) or the Draft Street Tree Masterplan 2022 (*Waterhousea floribunda*).

The proposed landscape design as shown in 360 Landscape Plan – Ground Floor Rev D 15/12/2022 proposes to replace the existing street trees with Lophostemon confertus. Replacement of the existing trees with new planting of Lophostemon confertus would meet the objectives of the current City of Sydney Street Tree Masterplan 2011. Replacement of the existing trees would also allow formative pruning of the new trees to accommodate the proposed awning.

Tree no.	Species	Recommendations	Comments
1.	Lophostemon confertus	Viable to be retained.	Viable to be retained and protected in accordance with 8.0.
2.	Celtis australis	Viable to be retained	Viable to retained with significant impact to crown. Consider replacement to meet requirements of City of Sydney Street Tree Masterplan.
3.	Celtis australis	Viable to be retained	Viable to retained with significant impact to crown. Consider replacement to meet requirements of City of Sydney Street Tree Masterplan.

8.0 **Pre-Construction Tree Protection Measures**

8.1 General

All tree protection works shall be carried out before excavation, grading and site works commence. Tree protection works shall be inspected and approved by a Consulting Arborist meeting AQF Level 5 prior to construction works commencing.

Storage of materials, mixing of materials, vehicle parking, disposal of liquids, machinery repairs and refueling, site office and sheds, and the lighting of fires, stockpiling of soil, rubble or any debris shall not be carried out within the TPZ of existing trees. No backfilling shall occur within the TPZ of existing trees. Trees shall not be removed or lopped unless specific instruction is given in writing by the Superintendent.

8.2 Identification

All trees to be protected shall be clearly identified and all TPZs surveyed.

8.3 **Project Arborist**

Prior to all site works commencing, a Site Arborist is to be appointed with the responsibility of implementing all Tree Protection Measures in this report as well as compliance with AS4970-2009 Protection of Trees on Development Sites. The Site Arborist is to hold qualifications equivalent of AQF Level 5.

8.4 **Protective Fence**

Fencing is to be erected around existing trees to be retained. In addition to this protective fencing within the site, Protective Fencing is to be installed to the full extent of the TPZs within the site. This fencing is to be erected prior to any materials being brought on site or before any site, civil works or construction works commence. The fence shall enclose a sufficient area so as to prevent damage to the TPZ as defined on Appendix D Tree Protection Plan and as defined in 5.1 above. Fence to comprise 1800mm high chain wire mesh fixed to 50mm diameter Galvanised steel posts. Panels should be securely fixed top and bottom to avoid separation. No storage of building materials, tools, paint, fuel or contaminants and the like shall occur within the fenced area.

8.5 Mulching

Install mulch to the extent of all tree protection fencing. Use a leaf mulch conforming to AS 4454 which is free of deleterious and extraneous matter such as soil, weeds, sticks and stones and consisting of a minimum of 90% recycled content compliant with AS 4454 (1999) and AS 4419 (1998). All trees marked as to be removed on the proposed development are to be chipped and reused for this purpose. Place mulch evenly and to a depth of 100mm.

8.6 Signage

Prior to works commencing, tree protection signage is to be attached to each tree protection zone, displayed in a prominent position and the sign repeated at 10 metres intervals or closer where the fence changes direction. Each sign shall contain in a clearly legible form, the following information:

Tree protection zone.

- This fence has been installed to prevent damage to the trees and their growing environment both above and below ground and access is restricted.
- No Access within Tree Protection Zone
- The name, address, and telephone number of the developer.

The name and telephone number of the Site Arborist.

8.7 Trunk and Branch Protection

Where a tree is to be retained and a Tree Protection Zone cannot be adequately established due to restricted access, the trunk and branches in the lower crown will be protected by wrapping 2 layers of hessian or carpet underfelt around the trunk and branches for a minimum of 2 m or as lower branches permit, then metal strapping secures 38x50 x2000 mm timber battens together around the trunk (do not nail or screw to the trunk or branches). The number of battens to be used is as required to encircle the trunk and the battens are to extend to the base of the tree (AS4970 2009 Protection of trees on development sites, Figure 3 Examples of Trunk, Branch and ground protection).




Figure 1 - Trunk Protection

9.0 Site Management Issues

9.1 Soil Compaction

Plant and pedestrian traffic during the construction period will cause significant soil compaction. This will be exacerbated by increased water expected on these soils as result of adjacent construction and weather. Compaction of the soil within the TPZ will reduce the voids between soil peds or particles therefore will reduce the gaseous exchange capacity of the root system which will slow critical metabolic processes. No pedestrian or plant access is permissible to the TPZ.

9.2 Site Access

Sufficient access is required to enable efficient construction. It is essential to delineate access zones or corridors which will provide suitable access without damaging the existing trees to be retained or causing compaction to the root zone.

9.3 Excavation within Tree Protection Area

No excavation is to be carried out within the TPZs of retained trees without the permission and supervision of the Site Arborist (AQF5)

9.4 **Possible Contamination / Storage of Materials**

The construction site will require the use of many chemicals and materials that are possible contaminants which if not managed will pose a risk to the existing trees. These possible contaminants include fuels, herbicides, solvents and the like. A site-specific Environmental Management Plan shall be provided, and this specific risk identified and addressed.

10.0 Tree Protection Measures During Construction

10.1 Maintenance of Pre-Construction Tree Protection Measures

The Pre-Construction Tree Protection Measures identified in 5.0 above are to be maintained in good and serviceable condition throughout the construction period.

10.2 Possible Contaminants

Do not store or otherwise place bulk materials and harmful materials under or near trees. Do not place spoil from excavations within the TPZs. Prevent wind-blown materials such as cement from harming trees. All possible contaminants are to be stored in a designated and appropriate area with secure chemical spill measures such as a bund in place.

10.3 Physical Damage

Prevent damage to tree. Do not attach stays, guys and the like to trees. No personnel, plant, machinery or materials are to be allowed within the tree protection fencing.

10.4 Compaction

No filling or compaction shall occur over tree roots zones within tree protection fenced areas. Where construction occurs close to or the TPZ of trees to be retained it shall be necessary to install protection to avoid compaction of the ground surface. This protection is to be planks supported clear of the ground fixed to scaffolding.

10.5 Trenching

No Trenching should be necessary within the TPZs or within tree protection fencing. No further trenching is to be carried out without the approval of the Site Arborist. Should any further trenching be required within the TPZs identified, this work is to be carried out by hand and under the supervision of a qualified Arborist.

10.6 Irrigation/Watering

Contractor is to ensure that soil moisture levels are adequately maintained. Apply water at an appropriate rate suitable for the species during periods of little or no rainfall.

10.7 Site Sheds / Amenities/ Storage

Site sheds, site amenities, ablutions and site storage shall be in the area clear of all TPZ. Chemicals and potential contaminants are to be stored appropriately and this

storage area is to be enclosed by a chemical spill bund to prevent the potential run off of contaminants in the event of a spillage or accident.

11.0 Environmental / Heritage/ Legislative Considerations

None of the subject trees are identified as threatened species or elements of endangered ecological communities within the NSW Biodiversity Conservation Act 2016.

12.0 References

Mattheck, C. Breloer, K. 1993, The Body Language of Trees: A Handbook for Failure Analysis, 12th Impression 2010 The Stationery Office.

AS4970-2009 Protection of Trees on Development Sites: Standards Australia

13.0 Disclaimer

This Appraisal has been prepared for the exclusive use of the Client and Birds Tree Consultancy.

Birds Tree Consultancy accepts no responsibility for its use by other persons. The Client acknowledges that this Appraisal, and any opinions, advice or recommendations expressed or given in it, are based on the information supplied by the Client and on the data inspections, measurements and analysis carried out or obtained Birds Tree Consultancy and referred to in the Appraisal. The Client should rely on the Appraisal, and on its contents, only to that extent.

Every effort has been made in this report to include, assess and address all defects, structural weaknesses, instabilities and the like of the subject trees. All inspections were made from ground level using only visual means and no intrusive or destructive means of inspection were used. For many structural defects such as decay and inclusions, internal inspection is required by means of Resistograph or similar. No such investigation has been made in this case. Trees are living organisms and are subject to failure through a variety of causes not able to be identified by means of this inspection and report.

Appendix A Landscape Significance

IACA Significance of a Tree, Assessment Rating System (STARS) © (IACA 2010) ©

In the development of this document IACA acknowledges the contribution and original concept of the Footprint Green Tree Significance & Retention Value Matrix, developed by Footprint Green Pty Ltd in June 2001.

The landscape significance of a tree is an essential criterion to establish the importance that a particular tree may have on a site. However, rating the significance of a tree becomes subjective and difficult to ascertain in a consistent and repetitive fashion due to assessor bias. It is therefore necessary to have a rating system utilising structured qualitative criteria to assist in determining the retention value for a tree. To assist this process all definitions for terms used in the *Tree Significance - Assessment Criteria* and *Tree Retention Value - Priority Matrix*, are taken from the IACA Dictionary for Managing Trees in Urban Environments 2009.

This rating system will assist in the planning processes for proposed works, above and below ground where trees are to be retained on or adjacent a development site. The system uses a scale of *High*, *Medium* and *Low* significance in the landscape. Once the landscape significance of an individual tree has been defined, the retention value can be determined.

Tree Significance - Assessment Criteria

1. High Significance in landscape



- The tree is in good condition and good vigour;
- The tree has a form typical for the species;
- The tree is a remnant or is a planted locally indigenous specimen and/or is rare or uncommon in the local area or of botanical interest or of substantial age;
- The tree is listed as a Heritage Item, Threatened Species or part of an Endangered ecological community or listed on Councils significant Tree Register;
- The tree is visually prominent and visible from a considerable distance when viewed from most directions within the landscape due to its size and scale and makes a positive contribution to the local amenity;
- The tree supports social and cultural sentiments or spiritual associations, reflected by the broader population or community group or has commemorative values;
- The tree's growth is unrestricted by above and below ground influences, supporting its ability to reach dimensions typical for the taxa *in situ* tree is appropriate to the site conditions.

2. Medium Significance in landscape

- The tree is in fair-good condition and good or low vigour;
- The tree has form typical or atypical of the species;
- The tree is a planted locally indigenous or a common species with its taxa commonly planted in the local area
- The tree is visible from surrounding properties, although not visually prominent as partially obstructed by other vegetation or buildings when viewed from the street,
- The tree provides a fair contribution to the visual character and amenity of the local area,
- The tree's growth is moderately restricted by above or below ground influences, reducing its ability to reach dimensions typical for the taxa *in situ*.

3. Low Significance in landscape


- The tree is in fair-poor condition and good or low vigour;
- The tree has form atypical of the species;
- The tree is not visible or is partly visible from surrounding properties as obstructed by other vegetation or buildings,
- The tree provides a minor contribution or has a negative impact on the visual character and amenity of the local area,
 The tree is a young specimen which may or may not have reached dimension to be protected by local Tree Preservation orders or similar protection mechanisms and can easily be replaced with a suitable specimen.
- The tree's growth is severely restricted by above or below ground influences, unlikely to reach dimensions typical for the taxa *in situ* - tree is inappropriate to the site conditions,
- The tree is listed as exempt under the provisions of the local Council Tree Preservation Order or similar protection mechanisms,
- The tree has a wound or defect that has potential to become structurally unsound. Environmental Pest / Noxious Weed Species

- The tree is an Environmental Pest Species due to its invasiveness or poisonous/ allergenic properties,
- The tree is a declared noxious weed by legislation.
- Hazardous/Irreversible Decline
- The tree is structurally unsound and/or unstable and is considered potentially dangerous,
- The tree is dead, or is in irreversible decline, or has the potential to fail or collapse in full or part in the immediate to short term.

The tree is to have a minimum of three (3) criteria in a category to be classified in that group.

Note: The assessment criteria are for individual trees only, however, can be applied to a monocultural stand in its entirety e.g. hedge.

Appendix B Tree Retention Values



REFERENCES

Australia ICOMOS Inc. 1999, The Burra Charter – The Australian ICOMOS Charter for Places of Cultural Significance, International Council of Monuments and Sites, www.icomos.org/australia

Draper BD and Richards PA 2009, Dictionary for Managing Trees in Urban Environments, Institute of Australian Consulting Arboriculturists (IACA), CSIRO Publishing, Collingwood, Victoria, Australia.

Footprint Green Pty Ltd 2001, Footprint Green Tree Significance & Retention Value Matrix, Avalon, NSW Australia, www.footprintgreen.com.au

Appendix C - Tree Inspection Data

Birds Tree Consultancy

Consulting Arborist• Project Management • Horticultural Consultancy • Landscape Management

					C			Munugemen			incy Lunus	upe munug	emeni										
Inspe	ction Data	2-Dec-22																					
4-6 BI	igh Street Sydney																						
	<u> </u>			Trunk																			
				(single,																	Env. &		
				twin,			Diameter at				Overall	Crown								Life	Landcape		
																_	-				1		
Tree				multiple		TPZ	Root Flare	SRZ radius			Health &	Distributio		Pruning		Pest	Canopy	Deadwoo	Epicormic	expectanc	significanc	Retention	
no.	Species	Height	Spread(m)	@)	DBH (mm)	Radius (m)) (DRF) (mm)	(m)	Trunk lean	Tree Age	Vigour	n	Structure	History	Defects	Infestation	Density	d	Growth	у	e	Value	Notes/Comments
	Lophostemon									Semi		Symmetri											
-	confertus	6	2	Single	50	2	90	1.20	Nil	mature	Good	cal	Good	No Evidence	No Evidence	No Evidence	normal	<5%	<5%	40+ years	Medium	High	
												Symmetri								21-40			
	Celtis australis	9	8	Single	290	3.48	370	2.18	Nil	Mature	Good	cal	Good	No Evidence	No Evidence	No Evidence	normal	<5%	<5%	years	Medium	Medium	
												Symmetri								21-40			
3	Celtis australis	10	9	Single	270	3.24	330	2.08	Nil	Mature	Good	cal	Good	No Evidence	No Evidence	No Evidence	normal	<5%	<5%	years	Medium	Medium	
												Symmetri								21-40			
4	Celtis australis	10	8	Single	280	3.36	330	2.08	Nil	Mature	Good	cal	Good	No Evidence	No Evidence	No Evidence	normal	<5%	<5%	years	Medium	Medium	
												Symmetri								21-40			
,	celtis australis	11	9	Single	300	3.6	5 350	2.13	Nil	Mature	Good	cal	Good	No Evidence	No Evidence	No Evidence	normal	<5%	<5%	years	Medium	Medium	

Appendix D - Tree Location Plan



Legend

Tree Viable to be Retained

Tree to be Removed

Tree Not Viable to be Retained due to Proposed Development

Tree Protection Zone (TPZ) in accordance with AS4970-2009

Birds Tree Consultancy

0438 892 634 glenn@birdstrees.com.au www.birdstrees.com.au

Project: 4-6 Bligh Street Sydney Client: Holdmark DWG: A01 REV A Plan: Tree Location Plan Date: 22 Dec 2022 Scale : 1:200 @ A3