

EROSION CONTROL NOTES

ALL CONTROL WORK INCLUDING DIVERSION BANKS AND CATCH DRAINS, V-DRAINS AND SILT FENCES SHALL BE COMPLETED DIRECTLY FOLLOWING THE COMPLETION OF THE EARTHWORKS.

- SILT FENCES AND SILT FENCE RETURNS SHALL BE ERECTED CONVEX TO THE CONTOUR TO POND WATER.
- HAY BALE BARRIERS AND GEOTEXTILE FENCES ARE TO BE CONSTRUCTED TO TOE OF BATTER, PRIOR TO COMMENCEMENT OF EARTHWORKS, IMMEDIATELY AFTER CLEARING OF VEGETATION AND BEFORE REMOVAL OF TOP SOIL.
- ALL TEMPORARY EARTH BERMS, DIVERSION AND SILT DAM EMBANKMENTS ARE TO BE MACHINE COMPACTED, SEEDED AND MULCHED FOR TEMPORARY VEGETATION COVER AS SOON AS THEY HAVE BEEN FORMED.
- CLEAR WATER IS TO BE DIVERTED AWAY FROM DISTURBED GROUND AND INTO THE DRAINAGE SYSTEM.
- THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND PROVIDING ON GOING ADJUSTMENT TO EROSION CONTROL MEASURES AS REQUIRED DURING CONSTRUCTION.
- ALL SEDIMENT TRAPPING STRUCTURES AND DEVICES ARE TO BE INSPECTED AFTER STORMS FOR STRUCTURAL DAMAGE OR CLOGGING. TRAPPED MATERIAL IS TO BE REMOVED TO A SAFE, APPROVED LOCATION.
- ALL FINAL EROSION PREVENTION MEASURES INCLUDING THE ESTABLISHMENT OF GRASSING ARE TO BE MAINTAINED UNTIL THE END OF THE DEFECTS LIABILITY PERIOD.
- ALL EARTHWORKS AREAS SHALL BE ROLLED ON A REGULAR BASIS TO SEAL THE EARTHWORKS.
- ALL FILL AREAS ARE TO BE LEFT WITH A BUND AT THE TOP OF THE SLOPE AT THE END OF EACH DAYS EARTHWORKS. THE HEIGHT OF THE BUND SHALL BE A MINIMUM OF 200MM.
- ALL CUT AND FILL SLOPES ARE TO BE SEEDED AND HYDROMULCHED WITHIN 10 DAYS OF COMPLETION OF FORMATION.
- AFTER REVEGETATION OF THE SITE IS COMPLETE AND THE SITE IS STABLE IN THE OPINION OF A SUITABLY QUALIFIED PERSON ALL TEMPORARY WORK SUCH AS SILT FENCE, DIVERSION DRAINS ETC SHALL BE REMOVED.
- ALL TOPSOIL STOCKPILES ARE TO BE SUITABLY COVERED TO THE SATISFACTION OF THE SITE MANAGER TO PREVENT WIND AND WATER EROSION.
- ANY AREA THAT IS NOT APPROVED BY THE CONTRACT ADMINISTRATOR FOR CLEARING OR DISTURBANCE BY THE CONTRACTOR'S ACTIVITIES SHALL BE CLEARLY MARKED AND SIGN POSTED, FENCED OFF OR OTHERWISE APPROPRIATELY PROTECTED AGAINST ANY SUCH DISTURBANCE.
- ALL STOCKPILE SITES SHALL BE SITUATED IN AREAS APPROVED FOR SUCH USE BY THE SITE MANAGER. A 6m BUFFER ZONE SHALL EXIST BETWEEN STOCKPILE SITES AND ANY STREAM OR FLOW PATH. ALL STOCKPILES SHALL BE ADEQUATELY PROTECTED FROM EROSION AND CONTAMINATION OF THE SURROUNDING AREA BY USE OF THE MEASURES APPROVED IN THE EROSION AND SEDIMENTATION CONTROL PLAN.
- ACCESS AND EXIT AREAS SHALL INCLUDE SHAKE-DOWN OR OTHER METHODS APPROVED BY THE SITE MANAGER FOR THE REMOVAL OF SOIL MATERIALS FROM MOTOR VEHICLES.
- THE CONTRACTOR IS TO ENSURE RUNOFF FROM ALL AREAS WHERE THE NATURAL SURFACE IS DISTURBED BY CONSTRUCTION, INCLUDING ACCESS ROADS, DEPOT AND STOCKPILE SITES, SHALL BE FREE OF POLLUTANTS BEFORE IT IS EITHER DISPERSED TO STABLE AREAS OR DIRECTED TO NATURAL WATERCOURSES.
- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN SLOPES, CROWNS AND DRAINS ON ALL EXCAVATIONS AND EMBANKMENTS TO ENSURE SATISFACTORY DRAINAGE AT ALL TIMES WATER SHALL NOT BE ALLOWED TO POND ON THE WORKS UNLESS SUCH PONDING IS PART OF AN APPROVED ESCP / SWMP.

SEDIMENTATION BASIN NOTE:

FOR SEDIMENT & EROSION CONTROL DETAILS REFER TO DRAWING C012693.00-DA25.

SEDIMENTATION BASIN SIZING BASED ON RECOMMENDATIONS OF 'SOILS AND CONSTRUCTION, MANAGING URBAN STORMWATER-THE BLUE BOOK' CAPACITY BASED UPON 5 DAY RAINFALL DEPTH AT 80th PERCENTILE INTENSITY (24.6mm).

APPROXIMATE AREA OF DISTURBED SITE = 16.30ha

SEDIMENT BASIN 1:
 DISTURBED CATCHMENT AREA = 4.12ha
 REQUIRED BASIN VOLUME = 760m³
 PROVIDED BASIN VOLUME = 3,500m³

SEDIMENT BASIN 2:
 DISTURBED CATCHMENT AREA = 12.18ha
 REQUIRED BASIN VOLUME = 2,247m³
 PROVIDED BASIN VOLUME = 5,600m³

SEDIMENTATION BASINS TO COLLECT RUN-OFF IN EXTREME RAINFALL EVENTS. COLLECTED RUN-OFF TO BE ASSESSED BY A QUALIFIED LABORATORY FOR DOUSING RATES OF ALUM OR GYPSUM TO ENSURE COAGULATION OF SEDIMENTS PRIOR TO WATER BEING DISCHARGED TO COUNCIL STORMWATER SYSTEM.

EACH BASIN IS TO HAVE A MARKER PLACED AS PER THE DETAIL TO INDICATE WHEN SEDIMENT IS TO BE REMOVED. REMOVED SEDIMENT IS TO BE CLASSED AND DEWATERED PRIOR TO REMOVAL FROM SITE.

ALLOWANCE TO BE MADE DURING BENCHING OF SITE TO ENSURE RUN-OFF IS DIRECTED TO SEDIMENTATION BASINS.

- NOTES:**
- ASSUME TYPE D SOIL (CLAY/SILTY CLAY)
 - ASSUME GROUP D SOIL


EROSION & SEDIMENT CONTROL PLAN

SCALE 1:1000


LEGEND:

- SILT FENCE
- DIVERSION DRAIN
- HAY BALES


FOR SECTION 96




ISSUED FOR SECTION 96		21.07.15	B	ARCHITECT		CLIENT		PROJECT		Costin Roe Consulting Pty Ltd.		DRAWING TITLE	
FOR INFORMATION ONLY		30.03.15	A	WESTERN SYDNEY PARKLANDS TRUST		WESTERN SYDNEY PARKLANDS TRUST		EASTERN CREEK BUSINESS HUB		Consulting Engineers		EROSION & SEDIMENT CONTROL PLAN	
AMENDMENTS		DATE	ISSUE	LEVEL 1, 10 VALENTE AVENUE		WESTERN SYDNEY PARKLANDS TRUST		WATERWORKS		Level 1, 8 Windmill Street		DRAWING No	
AMENDMENTS		DATE	ISSUE	PARRAMATTA NSW 2150		WESTERN SYDNEY PARKLANDS TRUST		CONCRETE		Wahbi Hwy, Sydney NSW 2000		C012693.00-DA20	
AMENDMENTS		DATE	ISSUE	DESIGNED		DRAWN		CHECKED		SCALE		ISSUE	
AMENDMENTS		DATE	ISSUE	M.W.		X.C.		MAR 2015		AS SHOWN		B	
AMENDMENTS		DATE	ISSUE	CAD REF:		C012693.00-DA20		CONCRETE		Value in Engineering and Management		ISSUE	
AMENDMENTS		DATE	ISSUE	CAD REF:		C012693.00-DA20		CONCRETE		Value in Engineering and Management		ISSUE	




KERB INLET CONTROL
N.T.S.




TYPICAL SILT FENCE DETAIL
N.T.S.
PROVIDE 1m RETURNS AT 30m INTERVALS.
TYPICAL




TYPICAL OPEN DRAIN & SILT FENCE
SCALE 1:20




SILT FENCE WITH HAY BAIL PLAN
N.T.S.



GRATED INLET PIT FILTER DETAIL
N.T.S.




TYPICAL STOCKPILE DETAIL
N.T.S.




SILT FENCE WITH HAY BAIL DETAIL
N.T.S.

NOTE: ADOPT ABOVE DETAILS AROUND ALL PITS WITHIN AREA ENCOMPASSED BY SILT FENCE & TO PITS ON THE ROAD ADJACENT TO SITE BOUNDARY.

- STOCKPILE NOTES**
1. PLACE ALL STOCKPILES IN LOCATIONS MORE THAN 5m FROM EXISTING VEGETATION, ROADS & HAZARD AREAS.
 2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT ELONGATED MOUNDS. SIDE SLOPE TO BE 1 V : 2 H MAX.
 3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT.
 4. WHERE STOCKPILES ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE USING WOOD CHIP MULCH - 16 TONNE/ha.
 5. CONSTRUCT SILT FENCE WITH CATCH DRAIN ON UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES & SILT FENCE ONLY 1 TO 2m DOWNSLOPE AS SHOWN.



TYPICAL CROSSING OVER DIVERSION CHANNEL
SCALE 1:20



STABILISED CONSTRUCTION ENTRANCE 'TRUCK SHAKER'
SCALE 1:20

FOR SECTION 96

ISSUED FOR SECTION 96 FOR INFORMATION ONLY		21.07.15 30.03.15	B A	ARCHITECT		CLIENT NSW Western Sydney Parklands Trust WESTERN SYDNEY PARKLANDS TRUST LEVEL 7, 10 VALENTE AVE PARRAMATTA NSW 2150		PROJECT EASTERN CREEK BUSINESS HUB WESTERN SYDNEY PARKLANDS		Costin Roe Consulting Pty Ltd. Consulting Engineers Level 1, 8 Windmill Street Wahbi Bay, Sydney NSW 2000 Tel: (02) 9551-7899 Fax: (02) 9541-3721 email: mail@costinroe.com.au		DRAWING TITLE EROSION & SEDIMENT CONTROL DETAILS		DRAWING No C012693.00-DA25		ISSUE B							
AMENDMENTS		DATE	ISSUE	AMENDMENTS		DATE	ISSUE	DESIGNED M.W.		DRAWN X.C.		CHECKED MAR 2015		SCALE AS SHOWN		CAD REF: 12693.00-DA25		Value in Engineering and Management		DRAWING No C012693.00-DA25		ISSUE B	