

Certificate of Test

Quote No.: NE7500

REPORT No.: FNE11605

AS/NZS 1530.3:1999 SIMULTANEOUS DETERMINATION OF IGNITABILITY, FLAME PROPAGATION, HEAT RELEASE AND SMOKE RELEASE

TRADE NAME: BlueScope COLORBOND Steel

SPONSOR: Bluescope Steel Limited
Innovations Lab
Old Port Road
PORT KEMBLA NSW 2505
AUSTRALIA

DESCRIPTION OF

SAMPLE: The sponsor described the tested specimen as a polyester painted steel sheet with aluminium-zinc-magnesium alloy coating on both sides.

Nominal thickness of steel sheet:	0.35 mm
Nominal thickness of aluminium-zinc-magnesium coating:	30 μm
Nominal thickness of paint layer:	50 μm
Nominal total thickness:	0.45 mm
Nominal total mass:	5.5 kg/m^2
Nominal total density:	7700 kg/m^3
Colour:	dark grey (Woodland Grey)/brown

TEST PROCEDURE: Six samples were tested in accordance with Australian Standard 1530, Method for fire tests on building components and structures, Part 3: Simultaneous determination of ignitability, flame propagation, heat release and smoke release, 1999. For the test, each sample was clamped to the specimen holder in four places.

RESULTS: The following means and standard errors were obtained:

Parameter	Mean	Standard Error
Ignition Time (min)	N/A	N/A
Flame Spread Time (s)	N/A	N/A
Heat Release Integral (kJ/m^2)	N/A	N/A
Smoke Release ($\log_{10}D$)	-1.560	0.072

For regulatory purposes these figures correspond to the following indices:

Ignitability Index (0-20)	Spread of Flame Index (0-10)	Heat Evolved Index (0-10)	Smoke Developed Index (0-10)
0	0	0	2

The results of this fire test may be used to directly assess fire hazard, but it should be recognised that a single test method will not provide a full assessment of fire hazard under all fire conditions.

DATE OF TEST: 11 February 2016

Issued on the 3rd day of March 2016 without alterations or additions.



Heherson Alarde
Testing Officer



Brett Roddy
Team Leader, Fire Testing and Assessments

Copyright CSIRO 2015 ©. Copying or alteration of this report without written authorisation from CSIRO is forbidden.



NATA Accredited Laboratory
Number: 165
Corporate Site No 3625
Accredited for compliance with ISO/IEC 17025

CSIRO INFRASTRUCTURE TECHNOLOGIES

14 Julius Avenue, Riverside Corporate Park, North Ryde NSW 2113 AUSTRALIA
Telephone: 61 2 9490 5444 Facsimile: 61 2 9490 5555 www.csiro.au

