



**MPN**  
CONSULTING

# Stormwater Management Plan

---

## Tangaratta Feed Mill

Date 05 April 2024

Prepared by

**MPN Consulting Pty Ltd**

Level 4, Building 3, Kings Row Office Park  
42 McDougall Street, Milton, Qld, 4064

**mpnc.au**




## Revision Status

---

**MPN Reference No:** 9883  
**Client:** Tangaratta Stockfeeds Pty Ltd  
**Site Address:** 771 Wallamore Road, Wallamore NSW  
**Report Title:** Stormwater Management Plan

## Document Control

---

Version	Date	Author	Reviewer	Approved	RPEQ
Draft Issue	9/02/2024	Ben Tarrant	Lachlan Stephenson		16903
Issue A	5/04/2024	Ben Tarrant	Lachlan Stephenson		16903



# Contents

---

1 >	Executive Summary	5
2 >	Purpose	6
3 >	Introduction	6
	3.1 Project Description	6
4 >	Site Characteristics	7
	4.1 Site Location	7
	4.3 Topography and Existing Site Drainage	8
5 >	Site Data	8
6 >	Stormwater	9
	6.1 Flooding	9
	6.2 Site Based Stormwater Management Plan	9
	6.3 Operational Phase	9
7 >	Conclusion	21
8 >	Limitations of Report	21



## Table of Figures

Figure 1 - Proposed Development	6
Figure 2 - Site Location	7
Figure 3 - Proposed Site Catchments (SKC.01)	<b>Error! Bookmark not defined.</b>
Figure 4 - Treatment Plan	16

## Table of Tables

Table 1 - Detention Basin Properties	11
Table 2 - Existing and Proposed Peak Flows with Detention (Catchments A, B, D) (DRAINS ILSAX)	11
Table 3 - Existing and Proposed Peak Flows of bypass catchments (Catchments E & F) (DRAINS ILSAX)	12
Table 4 - Existing and Proposed Peak Flows combined catchments (DRAINS ILSAX)	12
Table 5 - MUSIC Rainfall Runoff Parameters	14
Table 6 - Pollutant Export Parameters	14
Table 7 - Water Quality Objectives	15
Table 8 - Percentage Based Load Reduction Results	16

## Table of Appendices

Appendix A. Architectural Plans	22
Appendix B. MPN Plans	23



# 1 > Executive Summary

---

This report has been commissioned by Tangaratta Stockfeeds Pty Limited for the Environmental Impact Statement, to be lodged as part of the Development Application, for the proposed Tangaratta Feed Mill at 771 Wallamore Road, Wallamore.

This report addresses the following Engineering aspects of the proposed development:

- Topography
- Flooding
- Stormwater quality management
- Stormwater quantity management
- Erosion and sediment control.



## 2 > Purpose

This Stormwater Management Plan has been prepared to support the Environmental Impact Statement, to be lodged as part of the Development Application for the proposed Tangaratta Feed Mill.

## 3 > Introduction

### 3.1 Project Description

The current proposal includes the construction of a new poultry feed mill to the south of the existing feed mill, along with new car parking, loading docks, access roads, drainage swales, and a detention basin.

The proposed development is depicted on the architectural plans prepared by LGPM, attached in Appendix A, with excerpt below.




Figure 1 – Proposed Development



## 4 > Site Characteristics

### 4.1 Site Location

The site is located at 771 Wallamore Road, Wallamore on 40.62ha of rural land, formally described as Lot 4 on DP 578865.

The site is bounded by Wallamore Road to the East, Tangaratta Creek to the West and rural farmland to the North and South.



Figure 2 - Site Location



### 4.3 Topography and Existing Site Drainage

The site currently contains the current Tangaratta Stockfeeds mill, which will be expanded with the addition of the proposed new feed mill. The site is largely cleared and has been recently revegetated with native plants. There is an existing detention basin which was constructed to treat and detain the stormwater runoff from the existing development.

The site generally falls from the southern boundary to the north towards Wallamore Road, where there are a series of cut off drains directing stormwater flow to the western dam and the road table drains.

No external catchments appear to flow through the site, as the southern neighbour cuts off their overland flow with bunds and swales and directs it along the boundary toward Wallamore Road.

## 5 > Site Data

---

Site data has been obtained from the following sources of information:

- As constructed plans
- New South Wales Environmental Protection Authority (EPA)
- Tamworth Regional Council
- Satellite imagery
- Relevant reports
- Discussions with relevant authorities
- DBYD
- Survey plans.



## 6 > Stormwater

---

### 6.1 Flooding

Current flood mapping in the area indicates the site is not subject to flooding from any sources.

### 6.2 Site Based Stormwater Management Plan

The aim of the Stormwater Management Plan outlined below is to:

- Prevent or minimise adverse social or environmental impacts from stormwater runoff originating from the proposed development.
- Achieve acceptable levels of stormwater runoff quality and quantity.

The Stormwater Management Plan aims to identify Stormwater Quantity and Quality Best Management Practice for the site and demonstrate that water quantity and quality impacts will be minimised in receiving water.

The Stormwater Management Plan outlines the site in two sections, the operational phase and the construction phase. The operational phase addresses treatment of contaminated runoff from the developed site by natural methods before discharging into receiving waters, whilst the construction phase of the Stormwater Management Plan addresses erosion and sediment control to prevent contamination of water sources by stormwater runoff during construction of the site.

### 6.3 Operational Phase

#### 6.3.1 Proposed Site Drainage

The site has been split into three main sub-catchments – an upstream catchment (Catchment C) that has been cut and redirected West toward the existing dam, a catchment running North-West through the main site (Catchment A, B & D), sheet flowing toward the Northwest boundary, and a catchment discharging toward Wallamore Road (Catchment E & F), North-East of the site. The catchment locations and extents are shown on MPN Plans 9883-SKC.01 attached in Appendix B, with excerpt below.




Figure 3 - Proposed Site Catchments (SKC.01)

Stormwater runoff from each of the main sub-catchments will be collected and conveyed in a new internal stormwater pit, pipe and open channel network. Stormwater runoff from catchments C, D, E and F will be collected in grassed swales prior to discharge toward the site boundaries via overland flow.

The catchment running through the proposed site (Catchment A) will be discharged to a detention basin. Stormwater will discharge from the basin via overland flow toward the site boundaries, mimicking the existing catchment. Litter baskets will also be fitted to the new field inlet pits to capture gross pollutants.

The existing detention basin constructed as part of the existing development will be retained to service Catchment C.

The proposed site stormwater infrastructure is shown on MPN Plans 9883-SKC.02, attached in Appendix B.

### 6.3.2 Stormwater Quantity Management Strategy

For the management of stormwater quantity for the proposed development, a DRAINs computer model was used to calculate the stormwater runoff quantity for the existing and post-development conditions.



In order to limit the site stormwater discharge, stormwater runoff from Catchment A will be detained within a detention basin. The basin will be over-sized to cater for the areas which will bypass detention (Catchments B, D, E, F). The location and configuration of the basin is shown on MPN Plans 9883-SKC.02-03, attached in Appendix 2. The properties of the basins are listed in Table 1 below.

<b>Property</b>	<b>Detention Basin</b>
Max Detention Volume (Incl. Freeboard)	1,477.80m <sup>3</sup>
Max Water Depth (1% AEP) (Including Extended Detention)	0.72m
Max Water Depth (10% AEP) (Including Extended Detention)	0.53m
Base of Basin	374.00m
Top of Bund (min)	375.00m
Freeboard (1% AEP)	280mm
Outlet V-Notch Arrangement	2.4m Width @ RL 375 IL @ 374m

Table 1 - Detention Basin Properties

Runoff flows for the Annual Exceedance Probability (AEP) from 0.5EY (2-year ARI) to 1% AEP (100-year ARI) and durations of 5 minutes to 3 hours were calculated to ensure that peak runoff flows from the proposed development would not exceed peak runoff flows from the existing site. The most critical stormwater events for the site's catchment are compared in Table 2 and 3 and summarised in Table 4.

<b>AEP Event (%)</b>	<b>Pre-Development Discharge (m<sup>3</sup>/sec)</b>	<b>Post-Development Discharge (m<sup>3</sup>/sec)</b>	<b>Post-Development Detained Discharge (m<sup>3</sup>/sec)</b>
39.3	0.237	0.577	0.230
20	0.445	0.831	0.366
10	0.625	1.056	0.508
5	0.790	1.288	0.665
2	1.070	1.637	0.883
1	1.290	1.888	1.054

Table 2 - Existing and Proposed Peak Flows with Detention (Catchments A, B, D) (DRAINS ILSAX)



AEP Event (%)	Pre-Development Discharge (m <sup>3</sup> /sec)	Post-Development Discharge (m <sup>3</sup> /sec)
39.3	0.128	0.152
20	0.238	0.260
10	0.320	0.356
5	0.427	0.445
2	0.578	0.599
1	0.694	0.705

Table 3 - Existing and Proposed Peak Flows of bypass catchments (Catchments E & F) (DRAINS ILSAX)

AEP Event (%)	Pre-Development Discharge (m <sup>3</sup> /sec)	Post-Development Discharge (m <sup>3</sup> /sec)	Net Discharge Change (m <sup>3</sup> /sec)
39.3	0.365	0.382	0.017
20	0.683	0.626	-0.057
10	0.945	0.864	-0.081
5	1.217	1.110	-0.107
2	1.648	1.482	-0.166
1	1.984	1.759	-0.225

Table 4 - Existing and Proposed Peak Flows combined catchments (DRAINS ILSAX)

Table 4 above compares all catchments that are impacted by the site imperviousness, where the main catchment A has been over detained to offset the increase from the bypassing catchments.

### 6.3.3 Stormwater Quality Management Strategy

In order to reduce overall post-development pollutant loads and concentrations being discharged from the site, treatment solutions have been provided to remove hydrocarbons, suspended solids and nutrients prior to being discharged from site.



### 6.3.3.1 Potential Pollutants Generated

The pollutants that could be potentially generated as a result of the development use are as follows:

- Litter
- Sediment
- Nutrients (Nitrogen and Phosphorous)
- Hydrocarbons (oils and grease)
- Surfactants
- Pathogens/Faecal Coliforms (bacteria and viruses).

The MUSIC computer modelling program developed by the Co-operative Research Centre for Catchment Hydrology was used to predict the performance of the proposed stormwater treatment train.

At this stage the pollutants modelled in MUSIC are Total Suspended Solids (TSS), Total Phosphorous (TP) and Total Nitrogen (TN).

### 6.3.3.2 Rainfall

The rainfall data used in the model was based on the Bureau of Meteorology data from rainfall station 55054 Tamworth Airport. The model was run from 16 August 1993 to 31 December 2003. The modelling time step was 6 minutes.



### 6.3.3.3 Rainfall Runoff Properties

The rainfall runoff properties listed in Table 5 below were adopted for the MUSIC modelling undertaken for the development.

Parameter	Roof	VALUE Road	Ground Level
Rainfall Threshold (mm)	0.3	1.5	1.5
Soil Storage Capacity (mm)	100	100	100
Initial Storage (% of capacity)	25	25	25
Field Capacity (mm)	87	87	87
Infiltration Capacity Co-efficient a	250	250	250
Infiltration Capacity Co-efficient b	1.3	1.3	1.3
Initial Depth (mm)	10	10	10
Daily Recharge Rate (%)	60	60	60
Daily Base Flow Rate (%)	45	45	45
Deep Seepage (%)	0	0	0

Table 5 - MUSIC Rainfall Runoff Parameters

### 6.3.3.4 Pollutant Export Parameters

The adopted Pollutant Export Parameters for each source node type are presented in Table 6 below.

Runoff pollutant concentrations are generated stochastically from the defined mean and standard deviation.

		Log 10 TSS (mg/L)		Log 10 TN (mg/l)		Log 10 TP (mg/L)	
		Base Flow	Storm Flow	Base Flow	Storm Flow	Base Flow	Storm Flow
Roof	Mean	0	1.30	0	-0.89	0	0.30
	Std. Dev.	0	0.32	0	0.25	0	0.19
Roads	Mean	0	2.43	0	-0.30	0	0.34
	Std. Dev.	0	0.32	0	0.25	0	0.19
Ground Level	Mean	1.20	3.00	-0.85	-0.30	0.11	0.34
	Std. Dev.	0.17	0.32	0.19	0.25	0.12	0.19

Table 6 - Pollutant Export Parameters



### 6.3.3.5 Water Quality Objectives

In the absence of specific Water Quality Objectives from Tamworth Regional Council, the industry standard pollutant reduction targets listed in Table 7 below have been adopted.

#### WATER QUALITY OBJECTIVES

<b>Total Suspended Solids (TSS) % Reduction</b>	<b>Total Nitrogen (TN) % Reduction</b>	<b>Total Phosphorous (TP) % Reduction</b>	<b>Litter/ Gross Pollutants % Reduction</b>	<b>Oils/ Grease</b>
85	45	65	90	No visible films or odours

Table 7 - Water Quality Objectives

### 6.3.3.6 Treatment Plan

In order to achieve the pollutant load reduction targets for the development, it is proposed to use mechanical and natural treatment methods to treat the runoff prior to discharge from the site.

Stormwater runoff from Catchment A will be treated by GPTs and/or buffer strips prior to discharging via swales to the detention basin.

Stormwater runoff from Catchments B, D & E will be treated by buffer strips and swales.

The treatment plan for the site is depicted on MPN Plans 9883-SKC.01, attached in Appendix 2, with MUSIC excerpt shown below.




Figure 4 - Treatment Plan

### 6.3.3.7 MUSIC Results

The resulting percentage-based load reductions at the site outlet is shown in Table 8 below, together with the Water Quality Objectives for the receiving waters.

	Sources	Residual Load	%Reduction	Target %
Total Suspended Solids (kg/yr)	4490	414	90.8	85
Total Phosphorous (kg/yr)	7.99	1.78	77.7	65
Total Nitrogen (kg/yr)	38	18.7	50.8	45
Gross Pollutants (kg/yr)	482	32.6	93.2	90

Table 8 - Percentage Based Load Reduction Results

### 6.3.3.8 POD Pollutant Reduction

#### 6.3.3.8.1 Litter

Rubbish bins will be located within the development buildings and car parks for use by staff and visitors. As a result of this and with the installation of the GPTs and swales, levels of litter exiting the site via stormwater are expected to be negligible.



#### **6.3.3.8.2 Sediment**

The TSS outflow is identified in Table 8 above. As can be seen the pollutant load reduction achieves the Water Quality Objectives. The TSS level is therefore considered acceptable.

#### **6.3.3.8.3 Nitrogen and Phosphorous**

The TN and TP loads are identified in the above Table 8. As can be seen the TN and TP loads leaving the site achieve the Water Quality Objectives. Significant reductions in Nitrogen and Phosphorous have been achieved. The Nitrogen and Phosphorous residual loads are therefore considered acceptable.

#### **6.3.3.8.4 Hydrocarbons**

Hydrocarbons will be digested and processed by soil microorganisms within the swales and attachment to vegetation where biological breakdown of the hydrocarbons can occur. Hydrocarbons will also be captured within the GPTs.

#### **6.3.3.8.5 Surfactants**

If car or truck washing occurs on site it will be within a bunded area where surfactants will be captured and treated prior to discharging into the stormwater network.

#### **6.3.3.8.6 Heavy Metals**

Heavy metals in stormwater runoff generally become attached to fine sediment. The swales will remove the majority of this fine sediment. The removal of the fine sediment should effectively remove most of the heavy metals in the runoff.

#### **6.3.3.8.7 Pathogen/Faecal Coliforms**

Domestic animals within the development will be under the control of their owners at all times and the owners will be expected to clean up after them.

### **6.3.3.9 Proposed Stormwater Quality Treatment Devices**

#### **6.3.3.9.1 Locations**

The location of the proposed stormwater quality treatment devices is shown on MPN Plans 9883-SKC.01, attached in Appendix 2.

#### **6.3.3.9.2 Device and Size**

The device type and sizes are shown on MPN Plan 9883-SKC.01, attached in Appendix 2.

### **6.3.4 Construction Phase (Sediment and Erosion Control)**

#### **6.3.4.1 Intent of Erosion and Sediment Control Management Plan**

To prevent stormwater contamination (of watercourses) and the release of contaminated stormwater and wastewater by ensuring compliance with the Protection of the Environment Operations Act 1997.



### 6.3.4.2 Implementation Strategy

Establish control measures and best practice approaches to prevent stormwater contamination and minimise the risk and adverse effects of erosion and sedimentation. All Erosion and Sediment Control measures must be designed, constructed and maintained in a manner that is commensurate with the site's erosion risk.

#### 6.3.4.1 Erosion and Sediment Control Measures

- Obtain a license or approval to operate activities that are classed as environmentally relevant activities (i.e. they have the potential to cause environmental harm).
- Implement and maintain appropriate control measures to prevent sediment laden wastewater and other potential pollutants such as oil, paint and wet concrete from entering the stormwater system via stormwater drains and gullies. The control measures which must be considered to be adopted are:
  - Limitation of site access during construction to minimise disruption to traffic. Install a temporary construction entry/exit sediment trap at all site accesses to minimise mud and sediment from the site being tracked onto public road, particularly during wet weather or when the site is muddy.
  - Install and maintain appropriate sediment fences around construction areas.
  - Divert clean stormwater runoff, using catch drains, around construction areas to existing or new stormwater drainage system.
  - Install sandbags and other pollution containment devices around stormwater drains and any other locations where required to prevent sediment entering the trunk stormwater system.
  - Cover open earth/soil areas progressively (with concrete slabs and pavements or mulch) to minimise areas of bare earth/soil.
  - Any stockpiles of excavated soil and demolition/construction waste must be located where risk of erosion and sedimentation is minimal and must be protected from wind and water erosion.
  - Implement and maintain appropriate control measures such as catch drains and sediment fences to prevent ponding of stormwater or discharge of stormwater from the site to adjacent properties.
  - Provision of spill/pollution control equipment that is readily accessible to clean up spills and leaks.
  - Ensure spill/pollution control measures are available and maintained in working condition.
  - Sediment contained by the sediment control devices such as sandbags, sediment fences and containment bunds must be frequently removed and placed in a controlled area.
  - Implement an inspection schedule for any spill or leaks of any potential polluting areas or activities.



#### **6.3.4.2 Erosion and Sediment Control Management Goals**

- Licenses, approvals, permits, and inspection reports are in order.
- Sediment or pollution control devices such as sandbags, sediment fences and containment bunds are in place, maintained and effective.
- Spill/pollution control equipment is readily accessible at designated locations.
- No accumulated sediment is contained by the sediment control devices such as hay bales, sediment fences and containment bunds.
- No sediment exceeding a depth of 300mm in the pollution control devices (e.g. silt trap).

#### **6.3.4.3 Erosion and Sediment Control Implementation Program**

- Licenses, permits or approvals for each environmentally relevant activity must be obtained prior to the commencement of the particular activity.
- Appropriate control measures such as sediment fences, temporary construction entry/exit sediment traps, pollution containment devices (e.g. sandbags), stormwater diversion, and administrative controls must be installed and established prior to commencement of the earthworks and construction activities.
- Pollution control devices such as spill control equipment must be inspected on a regular basis (at least weekly).
- Other sediment and pollution control equipment such as containment bunds, hay bales and sediment fences must be inspected on a regular basis (at least daily).
- Inspection for any leaks, spills or potential contaminating activity must be performed on a regular basis (at least daily).
- Remove accumulated sediment or other contaminants from sediment/pollution control devices on a regular basis.
- All erosion and sediment control measures must be inspected within 24 hours of expected rain and within 18 hours of a rainfall event.

#### **6.3.4.4 Responsible Person or Organisation**

The contractor shall be responsible for the implementation and maintenance of the Erosion and Sediment Control Measures.

#### **6.3.4.5 Reporting/Review**

Records such as licenses, approvals, permits and inspection reports must be reviewed on a regular basis (e.g. at least monthly) to ensure that legal compliance is met, complaints are reviewed and systems are working to prevent contamination.



#### 6.3.4.6 Corrective Actions

- Perform clean-up of any spills immediately.
- Any mud or sediment which is tracked onto public roads is to be immediately removed using dry clean-up methods (i.e. shovel and broom).
- Remove or relocate any stockpiles of waste where there is a reasonable risk of erosion and sedimentation.
- Replace or repair sediment or pollution control devices if they are not maintained in good working condition.



## 7 > Conclusion

---

This Stormwater Management Plan demonstrates that under the proposed concept plan, stormwater quality and quantity treatment is achievable to the levels required by Tamworth Regional Council and Industry Best Management Practice.

Stormwater detention for the development will be provided in a detention basin located downstream of the site to suit the site's existing catchments. The detention basin will be over-sized to compensate for the areas of the site which bypass detention, and runoff from the basin will be evenly distributed via a level spreading bund.

Stormwater treatment for the development will be provided by a series of GPT's and swales located throughout the site, along with buffer strips along the internal roads.


## 8 > Limitations of Report

---

MPN have prepared this report for the proposed Tangaratta Feed Mill in accordance with MPN's proposal to Tangaratta Stockfeeds Pty Limited. This report is provided for the exclusive use of Tangaratta Stockfeeds Pty Limited for this specific project and its requirements. It should not be used or relied upon by a third party and MPN accept no responsibility for the use of this report by any party other than Tangaratta Stockfeeds Pty Limited.



## Appendix A. Architectural Plans




WALLAMORE ROAD

REVISION HISTORY			
REV	DESCRIPTION	DATE	APPROVED
D	MILL TOWERS WIDENED	18/10/2023	

**LGPM**  
 PROCESS INNOVATION  
 Bulk Materials Handling & Processing Systems  
 47-49 OVERSEAS DRIVE  
 NOBLE PARK, VIC 3174  
 PHONE: +61 (0)3 9702 4855  
 EMAIL: info@lgpm.com.au  
 WEBSITE: www.lgpm.com.au

MDL	JC	3/07/2023
DRN	JC	24/07/2023
CHK		
UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN mm		SCALE 1:1200
THIRD ANGLE PROJECTION		

CLIENT & PROJECT LOCATION		REV.	SHT
BAIADA TFM - TANGARATTA, NSW		D	1 OF 4
PROPOSED FEEDMILL GENERAL SITE LAYOUT OVERALL SITE			
P&ID ITEM No.	DRG No.	REV.	SHT
A1	9873-00002	D	1 OF 4



A SHEET 4

B SHEET 4

B SHEET 4

A SHEET 4

REVISION HISTORY			
REV	DESCRIPTION	DATE	APPROVED
D	MILL TOWERS WIDENED	18/10/2023	

CLIENT & PROJECT LOCATION  
**BAIADA TFM - TANGARATTA, NSW**

**PROPOSED FEEDMILL  
 GENERAL SITE LAYOUT  
 NEW MILL OVERVIEW**

P&ID ITEM No. DRG No. **9873-00002** REV. **D** SHT **2 OF 4**

**LGPM**  
 PROCESS INNOVATION  
 Bulk Materials Handling & Processing Systems

47-49 OVERSEAS DRIVE  
 NOBLE PARK, VIC 3174  
 PHONE: +61 (03) 9702 4855  
 EMAIL: info@lgpm.com.au  
 WEBSITE: www.lgpm.com.au

MDL JC 3/07/2023  
 DRN JC 24/07/2023  
 CHK


UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN mm

SCALE 1:400

THIRD ANGLE PROJECTION

MDL	JC	3/07/2023
DRN	JC	24/07/2023
CHK		

THIS DRAWING, ALL INFORMATION & DESIGNS HEREON, ARE THE PROPERTY OF LGPM. THIS DRAWING IS CONFIDENTIAL & MUST NOT BE MADE PUBLIC OR COPIED WITHOUT PRIOR WRITTEN AUTHORIZATION FROM LGPM AND IS SUBJECT TO RETURN ON DEMAND. NO USE OF THIS DRAWING, ANY INFORMATION OR DESIGNS HEREON IS PERMITTED EXCEPT WHEN SPECIFICALLY AUTHORIZED IN WRITING BY LGPM. ACCEPTANCE & POSSESSION OF THIS DRAWING CONSTITUTES AGREEMENT OF THE ABOVE CONDITIONS.





EXISTING MILL

- B DOUBLE TRUCK - OUTLOADING
- B DOUBLE TRUCK - LIQUIDS
- AB TRIPLE TRUCK - INLOADING

REVISION HISTORY			
REV	DESCRIPTION	DATE	APPROVED
D	MILL TOWERS WIDENED	18/10/2023	

<p><b>LGPM</b> Bulk Materials Handling &amp; Processing Systems</p>	<p>47-49 OVERSEAS DRIVE NOBLE PARK, VIC 3174 PHONE: +61 (0)3 9702 4855 EMAIL: info@lgpm.com.au</p>	<p>MDL JC 3/07/2023 DRN JC 24/07/2023 CHK</p>	<p>CLIENT &amp; PROJECT LOCATION BAIADA TFM - TANGARATTA, NSW</p>
	<p>UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN mm.</p>	<p>SCALE 1:600</p>	<p>PROPOSED FEEDMILL GENERAL SITE LAYOUT TRAFFIC FLOW OVERLAY</p>
	<p>PKET ITEM NO. DRG NO. 9873-00002</p>	<p>REV. D</p>	<p>SHT 3 OF 4</p>



REVISION HISTORY			
REV	DESCRIPTION	DATE	APPROVED
D	MILL TOWERS WIDENED	18/10/2023	

CLIENT & PROJECT LOCATION		BAIADA TFM - TANGARATTA, NSW	
PROPOSED FEEDMILL GENERAL SITE LAYOUT ELEVATION VIEWS			
PS/D ITEM No.	DRG No.	REV.	SHT
	9873-00002	D	4 OF 4


**LGPM**  
 PROCESS INNOVATION  
 Bulk Materials Handling & Processing Systems

47-49 OVERSEAS DRIVE  
 NOBLE PARK, VIC 3174  
 PHONE: +61 (03) 9702 4855  
 EMAIL: info@lgpm.com.au  
 WEBSITE: www.lgpm.com.au


MDL JC 3/07/2023  
 DRN JC 24/07/2023  
 CHK

UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN mm  
 SCALE 1:300  
 THIRD ANGLE PROJECTION

THIS DRAWING, ALL INFORMATION & DESIGNS HEREON, ARE THE PROPERTY OF LGPM. THIS DRAWING IS CONFIDENTIAL & MUST NOT BE MADE PUBLIC OR COPIED WITHOUT PRIOR WRITTEN AUTHORIZATION FROM LGPM AND IS SUBJECT TO RETURN ON DEMAND. NO USE OF THIS DRAWING, ANY INFORMATION OR DESIGN HEREON IS PERMITTED EXCEPT WHEN SPECIFICALLY AUTHORIZED IN WRITING BY LGPM. ACCEPTANCE & POSSESSION OF THIS DRAWING CONSTITUTES AGREEMENT OF THE ABOVE CONDITIONS.



## Appendix B. MPN Plans



**LEGEND**

- PROPOSED BUILDING
- PROPOSED EDGE OF PAVEMENT
- PROPOSED BARRIER KERB
- PROPOSED KERB AND CHANNEL
- PROPOSED STORM WATER MAIN
- PROPOSED TOP OF BATTER
- PROPOSED TOE OF BATTER
- PROPOSED CATCHMENT BOUNDARY
- PROPOSED SWALE DRAIN
- EXISTING CATCHMENT
- CONTOURS EXISTING
- CONTOURS PROPOSED
- SHEET FLOW
- PROPOSED ROOF AREA
- PROPOSED HARDSTAND AREA
- PROPOSED GROUND LEVEL AREA

**CATCHMENT SCHEDULE**

CATCHMENT	TYPE	AREA (ha)	TREATMENT
A	ROOF	0.214	SWALE
	HARDSTAND	1.609	BUFFER, SWALE
	LANDSCAPE	0.890	BUFFER, SWALE, GPT
B	HARDSTAND	0.450	BUFFER, SWALE
	LANDSCAPE	1.618	SWALE

**NOTE:**  
LITTER BASKETS TO BE FITTED TO FIELD INLETS LOCATED IN THE HARDSTAND AREAS.

A	05.04.24	DA ISSUE	BT	LS
ISSUE DATE		AMENDMENT	BY	APP

COPYRIGHT: THIS DESIGN AND PLANS ARE NOT TO BE USED OR REPRODUCED WHOLLY OR IN PART WITHOUT WRITTEN PERMISSION OF MPN CONSULTING PTY LIMITED 2023 ©

ABN: 39 062 191 799  
P: 61 7 3335 4555  
E: solutions@mpnc.au  
Level 4, Building 3, Kings Row Office Park, 42 McDougall Street, Milton, QLD, 4064

CLIENT:  
**BAIADA TFM**


**PROPOSED FEEDMILL GENERAL SITE LAYOUT**  
TANGARATTA, NSW


**STORMWATER CATCHMENT PLAN**

DESIGN: JB	DRAWN: LM	SCALES: AS SHOWN
CHKD: LS	APPRD: LS	DATE:
mpn JOB	DRAWING No.	REV
<b>9883</b>	<b>SKC.01</b>	<b>A</b>


**PRELIMINARY**

**NOT FOR CONSTRUCTION**








TYPICAL SWALE DRAIN DETAIL - TYPE 1 (0.5m DEEP)  
N.T.S.



TYPICAL SWALE DRAIN DETAIL - TYPE 2 (0.5m DEEP WITH 1.0m BASE)  
N.T.S.



TYPICAL SWALE DRAIN DETAIL - TYPE 3 (0.6m DEEP WITH 1.0m BASE)  
N.T.S.



LEGEND	
PROPOSED BUILDING	
PROPOSED EDGE OF PAVEMENT	
PROPOSED BARRIER KERB	
PROPOSED STORM WATER MAIN	
PROPOSED TOP OF BATTER	
PROPOSED TOE OF BATTER	
PROPOSED SWALE DRAIN	
EXISTING CATCHMENT	
CONTOURS EXISTING	
CONTOURS PROPOSED	



ISSUE	DATE	AMENDMENT	BY	APP.
B	05.04.24	DA ISSUE	BT	LS
A	09.02.24	DRAFT ISSUE	JB	LS

COPYRIGHT: THIS DESIGN AND PLANS ARE NOT TO BE USED OR REPRODUCED WHOLLY OR IN PART WITHOUT WRITTEN PERMISSION OF MPN CONSULTING PTY LIMITED 2023 ©

MPN CONSULTING  
 ABN: 39 062 191 799  
 P: 61 7 3335 4555  
 E: solutions@mpnc.au  
 Level 4, Building 3,  
 Kings Row Office Park,  
 42 McDougall Street, Milton, QLD, 4064

CLIENT:  
**BAIADA TFM**


**PROPOSED FEEDMILL  
GENERAL SITE LAYOUT**  
TANGARATTA, NSW

POST DEVELOPMENT PLAN		
DESIGN: JB	DRAWN: LM	SCALES: AS SHOWN
CHKD: LS	APPRD: LS	DATE:


mpn JOB	DRAWING No.	REV
<b>9883</b>	<b>SKC.02</b>	<b>B</b>

**PRELIMINARY**

**NOT FOR CONSTRUCTION**




LEGEND	
PROPOSED TOP OF BATTER	— · — · — · — · — · — · — · — · — · —
PROPOSED TOE OF BATTER	- - - - -
PROPOSED SWALE DRAIN	→ → → → →
CONTOURS EXISTING	- · - · - · - · - · - · - · - · - · -
CONTOURS PROPOSED	— — — — —




**BASIN DEPTH-AREA-VOLUME**


DEPTH (m)	ELEVATION (m)	AREA (m <sup>2</sup> )	Δ VOLUME (m <sup>3</sup> )	VOLUME TO HEIGHT (m <sup>3</sup> )
0.000	374.00	1019.1	0.0	0.0
0.125	374.13	1119.6	133.1	133.1
0.250	374.25	1232.3	147.0	280.1
0.375	374.38	1348.6	161.3	441.3
0.500	374.50	1468.3	176.0	617.3
0.625	374.63	1591.6	191.2	808.6
0.750	374.75	1718.5	206.8	1015.4
0.875	374.88	1848.8	222.9	1238.3
1.000	375.00	1982.7	239.4	1477.8



**TYPICAL ROCK LEVEL SPREADER DETAIL**  
N.T.S.



**TYPICAL V-NOTCH WEIR DETAIL**  
SCALE 1:10



**KEY PLAN**  
NTS



B	03.04.24	DA ISSUE	BT	LS
A	09.02.24	DRAFT ISSUE	JB	LS
ISSUE DATE	AMENDMENT	BY	APP	

A/N: 39 062 191 799  
 P: 61 7 3335 4555  
 E: solutions@mpnc.au  
 Level 4, Building 3,  
 Kings Row Office Park,  
 42 McDougall Street, Milton, QLD, 4064



CLIENT:  
**BAIADA TFM**  
**PROPOSED FEEDMILL**  
**GENERAL SITE LAYOUT**  
 TANGARATTA, NSW

BASIN DETAILS AND LAYOUT			
DESIGN: JB	DRAWN: LM	SCALES: AS SHOWN	
CHKD: LS	APPRD: LS	DATE:	


mpn JOB	DRAWING No.	REV
<b>9883</b>	<b>SKC.03</b>	<b>B</b>

**PRELIMINARY**

**NOT FOR CONSTRUCTION**



EXISTING	LEGEND	PROPOSED
---	PROPERTY BOUNDARY	---
---	EASEMENT BOUNDARY	---
---	CONTOUR	---
---	BUILDING	---
---	CONCRETE	---
---	EDGE OF BITUMEN	---
---	KERB AND CHANNEL	---
---	STORM WATER MAIN	---
---	RETAINING WALL	---
---	TOP OF BATTER	---
---	FACE OF BATTER	---
---	TOE OF BATTER	---
---	ESC CATCHMENT BOUNDARY	---
---	CLEAN CUT OFF DRAIN	---
---	DIRTY CUT OFF DRAIN	---
---	CLEAN WATER CUT OFF BUND	---
---	DIRTY WATER CUT OFF BUND	---
---	SEDIMENT FENCE	---
---	CONSTRUCTION ENTRY / EXIT	---
---	CHECK DAM	---
---	ROCK FILTER DAM	---
---	INLET SEDIMENT TRAP	---



ROCK CHECK DAMS AT MAX 50m SPACING TO ALL SWALES

WALLAMORE ROAD

NOT FOR CONSTRUCTION

A	05.04.24	DA ISSUE		JB	BT
ISSUE	DATE	AMENDMENT		BY	APP

COPYRIGHT: THIS DESIGN AND PLANS ARE NOT TO BE USED OR REPRODUCED WHOLLY OR IN PART WITHOUT WRITTEN PERMISSION OF MPN CONSULTING PTY LIMITED 2022 ©


 ABN: 39 062 191 799  
 P: 61 7 3335 4555  
 E: solutions@mpnc.au  
 Level 4, Building 3,  
 Kings Row Office Park,  
 42 McDougall Street, Milton, QLD, 4064

CLIENT:  
**BAIADA TFM**  
**PROPOSED FEEDMILL**  
**GENERAL SITE LAYOUT**  
 TANGARATTA, NSW

**EROSION AND SEDIMENT LAYOUT**

DESIGN: JB	DRAWN: BT	SCALES: AS SHOWN
CHKD: LS	APPRD: LS	DATE:

mpn JOB	DRAWING No.	REV
<b>9883</b>	<b>SKC.04</b>	<b>A</b>

**PRELIMINARY**

