



MATERIALS & FINISHES SCHEDULE (Refer to Sample Board for Further Information)

- (M1) Balustrade Type 1:
Framed balustrade system. Framing system, aluminum, powder coat finish. Colour to match GW1.
- (C1) Cladding Type 1:
Metal cladding system. Prefinished coating system. Colour and finish to match Alpic 'Charcoal'.
- (C2) Cladding Type 2:
Metal cladding system with expressed vertical aluminum fins over. Frequency of expressed fins vary. Metal cladding prefinished coating system. Colour and finish to match Alpic 'Medium Bronze Metallic'. Aluminum fins powder coat finish, colour equal to GW2.
- (C3) Cladding Type 3:
Metal cladding system with integrated louvers for building services. Prefinished coating system. Colour and finish to match Alpic 'Silver Metallic' and 'Medium Grey Metallic'. Distribution of panel type (i.e. solid / louvre) and colour varies across facade.

- (C4) Cladding Type 4:
Expressed vertical aluminum fins fixed over paint finish off form concrete. Frequency of fins varies. Fins powder coat finish, colour equal to GW2. Paint finish equal to PF1.
- (GW1) Glazed Wall System, Type 1:
Flush fixed aluminum framed glazed wall system to facade engineers specifications. Vision panel clear glass, green tint. Non-vision panel opaque colour back glass, colour to match. Aluminum frame powder coat finish, colour equal to Interpon Monument Matt. Performance of overall system to meet ESD and facade engineers requirements. Reflectivity to be less than 20%.
- (GW2) Glazed Wall System, Type 2:
Expressed mullions aluminum framed glazed wall system. Frequency of expressed mullions vary. Vision panel clear glass, light grey tint. Non-vision panel opaque colour back glass, colour to match. Aluminum frame including expressed mullions, powder coat finish, colour equal to Dulux Earthly Bronze Pearl Satin. Performance of overall system to meet ESD and facade engineers requirements. Reflectivity to be less than 20%.

- (GW3) Glazed Wall System, Type 3:
Expressed mullions aluminum framed glazed wall system. Frequency of expressed mullions vary. Vision panel translucent glass, light grey tint. Non-vision panel opaque colour back glass, colour to match. Aluminum frame including expressed mullions, powder coat finish, colour equal to GW2. Performance of overall system to meet ESD and facade engineers requirements. Reflectivity to be less than 20%.
- (PF1) Paint Finish Type 1:
Paint finish with cement render and / or FC lining to substrate. Colour to match Dulux 'Domino'.
- (S1) Screen, Type 1:
Vertical aluminum sun shade screen system, full height. Powder coat finish, colours equal to Interpon 'Gilded Green Matt', 'Cottage Green Matt', 'Wilderness Matt' and 'Headland Matt'.
- (S2) Screen, Type 2:
Vertical aluminum fins with integrated subframe. Powder coat finish, colour equal to GW2.