



MATERIALS & FINISHES SCHEDULE (Refer to Sample Board for Further Information)

- BAL1** Balustrade Type 1:
Framed balustrade system. Framing system, aluminium, powder coat finish. Colour to match GW1.
- CL1** Cladding Type 1:
Metal cladding system. Prefinished coating system. Colour and finish to match Alpolc 'Charcoal'.
- CL2** Cladding Type 2:
Metal cladding system with expressed vertical aluminium fins over, frequency of expressed fins vary. Metal cladding prefinished coating system, colour and finish to match Alpolc 'Medium Bronze Metallic'. Aluminium fins powder coat finish, colour equal to GW2.
- CL3** Cladding Type 3:
Metal cladding system with integrated louvres for building services. Prefinished coating system. Colour and finish to match Alpolc 'Silver Metallic' and 'Medium Grey Metallic'. Distribution of panel type i.e solid / louvre and colour varies across façade.
- CL4** Cladding Type 4: **NOT USED**
- GW1** Glazed Wall System, Type 1:
Flush lined aluminium framed glazed wall system to façade engineers specification. Vision panel clear glass, green tint. Non-vision panel opaque colour back glass, colour to match. Aluminium frame powder coat finish, colour equal to Interpon 'Monument Matt'. Performance of overall system to meet ESD and façade engineers requirements. Reflectivity to be less than 20%.
- GW2** Glazed Wall System, Type 2:
Expressed mullions aluminium framed glazed wall system, frequency of expressed mullions vary. Vision panel clear glass, no tint. Non-vision panel opaque colour back glass, colour to match. Aluminium frame including expressed mullions, powder coat finish, colour equal to Dulux 'Eternity Bronze Pearl Satin'. Performance of overall system to meet ESD and façade engineers requirements. Reflectivity to be less than 20%.
- GW3** Glazed Wall System, Type 3:
Expressed mullions aluminium framed glazed wall system, frequency of expressed mullions vary. Vision panel translucent glass, light grey tint. Non-vision panel opaque colour back glass, colour to match. Aluminium frame including expressed mullions, powder coat finish, colour equal to GW2. Performance of overall system to meet ESD and façade engineers requirements. Reflectivity to be less than 20%.
- PF1** Paint Finish, Type 1:
Paint finish with cement render and / or FC lining to substrate. Colour to match Dulux 'Domino'.
- PF2** Paint Finish, Type 2:
Decorative wall finish, cement render and paint.
- SC1** Screen, Type 1:
Vertical aluminium sun shade screen system, full height. Powder coat finish, colours equal to Interpon 'Glided Green Matt', 'Cottage Green Matt', 'Wilderness Matt' and 'Headland Matt'.

NOTES
 1. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE SPECIFIED.
 2. REFER TO ARCHITECTURAL DRAWINGS FOR FINISHES AND MATERIALS.
 3. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR SERVICES.
 4. REFER TO STRUCTURAL DRAWINGS FOR CONCRETE AND STEELWORK.
 5. REFER TO LANDSCAPE ARCHITECTURE DRAWINGS FOR LANDSCAPE AND PLANTING.
 6. REFER TO CIVIL DRAWINGS FOR ROADWORK AND UTILITIES.
 7. REFER TO ENVIRONMENTAL DRAWINGS FOR ENVIRONMENTAL IMPACT ASSESSMENT.
 8. REFER TO SUSTAINABILITY DRAWINGS FOR SUSTAINABILITY STRATEGIES.
 9. REFER TO SPECIALIST DRAWINGS FOR SPECIALIST SERVICES.
 10. REFER TO CONTRACT DOCUMENTS FOR CONTRACT CONDITIONS AND SPECIFICATIONS.

CLIENT
 THE GPT GROUP
 Level 51 MLC Centre 19 Martin Pl Sydney
 NSW 2000 AU

PROJECT MANAGER
 LEND LEASE
 The Bond, 30 Hickson Road, Millers Point,
 NSW 2000 AU

GPT
 The GPT Group

LEND LEASE

Project Title
 4MR
 4 Murray Rose Avenue SOP NSW 2127 AU

Scale
 1:100 (A4), 1:250 (A3)

Section 96 Submission
 Date: 16/11/21 DS
 Approved by: [Signature] Project No: 12022
 Drawn by: CM
 Checked by: H
 Date: 16/11/21 DS
 Approved by: [Signature] Project No: 12022
 Drawn by: CM
 Checked by: H

SECTIONS
 Section B

TURNER