

ARBORICULTURAL REPORT

Arboricultural Impact Assessment (AIA)

ESR

Banksmeadow SSDA Development

49-61 Stephen Road, Banksmeadow

27 March 2026

JN2246

Report Prepared By:

Marc Fisher (AQF5 Arboriculture)



ArborScan

Document Details and Record of Revisions

Company	ArborScan Pty Ltd
ABN	ABN 26 651 625 400
Phone	1800 ARBORSCAN (272 677)
Email	reports@arborscan.com.au

Client	ESR
Client Representative	Grace Macdonald
Site Location	49-61 Stephen Road Banksmeadow NSW 2019

Document Type	Arboricultural Impact Assessment (AIA)
Report Reference	JN2246
Report Prepared By / Author	Marc Fisher Arboricultural Consultant AQF5
ArborScan Industry Affiliations/Memberships	 Member – 240990  Member - 256027

Version Number	Date	Revision Description
Version 3	27 March 2026	Final Version

© (Copyright) ArborScan Pty Ltd 2026

This document remains the property of ArborScan Pty Ltd. The client is entering into a license to use this document and does not gain full ownership. All rights reserved. Except for purposes permitted by the Australian Copyright Act 1968, reproduction, adaption, electronic storage, transmission, and communication to the public by any means is prohibited without our written permission. This document may only be used for the purpose described in this document upon full payment of the fee by the licensee. The licensee is authorised to make an electronic copy of this document for filing purposes. Any third-party material, including images, maps & information contained in this publication, remains the property of the specified copyright owner unless otherwise indicated and is used subject to their licensing conditions. Copyright protects this publication.

27 March 2026

Grace Macdonald
ESR
Level 12, 135 King Street
Sydney NSW 2000

Arboricultural Impact Assessment (AIA) for Site 49-61 Stephen Road Banksmeadow NSW 2019

Dear Grace,

We are pleased to provide you with the following report to assist with the proposed Industrial development at 49-61 Stephen Road Banksmeadow NSW 2019.

This Arboricultural Impact Assessment (AIA) report is intended to identify any significant trees that could be affected by the development and to assess the likely impact of the proposed works on these trees. The report also provides recommendations for the protection of significant trees and the appropriate management measures that should be taken during and after the construction work. Protection zone advice includes specifications for fencing/trunk guards, signage, and other measures to protect trees during the construction process.

Complete use of this report is authorised under the conditions limiting its use as stated in the Arboricultural Reporting Assumptions, Limiting Conditions & Copyright Clause. This assessment and report is supplied strictly in accordance with the inclusions, conditions, terms and exclusions as detailed within our most recent quotation.

Any recommendations of this report do not constitute consent to carry out works. Approval is required in the form of Development Consent to prune or remove trees, as well as the consent of the tree owner where trees are on adjoining lands.

ArborScan Pty Ltd declares that it has no affiliation with any private contractors, associations or nurseries involved in the tree removal, pruning and tree supply business. This ensures an impartial approach to the recommendations given within this report.

Should you have any queries relating to this report or its recommendations, please do not hesitate to contact us on 1800 ARBORSCAN (272 677).

Regards,

Marc Fisher
Consulting Arborist
ArborScan Pty Ltd

Table Of Contents

1	Executive Summary	5
2	Introduction	6
3	Methodology	7
4	Observations.....	8
5	Impact Assessment.....	15
6	Recommendations	18
7	Tree Protection Specifications (TPS) AS 4970–2025	22
8	References.....	31
9	Impact Assessment Schedule.....	32
10	Tree Protection Plan (TPP).....	44
	Appendix 1. Assumptions and Limiting Conditions	52
	Appendix 2. Description of Survey Assessment Terms.....	53
	Appendix 3. General Arboricultural Terms	56
	Appendix 4. STARS® Tree Retention Value Matrix	58

1 Executive Summary

ArborScan Pty Ltd was commissioned by ESR (the Client) to undertake an Arboricultural Impact Assessment (AIA) of trees located at 49–61 Stephen Road, Banksmeadow NSW. The assessment considers 163 individually tagged trees (172 trees when grouped specimens are included), comprising 111 trees within the subject site and a further 52 trees located on adjoining or boundary land. The assessment has been prepared in accordance with recognised industry methodologies, including Visual Tree Assessment (VTA), the IACA STARS retention value system, and the Australian Standard AS 4970–2025 – Protection of Trees on Development Sites.

The proposed development results in a defined level of impact to the existing tree population, primarily associated with building footprints, bulk earthworks, and infrastructure installation. Of the 163 trees assessed, 61 trees are proposed for removal, while 102 trees are recommended for retention. Removals are predominantly attributed to trees subject to major encroachment, defined as impacts exceeding 20% of the Notional Root Zone (NRZ) or direct intrusion into the Structural Root Zone (SRZ), or where trees are located within the unavoidable development footprint or present as low retention value specimens. Conversely, trees identified for retention include all high retention value trees and a substantial proportion of medium and low value trees where impacts are considered manageable through appropriate design and construction controls.

The assessment identifies that a considerable proportion of trees are subject to major encroachment scenarios, reflecting the constrained nature of the site and the extent of proposed works. Notwithstanding this, retention has been recommended where feasible, supported by the adoption of tree-sensitive construction methodologies, including non-destructive excavation and constructing roadways above grade to minimising root disturbance. Where encroachment remains within minor to moderate thresholds, tree viability is considered achievable subject to the implementation of prescribed protection measures. Where impacts exceed acceptable thresholds and cannot be mitigated through design modification or construction methodology, removal has been recommended as the most appropriate outcome.

A number of assessed trees are located on adjoining land, and no works may be undertaken to these trees without the consent of the relevant landowner and, where applicable, the appropriate authority. Three trees (**Tree 107, 110, and 151**) have been identified where removal is required, and these will necessitate formal notification and approval prior to any works proceeding.

The successful retention of nominated trees is contingent upon strict adherence to the recommendations of this report and the requirements of AS 4970–2025. This includes the establishment of Tree Protection Zones (TPZs), installation of protective fencing, restriction of activities within TPZs, avoidance of soil level changes, and the use of non-destructive excavation techniques where required. Ongoing supervision and certification by a suitably qualified AQF Level 5 Project Arborist will be essential to ensure compliance and to manage unforeseen site conditions. Where conflicts arise during construction that cannot be reasonably mitigated, further assessment will be required, and recommendations may need to be updated to reflect site conditions at the time of works.

Overall, the assessment demonstrates that the proposed development can proceed with a balanced and defensible approach to tree management, facilitating the retention of higher-value trees while accommodating necessary removals driven by design constraints. This report should be read in conjunction with the detailed impact assessment schedule and tree protection plans, which provide tree-specific recommendations and are critical to the informed implementation of the proposed works.

2 Introduction

2.1 Report Purpose

- 2.1.1 ArborScan Pty Ltd was commissioned by ESR (The Client) to complete an Arboricultural Impact Assessment (AIA) for 163 trees (excluding groups) at 49-61 Stephen Road Banksmeadow NSW 2019 (The Site).
- 2.1.2 The purpose of this Arboricultural Impact Assessment (AIA) is to outline measures for managing existing trees in relation to proposed activities such as tree removal, tree pruning, demolition and construction/development at the site.
- 2.1.3 Comprehensive information regarding the trees located on the site, including an assessment of any development constraints they may pose, is required. Based on this assessment, recommendations regarding the preservation of trees in the developable regions immediately and nearby need to be discussed and presented.

2.2 Scope

- 2.2.1 Carry out a visual examination of the trees within the areas that have been identified by/with the Client for inspection. This includes any trees bordering on neighbouring allotments, or Council land, which have the potential to be impacted.
- 2.2.2 Conduct a thorough inspection of the trees and their growing environment and provide an impartial evaluation of the trees based on their species, estimated age, expected useful life, health, structural condition, and suitability for the landscape.
- 2.2.3 Measure tree stems in order to identify the NRZ, TPZ and SRZ.
- 2.2.4 Estimate tree height and widest canopy spread.
- 2.2.5 Provide independent recommendations on the retention value of the trees using a recognised tree significance rating system.
- 2.2.6 Assign identification numbers to the trees on aerial maps to facilitate their location on the site. Where directly specified by the Client, the numbering system is to be consistent with any previous reports and plans. New trees are to be added sequentially from the last tree number listed.
- 2.2.7 Identify hollows/cavities and features that may benefit native Fauna.
- 2.2.8 Include a schedule documenting tree attributes, calculated NRZ, TPZ, SRZ, calculated development incursions (if any) and recommendations in relation to retention values in accordance with AS 4970-2025: Protection of Trees on Development Sites.
- 2.2.9 Create a Tree Protection Plan (TPP) identifying trees that are proposed to be retained or removed, identify the tree protection area for each tree, clearly identify the development encroachment to the TPZ and further markup an approximate location for tree protection fence installation. The plan will be site-specific and will relate to the proposed development works. The provided plan is intended to be used as a reporting guide only, and it is not intended to be used for construction/development.
- 2.2.10 Where required by the project scope, recommend replacement species for any trees identified for removal.
- 2.2.11 Identify limitations and further reporting requirements.
- 2.2.12 Provide supporting evidence in the form of a PDF report to aid with the local Authority's development application process.

3 Methodology

- 3.1.1 Marc Fisher (The Author) of ArborScan Pty Ltd carried out a site inspection of the subject trees during the month of February 2024.
- 3.1.2 Trees that are the subject of this report were identified during discussions with the Client at the time of the requested site consultation and tree assessment.
- 3.1.3 The subject trees were inspected from the ground using the initial component of the recognised ground-based Visual Tree Assessment (VTA) technique (without the use of binoculars) developed by Mattheck and Breloer (1994), without the use of aerial or internal investigation, foliage, wood or soil sample analysis nor an underground investigation of the root plate.
- 3.1.4 Unless specified otherwise, tree height and widest canopy spread were estimated.
- 3.1.5 In instances where there were no restrictions on accessing the tree stem, such as in neighbouring property or areas with dense vegetation, diameter measurements were taken using forestry callipers. For tree stems that were not accessible, an estimated stem size was recorded.
- 3.1.6 NRZ, TPZ and SRZ were calculated in accordance with the Australian Standard AS 4970–2025: Protection of Trees on Development Sites.
- 3.1.7 Tree retention/significance values were determined using the Institute of Australian Consulting Arboriculturists, Australia (IACA) Significance of a Tree, Assessment Rating System (STARS).
- 3.1.8 ArborScan did not receive georeferenced plans. Instead, the NSW Sites cadastre boundary was utilised to manually place the site plans and surveyed tree locations. It should be acknowledged that the cadastre boundary utilised to locate the plans and surveys incorporated in this report may not accurately represent the property's boundary surveyed in the field. However, the plans and surveys are presented in a consistent scale with the uploaded files.
- 3.1.9 The subject trees have been tagged; they have also been mapped on high-resolution aerial imagery, with their number and location readily identifiable on the plan.
- 3.1.10 Any photographs that were taken at the time of the site inspection by the Author and have not been altered for brightness or contrast, nor have they been cropped.
- 3.1.11 A visual inspection from ground level for hollows/cavities and features that may benefit native Fauna has been performed by the Author on the day of the assessment. A licenced and trained ecological consultant has not been commissioned.
- 3.1.12 A risk assessment has not been performed for the purpose of this report. Data collected on the Site was analysed by the Author, collated into report format, and relevant recommendations were formulated.

4 Observations

4.1 The Site

- 4.1.1 The property at 49 Stephen Road, Banksmeadow, is a significant former industrial site, historically utilised for chemical manufacturing. Located within the highly sought-after South Sydney precinct, this site is one of the few remaining large-scale industrial landholdings in the Botany Bay area. Its proximity to major transport links, including Sydney Airport, Port Botany, and key arterial roads such as the M5 and M1 motorways, positions it as an ideal location for logistics, warehousing, and distribution operations.
- 4.1.2 With a substantial land area, ESR has the opportunity to develop a state-of-the-art two-level facility offering a Gross Floor Area (GFA) of approximately 58,000 sqm. The design could cater to modern industrial and commercial needs, incorporating sustainable building practices, advanced technological infrastructure, and efficient supply chain solutions. The site's ample space and dual-level configuration provide flexibility for tenants across various sectors, including manufacturing, e-commerce, and third-party logistics.

Table 1. General Site Details (ePlanning Spatial Viewer Property Report, Accessed 27 March 2026)

Site Details and Potential Planning Constraints	
KNOWN SITE NAME	Allnex Regional Head Office
STREET ADDRESS	49-61 Stephen Road Banksmeadow NSW 2019
LOT AND DP	A/-/DP190526
LOCAL GOVERNMENT AREA	BAYSIDE COUNCIL
LOCAL ENVIRONMENTAL PLANS	Bayside Local Environment Plan (2021)
LAND ZONING	IN1 - General Industrial: (pub. 8-7-2022)



Figure 1. Site map depicting boundary and land zoning. (NSW Planning Portal Spatial Viewer, 27 March 2026)

4.2 Statutory Planning Mapping Constraints (Desktop Review)

4.2.1 A desktop review of publicly available NSW Government and Local Council statutory mapping layers has been undertaken to identify potential planning constraints relevant to the subject site. This review is strictly limited to the mapping layers listed in Table 2. The assessment comprises a desktop GIS interrogation only and does not include field verification, cadastral survey confirmation, ecological ground-truthing, heritage assessment, aviation assessment, hydrological investigation, or broader town planning due diligence. Other statutory, environmental, zoning, easement, infrastructure, or site-specific constraints may apply but fall outside the scope of this arboricultural assessment. The information provided is advisory in nature and should not be relied upon as a comprehensive planning feasibility assessment. Engagement of a qualified town planning professional is recommended where development approval pathways are being considered.

Table 2. Statutory Planning Mapping Layers – Desktop Review Summary

No.	Constraint Name	Identified	Typical Advisor
1	Mapped Biodiversity Values	No	Ecologist
2	Mapped Terrestrial Biodiversity Values	No	Ecologist, Town Planner
3	Mapped Bushfire Prone Land, Vegetation Buffer, Vegetation Category 1 or 2	No	Bushfire Consultant
4	Mapped Heritage - Local	No	Heritage Consultant, Town Planner
5	Mapped Heritage - State	No	Heritage Consultant, Town Planner
6	Mapped Obstacle Limitation Surface	No	Town Planner
7	Mapped Riparian Lands and Watercourses	No	Ecologist
8	Mapped Scenic Protection Land	No	Town Planner
9	Mapped Wetlands	No	Ecologist, Town Planner
10	Mapped Environmentally Significant Land	No	Ecologist, Town Planner
11	Significant Tree Register	No	Heritage Consultant, Town Planner

4.3 Fauna / Wildlife Features

- 4.3.1 Habitat features capable of supporting Fauna such as Hollows, Stick nests, Nesting boxes, Carved hollows and Lifting loose bark were observed within none of the trees surveyed during the ground-based VTA inspection performed.

4.4 Ecological Considerations – Threatened Flora & Fauna

- 4.4.1 This report does not constitute an ecological assessment. ArborScan specialises in arboricultural tree care and management. Matters concerning protected vegetation communities or threatened species have not been addressed in this Arboricultural Impact Assessment (AIA). The report aims to evaluate the specific impacts on trees resulting from the proposed development design to determine the feasibility of tree retention or removal. While the loss of key vegetation species and threatened plants or wildlife is highly significant, this must be addressed by an expert in the field.

4.5 Tree Protection and Preservation Within the Local Government Area

- 4.5.1 Trees and vegetation, even those on private land, are protected under the State Environmental Planning Policy (Biodiversity and Conservation) 2021 (NSW), which prescribes that tree and vegetation works are to be processed using a permit system administered by BAYSIDE COUNCIL through its Development Control Plan.
- 4.5.2 Any exemptions under the BAYSIDE COUNCIL DCP may not be applicable to land that is a heritage item or within a heritage conservation area, Threatened Ecological Communities or for Native vegetation that is on land included on the Biodiversity Values Map. See the tree data table for guidance on trees that are deemed a proscribed tree, requiring approval from the land authority.

4.6 Tree Location & Ownership

- 4.6.1 A total of 163 tree numbers have been assessed as part of this report which includes a total of 172 trees when considering tree grouping (The criteria for tree grouping has been based on the selection of nearby trees which are of a similar species and size/condition attribute).
- 4.6.2 The subject site has a total of 111 assessed trees. In addition, there are 52 trees situated on adjoining lands or which are located beyond the fenced perimeter boundary. Trees on adjoining lands include **4, 5, 6, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 107, 108, 109, 110, 111, 124, 125, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163.**

4.7 Summary Of Tree Retention Values

- 4.7.1 Retention values have been determined using the Retention Value - Priority Matrix of the IACA Significance of a Tree, Assessment Rating System (STARS) (IACA, 2010).
- 4.7.2 This method uses a scale of High, Medium and Low significance in the landscape. Once the landscape significance of an individual tree has been defined, the retention value can be determined. Other criteria such as its physical dimensions, age class, location and its Amenity, Heritage and Environmental significance are also considered.
- 4.7.3 In accordance with the STARS Tree Significance - Assessment Criteria and Tree Retention Value - Priority Matrix, the retention value categories include:

Table 3. Summary Of IACA Significance of a Tree, Assessment Rating System (STARS)

STARS® Retention Value	Qty	%	Tree Numbers
HIGH	11	6.7	4, 117, 118, 137, 140, 141, 143, 144, 147, 159, 161
MEDIUM	74	45.4	2, 6, 12, 13, 14, 17, 19, 20, 22, 23, 24, 25, 28, 29, 30, 32, 33, 35, 43, 46, 47, 50, 51, 53, 55, 56, 57, 58, 60, 61, 66, 67, 68, 69, 70, 88, 89, 91, 92, 93, 94, 95, 96, 98, 99, 100, 101, 102, 105, 106, 107, 108, 110, 111, 114, 115, 116, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 136, 138, 156, 162, 163
LOW	77	47.2	1, 3, 5, 7, 8, 9, 10, 11, 15, 16, 18, 21, 26, 27, 31, 34, 36, 37, 38, 39, 40, 41, 42, 44, 45, 48, 49, 52, 54, 59, 62, 63, 64, 65, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 90, 97, 103, 109, 112, 113, 119, 132, 133, 134, 135, 139, 142, 145, 146, 148, 149, 150, 151, 152, 153, 154, 155, 157, 158, 160
PRIORITY FOR REMOVAL	1	0.7	104

4.8 Proposed Development

4.8.1 An overview of the works being proposed is as follows:

- Demolition of existing structures, above ground services and hard surfaces
- Contaminated soil remediation
- Tree removal
- Grading and level changes
- Road construction and road widening
- Development of structures & essential service installation
- Landscaping works

4.8.2 Plans and associated reports provided by the Client include:

- CO14950.01 - 26.03.04 Revised Civil Package
- Appendix F - Architectural Plans




Figure 2. Client plans representing the development works proposed. (Viewed, 27 March 2026)

4.9 Notional Root Zone Encroachment

- 4.9.1 As per the Australian Standard AS 4970–2025: Protection of Trees on Development Sites, it may be possible to encroach into or modify the Notional Root Zone (NRZ) under specific conditions. Encroachment may include activities such as excavation, the placement of compacted fill, or machine trenching. Where encroachment results in the loss of NRZ area, an equivalent area must be compensated for elsewhere.
- 4.9.2 Tree-sensitive construction methods such as pier and beam footings, suspended slabs, cantilevered building elements, screw piles, or contiguous piling should be adopted where feasible to minimise disturbance to the NRZ and TPZ.
- 4.9.3 The levels of permissible encroachment are defined within AS 4970–2025, and must be carefully assessed by a qualified arborist to determine whether the level of intrusion constitutes a minor or major encroachment. Where a major encroachment is proposed or unavoidable, specific tree protection and mitigation measures will be required to support tree retention.
- 4.9.4 The levels of encroachment are defined below:

Table 4. Encroachment AS 4970–2025: Protection of Trees on Development Sites

Major Encroachment (>20% NRZ or SRZ Impact)	Major encroachment is considered to occur when development works impact more than 20% of the total NRZ area or directly intrude into the SRZ. Trees affected by major encroachment are at significant risk of structural failure or long-term decline. In most cases, tree removal will be required unless non-destructive root mapping confirms minimal impact to critical structural roots and appropriate design modifications can be implemented. Where retention is proposed, extensive arboricultural supervision and ongoing tree protection measures will be required throughout all construction stages.
Moderate Encroachment (10%–20% NRZ)	Moderate encroachment occurs where development works impact between 10% and 20% of the total NRZ area. Trees with moderate encroachment require assessment and written justification by an AQF Level 5 consulting arborist to demonstrate that the tree can be viably retained. Exploratory root mapping and non-destructive excavation techniques may be necessary to identify the extent and significance of roots within the affected area. Where retention is feasible, design modifications such as bridging slabs, pier and beam footings, or boring for services must be implemented to minimise impacts. Tree removal may be recommended where roots critical to tree stability and health are likely to be irreparably damaged.
Minor Encroachment (<10% NRZ)	Minor encroachment is determined as being less than 10% of the total NRZ area and outside the SRZ. Trees with minor encroachment can generally be retained with standard tree protection measures, or with specific low-impact protection requirements as recommended by a consulting arborist. Where encroachment cannot be avoided, works must be undertaken using non-destructive techniques such as pneumatic, hydraulic, or hand digging to ensure critical roots (typically >30 mm diameter) are preserved. Tree removal is generally not required for minor encroachments unless pre-existing health or structural concerns render the tree unsuitable for retention.
No NRZ Encroachment (0%)	No encroachment is determined where development works are located entirely outside the NRZ and SRZ. Trees with no encroachment can typically be retained with standard tree protection fencing and exclusion zones installed prior to works commencing. No further arboricultural intervention is required unless site conditions change during the course of the project.

Table 5. Notional Root Zone Encroachment Summary

Encroachment Type	Qty	%	Tree Number(s)
Major Encroachment (>20% NRZ or SRZ Impact)	97	59.5	1, 2, 3, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 104, 105, 106, 107, 108, 109, 110, 129, 130, 131, 133, 151
Moderate Encroachment (10%–20% NRZ)	6	3.7	25, 26, 93, 94, 128, 132
Minor Encroachment (<10% NRZ)	4	2.5	92, 126, 127, 156
No Encroachment (0% NRZ)	56	34.4	4, 5, 90, 91, 95, 96, 97, 98, 99, 100, 101, 102, 103, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 152, 153, 154, 155, 157, 158, 159, 160, 161, 162, 163

4.10 Mitigating Development Impacts

4.10.1 The following table details the requirements according to AS 4970-2025, alongside the necessary mitigation measures for each encroachment category. These mitigation measures are applicable only if the trees are intended to be preserved.

Encroachment Type	Mitigation Measures
No Encroachment (0% NRZ)	Not applicable.
Minor Encroachment (<10% NRZ)	- The area lost to this encroachment should be compensated for elsewhere, contiguous with the NRZ. - Detailed root investigations are generally not required. - Tree protection must be installed and maintained.
Moderate Encroachment (10%–20% NRZ)	- The project arborist must demonstrate that the tree(s) would remain viable post-encroachment. - Root investigation by non-destructive methods may be required to confirm root location and distribution. - The area lost to this encroachment should be compensated for elsewhere, contiguous with the NRZ. - Tree protection must be installed and maintained. - The project arborist must supervise any works within the NRZ.
Major Encroachment (>20% NRZ or SRZ Impact)	- The project arborist must demonstrate the tree(s) would remain viable post-encroachment. - Detailed root investigation by non-destructive methods will likely be required for any trees proposed for retention. - A thorough assessment of relevant factors (tree species, condition, site constraints, design factors) must be undertaken. - The area lost to this encroachment should be compensated for elsewhere, contiguous with the NRZ. - Tree protection must be installed and maintained. - The project arborist must supervise any works within the NRZ.

5 Impact Assessment

- 5.1.1 The presumption of permissible encroachment on trees, while minimising any potential long-term health or structural damage, is contingent upon a comprehensive approach. This involves adherence to root-sensitive construction methods within the TPZ, limited excavation within the TPZ to avoid root severance, avoidance of any construction within the SRZ, availability of compensatory space surrounding the unaffected aspects of the tree, and enhancement of the existing TPZ through techniques such as mulching, soil conditioning, and irrigation as needed.
- 5.1.2 A review of the proposed design has been undertaken in the context of tree retention and removal across the site; the following trees have been identified to be impacted by the proposal –

Table 6. No Encroachment (0% NRZ)

Category	Qty	Tree Number(s)
Retain - Retained with no encroachment based on the development design.	54	4, 5, 90, 91, 95, 96, 97, 98, 99, 100, 101, 102, 103, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 152, 153, 154, 155, 157, 158, 159, 160, 161, 162, 163
Remove - Reasons unrelated to development impacts alone.	2	134, 135

Table 7. Minor Encroachment (<10% NRZ)

Category	Qty	Tree Number(s)
Retain - Susceptible to minor encroachment as a result of the development.	4	92, 126, 127, 156

Table 8. Moderate Encroachment (10%–20% NRZ)

Category	Qty	Tree Number(s)
Retain - Conflicts exist between the NRZs and the disturbance footprint. However, these impacts are considered manageable, and the trees are expected to remain viable for retention, provided that the specified tree protection measures and any root investigation works are strictly followed. Please refer to the data table and the assigned tree protection requirements for each tree to guide their retention and management.	5	25, 26, 93, 94, 128

Category	Qty	Tree Number(s)
Remove – These trees fall within the disturbance footprint of the proposed development. Regrettably, due to the expected extent of root severance or damage from the proposed construction activities, these trees are classified as having a ‘Moderate’ encroachment. Consequently, the retention of these trees is not feasible within the current development design.	1	132

Table 9. Major Encroachment (>20% NRZ or SRZ Impact)

Category	Qty	Tree Number(s)
Retain - Conflicts exist between the NRZs and the disturbance footprint. However, these impacts are considered manageable, and the trees are expected to remain viable for retention, provided that the specified tree protection measures and any root investigation works are strictly followed. Please refer to the data table and the assigned tree protection requirements for each tree to guide their retention and management.	39	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 108, 109, 130, 131
Remove – These trees fall within the disturbance footprint of the proposed development. Regrettably, due to the expected extent of root severance or damage from the proposed construction activities, these trees are classified as having a significant ‘Major’ encroachment. Consequently, the retention of these trees is not feasible within the current development design.	58	1, 2, 3, 16, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 104, 105, 106, 107, 110, 129, 133, 151

Table 10. Total Tree Summary Based On Design Proposal or When Considering Poor Tree Condition or Hazardous Trees

Status Breakdown			
Item	Tree Qty.	%	Tree Number(s)
Remove	61	37.4	1, 2, 3, 16, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 104, 105, 106, 107, 110, 129, 132, 133, 134, 135, 151
Retain	102	62.6	4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 108, 109, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 130, 131, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163

Table 11. Summary Of the Tree Status Breakdown Based On STARS Retention Value

Status Breakdown			
Item	Qty Retain	Qty Remove	Qty Habitat prune
HIGH	11	0	0
MEDIUM	50	24	0
LOW	41	36	0
PRIORITY FOR REMOVAL	0	1	0

Table 12. Summary Of The Tree Species Proposed For Removal

Status Breakdown	
Botanical Species	Qty
<i>Callistemon viminalis</i>	14
<i>Casuarina cunninghamiana</i>	1
<i>Casuarina glauca</i>	25
<i>Corymbia gummifera</i>	1
<i>Corymbia maculata</i>	1
<i>Cupressus torulosa</i>	7
<i>Elaeocarpus reticulatus</i>	1
<i>Eucalyptus sp.</i>	1
<i>Ficus sp.</i>	1
<i>Fraxinus angustifolia</i> ssp. <i>oxycarpa</i> 'Raywood'	2
<i>Glochidion ferdinandi</i>	1
<i>Hibiscus sp</i>	1
<i>Plumeria rubra</i> var. <i>acutifolia</i>	2
<i>Ricinus communis</i>	1
<i>Syagrus romanzoffiana</i>	1
<i>Unknown sp.</i>	1

6 Recommendations

6.1 Modifying Site Plans and Survey

- 6.1.1 The client must ensure that all site plans, survey plans, and associated project documentation are reviewed and, where necessary, revised to align with the specifications and requirements outlined in this Arboricultural Impact Assessment (AIA) report. This includes accurately reflecting the Tree Protection Zones (TPZs), Structural Root Zones (SRZs), tree numbers/IDs, and any additional trees identified during the assessment. The radial distances and tree numbers detailed in the data table of this report should be used as a minimum standard of accuracy. Furthermore, suitable locations for soil stockpiling, material waste (e.g. skip bins), site offices and sheds, parking, material delivery areas, and material storage/set-down areas must also be clearly shown on the plans where applicable.

6.2 Ecological Assessment

- 6.2.1 Where there are concerns about the site's ecology or uncertainties regarding protected vegetation or wildlife, ArborScan encourages clients to engage a suitable contractor with expertise in this area.

6.3 Transplanting

- 6.3.1 No trees have been identified as being suitable for transplant/relocation in the landscape.

6.4 Tree Canopy Pruning

- 6.4.1 Based on the proposed development plan, An overview of the works being proposed is as follows: trees will come into contact with, or will overhang the proposed development footprint, which will require limbs to be trimmed, this includes **no assessed trees**.
- 6.4.2 Where pruning is deemed to be required, ensure a high standard of work is achieved; all proposed arboricultural works must be completed by a suitably qualified and experienced Arborist of a minimum AQF Level 3 in accordance with the principles of the Australian Standard 4373-2007 Pruning of Amenity Trees.

6.5 Tree Removal

- 6.5.1 Out of the total number of tagged trees evaluated (163), it is proposed that a total of 61 trees be removed, which corresponds to 41.8% of the evaluated trees. This leaves a total of 102 trees that will be retained.
- 6.5.2 It is not permitted to perform any tree works on the trees located on adjoining property land. Performing tree works without permission can result in legal action and hefty fines, which can be avoided by seeking permission from the owner of the tree, and, where also required, the Lands Authority. It is recommended to advise the adjoining landowners of the 3 trees listed for removal, this includes **Tree 107, 110, 151**.

Table 13. Summary of Tree Removals

Tree Qty.	Tree Number(s)
Remove – Significant adverse impact based on development design	
58	1, 2, 3, 16, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 104, 105, 106, 107, 110, 129, 133, 151
Remove – Unrelated to development impact (i.e. Weed species, damaging infrastructure, inappropriate location)	
3	132, 134, 135, 135

- 6.5.3 All approved tree removal works shall be carried out by a qualified Arborist, with a minimum Level 3 AQF in arboriculture and in accordance with WorkCover's Code of Practice – Amenity Tree Industry.
- 6.5.4 Stumps located within the TPZ of trees to be retained shall be grubbed-out where required using a mechanical stump grinder (or by hand where less than 150mm in diameter) without damage to the root system of other trees. Stumps within the Tree Protection Zone of other trees to be retained shall not be pulled out using excavation equipment or similar without the prior consent of the Project Arborist.
- 6.5.5 Where trees to be removed are within the SRZ of any trees to be retained, consideration should be given to cutting the stump close to ground level and retaining the root crown intact. Grinding or excavating of stumps in the SRZ is not permitted without the prior consent of the Project Arborist.

6.6 Obtaining Approval For Tree Related Works

- 6.6.1 The following table identifies the trees that require confirmation with the land authority before removal, pruning, transplanting, or root pruning can occur. ArborScan specialises in tree-related advice and does not extend its expertise to planning controls or constraints that may be present on the site. Information provided by ArborScan regarding relevant codes and standards, including any requirements specific to trees stipulated by local councils, should serve strictly as a reference. It is recommended that this information be verified by consulting with a suitably qualified and experienced Planning consultant.

6.6.2 It is the responsibility of the landowner to confirm any exemptions with the relevant land authority prior to any tree removal taking place outside of a formal permit or development application process.

Table 14. Summary Of Tree Work Approval Needs

Category	Qty	Tree Number(s)
Retain tree	102	4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 108, 109, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 130, 131, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163
Prescribed site tree needing approval	53	2, 3, 16, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 105, 106, 129, 133
Prescribed tree needing approval, neighbours written consent required	3	110, 107, 151 (Confirm Ownership)
Non-prescribed site tree which is exempt (Size / Species / Location / Condition), neighbours written consent required	5	1, 104, 132, 134, 135

6.7 Offset Tree Planting

- 6.7.1 Replacement planting to help offset the loss of trees should aim to reflect, where possible, the number of trees removed and the associated reduction in amenity, canopy cover, and biomass. While a 1:1 planting ratio is often considered a baseline target, it is recognised that some sites may not be able to accommodate this level of replacement due to space or site constraints. In such cases, the land authority will determine the most suitable outcome in consultation with relevant stakeholders.
- 6.7.2 When space is limited, priority should be given to planting trees that have the potential to grow into the available space without causing infrastructure damage, and that will provide the greatest long-term benefit to the site's amenity, biodiversity, and canopy cover.
- 6.7.3 Replacement tree species should be chosen with a focus on contributing meaningfully to future canopy cover. This means selecting species that have the genetic potential to reach a mature size that maximises amenity, shade, and environmental benefits in their location. Suitability to site conditions, tolerance to local environmental factors, and compatibility with surrounding infrastructure should all be considered.
- 6.7.4 Final offset planting requirements, including the number and species of replacement trees, will be determined by the land authority. These decisions will consider site conditions, canopy cover objectives, and any practical limitations on planting opportunities.

Table 15. Summary Of The Minimum Tree Replacement Requirements To Offset Proposed Tree Removals

Category	Qty	Tree Number(s)
Retain tree	102	4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 108, 109, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 130, 131, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163
Authority to confirm replacement qty	61	1, 2, 3, 16, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 104, 105, 106, 107, 110, 129, 132, 133, 134, 135, 151

6.8 Tree Damage

- 6.8.1 In the event of any tree becoming damaged for any reason during the construction period, a consulting arborist (Australian Qualification Framework Level 5) shall be engaged to inspect and provide advice on any remedial action to minimise any adverse impact. Such remedial action shall be implemented as soon as practicable and certified by the arborist.

7 Tree Protection Specifications (TPS) AS 4970–2025

- 7.1.1 Injury to any part of a tree during development can detrimentally affect its health or structural stability. Damage to the crown is common through pruning or accidental injury from construction activities, resulting in a reduction in foliage and photosynthesis and ultimately decreasing carbohydrate production. This weakens the tree's ability to function normally and withstand environmental stresses. Trunk wounds caused by machinery or construction works similarly interfere with the transport of water, nutrients, and carbohydrates, leaving trees susceptible to decay and structural failure over time.
- 7.1.2 Root damage is the most frequent form of injury to trees on development sites and can occur through root removal during excavation, mechanical wounding, soil compaction, chemical contamination, or changes in soil moisture and drainage patterns. Soil compaction, often caused by vehicle and machinery movement, reduces macropores necessary for water, gas exchange, and drainage, severely limiting root function. Even minor compaction can extend to depths of 15–20 cm, the depth at which most absorbing roots are located, leading to poor soil aeration, restricted root growth, and long-term health decline. Careful planning and implementation of tree protection measures are therefore critical to avoid these adverse impacts.
- 7.1.3 Where recommended, tree protection must be installed by a competent person and certified by a minimum qualified Arborist (AQF level 5) before any machinery or materials are brought to the site and before the commencement of any works.
- 7.1.4 The following table shows trees with specific recommendations. Please refer to the general requirements which are additionally applicable, and will be guided by the appointed project arborist.

Table 16. Summary Of Trees Proposed To Be Retained

Tree Qty.	Tree Number(s)
Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	
54	4, 5, 90, 91, 95, 96, 97, 98, 99, 100, 101, 102, 103, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 152, 153, 154, 155, 157, 158, 159, 160, 161, 162, 163
Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	
48	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 92, 93, 94, 108, 109, 126, 127, 128, 130, 131, 156

Table 17. Summary Of Proposed Specific Tree Protection Considerations To Minimise Tree-Related Impact and Damage

Category	Qty	Tree Number(s)
Above grade construction techniques	38	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 156
Boundary fence offers protection	16	4, 5, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103
Document works (photos)	45	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 92, 93, 94, 108, 109, 130, 131, 156
Generic tree protection considerations apply	38	112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 152, 153, 154, 155, 157, 158, 159, 160, 161, 162, 163
Project arborist engagement (AQF5)	45	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 92, 93, 94, 108, 109, 130, 131, 156
Soil grade change not permitted	56	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 108, 109, 126, 127, 128
Tree proposed for removal	61	1, 2, 3, 16, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 104, 105, 106, 107, 110, 129, 132, 133, 134, 135, 151
Tree protection fencing	56	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 126, 127, 128, 130, 131
Trunk protection	3	136, 137, 156

7.2 Notional Root Zone (NRZ)

- 7.2.1 The NRZ is a radial distance measured from the centre of the trunk. It is a combination of the root area and crown area requiring protection from construction disturbance so that the tree remains viable.
- 7.2.2 Incursions into the NRZ may occur due to excavation, modification of existing ground levels, trenching or inverting the soil profile. Such works may damage part or all of the root system or affect soil structure and growing conditions required for long-term growth.
- 7.2.3 A NRZ should not be less than 2m nor greater than 15m (except where crown protection is required).
- 7.2.4 The NRZ of palms, other monocots, cycads, and tree ferns should not be less than 1m outside the crown projection. This is because these species generally have compact fibrous root systems that are largely contained beneath the crown.
- 7.2.5 Radial measurements for the NRZ can be found in the data schedule within this report.

7.3 Tree Protection Zone (TPZ)

- 7.3.1 The NRZ provides the baseline for determining the TPZ.
- 7.3.2 The TPZ is designed to offset incursions within the NRZ and protect areas of the tree, such as roots and canopy, that may be vulnerable to damage during construction.
- 7.3.3 The TPZ, where no change is specified, is equal to the NRZ, this is defined as the minimum TPZ area.
- 7.3.4 There is no defined maximum TPZ area. The TPZ may be increased on a single aspect or increased entirely. When determining the requirements of a larger TPZ area, the following factors should be taken into account where relevant:
 - The location and distribution of the roots and the potential loss of root mass resulting from any encroachment, including the number and diameter of roots likely to be impacted.
 - The tree species and its tolerance to root disturbance.
 - Whether the works will result in a temporary (e.g. service trench) or permanent (e.g. basement or car park) reduction in available soil volume.
 - The tree's age, health, current size and projected future size.
 - The presence of other trees with overlapping NRZs or grafted root systems.
 - The proposed staging and timing of excavation or root cutting works.
 - Planned tree maintenance and tree care activities during and after construction.
 - The tree's lean and structural stability.
 - Soil characteristics including soil volume, texture, compaction, topography and drainage capacity.
 - The presence of existing or past structures or obstacles that may have affected root growth or caused previous encroachments.
 - Proposed construction methodologies and design measures that could reduce impacts on trees, such as the use of pier and beam footings, suspended slabs, cantilevered sections or screw piles.
 - Whether a root investigation is required. If so, root location and distribution should be confirmed using minimally destructive methods such as pneumatic or hydraulic excavation, hand digging, or ground-penetrating radar. Where necessary, photographs and root maps should be prepared to address geospatial issues.
- 7.3.5 All root investigations should aim to minimise root damage. Roots must be exposed for the shortest possible time required to complete the investigation.

7.4 Working In Designated NRZ/TPZ

7.4.1 The following works are excluded from any NRZ/TPZ:

- Excavation
- Soil cut or fill, including trenching.
- Soil cultivation, disturbance or compaction.
- Stockpiling, storage or mixing of material.
- The parking, storing, washing and repairing of tools, equipment and machinery.
- The disposal of liquids and refuelling.
- The disposal of building materials.
- The siting of offices or sheds.
- Any other action leading to the impact on tree health or structure.

7.5 Structural Root Zone (SRZ)

- 7.5.1 The SRZ defines the area around the base of a tree that is required for the tree's stability in the ground. The woody root growth and soil cohesion in this area is necessary to hold the tree upright. The SRZ is nominally circular with the trunk at its centre and is expressed by its radius in metres. This zone considers a tree's structural stability only, not the root zone required for a tree's vigour and long-term viability, which will usually be a much larger area.
- 7.5.2 Incursions into the SRZ are not recommended as they are likely to result in loss or damage to woody roots, which may significantly affect stability.
- 7.5.3 Radial SRZ measurements can be found in the data schedule within this report.

7.6 Tree Protection Fencing

- 7.6.1 Fences should be erected before any machinery or materials are brought onto the site and before the commencement of works, including demolition, or in accordance with the TPS and as shown on the TPP. Once erected, protective fencing shall not be removed or altered without approval by the project arborist except in accordance with the TPS.
- 7.6.2 The fence should restrict access to the enclosed portion of the TPZ. Semi-permanent fences or options that make it difficult to move the fence should be considered where appropriate.
- 7.6.3 AS 4687.2 specifies applicable requirements where temporary fence panels are used. Where semi-permanent fences are used, the posts should be driven into the soil 600 mm (1000 mm in sand), and top rails should be used as required.
- 7.6.4 Existing perimeter fences and other structures may be used as part of the protective fence if suitable.

7.7 Tree Protection Signage

- 7.7.1 Signs identifying the TPZ is compliant with AS 4970–2025 should be placed in prominent positions at a maximum of 10m intervals around the edge of the TPZ and should be visible from within the development site. The sign should be minimum A3 size.

7.8 Tree Trunk Protection

- 7.8.1 Trunk protection should be undertaken in line with the Australian Standard AS 4790–2025: Protection of Trees on Development Sites.
- 7.8.2 Tree trunks and/or major branches located within close proximity to works must be wrapped with protective hessian or similar acceptable material to prevent tree injury. Major branches would typically be considered to be of a diameter greater than 100mm in diameter.
- 7.8.3 Timber battens (50mm x 100mm x 2m or similar) must be placed around the trunk with battens spaced at a maximum of 100mm intervals. Battens are to be strapped to the tree, not nailed or screwed into the trunk. Temporary signs, or any other items, shall not be fixed or attached to any tree.

7.9 Ground Protection

- 7.9.1 Ground protection should be undertaken in line with the Australian Standard AS 4790–2025: Protection of Trees on Development Sites.
- 7.9.2 Construction routes for approved equipment shall be confined to existing hard-surfaced areas wherever possible to minimise compaction and disturbance of the underlying soil profile and root zone. Where construction access into the TPZ of retained trees cannot be avoided, the root zone of each tree must be protected by placing weight distribution mats/track mats until such a time as the permanent above-ground surfacing is installed.
- 7.9.3 Exposed surface roots shall first be covered in a layer of mulch at a minimum thickness of 75-100mm before placing down weight distribution mats / track mats; root buttresses which are exposed shall have tree protection extended downward from the trunk to prevent tree injury.

7.10 Scaffolding/Hoarding

- 7.10.1 Where scaffolding/Hoarding is required, it should be erected outside the TPZ. Where it is essential for scaffolding/Hoarding to be erected within the TPZ, branch removal should be minimised. This can be achieved by designing scaffolding/Hoarding to avoid branches or tying back branches. The ground below the scaffolding / hoarding should be protected by boarding (e.g. scaffolding board or plywood sheeting). Where access is required, a boardwalk or other surface material should be installed to minimise soil compaction. Boarding should be placed over a layer of mulch and impervious sheeting to prevent soil contamination. The boarding should be left in place until the scaffolding is removed. If holes for supports are required, these are to be manually excavated (by hand).

7.11 Mulch In TPZ

- 7.11.1 Any TPZ, unless the existing surface is grass or garden, or specified otherwise by the Project Arborist, should be mulched to a depth of 75mm and kept free of weeds and grass for the duration of works. Mulching shall occur where existing landscape or hard surfaces are removed within the TPZ.

7.12 Addition of Fill (Soil)

- 7.12.1 Where practicable, site soil textural (field) analysis is recommended in order to help guide the composition of fill.
- 7.12.2 Unless otherwise specified, the selected fill should be composed of non-cohesive granular material, which is free draining.
- 7.12.3 As a guide (and in the absence of onsite soil analysis), fill should consist of suitably sourced and clean (i.e. free of weeds/contaminants and providing a beneficial environment for the promotion of plant growth) material consistent with a sandy loam. Indicative organic matter content should be no higher than 2–5%, with a clay content of between 10–20% by mass.
- 7.12.4 Backfill is to be consolidated/compacted as per construction standards/specifications.

7.13 Excavation In TPZ


- 7.13.1 Excavations within the TPZ of trees to be retained is to be carried out under arborist supervision (or with the express permission of the Project Arborist). No excavation should occur within the SRZ of these trees. Any proposed excavation should commence at the outer extent of the TPZ and move inwards to minimise root damage to these trees.
- 7.13.2 Works should be undertaken using techniques that are sensitive to tree roots to avoid unnecessary damage. Such techniques include:
- Excavation using a high-pressure water jet and vacuum truck
 - Excavation using an Air Spade with a vacuum truck
 - Mechanical excavation with a toothless bucket under direct Project Arborist supervision
 - Manual excavation by hand.
- 7.13.3 Machine excavation is prohibited within the TPZ of retained trees unless undertaken at the direct consent of (or under supervision from) the Project Arborist.
- 7.13.4 Roots discovered are to be treated with care and minor roots (<30mm diameter) pruned with a sharp, sterile handsaw or secateurs. All significant roots (>30mm diameter) are to be recorded, photographed and reported to the Project Arborist.

7.14 Exploratory Root Investigation (Non-Destructive Excavation)

- 7.14.1 Where specifically requested, or where further information is needed to support the development proposed, non-destructive excavation along the direct edge of the alignment posing impact will be needed to determine the severity. Non-destructive excavation techniques may include the use of hand-held implements, air pressure (using an Air-spade® device) or water pressure (hydro-excavation in combination with a vacuum extraction unit).
- 7.14.2 Hard surfaces such as concrete restricting access to exposed soil areas may require cutting/removing prior the non-destructive excavation taking place.
- 7.14.3 The exploratory excavation shall be undertaken along the perimeter of the alignment (within the TPZ). The exploration should be carried out to the extent of either the maximum depth of the proposed development excavation or the depth of the subterranean rock layer, whichever comes first.
- 7.14.4 Where large roots greater than 40mm in diameter are present and the AQF level 5 Arborist believes that these roots belong to a tree within the site (a tree to be removed) that root must be traced back to the trees buttress (clear photographic evidence is required).
- 7.14.5 An Exploratory Root Investigation Report must be prepared and submitted to and approved by Council's Planning Manager prior to the commencement of any such works, the report must:
- Be prepared by a qualified Arborist (minimum AQF Level 5).
 - Include the assessment and documentation (including photos) of tree root size, number and condition is to be prepared. Include a site plan showing all excavation lines and root locations in relation to the proposed works.
 - Information on the Arborist's involvement during these works.
 - All care shall be undertaken to preserve woody roots intact and undamaged during exploratory excavation. Any roots encountered of less than 30mm in diameter may be cleanly severed with clean sharp pruning implements at the face of the excavation. Where large woody roots (greater than 30mm diameter) are encountered during exploratory excavations, they are to be documented only and not severed.
 - Where vacuum excavation requires backfilling of holes or trenches, a clean-washed sand is to be used.

7.15 TPZ and SRZ Setbacks


- 7.15.1 Trees and their root systems may occupy a substantial part of any development site and, because of their potential size, can have a major influence on planning the use of the site. Early identification and protection of important trees on development sites is essential from the outset and will minimise the problems of retaining inappropriate trees.
- 7.15.2 The extent of encroachment within the tree protection zone (greater than 20%) will result in damage to structural roots. The structural roots and structural root zone (SRZ) are the area of the root system required for stability and anchorage of the tree.
- 7.15.3 The below TPZ and SRZ **radius measurements are to be taken from the centre of the stem at ground level.**



Legend:

1. Chain wire mesh panels that are held in place with concrete feet.
2. Alternatively, plywood or wooden paling fence panels may be used. This fencing material also prevents building materials or soil from entering the TPZ.
3. Mulch installation across the surface of the TPZ (as detailed in the TPS). No excavation, construction activity grade changes, surface treatment or storage of materials of any kind is permitted within the TPZ other than those indicated in the TPS.
4. Bracing may be used within the TPZ. Installation of posts or supports should avoid damaging roots.

Figure 3. Depicts standard fencing techniques. (AS 4970–2025).



Notes:

1. For trunk and branch protection, boards and padding may be used to prevent damage to bark. Boards shall be joined to each other using hoop straps and screws or similar. They shall not be screwed or nailed to the tree.
2. Wide wooden boards or plastic or metal plates should be of a suitable thickness to spread the load and prevent soil compaction and root damage.

Figure 4. Depicts trunk and ground protection techniques. (AS 4970–2025).

7.16 Project Milestones

- 7.16.1 The following visits and milestones were recommended as to when on-site tree inspection by the Project Arborist is required:

Table 18. Project Milestones

Item	Purpose of Visit	Timing of Visit	Prerequisites
1	Pre-start induction	Following sign-off from Item 1. Contractor to provide a minimum of five days advance notice for this visit.	Prior to the commencement of works. All parties involved in the project to attend.
2	Installation of tree protection measures.	Following the completion of its installation by a competent person.	Prior to the commencement of any site works, including demolition.
3	Supervision of works in TPZ, including all regrading and excavations	Whenever there is work planned to be performed within the TPZ. Contractor to provide a minimum of five days advance notice for such visits.	
4	Regular site inspections	Minimum frequency of 1 Monthly inspections for the duration of the project.	The checklist must be completed by the Project Arborist at each site inspection and signed by both parties.
5	Final sign off	Following completion of works.	Practical completion of works prior to tree protection removal.

7.17 Compliance Reporting

- 7.17.1 Following each inspection, the Project Arborist shall prepare a report detailing the condition of the trees. These reports should certify whether or not the works have been completed in compliance with the consent relating to tree protection.
- 7.17.2 These reports should contain photographic evidence where required to demonstrate that the work has been carried out as specified.
- 7.17.3 Matters to be monitored and included in these reports should include tree condition, tree protection measures and the impact of site works that may arise from changes to the approved plans.
- 7.17.4 The reports and Compliance Statements shall be submitted to the Project Manager (as well as the Clients' nominated representative) following each inspection.
- 7.17.5 The reports and any Non-Compliance Statements shall be submitted to the Project Manager (as well as the Clients' nominated representative) if tree protection conditions have been breached. Reports should contain clear remedial action specifications to minimise any adverse impact on any subject tree.

7.18 Project Arborist

- 7.18.1 An official "Project Arborist" must be commissioned to oversee the tree protection, any works within the TPZ's and complete regular monitoring compliance certification.
- 7.18.2 The project arborist must have minimum five (5) years industry experience in the field of arboriculture, horticulture with relevant demonstrated experience in tree management on construction sites, and Diploma level qualifications in arboriculture – AQF Level 5.

8 References

Barrell, J., 2009. Tree AZ - SULE: Its use and status into the New Millennium, London: Barrell Tree Consultancy.

Draper, Danny B. Dictionary for Managing Trees in Urban Environments. CSIRO PUBLISHING. Kindle Edition.

Department of Planning, Industry and Environment, 2020. Soil Landscapes of Central and Eastern NSW - v2.1, Sydney: NSW Office of Environment and Heritage.

eSpade - State Government of NSW and Department of Planning, Industry and Environment, 2015. Soil Landscapes of the Sydney 1:100,000 Sheet, Sydney: State Government of NSW and Department of Planning, Industry and Environment.

IACA, 2010. Significance of a Tree Rating System (STARS®), Institute of Australian Consulting Arborists.

NSW Rural Fire Service. 10/50 vegetation clearing. (Online) Available at: <https://www.rfs.nsw.gov.au/plan-and-prepare/1050-vegetation-clearing>. (Accessed 27 March 2026).

Roberts J, Jackson N & Smith M (2006) 'Tree roots in the built environment, research for amenity trees no. 8.' Department for Communities and Local Government. TSO (The Stationery Office), London, UK.

SEED - NSW Government. SEED – Sharing and Enabling Environmental Data. (Online) Available at: https://geo.seed.nsw.gov.au/Public_View/index.html?viewer=Public_View&locale=en-AU. (Accessed 27 March 2026).

Shigo AL (1991) Modern Arboriculture: A Systems Approach to the Care of Trees and Their Associates. Shigo and Trees, Durham, New Hampshire, USA.

Standards Australia, 2007. AS 4373–2007: Pruning of Amenity Trees, Sydney: Standards Australia.

Standards Australia, 2025. AS 4970–2025: Protection of Trees on Development Sites, Sydney: Standards Australia.

9 Impact Assessment Schedule



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area (m2)	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
1	<i>Fraxinus angustifolia</i> ssp. <i>oxycarpa</i> 'Raywood'	1	14	17	<5m	<5m	Fair	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.57	Excavation impacts, Soil grade change	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
2	<i>Unknown</i> sp.	1	33	36	5-10m	5-10m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	3.96	Unmodified	2.15	Directly within the footprint	49.24	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
3	<i>Fraxinus angustifolia</i> ssp. <i>oxycarpa</i> 'Raywood'	1	29	25	5-10m	5-10m	Poor	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	3.48	Unmodified	1.85	Directly within the footprint	38.03	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
4	<i>Ficus benjamina</i>	1	45	65	10-15m	10-15m	Good	Fair	Mature	Long (Over 40 years)	High	HIGH	5.40	Unmodified	2.76		0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection	Retain
5	<i>Elaeocarpus reticulatus</i>	1	18	22	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.16	Unmodified	1.75		0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection	Retain
6	<i>Cupaniopsis anacardioides</i>	1	60	70	5-10m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	7.20	Unmodified	2.85	Road construction, Root zone disturbance, Soil compaction, Soil grade change	38.64	24	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
7	<i>Cupressus torulosa</i>	1	22	24	10-15m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Low	LOW	2.64	Unmodified	1.82	Road construction, Root zone disturbance, Soil compaction, Soil grade change	8.89	41	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
8	<i>Cupressus torulosa</i>	1	17	20	10-15m	<5m	Fair	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	2.04	Unmodified	1.68	Road construction, Root zone disturbance, Soil compaction, Soil grade change	4.37	33	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
9	<i>Cupressus torulosa</i>	1	26	31	10-15m	<5m	Good	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	3.12	Unmodified	2.02	Road construction, Root zone disturbance, Soil compaction, Soil grade change	11.92	39	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
10	<i>Cupressus torulosa</i>	1	30	39	10-15m	<5m	Good	Fair	Semi-Mature	Short (5-15 years)	Medium	LOW	3.60	Unmodified	2.23	Road construction, Root zone disturbance, Soil compaction, Soil grade change	17.25	42	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
11	<i>Cupressus torulosa</i>	1	35	40	10-15m	<5m	Good	Good	Mature	Short (5-15 years)	Medium	LOW	4.20	Unmodified	2.25	Road construction, Root zone disturbance, Soil compaction, Soil grade change	25.83	47	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
12	<i>Cupressus torulosa</i>	1	38	39	10-15m	<5m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.56	Unmodified	2.23	Road construction, Root zone disturbance, Soil compaction, Soil grade change	29.57	45	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
13	<i>Cupressus torulosa</i>	1	36	41	10-15m	<5m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.32	Unmodified	2.28	Road construction, Root zone disturbance, Soil compaction, Soil grade change	25.83	44	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
14	<i>Cupressus torulosa</i>	1	37	42	10-15m	<5m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.44	Unmodified	2.3	Road construction, Root zone disturbance, Soil compaction, Soil grade change	29.08	47	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
15	Cupressus torulosa	1	40	49	10-15m	<5m	Good	Fair	Mature	Short (5-15 years)	Medium	LOW	4.80	Unmodified	2.45	Road construction, Root zone disturbance, Soil compaction, Soil grade change	33.68	47	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
16	Elaeocarpus reticulatus	1	6	9	<5m	<5m	Good	Excellent	Juvenile	Short (5-15 years)	Low	LOW	2.00	Unmodified	1.2	Directly within the footprint	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
17	Casuarina glauca	1	38	48	10-15m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.56	Unmodified	2.43	Road construction, Root zone disturbance, Soil compaction, Soil grade change	20.18	31	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
18	Casuarina glauca	1	41	54	10-15m	5-10m	Good	Good	Mature	Short (5-15 years)	Medium	LOW	4.92	Unmodified	2.55	Road construction, Root zone disturbance, Soil compaction, Soil grade change	24.66	32	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
19	Casuarina glauca	1	33	43	10-15m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	3.96	Unmodified	2.32	Road construction, Root zone disturbance, Soil compaction, Soil grade change	15.45	31	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
20	Casuarina glauca	1	33	50	10-15m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	3.96	Unmodified	2.47	Road construction, Root zone disturbance, Soil compaction, Soil grade change	14.82	30	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
21	Casuarina glauca	1	44	61	10-15m	5-10m	Good	Good	Mature	Short (5-15 years)	Medium	LOW	5.28	Unmodified	2.69	Road construction, Root zone disturbance, Soil compaction, Soil grade change	30.74	35	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
22	Casuarina glauca	1	25	37	10-15m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.00	Unmodified	2.18	Road construction, Root zone disturbance, Soil compaction, Soil grade change	7.57	27	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
23	Casuarina glauca	1	30	45	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.60	Unmodified	2.37	Road construction, Root zone disturbance, Soil compaction, Soil grade change	12.3	30	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
24	Casuarina glauca	1	34	46	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	4.08	Unmodified	2.39	Road construction, Root zone disturbance, Soil compaction, Soil grade change	16.55	32	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
25	Casuarina glauca	1	47	56	10-15m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	5.64	Unmodified	2.59	Road construction, Root zone disturbance, Soil compaction, Soil grade change	19.43	19	Moderate	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
26	Casuarina glauca	1	16	24	5-10m	<5m	Fair	Good	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.82	Road construction, Root zone disturbance, Soil compaction, Soil grade change	2.46	20	Moderate	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
27	Casuarina glauca	1	40	54	10-15m	5-10m	Good	Good	Mature	Short (5-15 years)	Medium	LOW	4.80	Unmodified	2.55	Road construction, Root zone disturbance, Soil compaction, Soil grade change	26.15	36	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
28	Casuarina glauca	1	38	49	10-15m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.56	Unmodified	2.45	Road construction, Root zone disturbance, Soil compaction, Soil grade change	23.24	36	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
29	Casuarina glauca	1	37	47	10-15m	5-10m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	4.44	Unmodified	2.41	Road construction, Root zone disturbance, Soil compaction, Soil grade change	20.39	33	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
30	Casuarina glauca	1	28	37	10-15m	5-10m	Fair	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	3.36	Unmodified	2.18	Road construction, Root zone disturbance, Soil compaction, Soil grade change	10.22	29	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
31	Cupressus torulosa	1	35	37	5-10m	<5m	Fair	Poor	Semi-Mature	Short (5-15 years)	Low	LOW	4.20	Unmodified	2.18	Road construction, Root zone disturbance, Soil compaction, Soil grade change	18.03	33	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
32	Cupressus torulosa	1	34	30	10-15m	<5m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	4.08	Unmodified	2	Road construction, Root zone disturbance, Soil compaction, Soil grade change	17.74	34	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
33	Casuarina glauca	1	32	41	15-20m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	3.84	Unmodified	2.28	Road construction, Root zone disturbance, Soil compaction, Soil grade change	16.55	36	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
34	Casuarina glauca	1	26	31	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	3.12	Unmodified	2.02	Road construction, Root zone disturbance, Soil compaction, Soil grade change	10.04	33	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
35	Casuarina glauca	1	37	54	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	4.44	Unmodified	2.55	Road construction, Root zone disturbance, Soil compaction, Soil grade change	26.23	42	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
36	Cupressus torulosa	1	29	32	5-10m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Low	LOW	3.48	Unmodified	2.05	Road construction, Root zone disturbance, Soil compaction, Soil grade change	18.82	49	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
37	Eucalyptus punctata	1	40	46	10-15m	10-15m	Fair	Poor	Semi-Mature	Limited (Under 5 years)	Low	LOW	4.80	Unmodified	2.39	Road construction, Root zone disturbance, Soil compaction, Soil grade change	35.07	48	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
38	Casuarina glauca	1	14	18	10-15m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.61	Road construction, Root zone disturbance, Soil compaction, Soil grade change	4.19	33	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
39	Cupressus torulosa	1	21	28	10-15m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.52	Unmodified	1.94	Road construction, Root zone disturbance, Soil compaction, Soil grade change	7.49	38	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
40	Casuarina glauca	1	21	27	10-15m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.52	Unmodified	1.91	Road construction, Root zone disturbance, Soil compaction, Soil grade change	7.44	37	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
41	Cupressus torulosa	1	29	32	10-15m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	3.48	Unmodified	2.05	Road construction, Root zone disturbance, Soil compaction, Soil grade change	17.61	46	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
42	Cupressus torulosa	1	28	31	10-15m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	3.36	Unmodified	2.02	Road construction, Root zone disturbance, Soil compaction, Soil grade change	15.74	44	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
43	Casuarina glauca	1	31	39	15-20m	5-10m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	3.72	Unmodified	2.23	Road construction, Root zone disturbance, Soil compaction, Soil grade change	18.6	43	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Encroachment considerations, Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
44	Cupressus torulosa	1	20	25	5-10m	<5m	Fair	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.85	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
45	Cupressus torulosa	1	26	28	5-10m	<5m	Fair	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	3.12	Unmodified	1.94	Directly within the footprint	30.57	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
46	Casuarina glauca	1	51	66	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	6.12	Unmodified	2.78	Directly within the footprint	117.61	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
47	Casuarina glauca	1	36	43	10-15m	5-10m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	4.32	Unmodified	2.32	Directly within the footprint	58.6	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
48	Casuarina glauca	1	36	48	10-15m	5-10m	Fair	Good	Mature	Short (5-15 years)	Medium	LOW	4.32	Unmodified	2.43	Directly within the footprint	58.6	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
49	Casuarina glauca	1	25	37	10-15m	5-10m	Good	Fair	Semi-Mature	Short (5-15 years)	Medium	LOW	3.00	Unmodified	2.18	Directly within the footprint	28.26	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
50	Casuarina glauca	1	32	43	15-20m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	3.84	Unmodified	2.32	Directly within the footprint	46.3	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
51	Casuarina glauca	1	34	55	10-15m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.08	Unmodified	2.57	Directly within the footprint	52.27	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
52	Cupressus torulosa	1	19	22	5-10m	<5m	Fair	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	2.28	Unmodified	1.75	Directly within the footprint	16.32	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
53	Casuarina glauca	1	25	32	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.00	Unmodified	2.05	Directly within the footprint	28.26	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
54	Cupressus torulosa	1	22	27	5-10m	<5m	Fair	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	2.64	Unmodified	1.91	Directly within the footprint	21.88	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
55	Casuarina glauca	1	33	44	10-15m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	3.96	Unmodified	2.34	Directly within the footprint	49.24	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
56	Casuarina glauca	1	36	47	10-15m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.32	Unmodified	2.41	Directly within the footprint	58.6	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
57	Casuarina glauca	1	24	35	5-10m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.88	Unmodified	2.13	Directly within the footprint	26.04	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
58	Casuarina glauca	1	37	50	15-20m	5-10m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	4.44	Unmodified	2.47	Directly within the footprint	61.9	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
59	Cupressus torulosa	1	25	26	10-15m	<5m	Good	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	3.00	Unmodified	1.88	Directly within the footprint	28.26	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
60	Casuarina glauca	1	26	33	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.12	Unmodified	2.08	Directly within the footprint	30.57	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
61	Cupressus torulosa	1	32	41	10-15m	<5m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	3.84	Unmodified	2.28	Directly within the footprint	46.3	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
62	Casuarina glauca	1	12	16	5-10m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.53	Directly within the footprint	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
63	Casuarina glauca	1	12	16	5-10m	<5m	Good	Good	Juvenile	Limited (Under 5 years)	Low	LOW	2.00	Unmodified	1.53	Directly within the footprint	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
64	Casuarina glauca	1	12	16	5-10m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.53	Directly within the footprint	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
65	Cupressus torulosa	1	24	23	10-15m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.88	Unmodified	1.79	Directly within the footprint	26.04	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
66	Casuarina glauca	1	30	37	10-15m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.60	Unmodified	2.18	Directly within the footprint	40.69	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
67	Casuarina glauca	1	38	47	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	4.56	Unmodified	2.41	Directly within the footprint	65.29	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
68	Casuarina glauca	1	23	28	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.76	Unmodified	1.94	Directly within the footprint	23.92	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
69	Casuarina glauca	1	25	33	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.00	Unmodified	2.08	Directly within the footprint	28.26	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
70	Casuarina glauca	1	35	40	10-15m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	4.20	Unmodified	2.25	Directly within the footprint	55.39	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
71	Casuarina glauca	1	35	41	10-15m	5-10m	Good	Good	Semi-Mature	Short (5-15 years)	Medium	LOW	4.20	Unmodified	2.28	Directly within the footprint	55.39	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
72	Casuarina glauca	1	26	29	5-10m	<5m	Fair	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	3.12	Unmodified	1.97	Directly within the footprint	30.57	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
73	Casuarina glauca	1	11	15	<5m	<5m	Good	Good	Juvenile	Limited (Under 5 years)	Low	LOW	2.00	Unmodified	1.49	Directly within the footprint	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
74	Callistemon viminalis	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
75	Callistemon viminalis	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
76	Callistemon viminalis	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
77	Callistemon viminalis	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
78	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
79	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
80	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
81	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
82	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
83	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
84	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
85	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
86	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
87	<i>Callistemon viminalis</i>	1	20	23	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.40	Unmodified	1.79	Directly within the footprint	18.09	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
88	<i>Plumeria rubra</i> var. <i>acutifolia</i>	1	22	35	5-10m	<5m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	2.64	Unmodified	2.13	Directly within the footprint	21.88	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
89	<i>Plumeria rubra</i> var. <i>acutifolia</i>	1	21	28	5-10m	<5m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	2.52	Unmodified	1.94	Directly within the footprint	19.94	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
90	<i>Melaleuca quinquenervia</i>	1	16	19	5-10m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.65	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
91	<i>Melaleuca quinquenervia</i>	1	20	24	5-10m	5-10m	Good	Fair	Juvenile	Medium (15-40 years)	Medium	MEDIUM	2.40	Unmodified	1.82	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
92	<i>Melaleuca quinquenervia</i>	1	26	30	5-10m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.12	Unmodified	2	Excavation impacts, Landscaping, Retaining wall(s), Road construction	2.27	7	Minor	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Boundary fence offers protection, Document works (photos), Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
93	<i>Melaleuca quinquenervia</i>	1	32	36	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.84	Unmodified	2.15	Excavation impacts, Landscaping, Retaining wall(s), Road construction	5.12	11	Moderate	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Boundary fence offers protection, Document works (photos), Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain
94	<i>Melaleuca quinquenervia</i>	1	36	38	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	4.32	Unmodified	2.2	Excavation impacts, Landscaping, Retaining wall(s), Road construction	8.6	15	Moderate	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Boundary fence offers protection, Document works (photos), Project arborist engagement (AQF5), Soil grade change not permitted, Tree protection fencing	Retain



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
95	Corymbia maculata	1	21	27	10-15m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.52	Unmodified	1.91	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
96	Banksia integrifolia	1	20	25	5-10m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.40	Unmodified	1.85	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
97	Banksia integrifolia	1	10	16	<5m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.53	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
98	Corymbia maculata	1	22	28	10-15m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.64	Unmodified	1.94	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
99	Banksia integrifolia	1	17	25	5-10m	<5m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.04	Unmodified	1.85	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
100	Corymbia maculata	1	11	15	5-10m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Medium	MEDIUM	2.00	Unmodified	1.49	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
101	Corymbia maculata	1	18	21	10-15m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.16	Unmodified	1.72	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
102	Banksia integrifolia	1	14	18	5-10m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.00	Unmodified	1.61	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
103	Corymbia maculata	1	7	11	5-10m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.31	Excavation impacts, Landscaping, Retaining wall(s), Road construction	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Boundary fence offers protection, Soil grade change not permitted, Tree protection fencing	Retain
104	Ricinus communis	1	27	35	5-10m	5-10m	Fair	Fair	Semi-Mature	Short (5-15 years)	Environmental Pest / Noxious Weed Species	PRIORITY FOR REMOVAL	3.24	Unmodified	2.13	Directly within the footprint	100	303	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
105	Casuarina glauca	1	23	28	5-10m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.76	Unmodified	1.94	Directly within the footprint	100	418	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
106	Casuarina glauca	1	38	49	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	4.56	Unmodified	2.45	Directly within the footprint	100	153	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
107	Corymbia gummifera	1	16	20	5-10m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.00	Unmodified	1.68	Directly within the footprint	100	796	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
108	Corymbia gummifera	1	27	38	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.24	Unmodified	2.2	Excavation impacts, Soil grade change	10.51	32	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Document works (photos), Project arborist engagement (AQF5), Soil grade change not permitted	Retain
109	Corymbia gummifera	1	12	14	5-10m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.45	Excavation impacts, Soil grade change	5.6	45	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Document works (photos), Project arborist engagement (AQF5), Soil grade change not permitted	Retain



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
110	Corymbia maculata	1	32	41	10-15m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.84	Unmodified	2.28	Below ground services, Excavation impacts, Soil grade change	19.23	42	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
111	Eucalyptus robusta	1	29	35	10-15m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.48	Unmodified	2.13		0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	None specified	Retain
112	Eucalyptus haemastoma	1	22	28	<5m	5-10m	Fair	Fair	Semi-Mature	Short (5-15 years)	Low	LOW	2.64	Unmodified	1.94	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
113	Eucalyptus haemastoma	1	14	18	5-10m	5-10m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.61	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
114	Eucalyptus haemastoma	1	16	20	5-10m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Medium	MEDIUM	2.00	Unmodified	1.68	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
115	Banksia integrifolia	1	16	19	5-10m	5-10m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.00	Unmodified	1.65	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
116	Banksia integrifolia	1	15	18	5-10m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.00	Unmodified	1.61	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
117	Eucalyptus microcorys	1	45	55	15-20m	10-15m	Good	Fair	Semi-Mature	Medium (15-40 years)	High	HIGH	5.40	Unmodified	2.57	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
118	Corymbia maculata	1	45	52	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	High	HIGH	5.40	Unmodified	2.51	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
119	Celtis sinensis	1	37	44	10-15m	10-15m	Good	Good	Mature	Long (Over 40 years)	Environmental Pest / Noxious Weed Species	LOW	4.44	Unmodified	2.34	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
120	Casuarina cunninghamiana	1	47	58	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	5.64	Unmodified	2.63	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
121	Casuarina cunninghamiana	1	38	44	15-20m	5-10m	Fair	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	4.56	Unmodified	2.34	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
122	Casuarina cunninghamiana	1	42	49	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	5.04	Unmodified	2.45	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
123	Casuarina cunninghamiana	1	40	49	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	4.80	Unmodified	2.45	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
124	Livistona australis	2	26		5-10m	<5m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	2.00	Unmodified		Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain



Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area [m2]	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
125	Casuarina cunninghamiana	1	32	38	10-15m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.84	Unmodified	2.2	Landscaping	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
126	Casuarina cunninghamiana	1	39	43	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	4.68	Unmodified	2.32	Landscaping, Road construction, Soil grade change	3.47	5	Minor	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Soil grade change not permitted, Tree protection fencing	Retain
127	Casuarina cunninghamiana	1	42	54	15-20m	10-15m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	5.04	Unmodified	2.55	Landscaping, Road construction, Soil grade change	8.12	10	Minor	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Soil grade change not permitted, Tree protection fencing	Retain
128	Casuarina cunninghamiana	1	42	53	15-20m	10-15m	Good	Good	Mature	Medium (15-40 years)	Medium	MEDIUM	5.04	Unmodified	2.53	Landscaping, Road construction, Soil grade change	13.57	17	Moderate	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Soil grade change not permitted, Tree protection fencing	Retain
129	Casuarina cunninghamiana	1	50	64	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	6.00	Unmodified	2.74	Excavation impacts, Road construction, Soil grade change	34.17	30	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
130	Callistemon viminalis	1	45	53	5-10m	5-10m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	5.40	Unmodified	2.53	Demolition of hard ground surfaces, Soil grade change	33.9	37	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Document works (photos), Project arborist engagement (AQF5), Structure prevents tree access, Tree protection fencing	Retain
131	Ficus benjamina	1	74	65	10-15m	15-20m	Good	Fair	Mature	Medium (15-40 years)	Medium	MEDIUM	8.88	Unmodified	2.76	Demolition of hard ground surfaces, Landscaping, Soil grade change	97.09	39	Major	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Document works (photos), Project arborist engagement (AQF5), Structure prevents tree access, Tree protection fencing	Retain
132	Syagrus romanzoffiana	1	24		5-10m	<5m	Fair	Fair	Semi-Mature	Medium (15-40 years)	Low	LOW	2.50	Unmodified		Directly within the footprint	2.91	15	Moderate	Remove - Reasons unrelated to direct development impact (i.e. Weed species, damaging infrastructure, inappropriate location)	Tree proposed for removal	Remove
133	Eucalyptus sp.	2	13	16	5-10m	<5m	Fair	Fair	Juvenile	Short (5-15 years)	Low	LOW	2.00	Unmodified	1.53	Directly within the footprint	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
134	Hibiscus sp	1	28	30	5-10m	<5m	Good	Fair	Mature	Medium (15-40 years)	Low	LOW	3.36	Unmodified	2		0	0	Nil	Remove - Reasons unrelated to direct development impact (i.e. Weed species, damaging infrastructure, inappropriate location)	Tree proposed for removal	Remove
135	Glochidion ferdinandi	1	14	17	5-10m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.57		0	0	Nil	Remove - Reasons unrelated to direct development impact (i.e. Weed species, damaging infrastructure, inappropriate location)	Tree proposed for removal	Remove
136	Platanus X acerifolia	1	42	42	10-15m	5-10m	Fair	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	5.04	Unmodified	2.3	Material delivery & storage, Site access	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Trunk protection	Retain
137	Eucalyptus botryoides	1	75	82	15-20m	10-15m	Good	Fair	Mature	Medium (15-40 years)	High	HIGH	9.00	Unmodified	3.04	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Trunk protection	Retain
138	Eucalyptus botryoides	1	43	51	10-15m	10-15m	Good	Fair	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	5.18	Unmodified	2.49	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
139	Eucalyptus botryoides	1	38	38	10-15m	5-10m	Fair	Fair	Semi-Mature	Short (5-15 years)	Medium	LOW	4.59	Unmodified	2.2	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain




Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area (m2)	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
140	<i>Eucalyptus botryoides</i>	1	44	46	10-15m	10-15m	Fair	Fair	Semi-Mature	Medium (15-40 years)	High	HIGH	5.28	Unmodified	2.39	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
141	<i>Eucalyptus botryoides</i>	1	62	66	15-20m	10-15m	Good	Good	Mature	Medium (15-40 years)	High	HIGH	7.44	Unmodified	2.78	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
142	<i>Eucalyptus botryoides</i>	1	41	49	15-20m	10-15m	Poor	Fair	Semi-Mature	Short (5-15 years)	Medium	LOW	4.92	Unmodified	2.45	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
143	<i>Eucalyptus botryoides</i>	1	61	67	10-15m	10-15m	Fair	Good	Mature	Medium (15-40 years)	High	HIGH	7.32	Unmodified	2.8	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
144	<i>Eucalyptus botryoides</i>	1	54	53	15-20m	10-15m	Fair	Good	Mature	Medium (15-40 years)	High	HIGH	6.48	Unmodified	2.53	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
145	<i>Beaucarnea recurvata</i>	7	11	16	<5m	<5m	Fair	Fair	Mature	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.53	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
146	<i>Beaucarnea recurvata</i>	1	11	16	<5m	<5m	Poor	Fair	Mature	Limited (Under 5 years)	Low	LOW	2.00	Unmodified	1.53	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
147	<i>Eucalyptus botryoides</i>	1	67	68	10-15m	10-15m	Good	Fair	Mature	Medium (15-40 years)	High	HIGH	8.04	Unmodified	2.81	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
148	<i>Ficus sp.</i>	1	29	28	5-10m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	3.48	Unmodified	1.94	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
149	<i>Ficus sp.</i>	1	23	29	5-10m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.80	Unmodified	1.97	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
150	<i>Beaucarnea recurvata</i>	2	10	17	<5m	<5m	Fair	Fair	Mature	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.57	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
151	<i>Ficus sp.</i>	1	16	17	<5m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.57	Directly within the footprint	12.56	100	Major	Remove - Significant adverse impact based on development design	Tree proposed for removal	Remove
152	<i>Ficus sp.</i>	1	22	25	<5m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.64	Unmodified	1.85	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
153	<i>Ficus sp.</i>	1	14	14	<5m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.45	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain




Tree Id	Botanical Name	Trees In Group	DSH [cm]	DRC [cm]	Height [m]	Canopy [m]	Health	Structure	Tree age	ULE [yrs]	Landscape Significance (STARS)	Retention Value (STARS)	Radial NRZ [m]	TPZ Status	Radial SRZ [m]	Likely Encroachment	Encroachment Area (m2)	Encroachment Area [%]	Encroachment Type	Development Recommendation	Tree Protection Considerations	Retention Status
154	<i>Ficus sp.</i>	1	18	24	<5m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.16	Unmodified	1.82	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
155	<i>Eucalyptus sp.</i>	1	9	11	<5m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.31	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
156	<i>Eucalyptus botryoides</i>	1	57	60	10-15m	10-15m	Poor	Fair	Mature	Short (5-15 years)	High	MEDIUM	6.84	Unmodified	2.67	Root zone disturbance, Site access, Soil grade change	14.66	10	Minor	Retain - Sustainable impact, protect tree with specific protection measures during works (i.e. Supervision of works and careful excavation in TPZ plus generic requirements)	Above grade construction techniques, Document works (photos), Project arborist engagement (AQF5), Trunk protection	Retain
157	<i>Eucalyptus sp.</i>	1	9	11	<5m	<5m	Good	Fair	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	1.31	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
158	<i>Tristaniopsis laurina</i>	1	4	5	<3m	<5m	Good	Good	Juvenile	Medium (15-40 years)	Low	LOW	2.00	Unmodified	0.94	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
159	<i>Eucalyptus saligna x botryoides</i>	1	45	52	10-15m	10-15m	Good	Fair	Semi-Mature	Medium (15-40 years)	High	HIGH	5.40	Unmodified	2.51	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
160	<i>Eucalyptus saligna x botryoides</i>	1	32	33	10-15m	5-10m	Poor	Fair	Semi-Mature	Short (5-15 years)	Medium	LOW	3.84	Unmodified	2.08	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
161	<i>Eucalyptus saligna x botryoides</i>	1	53	53	10-15m	10-15m	Good	Fair	Mature	Medium (15-40 years)	High	HIGH	6.36	Unmodified	2.53	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
162	<i>Melaleuca quinquenervia</i>	1	29	37	5-10m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.48	Unmodified	2.18	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain
163	<i>Melaleuca quinquenervia</i>	1	27	32	5-10m	5-10m	Good	Good	Semi-Mature	Medium (15-40 years)	Medium	MEDIUM	3.24	Unmodified	2.05	Material delivery & storage	0	0	Nil	Retain - Situated outside the development footprint, protect tree with generic protection measures during works (i.e. protective fencing and restriction of activities within TPZ)	Generic tree protection considerations apply	Retain

10 Tree Protection Plan (TPP)



ArborScan



PROJECT NOTES

1 - All works within the TPZ are to be undertaken under AQF5 Project Arborist supervision to ensure root preservation and compliance with AS 4970:2025. Tree protection fencing is to be used to exclude the trees from damages. Changes to the clients design have been made which include the construction of the roadway to be above grade. No excavation below the natural grade is permitted. The encroachment considers a maximum potential value. The existing hard ground surfaces within the tree protection zone are to be demolished towards the end of the project, so it can be used to maintain vehicle access, and reduce the impact to the tree root system.

MAP LEGEND

- STARS RETENTION STATUS - HIGH x 11
- STARS RETENTION STATUS - MEDIUM x 74
- STARS RETENTION STATUS - LOW x 77
- STARS RETENTION STATUS - PRIORITY FOR REMOVAL x 1


Tree Protection Zone (TPZ)

- Structural Root Zone (SRZ)
- Notional Root Zone (NRZ) Proposed Retention - 102 Trees
- Notional Root Zone (NRZ) Proposed Removal - 61 Trees

- Trunk protection requirements
- Ground protection requirements
- Branch protection requirements
- TPZ is to be protected by fencing in line with the Australian Standard AS 4970-2025

- Further Investigation
- Note: A qualified Project Arborist must be appointed to oversee all tree protection measures for the duration of works. This includes managing activities within Tree Protection Zones (TPZs), ongoing monitoring, and issuing compliance certification. The arborist must have at least five years' arboricultural experience and ensure all protection measures meet AS 4970-2025. Duties include establishing TPZ fencing, installing trunk and branch protection, and applying ground protection to prevent compaction and root damage.

PROJECT NOTES



MAP LEGEND

- STARS RETENTION STATUS - HIGH x 11
- STARS RETENTION STATUS - MEDIUM x 74
- STARS RETENTION STATUS - LOW x 77
- STARS RETENTION STATUS - PRIORITY FOR REMOVAL x 1
- Tree Protection Zone (TPZ)


- Structural Root Zone (SRZ)
- Notional Root Zone (NRZ) Proposed Retention - 102 Trees
- Notional Root Zone (NRZ) Proposed Removal - 61 Trees

- Trunk protection requirements
- Ground protection requirements
- Branch protection requirements
- TPZ is to be protected by fencing in line with the Australian Standard AS 4970-2025

- Further Investigation
- Note: A qualified Project Arborist must be appointed to oversee all tree protection measures for the duration of works. This includes managing activities within Tree Protection Zones (TPZs), ongoing monitoring, and issuing compliance certification. The arborist must have at least five years' arboricultural experience and ensure all protection measures meet AS 4970-2025. Duties include establishing TPZ fencing, installing trunk and branch protection, and applying ground protection to prevent compaction and root damage.







PROJECT NOTES

3 - All works within the TPZ are to be undertaken under AQF5 Project Arborist supervision to ensure root preservation and compliance with AS 4970:2025. Tree protection fencing is to be used to exclude the trees from damages.

MAP LEGEND

- STARS RETENTION STATUS - HIGH x 11
- STARS RETENTION STATUS - MEDIUM x 74
- STARS RETENTION STATUS - LOW x 77
- STARS RETENTION STATUS - PRIORITY FOR REMOVAL x 1
- Tree Protection Zone (TPZ)

- Structural Root Zone (SRZ)
- Notional Root Zone (NRZ) Proposed Retention - 102 Trees
- Notional Root Zone (NRZ) Proposed Removal - 61 Trees

- Trunk protection requirements
- Ground protection requirements
- Branch protection requirements
- TPZ is to be protected by fencing in line with the Australian Standard AS 4970-2025

- Further Investigation
- Note: A qualified Project Arborist must be appointed to oversee all tree protection measures for the duration of works. This includes managing activities within Tree Protection Zones (TPZs), ongoing monitoring, and issuing compliance certification. The arborist must have at least five years' arboricultural experience and ensure all protection measures meet AS 4970-2025. Duties include establishing TPZ fencing, installing trunk and branch protection, and applying ground protection to prevent compaction and root damage.





must be appointed to oversee the duration of works. This in Tree Protection Zones issuing compliance have at least five years' ensure all protection measures include establishing TPZ fencing, protection, and applying ground and root damage.

- STARS RETENTION STATUS - HIGH x 11
- STARS RETENTION STATUS - MEDIUM x 74
- STARS RETENTION STATUS - LOW x 77
- STARS RETENTION STATUS - PRIORITY FOR REMOVAL x 1
- Tree Protection Zone (TPZ)


- | | | | |
|---|--|---|---|
|  | Structural Root Zone (SRZ) |  | Trunk protection requirements |
|  | Notional Root Zone (NRZ)
Proposed Retention - 102 Trees |  | Ground protection requirements |
|  | Notional Root Zone (NRZ)
Proposed Removal - 61 Trees |  | Branch protection requirements |
| | |  | TPZ is to be protected by fencing in line with the Australian Standard AS 4970–2025 |

- ### Further Investigation




Note: A qualified Project Arborist must be appointed to oversee all tree protection measures for the duration of works. This includes managing activities within Tree Protection Zones (TPZs), ongoing monitoring, and issuing compliance certification. The arborist must have at least five years' arboricultural experience and ensure all protection measures meet AS 4970–2025. Duties include establishing TPZ fencing, installing trunk and branch protection, and applying ground protection to prevent compaction and root damage.





PROJECT NOTES



Note: A qualified Project Arborist must be appointed to oversee all tree protection measures for the duration of works. This includes managing activities within Tree Protection Zones (TPZs), ongoing monitoring, and issuing compliance certification. The arborist must have at least five years' arboricultural experience and ensure all protection measures meet AS 4970-2025. Duties include establishing TPZ fencing, installing trunk and branch protection, and applying ground protection to prevent compaction and root damage.



ArborScan

APPENDIX 1. ASSUMPTIONS AND LIMITING CONDITIONS

Copyright notice: ©ArborScan Pty Ltd. All rights reserved, except as expressly provided otherwise in this publication.

Disclaimer: Although ArborScan Pty Ltd uses all due care and skill in providing you with the information made available in this report, to the extent permitted by law, ArborScan Pty Ltd otherwise excludes all warranties of any kind, either expressed or implied. To the extent permitted by law, you agree that ArborScan Pty Ltd is not liable to you or any other person or entity for any loss or damage caused or alleged to have been caused (including loss or damage resulting from negligence), either directly or indirectly, by your use of the information (including by way of example, arboricultural advice) made available to you in this report. Without limiting this disclaimer, in no event, will ArborScan Pty Ltd be liable to you for any lost revenue or profits or for special, indirect, consequential or incidental damage (however caused and regardless of the theory of liability) arising out of or related to your use of that information, even if ArborScan Pty Ltd has been advised of the possibility of such loss or damage. This disclaimer is governed by the law in force in the State of NSW, Australia. Any legal description provided to ArborScan Pty Ltd will be assumed to be correct. Any titles and ownership of any property will be assumed to be good. No responsibility is assumed for matters outside the consultant's control.

ArborScan Pty Ltd assumes that any property or project is not in violation of any applicable codes, ordinances, statutes or other local, state or federal government regulations.

ArborScan Pty Ltd shall take care to obtain all information from reliable sources. All data shall be verified insofar as possible, however, ArborScan Pty Ltd can neither guarantee nor be responsible for the accuracy of the information provided by others not directly under ArborScan Pty Ltd's control.

No ArborScan Pty Ltd employee or subcontractor shall be required to give testimony or to attend court by reason of the report unless subsequent contractual arrangements are made, including payment of an additional fee for such services.

Loss of the report or alteration of any part of the report not undertaken by ArborScan Pty Ltd invalidates the entire report. Possession of the report or a copy thereof does not imply right of publication or use for any purpose by anyone but the client or their directed representatives without the prior written consent of ArborScan Pty Ltd.

The report and any values expressed therein represent the opinion of ArborScan Pty Ltd's consultants and ArborScan Pty Ltd's fee is in no way conditional upon the reporting of a specified value, a stipulated result, the occurrence of a subsequent event, nor upon any finding to be reported.

Sketches, diagrams, graphs and photographs used in the report, being intended as visual aids, are not necessarily to scale and should not be construed as engineering or architectural drawings, reports or surveys.

Unless expressed otherwise: i) Information contained in this report covers only those items that were covered in the project brief or that were examined during the assessment and reflect the condition of those items at the time of inspection; and ii) The inspection is limited to visual examination of accessible components without dissection, excavation, further testing or probing unless otherwise stipulated.

There will be no warranty or guarantee, expressed or implied by ArborScan Pty Ltd, that failures, problems or deficiencies of the trees subject to the report (or parts thereof) may not arise at any time in the future.

All instructions (verbal or written) that define the scope of the report have been included in the report and all documents and other materials that the ArborScan Pty Ltd consultant has been instructed to consider or to take into account in preparing this report have been included or listed within the report. To the writer's knowledge all facts, matter and all assumptions upon which the report proceeds have been stated within the body of the report and all opinion contained within the report have been fully researched and referenced and any such opinion not duly researched is based upon the writer's experience and observations.

Tree risk assessment is limited in scope to the specific risk of interest and does not include any and all risks. The tree risk assessment will consider significant known and/or assigned targets and visible or detectable tree conditions, the risk assessment will represent the assessed tree and site at the time of the inspection. For the purpose of this report, the timeframe considered for likelihood of failure is 12 months. It is important to note that the timeframe should not be considered a 'guarantee period' for the risk assessment.

APPENDIX 2. DESCRIPTION OF SURVEY ASSESSMENT TERMS

The trees assessed by visual examination which form the survey reflect an impartial assessment by the assessor and is based on the assessor's arboriculture experience and on the condition of the tree on the day of its survey. The following definitions have been provided to guide a better understanding of the assessment categories included within the issued report. Depending on the report type, all categories may not be applicable.

- **Tree Number** – Number assigned to the tree, often referenced on an aerial site map, depending on the project scope, a physical tag with the trees corresponding number may also be installed.
- **Tree Location Coordinates** – Easting and northing coordinates Geocentric Datum of Australia 1994 (GDA94) will be collected for each tree surveyed and will be displayed within the reports inventory. Coordinates unless otherwise specified are +/- 4m in accuracy.
- **Tree Height & Canopy Spread** – Estimated size range in metres on its broadest axis. Where required tree height and canopy spread will be estimated to the nearest metre. Heights and spreads will only be measured where required by the scope.
- **Diameter At Standard Height (DSH)** – Estimated trunk diameter size range in 'mm' at its broadest axis at 1.4m from ground level for a single trunked tree. DBH will be accurately measured as per the Australian Standard AS 4970–2025: Protection of Trees on Development Sites when defined in the projects scope.
- **Diameter At Root Crown (DRC)** – Estimated trunk diameter size range in 'mm' at its broadest axis at immediately above the buttress. The DRC will be accurately measured as per the Australian Standard AS 4970–2025: Protection of Trees on Development Sites when defined in the projects scope.
- **Tree Species** – The accepted common name and botanical name (genus and species) will be identified and documented in the report where reproductive material and features of the tree are available to the assessor. Where species cannot be accurately identified, the assessor will identify the genus, where the genus cannot be identified, a family or general identification reference will be otherwise assigned.

Table 19. Definition – Age / Maturity Class

Term	Definition
Young	Establishing tree which has been planted or self-seeded within the last 5 years, in situ.
Juvenile	Tree aged less than 90% of its life expectancy, in situ.
Semi Mature	Tree aged less than 80% of its life expectancy, in situ.
Mature	Tree aged 20–80% of its life expectancy, in situ.
Over-mature	Tree aged greater than >80% of its life expectancy, in situ, or senescent with or without reduced vigour, and declining gradually or rapidly but irreversibly to death.

Table 20. Definition – Tree Health

Term	Definition
Excellent	Perfect specimen with excellent form and vigour, along with a well-balanced canopy. Trunk is sound and solid. No apparent pest problems. Normal to exceeding shoot length on new growth. Normal leaf size and colour. Exceptional life expectancy for the species.
Good	The tree should exhibit a full canopy of foliage. May lack natural symmetry. Good growth rate and minor deficiency in leaf development. Few pest issues or damage, and controllable if present. Normal branch and stem development with healthy growth. Typical life expectancy for the species.
Fair	The tree is in reasonable condition but growing well. Canopy decline and dieback up to 25% of the canopy. Fair overall symmetry. Leaf size smaller and colour somewhat chlorotic. There may be some deadwood present in the canopy. Minor decay in the trunk and major branches. Minor pathogen damage. Shoot extensions indicate some stunting and stressed growing conditions. Some signs of pest problems contributing to a lesser condition. Moderate life expectancy for the species.
Poor	Lacking a full canopy, with more than 50% decline and dieback that especially affects larger branches. Not growing to its full capacity. Stunting obvious, with little evidence of growth on smaller stems. Large amounts of deadwood may be evident throughout the canopy. Moderate decay in the trunk and major branches. Moderate pathogen damage. Leaf size and colour reveals overall stress in the plant. Insect or disease infestation may be severe. Low life expectancy for the species.
Very Poor	More than 70% of the canopy is in severe decline or dead. Canopy density is extremely low, with chlorotic and necrotic tissue dominating the canopy. Significant/Severe decay in the trunk and major branches. Significant/Severe pathogen damage. Root plate damage with a majority of roots damaged, diseased, or missing. Very low life expectancy for the species.
Dead	No live plant material observed.

Table 21. Definition – Tree Origin

Term	Definition
Exotic	A plant introduced from another country or region to a place where it was not indigenous. Such plants may become naturalised and often originate as garden escapees.
Native	A plant found to occur as an endemic or indigenous species where it is growing or a plant known to have originated as an endemic or indigenous species from a particular place, e.g. continent, country, region, mountain or island.
Endemic	A native plant usually with a restricted occurrence limited to a particular country, geographic region or area and often further confined to a specific habitat.
Invasive / Noxious weed	A plant species of any taxa declared a weed by legislation. Treatment for the control or eradication of such weeds is usually prescribed by the legislation.

Table 22. Definition – Tree Form

Term	Definition
Excellent	Ideal tree for that species, including shape and canopy symmetry, health, and density. Outstanding function on the site or location.
Good	Tree of typical canopy shape and habit with proportions representative of the taxa considering constraints such as origin, e.g. indigenous or exotic, but does not appear to have been adversely influenced in its development by environmental factors in situ such as soil water availability, prevailing wind, or cultural practices such as lopping and competition for space and light.
Fair	Acceptable tree for that species. Tree shape and symmetry are adequate, with some substantial asymmetry in shape and canopy form. May have considerable concerns for its use and function on the site or location.
Poor	Poor tree for that species. Highly irregular canopy shape and undesirable form make it unattractive and dysfunctional on the site or location.
Very Poor	Disagreeable tree for that species, with highly diminished function and aesthetic appeal on the site or location.
Dead	No live plant material observed.

Table 23. Definition – Vigour

Term	Definition
Good	Accelerated growth of a tree due to incidental or deliberate artificial changes to its growing environment that are seemingly beneficial, but may result in premature aging or failure if the favourable conditions cease or promote prolonged senescence if the favourable conditions remain, e.g. water from a leaking pipe; water and nutrients from a leaking or disrupted sewer pipe; nutrients from animal waste, a tree growing next to a chicken coop, or a stock feedlot, or a regularly used stockyard; a tree subject to a stringent watering and fertilising program, or some trees may achieve an extended lifespan from continuous pollarding practices over the life of the tree.
Normal	Ability of a tree to maintain and sustain its life processes. This may be evident by the typical growth of leaves, Canopy cover and density, branches, roots and trunk and resistance to predation. This is independent of the condition of a tree but may impact upon it, and especially the ability of a tree to sustain itself against predation.
Low	Reduced ability of a tree to sustain its life processes. This may be evident by the atypical growth of leaves, reduced canopy cover and density, branches, roots, and trunk, and a deterioration of their functions with reduced resistance to predation. This is independent of the condition of a tree but may impact upon it, and especially the ability of a tree to sustain itself against predation.

Table 24. Definition – Structure

Term	Definition
Good	Root plate appears normal, with no damage. No trunk defects. Good branch habit and attachment; minor dieback with no visible structural defects. There may be some signs of previous pruning. Minimal deadwood. Codominant stem formation may be present. No fungal pathogens present.
Fair	Root plate reveals previous minor damage or disturbance (Tree Protection Zone (TPZ) Encroachment <10%). Evidence of minor trunk damage or cavities where decay could colonise. Less than 25% of bark sections missing. Included stems are present with no evidence of cracks or splits. Some branch unions may exhibit minor structural faults. Branching habit and attachments indicate poor pruning or damage, which requires moderate corrections. Minimal previous branch failures have occurred. Fungal pathogens may be present. Removal of surrounding trees and or the removal or the addition of buildings or structures has occurred partly exposing the tree or its parts to increased wind loads.
Poor	Root plate disturbance and defects indicate major damage (Tree Protection Zone (TPZ) Encroachment >10%). Girdling roots around the trunk flare. Wounding evident with cavities and/or decay present. Trunk reveals more than 50% of bark section missing. Included stems are present and are considered likely to fail in 0–5 years. Branch structure has poor attachments, with several structurally important branches dead or broken. Branch unions may be poor or faulty at the point of attachment. Canopy reveals signs of damage or previous topping or lion-tailing, with major corrective action required. Fungal pathogens are present. Removal of surrounding trees and or the removal or the addition of buildings or structures has occurred fully exposing the tree or its parts to increased wind loads.
Very Poor	Failure imminent. Severe damage within the root plate and root collar exhibits major defects that could lead to tree death or failure. Partial root plate failure. A majority of the bark or trunk is affected, either decayed or missing. Branching is extremely poor or severely topped, with severe dieback in canopy. Active splits or partial failure. The tree has a very poorly structured canopy. Little or no opportunity for mitigation of any tree parts. Fungal pathogens are severely impacting tree structure. Tree is significantly exposed to increased wind loads as a result of the removal of surrounding trees and or the removal or the addition of buildings or structures.

Table 25. Definition – Estimated Useful Life Expectancy

Term	Definition
Dead	No live plant material observed
Limited Term	A period of time <5
Short Term	A period of time 5–15 years
Medium Term	A period of time 15–40 years
Long Term	A period of time greater than >40 years

APPENDIX 3. GENERAL ARBORICULTURAL TERMS

Abrasion wound—Mechanical wound causing laceration of tissue by an abrasive impact episode, e.g. grazed by a motor vehicle or the continuous action of the rubbing of crossed branches or stems where no graft has formed.

Aerial inspection—Assessment of the canopy of a tree by climbing within the canopy or by the use of an elevating work platform, often to examine a particular defect, e.g. cavity or hollow.

Arboriculture—The science and culture of the growth, planning, management, care and maintenance of trees primarily for amenity and utility purposes.

Asymmetrical—Imbalance within a canopy, where there is an uneven distribution of branches and the foliage canopy or root plate around the vertical axis of the trunk. This may be due to codominant or suppressed canopy form as a result of restrictions, e.g. buildings, or competition for space and light with other trees, or exposure to wind, or artificially caused by pruning for clearance of roads, buildings or power lines. An example of an expression of this may be, canopy asymmetrical, bias to west.

Basal flare—Swelling at the root crown is usually uniform around the base of the trunk involving tissue from the trunk and root crown. Here first-order roots may not be evident at the root crown.

Basal trunk wound—A wound on the trunk extending to the root crown where the base of the wound is open at the ground and usually truncated. Dependent upon the width of its base, such a wound may not become occluded.

Bracing—Systems of cables and ropes, traditionally using metal wires but generally replaced by polypropylene, used to support and prolong the life of trees in part or full; systems are susceptible to failure due to evident weaknesses in branch unions. Examples of such proprietary systems are Cobra and Yale nylon webbing.

Bracket fungus—The rigid sporophore of some fungus species, especially those associated with live trees or the decay of wood. Structures comprised of hyphae for the dispersal of spores, often bracket-shaped, usually protruding from the roots, trunk or branches of a host tree when the fungus matures. The fruiting body may be ephemeral or persistent and may last for only one season or persist for many years, with the fruiting body growing incrementally larger and continuing to produce new spores. Such fruiting bodies may be solitary or gregarious.

Cavity—A void often localised initiated by a wound and subsequent decay within the trunk, branches or roots, or beneath the bark, and maybe enclosed or have one or more openings.

Deadwooding—Removing of dead branches by pruning. Such pruning may assist in the prevention of the spread of decay from dieback or for reasons of safety near an identifiable target.

Dead Tree—A tree that does not contain any live tissue, i.e., green leaves or live limbs.

Decay—Process of degradation of wood by micro-organisms and fungus.

Deciduous—A woody plant, e.g. tree, shrub or vine, that sheds all of its leaves in one season and enters a dormant period, usually during winter.

Defect—In relation to tree hazards, any feature of a tree which detracts from the uniform distribution of mechanical stress, or which makes the tree mechanically unsuited to its environment.

Dieback—The death of some areas of the canopy. Symptoms are leaf drop, bare twigs, dead branches and tree death, respectively. This can be caused by root damage, root disease, bacterial or fungal canker, severe bark damage, intensive grazing by insects, abrupt changes in growth conditions, drought, water-logging or over-maturity. Dieback often implies reduced resistance, stress or decline which may be temporary. Dieback can be categorised as Low volume dieback, Medium volume dieback and High volume dieback.

Dormant Tree—Vigour presently indeterminable, assessment to take place at the time of leaf return.

Emergency removal—Tree removal as a matter of urgency due to its imminent potential to cause damage to people or property as a result of structural defects or modifications to its growing environment rendering it vulnerable to failure in full or part, e.g. a tree in adverse weather conditions suddenly developing a progressive lean and collapsing across a busy road.

End weight—Excessive formation of foliage concentrated at the distal end of a branch.

Epicormic shoots—Juvenile shoots produced at branches or trunk from epicormic strands in some Eucalypts (Burrows 2002, pp. 111–131) or sprouts produced from dormant or latent buds concealed beneath the bark in some trees. Production can be triggered by fire, pruning, wounding, or root damage but may also be as a result of stress or decline. Epicormic shoots can be categorised as low volume epicormic shoots, medium volume epicormic shoots and high volume epicormic shoots.

Epicormic stem—Branch derived from an epicormic shoot.

Flush cut—An incorrect cut that damages or removes the branch collar or branch bark ridge and, as a result, damages stem tissue.

Formative pruning—The pruning of young trees is usually to assist with the development of canopy form and shape and to develop strong structure (Australian Standard 2007, p. 7). Such pruning may reduce developmental weaknesses, e.g. crossed branches, branches with branch bark inclusions, or to remove codominant first-order branches to extend the length of a trunk or to guide the canopy form of a tree to a single first-order structural branch, or to encourage branching to make a canopy shape excurrent or deliquescent, respectively.

Habitat Features—The habitat features described in this report are parts of the environment (living or non-living) that may provide native animals with food and shelter and sites for nesting, migration and social interaction.

Included bark—1. The bark on the inner side of the branch union or is within a concave crotch that is unable to be lost from the tree and accumulates or is trapped by acutely divergent branches forming a compression fork. 2. Growth of bark at the interface of two or more branches on the inner side of a branch union or in the crotch where each branch forms a branch collar, and the collars roll past one another without forming a graft where no one collar is able to subsume the other. The risk of failure is worsened where branching is acutely divergent or acutely convergent and ascending or erect.

Lightning strike wound—A wound from a lightning strike. Such a wound may kill a tree outright or cause it to catch fire or may destroy the tree in full or part, or no injury may be evident, and a tree gradually declines through resulting stress. Bark may be exploded from the tree by pressure radiating from the core of the lightning path resulting in further compounded damage through water heating and steam explosions in the tissues and the electrical disruption of living cells.

Mixed-age population—A population of trees that contains representatives of each age class, i.e., young, mature and over-mature, so that trees in the population will not all mature or become senescent at the same time. This is usually achieved by staggering planting and/or removal of trees in a systematic manner. This also spreads the cost of planting, maintenance and removal over time.

Mulch—Any organic or inorganic material placed over the soil or growing media near cultivated plants primarily to suppress weeds, modify soil temperature and retain soil moisture levels. This artificial process generally imitates the function of leaf litter in a forest environment.

Nesting hollow—A hollow or cavity within any part of a tree utilised as habitat or shelter for any part of the life cycle of Fauna, e.g., birds, reptiles or mammals.

Non-invasive root mapping—Any root mapping process that does not disturb or displace soil or growing media to locate roots, e.g. ground-penetrating radar.

Occlusion Growth—Processes where wound wood develops to enclose the wound face by the merging of wound margins concealing the wound and restoring the growing surface of the structure with each growth increment gradually realigning fibres in the wood longitudinally along the stem to maximise uniform stress loading.

Occupancy rating—The frequency of use of a likely target and the possibility that people will be present when tree failure or collapse occurs.

Pathogen—Any organism is causing disease, e.g. fungus, bacterium, mycoplasma, virus, virioid, nematode or protozoan.

Pruning—Removal of any branch or root, dead or alive, by severance across the stem, back to the intersection of another live stem to a swollen area at the intersection called a branch collar where such a structure exists, with a final cut at the outer edge of the collar leaving no stub, or to undamaged woody tissue for roots. Also, the severing of any part of a tree so as to cause a reduction of the air space occupied by the branches and foliage in the canopy or roots in the root plate. Examples of pruning are dead wooding, crown lifting, formative pruning, reduction pruning, selective pruning, crown thinning, and remedial and restorative pruning (Australian Standards 2007, p. 6). Pruning should conform to recognised standards, e.g. Australian Standard® AS 4373 'Pruning of Amenity Trees'. The following are not recognised as pruning: lop, lopping, top, topping, top lopping.

Pruning wound—A wound created by the act of pruning.

Radial trenching—A series of excavated trenches near to the trunk, usually between first-order roots, allowing space for the introduction of improved growing media. This process is designed to stimulate new root growth through reduced compaction, improved aeration and removal of contaminated soil.

Mitigations/Recommendations/Actions—A list of arboricultural and/or plant health care works that are aimed at maintaining or improving the tree's health, structural condition or form. Actions may also directly or indirectly reduce the risk potential of the tree, such as via the removal of a particular branch or the moving of infrastructure from under its canopy.

Resistance Drilling—A self-powered drilling device that operates a thin spade drill bit at a constant forward speed to record soundness of wood by measuring resistance to drilling that is plotted on graph paper or with an electronic unit that gives clear support in taking, documenting and evaluating measurements. Examples of such proprietary devices are the **IML-RESI PowerDrill®** and **Resistograph®**.

Structural Root Zone (SRZ)—An zone which defines the structural root zone which is an area required for tree stability. The SRZ is located within the TPZ.

Notional Root Zone (NRZ)—An exclusion area that allows for protection of canopy and roots. The radius of the NRZ is normally calculated for each tree by multiplying the DBH × 12. The minimum distance will be 2m and maximum 15m as stipulated in the Australian Standard 4970-2025: Protection of trees on development sites.

Tree significance—Includes environmental, social or historical reasons why the tree is significant to the site. The tree may also be rare under cultivation or have a rare or localised natural distribution.

Ultrasonic tomography—Electronic devices that measure the transmissibility of ultrasound waves through a given section of a tree by detecting pulses through multiple sensors placed around a stem to indicate areas with the same density. An example of such a proprietary device is the **Picus® Tomograph**.

Visual tree assessment (VTA)—A visual inspection of a tree from the ground-based on the principle that, when a tree exhibits apparently superfluous material in its shape, this represents repair structures to rectify defects or to reinforce weak areas in accordance with the axiom of uniform stress. Such assessments should only be undertaken by suitably competent practitioners.

Weed species—Any plant species exotic or native that is known to spread by the production of viable progeny often in large numbers, outcompeting and disrupting existing vegetation, e.g. in gardens, parks or bushland. The species concerned may be introduced from outside its area of natural distribution to an area where there are few or no natural predators, or it may have an ability to spread due to changes in land use creating a favourable habitat.

Information Source: Draper, Danny B. Dictionary for Managing Trees in Urban Environments. CSIRO PUBLISHING. Kindle Edition.

APPENDIX 4. STARS[®] TREE RETENTION VALUE MATRIX

10.1 IACA Significance of a Tree, Assessment Rating System (STARS[®]) (IACA 2010)[®]

- 10.1.1 In the development of this assessment rating system, the Institute of Australian Consulting Arboriculturists (IACA) acknowledges the contribution and original concept of the Footprint Green Tree Significance and Retention Value Matrix, developed by Footprint Green Pty Ltd in June 2001. The landscape significance of a tree is an essential criterion to establish the importance that a particular tree may have on a site. However, rating the significance of a tree becomes subjective and difficult to ascertain in a consistent and repetitive fashion due to assessor bias. It is, therefore, necessary to have a rating system utilising structured qualitative criteria to assist in determining the retention value for a tree. To assist this process, all definitions for terms used in the Tree Significance - Assessment Criteria and Tree Retention Value - Priority Matrix are taken from the IACA Dictionary for Managing Trees in Urban Environments 2009.
- 10.1.2 This rating system will assist in the planning processes for proposed works, above and below ground, where trees are to be retained on or adjacent to a development site. The system uses a scale of High, Medium and Low significance in the landscape. Once the landscape significance of an individual tree has been defined, the retention value can be determined.

Table 26. Tree Significance - Assessment Criteria

1. High Significance in landscape	2. Medium Significance in landscape	3. Low Significance in landscape
The tree is in good condition and good vigour, The tree has a form typical for the species, The tree is a remnant or is a planted locally indigenous specimen and/or is rare or uncommon in the local area or of botanical interest or of substantial age, The tree is listed as a Heritage Item, Threatened Species or part of an Endangered ecological community or listed on Councils significant Tree Register, The tree is visually prominent and visible from a considerable distance when viewed from most directions within the landscape due to its size and scale and makes a positive contribution to the local amenity, The tree supports social and cultural sentiments or spiritual associations, reflected by the broader population or community group or has commemorative values, The tree's growth is unrestricted by above and below ground influences, supporting its ability to reach dimensions typical for the taxa in situ - the tree is appropriate to the site conditions.	The tree is in fair-good condition and good or low vigour, The tree has form typical or atypical of the species, The tree is a planted locally indigenous or a common species with its taxa commonly planted in the local area, The tree is visible from surrounding properties, although not visually prominent as partially obstructed by other vegetation or buildings when viewed from the street, The tree provides a fair contribution to the visual character and amenity of the local area, The tree's growth is moderately restricted by above or below ground influences, reducing its ability to reach dimensions typical for the taxa in situ.	The tree is in fair-poor condition and good or low vigour, The tree has form atypical of the species, The tree is not visible or is partly visible from surrounding properties as obstructed by other vegetation or buildings, The tree provides a minor contribution or has a negative impact on the visual character and amenity of the local area, The tree is a young specimen that may or may not have reached dimension to be protected by local Tree Preservation orders or similar protection mechanisms and can easily be replaced with a suitable specimen, The tree's growth is severely restricted by above or below ground influences, unlikely to reach dimensions typical for the taxa in situ - the tree is inappropriate to the site conditions, The tree is listed as exempt under the provisions of the local Council Tree Preservation Order or similar protection mechanisms, The tree has a wound or defect that has the potential to become structurally unsound.
		Environmental Pest / Noxious Weed Species The tree is an Environmental Pest Species due to its invasiveness or poisonous/ allergenic properties, The tree is a declared noxious weed by legislation.
		Hazardous/Irreversible Decline The tree is structurally unsound and/or unstable and is considered potentially dangerous, The tree is dead, or is in irreversible decline, or has the potential to fail or collapse in full or part in the immediate to short term.

The tree is to have a minimum of three (3) criteria in a category to be classified in that group. Note: The assessment criteria are for individual trees only; however, they can be applied to a monocultural stand in its entirety



ArborScan

ARBORICULTURAL SPECIALISTS