

Development Consent

Section 4.16 of the Environmental Planning and Assessment Act 1979

The Independent Planning Commission (the Commission), as the declared consent authority under section 2.7 of the *State Environmental Planning Policy (Planning Systems) 2021* and section 4.5(a) of the *Environmental Planning and Assessment Act 1979*, approves the development application referred to in Schedule 1, subject to the conditions in Schedule 2.

These conditions are required to:

- prevent, minimise, or offset adverse environmental impacts;
- set standards and performance measures for acceptable environmental performance;
- require regular monitoring and reporting; and
- provide for the ongoing environmental management of the development

Dr Sheridan Coakes (Chair)
Member of the Commission

Michael Chilcott
Member of the Commission

Sydney

19 August 2025

File: SSD-68708456

The Department has prepared a consolidated version of the consent which is intended to include all modifications to the original determination instrument.

The consolidated version of the consent has been prepared by the Department with all due care. This consolidated version is intended to aid the consent holder by combining all consents relating to the original determination instrument but it does not relieve a consent holder of its obligation to be aware of and fully comply with all consent obligations as they are set out in the legal instruments, including the original determination instrument and all subsequent modification instruments.

CONSOLIDATED INSTRUMENT

SCHEDULE 1

Application Number:	SSD-68708456
Applicant:	The Trustee for the Think Planners Unit Trust
Consent Authority:	NSW Independent Planning Commission
Site:	242-244 Beecroft Road, Epping Lot 220, DP 1251471 and Lot 222, DP 1251471
Development:	Alterations and additions to the approved mixed-use development, including: • additional one to two storeys to Buildings A and D • additional three to four storeys to Buildings B, C and E • additional 105 apartments • additional basement parking level • minimum 15% of residential gross floor area to be used as affordable housing dwellings for at least 15 years • stratum subdivision of the site

(Advisory Note 1: The development approved under this consent is in conjunction with the development approved under consent SSD-31576972 for a mixed-use development on the site)

CONSOLIDATED INSTRUMENT

Summary of Modifications

SSD-68708456	Approved by NSW Independent Planning Commission on 19 August 2025
SSD-68708456-Mod-1	Withdrawn
SSD-68708456-Mod-2	Approved by the ED, Key Sites and Housing Assessment on 06 July 2025, for: • Modifications to maximum building heights, building separation, setbacks to the boundaries, landscaping including the through site link, external façade, allocation of rooms and spaces at the lower ground and basement levels and layout of apartment units and commercial tenancies at the upper levels.

CONSOLIDATED INSTRUMENT

DEFINITIONS

Above Ground Works	Development above finished ceiling level of the Basement 1 level
Advisory notes	Advisory information relating to the consent but do not form a part of this consent
AQMP	Air Quality Management Sub-Plan
Applicant	The Trustee for the Think Planners Unit Trust, or any person carrying out any development to which this consent applies
AS	Australian Standard published by Standards Australia International Limited and means the current standard which applies at the time the relevant work is undertaken
AHD	Australian Height Datum
CCS	Community Consultative Strategy
Certifier	A person who is authorised by or under section 6.17 of the EP&A Act to issue Part 6 certificates
CEMP	Construction Environmental Management Plan
CNVMP	Construction Noise and Vibration Management Sub-Plan
Conditions of this consent	Conditions contained in Schedule 2 of this document
Construction	The demolition and removal of buildings or works, the carrying out of works for the purposes of development, including site establishment works, relocation of utilities, earthworks, and erection of buildings and other infrastructure permitted by this consent
Construction Certificate	A certificate to the effect that building work completed in accordance with specified plans and specifications or standards will comply with the requirements of the EP&A Act
Council	City of Parramatta Council
CPTED	Crime Prevention Through Environmental Design
CPTMP	Construction Pedestrian and Traffic Management Sub-Plan
Day	The period from 7 am to 6 pm on Monday to Saturday, and 8 am to 6 pm on Sundays and Public Holidays
Demolition	The deconstruction and removal of buildings, sheds and other structures on the site
Department	NSW Department of Planning, Housing and Infrastructure
Development	The development described in the EIS, Response to Submissions, any additional information provided by the Applicant in support of the application and approved pursuant to this consent, as modified by the conditions of this consent
EIS	The Environmental Impact Statement titled Amended Mixed-Use Development - 242-244 Beecroft Road, Epping, dated August 2024, submitted with the application for consent for the development, including any additional information provided by the Applicant in support of the application
Environment	Includes all aspects of the surroundings of humans, whether affecting any human as an individual or in their social groupings
EPA	NSW Environment Protection Authority
EP&A Act	<i>Environmental Planning and Assessment Act 1979</i>
EP&A Regulation	<i>Environmental Planning and Assessment Regulation 2021</i>
ESD	Ecologically Sustainable Development
Feasible	Means what is possible and practical in the circumstances
Fire Safety Certificate	Has the same meaning as in the <i>Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021</i>

CONSOLIDATED INSTRUMENT

Heritage items	A building and/or place identified as an item of environmental heritage within an environmental planning instrument, and/or listed on the State Heritage Register under the <i>Heritage Act 1977</i>
Incident	An occurrence or set of circumstances that causes, or threatens to cause material harm and which may or may not be or cause a non-compliance Note: "material harm" is defined in this consent
Land	Has the same meaning as the definition of the term in section 1.4 of the EP&A Act
Material harm	Is harm that: a) involves actual or potential harm to the health or safety of human beings or to the environment that is not trivial, or b) results in actual or potential loss or property damage of an amount, or amounts in aggregate, exceeding \$10,000, (such loss includes the reasonable costs and expenses that would be incurred in taking all reasonable and practicable measures to prevent, mitigate or make good harm to the environment).
Minister	NSW Minister for Planning and Public Spaces (or delegate)
NCC	National Construction Code, meaning the current standard which applies at the time the relevant work is undertaken, published by the Australian Building Codes Board
Non-compliance	An occurrence, set of circumstances or development that is a breach of this consent
Operation	The carrying out of the approved land uses upon completion of construction
Owner	The registered proprietor of the Property from time to time
Planning Secretary	Planning Secretary under the EP&A Act, or nominee
Reasonable	Means applying judgement in arriving at a decision, taking into account: mitigation benefits, costs of mitigation versus benefits provided, community views, and the nature and extent of potential improvements
Registered Surveyor	A person who is registered with the Board of Surveying and Spatial Information
RtS	Response to Submissions, meaning the Applicant's response to issues raised in submissions received in relation to the application for this development consent under the EP&A Act, including any additional information provided by the Applicant in support of the application
Site	The land identified in Schedule 1
Sensitive Receiver	Residence, education institution (e.g. school, university, TAFE college), health care facility (e.g. nursing home, hospital), religious facility (e.g. church) and children's day care facility
SDRP	State Design Review Panel
SSD	State Significant Development
TfNSW	Transport for NSW
Work(s)	Any physical work to construct or facilitate the construction of the development, including low impact work and environmental management measures

CONSOLIDATED INSTRUMENT

SCHEDULE 2 – CONDITIONS OF THIS CONSENT

PART A – ADMINISTRATIVE CONDITIONS

OBLIGATION TO MINIMISE HARM TO THE ENVIRONMENT

- A1. In addition to meeting the specific performance measures and criteria in this consent, all reasonable and feasible measures must be implemented to prevent, and if prevention is not reasonable and feasible, minimise, any material harm to the environment that may result from the construction and operation of the development.

TERMS OF CONSENT

- A2. The development may only be carried out:
- (a) in compliance with the conditions of this consent;
 - (b) in accordance with all written directions of the Planning Secretary;
 - (c) in accordance with the EIS, including the Applicant's response to submissions (RtS), and the Applicant's responses to requests for further information;
 - (d) [Section 4.55 \(1A\) modification SSD-68708456-Mod-2; and](#)
 - (e) in accordance with the approved plans in the table below:

Architectural Drawings prepared by Turner Studio			
Drawing Number	Drawing Name	Revision	Date
DA-001-001	Title Sheet	A	11/07/24
DA-010-010	Site Plan	A	11/07/24
DA-010-011	Site Analysis	A	11/07/24
DA-012-001	Staging Diagram B2 – Ground	A	11/07/24
DA-012-002	Staging Diagram Level 1	A	11/07/24
DA-051-008	Demolition Plan	A	11/07/24
DA-110-005	Basement 03	H	04/06/26
DA-110-006	Basement 02	H	04/06/26
DA-110-007	Basement 01	H	04/06/26
DA-110-008	Lower Ground	H	04/06/26
DA-110-010	Ground Level	F	04/06/26
DA-110-020	Level 01-05	F	04/06/26
DA-110-030	Level 06	F	04/06/26
DA-110-040	Level 07	F	04/06/26
DA-110-050	Level 08-13	F	04/06/26
DA-110-080	Level 14	F	04/06/26
DA-110-090	Level 15	F	04/06/26
DA-110-110	Level 16	F	04/06/26
DA-110-120	Level 17	F	04/06/26
DA-110-130	Roof Level	F	04/06/26
DA-210-101	Building A West Elevation	F	04/06/26
DA-210-201	Building B South Elevation	F	04/06/26
DA-210-301	Building B North Elevation	F	04/06/26
DA-210-401	Building C North Elevation	F	04/06/26
DA-210-501	Building E North Elevation	F	04/06/26
DA-210-601	Site East Elevation	F	04/06/26
DA-210-701	Building C and E Elevation	F	04/06/26
DA-210-801	Building C South Elevation	F	04/06/26
DA-210-901	Building E South Elevation	F	04/06/26
DA-210-1001	Site West Elevation	F	04/06/26

CONSOLIDATED INSTRUMENT

DA-310-101	Section AA - North-South	E	04/06/26
DA-310-201	Section BB - Building A & B	E	04/06/26
DA-310-301	Section CC - Building C & D	E	04/06/26
DA-310-401	Section DD - Building E	E	04/06/26
DA-310-501	Section Across Ray Road, Building A & B	A	11/07/24
DA-310-601	Section Across Ray Road, Building C & D	A	11/07/24
DA-310-701	Section Across Ray Road, Building E	A	11/07/24
DA-310-801	Public Domain Interface	A	11/07/24
DA-730-001	Deep Soil and Communal Space Diagrams Ground Level Deep Soil	A	11/03/26
DA-730-002	Communal Open Space	A	11/07/24
DA-810-001	Adaptable Plan Layouts	E	11/03/26
DA-810-002	Adaptable Plan Layouts	E	11/03/26
DA-810-003	Adaptable Plan Layouts	E	11/03/26
DA-810-004	Adaptable Plan Layouts	E	11/03/26
DA-810-005	Liveable Plan Layouts	E	11/03/26
DA-820-001	Affordable Housing	C	11/03/26
DA-820-002	Affordable Housing	C	11/03/26
DA-890-001	Materials & Finishes Board Materials	E	04/06/26
Landscape Drawings prepared by Site Image			
Drawing Number	Drawing Name	Revision	Date
SS21-4819-000	Landscape Coversheet	A	17.09.2025
SS21-4819-001	Landscape Plant Schedule & Legend	A	17.09.2025
SS21-4819-002	Ground Floor Masterplan	A	17.09.2025
SS21-4819-003	Tree Retention and Removal Plan	A	17.09.2025
SS21-4819-101	Ground Floor Landscape Plan	A	17.09.2025
SS21-4819-102	Ground Floor Landscape Plan	A	17.09.2025
SS21-4819-103	Ground Floor Landscape Plan	A	17.09.2025
SS21-4819-104	Ground Floor Landscape Plan	A	17.09.2025
SS21-4819-105	Ground Floor Landscape Plan	A	17.09.2025
SS21-4819-106	Ground Floor Landscape Plan	A	17.09.2025
SS21-4819-110	Level 1-5 Masterplan	A	17.09.2025
SS21-4819-111	Level 1-5 Landscape Plan	A	17.09.2025
SS21-4819-120	Level 6-7 Masterplan	A	17.09.2025
SS21-4819-121	Level 06 Landscape Plan	A	17.09.2025
SS21-4819-122	Level 07 Landscape Plan	A	17.09.2025
SS21-4819-123	Level 07 Landscape Plan	A	17.09.2025
SS21-4819-130	Landscape Plan – Level 16-17 Masterplan	A	17.09.2025
SS21-4819-131	Level 16 Landscape Plan	A	17.09.2025
SS21-4819-132	Level 16 Landscape Plan	A	17.09.2025
SS21-4819-133	Level 17 Masterplan	A	17.09.2025
SS21-4819-500	Landscape Maintenance Plan	A	17.09.2025
SS21-4819-501	Landscape Details	A	17.09.2025
SS21-4819-502	Landscape Details	A	17.09.2025
SS21-4819-503	Landscape Planting Matrix Details	A	17.09.2025
SS21-4819-601	Landscape Sections	A	17.09.2025
SS21-4819-602	Landscape Sections	A	17.09.2025
SS21-4819-603	Landscape Sections	A	17.09.2025
SS21-4819-604	Landscape Sections	A	17.09.2025

CONSOLIDATED INSTRUMENT

SS21-4819-605	Landscape Sections	A	17.09.2025
SS21-4819-606	Landscape Sections	A	17.09.2025

- A3. Consistent with the requirements in this consent, the Planning Secretary may make written directions to the Applicant in relation to:
- (a) the content of any strategy, study, system, plan, program, review, audit, notification, report or correspondence submitted under or otherwise made in relation to this consent, including those that are required to be, and have been, approved by the Planning Secretary; and
 - (b) the implementation of any actions or measures contained in any such document referred to in condition A3(a) above.
- A4. The conditions of this consent and directions of the Planning Secretary prevail to the extent of any inconsistency, ambiguity or conflict between them and a document listed in condition A2(c) or **Error! Reference source not found.** In the event of an inconsistency, ambiguity or conflict between any of the documents listed in condition A2(c) and **Error! Reference source not found.**, the most recent document prevails to the extent of the inconsistency, ambiguity or conflict.
- A5. The conditions of this consent and directions of the Planning Secretary prevail to the extent of any inconsistency, ambiguity or conflict between them and the conditions of development consent SSD 31576372.

LEGAL NOTICES

- A6. Any advice or notice to the consent authority must be served on the Planning Secretary.

PLANNING SECRETARY AS MODERATOR

- A7. In the event of a dispute between the Applicant and a public authority, in relation to an applicable requirement in this approval or relevant matter relating to the Development, either party may refer the matter to the Planning Secretary for resolution.

MODIFICATION OF DEVELOPMENT CONSENT SSD 31576972

- A8. Pursuant to Section 4.17(1)(b) and (5) of the *Environmental Planning and Assessment Act 1979*, development consent SSD 8784 (as modified) is modified in accordance with **Schedule 3**. The Applicant must deliver a notice of modification to the Planning Secretary that complies with section 67 of the *Environmental Planning and Assessment Regulation 2021* within six months of the date of this determination. The notice must set out the modifications to conditions in SSD 31576972 that are listed in **Schedule 3** of this consent.

APPLICABILITY OF GUIDELINES

- A9. References in the conditions of this consent to any guideline, protocol, Australian Standard or policy are to such guidelines, protocols, Standards or policies in the form they are in as at the date of this consent.
- A10. Notwithstanding condition A9, consistent with the conditions of this consent and without altering any limits or criteria in this consent, the Planning Secretary may, when issuing directions under this consent in respect of ongoing monitoring and management obligations, require compliance with an updated or revised version of such a guideline, protocol, Standard or policy, or a replacement of them.

EVIDENCE OF CONSULTATION

- A11. Where conditions of this consent require consultation with an identified party, the Applicant must:
- (a) consult with the relevant party prior to submitting the subject document to the Planning Secretary for approval; and
 - (b) provide details of the consultation undertaken including:
 - (i) the outcome of that consultation, matters resolved and unresolved; and
 - (ii) details of any disagreement remaining between the party consulted and the Applicant and how the Applicant has addressed the matters not resolved.

STRUCTURAL ADEQUACY

- A12. All new buildings and structures, and any alterations or additions to existing buildings and structures, that are part of the development, must be constructed in accordance with the relevant requirements of the National Construction Code (NCC).

Notes:

Under Part 6 of the EP&A Act, the Applicant is required to obtain construction and occupation certificates for the proposed building works

CONSOLIDATED INSTRUMENT

The Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021 sets out the requirements for the certification of the development.

OPERATION OF PLANT AND EQUIPMENT

A13. All plant and equipment used on site, or to monitor the performance of the development must be:

- (a) maintained in a proper and efficient condition; and
- (b) operated in a proper and efficient manner.

MONITORING AND ENVIRONMENTAL AUDITS

A14. Any condition of this consent that requires the carrying out of monitoring or an environmental audit, whether directly or by way of a plan, strategy or program, is taken to be a condition requiring monitoring or an environmental audit under Division 9.4 of Part 9 of the EP&A Act. This includes conditions in respect of incident notification, reporting and response, non-compliance notification and independent environmental auditing.

Note: *For the purposes of this condition, as set out in the EP&A Act, "monitoring" is monitoring of the development to provide data on compliance with the consent or on the environmental impact of the development, and an "environmental audit" is a periodic or particular documented evaluation of the development to provide information on compliance with the consent or the environmental management or impact of the development.*

COMPLIANCE

A15. The Applicant must ensure that all of its employees, contractors (and their sub-contractors) are made aware of, and are instructed to comply with, the conditions of this consent relevant to activities they carry out in respect of the development

REVISION OF STRATEGIES, PLANS AND PROGRAMS

A16. Within three months of:

- (a) the submission of a compliance report under this consent;
- (b) the submission of an incident report under this consent;
- (c) the submission of an Independent Audit under this consent;
- (d) the approval of any modification of the conditions of this consent (excluding modifications made under section 4.55(1) of the EP&A Act); or
- (e) the issue of a direction of the Planning Secretary under this consent which requires a review,

the strategies, plans and programs required under this consent must be reviewed, and the Department must be notified in writing that a review is being carried out.

A17. If necessary, to either improve the environmental performance of the development, cater for a modification or comply with a direction, the strategies, plans and programs required under this consent must be revised, to the satisfaction of the Planning Secretary. Where revisions are required, the revised document must be submitted to the Planning Secretary for approval within six weeks of the review.

Note: *This is to ensure strategies, plans and programs are updated on a regular basis and to incorporate any recommended measures to improve the environmental performance of the development.*

COMPLIANCE REPORTING

A18. Compliance Reports of the project must be carried out in accordance with the Compliance Reporting Requirements outlined in the Compliance Reporting Post Approval Requirements.

A19. Compliance Reports must be submitted to the Department in accordance with the timeframes set out in the Compliance Reporting Post Approval Requirements, unless otherwise agreed to by the Planning Secretary.

A20. The Applicant must make each Compliance Report publicly available 60 days after submitting it to the Planning Secretary, unless otherwise agreed by the Planning Secretary.

A21. Notwithstanding the requirements of the Compliance Reporting Post Approval Requirements, the Planning Secretary may approve a request for ongoing annual operational compliance reports to be ceased, where it has been demonstrated to the Planning Secretary's satisfaction that an operational compliance report has demonstrated operational compliance.

INDEPENDENT ENVIRONMENTAL AUDIT

A22. Independent Audits of the development must be conducted and carried out in accordance with the Independent Audit Post Approval Requirements.

A23. Proposed independent auditors must be agreed to in writing by the Planning Secretary prior to the commencement of an Independent Audit.

CONSOLIDATED INSTRUMENT

- A24. The Planning Secretary may require the initial and subsequent Independent Audits to be undertaken at different times to those specified above, upon giving at least 4 weeks' notice (or timing) to the Applicant of the date upon which the audit must be commenced.
- A25. In accordance with the specific requirements in the Independent Audit Post Approval Requirements, the Applicant must:
- (a) review and respond to each Independent Audit Report prepared under this consent;
 - (b) submit the response to the Planning Secretary; and
 - (c) make each Independent Audit Report, and response to it, publicly available 60 days after submission to the Planning Secretary.
- A26. Independent Audit Reports and the Applicant's response to audit findings must be submitted to the Planning Secretary within 2 months of undertaking the independent audit site inspection as outlined in the Independent Audit Post Approvals Requirements unless otherwise agreed by the Planning Secretary.
- A27. Notwithstanding the requirements of the Independent Audit Post Approvals Requirements, the Planning Secretary may approve a request for ongoing independent operational audits to be ceased, where it has been demonstrated to the Planning Secretary's satisfaction that independent operational audits have demonstrated operational compliance.

SYDNEY METRO CORRIDOR PROTECTION GENERAL CONDITIONS

- A28. Any conditions or other requirements imposed by Sydney Metro as part of its approval/endorsement of any documents provided by the Applicant to Sydney Metro in accordance with these conditions of consent must also be complied with by the Applicant when implementing any approved/endorsed documents, plans, reports during the construction and operation of the development (as applicable).
- A29. Where a condition of consent requires Sydney Metro endorsement or approval, the Certifier must not issue a Construction Certificate or Occupation Certificate, as the case may be, until written confirmation has been received from those entities that the particular condition has been complied with. The issuing of staged Construction Certificates by the Certifier dealing with specific works and compliance conditions can only occur subject to written confirmation from Sydney Metro.
- A30. All reasonable Sydney Metro costs associated with review of plans, designs and legal must be borne by the Applicant.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - INSPECTIONS

- A31. At any time during the construction of the development, Sydney Metro and persons authorised by that entity may give reasonable notice to the Applicant or the Applicant's principal contractor that Sydney Metro or persons authorised by that entity seek to:
- (a) inspect the development site and all works and structures that may impact on the rail corridor, including at specified "hold points" in the construction of the development; and
 - (b) attend on-site meetings with the Applicant and its contractors;
- to enable Sydney Metro to determine whether the development has been or is being constructed and maintained in accordance with all approved plans and this development consent.

CONSOLIDATED INSTRUMENT

PART B – PRIOR TO THE ISSUE OF CONSTRUCTION CERTIFICATE

DESIGN EXCELLENCE AND INTEGRITY

- B1. The architectural design team comprising Turner Studio is to have direct involvement in the design documentation, contract documentation and construction stages of the project.
- B2. The architectural design team is to have full access to the site, following safety induction, and is to be authorised by the Applicant to respond directly to the consent authority where information or clarification is required in the resolution of any design issues throughout the procurement and construction stages, and the final occupancy of the development.
- B3. The architectural design team is not to be changed without prior written notice and approval of the Planning Secretary.
- B4. To ensure the scheme retains, or is an improvement upon, the approved design excellence qualities, the Applicant must notify the Planning Secretary of any proposed modifications to the approved architectural drawings.
- B5. The Planning Secretary is to determine whether any proposed modifications to the approved architectural drawings require review by the Key Sites and TOD Assessments Team, GANSW and/or the State Design Review Panel (SDRP). For clarity, this condition relates to design excellence and integrity and does not negate the need to modify the development consent in accordance with the EP&A Act (if necessary).

DESIGN AMENDMENTS FOR WASTE COLLECTION VEHICLES

- B6. Prior to the issue of the relevant Construction Certificate, the Applicant must provide written evidence to the Planning Secretary that prepare and submit to the satisfaction of Council has reviewed the final design drawings and details for the basement levels demonstrating heavy rigid vehicles (HRV) can be accommodated and that all of the requirements in Council's submission dated 16 May 2025 are satisfied.

MATERIALS AND FINISHES

- B7. Prior to the issue of the relevant Construction Certificate, the Applicant must prepare and submit to the satisfaction of the Planning Secretary details of final materials and finishes to ensure the design excellence objectives of the project are met. The details must include:
- (a) specifications and digital sample boards for all external finishes, colours and glazing including annotated drawings and computer-generated imagery of their application; and
 - (b) detailed architectural drawings of the facade details, including glazing specification and sun shading devices.

MAXIMUM BUILDING HEIGHTS

- B8. Prior to the issue of the Construction Certificate for Above Ground Works, the Applicant must submit to the satisfaction of the Certifier details confirming the maximum height of the buildings do not exceed the following, including plant and lift overruns, but excluding communication devices, antennas, satellite dishes, masts, flagpoles, chimneys, flues and the like.

Building	Maximum height
A	RL 108.28
B	RL 145.08
C	RL 143.92
D	RL 110.44
E	RL 143.06

GROSS FLOOR AREA CERTIFICATION

- B9. Prior to the issue of the Construction Certificate, the Applicant must submit to the satisfaction of the Certifier details confirming the gross floor area of the development does not exceed 11,216m².

Note: The amount of GFA above is in relation to this application. Refer to Schedule 3 (amending conditions to SSD-31576972) in relation to total site GFA.

LONG SERVICE LEVY

- B10. Prior to the issue of the Construction Certificate, the Applicant must submit to the satisfaction of the Certifier details confirming payment of a Long Service Levy. For further information on the current levy rate and methods of payment, contact the Long Service Levy Payments Corporation Helpline on 131 441.

CONSOLIDATED INSTRUMENT

DEVELOPER CONTRIBUTIONS – LOCAL CONTRIBUTIONS

- B11. Prior to the issue of the Construction Certificate or the issue of any subdivision certificate, whichever occurs first, the Applicant must obtain evidence of receipt from Council confirming the monetary contribution for the development pursuant to the provisions of City of Parramatta (Outside CBD) Development Contributions Plan 2021 (Amendment 1). The amount payable, including how the contribution will be indexed, must be obtained from Council.
- B12. A copy of the receipt for payment of contributions must be submitted to the Certifier with the first Construction Certificate or subdivision certificate, whichever occurs first.

DEVELOPER CONTRIBUTIONS – HOUSING AND PRODUCTIVITY CONTRIBUTIONS

- B13. Prior to the issue of the Construction Certificate or the issue of any subdivision certificate, whichever occurs first, the Applicant must obtain evidence of receipt confirming the Housing and Productivity Contribution (HPC) set out in the table below has been made:

Housing and Productivity Contribution	Amount
Housing and productivity contribution (base component)	\$407,005.22
Total housing and productivity contribution	\$407,005.22

- B14. At the time of payment, the amount of the HPC is to be adjusted in accordance with the *Environmental Planning and Assessment (Housing and Productivity Contributions) Order 2024* (HPC Order).
- B15. The HPC may be made wholly or partly as a non-monetary contribution (apart from any transport project component) if the Minister administering the EP&A Act 1979 agrees.
- B16. The HPC is not required to be made to the extent that a planning agreement excludes the application of Subdivision 4 of Division 7.1 of the EP&A Act 1979 to the development, or the HPC Order exempts the development from the contribution.

Note: The contribution amount is subject to indexation in accordance with the *Environmental Planning and Assessment (Housing and Productivity Contributions) Order 2024* at the time of payment. A request for assessment of the adjusted amount and instructions on how to make a payment can be made by contacting hpc.enquiry@planning.nsw.gov.au.

STRUCTURAL DETAILS

- B17. Prior to the issue of a Construction Certificate, the Applicant must submit to the Certifier detailed structural drawings for the Development and a Report prepared by a suitably qualified and experienced professional engineer demonstrating that the structural drawings comply with:
- (a) relevant clauses of the NCC; and
 - (b) this development consent.

EXTERNAL WALLS AND CLADDING

- B18. The external walls of all buildings including additions to existing buildings must comply with the relevant requirements of the NCC.
- B19. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier documented evidence that the products and systems proposed for use or used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the requirements of the NCC. The Applicant must provide a copy of the documentation to the Planning Secretary for information.

ACCESS AND FACILITIES FOR PEOPLE WITH DISABILITIES

- B20. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier details prepared by a suitably qualified professional demonstrating that the buildings and external elements around the buildings has been designed and will be constructed to provide access and facilities for people with a disability in accordance with the NCC and Disability (Access to Premises – Buildings) Standards 2010.

MECHANICAL VENTILATION

- B21. The premises must be ventilated in accordance with the NCC and applicable Australian Standards.
- B22. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier details that any mechanical ventilation and/or air conditioning system for the Development complies with

CONSOLIDATED INSTRUMENT

the NCC and applicable Australian Standards, prepared by a suitably qualified professional engineer and certified in accordance with relevant provisions of the NCC, to ensure adequate levels of health and amenity to the occupants of the building and to ensure environment protection.

REFLECTIVITY

- B23. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier a report/documentation demonstrating that external treatments, materials and finishes of the development do not cause adverse or excessive glare.

SITE STABILITY AND CONSTRUCTION WORK

- B24. Prior to the issue of the Construction Certificate, the Applicant must submit to the satisfaction of the Certifier a report obtained from a suitably qualified and experienced professional engineer/s, which includes the following:
- (a) geotechnical details which confirm the suitability and stability of the site for the development;
 - (b) relevant design and construction requirements to be implemented to ensure the stability and adequacy of the development and adjacent land;
 - (c) details of the proposed methods of excavation and support for the adjoining land (including any public place) and buildings;
 - (d) details to demonstrate that the proposed methods of support and construction are suitable for the site and will not result in any damage to the adjoining premises, buildings or any public place, as a result of the works and any associated vibration;
 - (e) the adjoining land and buildings located upon the adjoining land must be adequately supported at all times throughout building work; and
 - (f) details of written approvals that have been obtained from the owners of the adjoining land to install any ground or rock anchors underneath the adjoining premises (including any public roadway or public place).

CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN

- B25. Prior to the issue of the relevant Construction Certificate, the Applicant must submit a report prepared by a suitably qualified professional to the Certifier demonstrating that the design of the development has incorporated the Crime Prevention Through Environmental Design Assessment (CPTED) management and mitigation measures included within the CPTED report prepared by Think Planners dated 27 June 2024.

ECOLOGICALLY SUSTAINABLE DEVELOPMENT

- B26. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier evidence demonstrating the development incorporates all design, construction and operation measures as identified in the Sustainability Report prepared by Northrop dated 8 July 2024.
- B27. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier evidence demonstrating that the development will achieve a minimum 5 Star Green rating (and target a 6 Star Green rating where reasonable and feasible).

MECHANICAL PLANT NOISE MITIGATION

- B28. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier details of noise mitigation measures for all mechanical plant (as detailed on relevant Construction Certificate drawings) and certification from an appropriately qualified acoustic engineer and/or consultant that the proposed measures will achieve compliance with the Noise Policy for Industry (EPA, 2017) and other guidelines applicable to the development.

COMPLIANCE WITH ACOUSTIC ASSESSMENT

- B29. Prior to the issue of the relevant Construction Certificate, the Applicant must submit a report prepared by a suitably qualified acoustic engineer and/or consultant to the Certifier demonstrating that the design of the development has incorporated all performance parameters, requirements, engineering assumptions and recommendations contained in the Acoustic Review of DA Modification prepared by Acoustic Logic dated 27 March 2024.

WIND MITIGATION MEASURES

- B30. Prior to the issue of the first Construction Certificate for Above Ground Works, the Applicant must submit evidence to the Certifier demonstrating that the design of the development has incorporated the wind mitigation measures contained within the document titled Pedestrian Wind Environment Study prepared by Windtech dated 28 March 2024. Evidence provided must include information from a suitably qualified engineer that the wind mitigation measures remain valid for the development's design and confirm no wind tunnel testing is required to be undertaken. Should a suitably qualified engineer determine wind tunnel testing is required, it must be undertaken and evidence from the suitably qualified engineer must be submitted to the Certifier demonstrating the design of the development incorporates any additional wind mitigation measures resulting.

CAR AND MOTORCYCLE PARKING

- B31. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier plans demonstrating compliance with the following traffic and parking requirements:
- (a) on site car parking spaces provided as follows:
 - (i) 474 residential spaces, comprising 433 market apartment spaces and 41 affordable housing spaces;
 - (ii) 68 visitor spaces;
 - (iii) 12 commercial spaces;
 - (iv) 4 motorcycle spaces;
 - (v) 1 carshare space; and
 - (vi) 1 car wash bay;
 - (b) allocation of 1 accessible car parking space for each adaptable dwelling;
 - (c) all vehicles must enter and leave the subject site in a forward direction without interfering with any on-street parking space;
 - (d) all vehicles are to be wholly contained on site before being required to stop;
 - (e) parking associated with the development (including driveways, grades, turn paths, sight distance requirements, aisle widths, aisle lengths and parking bay dimensions) must be in accordance with the applicable Australian Standards;
 - (f) appropriate pedestrian advisory signs must be provided at the egress from parking areas;
 - (g) electric vehicle charging infrastructure in accordance with the NCC;
 - (h) all works/regulatory signposting associated with the development must be at no cost to the relevant roads authority; and
 - (i) the swept path of the longest vehicle (including garbage trucks) entering and exiting the Site, as well as manoeuvrability through the subject Site, must be in accordance with AUSTROADS, AS2890.1-2004 and AS2890.2-2018 (or their latest versions).

BICYCLE PARKING

- B32. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier plans demonstrating compliance with the following:
- (a) a minimum of 479 residential bicycle parking spaces;
 - (b) a minimum of 48 residential visitor bicycle parking spaces;
 - (c) a minimum of 8 non-residential bicycle parking spaces; and
 - (d) end-of-trip facilities for non-residential floor space comprising minimum 4 showers and 8 lockers.
- B33. The layout, design and security of bicycle facilities must comply with applicable Australian Standards.

LANDSCAPING

- B34. Prior to the issue of the relevant Construction Certificate, the Applicant must prepare and submit to the satisfaction of the Planning Secretary, detailed Landscape Plans. The plans must be generally consistent with the Landscape Plans and Report prepared by Site Image listed in Condition A2 and include:
- (a) landscaping that interprets or reflects the local/cultural setting, including as part of the overall Connection to Country response including patternation of materials and motifs;
 - (b) details of tree planting, including pot sizes;
 - (c) details of soil depth and volume;
 - (d) detail of the location, species, maturity and height at maturity of plants to be planted on-site;
 - (e) demonstrate adequate drainage and watering systems for the planters;
 - (f) details of plant maintenance and watering including the first 36 months after the issue of an occupation certificate;
 - (g) a commitment to replace plants with the same species at the same maturity if any plant loss occurs within the maintenance period; and
 - (h) detail of all landscape materials, surfaces and finishes.

PUBLIC DOMAIN PLANS

- B35. Prior to the issue of the relevant Construction Certificate, the Applicant must prepare and submit to the satisfaction of Council detailed updated Public Domain Plans. A copy of Council's approval for the Public Domain Plans is to be provided to the Planning Secretary. The plans must incorporate:
- (a) undergrounding of power lines along Ray Road and Beecroft Road;

CONSOLIDATED INSTRUMENT

- (b) street trees along Beecroft Road in consultation with Transport for NSW (**TfNSW**) with consideration given to Council's preferred species of *Lophostemon confertus* rather than *Tristanopsis laurina*;
- (c) street trees along Ray Road to be *Waterhousia floribunda* rather than *Callistemon King Park Special*;
- (d) street trees planters at minimum 8-10m intervals;
- (e) reconstruction of all existing footpaths, kerbs and gutters along the Ray Road and Beecroft Road frontages;
- (f) footpaths must be 1.8m wide and constructed to Council's standards;
- (g) footpaths must be built at the property boundaries enabling as wide a verge as possible;
- (h) green power pillars, were required, must be installed with a c/c distance of 100mm from the property boundary; and
- (i) street furniture must be provided as per Parramatta Public Domain Guidelines.

STORMWATER MANAGEMENT SYSTEM

- B36. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier an operational stormwater management system for the development. The system must:
- (a) be designed by a suitably qualified and experienced professional engineer(s);
 - (b) be generally in accordance with the conceptual design in the EIS and RtS;
 - (c) be in accordance with Council's Guidelines and Specifications;
 - (d) be in accordance with applicable Australian Standards;
 - (e) ensure that the system capacity has been designed in accordance with *Australian Rainfall and Runoff* (Geoscience Australia, 2019) and *Managing Urban Stormwater: Council Handbook* (EPA, 1997) guidelines; and
 - (f) reduce annual average pollution export loads from the development in line with the following environmental targets:
 - (i) 90% reduction in the annual average load of gross pollutants;
 - (ii) 85% reduction in the annual average load of total suspended solids;
 - (iii) 65% reduction in the annual average load of total phosphorous; and
 - (iv) 45% reduction in the annual average load of total nitrogen.
- B37. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier amended plans for the onsite detention tank achieving the following outcomes:
- (a) relocation of the detention tank so it is not directly below habitable rooms or located directly adjacent to habitable rooms; and
 - (b) incorporate access grates to Council's standards comprising 900mm x 900mm ventilation and access openings spaced not more than 4 metres apart across the roof of the tank.

STORMWATER QUALITY

- B38. Prior to the issue of the relevant Construction Certificate, detailed stormwater management plans consistent with the Civil Engineering Package prepared by Northrop dated 5 July 2024 and with written evidence of endorsement by Council must be submitted to the certifying authority where it relates to existing or proposed public/street drainage.

FLOOD MITIGATION

- B39. Prior to the issue of the relevant Construction Certificate, the Applicant must demonstrate to the satisfaction of the Certifier that the development will manage flood risk within and in the vicinity of the site in accordance with the recommendations of the Flood Study and Impact Assessment prepared by Northrop dated 10 July 2024.
- B40. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier construction drawings and specifications for flood gates at the driveway along Ray Road and at the Building A lobby along Ray Road.

ADAPTABLE UNITS

- B41. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier a report from a suitably qualified consultant confirming that any adaptable dwellings specified in the approved plans or supporting documentation comply with the applicable Australian Standards.

BASIX CERTIFICATION

- B42. The development's BASIX commitments must be implemented and all BASIX commitments thereafter maintained in accordance with BASIX Certificate No. 1312666M_04 and any updated certificate issued if amendments are made. The BASIX Certificate must be submitted to the Certifier with all commitments clearly shown on the Construction Certificate plans.

WASTE MANAGEMENT

- B43. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the Certifier a report prepared by a suitably qualified professional that:
- (a) the development can accommodate the pickup of all waste within the building;
 - (b) all waste vehicles can enter and leave the building in a forward direction;
 - (c) the development has incorporated separate dedicated waste storage areas, to facilitate the separation of residential waste and recycling from commercial material; and
 - (d) the development has been designed and constructed in accordance with Council's waste guidelines and specifications including Appendix 2 – Waste Management of Parramatta Development Control Plan 2023.

SYDNEY WATER CONDITION – BUILDING PLAN APPROVAL

- B44. The plans must be approved Sydney Water prior to demolition, excavation or construction works commencing. This allows Sydney Water to determine if sewer, water or stormwater mains or easements will be affected by any part of the development. Any amendments to plans will require re-approval. Sydney Water recommends the developer apply for a Building Plan Approval early to reduce unnecessary delays for further referrals or development timeframes.

SYDNEY WATER CONDITION – TRADE WASTEWATER REQUIREMENTS

- B45. If the development generates trade wastewater, the property owner must submit an application requesting permission to discharge trade wastewater to Sydney Water's sewerage system. Sydney Water approval for this permit must be obtained before any trade wastewater generating land use can commence.
- B46. A Boundary Trap is required for all developments that discharge trade wastewater where arrestors and special units are installed for trade wastewater pre-treatment.

SYDNEY WATER CONDITION – BACKFLOW PREVENTION REQUIREMENTS

- B47. All developments connected to Sydney Water's supply must install a testable Backflow Prevention Containment Device appropriate to the development's hazard rating. Developments with a high or medium hazard rating must have the backflow prevention containment device tested annually. Developments identified as having a low hazard rating must install a non-testable device as a minimum.
- B48. Prior to installing a backflow prevention device, a hydraulic consultant or licenced plumber with backflow accreditation must:
- (a) confirm water pressure available to the site meets the development's water pressure and flow requirements; and
 - (b) complete a site assessment to confirm the hazard rating of the development and its services.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - ENGINEERING

- B49. All excavation and construction works are to be undertaken in accordance with the details, methodology, advice, undertakings, measures and recommendations detailed in the following documents:
- (a) Geotechnical Investigation Report prepared by PSM, dated 27 May 2022;
 - (b) Structural Drawings prepared by JSBC Consulting, as listed below:
 - (i) Shoring and Early Works Plan, Revision A, dated 16 October 2024;
 - (ii) Shoring Elevations - Sheet 1, Revision, dated 16 October 2024;
 - (iii) Shoring Infrastructure Sections – Sheet 1, dated 16 October 2024;
 - (iv) Shoring Infrastructure Sections – Sheet 2, dated 16 October 2024;
 - (v) Shoring Infrastructure Sections – Sheet 3, dated 16 October 2024;
 - (vi) Shoring Infrastructure Sections – Sheet 4, dated 16 October 2024; and
 - (vii) Shoring Adjacent to Beecroft Road Construction Methodology, dated 16 October 2024;
 - (c) 242-244 Beecroft Road, Epping – Sydney Metro Tunnel Structural Assessment, Revision F, prepared by Hyve Designs, dated 31 March 2025;
 - (d) Risk Assessment, prepared by ArchArtifex, dated 18 November 2024;
 - (e) Noise and Vibration Impact Assessment, Revision 4, prepared by Acoustic Logic dated 6 November 2024;
 - (f) Electrolysis Risk Assessment Report, Revision 1, prepared by Corrosion Control Engineering, dated 1 November 2024;
 - (g) Finite Element Analysis for Sydney Metro 242-244 Beecroft Road, Epping, prepared by EI Australia, dated 19 November 2024;
 - (h) Geotechnical Letter for Endorsement of Additional Basement, prepared by EI Australia, dated 19 November 2024; and

- (i) Structural Sydney Metro Report – Endorsement for Additional Basement, prepared by JSBC Consulting, dated 19 November 2024,

subject to any amendments to those documents required by Sydney Metro in accordance with this consent.

- B50. The Certifier must not issue a Construction Certificate for the development until the Certifier has confirmed which documents (including the versions of those documents) apply to the development and the Certifier has confirmed in writing to Sydney Metro that the construction drawings and specifications comply with those documents. The Certifier must not issue a Construction Certificate for the development until written confirmation has been received from Sydney Metro that this condition has been satisfied.

Prior to the commencement of works, the Certifier must provide written verification to Sydney Metro that this condition has been complied with.

- B51. The Certifier must not issue a Construction Certificate for the development unless the Applicant has submitted to Sydney Metro, and Sydney Metro has provided written approval of, the following items:

- (a) final design construction drawings with details of internal props, foundations of bracing system for the Construction Certificate;
- (b) latest instrumentation and monitoring plan with trigger levels and actions; and
- (c) a risk assessment in accordance with Section 7.3 of Sydney Metro Underground Corridor Protection Technical Guidelines and/or Sydney Metro at Grade and Elevated Sections Corridor Protection Guidelines, including the consideration of likelihood, consequences, mitigation measures and risk levels.

Prior to the commencement of works, the Certifier must provide written verification to Sydney Metro that this condition has been complied with.

SYDNEY METRO CORRIDOR PROTECTION CONDITION – RAIL CORRIDOR

- B52. All structures must be designed, constructed and maintained so as to allow for the future operation and demolition of any part of the development without damaging or otherwise interfering with the Northwest rail corridor or rail operations. Where any part of the development is to be retained because its demolition would damage or otherwise interfere with the Northwest rail corridor or rail operations, that part of the development must have a minimum design life of 100 years.

SYDNEY METRO CORRIDOR PROTECTION CONDITION – SURVEY AND SERVICES

- B53. Prior to the issue of a Construction Certificate:

- (a) the Applicant must provide Sydney Metro with an accurate survey of the development and its location relative to the rail corridor boundary and any rail infrastructure. The survey is to be undertaken by a registered surveyor, to the satisfaction of Sydney Metro; and
- (b) a registered surveyor shall peg-out the common property boundary between the development site and the rail corridor and any Sydney Metro easements to ensure that there is no encroachment by the development. A copy of the survey report indicating the location of pegs must be provided to Sydney Metro prior to the commencement of works.

- B54. Prior to the issue of a Construction Certificate, the Applicant must undertake a services search to establish the existence and location of any rail services and provide the results of the search to Sydney Metro. A services search must be based on current and not expired information and include information obtained through the Dial Before You Dig service. Persons performing the service search shall use equipment that will not have any impact on rail services and signalling. Should rail services be identified within the development site, the Applicant must discuss with Sydney Metro whether the services are to be relocated or incorporated within the development site.

SYDNEY METRO CORRIDOR PROTECTION CONDITION – NOISE AND VIBRATION

- B55. The development must:

- (a) comply with *State Environmental Planning Policy (Transport and Infrastructure) 2021*, the NSW Department of Planning & Environment's document titled "Development Near Rail Corridors and Busy Roads - Interim Guideline" (2008) and the Sydney Metro Underground Corridor Protection Guidelines;
- (b) be designed, constructed and maintained so as to avoid damage or other interference which may occur as a result of air-borne noise, ground-borne noise and vibration effects that may emanate from the rail corridor during rail construction and operations; and
- (c) not have any noise or vibration impacts on the rail corridor or rail infrastructure.

- B56. The Applicant must incorporate as part of the development all the measures recommended in the acoustic assessment report Noise and Vibration Impact Assessment, prepared by Acoustic Logic, Revision 4, dated 6 November 2024. A copy of the acoustic assessment report is to be provided to the Certifier and Council prior to the relevant Construction Certificate being issued by the Certifier. A report prepared by a suitably qualified acoustic engineer and/or consultant must be submitted to the Certifier which demonstrates the recommendations of the

acoustic assessment report are incorporated in the construction drawings and documentation prior to issuing the relevant Construction Certificate for the development.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - ELECTROLYSIS

- B57. Prior to the issue of a Construction Certificate, the Applicant is to engage an electrolysis expert to prepare a report on the electrolysis risk to the development from stray currents. The Applicant must incorporate in the development all the measures recommended in the electrolysis report to control that risk. A copy of the electrolysis report is to be provided to the Certifier with the application for a Construction Certificate.
- B58. Prior to issuing a Construction Certificate for the development, the electrolysis expert must provide documentary evidence to the Certifier that the recommendations of the electrolysis report are incorporated in the construction drawings and documentation.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - DESIGN

- B59. The roots and foliage of trees planted beside the rail corridor as part of the development must not impact on the rail corridor or rail operations. A final landscaping and planting plan demonstrating measures to ensure compliance with this condition must be prepared to the satisfaction of Sydney Metro. The Certifier must not issue a Construction Certificate for the development until written confirmation has been received from Sydney Metro that this condition has been satisfied.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - CONSTRUCTION

- B60. No work is permitted within the rail corridor, or any easements which benefit Sydney Metro, at any time, unless the prior approval of, or an Agreement with, Sydney Metro has been obtained by the Applicant. The Certifier must not issue a Construction Certificate for the development until written confirmation has been received from Sydney Metro that this condition has been satisfied.
- B61. No rock anchors, rock bolts, ground anchors or rock ties, piles, foundations, rock pillars, transfer structures, basement walls, slabs, columns, beams, cut rock faces, are to be installed in the rail corridor, Sydney Metro property or easements. The Certifier must not issue a Construction Certificate for the development until it has received written confirmation from Sydney Metro that this condition has been satisfied.
- B62. Prior to the issuing of a Construction Certificate, the following information must be submitted to Sydney Metro for review and endorsement:
- (a) machinery to be used during excavation/construction; and
 - (b) demolition, excavation and construction methodology and staging.
- The Certifier must not issue a Construction Certificate for the development until it has received written confirmation from Sydney Metro that this condition has been satisfied
- B63. If required by Sydney Metro, prior to the issue of a Construction Certificate a Risk Assessment/Management Plan and detailed Safe Work Method Statements for the proposed works are to be submitted to Sydney Metro for review and endorsement regarding impacts on the rail corridor. The Certifier must not issue a Construction Certificate for the development until written confirmation has been received from Sydney Metro that this condition has been satisfied.
- B64. If required by Sydney Metro, a tunnel monitoring plan (including instrumentation and the monitoring regime during excavation and construction phases) is to be submitted to Sydney Metro for review and endorsement prior to the issuing of a Construction Certificate. The Certifier must not issue a Construction Certificate until written confirmation has been received from Sydney Metro that this condition has been satisfied.
- B65. Prior to the issuing of a Construction Certificate, the Applicant must submit to Sydney Metro a plan showing all craneage and other aerial operations for the development and must comply with all Sydney Metro requirements. If required by Sydney Metro, the Applicant must amend the plan showing all craneage and other aerial operations to comply with all Sydney Metro requirements. The Certifier must not issue a Construction Certificate for the development until written confirmation has been received from Sydney Metro that this condition has been satisfied.
- B66. If required by Sydney Metro, prior to the issue of a Construction Certificate the Applicant is to contact Sydney Metro's Corridor Protection Team to determine the need for public liability insurance cover and the level of insurance required. If insurance cover is deemed necessary, the Applicant must obtain insurance for the sum determined by Sydney Metro and such insurance shall not contain any exclusion in relation to works on or near the rail corridor or rail infrastructure and must be maintained for the period specified by Sydney Metro. Prior to issuing a Construction Certificate for the development, the Certifier must witness written proof of any insurance required by Sydney Metro in accordance with this condition, including the written advice of Sydney Metro to the Applicant regarding the level of insurance required.
- B67. If required by Sydney Metro, prior to the issue of a Construction Certificate the Applicant must contact the Sydney Metro Corridor Protection Team to determine the need for the lodgement of a bond or bank guarantee for the duration of the works and the sum of any required bond or bank guarantee. Prior to issuing a Construction

CONSOLIDATED INSTRUMENT

Certificate for the development, the Certifier must witness written confirmation from Sydney Metro that the Applicant has lodged any bond or bank guarantee required by this condition.

- B68. Prior to the issue of a Construction Certificate, the Applicant must prepare and provide to Sydney Metro for review and endorsement a hydrologic assessment report demonstrating that any dewatering during construction will not have any adverse settlement impacts on the rail corridor. The Certifier must not issue a Construction Certificate until this report has been endorsed by Sydney Metro in writing.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - DRAINAGE

- B69. The Applicant must ensure that all drainage from the development is adequately disposed of and managed and must ensure that no drainage is discharged into the railway corridor unless prior written approval has been obtained from Sydney Metro. The Certifier must not issue a Construction Certificate or Occupation Certificate for the development unless this condition has been satisfied.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - DOCUMENTATION

- B70. Copies of any certificates, drawings, approvals or documents endorsed by, given to or issued by Sydney Metro must be provided to the Planning Secretary for information prior to the issue of any Construction Certificate.

STRATUM SUBDIVISION PLANS

- B71. Prior to the issue of the relevant Construction Certificate, draft stratum subdivision plans must be prepared to the satisfaction of the Certifier.

CONSOLIDATED INSTRUMENT

PART C – PRIOR TO THE COMMENCEMENT OF WORKS

NOTICE OF COMMENCEMENT

- C1. The Department, Council and TfNSW (including Sydney Metro) must be notified in writing of the dates of commencement of physical work and operation at least 48 hours before those dates.
- C2. If the construction or operation of the development is to be staged, the Department, Council and TfNSW (including Sydney Metro) must be notified in writing at least 48 hours before the commencement of each stage, of the date of commencement and the development to be carried out in that stage.

ACCESS TO INFORMATION

- C3. At least 48 hours before the commencement of construction until the completion of all works under this consent, or such other time as agreed by the Planning Secretary, the Applicant must:
- (a) make the following information and documents (as they are obtained or approved) publicly available on its website:
 - (i) the documents referred to in Condition A2 of this consent;
 - (ii) all current statutory approvals for the development;
 - (iii) all approved strategies, plans and programs required under the conditions of this consent;
 - (iv) regular reporting on the environmental performance of the development in accordance with the reporting arrangements in any plans or programs approved under the conditions of this consent;
 - (v) a comprehensive summary of the monitoring results of the development, reported in accordance with the specifications in any conditions of this consent, or any approved plans and programs;
 - (vi) a summary of the current stage and progress of the development;
 - (vii) contact details to enquire about the development or to make a complaint;
 - (viii) a complaints register, updated monthly;
 - (ix) audit reports prepared as part of any independent environmental audit of the development and the Applicant's response to the recommendations in any audit report; and
 - (x) any other matter required by the Planning Secretary;
 - (b) keep such information up to date, to the satisfaction of the Planning Secretary; and
 - (c) address any other matter relating to compliance with the terms of this consent or requested by the Planning Secretary.

SURVEY CERTIFICATE

- C4. While building work is being carried out, a registered surveyor is to measure and mark the positions of the following and provide them to the principal certifier:
- (a) all footings/ foundations; and
 - (b) at other stages of construction - any marks that are required by the Principal Certifier.
- C5. Prior to the commencement of works, the Applicant must submit to the satisfaction of the Certifier a Registered Surveyor's certificate detailing the setting out of the proposed building on the site, including the relationship of the set out building to property boundaries.

PROTECTION OF PUBLIC INFRASTRUCTURE AND STREET TREES

- C6. Prior to the commencement of works, the Applicant must:
- (a) consult with the relevant owner and provider of services that are likely to be affected by the development to make suitable arrangements for access to, diversion, protection and support of the affected infrastructure;
 - (b) prepare a dilapidation report identifying the condition of all public infrastructure in the vicinity of the site (including roads, gutters and footpaths) and submit a copy of the dilapidation report to the Certifier, Planning Secretary and Council; and
 - (c) ensure all street trees directly outside the site not approved for removal are retained and protected in accordance with the applicable Australian Standards.

UTILITIES AND SERVICES

- C7. Prior to the construction of any utility works associated with the development, the Applicant must obtain relevant approvals from service providers. Any costs in the relocation, adjustment or support of services are the responsibility of the Applicant.

CONSOLIDATED INSTRUMENT

- C8. Prior to the commencement of works written advice must be obtained from the electricity supply authority, an approved telecommunications carrier and an approved gas carrier (where relevant) stating that satisfactory arrangements have been made to ensure provisions of adequate services.

BEFORE YOU DIG SERVICE

- C9. Prior to the commencement of any excavation on or near the site, the Applicant must submit to the satisfaction of the Certifier written confirmation from Before You Dig Australia that the proposed excavation will not conflict with any underground utility services.

DEMOLITION

- C10. Demolition work must comply with *Australian Standard AS 2601-2001 The demolition of structures* (or its latest version). The work plans required by AS 2601-2001 must be accompanied by a written statement from a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the statement of compliance must be submitted to the Certifier before the commencement of works.

COMMUNITY COMMUNICATION STRATEGY

- C11. Before the commencement of construction, the Applicant must prepare a Community Communication Strategy (CCS) for the development to provide mechanisms to facilitate communication between the Applicant, the relevant Council and the community (including adjoining affected landowners and businesses, and others directly impacted by the development), during the design and construction of the development and for a minimum of 12 months following the issue of the final Occupation Certificate for the development.
- C12. The CCS for the development must:
- (a) identify people to be consulted during the design and construction phases;
 - (b) set out procedures and mechanisms for the regular distribution of accessible information about or relevant to the development;
 - (c) provide for the formation of community-based forums, if required, that focus on key environmental management issues for the development;
 - (d) set out procedures and mechanisms:
 - (i) through which the community can discuss or provide feedback to the Applicant;
 - (ii) through which the Applicant will respond to enquiries or feedback from the community; and
 - (iii) to resolve any issues and mediate any disputes that may arise in relation to construction and operation of the development, including disputes regarding rectification or compensation; and
 - (e) include any requirements which may relate to specific issues for example traffic, noise and vibration, soil and water, vegetation removal and landscaping and contamination.
- C13. The CCS must be submitted to the Planning Secretary for approval no later than one month before the commencement of construction. A copy of the approved CCS must be provided to Council.
- C14. Construction must not commence until the CCS has been approved by the Planning Secretary, or within another timeframe agreed with the Planning Secretary.
- C15. The CCS, as approved by the Planning Secretary, must be implemented for a minimum of 12 months following the completion of construction.

PRE-CONSTRUCTION DILAPIDATION REPORTS

- C16. Prior to the commencement of any construction, the Applicant must submit to the satisfaction of the Certifier a Pre-Construction Dilapidation Report, prepared by a suitably qualified person.
- C17. The Pre-Construction Dilapidation Report is to detail the current structural condition of all the following items within the 'zone of influence', as defined in the Pre-Construction Dilapidation Report:
- (a) adjoining buildings; and
 - (b) infrastructure and roads, including:
 - (i) public domain site frontages;
 - (ii) footpaths;
 - (iii) kerbs and gutters;
 - (iv) driveway crossovers and laybacks;
 - (v) kerb ramps;
 - (vi) road carriageway;
 - (vii) street trees and plantings;
 - (viii) parking restrictions and traffic signs; and

- (ix) all other existing infrastructure along the street.

Any entry into private land is subject to the consent of the owner of the land and any inspection of buildings on privately affected land must include details of the whole building where only part of the building may fall within the 'zone of influence'. A copy of the report is to be forwarded to the Planning Secretary and each of the affected property owners.

- C18. In the event that access for undertaking a Pre-Construction Dilapidation Report is denied by an adjoining owner, the Applicant must demonstrate, in writing, to the satisfaction of the Certifier that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the report and that these steps have failed.
- C19. Any damage to the public way including trees, footpaths, kerbs, gutters, road carriageway and the like must be made safe and functional by the Applicant to the satisfaction of the public authority responsible for the public way.

CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN

- C20. Prior to the commencement of any earthworks or construction, a Construction Environmental Management Plan (**CEMP**) must be submitted to the Certifier. The CEMP must address, but not be limited to, the following matters where relevant:
 - (a) Details of:
 - (i) hours of work;
 - (ii) 24 hour contact details of the site manager;
 - (iii) community consultation (including consultation under the CCS) and complaint handling procedures;
 - (iv) traffic management;
 - (v) noise and vibration management, prepared by a suitably qualified person;
 - (vi) management of dust and odour to protect the health and amenity of the neighbourhood;
 - (vii) stormwater control and discharge, including measures to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site;
 - (viii) contamination management, including any unexpected contamination finds protocol;
 - (ix) waste management;
 - (x) compliance with the social impact management measures as detailed within the Social Impact Assessment prepared by Hill PDA Consulting, dated 28 June 2024;
 - (xi) external lighting in compliance with applicable Australian Standards; and
 - (xii) flora and fauna management;
 - (b) Construction Pedestrian and Traffic Management Sub-Plan (see condition C21);
 - (c) Construction Noise and Vibration Management Sub-Plan (see condition C23);
 - (d) Air Quality Management Sub-Plan (see condition C24);
 - (e) Construction Waste Management Sub-Plan (see condition C27);
 - (f) Construction Soil and Water Management Sub-Plan (see condition C28);
 - (g) an unexpected finds protocol for contamination and associated communications procedure;
 - (h) an unexpected finds protocol for Aboriginal and non-Aboriginal heritage and associated communications procedure; and
 - (i) waste classification (for materials to be removed) and validation (for materials to remain) to be undertaken to confirm the contamination status in these areas of the site.

CONSTRUCTION PEDESTRIAN AND TRAFFIC MANAGEMENT PLAN SUB-PLAN

- C21. Prior to the commencement of any earthworks or construction, the Applicant must submit to the satisfaction of the Certifier a final Construction Pedestrian and Traffic Management Plan Sub-Plan (**CPTMP**), prepared in consultation with TfNSW and Council. The CPTMP needs to specify matters including, but not limited to, the following:
 - (a) a description of the development;
 - (b) details of compliance with the requirements of condition B11 of SSD-6893460;
 - (c) location of any proposed work zone(s);
 - (d) details of crane arrangements including location of any crane(s) and crane movement plan;
 - (e) haulage routes;
 - (f) proposed construction hours;
 - (g) predicted number of construction vehicle movements, detail of vehicle types and demonstrate that proposed construction vehicle movements can work within the context of road changes in the surrounding area, noting that construction vehicle movements are to be minimised during peak periods;

- (h) construction vehicle access arrangements;
 - (i) construction program and construction methodology, including any construction staging;
 - (j) a detailed plan of any proposed hoarding and/or scaffolding;
 - (k) measures to avoid construction worker vehicle movements within the precinct;
 - (l) consultation strategy for liaison with surrounding stakeholders, including other developments under construction;
 - (m) identify any potential impacts to general traffic, cyclists, pedestrians, bus services within the vicinity of the site from construction vehicles during the construction of the proposed works. Proposed mitigation measures must be clearly identified and included in the CPTMP; and
 - (n) identify the cumulative construction activities of the development and other projects within or around the development site. Proposed measures to minimise the cumulative impacts on the surrounding road network must be clearly identified and included in the CPTMP.
- C22. Independent road safety audits are to be undertaken for all stages of further design development involving road operations and traffic issues and cognisant of all road users. Any issues identified by the audits must be closed out in consultation with Sydney Coordination Office, TfNSW RMS and/or Council to the satisfaction of the relevant roads authorities.

CONSTRUCTION NOISE AND VIBRATION MANAGEMENT SUB-PLAN

- C23. Prior to the commencement of any earthworks or construction, the Applicant must submit to the satisfaction of the Certifier a Construction Noise and Vibration Management Sub-Plan (**CNVMP**) for the development. The Sub-Plan must include:
- (a) identification of the specific activities that will be carried out and associated noise sources at the site;
 - (b) identification of all potentially affected sensitive residential receiver locations;
 - (c) quantification of the rating background noise level (**RBL**) for sensitive receivers, as part of the Sub-Plan, or as undertaken in the EIS;
 - (d) the construction noise, ground-borne noise and vibration objectives derived from an application of the EPA Interim Construction Noise Guideline (**ICNG**), as reflected in conditions of approval;
 - (e) prediction and assessment of potential noise, ground-borne noise (as relevant) and vibration levels from the proposed construction methods expected at sensitive receiver premises against the objectives identified in the ICNG and conditions of approval;
 - (f) where objectives are predicted to be exceeded, an analysis of feasible and reasonable noise mitigation measures that can be implemented to reduce construction noise and vibration impacts;
 - (g) description of management methods and procedures, and specific noise mitigation treatments/measures that can be implemented to control noise and vibration during construction;
 - (h) where objectives cannot be met, additional measures including, but not necessarily limited to, the following must be considered and implemented where practicable; reduce hours of construction, the provision of respite from noise/vibration intensive activities, acoustic barriers/enclosures, alternative excavation methods or other negotiated outcomes with the affected community;
 - (i) where night-time noise management levels cannot be satisfied, a report must be submitted to the Planning Secretary outlining the mitigation measures applied, the noise levels achieved and justification that the outcome is consistent with best practice;
 - (j) measures to identify non-conformances with the requirements of the Sub-Plan, and procedures to implement corrective and preventative action;
 - (k) suitable contractual arrangements to ensure that all site personnel, including sub-contractors, are required to adhere to the noise management provisions in the Sub-Plan;
 - (l) procedures for notifying residents of construction activities that are likely to affect their noise and vibration amenity;
 - (m) measures to monitor noise performance and respond to complaints;
 - (n) measures to reduce noise related impacts associated with offsite vehicle movements on nearby access and egress routes from the site;
 - (o) procedures to allow for regular professional acoustic input to construction activities and planning; and
 - (p) effective site induction, and ongoing training and awareness measures for personnel (e.g., toolbox talks, meetings etc).

AIR QUALITY MANAGEMENT SUB-PLAN

- C24. Prior to the commencement of any earthworks or construction, the Applicant must submit to the satisfaction of the Certifier an Air Quality Management Sub-Plan (**AQMP**) for the development. The Sub-Plan must include, as a minimum, the following elements:
- (a) be prepared by a suitably qualified and experienced expert in accordance with the EPA's Approved Methods for the Modelling and Assessment of Air Pollutants in NSW (the Approved Methods);
 - (b) relevant environmental criteria to be used in the day-to-day management of dust and volatile organic compounds (VOC/odour);
 - (c) dust and VOCs/odour management strategies consisting of:
 - (i) objectives and targets;
 - (ii) risk assessment;
 - (iii) suppression improvement plan;
 - (iv) monitoring requirements including assigning responsibility (for all employees and contractors);
 - (v) communication strategy; and
 - (vi) system and performance review for continuous improvements.
- C25. The AQMP must detail management practices to be implemented for all dust and VOC/odour sources at the site. The AQMP must also detail the dust, odour, VOC and semi-volatile organic compounds (SVOC) monitoring program (e.g. frequency, duration and method of monitoring) to be undertaken for the project.
- C26. The Applicant must also develop and implement an appropriate comprehensive Reactive Air Quality and Odour Management Plan which will incorporate an Ambient Air Monitoring Program and Reactive Management Strategy to ensure that the assessment criteria are met during the works.

CONSTRUCTION WASTE MANAGEMENT SUB-PLAN

- C27. Prior to the commencement of any earthworks or construction, the Applicant must submit to the satisfaction of the Certifier a Construction Waste Management Sub-Plan for the development. The Sub-Plan must include, as a minimum, the following elements:
- (a) require that all waste generated during the project is assessed, classified, and managed in accordance with the EPA's "Waste Classification Guidelines Part 1: Classifying Waste";
 - (b) demonstrate that an appropriate area will be provided for the storage of bins and recycling containers and all waste and recyclable material generated by the works;
 - (c) procedures for minimising the movement of waste material around the site and double handling;
 - (d) waste (including litter, debris or other matter) is not caused or permitted to enter any waterways;
 - (e) any vehicle used to transport waste or excavation spoil from the site is covered before leaving the premises;
 - (f) the wheels of any vehicle, trailer or mobilised plant leaving the site are cleaned of debris prior to leaving the premises;
 - (g) details in relation to the transport of waste material around the site (on-site) and from the site, including (at a minimum):
 - (i) a traffic plan showing transport routes within the site;
 - (ii) a commitment to retain waste transport details for the life of the project to demonstrate compliance with the *Protection of the Environment Operations Act 1997*; and
 - (iii) the name and address of each licensed facility that will receive waste from the site (if appropriate).

CONSTRUCTION SOIL AND WATER MANAGEMENT PLAN SUB-PLAN

- C28. Prior to the commencement of any earthworks or construction, the Applicant must submit to the satisfaction of the Certifier a Construction Soil and Water Management Sub-Plan which must be prepared by a suitably qualified expert, in consultation with Council and address, but not be limited to the following:
- (a) describe all erosion and sediment controls to be implemented during construction;
 - (b) provide a plan of how all construction works will be managed in a wet-weather event (i.e., storage of equipment, stabilisation of the Site);
 - (c) detail all off-Site flows from the Site; and
 - (d) describe the measures that must be implemented to manage stormwater and flood flows for small and large sized events, including, but not limited to 1 in 1-year ARI, 1 in 5-year ARI and 1 in 100-year ARI.

CONSTRUCTION PARKING

- C29. Prior to the commencement of any earthworks or construction, the Applicant must submit to the satisfaction of the Certifier evidence that sufficient off-street parking has been provided for heavy vehicles and for site personnel

CONSOLIDATED INSTRUMENT

(where required), to ensure that construction traffic associated with the development does not utilise on-street parking or public parking facilities.

COMPLIANCE

- C30. Prior to the commencement of any earthworks or construction, the Applicant must ensure that all of its employees, contractors (and their sub-contractors) are made aware of, and are instructed to comply with, the conditions of this consent relevant to activities they carry out in respect of the development.

BARRICADE PERMIT

- C31. Where construction/building works require the use of a public place including a road or footpath, approval under section 138 of the *Roads Act 1993* for a Barricade Permit is to be obtained from the relevant authority prior to the commencement of work. Details of the barricade construction, area of enclosure and period of work are required to be submitted to the satisfaction of the relevant authority.

HOARDING

- C32. An application under section 138 of the *Roads Act 1993* is to be made to the relevant road authority to erect a hoarding and/or scaffolding in a public road (if required) and such application is to include:
- (a) architectural, construction and structural details of the design as well as any proposed artwork; and
 - (b) structural certification prepared and signed by an appropriately qualified practising structural engineer.

OUTDOOR LIGHTING

- C33. Prior to commencement of any lighting installation, evidence must be submitted to the satisfaction of the Certifier that all outdoor lighting within the site has been designed to comply with *AS 1158.3.1:2020 Lighting for roads and public spaces Pedestrian area (Category P) lighting – Performance and design requirements* (or its latest version) and *AS 4282-2019 Control of the obtrusive effects of outdoor lighting* (or its latest version).

REMEDIATION

- C34. Prior to the issue of any Construction Certificate for aboveground works, the Applicant must submit to the satisfaction of the Certifier, evidence of compliance with the Detailed Site Investigation prepared by EI Australia dated 29 June 2022, including preparation and implementation of the Remediation Action Plan and the preparation of the Site Validation Report.

UNEXPECTED FINDS PROTOCOL

- C35. Prior to the commencement of any earthworks or remediation works, the Applicant must submit to the satisfaction of the Certifier an Unexpected Finds Protocol which has been reviewed and endorsed by an EPA accredited site auditor. The protocol must outline contingency measures and the procedures to be followed in the event unexpected finds of contaminated material are encountered during works.

CONSOLIDATED INSTRUMENT

PART D – DURING CONSTRUCTION

APPROVED PLANS TO BE ON-SITE

- D1. A copy of the approved and certified plans, specifications and documents incorporating conditions of approval and certification must be always kept on the Site and must be readily available for perusal by any officer of the Department, Council or the Certifier.

SITE NOTICE

- D2. A site notice(s) must be erected in a prominent position on the site for the purposes of informing the public of project details including, but not limited to the details of the Development's Builder, Certifier and Structural Engineer. The notice(s) is to satisfy all, but not be limited to, the following requirements:
- (a) state the name, address and telephone number of the principal certifier for the work;
 - (b) state the name of the principal contractor (if any), its address and 24-hour contact phone number for any inquiries, including construction/noise complaints;
 - (c) state the approved hours of work;
 - (d) state that unauthorised entry to the work site is prohibited;
 - (e) the minimum dimensions of the notice are to measure 841 mm x 594 mm (A1) with any text on the notice to be a minimum of 30-point type size;
 - (f) the notice is to be durable and weatherproof and is to be displayed throughout the works period; and
 - (g) the notice(s) is to be mounted at eye level on the perimeter hoardings/fencing.

HOURS OF CONSTRUCTION

- D3. Construction, including the delivery of materials or machinery to and from the site as well as the removal of excavated material (including loading of trucks), may only be carried out between the following hours:
- (a) between 7am and 5pm, Mondays to Fridays inclusive; and
 - (b) between 8am and 5pm, Saturdays.
- D4. No work may be carried out on Sundays or public holidays.
- D5. Activities may be undertaken outside of the hours specified in conditions D3 and D4 if required:
- (a) by the Police or a public authority for the delivery or removal of vehicles, plant or materials, or the installation and dismantling of plant or equipment; or
 - (b) in an emergency to avoid the loss of life, damage to property or to prevent environmental harm.
- D6. Notification of activities undertaken in the circumstances in Condition D5 must be given to affected residents before undertaking the activities or as soon as is practical afterwards.
- D7. Rock breaking, rock hammering, sheet piling, pile driving, and similar activities may only be carried out between the following hours:
- (a) 9am to 12pm, Monday to Friday;
 - (b) 2pm to 5pm, Monday to Friday; and
 - (c) 9am to 12pm, Saturday.

INCIDENT NOTIFICATION, REPORTING AND RESPONSE

- D8. The Department must be notified via the NSW planning portal (Major Projects) immediately after the Applicant becomes aware of an incident. The notification must identify the development (including the development application number and the name of the development if it has one) and set out the location and nature of the incident.
- D9. Subsequent notification must be given and reports submitted in accordance with the requirements set out in **Error! Reference source not found..**

NON-COMPLIANCE NOTIFICATION

- D10. The Department must be notified via the NSW planning portal (Major Projects) within seven days after the Applicant becomes aware of any non-compliance. The Certifier must also notify the Department via the NSW planning portal (Major Projects) within seven days after they identify any non-compliance.
- D11. The notification must identify the development and the application number for it, set out the condition of consent that the development is non-compliant with, the way in which it does not comply and the reasons for the non-compliance (if known) and what actions have been, or will be, undertaken to address the non-compliance.
- D12. A non-compliance which has been notified as an incident does not need to also be notified as a non-compliance.

SAFework REQUIREMENTS

- D13. To protect the safety of work personnel and the public, the work site must be adequately secured to prevent access by unauthorised personnel, and work must be conducted at all times in accordance with relevant SafeWork requirements.

IMPLEMENTATION OF MANAGEMENT PLANS

- D14. The Applicant must implement and comply with the requirements of any management plan or sub-plan required under this consent. To the extent of any inconsistency between a condition of consent and a management plan or sub-plan, the condition of consent prevails.

CONSTRUCTION NOISE LIMITS

- D15. The development must be constructed having regard to the construction noise management levels detailed in the Interim Construction Noise Guideline (DECC, 2009). All feasible and reasonable noise mitigation measures must be implemented and any activities that could exceed the construction noise management levels must be identified and managed in accordance with the management and mitigation measures identified in the approved CNVMP.
- D16. The Applicant must ensure construction vehicles (including concrete agitator trucks) do not arrive at the subject site or surrounding residential precincts outside of the construction hours of work outlined under this consent.
- D17. The Applicant must implement, where practicable and without compromising the safety of construction staff or members of the public, audible movement alarms of a type that would minimise noise impacts on surrounding noise sensitive receivers.
- D18. The Applicant must ensure that any work generating high noise impact (i.e. work exceeding a NML of LAeq 75dBA) as measured at any sensitive receiver is only undertaken in continuous blocks of no more than 3 hours, with at least a 1 hour respite between each block of work generating high noise impact, where the location of the work is likely to impact the same receivers. For the purposes of this condition 'continuous' includes any period during which there is less than 1 hour respite between ceasing and recommencing any of the work the subject of this condition.
- D19. Any noise generated during construction of the development must not be offensive noise within the meaning of the *Protection of the Environment Operations Act 1997* or exceed approved noise limits for the Site.

VIBRATION CRITERIA

- D20. Vibration caused by construction at any residence or structure outside the Site must be limited to:
- (a) for structural damage, the latest version of DIN 4150-3 (1992-02) *Structural Vibration - Effects of Vibration on Structures* (German Institute for Standardisation, 1999); and
 - (b) for human exposure to vibration, the evaluation criteria set out in the *Environmental Noise Management Assessing Vibration: A Technical Guideline* (Department of Environment and Conservation, 2006) (as may be updated or replaced from time to time).
- D21. Vibratory compactors must not be used within 30 metres of residential developments or heritage items unless vibration monitoring confirms compliance with the vibration criteria specified above. These limits apply unless otherwise outlined in the project specific CNVMP required by this consent.

AIR QUALITY

- D22. The Applicant must take all reasonable steps to minimise dust generated during all works authorised by this consent. During construction, the Applicant must ensure that:
- (a) exposed surfaces and stockpiles are suppressed by regular watering;
 - (b) all trucks entering or leaving the site with loads have their loads covered;
 - (c) trucks associated with the development do not track dirt onto the public road network;
 - (d) public roads used by these trucks are kept clean; and
 - (e) land stabilisation works are carried out progressively on site to minimise exposed surfaces.

SHORING AND ADEQUACY OF ADJOINING PROPERTY

- D23. If the development involves an excavation that extends below the level of the base of the footings of a building, structure or work on adjoining land (including any structure or work within a road or rail corridor), the person having the benefit of the development consent must, at the person's own expense:
- (a) protect and support the building, structure or work from possible damage from the excavation, and
 - (b) where necessary, underpin the building, structure or work to prevent any such damage.

This condition does not apply if the person having the benefit of the development consent owns the adjoining land or the owner of the adjoining land has given consent in writing to this condition not applying.

CONSOLIDATED INSTRUMENT

EROSION AND SEDIMENT CONTROL

- D24. All erosion and sediment control measures must be effectively implemented and maintained at or above design capacity for the duration of the construction works and until such time as all ground disturbed by the works have been stabilised and rehabilitated so that it no longer acts as a source of sediment. Erosion and sediment control techniques, as a minimum, are to be in accordance with the publication *Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004)* commonly referred to as the 'Blue Book' and must comply with the CSWMSP.

CUT AND FILL

- D25. While building work is being carried out, the Certifier must be satisfied all soil removed from or imported to the Site is managed in accordance with the following requirements:
- (a) all excavated material removed from the Site must be classified in accordance with the EPA's Waste Classification Guidelines before it is disposed of at an approved waste management facility; and
 - (b) the classification and the volume of material removed must be reported to the Certifier.
- D26. All fill material imported to the Site must be Virgin Excavated Natural Material as defined in Schedule 1 of the *Protection of the Environment Operations Act 1997* or a material identified as being subject to a resource recovery exemption by the EPA.

DISPOSAL OF SEEPAGE AND STORMWATER

- D27. Any seepage or rainwater collected on-site during construction or groundwater must not be pumped to the street stormwater system unless separate prior approval is given in writing by the EPA in accordance with the *Protection of the Environment Operations Act 1997*.
- D28. Adequate provisions must be made to collect and discharge stormwater drainage during construction of the development. Prior written approval of Council must be obtained to connect or discharge site stormwater to Council's stormwater drainage system or street gutter.
- D29. A separate written approval from Council is required to be obtained in relation to any proposed discharge of groundwater into Council's drainage system external to the site, in accordance with the requirements of section 138 of the *Roads Act 1993*.

ASBESTOS

- D30. The Applicant must ensure that any asbestos encountered on site is monitored, handled, transported and disposed of by appropriately qualified and licensed contractors in accordance with the requirements of SafeWork NSW and relevant guidelines, including:
- (a) Work Health and Safety Regulation 2017;
 - (b) SafeWork NSW Code of Practice – How to Manage and Control Asbestos in the Workplace December 2022;
 - (c) SafeWork NSW Code of Practice – How to Safely Remove Asbestos December 2022; and
 - (d) *Protection of the Environment Operations (Waste) Regulation 2014*.

CONSTRUCTION TRAFFIC

- D31. All construction vehicles are to be contained wholly within the Site, except if located in an approved on-street work zone, and vehicles must enter the Site before stopping.

ROAD OCCUPANCY LICENCE

- D32. A Road Occupancy Licence must be obtained from the relevant transport authority for any works that impact on traffic flows during construction activities.

NO OBSTRUCTION OF PUBLIC WAY

- D33. The public way must not be obstructed by any materials, vehicles, refuse skips or the like, under any circumstances. Non-compliance with this requirement may result in the issue of a notice by the Planning Secretary to stop all work on Site.

CONTACT TELEPHONE NUMBER

- D34. The Applicant must ensure that the 24-hour contact telephone number is continually attended by a person with authority over the works for the duration of construction.

COVERING OF LOADS

- D35. All vehicles involved in the excavation and / or demolition process and departing from the Site with materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

VEHICLE CLEANSING

- D36. Prior to the commencement of work, suitable measures are to be implemented to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the Site. It is an offence to allow, permit or cause materials to pollute or be placed in a position from which they may pollute waters.

UNCOVERING RELICS OR ABORIGINAL OBJECTS

- D37. All works must cease immediately if a relic or Aboriginal object is unexpectedly discovered. The Applicant must notify the Heritage Council of NSW in respect of a relic and notify the Planning Secretary and the Heritage Council of NSW in respect of an Aboriginal object. Building work may recommence at a time confirmed by either the Heritage Council of NSW or the Planning Secretary.
- D38. In condition D37:
- (a) "relic" means any deposit, artefact, object or material evidence that:
 - (i) relates to the settlement of the area that comprises New South Wales, not being Aboriginal settlement, and
 - (ii) is of State or local heritage significance; and
 - (b) "Aboriginal object" means any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises New South Wales, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction and includes Aboriginal remains.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - SUPERVISION

- D39. Unless advised by Sydney Metro in writing, all excavation, shoring and piling works within 25m of the rail corridor are to be supervised by a geotechnical engineer experienced with such excavation projects and who holds current professional indemnity insurance.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - CONSULTATION

- D40. The Applicant must ensure that at all times they have a representative (which has been notified to Sydney Metro in writing), who:
- (a) oversees the carrying out of the Applicant's obligations under the conditions of this consent and in accordance with correspondence issued by Sydney Metro;
 - (b) acts as the authorised representative of the Applicant; and
 - (c) is available (or has a delegate notified in writing to Sydney Metro that is available) on a 7 day a week basis to liaise with the representative of Sydney Metro as notified to the Applicant.
- D41. Without in any way limited the operation of any other condition of this consent, the Applicant must, during demolition, excavation and construction works, consult in good faith with Sydney Metro in relation to the carrying out of the development works and must respond or provide documentation as soon as practicable to any queries raised by Sydney Metro in relation to the works.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - DRAINAGE

- D42. The Applicant must ensure that all existing and future drainage works on the development site will be directed into the appropriate local council or approved drainage system.
- D43. The Applicant must ensure that during works no water collects on or near the railway corridor. Should water be allowed to pond adjacent to rail infrastructure facilities and service is interrupted, the Applicant shall be liable for any Sydney Metro expenditure involved with restoring or maintaining alternative services.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - INSPECTIONS

- D44. If required by Sydney Metro, the Applicant must give Sydney Metro written notice at least 5 business days before any of the following events occur within 25 metres of the rail corridor:
- (a) site investigations;
 - (b) foundation, pile and anchor set out;
 - (c) set out of any other structures below ground surface level or structures which will transfer any load or bearing;
 - (d) foundation, pile and anchor excavation;
 - (e) other excavation;
 - (f) surveying of foundation, pile and anchor excavation and surveying of as-built excavations;
 - (g) other concreting; or
 - (h) any other event that Sydney Metro has notified to the Applicant in writing,

CONSOLIDATED INSTRUMENT

so that Sydney Metro may inspect the carrying out or completion of those works on the development site.

- D45. If required by Sydney Metro, prior to the commencement of works or at any time during the excavation and construction period deemed necessary by Sydney Metro, a joint inspection of the rail infrastructure and property in the vicinity of the development is to be carried out by representatives from Sydney Metro and the Applicant and a dilapidation survey prepared. The dilapidation survey(s) will establish the extent of any existing damage and enable any deterioration during construction to be observed and rectified at the Applicant's cost. The submission of a detailed dilapidation report by the Applicant for review and approval by Sydney Metro will be required within 10 days following the undertaking of any joint inspection, unless otherwise notified by Sydney Metro in writing.

CONSOLIDATED INSTRUMENT

PART E – PRIOR TO OCCUPATION OR COMMENCEMENT OF USE

OCCUPATION CERTIFICATE

- E1. The Applicant must obtain an Occupation Certificate from the Certifier prior to commencement of occupation or use of the whole or any part of a new building or, an altered portion or, an extension to an existing building.

AFFORDABLE HOUSING

- E2. Prior to the issue of an Occupation Certificate, evidence of the following shall be provided to the satisfaction of the Certifier and copies provided for the information of the Planning Secretary:
- (a) the existing covenant over the property for 5% of residential gross floor area to be used as affordable housing shall be deregistered;
 - (b) a new covenant shall be registered against the title of the property in accordance with Section 88E of the *Conveyancing Act 1919* to ensure:
 - (i) a minimum of 15% of the total gross floor area of the development is used for the purposes of affordable housing for at least 15 years from the date of issue of the Occupation Certificate, as defined by the EP&A Act and the *State Environmental Planning Policy (Housing) 2021*; and
 - (ii) the affordable housing is managed by a registered Community Housing Provider; and
 - (c) evidence of an agreement with a registered Community Housing Provider shall be provided to the Registrar of Community Housing including the name of the registered Community Housing Provider.

WORKS-AS-EXECUTED PLANS AND ANY OTHER DOCUMENTARY EVIDENCE

- E3. Prior to the issue of an Occupation Certificate, the Applicant must submit to the satisfaction of the Certifier works-as-executed drawings, signed by a registered surveyor, demonstrating that the stormwater drainage and finished ground levels have been constructed as approved.

The Certifier must provide a copy of the plans to the Planning Secretary and Council with the Occupation Certificate.

NOTIFICATION OF OCCUPATION

- E4. The Department must be notified in writing at least one month prior to the proposed occupation of the development.
- E5. If the occupation or use of the development is to be staged, the Department must be notified in writing at least one month before the commencement of the occupation of each stage, of the date of commencement of the occupation of the relevant stage.

GFA AND BUILDING HEIGHT CERTIFICATION

- E6. A Registered Surveyor is to certify that the development does not exceed the approved gross floor area and building height. Details must be provided to the Certifier demonstrating compliance with this condition prior to the issue of an Occupation Certificate.

EXTERNAL WALLS AND CLADDING FLAMMABILITY

- E7. Prior to any Occupation Certificate being issued, evidence must be submitted to the Certifier demonstrating all external walls of the new building, including cladding, comply with the relevant requirements of the NCC, consistent with the requirements of this consent.
- E8. The Applicant must provide a copy of the documentation to the Planning Secretary within seven days after the Certifier accepts it.

PROTECTION OF PUBLIC INFRASTRUCTURE

- E9. Unless the Applicant and the applicable authority agree otherwise, the Applicant must:
- (a) repair/reconstruct, or pay the full costs associated with repairing/reconstructing, any public infrastructure that is damaged by carrying out the development; and
 - (b) relocate, or pay the full costs associated with relocating any infrastructure that needs to be relocated as a result of the development.
- E10. Infrastructure includes, but is not limited to, ramps, footpaths, kerb and gutter, light poles, kerb inlet pits, service provider pits, street trees or any other infrastructure in the street footpath area.

MECHANICAL VENTILATION

- E11. Prior to occupation or commencement of use, the Applicant must provide evidence to the Certifier that the installation and performance of the mechanical ventilation systems complies with:
- (a) any conditions of this consent;

- (b) the NCC;
- (c) any applicable Australian Standards; and
- (d) any dispensation granted by Fire and Rescue NSW.

OPERATIONAL WASTE MANAGEMENT PLAN

- E12. Prior to the occupation or commencement of use, the Applicant must prepare an Operational Waste Management Plan for the development and submit it to the Certifier. The Operational Waste Management Plan must:
- (a) be prepared in consultation with Council;
 - (b) confirm the location of waste collection and establish appropriate routes to the collection point;
 - (c) provide confirmation of the engagement of a qualified private waste collection contractor;
 - (d) detail the type and quantity of waste to be generated during operation of the development;
 - (e) describe the handling, storage and disposal of all waste streams generated on site, consistent with the *Protection of the Environment Operations Act 1997*, *Protection of the Environment Operations (Waste) Regulation 2014* and the Waste Classification Guideline (EPA);
 - (f) detail the materials to be reused or recycled, either on or off site; and
 - (g) include the Management and Mitigation Measures included in the EIS.

FINAL INSPECTION OF WASTE STORAGE AREAS

- E13. Prior to the issue of any Occupation Certificate, a final inspection of the waste storage areas and associated management facilities must be undertaken by Council's waste management staff. This is to ensure compliance with Council's design specifications and that necessary arrangements are in place for domestic waste collection by Council and its domestic waste collection contractor.

DOMESTIC WASTE COLLECTION RISK ASSESSMENT

- E14. Prior to the issue of any Occupation Certificate, a risk assessment must be undertaken on site by Council's waste management staff. The time for the assessment must be arranged when clear unobstructed circulation in and out of the Site is available for Council's domestic waste contractor to perform a mock collection run at the site.

WASTE AND RECYCLING COLLECTION

- E15. Prior to the occupation or commencement of use, whichever is earlier, the building owner must ensure that there is a contract with a licensed contractor for the removal of all trade waste. No waste is to be placed on the public way e.g. the roadways, footpaths, plazas, and reserves at any time.

POST-CONSTRUCTION DILAPIDATION REPORT

- E16. Before the issue of any Occupation Certificate, a suitably qualified engineer must prepare a Post-Construction Dilapidation Report, to the satisfaction of the Certifier, detailing whether:
- (a) after comparing the Pre-Construction Dilapidation Report to the Post-Construction Dilapidation Report required under this condition, there has been any structural damage to any adjoining buildings, infrastructure or roads;
 - (b) where there has been structural damage to any adjoining buildings, infrastructure or roads, that it is a result of the building work approved under this development consent; and
 - (c) relevant authorities have confirmed that there is no adverse structural damage to their infrastructure and roads.
- E17. Before the issue of any Occupation Certificate, the Applicant is to provide a copy of the Post-Construction Dilapidation Report to the Planning Secretary and to the relevant adjoining property owner(s).
- E18. Any damage identified in the Post-Construction Dilapidation Report required by condition E16 must be fully rectified by the Applicant in accordance with the Council's standards prior to a Certificate of Completion being issued for Public Domain Works or before the final Occupation Certificate is issued for the development, whichever is the sooner.

ROAD DAMAGE

- E19. Prior to the occupation or commencement of the use, the cost of repairing any damage caused to Council or other public authority's assets in the vicinity of the Site as a result of construction works associated with the approved development is to be paid in full by the Applicant.

FIRE SAFETY CERTIFICATION

- E20. Prior to the issue of the any Occupation Certificate, a Fire Safety Certificate must be obtained for all the relevant Essential Fire or Other Safety Measures forming part of the works subject to the Occupation Certificate. A copy of the Fire Safety Certificate must be submitted to the relevant authority and Certifier and be prominently displayed in the building.

STRUCTURAL INSPECTION CERTIFICATE

- E21. Prior to the occupation or commencement of use of the relevant parts of any new or refurbished buildings, a Structural Inspection Certificate or a Compliance Certificate prepared by an experienced professional engineer must be submitted to the Certifier. A copy of the Certificate with an electronic set of final drawings must be submitted to the Planning Secretary and the Council after:
- (a) the Site has been periodically inspected and the Certifier is satisfied that the structural works is deemed to comply with the final design drawings; and
 - (b) the drawings listed on the Inspection Certificate have been checked with those listed on the final Design Certificate/s.

WARM WATER SYSTEMS AND COOLING SYSTEMS

- E22. The operation and maintenance of warm water systems and water-cooling systems (as defined under the *Public Health Act 2010*) must comply with the *Public Health Act 2010*, *Public Health Regulation 2022* the NSW Health Code of Practice for the Control of Legionnaires' Disease and applicable Australian Standards.

OUTDOOR LIGHTING

- E23. Prior to the occupation or commencement of use, the Applicant must submit evidence from a suitably qualified practitioner to the Certifier that demonstrates that installed lighting associated with the development achieves the objective of minimising light spillage to any adjoining or adjacent sensitive receivers and:
- (a) complies with the latest version of AS 4282-2019 - Control of the obtrusive effects of outdoor lighting (or its most recent version); and
 - (b) has been mounted, screened and directed in such a manner that it does not create a nuisance to surrounding properties or the public road network.

STORMWATER

- E24. Prior to the issue of any Occupation Certificate, the Applicant must submit a copy of the stormwater drainage works-as-executed (**WAE**) plans certified by a licensed surveyor to the Certifier, Planning Secretary and Council. The stormwater drainage WAE plans can be marked-up versions of the stormwater drainage design plans and must be prepared by a Practising Professional Engineer experienced in the design of stormwater drainage systems.
- E25. Prior to the issue of any Occupation Certificate, the Applicant must submit to the satisfaction of the Certifier a Stormwater Operational and Maintenance Plan (**SOMP**) to ensure the proposed stormwater quality measures remain effective. The SOMP must contain the following:
- (a) maintenance schedule of all stormwater quality treatment devices;
 - (b) record and reporting details;
 - (c) relevant contact information; and
 - (d) Work Health and Safety requirements.

SYDNEY WATER COMPLIANCE

- E26. Prior to the issue of any Occupation Certificate, the Applicant must submit to the satisfaction of the Certifier a Section 73 Compliance Certificate under the *Sydney Water Act 1994*, obtained from Sydney Water Corporation.

UTILITY PROVIDERS

- E27. Before the issue of any Occupation Certificate, the Applicant must ensure any adjustment or augmentation of any public utility services including gas, water, sewer, electricity, street lighting and telecommunications, required as a result of the development, is completed to the satisfaction of the relevant authority, with written confirmation from the relevant authority provided to the Certifier.

GREEN TRAVEL PLAN

- E28. Prior to the issue of any Occupation Certificate, the Applicant must prepare a Green Travel Plan (GTP) in consultation with TfNSW and submit it to development.sco@transport.nsw.gov.au for their endorsement. The GTP must be consistent with the framework and initiatives in Section 3.13 of the Transport Impact Assessment dated 2 July 2024 prepared by SCT Consulting. The GTP must consider, but not be limited to, the following matters:
- (a) the requirements of Section 6.1.2 of the Parramatta Development Control 2023;
 - (b) objectives and mode share targets (i.e., site and land use specific, measurable and achievable and timeframes for implementation) to define the direction and purpose of the GTP;
 - (c) specific tools and actions to help achieve the objectives and mode share targets;
 - (d) measures to promote and support the implementation of the plan, including financial and practical requirements, roles and responsibilities for relevant residents and employees involved in the implementation of the GTP;

CONSOLIDATED INSTRUMENT

- (e) quantification and analysis of resident and employee numbers on the Site and analysis of journey to work data to properly understand public transport and car parking demand and develop effective strategies in response, as well as help to inform service planning considerations;
- (f) consideration of a travel survey and workforce data analysis to inform likely travel patterns and resultant travel plan strategies to / from the Site;
- (g) strategies for promoting higher mode share targets for alternate transport use;
- (h) identification of a responsible party (or Committee) for the ongoing implementation of the Travel Plan and its initiatives;
- (i) confirmation of extent and nature of end of trip facilities and bike parking, including their location, and how they will be promoted to residents and employees;
- (j) encourages the use of carpooling through the implementation of a carpooling scheme for staff;
- (k) considers the potential for fleet bikes to be used for travel within the site and its surrounds;
- (l) identification of a communications strategy for conveying Travel Plan information to residents, staff and visitors;
- (m) consideration of car parking management strategies that may be required to encourage sustainable transport use / mode share targets (such as pricing, prioritisation for those that carpool, use of wait lists, etc);
- (n) a detailed action plan comprising specific tasks needed to complete the proposed actions, the person/s responsible for completion of the task, completion date and anticipated costs;
- (o) an implementation checklist to achieve the proposed initiatives;
- (p) alternative actions to undertake where targets are not achieved;
- (q) the establishment and composition of a steering group or committee of relevant internal and external stakeholders to inform future targets and the ongoing monitoring and revision of the GTP for five years; and
- (r) details regarding the methodology and monitoring/review program to measure the effectiveness of the objectives and mode share targets of the GTP, including the frequency of monitoring and the requirement for travel surveys to identify travel behaviours of users of the development.

E29. The GTP must be reviewed and updated annually in consultation with TfNSW and provide an Implementation Strategy that commits to specific management actions, including operational procedures to be implemented along with timeframes. The GTP (as reviewed and updated annually) must be implemented by the Applicant for the life of the development.

E30. The GTP must be made available to the Planning Secretary upon request.

LOADING AND SERVICING MANAGEMENT PLAN

E31. Prior to the issue of any Occupation Certificate, the Applicant must submit to the satisfaction of the Certifier a detailed Loading and Servicing Management Plan prepared in consultation with TfNSW. This Plan must ensure that any potential traffic and safety impacts associated with the car park and loading dock operation are mitigated. The Applicant must submit a copy of the final plan to TfNSW and the Planning Secretary. The Plan needs to specify, but not be limited to, the following:

- (a) details of the development's loading and servicing profile, including the forecast loading and servicing traffic volumes by vehicle size, frequency, time of day and duration of stay;
- (b) details of measures to manage any potential traffic and safety impacts of the loading dock operation; and
- (c) details of how vehicles larger than a 6.4m SRV delivering to the site must be managed.

E32. The Loading and Servicing Management must be implemented by the Applicant following the issue of the Occupation Certificate.

LANDSCAPE PRACTICAL COMPLETION REPORT

E33. Prior to the issue of any Occupation Certificate, the Applicant must submit to the satisfaction of the Certifier a Landscape Practical Completion Report prepared by the consultant responsible for the landscape design plan. The Report is to verify that all landscape works have been carried out generally in accordance with the comprehensive landscape design plan and specifications that were required to be included in documentation for a Construction Certificate application and is to verify that an effective maintenance program has been commenced.

STREET NUMBERING

E34. Prior to the issue of any Occupation Certificate, the Applicant must provide to the Certifier evidence that street numbers are clearly displayed at the ground level frontage of the building. If new street numbers or a change to street numbers is required, a separate application must be made to the relevant authority.

CONSOLIDATED INSTRUMENT

COMPLIANCE WITH BASIX CERTIFICATE

- E35. Prior to the issue of any Occupation Certificate, the Applicant must submit to the satisfaction of the Certifier evidence that all the commitments contained in the BASIX Certificate approved under this consent have been implemented.

REGISTRATION OF EASEMENTS

- E36. Prior to the issue of any Occupation Certificate, the Applicant must provide to the Certifier evidence that all matters required to be registered on title including easements required by this consent, approvals, and other consents have been lodged for registration or registered at the NSW Land Registry Services.
- E37. Easements under section 88A and/or restrictions or public positive covenants under section 88E of the *Conveyancing Act 1919* naming Council as the prescribed authority, which can only be revoked, varied or modified with the consent of Council, and which provides for public use and access to plazas and paths that are identified to be privately owned lands but publicly accessible, comprising the site through site link, must be registered on title prior to occupation or issue of Subdivision Certificate, whichever is earlier.

CREATION OF RESTRICTIONS/POSITIVE COVENANTS

- E38. Before an Occupation Certificate is issued, relevant restrictions/ positive covenants must be registered on the title of the subject site via dealing/ request document or Section 88B instrument associated with a plan for stormwater pumps and detention systems, water sensitive urban design elements and waste collection.

CARSHARE SPACES

- E39. Prior to the issue of an Occupation Certificate, a restriction is to be registered against the title of the property on which development is to be carried out, in accordance with section 88E of the *Conveyancing Act 1919*, requiring a minimum of one car parking space within the approved basement to be used for the exclusive use of carshare schemes.

MANAGEMENT PLAN OF THROUGH SITE LINK AND PUBLICLY ACCESSIBLE SPACES

- E40. Prior to the issue of any Occupation Certificate, the Applicant must prepare to the satisfaction of the certifier a final plan of management, and provide a copy to the Planning Secretary, for the on-going maintenance and management of the through-site link and publicly accessible spaces. The Plan must be prepared in consultation with Council, and must address:
- (a) maintenance standards, schedule and safety measures of publicly accessible spaces, including any water features and public art;
 - (b) safe pedestrian movements;
 - (c) hours of operation;
 - (d) programming, events and community use of the spaces;
 - (e) security measures;
 - (f) provision for future reviews and updates; and
 - (g) management of amenity impacts on occupants of the development.
- E41. The through site link plan of management referred to in condition E40 must be reviewed and revised from time to time in response to any reasonable direction of public authorities or Council to address public safety and amenity issues.

FLOOD EMERGENCY RESPONSE PLAN

- E42. Prior to the issue of the Occupation Certificate, the Applicant shall prepare a Flood Emergency Response Plan to the satisfaction of the Certifier. The Flood Emergency Response Plan shall be prepared in consultation with Council and in accordance with the recommendations contained within the document titled Flood Study and Impact Assessment, prepared by Northrop Engineering dated 10 July 2024.

SYDNEY WATER CONDITION – SECTION 73 COMPLIANCE CERTIFICATE

- E43. A Section 73 Compliance Certificate must be obtained from Sydney Water under Section 73 of the *Sydney Water Act 1994* before an Occupation or Subdivision Certificate is issued. The availability of water and wastewater services may require extensions, adjustments, or connections to mains. An early application for the Section 73 Certificate must be made as there may be assets to be built and this can take time. Applications can be made either directly to Sydney Water or through a Sydney Water accredited Water Servicing Coordinator.

SYDNEY METRO CORRIDOR PROTECTION CONDITION – NOISE AND VIBRATION

- E44. Prior to the issue of an Occupation Certificate, an acoustic assessment report must be prepared and submitted to the Certifying Authority, Council and Sydney Metro certifying that the completed development meets the requirements of:
- (a) *State Environmental Planning Policy (Transport and Infrastructure) 2021*;

CONSOLIDATED INSTRUMENT

- (b) the Department of Planning, Infrastructure and Environment's Development Assessment Guideline titled "Development Near Rail Corridors and Busy Roads - Interim Guidelines"; and
- (c) any other noise and vibration requirements imposed by this consent.

E45. The acoustic report must demonstrate testing of external and internal noise levels for the completed development and ensure that external noise levels are representative of the typical maximum levels that may occur at the development and internal noise levels meet the required dB(A) levels. Where it is found that internal noise levels are greater than the required dB(A) level, necessary corrective measures must be carried out to ensure that internal noise levels are compliant with the requirements of this consent.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - DOCUMENTATION

- E46. Prior to the issue of an Occupation Certificate, the Applicant is to submit as-built drawings to Sydney Metro and Council. The as-built drawings are to be endorsed by a registered surveyor confirming that there has been no encroachment into the rail corridor or Sydney Metro easements, unless agreed to by Sydney Metro in writing. The Certifier must not issue an Occupation Certificate until written confirmation has been received from Sydney Metro that this condition has been satisfied.
- E47. Copies of any certificates, drawings, approvals or documents endorsed by, given to or issued by Sydney Metro must be provided to the Planning Secretary for information prior to the issue of any Occupation Certificate.

SYDNEY METRO CORRIDOR PROTECTION CONDITION - INSPECTIONS

- E48. If required by Sydney Metro, prior to the issue of an Occupation Certificate, a joint inspection of the rail infrastructure and property in the vicinity of the development is to be carried out by representatives from Sydney Metro and the Applicant and a dilapidation survey prepared. The dilapidation survey will establish the extent of any existing damage and enable any deterioration during operation of the development to be observed. The Certifier is not to issue an Occupation Certificate for the development until written confirmation has been received from Sydney Metro that this condition has been satisfied.

SURVEY CERTIFICATE

- E49. Prior to the issue of an occupation certificate, a registered surveyor must submit documentation to the principal certifier which demonstrates that:
- (a) no existing survey mark(s) have been removed, damaged, destroyed, obliterated or defaced, or
 - (b) the Applicant has re-established any survey mark(s) that were damaged, destroyed, obliterated or defaced in accordance with the Surveyor General's Direction No. 11 - Preservation of Survey Infrastructure.

CONSOLIDATED INSTRUMENT

PART F – OCCUPATION AND ONGOING USE

FIRE SAFETY CERTIFICATION

- F1. The development must operate in accordance with the Fire Safety Certificate obtained in accordance with this consent.

MAINTENANCE OF WASTEWATER AND STORMWATER TREATMENT DEVICE (IF APPLICABLE)

- F2. During occupation and ongoing use of the building, the Applicant must ensure all wastewater and stormwater treatment devices (including drainage systems, sumps and traps, and on-site detention) are regularly maintained, to remain effective and in accordance with any positive covenant (if applicable).

STORAGE AND HANDLING OF WASTE

- F3. All waste collection services must be undertaken in accordance with this consent.
- F4. Waste must not be placed for collection in a public place e.g., footpaths, roadways and reserves under any circumstances.
- F5. Adequate provisions are to be made within the premises for the storage, collection and disposal of waste and recyclable materials, to the satisfaction of Council.
- F6. Trade/commercial waste materials must not be disposed via council's domestic garbage service. All trade/commercial waste materials must be collected by Council, or a waste contractor authorised by the Environmental Protection Authority and details of the proposed waste collection and disposal service are to be submitted to the Council prior to commencing operation of commercial uses of the Site.

LOADING/UNLOADING

- F7. All loading and unloading operations associated with the site must be carried out:
- (a) in accordance with the Loading and Servicing Management Plan approved under this consent;
 - (b) within the confines of the site, at all times and must not obstruct other properties or the public way; and
 - (c) in a manner so as not to cause inconvenience to the public or detrimentally impact the amenity of the locality.
- F8. The service vehicle docks, car parking spaces and repo driveways must be kept clear of goods at all times and must not be used for storage purposes, including waste storage.

ENVIRONMENTAL AMENITY AND ENVIRONMENTAL HEALTH

- F9. External lighting on the Site must be designed and located to minimise light-spill beyond the property boundary or cause a public nuisance. Notwithstanding this consent, should any outdoor lighting result in any residual impacts on the amenity of surrounding sensitive receivers, the Applicant must provide mitigation measures in consultation with affected landowners to reduce the impacts to an acceptable level.
- F10. The use and operation of the Site must not give rise to an environmental health or public nuisance.
- F11. There are to be no emissions or discharges from the Site which give rise to a public nuisance or result in an offence under the *Protection of the Environment Operations Act 1997* and Regulations.

NOISE CONTROL – MECHANICAL PLANT AND EQUIPMENT

- F12. The operation of plant and equipment shall not give rise to an 'offensive noise' as defined in the *Protection of the Environment Operations Act 1997* and Regulations.

OPERATION OF PLANT AND EQUIPMENT

- F13. All plant and equipment used in the development, or used to monitor the performance of the development must be:
- (a) maintained in a proper and efficient condition; and
 - (b) operated in a proper and efficient manner.

ECOLOGICALLY SUSTAINABLE DEVELOPMENT

- F14. Unless otherwise agreed by the Planning Secretary, within twelve months of commencement of operation, Green Star certification must be obtained demonstrating the development, operating in accordance with this consent achieves a minimum 5 Star Green Star As-Built rating (and target a 6 Star Green rating where reasonable and feasible). Evidence of the certification must be provided to the Certifier and the Planning Secretary.

GREEN TRAVEL PLAN

- F15. The Green Travel plan approved under this consent shall be implemented following occupation of the development. The Green Travel Plan is to be reviewed and updated annually as required by Condition E29.

AFFORDABLE HOUSING

- F16. A minimum of 15% of the total gross floor area within the approved development (the affordable housing component) must be used for the purpose of affordable housing as defined by the EP&A Act and *State Environmental Planning Policy (Housing) 2021*, for a minimum tenure of 15 years from the date of the issue of the Occupation Certificate containing affordable housing.
- F17. The affordable housing component must be managed by a registered community housing provider during the relevant period.
- F18. Notice of any change in the registered community housing provider who manages the affordable housing component must be given to the Registrar of Community Housing and the Planning Secretary no later than 3 months after the change.
- F19. The registered community housing provider who manages the affordable housing component must apply the Affordable Housing Guidelines.
- F20. The Applicant must use best endeavours to ensure the affordable housing component is at full occupancy and, by 30 June of each year, must submit to the Planning Secretary a report relating to the previous 12-month period as to:
- (a) the occupancy rate of the affordable housing component for that year, and
 - (b) compliance with the requirement in this condition to use best endeavours to achieve full occupancy.

CONSOLIDATED INSTRUMENT

PART G – PRIOR TO ISSUE OF SUBDIVISION CERTIFICATE

REQUIREMENTS OF THE EP&A ACT – PART 6 CERTIFICATES

- G1. In undertaking the subdivision approved under this consent, the Applicant must comply with the requirements of Part 6 of the EP&A Act in relation to the issue of a Subdivision Certificate. For the purpose of this approval, the issue of a Subdivision Certificate/s is restricted to the development carried out in accordance with the documents set out in Condition A2.

SUBDIVISION CERTIFICATE

- G2. Before granting any Subdivision Certificate, the Certifier must be satisfied that the Applicant has complied with all conditions of this consent that are required to be complied with before a Subdivision Certificate may be issued in relation to the plan of subdivision.

BUILDING MANAGEMENT STATEMENT

- G3. Prior to the issue of a Subdivision Certificate, a Building Management Statement must be prepared in the approved form prescribed by Schedule 8A of the *Conveyancing Act 1919* or a Strata Management Statement must be prepared in the approved form prescribed by Part 6 of the *Strata Schemes Development Act 2015* and submitted to the Certifier.
- G4. The Building Management Statement or Strata Management Statement (as applicable) is to apply to the development as a 'united building'. The Building Management Statement or Strata Management Statement (as applicable) must include details of the following:
- (a) the use, operation and arrangements for the supply of services, maintenance and upgrading of infrastructure of each stratum lot within the subdivision;
 - (b) the ongoing maintenance, upgrading, redevelopment and structural adequacy of each stratum lot within the subdivision;
 - (c) the use, operation and management of carshare spaces;
 - (d) any other matters which the Certifier considers relevant and pertinent to the issue of a Subdivision Certificate; and
 - (e) the implementation of the approved Flood Emergency Response Plan in accordance with Condition E42.

CREATION OF EASEMENTS

- G5. Prior to the issue of a Subdivision Certificate, easements for services, drainage, support and shelter, use of plant, equipment, loading areas and service rooms, repairs, maintenance or any other encumbrances and indemnities required for joint or reciprocal use of part or all of the proposed lots as a consequence of the subdivision, must be created over the appropriate lots in the subdivision pursuant to section 88B of the *Conveyancing Act 1919*.

REGISTRATION OF EASEMENTS

- G6. Prior to the issue of a Subdivision Certificate, the Applicant must provide to the Certifier evidence that all matters required to be registered on title, including easements noted on the draft subdivision plans listed in Condition B71, are contained within the subdivision plan to be lodged for registration at the NSW Land Registry Services.

ENCROACHING AND/OR SHARED SERVICES

- G7. Any pipes, service lines or the like servicing each lot must be contained within their respective lots or, if service lines encroach upon adjoining lots within the subdivision, or are shared by more than one lot, appropriate easements must be created, pursuant to section 88B of the *Conveyancing Act 1919*, over the service lines where any such encroachment occurs.

ACCESS EASEMENT – GROUND LEVEL

- G8. Prior to the registration of the stratum plan for the site, appropriate ground level access easement/s are to be created to provide access to the building from the public domain for each respective building owner/s, tenant/s and visitors, as relevant to the stratum lot/s the subject of the stratum plan to the satisfaction of the Certifier. Each easement is to address construction staging, including any restrictions to access as a result of the construction activities, including erecting hoardings as relevant.
- G9. Suitable easements for access or rights-of-way benefiting the public are to be created over the public domain areas of the residual lot at each stage in the stratum subdivision to ensure public access to the public domain areas. The rights of public access are to be triggered by an Occupation Certificate for the relevant public domain areas (temporary or permanent) within the site.

CONSOLIDATED INSTRUMENT

COMPLIANCE CERTIFICATE

- G10. Prior to issue of any Subdivision Certificate, a compliance certificate issued under Part 6, Division 9 of the *Sydney Water Act 1994* must be obtained from Sydney Water and must be provided to the Certifier demonstrating that the development has satisfied the detailed requirements of Sydney Water in respect to water and wastewater.
- G11. Prior to the issue of each Subdivision Certificate (as relevant), a Registered Surveyor must confirm that the parcel boundary of the plan corresponds with floors, external walls and ceilings of the relevant building/structures as constructed or alternatively, has the benefit of an appropriate easement or is the subject of appropriate provisions in the Building Management Statement or Strata Management Statement, to enable the registration of the plan.

STATEMENT OF COMPLIANCE – COMPLETION IN ACCORDANCE WITH DEVELOPMENT CONSENT

- G12. Prior to the issue of a Subdivision Certificate for stratum subdivision, a Statement of Compliance shall be provided to the Certifying Authority demonstrating that the approved subdivision is consistent with relevant conditions of development consent.

CONSOLIDATED INSTRUMENT

ADVISORY NOTES

- AN1. All new buildings and structures, and any alterations or additions to existing buildings and structures, that are part of the development, including external walls of all buildings and ventilation of premises, must be constructed in accordance with the relevant requirements of the NCC and applicable Australian Standards.
- AN2. The development consent is subject to, and the Applicant must comply with, the Prescribed Conditions.
- AN3. No condition of this consent overcomes any obligation on the Applicant to obtain, renew or comply with licences, permits, approvals, certifications and consents which may be required under law required to carry out the development. The Applicant is responsible for obtaining any such licences, permits, approvals, certifications and consents, licences, permits, approvals, certifications and consents may include but are not limited to:
- (a) modifications to this consent or other development consents required under the EP&A Act;
 - (b) certificates under Part 6 of the EP&A Act;
 - (c) approval under section 138 of the *Roads Act 1993* for activities and works including road occupancy, hoarding, scaffolding, barricades and other construction/building works requiring the use of a public place including a road or footpath;
 - (d) approvals for the installation of any hoardings over Council footways or road reserves;
 - (e) approval under the Commonwealth *Environment Protection and Biodiversity Conservation Act 1999* (EPBC Act);
 - (f) approvals required under the *Sydney Water Act 1994*.
- AN4. The Applicant is responsible for ensuring that all agreements required to carry out the development are obtained from other authorities or other parties, as relevant.
- AN5. No condition of this consent removes any obligation on the Applicant to comply with laws, including but not limited to:
- (a) work health and safety laws;
 - (b) environmental laws including *Protection of the Environment Operations Act 1997* and its regulations;
 - (c) *Disability Discrimination Act 1992* (Cth);
 - (d) *Building and Construction Industry Long Service Payments Act 1986*;
 - (e) *Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021*;
 - (f) *Airports (Protection of Airspace) Regulations 1996*.
- AN6. The operation and maintenance of warm water systems and water-cooling systems (as defined under the *Public Health Act 2010*) must comply with the *Public Health Act 2010*, *Public Health Regulation 2012* the NSW Health Code of Practice for the Control of Legionnaires' Disease and applicable Australian Standards.
- AN7. The owner must submit to Council an Annual Fire Safety Statement, each 12 months after the final Safety Certificate is issued. The certificate must be on, or to the effect of, Council's Fire Safety Statement.
- AN8. Certain tree species placed in proximity to Sydney Water's underground assets have the potential to inflict damage through invasive root penetration and soil destabilisation. Section 46 of the Sydney Water Act specifies what might occur when there is interference or damage to assets caused by trees.
- AN9. Any trees proposed or planted that may cause destruction of, damage to, or interference with, Sydney Water work are in breach of the *Sydney Water Act 1994*. Sydney Water may issue an order to remove that tree or directly remove it and seek recover for all loss and associated compensation for the removal.

APPENDIX 1 – INCIDENT NOTIFICATION AND REPORTING REQUIREMENTS

WRITTEN INCIDENT NOTIFICATION REQUIREMENTS

1. All Incident notifications and reports must be submitted via the NSW planning portal (Major Projects).
2. The Applicant must provide notification as required under these requirements, even if the Applicant fails to give the notification required under Condition D8 or, having given such notification, subsequently forms the view that an Incident has not occurred.
3. Within 7 days (or as otherwise agreed by the Planning Secretary) of the Applicant making the immediate Incident notification (in accordance with Condition D8), the Applicant is required to submit a subsequent Incident report that (in accordance with Condition D9):
 - (a) identifies how the Incident was detected;
 - (b) identifies when the Applicant became aware of the Incident;
 - (c) identifies any actual or potential non-compliance with conditions of consent;
 - (d) identifies further action(s) that will be taken in relation to the Incident;
 - (e) a summary of the Incident;
 - (f) outcomes of an Incident investigation, including identification of the cause of the Incident;
 - (g) details of the corrective and preventative actions that have been, or will be, implemented to address the Incident and prevent recurrence, including the period for implementing any corrective and/or preventative actions; and
 - (h) details of any communication with other stakeholders regarding the Incident.
4. The Applicant must submit any further reports as directed by the Planning Secretary.

SCHEDULE 3 – MODIFICATIONS TO SSD-31576972

- (a) Schedule 1 is amended by the insertion of the **bold and underlined** words / numbers and deletion of the ~~struck out~~ words/numbers as follows:

SCHEDULE 1

Application Number:	SSD-31576972
Applicant:	Beecroft Property Developments Pty Ltd
Consent Authority:	NSW Independent Planning Commission
Site:	242-244 Beecroft Road, Epping Lots 220 and 222, DP 1251471
Development:	Construction of a mixed use development with a scale of <u>seven</u> five to <u>18</u> 45 storeys and containing: • five residential flat buildings containing <u>479</u> 374 apartments including <u>81</u> 48 affordable housing dwellings • commercial premises • basement car parking • infrastructure upgrades, civil and stormwater works • outdoor public plaza and through-site link • stratum subdivision of the site

- (b) Condition A2 is amended by the insertion of the **bold and underlined** words/numbers and deletion of the ~~struck out~~ words/numbers as follows:

TERMS OF CONSENT

A2. The development may only be carried out:

- (a) in compliance with the conditions of this consent;
- (b) in accordance with all written directions of the Planning Secretary;
- (c) in accordance with the EIS, RtS and any Response to Request for Information;
- (d) in accordance with the approved plans in the table below;
- (e) **in accordance with the Environmental Impact Statement titled Amended Mixed Use Development - 242-244 Beecroft Road, Epping, dated August 2024, submitted with the application for consent for the development, including any additional information provided by the Applicant in support of the application for SSD-68908456;**
- (f) **Section 4.55(1A) modification SSD-68708456-Mod-2 and**
- (g) in accordance with the plans approved by the Planning Secretary in accordance with Conditions B1 and B2.

<u>Amending Architectural Drawings prepared by Turner Studio</u>			
<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Revision</u>	<u>Date</u>
<u>DA-001-001</u>	<u>Title Sheet</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-010-010</u>	<u>Site Plan</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-010-011</u>	<u>Site Analysis</u>	<u>A</u>	<u>11/07/24</u>

<u>DA-012-001</u>	<u>Staging Diagram B2 – Ground</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-012-002</u>	<u>Staging Diagram Level 1</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-051-008</u>	<u>Demolition Plan</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-110-005</u>	<u>Basement 03</u>	<u>H</u>	<u>04/06/26</u>
<u>DA-110-006</u>	<u>Basement 02</u>	<u>H</u>	<u>04/06/26</u>
<u>DA-110-007</u>	<u>Basement 01</u>	<u>H</u>	<u>04/06/26</u>
<u>DA-110-008</u>	<u>Lower Ground</u>	<u>H</u>	<u>04/06/26</u>
<u>DA-110-010</u>	<u>Ground Level</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-020</u>	<u>Level 01-05</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-030</u>	<u>Level 06</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-040</u>	<u>Level 07</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-050</u>	<u>Level 08-13</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-080</u>	<u>Level 14</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-090</u>	<u>Level 15</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-110</u>	<u>Level 16</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-120</u>	<u>Level 17</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-110-130</u>	<u>Roof Level</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-101</u>	<u>Building A West Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-201</u>	<u>Building B South Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-301</u>	<u>Building B North Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-401</u>	<u>Building C North Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-501</u>	<u>Building E North Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-601</u>	<u>Site East Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-701</u>	<u>Building C and E Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-801</u>	<u>Building C South Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-901</u>	<u>Building E South Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-210-1001</u>	<u>Site West Elevation</u>	<u>F</u>	<u>04/06/26</u>
<u>DA-310-101</u>	<u>Section AA - North-South</u>	<u>E</u>	<u>04/06/26</u>
<u>DA-310-201</u>	<u>Section BB - Building A & B</u>	<u>E</u>	<u>04/06/26</u>
<u>DA-310-301</u>	<u>Section CC - Building C & D</u>	<u>E</u>	<u>04/06/26</u>
<u>DA-310-401</u>	<u>Section DD - Building E</u>	<u>E</u>	<u>04/06/26</u>
<u>DA-310-501</u>	<u>Section Across Ray Road, Building A & B</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-310-601</u>	<u>Section Across Ray Road, Building C & D</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-310-701</u>	<u>Section Across Ray Road, Building E</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-310-801</u>	<u>Public Domain Interface</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-730-001</u>	<u>Deep Soil and Communal Space Diagrams</u> <u>Ground Level Deep Soil</u>	<u>D</u>	<u>11/03/26</u>
<u>DA-730-002</u>	<u>Communal Open Space</u>	<u>A</u>	<u>11/07/24</u>
<u>DA-810-001</u>	<u>Adaptable Plan Layouts</u>	<u>E</u>	<u>11/03/26</u>

<u>DA-810-002</u>	<u>Adaptable Plan Layouts</u>	E	11/03/26
<u>DA-810-003</u>	<u>Adaptable Plan Layouts</u>	E	11/03/26
<u>DA-810-004</u>	<u>Adaptable Plan Layouts</u>	E	11/03/26
<u>DA-810-005</u>	<u>Liveable Plan Layouts</u>	E	11/03/26
<u>DA-820-001</u>	<u>Affordable Housing</u>	C	11/03/26
<u>DA-820-002</u>	<u>Affordable Housing</u>	C	11/03/26
<u>DA-890-001</u>	<u>Materials & Finishes Board</u> <u>Materials</u>	E	04/06/26

Amending Landscape Drawings prepared by Site Image

<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Revision</u>	<u>Date</u>
<u>SS21-4819-000</u>	<u>Landscape Coversheet</u>	A	17.09.2025
<u>SS21-4819-001</u>	<u>Landscape Plant Schedule & Legend</u>	A	17.09.2025
<u>SS21-4819-002</u>	<u>Ground Floor Masterplan</u>	A	17.09.2025
<u>SS21-4819-003</u>	<u>Tree Retention and Removal Plan</u>	A	17.09.2025
<u>SS21-4819-101</u>	<u>Ground Floor Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-102</u>	<u>Ground Floor Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-103</u>	<u>Ground Floor Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-104</u>	<u>Ground Floor Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-105</u>	<u>Ground Floor Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-106</u>	<u>Ground Floor Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-110</u>	<u>Level 1-5 Masterplan</u>	A	17.09.2025
<u>SS21-4819-111</u>	<u>Level 1-5 Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-120</u>	<u>Level 6-7 Masterplan</u>	A	17.09.2025
<u>SS21-4819-121</u>	<u>Level 06 Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-122</u>	<u>Level 07 Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-123</u>	<u>Level 07 Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-130</u>	<u>Level 16-17 Masterplan</u>	A	17.09.2025
<u>SS21-4819-131</u>	<u>Level 16 Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-132</u>	<u>Level 16 Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-132</u>	<u>Level 17 Landscape Plan</u>	A	17.09.2025
<u>SS21-4819-500</u>	<u>Landscape Maintenance Plan</u>	A	17.09.2025
<u>SS21-4819-501</u>	<u>Landscape Details</u>	A	17.09.2025
<u>SS21-4819-502</u>	<u>Landscape Details</u>	A	17.09.2025
<u>SS21-4819-503</u>	<u>Landscape Planting Matrix Details</u>	A	17.09.2025
<u>SS21-4819-601</u>	<u>Landscape Sections</u>	A	17.09.2025
<u>SS21-4819-602</u>	<u>Landscape Sections</u>	A	17.09.2025
<u>SS21-4819-603</u>	<u>Landscape Sections</u>	A	17.09.2025
<u>SS21-4819-604</u>	<u>Landscape Sections</u>	A	17.09.2025
<u>SS21-4819-605</u>	<u>Landscape Sections</u>	A	17.09.2025
<u>SS21-4819-606</u>	<u>Landscape Sections</u>	A	17.09.2025

Architectural drawings prepared by Turner Studio			
<u>Drawing Number</u>	<u>Rev</u>	<u>Name of Plan</u>	<u>Date</u>
DA-012-004	03	Staging Diagram B2 — Ground	15.05.23
DA-012-002	03	Staging Diagram Level 4	15.05.23

DA-051-008	03	Demolition Plan	15.05.23
DA-110-001	06	GA Plans — Basement 02	15.05.23
DA-110-002	08	GA Plans — Basement 01	15.05.23
DA-110-003	08	GA Plans — Lower Ground	15.05.23
DA-110-004	07	GA Plans — Ground	15.05.23
DA-110-010	06	GA Plans — Level 01-04	15.05.23
DA-110-020	06	GA Plans — Level 05	15.05.23
DA-110-040	05	GA Plans — Level 06	15.05.23
DA-110-030	06	GA Plans — Level 07-11	15.05.23
DA-110-025	06	GA Plans — Level 12	15.05.23
DA-110-100	06	GA Plans — Level 13	15.05.23
DA-110-101	06	GA Plans — Roof Level	15.05.23
DA-210-101	07	GA Elevations — Building A West Elevation	15.05.23
DA-210-201	07	GA Elevations — Building B South Elevation	15.05.23
DA-210-301	07	GA Elevations — Building B North Elevation	15.05.23
DA-210-401	07	GA Elevations — Building C North Elevation	15.05.23
DA-210-501	07	GA Elevations — Building E North Elevation	15.05.23
DA-210-601	07	GA Elevations — Site East Elevation	15.05.23
DA-210-701	07	GA Elevations — Building C and E Elevation	15.05.23
DA-210-801	07	GA Elevations — Building C South Elevation	15.05.23
DA-210-901	07	GA Elevations — Building E South Elevation	15.05.23
DA-210-1001	06	GA Elevations — Site West Elevation	15.05.23
DA-310-101	04	GA Sections — Section AA North-South	15.05.23
DA-310-201	04	GA Sections — Section BB Building A & B	15.05.23
DA-310-301	04	GA Sections — Section CC Building C & D	15.05.23
DA-310-401	04	GA Sections — Section DD Building E	15.05.23
DA-310-501	03	GA Sections — Section Across Ray Road, Building A & B	15.05.23
DA-310-601	03	GA Sections — Section Across Ray Road, Building C & D	15.05.23
DA-310-701	03	GA Sections — Section Across Ray Road, Building E	15.05.23
DA-310-801	04	GA Sections — Public Domain Interface	15.05.23
DA-730-001	03	Deep Soil and Communal Open Space Diagrams — Ground Level Deep Soil	15.05.23
DA-730-002	03	Deep Soil and Communal Open Space Diagrams — Communal Open Spaces	15.05.23
DA-810-001	03	Adaptable Plan Layouts	15.05.23
DA-810-002	04	Adaptable Plan Layouts	15.05.23
DA-810-003	04	Adaptable Plan Layouts — Liveable Plan Layouts	15.05.23
DA-820-001	03	Affordable Housing	15.05.23
DA-820-002	03	Affordable Housing	15.05.23
DA-890-001	03	Materials & Finishes Board — Materials	15.05.23

DA-890-002	02	Materials & Finishes Board — Podium Materials	15.05.23
DA-890-003	02	Materials & Finishes Board — Podium Materials 2	15.05.23
Landscape drawings prepared by Site Image			
Drawing Number	Rev	Name of Plan	Date
SS21-4819-000	K	Landscape Coversheet	15.05.23
SS21-4819-001	H	Landscape Plant Schedule and Legend	15.05.23
SS21-4819-002	K	Ground Floor Masterplan	15.05.23
SS21-4819-003	J	Tree Retention and Removal Plan	15.05.23
SS21-4819-101	I	Ground Floor Landscape Plan	15.05.23
SS21-4819-102	I	Ground Floor Landscape Plan	15.05.23
SS21-4819-103	H	Ground Floor Landscape Plan	15.05.23
SS21-4819-104	I	Ground Floor Landscape Plan	15.05.23
SS21-4819-105	I	Ground Floor Landscape Plan	15.05.23
SS21-4819-106	K	Ground Floor Landscape Plan	15.05.23
SS21-4819-110	G	Level 1-4 Masterplan	02.03.23
SS21-4819-111	G	Level 1-4 Landscape Plan	02.03.23
SS21-4819-120	G	Rooftop Masterplan	02.03.23
SS21-4819-121	G	Level 05 Landscape Plan	02.03.23
SS21-4819-122	B	Level 05 Landscape Plan	02.03.23
SS21-4819-123	B	Level 05 Landscape Plan	02.03.23
SS21-4819-131	B	Level 13 Landscape Plan	02.03.23
SS21-4819-132	B	Level 13 Landscape Plan	02.03.23
SS21-4819-500	A	Landscape Maintenance Plan	20.03.23
SS21-4819-501	A	Landscape Typical Details	20.06.22
SS21-4819-502	B	Landscape Typical Details	29.06.22
SS21-4819-503	B	Landscape Planting Matrix Details	29.06.22
SS21-4819-601	D	Landscape Sections	02.03.23
SS21-4819-602	D	Landscape Sections	02.03.23
SS21-4819-603	D	Landscape Sections	05.04.23
SS21-4819-604	E	Landscape Sections	15.05.23
SS21-4819-605	E	Landscape Sections	10.05.23
SS21-4819-606	C	Landscape Sections	15.05.23

- (c) Condition B10 is amended by the insertion of the **bold and underlined** words/numbers and deletion of the ~~struck out~~ words/numbers as follows:

MAXIMUM BUILDING HEIGHTS

- B10. Prior to the issue of the Construction Certificate for above ground works, the Applicant must submit to the satisfaction of the Certifier details confirming the maximum height of the buildings does not exceed the following, including plant and lift overruns, but excluding communication devices, antennas, satellite dishes, masts, flagpoles, chimneys, flues and the like.

<u>Building</u>	<u>Maximum height</u>
<u>A</u>	<u>RL 108.28</u>
<u>B</u>	<u>RL 145.08</u>
<u>C</u>	<u>RL 143.92</u>
<u>D</u>	<u>RL 110.44</u>
<u>E</u>	<u>RL 143.06</u>

<u>Building</u>	<u>Maximum height</u>
A	RL 105.31
B	RL 133.86
C	RL 131.21
D	RL 103.86
E	RL 130.96

- (d) Condition B12 is amended by the insertion of the **bold and underlined** words/numbers and deletion of the ~~struck out~~ words/numbers as follows:

GROSS FLOOR AREA CERTIFICATION

- B12. Prior to the issue of the Construction Certificate for Above Ground Works, the Applicant must submit to the satisfaction of the Certifier details confirming the gross floor area of the development does not exceed **49,829m²** ~~38,613m²~~.

- (e) Condition B31(a) is amended by the deletion of the ~~struck out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

CAR AND MOTORCYCLE PARKING

- B31. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier plans demonstrating compliance with the following traffic and parking requirements:

- (a) on site car parking spaces provided as follows:

- (i) 474 residential spaces, comprising 433 market apartment spaces and 41 affordable housing spaces;**
- (ii) 68 visitor spaces;**
- (iii) 12 commercial spaces;**
- (iv) 4 motorcycle spaces;**
- (v) 1 carshare space; and**
- (vi) 1 car wash bay;**
- ~~(i) 299 residential spaces~~
- ~~(ii) 53 visitors spaces~~
- ~~(iii) 13 commercial spaces~~
- ~~(iv) 4 motorcycle spaces~~

(v) — 1 carshare space

(vi) — 1 car wash bay

- (f) Condition B31(g) – (i) is amended by deletion of the ~~struck-out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

(g) electric vehicle charging infrastructure in accordance with the NCC;

~~(g)~~**(h)** all works/regulatory signposting associated with the development must be at no cost to the relevant roads authority; and

~~(h)~~**(i)** the swept path of the longest vehicle (including garbage trucks) entering and exiting the Site, as well as manoeuvrability through the subject Site, must be in accordance with AUSTROADS, **AS2890.1-2004 and AS2890.2-2018 (or their latest versions).**

- (g) Condition B33 is amended by the deletion of the ~~struck-out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

BICYCLE PARKING

B33. Prior to the issue of the relevant Construction Certificate, the Applicant must submit to the satisfaction of the Certifier plans demonstrating compliance with the following traffic and parking requirements:

- (a) a minimum of **479** ~~374~~ residential bicycle parking spaces
- (b) a minimum of **48** ~~40~~ residential visitor bicycle parking spaces
- (c) a minimum of **4** ~~8~~ non-residential bicycle parking spaces
- (d) end-of-trip facilities for non-residential floor space comprising a minimum of 4 showers and 8 lockers.

- (h) Condition B45 is amended by the deletion of the ~~struck-out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

SYDNEY METRO CONDITIONS – ENGINEERING

B45. All excavation and construction works are to be undertaken in accordance with the details, methodology, advice, undertakings, measures and recommendations detailed in the following documents:

(a) Geotechnical Investigation Report prepared by PSM, dated 27 May 2022.

(b) Structural Drawings prepared by JSBC Consulting, as listed below:

(i) Shoring and Early Works Plan, Revision A, dated 16 October 2024.

(ii) Shoring Elevations - Sheet 1, Revision, dated 16 October 2024.

(iii) Shoring Infrastructure Sections – Sheet 1, dated 16 October 2024.

(iv) Shoring Infrastructure Sections – Sheet 2, dated 16 October 2024.

(v) Shoring Infrastructure Sections – Sheet 3, dated 16 October 2024.

(vi) Shoring Infrastructure Sections – Sheet 4, dated 16 October 2024.

(vii) Shoring Adjacent to Beecroft Road Construction Methodology, dated 16 October 2024.

(c) 242-244 Beecroft Road, Epping – Sydney Metro Tunnel Structural Assessment, Revision F, prepared by Hyve Designs, dated 31 March 2025.

(d) Risk Assessment, prepared by ArchArtifex, dated 18 November 2024.

(e) Noise and Vibration Impact Assessment, Revision 4, prepared by Acoustic Logic dated 6 November 2024.

(f) Electrolysis Risk Assessment Report, Revision 1, prepared by Corrosion Control Engineering, dated 1 November 2024.

(g) Finite Element Analysis for Sydney Metro 242-244 Beecroft Road, Epping, prepared by EI Australia, dated 19 November 2024.

(h) Geotechnical Letter for Endorsement of Additional Basement, prepared by EI Australia, dated 19 November 2024.

(i) Structural Sydney Metro Report – Endorsement for Additional Basement, prepared by JSBC Consulting, dated 19 November 2024.

subject to any amendments to those documents required by Sydney Metro in accordance with this consent.

~~B45. All excavation and construction works are to be undertaken in accordance with the details, methodology, advice, undertakings, measures and recommendations detailed in the following documents:~~

~~(a) Preliminary Sydney Metro Geotechnical Impact Assessment (Ref. PSM4547 – 007R) prepared by PSM dated 07 July 2022, including but not limited to the appended documentation:~~

~~(i) Section A – Run01 & Run02 – Model Geometry prepared by PSM dated 05 July 2022~~

~~(ii) Section B – Run01 & Run02 – Model Geometry prepared by PSM dated 05 July 2022~~

~~(iii) Section C – Run01 & Run02 – Model Geometry prepared by PSM dated 06 July 2022~~

~~(iv) Section A – Run01 – Horizontal Displacement prepared by PSM dated 05 July 2022~~

~~(v) Section A – Run01 – Vertical Displacement prepared by PSM dated 05 July 2022~~

~~(vi) Section A – Run02 – Horizontal Displacement prepared by PSM dated 05 July 2022~~

~~(vii) Section A – Run02 – Vertical Displacement prepared by PSM dated 05 July 2022~~

~~(viii) Section B – Run01 – Horizontal Displacement prepared by PSM dated 05 July 2022~~

~~(ix) Section B – Run01 – Vertical Displacement prepared by PSM dated 05 July 2022~~

~~(x) Section B – Run02 – Horizontal Displacement prepared by PSM dated 05 July 2022~~

~~(xi) Section B – Run02 – Vertical Displacement prepared by PSM dated 05 July 2022~~

~~(xii) Section C – Run01 – Horizontal Displacement prepared by PSM dated 05 July 2022~~

~~(xiii) Section C – Run01 – Vertical Displacement prepared by PSM dated 05 July 2022~~

~~(xiv) Section C – Run02 – Horizontal Displacement prepared by PSM dated 05 July 2022~~

~~(xv) Section C – Run02 – Vertical Displacement prepared by PSM dated 05 July 2022~~

~~(xvi) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 1 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xvii) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 2 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xviii) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 3 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xix) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 4 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xx) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 5 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xxi) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 6 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xxii) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 7 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xxiii) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 8 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xxiv) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 9 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xxv) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 10 of 11) Revision B prepared by LTS dated 20 December 2021~~

~~(xxvi) Plan of Detail and Levels over Lot 220 DP 125471 (Sheet 11 of 11) Revision B prepared by LTS dated 20 December 2021~~

(b) ~~Structural Report for Sydney Metro (Ref. 21074) Revision 01 prepared by JSBC Consulting dated 01 July 2022, including but not limited to the appended documentation:~~

~~(i) Dwg. SK01 Revision 01 prepared by JSBC Consulting dated 16 June 2022~~

~~(ii) Dwg. SK02 Revision 01 prepared by JSBC Consulting dated 16 June 2022~~

~~(iii) Dwg. SK03 Revision 01 prepared by JSBC Consulting dated 16 June 2022~~

~~(iv) Dwg. SK04 Revision 01 prepared by JSBC Consulting dated 16 June 2022~~

~~(v) Dwg. SK05 Revision 01 prepared by JSBC Consulting dated 16 June 2022~~

(c) ~~Email correspondence, subject title 'RE: Sydney Metro Submission PSD4547' prepared by Daniel De Cataldo (Senior Geotechnical Engineer, PSM) dated 12 December 2022~~

~~subject to any amendments to these documents required by Sydney Metro in accordance with this consent.~~

(i) Condition B45A is added by the insertion of the **bold and underlined** words/numbers as follows:

B45A. The Certifier must not issue a Construction Certificate for the development unless the Applicant has submitted to Sydney Metro, and Sydney Metro has provided written approval of, the following items:

(a) Final design construction drawings with details of internal props, foundations of bracing system for the Construction Certificate;

(b) Latest instrumentation and monitoring plan with trigger levels and actions; and

(c) A risk assessment in accordance with Section 7.3 of Sydney Metro Underground Corridor Protection Technical Guidelines and/or Sydney Metro At Grade and Elevated Sections Corridor Protection Guidelines, including the consideration of likelihood, consequences, mitigation measures and risk levels.

Prior to the commencement of works, the Certifier must provide written verification to Sydney Metro that this condition has been complied with.

(j) Condition B50 is amended by the deletion of the ~~struck-out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

B50. The Applicant must incorporate as part of the development all the measures recommended in the acoustic assessment report Noise and Vibration Impact Assessment, prepared by Acoustic Logic, Revision 4, dated 6 November 2024. A copy of the acoustic assessment report is to be provided to the Certifier and Council prior to a Construction Certificate being issued by the Certifier. The Certifier must ensure that the recommendations of the acoustic assessment report are incorporated in the construction drawings and documentation prior to issuing a Construction Certificate for the development.

~~B50. The Applicant must incorporate as part of the development all the measures recommended in the acoustic assessment report Noise and Vibration Impact Assessment (Ref 20220102.1/0302A/R3/AR) Revision 3 prepared by Acoustic Logic dated 03 February 2023. A copy of the acoustic assessment report is to be provided to the Certifier and Council prior to a Construction Certificate being issued by the Certifier. The Certifier must ensure that the recommendations of the acoustic assessment report are incorporated in the construction drawings and documentation prior to issuing a Construction Certificate for the development~~

(k) Condition B50A is added by the insertion of the **bold and underlined** words/numbers as follows:

B50A. The development must:

(a) comply with State Environmental Planning Policy (Transport and Infrastructure) 2021 and the NSW Department of Planning & Environment's document titled "Development Near Rail Corridors and Busy Roads - Interim Guideline" (2008) and the Sydney Metro Underground Corridor Protection Guidelines;

(b) be designed, constructed and maintained so as to avoid damage or other interference which may occur as a result of air-borne noise, ground-borne noise and vibration effects that may emanate from the rail corridor during rail construction and operations; and

(c) not have any noise or vibration impacts on the rail corridor or rail infrastructure.

(l) Condition B51 is amended by the deletion of the ~~struck-out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

B51. Prior to the issue of a Construction Certificate, the Applicant is to engage an electrolysis expert to prepare a report on the electrolysis risk to the development from stray currents. The Applicant must incorporate in the development all the measures recommended in the electrolysis report to control that risk. A copy of the electrolysis report is to be provided to the Certifier with the application for a Construction Certificate.

~~B51. The Applicant must incorporate as part of the development all the measures recommended in the electrolysis assessment report Electrolysis Risk Report (Ref. W22971/NSW-P100071) Revision 0 prepared by Corrosion Control Engineering dated 20 December 2022. A copy of the electrolysis report is to be provided to the Certifier prior to the issue of a Construction Certificate by the Certifier. The Certifier must ensure that the recommendations of the electrolysis report are incorporated in the construction drawings and documentation prior to issuing a Construction Certificate for the development~~

- (m) Condition B51A is added by the insertion of the **bold and underlined** words/numbers as follows:

B51A. Prior to issuing a Construction Certificate for the development, the Certifier must ensure that the recommendations of the electrolysis report are incorporated in the construction drawings and documentation.

- (n) Condition B51B is added by the insertion of the **bold and underlined** words/numbers as follows:

SYDNEY METRO CONDITION - DESIGN

B51B. The roots and foliage of trees planted beside the rail corridor as part of the development must not impact on the rail corridor or rail operations. A final landscaping and planting plan demonstrating measures to ensure compliance with this condition must be prepared to the satisfaction of Sydney Metro. The Certifier must not issue a Construction Certificate for the development until written confirmation has been received from Sydney Metro that this condition has been satisfied

- (o) Condition D14 is amended by the deletion of the ~~struck out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

D14. The Applicant must implement and comply with the requirements of any management plan or sub-plan required under this consent. To the extent of any inconsistency between a condition of consent and a management plan or sub-plan, the condition of consent prevails.

~~D14. The Applicant must ensure the requirements of the Construction Environmental Management Plan, Construction Pedestrian Traffic Management Plan, Construction Noise and Vibration Management Sub Plan, Air Quality Management Plan and Construction Waste Management Plan required by Part B of this consent are implemented during construction.~~

- (p) Conditions E38 and E39 are amended by the deletion of the ~~struck out~~ words/numbers and insertion of the **bold and underlined** words/numbers as follows:

AFFORDABLE HOUSING

E38. A minimum of **15% of the total gross floor area** ~~49 dwellings~~ within the approved development must be used for the purpose of affordable housing as defined by **the EP&A Act and State Environmental Planning Policy (Housing) 2021** ~~State Environmental Planning Policy (Affordable Rental Housing) 2009~~, for a minimum tenure of 15 years from the date of the issue of the occupation certificate **containing affordable housing**. All affordable housing at the site must be managed by a registered community housing provider.

E39. Prior to the issue of an occupation certificate, a covenant must be registered on the title of the property providing that 15% of the **total** gross floor area is provided as affordable housing for a minimum of 15 years defined by **the EP&A Act and State Environmental Planning Policy (Housing) 2021**. ~~evidence demonstrating compliance with the affordable housing covenant registered against the title of the property must be submitted to the Certifier.~~

- (q) Condition E39A is added by the insertion of the **bold and underlined** words/numbers as follows:

E39A. Notice of any change in the registered community housing provider who manages the affordable housing component must be given to the Registrar of Community Housing and the Planning Secretary no later than 3 months after the change.

- (r) Condition E39B is added by the insertion of the **bold and underlined** words/numbers as follows:

E39B. The registered community housing provider who manages the affordable housing component must apply the Affordable Housing Guidelines.

- (s) Condition E39C is added by the insertion of the **bold and underlined** words/numbers as follows:

E39C The Applicant must use best endeavours to ensure the affordable housing component is at full occupancy and, by 30 June each year, must submit to the Planning Secretary a report relating to the previous 12 month period as to:

- (a) the occupancy rate of the affordable housing component for that year, and**
- (b) compliance with the requirement in this condition to use best endeavours to achieve full occupancy.**