

Warehousing Facility, Horsley Drive Business Park (SSD 7078) Waste Management Plan

Report Number 610.15399-R2

30 July 2015

Australand PO Box 3307 Rhodes NSW 2138

Version: Revision 2

Warehousing Facility, Horsley Drive Business Park (SSD 7078) Waste Management Plan

PREPARED BY:

SLR Consulting Australia Pty Ltd

ABN 29 001 584 612

2 Lincoln Street

Lane Cove NSW 2066 Australia

(PO Box 176 Lane Cove NSW 1595 Australia)

T: +61 2 9427 8100 F: +61 2 9427 8200

sydney@slrconsulting.com www.slrconsulting.com

This report has been prepared by SLR Consulting Australia Pty Ltd with all reasonable skill, care and diligence, and taking account of the timescale and resources allocated to it by agreement with the Client. Information reported herein is based on the interpretation of data collected, which has been accepted in good faith as being accurate and valid.

This report is for the exclusive use of Australand.

No warranties or guarantees are expressed or should be inferred by any third parties.

This report may not be relied upon by other parties without written consent from SLR.

SLR disclaims any responsibility to the Client and others in respect of any matters outside the agreed scope of the work.

DOCUMENT CONTROL

Reference	Status	Date	Prepared	Checked	Authorised
610.15399-R2	Revision 2	30 July 2015	Gemma Dawson	Tanya Henley	Gemma Dawson
610.15399-R2	Revision 1	29 June 2015	Gemma Dawson	Tanya Henley	Gemma Dawson
610.15399-R2	Revision 0	29 June 2015	Gemma Dawson	Tanya Henley	Gemma Dawson

Table of Contents

1	INTE	RODUCT	TION	5
	1.1	Secret	ary's Environmental Assessment Requirements	5
	1.2	Scope		5
	1.3	Object	ives	6
2	BET	TER PR	ACTICE FOR WASTE MANAGEMENT AND RECYCLING	7
	2.1	Waste	Management Hierarchy	7
	2.2	Benefi	ts of Implementing Better Practice for Waste Management and Recycling	7
3	WAS	STE LEG	ISLATION AND GUIDANCE	8
4	PRO	JECT D	ESCRIPTION	9
	4.1	Overvi	ew of Proposed Development	9
		4.1.1	Development Schedule	9
5	CON	ISTRUC	TION WASTE MANAGEMENT	10
	5.1	Waste	Streams and Classifications	10
	5.2	Constr 5.2.1	ruction Waste Generation Rates Estimation of Waste Volumes	11 12
	5.3	Waste	Avoidance Measures	13
	5.4	Re-use	e, Recycling and Disposal	14
		5.4.1	Site Specific Procedures	15
	5.5	Waste	Storage and Servicing	15
		5.5.1	Space and Amenity	16
		5.5.2	Contaminated/Hazardous Waste	16
		5.5.3	Liquid Waste / Stormwater / Wastewater Management	17
		5.5.4	Spills Management	17
	5.6	Signag		17
	5.7		ng and Awareness	17
	5.8		oring and Reporting	18
	5.9	Roles	and Responsibilities	18
6	OPE	RATION	IAL WASTE MANAGEMENT	19
	6.1	Waste	Streams and Classifications	19
		6.1.1	Anticipated Waste Generation Rates for Operational Development	21
	6.2	Waste	Avoidance, Re-use and Recycling Measures	21
		6.2.1	Waste Avoidance	21
		6.2.2	Re-use	21
		6.2.3	Recycling	21
	6.3		Storage and Servicing Requirements	22
		631	Waste Collection Area Location	22

7

Table of Contents

	6.3.2	Waste Collection Area Requirements	22
6.4	Specia	I Wastes	22
0	6.4.1	Contaminated / Hazardous Wastes	22
	6.4.2	Liquid Waste	22
	6.4.3	Stormwater Treatment	23
	• • • • • • • • • • • • • • • • • • • •		
	6.4.4	Spills Management	23
	6.4.5	Signage	23
	6.4.6	Contract Clauses	23
TABLES			
Table 1		etary's Environmental Assessment Requirements – Warehousing Facility, n Brower – Horsley Drive Business Park (Application Number SSD 7078)	5
Table 2	NSW	Waste Legislation and Guidance Summary	8
Table 3		ey Drive Business Park Lots 5 and 6 Development Schedule	9
Table 4		ntial Waste Generation and EPA Classifications	10
Table 5		eline to Waste Composition and Volumes - Construction	12
Table 6		onmental Performance Indicator for Waste Volumes from New Developments	12
Table 7		nated Waste Generation for the Development	13
Table 8		nated Waste Volumes and Materials for the Development	13
Table 9 Table 10		mmended Roles and Responsibilities ntial Waste Generation and EPA Classifications - Operational	18 19
Table 10		ipated Weekly Waste Generation	21
IADIE II	Ando	ipaled Weekly Waste Generation	۷ ا
FIGURES			

APPENDICES

Figure 1

Appendix A Horsley Drive Business Park Lot 5 Masterplan

Waste Hierarchy

1 INTRODUCTION

Australand

SLR Consulting Australia Pty Ltd (SLR) has been engaged by Australand Industrial Constructions Pty Ltd (Australand) on behalf of The Martin Brower Company (Martin Brower) to prepare a Waste Management Plan (WMP) for the proposed construction and operation of a warehousing facility located on the corner of Horsley Drive and Cowpasture Road, Wetherill Park (the Project site). This assessment forms a part of the Environmental Impact Statement (EIS) for the Project.

The Environmental Planning and Assessment Act 1979 (EP&A Act) forms the statutory framework for planning approval and environmental assessment in NSW. The project is considered 'State Significant Development' (SSD 7078) in accordance with Division 4.1 of Part 4 of the EP&A Act, as it is a type listed in Schedule 1 of the State Environmental Planning Policy (SEPP) - State and Regional Development.

1.1 Secretary's Environmental Assessment Requirements

The NSW Department of Planning and Environment (DP&E) issued Secretary's Environmental Assessment Requirements (SEARs) for the Project on 24 June 2015. The SEARs are outlined below in Table 1.

Table 1 Secretary's Environmental Assessment Requirements - Warehousing Facility, Martin Brower - Horsley Drive Business Park (Application Number SSD 7078)

Key Issue	Assessment Requirement	Addressed in Section
Waste Details of the quantities and classification of all waste streams to be ger site.		Section 6.1
	Details of waste storage, handling and disposal. Section 6.3	
	Details of the measures that would be implemented to ensure that the development is consistent with the aims, objectives and guidance in the NSW Waste Avoidance and Resource Recovery Strategy 2014-2021.	Section 6.2

Issued: 24 June 2015; Department of Planning & Environment, NSW Government, File Reference: SSD 7078.

The SEARs require that the assessment be performed in accordance with relevant policies, guidelines and plans including:

- The NSW Waste Avoidance and Resource Recovery (WARR) Strategy 2014-21 (Environment Protection Authority [EPA]); and
- The NSW WARR Performance Report 2006 (DECC, now EPA).

This assessment addresses the key issues raised within the SEARs and is performed in accordance with the relevant policies and guidelines.

Scope 1.2

This WMP applies to the demolition, construction and on-going operation of the proposed development.

The provisions contained in the WMP must be implemented at all stages of the development, and may be subject to review upon expansion or changes in operational procedures.

- See page 11 for the Construction WMP.
- See page 21 for the Operational WMP.

1.3 Objectives

The principal objective of this WMP is to identify all potential wastes likely to be generated at the site during development and operational phases of the Project, including a description of how waste would be handled, processed and disposed of (or re-used/recycled), in accordance with the relevant regulatory requirements.

The specific objectives of this WMP are as follows:

- to encourage the minimisation of waste production and maximisation of resource recovery;
- to ensure the appropriate management of contaminated/hazardous waste;
- to identify procedures and chain of custody records for waste management; and
- to assist in ensuring that any environmental impacts during the operational life of development comply with the development consent conditions and other relevant regulatory authorities.

2 BETTER PRACTICE FOR WASTE MANAGEMENT AND RECYCLING

2.1 Waste Management Hierarchy

Where appropriate, this WMP aims to meet the principles of the waste management hierarchy, by promoting waste as a resource through the following in order of preference:

- waste avoidance through prevention or reduction of waste generation (waste avoidance is best achieved through better design and purchasing choices);
- waste reuse, without substantially changing the form of waste;
- waste recycling through the treatment of waste that is no longer usable in its current form to produce new products;
- energy recovery through thermal treatment of residual waste materials and from green waste processing;
- waste disposal, in a manner that causes the least harm to the natural environment;
- energy recovery through thermal treatment of residual waste materials and from green waste processing; and
- waste disposal, in a manner that causes the least harm to the natural environment.

The waste hierarchy pictured below demonstrates a classification of waste management options in order of their environmental impacts, as established under the Waste Avoidance and Resource Recovery Act 2001.

Reduce or avoid waste

Reuse waste

Recycle waste

Recover energy

Treat waste

Dispose of waste

Least preferable

Figure 1 Waste Hierarchy

Source: NSW WARR Strategy 2014-21 (EPA)

2.2 Benefits of Implementing Better Practice for Waste Management and Recycling

The benefits of implementation better practices for waste management and recycling include:

- enhanced social and environmental reputation of an organisation;
- reduced costs associated with waste disposal;
- benefits to all stakeholders and the wider community; and
- improved environmental outcomes.

3 WASTE LEGISLATION AND GUIDANCE

The legislation and guidance outlined in **Table 2** below should be referred to during construction and operational phases of the development.

Table 2 NSW Waste Legislation and Guidance Summary

Legislation	Objectives
Waste Avoidance and Resource Recovery Act 2001	To promote extended producer responsibility in place of industry waste reduction plans. Specific objectives include:
	To encourage efficient use of resources.
	 To minimise the consumption of natural resources and the final disposal of waste by encouraging the avoidance of waste and the reuse and recycling of waste.
	 To ensure that industry shares with the community the responsibility for reducing and dealing with waste.
	 To ensure the efficient funding of waste and resource management planning, programs and service delivery.
Protection of the Environment Operations Act (POEO) 1997 & Amendment Act 2011	Administered by the Environmental Protection Authority (EPA) to enable the Government to establish instruments for setting environmental standards, goals, protocols and guidelines.
	Important Note: The owner of a premises, the employer or any person carrying on the activity which causes a pollution incident is to <i>immediately</i> notify the relevant authorities when material harm to the environment is caused or threatened.
	A list of each relevant authority is provided in the POEO Amendment Act and will be noted in the site's incident register.
NSWEPA's Waste Classification Guidelines (Part 1) 2014	To assist waste generators to effectively manage, treat and dispose of waste to ensure the environmental and human health risks associated with waste are managed appropriately and in accordance with the POEO Act and is associated regulations.
Building Code of Australia (BCA) and relevant Australian Standards (AS)	The BCA has the aim of achieving nationally consistent, minimum necessary standards of relevant health and safety, amenity and sustainability objectives efficiently.
NSWEPA's Better Practice Guidelines for Waste Management and Recycling in Commercial and Industrial Facilities 2012	The EPA's Better Practice Guidelines (2012) encourage efficient waste minimisation and resource recovery for commercial and industrial facilities and is used as a benchmark document when assessing waste production rates within Australia and details a range of waste management provisions.
NSWEPA's Waste Avoidance and Resource Recovery (WARR) Strategy 2014-21	A key component of the State Government's vision for the environmental and economic future of the state that will be supported financially by the Waste Less, Recycle More funding initiative providing long-term targets for 6 key result areas including increased recycling of construction and demolition waste.
Australian Packaging Covenant	Each building should be encouraged to establish an Action Plan to demonstrate their contribution to the achievement of the Australian Packaging Covenant's (APC) goals. The three main performance goals of the APC are:
	 Design: Optimise packaging to use resources efficiently and reduce environmental impact without compromising product quality/safety.
	Recycling: Efficiently collect and recycle packaging.
	 Product Stewardship: Demonstrate commitment of all signatories.

4 PROJECT DESCRIPTION

Martin Brower proposes to operate a distribution facility at Lots 5 and 6, Corner of Horsley Drive and Cowpasture Road, Wetherill Park. The development will occupy approximately 5.6 hectares of land within easy access to Sydney's primary motorways (the M7, M4 and M5) and is located within Fairfield City Council Local Government Area.

A copy of the current masterplan is appended to this document (Appendix A).

4.1 Overview of Proposed Development

The development will comprise a distribution facility that receives palletised goods, loads outbound palletised goods, and delivers direct to customers. The products will be primarily made up of food and packaging in three temperature zones: frozen, chill and ambient.

The facility will hold between 6,500 to 10,000 pallets in the facility. A breakdown by product type is provided below:

•	Ambient food products in corrugate packaging (liquid and solid)	21%
•	Ambient paper and plastic products in corrugate packaging	26%
•	Ambient hard goods (paper, plastic or metal) in corrugate packaging	25%
•	Chilled food products (fresh and packaged) in corrugate packaging	8%
•	Frozen food products in corrugate packaging	20%

The operation will not store or ship out any polystyrene products.

4.1.1 Development Schedule

The development schedule for Lots 5 and 6 are presented below in **Table 3**.

Table 3 Horsley Drive Business Park Lots 5 and 6 Development Schedule

Site Description	Unit	Number
Site Area	sqm	57,569
Warehouse	sqm	15,427
Two Storey Office	sqm	3,132
Total Building Area	sqm	18,559
Site Coverage	%	32.4
Car parking	spaces	250

5 CONSTRUCTION WASTE MANAGEMENT

Demolition and construction stages of developments have the greatest potential for waste minimisation.

The building construction will follow bulk earthworks and site preparatory works that are subject to a separate Development Application and therefore all construction waste associated with this stage of the development is not considered further in this report.

Key construction activities will include:

- construction of multiple warehouse structures and distribution-related facilities across the site;
- construction of the internal access road that will be capable of accommodating both heavy and light vehicles;
- construction of lead-in services including electricity, sewer and potable water; and
- construction of a new traffic driveway from the Estate access road to provide entry into the Site.

5.1 Waste Streams and Classifications

The development is likely to generate the following broad waste streams:

- demolition wastes;
- excavation material;
- construction wastes;
- plant maintenance waste;
- packaging waste;
- work compound (on-site employee) waste; and
- waste water.

Possible waste types along with their waste classification are provided below in Table 4.

Table 4 Potential Waste Generation and EPA Classifications

Waste Types	NSW Classification	Proposed Reuse / Recycling / Disposal Method
Construction		
Steel reinforcing, other metal (eg wire mesh)	General solid (non-putrescible) waste	Off-site recycling
Conduits and pipes	General solid (non-putrescible) waste	Off-site recycling
Timber formwork	General solid (non-putrescible) waste	Reuse on-site or off-site recycling
Metals and bulk electrical cabling	General solid (non-putrescible) waste	Off-site recycling
Plasterboard	General solid (non-putrescible) waste	Off-site recycling or disposal
Bricks	General solid (non-putrescible) waste	Off-site recycling
Glass	General solid (non-putrescible) waste	Off-site recycling
Light bulbs	Hazardous waste	Off-site recycling
Stormwater run-off	Liquid waste	Collection via the erosion and sediment control system and treated in accordance with erosion and sediment control plans

Waste Types	NSW Classification	Proposed Reuse / Recycling / Disposal Method
Plant Maintenance		
Empty oil and other drums / tins (e.g. fuel, chemicals, paints, spill clean ups)	Hazardous waste if the containers were previously used to store Dangerous Goods (Class 1, 3, 4, 5 or 8) and from which residues have not been removed by washing or vacuuming. General solid (non-putrescible) waste if the containers have been cleaned by washing or vacuuming.	Transport to comply with the transport of Dangerous Goods Code applies in preparation for off-site recycling or disposal at licensed facility. (Note: Discharge to sewer subject to Trade Waste Agreement with Sydney Water.)
Air and oil filters and rags	General solid (non-putrescible) waste	General solid (non-putrescible) waste
Batteries	Hazardous waste	Off-site recycling
Packaging		
Packaging materials, including wood, plastic (including stretch wrap or LLPE), cardboard and metals	General solid (non-putrescible) waste	Off-site recycling
Wooden crates	General solid (non-putrescible) waste	Reused for similar projects, returned to suppliers, or off-site recycling
Work Compound and Associated Offices		
Recyclable beverage containers (glass and plastic bottles, aluminium cans, tin cans)	General solid (non-putrescible) waste	Co-mingled recycling at off-site licensed facility
Clean paper and cardboard	General solid (non-putrescible) waste	Paper and cardboard recycling at off-site licensed facility
General domestic waste generated by workers (soiled paper and cardboard, food stuffs, polystyrene)	General solid (non-putrescible) waste mixed with putrescible waste	Disposal at landfill
Pump-out waste and septage (sewage)	Liquid (trade) waste	Off-site disposal at licensed facility or disposal direct to sewer where arranged with Sydney Water

For further information on how to determine a waste's classification, refer to the EPA's *Waste Classification Guidelines* (2014).

5.2 Construction Waste Generation Rates

The Construction Site Manager will need to specify the types and quantities of wastes produced during construction and on this basis, the numbers and capacity of skip bins can be determined.

A guide/estimate of the potential waste percentages is provided based on published waste generation rates for construction and demolition projects, as indicated in **Table 5**. These figures have been referenced from a number of sources including the Inner Sydney Waste Board's Waste Planning Guide for Development Applications (1998), Victoria's Ecorecycle Waste Wise Events toolkit, the UK's WRAP composition and conversion factors and the UK Department of Environment, Food and Rural Affairs (DEFRA) conversion factors. Conservative estimates have been made where indicative waste compositions were not available.

Revision 2 Page 12

Table 5 **Guideline to Waste Composition and Volumes - Construction**

Material	Estimated Waste %	Conversion Factors (Density) tonne per m ³
Hard Material	32%	1.2
Timber	24%	0.3
Plastics	15%	0.13
Cement sheet	9%	0.5
Gy psum material	6%	0.2
Metals	6%	0.9
Paper/card	4%	0.1
Vegetation	3%	0.15
Soil	1%	1.6
Other	0.3%	0.3

Source: Sustainability Victoria Waste Wise Tool Kit (accessed 2013)

The UK DEFRA and the UK Building Research Establishment (BRE) have developed a number of benchmark indicators to help determine approximate tonnages of waste produced during various construction projects including civil engineering and commercial retail works. The benchmarks include Environmental Performance Indicators (EPI) which measure the volume (cubic metres, m³) of waste produced per 100 square metres (m²).

The EPI indicators provided in Table 6 have been used for the purposes of this WMP to estimate the amounts of demolition and construction wastes that could be generated by the Project.

Table 6 **Environmental Performance Indicator for Waste Volumes from New Developments**

Project Type	Average Volume (m³) of Waste per 100 m²
Residential	17.7
Public Buildings	23.8
Leisure	15.6
Industrial Buildings	14
Healthcare	18.1
Education	19.8
Commercial Other	16.9
Commercial Offices	20.4
Commercial Retail	22.1
Civil Engineering	28.1

5.2.1 **Estimation of Waste Volumes**

The estimated waste volumes for the overall development area are presented in Table 7 and Table 8. The waste arisings are based on the EPI estimates presented above in Table 6. Actual waste tonnage and composition will vary however this estimate is provided to inform potential on-site or off-site re-use and recycling opportunities.

Table 7 Estimated Waste Generation for the Development

Proposed Land Use	Area (m2)	Estimated Construction Waste Generation (m3)
General business (office)	3 ,132	639
Storage or distribution	15,427	2,160
Hard landscaping	31,810	4,201
Car parking	3,600	560
Soft landscaping	3,600	0
Total	57,569	7,560

^{1.} Assumes no waste generated by soft landscaping

Table 8 Estimated Waste Volumes and Materials for the Development

Material	Split (%)	Waste (m³)	Conversion factor	Waste (tonnes)
Hard material	40%	3,024	1.2	3,629
Timber	16%	1,210	0.3	363
Plastics	7%	529	0.13	69
Cement sheet	10%	756	0.5	378
Gypsum material	14%	1,058	0.2	212
Metals	8%	605	0.9	544
Paper / card	2%	151	0.1	15
Bio-organic	2%	151	0.15	23
Soil	0%	0	1.6	0
Chemicals / paint	1%	76	0.3	23
Total	100%	7,560		5,255

It is estimated that more than 70% of the predicted construction waste arisings from each Lot can be re-used (on-site or at another development) or recycled off-site. The NSW target for construction and demolition waste recycling is 75% (increasing to 80% by 2021-22)¹.

5.3 Waste Avoidance Measures

The Construction Site Manager will identify opportunities for waste avoidance by:

- selecting construction materials taking into consideration to their long lifespan and potential for reuse:
- ordering materials to size and ordering pre-cut and prefabricated materials;
- reuse of formwork (where possible);
- planned work staging;

reducing packaging waste on-site by returning packaging to suppliers where possible, purchasing
in bulk, requesting cardboard or metal drums rather than plastics, requesting metal straps rather
than shrink wrap and using returnable packaging such as pallets and reels;

¹ NSW Waste and Avoidance Resource Recovery Strategy 2014-21

- careful on-site storage and source separation;
- subcontractors informed of site waste management procedures; and
- coordination and sequencing of various trades.

The Construction Site Manager should also advise on material selection for the reduction of embodied energy and resource depletion. This includes the use of recycled concrete and steel, the reduction of PVC use, the use of low volatile organic compounds (VOC) paints and adhesives, and the use of post-consumer reused timber or Forest Stewardship Council (FSC) certified timber. Designs enabling disassembly and reuse of materials are also desirable. Final material selection will be made with consideration for the Ecologically Sustainable Design strategy for the site.

The following measures will also be completed to improve onsite waste management and to provide more reliable figures:

- record waste generated and disposal methods used during the construction;
- conduct waste audits of current projects;
- compare projected waste quantities with actual waste quantities produced during the construction period;
- review at past waste disposal receipts; and
- record this information to help in waste estimations for future waste management plans.

5.4 Re-use, Recycling and Disposal

Effective management of construction materials and demolition/construction waste, including options for reuse and recycling where applicable and practicable, will be conducted.

Only project wastes that cannot be cost effectively reused or recycled are to be sent to landfill or appropriate disposal facilities.

The following procedures are to be implemented:

- all solid waste timber, brick, concrete, rock that cannot be reused or recycled will be taken to an appropriate landfill site and disposed of in an approved manner;
- all metals will be recycled where economically viable;
- waste oil will be recycled or disposed of in an appropriate manner;
- all asbestos, hazardous and/or intractable wastes are to be disposed of in accordance with Workcover Authority and EPA requirements;
- washdown equipment/plant/machinery and concrete delivery trucks within a specified, appropriately bunded, washdown bay or return to the batching plant before washing out. Liquid waste is often produced from the washing down of plant and apparatus. There may be a local sewer that this waste water can be connected to; alternatively, this could be transferred into a localised waste water treatment facility or plant;
- completion of refuelling activities in designated areas with appropriate spill containment measures to avoid overspill to sensitive areas;
- provision of portable, self-contained toilet and washroom facilities at the site ensuring these units are regularly emptied and serviced by a suitably licensed contractor;
- where applicable, provide coloured, clearly labelled coordinated and easily accessible, comingled and paper/cardboard recycling bins on-site for employee use nearby common areas for large work compounds/work sites;
- dispose of general waste via a council approved system; and

• investigate any opportunities for materials exportation and reuse with other local construction operations. This will have two benefits: minimising energy through reduction of material reprocessing, encouraging material reuse.

5.4.1 Site Specific Procedures

The Construction Site Manager will also consider implementation of the following procedures:

- all used crates will be stored for reuse unless damaged;
- all cardboard waste is to be recycled via on-site recycling compactors which shall be collected by an appropriate recycling contractor;
- all glass and metals that can be economically recycled will be;
- all re-enforcing mesh to be utilised within the construction stages of the construction;
- colour bond roof material off cuts to be stockpiled on site for reuse or recycling;
- waste concrete will be disposed of at a crushing/recycling plant where practicable;
- waste bricks will be crushed and utilised on site. All half/damaged bricks and blacks will be stored
 on site to be removed for offsite crushing and recycling;
- excavation material will be reused on-site where possible with all excess reused on other projects or sold;
- all other solid waste including bitumen paving, tile, timber, rock and soil will be taken to an
 appropriate materials recycling facility/landfill site and processed in an approved manner; and
- all garbage will be disposed of via a council approved system.

5.5 Waste Storage and Servicing

For construction stages, consider minimum dedicated skips for:

- timber;
- plasterboard/gyprock;
- concrete;
- bricks;
- steel/scrap metal;
- general waste; and
- other waste (i.e. for the collection of materials that may be re-used on future projects).

Separate receptacles for the safe disposal of hazardous waste types (i.e. light bulbs, batteries, etc) will also be provided where applicable.

Where possible, employee co-mingled recycling bins will be provided nearby common areas at work compounds/work sites for plastic and glass bottles, soft drink cans, aluminium and tin cans to ensure these items do not end up at landfill. Specialised bins for cigarette butts should also be provided outside lunchrooms and nearby common areas at work compounds/work sites.

All site generated building waste collected in the skip bins will leave the site and be deposited in the approved recycling centre, transfer station or landfill site.

The frequency of the waste removal will, in most cases, be dictated by the volume of material being deposited into each of the dedicated skips.

Skips are to be checked on a daily basis by the Construction Site Manager to ensure that they are not overflowing. If skips are reaching capacity, removal and replacement must be organised with the next 24 hours. All skips leaving the project site will be covered with a suitable tarpaulin to ensure that the spillage of wastes from the skips whilst in transit is eliminated.

All waste collection activities for demolition and construction are to be conducted between 7am and 6pm daily.

5.5.1 Space and Amenity

Waste storage areas will be accessible and allow sufficient space for storage and servicing requirements. The storage areas will also be flexible in order to cater for change of use throughout the Project.

Where space is restricted, dedicated stockpile areas are to be delineated on the site, with regular transfers to dedicated skip bins for sorting. The positions of the designated waste holding areas on site will change according to building works and the progression of the development, but must consider visual amenity, OH&S and accessibility in their selection.

All waste placed in stockpile areas/skips for disposal or recycling shall be adequately contained to ensure that the waste does not fall, blow, wash or otherwise escape from the site. Appropriate siting of waste stockpile locations will take into account slope and drainage factors to avoid contamination of stormwater drains during rain events.

Waste containers are to be kept clean and in a good state of repair.

5.5.2 Contaminated/Hazardous Waste

During the construction phases of the development, there must be a commitment to engage qualified and certified contractors to remove all contaminated/hazardous materials (e.g. asbestos) and dispose of all contaminated/hazardous waste at an appropriately licenced facility, where applicable.

In the event that any contaminated or hazardous materials are unexpectedly uncovered during demolition or excavation works, the Construction Site Manager is to stop work immediately and contact the relevant hazardous waste contractor prior to further works being undertaken in the area.

Contaminated material stockpiled on site will be minimised as far as possible and should be stored on HD polythene liner, in a bunded location which is protected from inclement weather. Sediment fences should also be installed around the base of stockpiles and the stockpiles should be covered. Where excavated material requires validations, samples should be taken for NATA laboratory testing as per the requirements of the contamination assessment prior to restoration works, backfilling exercises and disposal.

Any trucks carrying contaminated materials should be securely and completely covered immediately after loading the materials, to prevent windblown emissions and spillage.

Decontamination of all equipment prior to demobilisation from the site is important in order that contaminated materials are not spread off-site. This should be achieved using dry cleaning methods as far as practicable and collection of material for disposal. The following additional measures should be employed on site:

- as far as possible, all tracked surfaces to be kept free of contaminated material; and
- all equipment should be cleaned in an area contained contaminated soils so that they remain
 within the area, or on a lined surface and collected spoil should be treated as contaminated
 material.

5.5.3 Liquid Waste / Stormwater / Wastewater Management

Any liquid wastes or dangerous goods wastes generated by the construction activities (e.g. due to damage or leakage of containment) will be disposed of by a suitably qualified contractor to an appropriately licensed disposal facility.

Wastewater storage tanks (where applicable) will be carefully monitored to ensure overflow does not occur and no liquid wastes or wash down waters will be disposed of via the stormwater drainage system.

Stormwater runoff will be collected via the erosion and sediment control system specified in the Civil Engineering Report and treated in accordance with erosion and sediment control plans.

5.5.4 Spills Management

Spills on the worksite are most likely to involve fuel, hydraulic oil or engine oil spilled from plant items, and paints and solvents.

If a spillage occurs, site staff will immediately identify the spilled materials and notify the Construction Site Manager. Then contain the spill as soon as possible so it doesn't spread.

Containment measures for spillages will be provided at appropriate locations and in close proximity to staff car park areas, dangerous goods stores areas and main Project work areas (e.g. a spill kit containing non-combustible absorbent material).

Material Safety Data Sheets (MSDS) will also be located nearby spill kit areas for advice on spillage clean-up and disposal.

5.6 Signage

Standard signage will be posted in all storage/waste collection areas and all skips/drums/bins are required to be labelled correctly and clearly to identify materials stored within.

Where applicable, general and co-mingled recycling bins placed nearby staff tearoom/break areas will be colour coded with clear labels.

5.7 Training and Awareness

All staff (including sub-contractors and site staff) employed during the construction phases of the development must undergo induction training regarding waste management for the development site.

Induction training is to cover, as a minimum, an outline of the WMP including:

- legal obligations;
- emergency response procedures on site;
- waste storage locations and separation of waste;
- implications of poor waste management practices;
- · correct use of General Purpose Spill Kit; and
- details of responsibility and reporting (including identification of personnel responsible for waste management and individual responsibilities).

It is the responsibility of the Construction Site Manager or Environmental Management Representative (EMR) to notify Council of the appointment of waste removal, transport or disposal contractors.

5.8 Monitoring and Reporting

Records of waste volumes recycled, reused or contractor removed are to be maintained and reported to the Principal Contractor on a quarterly basis. Additionally, dockets/receipts verifying recycling/disposal in accordance with the WMP must be kept.

Daily visual inspections of waste storage areas will be undertaken by site personnel and inspection checklists/logs recorded for reporting to the Construction Site Manager or EMR on a weekly basis or as required. These inspections will be used to identify and rectify any resource and waste management issues.

Waste audits are to be carried out by the EMR to gauge the effectiveness and efficiency of waste segregation procedures and recycling/reuse initiatives. Where audits show that the above procedures are not carried out effectively, additional staff training will be undertaken and signage re-examined.

All environmental incidents are to be dealt with promptly to minimise potential impacts. An incident register must be maintained on-site at all times and include the contact details of the 24 hour EPA Pollution line. Likely incidents to occur during the construction phase of the Project may involve fuel or chemical spills, seepage of mishandling of hazardous waste, or unlicensed discharge of pollutants to environment.

5.9 Roles and Responsibilities

All personnel have a responsibility for their own environmental performance and compliance with all legislation. It will be the responsibility of the Contractor to implement the WMP, and an employee responsibility to ensure that they comply with the guideline at all times.

Where possible, an Environmental Management Representative (EMR) should be appointed for the Project. Suggested roles and responsibilities are provided below.

Table 9 Recommended Roles and Responsibilities

Role	Responsibility
Construction Site Manager	Ensuring plant and equipment are well maintained. Ordering only the required amount of materials. Keeping materials segregated to maximise reuse and recycling. Ultimately responsible for routinely check waste sorting and storage areas for cleanliness, hygiene and OH&S issues, contaminated waste materials, and also ensuring that all monitoring and audit results are well documented and carried out as specified in the WMP.
Environmental Management Representative (EMR)	Approaching and establishing the local commercial reuse of materials where reuse on-site is not practical. Establishing separate skips and recycling bins for effective waste segregation and recycling purposes. Training and awareness of the requirements of the WMP and specific waste management strategies adopted for the Project. Contaminated waste management and approval of off-site waste transport, disposal locations and checking licensing requirements. Approval of off-site waste disposal locations and checking licensing requirements. Assessment of suspicious potentially contaminated materials, hazardous materials and liquid wastes. Monitoring, inspection and reporting requirements.

Daily visual inspections of waste storage areas may be delegated to other on site staff. All subcontractors will be responsible for ensuring that their work complies with the WMP through the site induction and contract engagement process.

6 OPERATIONAL WASTE MANAGEMENT

Ineffective waste management for commercial premises can lead to environmental pollution, offensive odours, litter, attraction of vermin and occupational safety and hygiene problems.

Effective waste management reduces costs through the reuse of resources and minimisation of fees associated with removal, transportation and disposal of waste, and improves environmental outcomes locally, regionally and globally.

Effective waste management is achieved through the implementation of a WMP for the operational life of the development.

6.1 Waste Streams and Classifications

The operation of the Project will generate the following broad waste streams:

- general waste;
- packaging wastes (cardboard, paper, plastic, pallets);
- office wastes;
- amenity wastes;
- maintenance wastes; and
- truckwash waste water.

Potential waste types along with their waste classification are provided below in **Table 10**. It is noted that no manufacturing is undertaken on site and as such the facility will not generate waste water requiring collection or treatment as a result of warehouse operations (other than amenity and maintenance related waste water). Refer to **Section 6.4.2** for general conditions related to liquid wastes and truck wash down waters and **Section 6.4.3** for stormwater treatment.

Table 10 Potential Waste Generation and EPA Classifications - Operational

Waste Types	NSW Classification	Proposed Reuse / Recycling / Disposal Method
General Operations		
General garbage (including non-recyclable plastics)	General solid (putrescible) waste	Disposal at landfill
Recyclable beverage containers (glass and plastic bottles, aluminium cans, tin cans)	General solid (non-putrescible) waste	Co-mingled recycling at off-site licensed facility
Paper	General solid (non-putrescible) waste	Off-site secure shredding and recycling
Plastic packaging materials (including stretch wrap or LLPE)	General solid (non-putrescible) waste	Baled and sent for off-site recycling
Bulk cardboard	General solid (non-putrescible) waste	Baled and sent for recycling at off-site licensed facility
Wooden crates / pallets	General solid (non-putrescible) waste	Reused for similar projects, returned to suppliers, or off-site recycling
Maintenance		
Spent Smoke Detectors ¹	General solid (putrescible) waste OR Hazardous waste (some Commercial varieties)	Disposal at landfill OR offsite disposal at licensed facility

Waste Types	NSW Classification	Proposed Reuse / Recycling / Disposal Method
Light bulbs	Hazardous waste	Off-site recycling
E-waste (e.g. chillers and freezers)	Hazardous waste	Off-site recycling
Batteries	Hazardous waste	Off-site recycling
Maintenance waste (i.e. empty oil / paint drums etc)	Hazardous waste if the containers were previously used to store Dangerous Goods (Class 1, 3, 4, 5 or 8) and from which residues have not been removed by washing or vacuuming. General solid (non-putrescible) waste if the containers have been cleaned by washing or vacuuming.	Transport to comply with the transport of Dangerous Goods Code applies in preparation for off-site recycling or disposal at licensed facility. (Note: Discharge to sewer subject to Trade Waste Agreement with Sydney Water.)
Air -conditioning parts and filters	General solid (non-putrescible) waste	Disposal to landfill
Maintenance waste (i.e. cleaning chemicals, solvents, area wash downs)	Hazardous waste if the containers store Dangerous Goods (Class 1, 3, 4, 5 or 8).	Transport to comply with the transport of Dangerous Goods Code applies in preparation for off-site recycling or disposal at licensed facility. (Note: Discharge to sewer subject to Trade Waste Agreement with Sydney Water.)1
Truckwash Waste Water	Liquid (trade) waste	Collected on-site prior to disposal to sewer via trade waste agreement with Sydney Water.
Amenities		
Grey water (from bathrooms)	Liquid waste	A new sewer connection to the existing sewer submain in Newton Road will be constructed as part of the infrastructure works.
Sewage	Liquid (trade) waste	A new sewer connection to the existing sewer submain in Newton Road will be constructed as part of the infrastructure works.
Sanitary Waste	General solid waste (putrescible)	Contractor disposal at licensed facility

Source: http://www.environment.nsw.gov.au/waste/envguidlns/index.htm

Note 1: The Australian Radiation Protection and Nuclear Safety Agency (ARPANSA) require that when more than 10 smoke alarms (particularly americium-241 sources) are collected for bulk disposal they must be treated as radioactive waste and the requirements of the National Health and Medical Research Council's Code of practice for the near-surface disposal of radioactive waste in Australia (1992) must be met. Contact ARPANSA for more information. http://www.arpansa.gov.au/radiationprotection/factsheets/is_smokedetector.cfm

For further information on how to determine a waste's classification, refer to the EPA's Waste Classification Guidelines (2014).

6.1.1 Anticipated Waste Generation Rates for Operational Development

Table 11 provides a summary of the anticipated weekly waste generation for the operational development. These estimates are based on other similar sized facilities.

Table 11 Anticipated Weekly Waste Generation

Waste type	Waste (tonnes)	Conversion factor	Waste (m3)
General waste	2	0.15	15
Cardboard	1	0.13	8
Paper	1	0.1	5
Plastic	2	0.156	13
Pallets	15	0.156	96
Total	21	-	137

It is recommended that scheduled waste audits be undertaken approximately one month into the operational phase of the development to quantify actual waste generation rates generated by the development.

The assessment of generated waste volumes will also be influenced by management and employee attitude to recycling and disposal.

6.2 Waste Avoidance, Re-use and Recycling Measures

Martin Brower is committed to moving the management of resources up the waste hierarchy and offers clients a number of services to reduce the overall carbon footprint of its business. Some examples of how the reduction, re-use and recycling of waste can be achieved are listed below.

6.2.1 Waste Avoidance

Waste avoidance measures may include:

- provision of take back services to clients to reduce waste further along the supply chain;
- re-work/re-packaging of products prior to local distribution to reduce waste arisings;
- review of packaging design to reduce waste but maintain 'fit for purpose'; and
- investigating leased office equipment and machinery rather than purchase and disposal.

6.2.2 Re-use

Establish systems with in-house and with supply chain stakeholders to transport products in reuseable packaging where possible.

6.2.3 Recycling

Recycling opportunities include:

- development of 'buy recycled' purchasing policy;
- flatten or bale cardboard to reduce number of bin lifts required; and
- providing recycling collections within each of the offices (e.g. plastics, cans and glass).

Over time the development will also generate waste fridges and chillers. These items will either be leased and therefore the retailer will replace and recycle end of life items or Martin Brower will arrange for removal and recycling of the items.

6.3 Waste Storage and Servicing Requirements

6.3.1 Waste Collection Area Location

A dedicated waste and recycling storage area has been identified in the south eastern corner of the building (see **Appendix A**) where the recycling bins, garbage bins, and cardboard and plastic bales will be stored prior to collection. Sufficient clearance has been provided to enable collection vehicles to access the bin storage area. Where possible collection times should not coincide with peak operational delivery schedules however all areas identified will not interfere with operational truck movements.

6.3.2 Waste Collection Area Requirements

The construction of garbage areas, rooms and equipment are to comply with BCA (Building Code of Australia) requirements and Australian Standards.

Waste/recycling storage areas will be constructed of an adequate size to accommodate all waste bins (up to 15 x 1,000 litre bins) and recycling bales associated with the development.

Doors/gates to the storage area will be able to be opened from both the inside and outside and wide enough to allow for easy passage of waste/recycling containers.

Sufficient space will be provided for the segregation and storage of varying waste types including provision for the collection of fluorescent tubes, smoke detectors, e-wastes and other recyclable resources.

Sufficient space will also be provided for reuse items such as crates and pallets for occupational safety purposes.

6.4 Special Wastes

6.4.1 Contaminated / Hazardous Wastes

- All contaminated and hazardous wastes (i.e. fluorescent tubing, batteries, e-wastes and smoke detectors) should be recycled at an appropriately licensed facility.
- E-waste (electronic waste such as computers, mobile phones, printer toners and ink cartridges) and batteries contain heavy metal contaminants and should be recycled at an appropriately licensed recycling facility.
- Refrigeration and air conditioning units will be sent for recycling once they reach the end of lease or end of life.
- Commercial-use smoke detectors should be returned to the supplier for disposal (it is a condition
 of the supplier's licence to sell smoke detectors) and not disposed of with general landfill waste
 as they contain small amounts of radioactive material. Contact the supplier and/or the EPA for
 information on how to return used smoke detectors.

6.4.2 Liquid Waste

 Liquid, semi-liquids or moist substances will not be placed in waste containers, unless securely wrapped or contained to prevent the substance from leaking.

- Any liquid wastes or dangerous goods wastes generated by the development (e.g. due to damage or leakage of containment) should be disposed of by a suitably qualified contractor to an appropriately licensed disposal facility.
- No liquid wastes or wash down waters (i.e. from the truckwash bay) will be disposed of via the stormwater drainage system. All wash down water will be collected on site prior to disposal to sewer via a trade waste agreement with Sydney Water.

6.4.3 Stormwater Treatment

Car parking areas must drain to a stormwater treatment device capable of removing litter, oil, grease and sediment prior to discharge to the stormwater system.

All wastewater and stormwater treatment devices are required to be regularly maintained and cleaned to ensure these devices remain effective, with all solid and liquid wastes collected from these devices disposed of in accordance with this WMP and the POEO Act.

6.4.4 Spills Management

Containment measures for spillages should be provided at appropriate locations and in close proximity to staff car park areas, dangerous goods stores areas and main warehouse operation areas (e.g. a spill kit containing non-combustible absorbent material). Material Safety Data Sheets (MSDS) should also be located nearby spill kit areas for advice on spillage clean up and disposal.

6.4.5 Signage

Education and communication must be regular and ongoing to overcome the transient nature of contractors and visiting staff members. The main signage aspects to consider are:

- garbage and recycling bins must be clearly and correctly labelled at all times;
- waste storage areas must have clear signage instructing cleaners and tenants how to correctly separate (if required);
- the location of, and directions to, waste storage areas must be well signposted;
- all hazards or potential dangers associated with the waste facilities should be clearly identified, especially those linked to compaction or other waste handling equipment; and
- emergency contact information should be displayed in case there are any issues with the waste and recycling systems/services in the building.

All signage should conform to the relevant Australian Standard and the NSW EPA's standard recycling signs. The design and use of safety signs for waste rooms and enclosures should comply with AS 1319 Safety signs for the occupational environment. Australian Standards are available from the SAI Global Limited website (www.saiglobal.com).


6.4.6 Contract Clauses

Waste collection contracts and cleaning contracts should include clauses relating to waste servicing requirements. Lease agreements should also outline and enforce proper use of waste facilities.

Refer to Appendix H of the EPA's Better Practice Guidelines (2012) for example clauses.

Appendix A

Report Number 610.15399-R2 Page 1 of 1 HORSLEY DRIVE MASTERPLAN



POST, POWDERCOAT

BLACK PAINT

PALLISADE FENCE

POWDERCOAT

PROVISION FOR

PAD LOCK

GATE CATCH AND

FINISHED

CATCH

- PALLISADE FENCE - 1:50 @ B1

2500

SCALE - 1:50 @ B1

PERPENDICULAR PARKING DETAILS

ALL LEVELS ARE INDICATIVE AND SHOULD BE READ IN

CONJUNCTION WITH CIVIL ENGINEER'S DRAWINGS.

ALL DRIVEWAY, PARKING SPACE AND AISLE WIDTH

FOR FINAL LEVELS OF ALL EARTHWORKS.

IN ACCORDANCE WITH AS.2890.1 2004 &

ALL LEVELS ARE TO BE +/- 1000mm.

AS.2890.2 2002

AND PADLOCK

TYPICAL LINE MARK

SPACE

CAR PARKING


DO NOT SCALE DRAWINGS. VERIFY ALL DIMENSIONS ON SIT © 2004 AUSTRALAND HOLDINGS LIMITED. This drawing is confidential and is subject to copyright. It may not be copied, used, reproduced or transmitted in any way or in any form

without the e	express permission of Australand Holdings Limite	ed.
REVISION	DESCRIPTION	DATE
P1	PRELIMINARY ISSUE	30.06.15

DEVELOPMENT AREAS

SITE AREA	57 558 SQM
WAREHOUSE	15 427 SQM
INCLUDES:	
DRY STORE	6 315 SQM
AMBIENT STAGING	593 SQM
TOMATO ROOM	53 SQM
RECYCLING	93 SQM
CHILLER	604 SQM
FREEZER	3 140 SQM
RECEIVING STAGING	1 158 SQM
DESPATCH STAGING	2 475 SQM
RECEIVING OFFICE	116 SQM
VESTIBULE	308 SQM
BATTERY CHARGE ROOM	340 SQM
PLANT ROOMS 1& 2	232 SQM
TWO STOREY OFFICE	3 132 SQM
TOTAL BUILDING AREA	18 559 SQM

EFFICIENCY 32.4%





1 HOMEBUSH BAY DRIVE BUILDING C, LEVEL 3 RHODES NSW 2138 FAX 02 9767 2908

PO BOX 3307 RHODES NSW 2138

PROJECT

MARTIN BROWER WAREHOUSE FACILITY/ DISTRIBUTION CENTRE

PROPOSED LOT 5, CORNER OF HORSLEY DRIVE & COWPASTURE ROAD, HORSLEY PARK

DRAWING TITLE SITE PLAN

1:600 @ B1

DRAWING NUMBER

MB-WSPT-DA-003 P1