


Appendix 17
**Engineering Plans of the Proposed
Development**





35 - 37 Frank Street, Wetherill Park



Bell Consultancy Team

**Resource Co.
35 - 37 Frank Street
Wetherill Park**

Drawing List

| Drawing Number | Drawing Title |
|----------------|---|
| 101 | Cover Sheet |
| 102 | Notes and Legends |
| 103 | General Arrangement Plan |
| 104 | Sediment and Erosion Management Control Concept Plan |
| 105 | Sediment and Erosion Management Details |
| 106 | Site Cross Sections - 1 of 2 |
| 107 | Site Cross Sections - 2 of 2 |
| 108 | Bulk Earthworks Layout Plan |
| 109 | Siteworks and Stormwater Drainage Plan - Sheet 1 of 2 |
| 110 | Siteworks and Stormwater Drainage Plan - Sheet 2 of 2 |
| 111 | Retaining Wall Plan |
| 112 | Stormwater Drainage Catchment Plan |

Development Application Drawings

MMD-364729-C-DR-DA01-101 P3
Date: 27.01.16

| General Notes | |
|---------------|--|
| GN1 | All workmanship and materials shall comply with the National Construction Code of Australia and the relevant current Australian Standards. |
| GN2 | Any discrepancies, omissions or errors shall be reported to the Superintendent for clarification before proceeding with the work. |
| GN3 | Do NOT scale measurements from the drawings. |

| Existing Services Notes | |
|-------------------------|---|
| ES1 | Existing services have been plotted from supplied data and as such their accuracy cannot be guaranteed. It is the responsibility of the contractor to establish the location and level of all existing services prior to the commencement of any work. Any discrepancies shall be reported to the superintendent. |
| ES2 | The contractor shall allow for the capping off, excavation and removal if required of all redundant existing services in areas affected by works within the contract area, as shown on the drawings unless directed otherwise by the superintendent. |
| ES3 | The contractor shall ensure that at all times services to all buildings not affected by the works are not disrupted. |
| ES4 | If required, the contractor shall construct temporary services to maintain existing supply to buildings remaining in operation during works to the satisfaction and approval of the superintendent. Once diversion is complete and commissioned the contractor shall remove all such temporary services and make good to the satisfaction of the superintendent and the relevant service authority. |
| ES5 | Interruption to supply of existing services shall be done so as not to cause any inconvenience to the principal. The contractor is to gain approval from the superintendent for time of interruption - the contractor is responsible for all liaison. |
| ES6 | All branch gas and water services under driveways and brick paving shall be located in Ø80mm uPVC sewer grade conduits extending a minimum of 500mm beyond the edge of paving. |
| ES7 | Clearance and cover requirements shall be obtained from the relevant service authority before commencement of works and shall be adhered to at all times. |
| ES8 | Care is to be taken when excavating near existing services. No mechanical excavations are to be undertaken over telecom or electrical services. Hand excavate in these areas only. |

| Work As Executed | |
|------------------|--|
| WX1 | Upon completion of the new works, the following shall be submitted prior to any Certification being issued: <ul style="list-style-type: none"> Work-as-Executed plans based on the approved stormwater drainage plans prepared by a registered surveyor to verify that all as-built alignments and levels which are constructed in accordance with design requirements. Any minor changes or variations to the approved plans should be highlighted in red on the approved engineering plans. Compaction test results shall be prepared by a geotechnical engineer and submitted on all stormwater drainage trenches ensuring that all trenches are backfilled to 98% standard to AS1289 at +2%-0% optimum moisture content. |
| WX2 | A qualified practitioner, with a certificate of attainment in NWP331A Perform Conduit Evaluation, shall undertake a closed circuit television (CCTV) inspection and then report on the condition of the entire as-built Council drainage pipelines after the completion of all works. No person is to enter any stormwater conduit without written approval from the superintendent. The camera and its operation shall comply with the following - <ul style="list-style-type: none"> The internal surface of the drainage pipe shall be viewed and recorded in a clear and concise manner. The CCTV camera used shall be capable to pan, tilt and turning at right angles to the pipe axis over an entire vertical circle to view the conduit joints. Distance from the manholes shall be accurately measured and displayed on the video. All pipe joints and defects are to be inspected by stopping movement and panning the camera to fully inspect the joint and/or defect. The inspection survey shall be conducted from manhole to manhole. The written report, together with a copy of the digital video footage of the pipelines shall be submitted to Council. Any defects identified from the CCTV and report shall be rectified by the applicant or the applicant's contractors to the satisfaction of Council's Engineers. |

| Concrete Notes | | | | | | | |
|---------------------------|--|---|------------------------------------|---|----------------------------|---------|--|
| General | | | | | | | |
| CN1 | Use "AS3972 - 2010 - General purpose and blended cements - Type GP" cement (UNO). | | | | | | |
| CN2 | All concrete shall be subject to project control sample and testing to AS3600 - 2009 - concrete structures. | | | | | | |
| CN3 | Consolidate all concrete, including footings and slabs on ground with mechanical vibrators. | | | | | | |
| CN4 | Cure all concrete as follows - <ul style="list-style-type: none"> keep surfaces continuously wet for 3 days, then prevent moisture loss for the next 4 days using polythene sheeting or wet hessian protected from wind and traffic, and then allow drying out. curing compounds may be used provided that they comply with AS3799 and they do not affect floor finishes. PVA-based curing compounds are NOT acceptable. | | | | | | |
| CN5 | Fix reinforcement as shown on drawings. The type and grade is indicated by a symbol as shown below - <table border="0" style="margin-left: 20px;"> <tr> <td>N</td> <td>hot rolled deformed bar, grade 500</td> </tr> <tr> <td>R</td> <td>plain round bar, grade 250</td> </tr> <tr> <td>SL / RL</td> <td>hard drawn wire fabric square or rectangular</td> </tr> </table> <p style="margin-left: 20px;">following this symbol a numeral indicates the specified diameter.</p> | N | hot rolled deformed bar, grade 500 | R | plain round bar, grade 250 | SL / RL | hard drawn wire fabric square or rectangular |
| N | hot rolled deformed bar, grade 500 | | | | | | |
| R | plain round bar, grade 250 | | | | | | |
| SL / RL | hard drawn wire fabric square or rectangular | | | | | | |
| CN6 | Provide bar supports or spacers to provide concrete cover as detailed to all reinforcement. | | | | | | |
| Concrete Pavements | | | | | | | |
| CN7 | Concrete mix parameters - <ul style="list-style-type: none"> maximum aggregate size 20mm flexural strength at 28 days = 3.5 MPa, F_c = 32 MPa, (UNO) flexural strength at 90 days = 3.85 MPa max water/cement ratio = 0.55 max shrinkage limit = 650 micron strains (AS1012.13-1992) min cement content = 300kg/m³ cement to be type "SL" (normal cement) to AS3972-2010 slump = 80mm | | | | | | |
| CN8 | Early age saw cutting ('softcut') or similar shall be used for initial saw cut. It is to be performed as soon as the concrete has hardened sufficiently, to prevent excessive chipping, spalling, or tearing regardless of time or weather conditions. | | | | | | |
| CN9 | Joint layout shall be as detailed on the plans. | | | | | | |
| CN10 | Provide 10mm wide expansion joints between all buildings, other structures and pavements. | | | | | | |
| CN11 | Bond breaker to be two (2) uniform coats of bitumen emulsion all over the exposed surface and on end. | | | | | | |
| CN12 | Dowels and tie bars to meet strength requirements of structural grade steel in accordance with AS ISO 1302 - 2005 - geometrical product specifications. Dowels and tie bars shall be - <ul style="list-style-type: none"> straight, to length specified, all dowels to be hot dip galvanised, sawn to length not cropped. | | | | | | |
| CN13 | Dimensions of sealant reservoir dependant on the sealant type adopted. Superintendent approval to be obtained for sealant and reservoir dimensions and detail proposed by the contractor. Refer to plans for typical arrangement and sealant. | | | | | | |
| CN14 | Prior to the placement of concrete in the adjacent slab, 'Ableflex' filler shall be adhered to the already cast and cleaned concrete face using an approved waterproof adhesive. Adhesive shall be liberally applied to the full face of the concrete slab to be covered by the filler, and on the full face of the filler to be adhered. | | | | | | |
| CN15 | The base course shall be kept moist (not wet) by sprinkling with water immediately prior to pouring the concrete. | | | | | | |
| CN16 | All work to be finished to satisfy its intended use as shown on the plans, and / or in accordance with the specification. | | | | | | |
| Kerbing Notes | | | | | | | |
| CN17 | All concrete kerbs to have a minimum characteristic compressive strength F _c =32MPa (UNO). | | | | | | |
| CN18 | All kerbs, dish drains, etc. to be constructed on 75mm minimum base course.(UNO on the Drawings) | | | | | | |
| CN19 | Kerb expansion joints shall be formed from 10mm 'Ableflex' (or approved equivalent) for the full depth of the section. | | | | | | |
| CN20 | Expansion joints shall be located at drainage pits, tangent points of curves and elsewhere at 12m maximum spacing (UNO). | | | | | | |
| CN21 | Tooled joints shall be min 3mm wide and located at maximum 3m spacing. | | | | | | |
| CN22 | Integral kerb joints shall match the location of the pavement jointing. | | | | | | |

| Stormwater Notes | |
|------------------|---|
| SW1 | For commercial or industrial sites - <ul style="list-style-type: none"> All Ø300mm to Ø600mm drainage pipes shall be Class 4 approved spigot and socket reinforced concrete pipes with rubber ring joints (UNO). All Ø675mm or larger drainage pipes shall be Class 3 approved spigot and socket reinforced concrete pipes with rubber ring joints (UNO). |
| SW2 | All drainage pipes less than or equal to Ø225mm shall be PVC-u DWV grade Class SN8 in accordance with AS/NZS 1260 : 2009 - PVC-u Pipes and Fittings for Drain, Waste and Vent Application with solvent welded joints. |
| SW3 | Equivalent strength fibrous reinforced concrete (F.R.C.) and / or high density polyethylene (H.D.P.E.) may be used subject to approval by the superintendent. |
| SW4 | All pipe junctions up to and including Ø450mm and tapers, shall be via purpose made fittings (UNO). |
| SW5 | Minimum grade to stormwater lines to be 1% (UNO). |
| SW6 | Contractor to supply and install all fittings and specials including various pipe adaptors to ensure proper connection between dissimilar pipework. |
| SW7 | All connections to existing drainage pits shall be made in a tradesman-like manner and the internal wall of the pit at the point of entry shall be cement rendered to ensure a smooth finish with no protrusions. |
| SW8 | All in-situ concrete pits to be 32Mpa minimum at 28 days. |
| SW9 | Pits and pipes in areas of salinity hazard shall have increased cover to any reinforcement. |
| SW10 | Precast concrete pits may be installed in lieu of cast in-situ pits, when pipe junctions are accommodated within the overall dimensions of the pit, and approved by the superintendent. |
| SW11 | Pits deeper than 1000mm shall have step irons installed in accordance with the local or statutory authority requirements. |
| SW12 | Bedding shall be Type H2 (UNO) for pipes not under pavements, and Type HS2 for pipes under pavements in accordance with AS/NZS 3725 : 2007 - Design for Installation of Buried Concrete Pipes. |
| SW13 | Backfill trench with sand or approved granular backfill to 300mm (min) above the pipe. Where the pipe is under pavements backfill remainder of trench to pavement subgrade with sand or approved gravel sub-base compacted in 150mm layers to 98% standard maximum dry density. The contractor is to ensure compaction equipment is appropriate for the pipe class used. |
| SW14 | Where stormwater lines pass under floor slabs DWV grade PVC-u rubber ring joints are to be used (UNO). |
| SW15 | Where subsoil drainage lines pass under floor slabs and vehicular pavements, unslotted PVC-u DWV grade Class SN8 pipe shall be used. |
| SW16 | Provide 3m length of Ø100mm subsoil drainage line or 200 'Nylux' strip drain surrounded with 150mm of 20mm blue metal or gravel, and wrapped in 'Bidim' A24 geotextile filter fabric or approved equivalent, at invert of incoming upstream pipe on each pit. |

| Civil Works Legend | |
|--------------------|-------------------------------------|
| ROAD No 1 | Road name / number |
| --- KO --- | Sawcut existing pavement |
| --- KG --- | Construct kerb only |
| --- DD --- | Construct kerb and gutter |
| --- DD --- | Construct dish drain |
| ⊗ | Transition kerb profile over 1.5m |
| ⊥ | Construct batter |
| ⊙ RW ⊙ | Construct reinforced retaining wall |
| --- | Limit of works |
| ▨ | Proposed Building |

| Siteworks Notes | |
|-----------------|---|
| SN1 | Datum : Australian Height Datum (AHD) Origin of levels : SSM 154595 RL 50.98 Origin of co-ordinates : Mapping Grid Of Australia (MGA) Survey prepared by : William L. Backhouse Suite 8, Brookhollow Ave, Baulkham Hills wb@backhouse.com.au / 02 9634-2866 |
| SN2 | The contractor must verify all dimensions and existing levels on site prior to commencement of work, and report any discrepancies to the superintendent. |
| SN3 | All existing services (including any not shown on the plans) must be accurately located in position and level prior to any excavation. Any discrepancies shall be reported to the superintendent. Minimum service clearances shall be maintained from the relevant service authority. |
| SN4 | The contractor shall arrange for all setting out by a registered surveyor. |
| SN5 | It is the contractors responsibility to notify the Department of Land and Property Information NSW, of any survey marks that will be destroyed in the construction of works. Contact Head Office on 1300 052 637 www.lpi.nsw.gov.au and http://scims.lpi.nsw.gov.au/status_report_frames.html |
| SN6 | The contractor shall obtain all regulatory authority approvals at their own expense. |
| SN7 | Where new works abut existing, the contractor must ensure that a smooth and even profile, free from abrupt changes is obtained. |
| SN8 | All disturbed areas shall be restored to their original condition, unless specified otherwise. |
| SN9 | Excavated trenches shall be compacted to the same density as the adjacent natural material. Any subsidence during the period to be rectified as directed by the superintendent. |
| SN10 | Any existing trees which form part of the final landscaping plan will be protected from construction activities in accordance with the landscape architect's details and / or by - Protecting them with barrier fencing or similar materials installed outside the drip line, ensuring that nothing is nailed to them, prohibiting paving, grading, sediment wash or placing of stockpiles within the drip line except under the following conditions - Encroachment only occurs on one side and no closer to the trunk than either 1.5m or half the distance between the outer edge of the drip line and the trunk, which ever is the greater, a drainage system that allows air and water to circulate through the root zone (eg a gravel bed) is placed under all fill layers of more than 300mm care is taken not to cut roots unnecessarily nor to compact the soil around them. |
| SN11 | Receptors for concrete and mortar slurries, paints, acid washings, light-weight waste materials and litter are to be employed as necessary. Disposal of waste shall be in a manner approved by the superintendent or as specified in the works contract. |

| Pavement Legend | |
|--|--|
| | Pavement Type 1 - Road Pavement For details refer to drawing 103. |
| | Pavement Type 2 - Carpark Pavement For details refer to drawing 103. |
| | Pavement Type 3 - Footpath Pavement |
| | Pavement Type 4 - Paving Refer to Landscape Architect's drawings for details of different paving treatment. |
| | Landscaping as per Landscape Architect's drawings |
| Note All pavements are Indicative only. To be confirmed by Geotechnical investigation, testing and design. | |

| Earthworks Notes | | | | | | | | | | | |
|---------------------------|--|----------|----------------------|----------------------|-----|-----------------------|------|---------------------------|-----|------------------|-----|
| EW1 | All work shall comply with AS3798 (2007) - Guidelines on earthworks for commercial and residential developments. | | | | | | | | | | |
| EW2 | All work shall comply with the project geotechnical report - | | | | | | | | | | |
| EW3 | Strip topsoil to expose naturally occurring engineering material and stockpile on site for reuse as directed by the superintendent. | | | | | | | | | | |
| EW4 | All soft, wet or unsuitable material to be removed as directed by the superintendent and replaced with approved fill material. | | | | | | | | | | |
| EW5 | All fill material shall be from a source approved by the superintendent and shall comply with the following - a) free from organic and perishable matter, b) maximum particle size 75mm, c) plasticity index - between 2% and 15%. | | | | | | | | | | |
| EW6 | All fill material shall be placed in maximum 200mm thick layers and compacted at optimum moisture content (+ or - 2%) to achieve a dry density determined in accordance with AS1289.5.1.1 - 2003 - methods of testing soils for engineering purposes of not less than the following standard minimum dry density - <table border="1" style="margin-left: 20px;"> <thead> <tr> <th>location</th> <th>standard dry density</th> </tr> </thead> <tbody> <tr> <td>under building slabs</td> <td>98%</td> </tr> <tr> <td>vehicular paved areas</td> <td>100%</td> </tr> <tr> <td>non-vehicular paved areas</td> <td>98%</td> </tr> <tr> <td>landscaped areas</td> <td>95%</td> </tr> </tbody> </table> | location | standard dry density | under building slabs | 98% | vehicular paved areas | 100% | non-vehicular paved areas | 98% | landscaped areas | 95% |
| location | standard dry density | | | | | | | | | | |
| under building slabs | 98% | | | | | | | | | | |
| vehicular paved areas | 100% | | | | | | | | | | |
| non-vehicular paved areas | 98% | | | | | | | | | | |
| landscaped areas | 95% | | | | | | | | | | |
| EW7 | The contractor shall program the earthworks operation so that the working areas are adequately drained during the period of construction. The surface shall be graded and sealed off to remove depressions, roller marks and similar which would allow water to pond and penetrate the underlying material. Any damage resulting from the contractor not observing these requirements shall be rectified by the contractor at their own expense. | | | | | | | | | | |
| EW8 | Testing of the fill material shall be carried out by an approved NATA registered laboratory at the contractors expense. | | | | | | | | | | |
| EW9 | Where the subgrade is unable to support construction equipment, or it is not possible to compact overlying pavement layers, only because of the subgrade moisture content, then the contractor shall condition or replace the material at the contractors discretion and expense. | | | | | | | | | | |
| EW10 | Earthworks calculations are volumetric only and do not allow for bulking of excavated material. It is the contractors responsibility to make allowances for these items as part of the tender / works. | | | | | | | | | | |
| EW11 | No allowance has been made for footings or foundations, retaining walls or trenching. It is the contractors responsibility to make allowances for these items as part of the tender / works. | | | | | | | | | | |

| Stormwater Drainage Legend | |
|----------------------------|--|
| | Stormwater drainage structure / pit number |
| | Construct surface inlet pit |
| | Construct junction pit |
| | Construct kerb inlet pit |
| | Stormwater drainage line Upstream invert level Pipe size / class Grade Length Flow Downstream invert level |
| | Construct grated drain |
| | Construct slotted subsoil drainage line |
| | Construct unslotted subsoil drainage line |
| | Construct subsoil intermediate riser |
| | Construct subsoil high end riser |

| Survey Legend | |
|---------------|--|
| | Existing boundary, bearing and distance |
| | Existing road name |
| | Existing building |
| | Existing kerb and spot levels |
| | Existing block wall |
| | Existing fence |
| | Existing spot level |
| | Existing earth batter |
| | Existing tree, level, trunk diameter, height and spread |
| | Existing electricity (underground) |
| | Existing electricity (overhead) |
| | Existing gas |
| | Existing sewer |
| | Existing stormwater drainage |
| | Existing water |
| | Existing telecommunications (underground) |
| | Existing electricity pit, pole, pole with light and light pole |
| | Existing gas valve |
| | Existing sewer pit and maintenance hole |
| | Existing stormwater grate, maintenance hole and pit |
| | Existing water hydrant, stop valve and valve |
| | Existing telecommunications pit and pillar |
| | Existing maintenance hole (unspecified) |
| | Existing pole (unspecified) |
| | Existing pit (unspecified) |
| | Existing traffic signal |
| | Existing public road pavement |

| Civil Grading Legend | |
|------------------------------|---|
| Construct surface to level.. | |
| ● F 10.00 | Finished surface level |
| ● F 10.00' | Levels to be confirmed on site prior to commencement of works |
| ● IL 10.00 | Invert level |
| — F10.00 | Major contour |
| — F9.50 | Minor contour |
| XX % Fall | Construct finished surface to grade |
| | Construct batter slope |

© Mott MacDonald
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

| Rev | Date | Drawn | Description | Ch'k'd | App'd |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 27.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |




Level 10, 383 Kent Street
Sydney, NSW 2000
Australia
PO Box Q1678
Q15 Sydney NSW 1230
T +61 (0)2 9098 6800
W www.mottmac.com.au

Client
BELL
Consultancy Team

Project
Resource Co
35 - 37 Frank Street, Wetherill Park
Title
Notes and Legends


| | | | | | |
|----------------|--------------------------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | N/A | Status | APR | Rev | P3 |
| Drawing Number | MMD-364729-C-DR-DA01-102 | | | | |

Preliminary - Not for Construction




Concrete Pavement - Road Circulation
1:10

Pavement Type 1



Concrete Pavement - Carpark
1:10


Pavement Type 2



Footpath Pavement
1:10


Pavement Type 3

- Pavement notes**
- Pavement construction is to follow the general approach and specifications as outlined in the Geotechnical report.
 - All pavement design is subject to geotechnical / structural testing, investigation and design. The pavements listed on this drawing are provisional only.
 - Design subgrade CBR to be confirmed by geotechnical engineer during construction and select fill depth to be varied accordingly subject to test results.



© Mott MacDonald
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

| | | | | | |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 28.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |
| Rev | Date | Drawn | Description | Ch'k'd | App'd |



Level 10, 383 Kent Street
Sydney, NSW 2000
Australia
PO Box Q1678
QVB Sydney NSW 1230
T +61 (0)2 9098 6800
www.mottmac.com.au

Client
BELL
Consultancy Team

Project
Resource Co
35 - 37 Frank street, Wetherill Park


Title
General Arrangement Plan

| | | | | | |
|---|-----------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | Status | Rev | Sec | | |
| 1:10,400 | APR | P3 | STD | | |
| Drawing Number MMD-364729-C-DR-DA01-103 | | | | | |

Preliminary - Not for Construction

| Sediment Basin Details | | | | | | |
|------------------------|------|-------------------------------|---------------------------|---------------------------|------------------------------|-------------------------|
| Site | Cv | Rainfall event (x-day y-%ile) | Total catchment area (ha) | Settling zone volume (m3) | Sediment storage volume (m3) | Total basin volume (m3) |
| Resource Co | 0.50 | 32.2 | 2.0773 | 334 | 167 | 501 |

| Erosion and Sediment Control Legend | |
|-------------------------------------|------------------------------------|
| | Construct catch drain |
| | Construct temporary sediment fence |
| | Install sandbag sediment traps |
| | Install haybale sediment traps |
| | Install temporary site access |
| | Construct sediment basin |



Connect outlet to existing Ø900 pipe

Construct temporary sediment fence around site perimeter. Refer detail on drawing 105.

Construct temporary Ø375 RCP under accessway


Construct temporary site entrance with shaker grid. Refer to detail on drawing 105.

Provide temporary on-grade sandbag sediment trap. Refer to detail on drawing 105.

© Mott MacDonald
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Preliminary - Not for Construction

| Rev | Date | Drawn | Description | Ch'k'd | App'd |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 27.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |



Level 10, 383 Kent Street
Sydney, NSW 2000
Australia
PO Box Q1678
QVB Sydney NSW 1230
T +61 (0)2 9098 6800
W www.mottmac.com.au

Client
BELL
Consultancy Team

Project
Resource Co
35 - 37 Frank Street, Wetherill Park

Title
Concept Sediment and Erosion Management Control Plan

| | | | | | |
|----------------|---------------------------------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | Status | Rev | Sec | | |
| 1:400 | APR | P3 | STD | | |
| Drawing Number | MMD-364729-C-DR-DA01-104 | | | | |

Soil and Water Management Notes

General Instructions

SWM01 These plans present a conceptual soil and water management plan (SWMP) only and shows a possible way of managing soil and erosion. The contractor shall be responsible for the establishment and management of the site and preparing a detailed plan and obtaining approval from the relevant authority prior to the commencement of any works.

SWM02 This plan is to be read in conjunction with the engineering plans and any other plans, written instructions, specification or documentation that may be issued and relating to development of the subject site.

SWM03 The contractor will ensure that all soil and water management works are consistent with 'Managing Urban Stormwater - Soils and Construction' - also known as 'The Blue Book'.

SWM04 All builders and sub-contractors shall be informed of their responsibilities in minimising the potential for soil erosion and pollution to downslope lands and waterways.

Erosion Control

SWM05 Water shall be prevented from entering the permanent drainage system until sediment concentration is less than or equal to 50mg/L, ie the catchment area has been permanently landscaped and / or any likely sediment has been filtered through an approved structure.

SWM06 Any sand used in the concrete curing process (spread over the surface) will be removed as soon as possible and within 10 working days from placement.

SWM07 Acceptable receptors will be constructed for concrete and mortar slurries, paints, acid washings, light-weight waste materials and litter.

SWM08 'Sediment' fencing will be installed as indicated on the plans and at the direction of site superintendent to ensure containment of sediment. The sediment fencing will outlet or overflow under stabilised conditions into the sediment basin, to safely convey water into a suitable filtering system should the pores in the fabric block.

SWM09 The sediment basins will be constructed with the minimum sediment storage capacity of 205 cubic metres and designed to remain stable in at least the 1 in 20 year critical duration storm event. Artificial flocculation of the finer particles may not be necessary in this instance.

SWM10 Stockpiles should not be located within 5m of trees and hazard areas, including likely areas of concentrated or high velocity flows such as waterways, drainage lines, paved areas and driveways. Where they are within 5m from such areas, special sediment control measures should be taken to minimise possible pollution to downstream waters. Measures should also be applied to prevent the erosion of the stockpile.

SWM11 All cut and fill batters are to be seeded and mulched within 14 days of completion of formation.

SWM12 Any existing trees which form part of the final landscaping plan will be protected from construction activities by-

- Protecting them with barrier fencing or similar materials installed outside the drip line,
- Ensuring that nothing is nailed to them,
- Prohibiting paving, grading, sediment wash or placing of stockpiles within the drip line except under the following conditions,
 - Encroachment only occurs on one side and no closer to the trunk than either 1.5 metres or half the distance between the outer edge of the drip line and the trunk, whichever is the greater,
 - A drainage system that allows air and water to circulate through the root zone (e.g. a gravel bed) is placed under all fill layers of more than 300 millimetres depth
 - Care is taken.

SWM13 During windy weather, large disturbed unprotected areas should be kept moist (not wet) by sprinkling with water to keep dust under control.

SWM14 Temporary protection from erosive forces will be undertaken on lands where final shaping has not been completed but works are unlikely to proceed for periods of two months or more (eg. on topsoil stockpiles). This may be achieved with a vegetative cover. A recommended listing of plant species for temporary cover is -

- autumn/winter sowing
 - oats/ryecorn at 20 kg/ha
 - japanese millet at 10 kg/ha
- spring/summer sowing
 - japanese millet at 20 kg/ha
 - oats/ryecorn at 10 kg/ha

SWM15 Diversion banks / channels will be rehabilitated as soon as possible and within 5 working days from their final shaping. Other than in the winter months, suitable materials include turf grasses such as Couch or Kikuyu. During winter, or at other times when temporary rehabilitation (more than 3 months) is required, it is suggested that hessian cloth is used but only if tacked with appropriate pegs and an anionic bitumen emulsion. Foot and vehicular traffic should be kept away from these areas.

SWM16 Undertake site development works in accordance with the engineering plans. Where possible, phase development so that land disturbance is confined to areas of workable size.

Construction Sequence

SWM17 Where practical, the soil erosion hazard on the site should be kept as low as possible. To this end, works should be undertaken in the FOLLOWING SEQUENCE -

- Install inlet sediment traps to all gully pits fronting the site,
- Install a 1.8m chain wire fence around the boundaries and attach hessian cloth or similar to it on the windward side (ties at the top, centre and bottom and at 1m intervals or as instructed by the superintendent),
- Install geofabric sediment fence and sediment traps around all permanent stormwater reticulation structures as shown on the plan,
- Construct stabilised construction entrance as shown on the plan or to location as determined by superintendent,
- Install diversion banks along the boundary where required, rehabilitate disturbed lands downslope from the basins within 20 working days,
- Ensure that the sediment basin is directed onto a turfed area and drains to a suitable location. A temporary stormwater line may be necessary to convey the flows to this location. Construct diversion channels at the boundary to drain into the sediment basin as shown on plans,
- At completion stabilise site and decommission sediment basin and all erosion control devices.

SWM18 Temporary soil and water management structures will be removed only after the lands they are protecting are rehabilitated.


SWM19 Final site landscaping will be undertaken as soon as possible and within 20 working days from completion of construction activities.

Site Inspection and Maintenance


SWM20 At least weekly and after every rain fall event, the contractor will inspect the site and ensure that -

- Drains and all sediment control devices operate effectively and initiate repair or maintenance as required,
- Receptors for concrete and mortar slurries, paints, acid washings, light-weight waste materials and litter are to be emptied as necessary. Disposal of waste shall be in a manner approved by the superintendent,
- Spilled sand (or other materials) is removed from hazard areas, including likely areas of concentrated or high velocity flows such as waterways, gutters, paved areas and driveways,
- Sediment is removed from basins and / or traps when less than 20m³ of trapping capacity remain per 1000m² of disturbed lands, and / or less than 500mm depth remains in the settling zone. Any collected sediment will be disposed in areas where further pollution to down slope lands and waterways is unlikely,
- Rehabilitated lands have effectively reduced the erosion hazard and initiate upgrading or repair as appropriate.


SWM21 The contractor shall provide all monitoring control and testing.




Sediment Trap for Kerb Inlet (On Grade - Sandbag)
NTS




Sediment Trap for Kerb Inlet (at Low Point - Sandbag)
NTS




Sediment Fence (Geotextile Filter Fabric)
NTS



Temporary Site Entrance
NTS




Shaker Pad
NTS



Sediment Trap for Drop Inlet (Geotextile Filter Fabric)
NTS

Maintenance

- The temporary access shall be maintained in a condition that prevents tracking or flowing of sediment onto public rights of way,
- This may require periodic top dressing with additional gravel as conditions demand and repair and/or cleanout of any measures used to trap sediment,
- All sediment spilled, dropped, washed or tracked onto public rights of way must be removed immediately.



Catch Drain
NTS

© Mott MacDonald
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

| | | | | | |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 27.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |
| Rev | Date | Drawn | Description | Ch'k'd | App'd |




Level 10, 383 Kent Street
Sydney, NSW 2000
Australia
PO Box Q1678
QVB Sydney NSW 1230
T +61 (0)2 9098 6800
www.mottmac.com.au

Client
BELL
Consultancy Team


Project
Resource Co
35 - 37 Frank Street, Wetherill Park
Title
Concept Sediment and Erosion Management Details

| | | | | | |
|----------------|--------------------------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | N/A | Status | APR | Rev | P3 |
| Drawing Number | MMD-364729-C-DR-DA01-105 | | | | |


Preliminary - Not for Construction




Section 6
1:500 Hor
103



Section 9
1:500 Hor
103



Section 5
1:500 Hor
103



Section 8
1:500 Hor
103




Section 10
1:100.500
103


For details of retaining wall geometry and preservation of existing trees along the Western boundary - refer to landscape architect's drawing 0215-0954 LD 400

| Proposed Level | Existing Level | Offset |
|----------------|----------------|--------|
| 0.00 | 47.91 | 47.85 |
| 0.32 | 48.09 | 47.84 |
| 1.82 | 48.52 | 47.80 |
| 2.00 | 48.53 | 47.80 |
| 9.70 | 48.42 | 48.00 |
| 15.50 | 48.63 | 48.15 |
| 15.68 | 48.64 | 48.30 |
| 17.43 | 48.81 | 48.34 |
| 19.40 | 48.96 | 48.70 |
| 19.60 | 48.97 | 50.06 |
| 22.18 | 49.11 | 49.99 |
| 22.36 | 49.12 | 49.85 |
| 52.69 | 49.69 | 50.68 |
| 60.30 | 49.99 | 50.83 |
| 63.30 | 50.25 | 50.85 |
| 66.40 | 50.65 | 50.94 |
| 74.40 | 50.89 | 50.87 |
| 74.58 | 50.89 | 51.17 |
| 76.08 | 50.87 | 51.21 |
| 77.39 | 53.35 | 53.95 |

Section 4
1:500 Hor
103



Section 7
1:500 Hor
103



Level 10, 383 Kent Street
Sydney, NSW 2000
Australia
PO Box Q1678
Q16 Sydney NSW 1230
T +61 (0)2 9098 6800
www.mottmac.com.au



Client
BELL
Consultancy Team

Project
Resource Co
35 - 37 Frank Street, Wetherill Park


Title
Site Cross Sections
Sheet 2 of 2

| | | | | | |
|----------------|--------------------------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | 1:100,500 | Status | APR | Rev | P3 |
| Drawing Number | MMD-364729-C-DR-DA01-107 | | Sec | STD | |

Preliminary - Not for Construction

| Bulk Earthworks Legend | |
|---|-----------|
|  | Cut zone |
|  | Fill zone |



| Bulk Earthworks Calculations | |
|---|-------------------------------------|
| Cut: | -3,000m ³ |
| Fill: | +12,000m ³ |
| Balance: | 9,000m ³ (Imported Fill) |
| Assumptions: | |
| 1. Earthworks calculations are preliminary only | |
| 2. Strip site: nil | |
| 3. Pavement Depths: | 400mm |
| 4. Building Slab Depth: | 400mm |
| Note | |
| Refer to earthworks construction notes on Drg.102 | |



© Mott MacDonald
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Preliminary - Not for Construction

| Rev | Date | Drawn | Description | Ch'k'd | App'd |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 28.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |


Level 10, 383 Kent Street
 Sydney, NSW 2000
 Australia
 PO Box Q1678
 QVB Sydney NSW 1230
 T +61 (0)2 9098 6800
 W www.mottmac.com.au

Client
BELL
 Consultancy Team

Project
Resource Co
 35 - 37 Frank Street, Wetherill Park

Title
Bulk Earthworks Layout Plan

| | | | | | |
|---|-----------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | Status | Rev | Sec | | |
| 1:400 | APR | P3 | STD | | |
| Drawing Number MMD-364729-C-DR-DA01-108 | | | | | |




For continuation refer to Dwg No 110

© Mott MacDonald
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Preliminary - Not for Construction

| | | | | | |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 28.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |
| Rev | Date | Drawn | Description | Ch'k'd | App'd |



Level 10, 383 Kent Street
 Sydney, NSW 2000
 Australia
 PO Box Q1678
 QVB Sydney NSW 1230
 T +61 (0)2 9098 6800
 www.mottmac.com.au


Client
BELL
 Consultancy Team

Project
Resource Co
 35 - 37 Frank Street, Wetherill Park

Title
Siteworks and Stormwater Drainage Plan - Sheet 1 of 2

| | | | | | |
|----------------|--------------------------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | 1:200 | Status | APR | Rev | P3 |
| Drawing Number | MMD-364729-C-DR-DA01-109 | | | | |
| | | | | Sec | STD |


For continuation refer to Dwg No 109



Preliminary - Not for Construction

© Mott MacDonald
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

| | | | | | |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 28.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |
| Rev | Date | Drawn | Description | Ch'k'd | App'd |






Level 10, 383 Kent Street
Sydney, NSW 2000
Australia
PO Box Q1678
QVB Sydney NSW 1230
T +61 (0)2 9038 6800
www.mottmac.com.au

Client
BELL
Consultancy Team

Project
Resource Co
35 - 37 Frank Street, Wetherill Park


Title
Siteworks and Stormwater Drainage Plan - Sheet 2 of 2

| | | | | | |
|---|-----------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | Status | APR | Rev | P3 | Sec |
| 1:200 | | | | | STD |
| Drawing Number MMD-364729-C-DR-DA01-110 | | | | | |

| Legend | |
|---|---|
|  | Proposed Retaining Wall |
|  | Proposed Retaining Wall Number |
|  | Proposed height of retaining wall (FSL - ESL) |

Note


Retaining Walls that are integral to the factory have not been shown on this drawing.



© Mott MacDonald
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Preliminary - Not for Construction

| Rev | Date | Drawn | Description | Ch'k'd | App'd |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 28.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |





Level 10, 383 Kent Street
 Sydney, NSW 2000
 Australia
 PO Box Q1678
 Q1/S Sydney NSW 1230
 T +61 (0)2 9098 6800
 W www.mottmac.com.au

Client
BELL
 Consultancy Team

Project
Resource Co
 35 - 37 Frank Street, Wetherill Park

Title
 Retaining Wall Plan



| | | | | | |
|--------------------------|-----------|----------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | 1:400 | Status | APR | Rev | P3 |
| Sec | STD | Drawing Number | | | |
| MMD-364729-C-DR-DA01-111 | | | | | |



© Mott MacDonald
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Mott MacDonald was commissioned. Mott MacDonald accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Preliminary - Not for Construction

| Rev | Date | Drawn | Description | Ch'k'd | App'd |
|-----|----------|-------|--------------------------|--------|-------|
| P3 | 28.01.16 | DRC | Issued for Approval | RBD | JG |
| P2 | 22.01.16 | DRC | Issued for Coordination | RBD | |
| P1 | 23.12.15 | DRC | Issued for Client Review | RBD | |

Level 10, 383 Kent Street
 Sydney, NSW 2000
 Australia
 PO Box Q1678
 QVB Sydney NSW 1230
 T +61 (0)2 9098 6800
 www.mottmac.com.au

Client
BELL
 Consultancy Team

Project
Resource Co
 35 - 37 Frank Street, Wetherill Park

Title
Stormwater Drainage Catchment Plan

| | | | | | |
|---|-----------|------------|--------------|------------|------------|
| Designed | R. Deep | 27.01.2016 | Eng check | J.Gilligan | 27.01.2016 |
| Drawn | D.Chapman | 27.01.2016 | Coordination | R.Deep | 27.01.2016 |
| Dwg check | D.Chivers | 27.01.2016 | Approved | C.Avis | 27.01.2016 |
| Scale at A1 | Status | Rev | Sec | | |
| 1:400 | APR | P3 | STD | | |
| Drawing Number MMD-364729-C-DR-DA01-112 | | | | | |