

Figure 13 Proposed Development Plan for Jacfin Site

Appendix C – Wastewater Modelling Run Codes

The run codes used for the base and the updated models (2020 and 2036 scenarios) are presented in the following Table.

Planning Year	Base Model	Updated with Oakdale Industrial Development
2036	SMJA	SMJD
2020	SMJD	SMJE

Appendix D – Dry Weather System Performance


U/s Node	D/s Node	Pipe Dia (mm)	Slope (%)	2020 (Runcode: SMJE)			2036 (Runcode: SMJE)		
				PDWF (l/s)	Hmax/ D	Max Velocity (m/s)	PDWF (l/s)	Hmax/ D	Max Velocity (m/s)
East St. Clair Carrier Extension									
NEWMH24	NEWMH23	225	1.02	5	0.212	0.8	5	0.212	0.8
NEWMH23	NEWMH22	225	1.02	5	0.212	0.8	5	0.212	0.8
NEWMH22	NEWMH21	225	0.95	5	0.216	0.78	5	0.216	0.78
NEWMH21	NEWMH20	225	1.01	5	0.213	0.8	5	0.213	0.8
NEWMH20	NEWMH19	225	1.00	9	0.296	0.96	9	0.296	0.96
NEWMH19	NEWMH18	225	1.01	9	0.295	0.96	9	0.295	0.96
NEWMH18	NEWMH15	225	1.26	9	0.279	1.04	9	0.279	1.04
NEWMH15	NEWMH14	450	2.58	23	0.339	0.77	55	0.531	0.99
NEWMH14	NEWMH13	450	0.83	23	0.297	0.75	55	0.458	0.97
NEWMH13	NEWMH12	450	0.81	24	0.386	0.62	55	0.573	0.83
NEWMH12	NEWMH11	450	1.19	29	0.36	0.79	60	0.524	1
NEWMH11	NEWMH10	450	1.81	29	0.374	1.14	60	0.499	1.41
NEWMH10	NEWMH09	525	0.19	81	0.531	0.77	113	0.643	0.84
NEWMH09	NEWMH08	525	0.20	81	0.652	0.65	113	0.756	0.74
NEWMH08	NEWMH07	525	0.21	112	0.596	0.89	143	0.693	0.95
NEWMH07	NEWMH06	525	0.23	112	0.604	0.9	143	0.704	0.96
NEWMH06	NEWMH05	525	0.21	112	0.605	0.89	143	0.705	0.94
NEWMH05	NEWMH04	525	0.20	112	0.594	0.89	143	0.691	0.95
NEWMH04	NEWMH03	525	0.26	112	0.614	0.89	143	0.71	0.96
NEWMH03	NEWMH02	525	0.26	112	0.587	0.94	143	0.679	1
NEWMH02	NEWMH01	525	0.29	112	0.578	0.96	143	0.664	1.03
Oakdale Central									
NEWMH24	NEWMH23	225	1.02	5	0.212	0.8	5	0.212	0.8
NEWMH23	NEWMH22	225	1.02	5	0.212	0.8	5	0.212	0.8
NEWMH22	NEWMH21	225	0.95	5	0.216	0.78	5	0.216	0.78
NEWMH21	NEWMH20	225	1.01	5	0.213	0.8	5	0.213	0.8
NEWMH20	NEWMH19	225	1.00	9	0.296	0.96	9	0.296	0.96
NEWMH19	NEWMH18	225	1.01	9	0.295	0.96	9	0.295	0.96
NEWMH18	NEWMH15	225	1.26	9	0.279	1.04	9	0.279	1.04
Oakdale East									
NEWMH38	NEWMH37	375	0.51	-	-	-	32	0.377	0.96
NEWMH37	NEWMH36	375	0.51	-	-	-	32	0.553	0.68
NEWMH36	NEWMH35	375	0.50	-	-	-	32	0.489	0.75
NEWMH35	NEWMH34	375	0.50	-	-	-	32	0.328	1.01
NEWMH34	NEWMH33	375	0.83	7	0.139	0.76	39	0.324	1.25
NEWMH33	NEWMH68	375	2.10	10	0.14	1.12	42	0.279	1.68
NEWMH68	NEWMH69	375	2.13	12	0.141	1.23	43	0.27	1.81

U/s Node	D/s Node	Pipe Dia (mm)	Slope (%)	2020 (Runcode: SMJE)			2036 (Runcode: SMJE)		
				PDWF (l/s)	Hmax/D	Max Velocity (m/s)	PDWF (l/s)	Hmax/D	Max Velocity (m/s)
NEWMH69	NEWMH32	375	2.65	12	0.134	1.33	43	0.255	1.95
NEWMH32	NEWMH15	375	0.99	14	0.184	0.97	45	0.339	1.38
Oakdale West									
NEWMH85	NEWMH84	375	0.49	4	0.15	0.42	4	0.15	0.42
NEWMH84	NEWMH83	375	0.50	4	0.251	0.26	4	0.251	0.26
NEWMH83	NEWMH82	375	0.50	10	0.256	0.54	10	0.256	0.54
NEWMH82	NEWMH81	375	0.50	10	0.258	0.54	10	0.258	0.54
NEWMH81	NEWMH80	375	0.50	10	0.361	0.4	10	0.361	0.4
NEWMH80	NEWMH79	375	0.50	13	0.295	0.61	13	0.295	0.61
NEWMH79	NEWMH78	375	0.50	13	0.294	0.61	13	0.294	0.61
NEWMH78	NEWMH76	375	0.50	13	0.417	0.45	13	0.417	0.45
NEWMH76	NEWMH25	375	0.46	21	0.47	0.55	21	0.47	0.55
NEWMH25	NEWMH08	375	0.54	30	0.334	0.93	30	0.338	0.93
NEWMH77	NEWMH30	225	1.31	7	0.452	0.59	7	0.452	0.59
NEWMH30	NEWMH31	225	1.18	7	0.439	0.6	7	0.439	0.6
NEWMH31	NEWMH76	225	0.96	7	0.262	0.88	7	0.262	0.88
NEWMH75	NEWMH74	300	1.21	8	0.32	0.56	8	0.32	0.56
NEWMH74	NEWMH73	300	1.20	8	0.318	0.56	8	0.318	0.56
NEWMH73	NEWMH72	300	1.21	8	0.347	0.52	8	0.347	0.52
NEWMH72	NEWMH71	300	1.20	8	0.345	0.52	8	0.345	0.52
NEWMH71	NEWMH26	300	1.21	8	0.359	0.5	8	0.359	0.5
NEWMH26	NEWMH25	300	1.18	10	0.587	0.38	10	0.587	0.38
Oakdale South									
NEWMH45	NEWMH44	375	1.50	2	0.184	0.27	2	0.184	0.27
NEWMH44	NEWMH50	375	0.48	4	0.198	0.4	4	0.198	0.4
NEWMH50	NEWMH43	375	1.09	5	0.176	0.58	5	0.176	0.58
NEWMH43	NEWMH42	375	0.59	5	0.164	0.54	5	0.164	0.54
NEWMH42	NEWMH55	375	0.53	5	0.303	0.36	5	0.303	0.36
NEWMH55	NEWMH41	375	0.51	11	0.502	0.65	11	0.502	0.65
NEWMH41	NEWMH40	450	0.51	45	0.394	0.9	45	0.394	0.9
NEWMH40	NEWMH67	450	0.51	47	0.505	0.75	47	0.505	0.75
NEWMH67	NEWMH39	450	0.48	53	0.397	1	53	0.397	1
NEWMH39	NEWMH10	450	0.53	53	0.327	1.17	53	0.327	1.17
Oakdale South									
NEWMH49	NEWMH48	300	2.86	26	0.262	1.78	26	0.262	1.78
NEWMH48	NEWMH56	300	1.23	26	0.327	1.31	26	0.327	1.31
NEWMH56	NEWMH47	300	4.12	26	0.236	2.06	26	0.236	2.06
NEWMH47	NEWMH46	300	1.29	34	0.384	1.37	34	0.384	1.37
NEWMH46	NEWMH41	300	2.03	34	0.351	1.54	34	0.351	1.54
NEWMH59	NEWMH58	225	0.29	5	0.551	0.28	5	0.551	0.28


U/s Node	D/s Node	Pipe Dia (mm)	Slope (%)	2020 (Runcode: SMJE)			2036 (Runcode: SMJE)		
				PDWF (l/s)	Hmax/D	Max Velocity (m/s)	PDWF (l/s)	Hmax/D	Max Velocity (m/s)
NEWMH57	NEWMH58	225	1.16	3	0.166	0.74	3	0.166	0.74
NEWMH58	NEWMH60	225	0.67	8	0.447	0.58	8	0.447	0.58
NEWMH60	NEWMH61	225	2.17	8	0.52	0.59	8	0.52	0.59
NEWMH61	NEWMH47	225	0.51	8	0.321	0.72	8	0.321	0.72
NEWMH51	NEWMH52	225	1.40	6	0.249	0.81	6	0.249	0.81
NEWMH52	NEWMH53	225	0.63	6	0.265	0.66	6	0.265	0.66
NEWMH53	NEWMH54	225	0.62	6	0.37	0.5	6	0.37	0.5
NEWMH54	NEWMH55	225	0.66	6	0.263	0.67	6	0.263	0.67
NEWMH62	NEWMH63	225	0.70	1	0.238	0.29	1	0.238	0.29
NEWMH63	NEWMH40	225	0.70	1	0.129	0.49	1	0.129	0.49
NEWMH64	NEWMH65	225	3.79	6	0.465	0.58	6	0.465	0.58
NEWMH65	NEWMH66	225	1.24	6	0.456	0.52	6	0.456	0.52
NEWMH66	NEWMH67	225	1.25	6	0.228	0.93	6	0.228	0.93
Jacfin Extension									
NEWMH89	NEWMH90	225	5.55	3	0.327	0.47	3	0.327	0.47
NEWMH90	NEWMH88	225	1.41	4	0.349	0.47	4	0.349	0.47
NEWMH88	NEWMH91	225	0.41	4	0.569	0.35	4	0.569	0.35
NEWMH91	NEWMH86	225	1.04	11	0.425	0.98	11	0.425	0.98
NEWMH86	NEWMH49	300	0.65	26	0.59	1.05	26	0.59	1.05
NEWMH87	NEWMH86	225	2.63	4	0.425	0.84	4	0.425	0.84
Downstream East St. Clair Carrier									
NEWMH01	268294	525	0.40	111	0.58	1.01	143	0.67	1.08
268294	1026826	525	0.31	112	0.571	0.99	143	0.661	1.05
1026826	1063394	525	0.36	112	0.652	0.9	143	0.754	0.96
1063394	1066126	525	0.32	112	0.536	1.04	144	0.621	1.11
1066126	1394278	525	0.32	113	0.453	1.2	145	0.533	1.25
1394278	1394282	600	0.19	114	0.456	0.94	146	0.526	1
1394282	1394286	600	0.32	115	0.421	1.03	146	0.493	1.09
1394286	1063358	600	0.27	115	0.506	0.9	146	0.579	0.96
1063358	1063366	600	0.25	115	0.472	0.93	146	0.542	0.99
1063366	1066102	600	0.26	117	0.479	0.96	147	0.548	1.01
1066102	1063374	600	0.27	118	0.469	0.99	149	0.535	1.06
1063374	1066110	600	0.26	119	0.398	1.19	149	0.45	1.28
1066110	1065994	600	0.15	120	0.467	0.96	150	0.533	1.01
1065994	1063274	750	0.15	120	0.369	0.84	151	0.423	0.88
1063274	1063286	750	0.15	120	0.387	0.78	151	0.441	0.82
1063286	1066022	750	0.18	120	0.425	0.72	151	0.476	0.78
1066022	1394274	750	0.24	125	0.368	0.88	156	0.416	0.93
1394274	1394290	800	0.20	125	0.322	0.91	156	0.36	0.97
1394290	1394294	800	0.20	125	0.29	1.1	156	0.324	1.18

U/s Node	D/s Node	Pipe Dia (mm)	Slope (%)	2020 (Runcode: SMJE)			2036 (Runcode: SMJE)		
				PDWF (l/s)	Hmax/D	Max Velocity (m/s)	PDWF (l/s)	Hmax/D	Max Velocity (m/s)
1394294	1394298	1200	0.24	125	0.165	1.05	156	0.183	1.12
1394298	1063298	900	0.28	125	0.306	0.89	156	0.342	0.95
1063298	1066026	900	0.28	125	0.327	0.82	156	0.366	0.87
1066026	1225433	900	0.28	125	0.303	0.89	156	0.338	0.95
1225433	1225013	900	0.28	125	0.3	0.9	156	0.335	0.96
1225013	1227493	900	0.28	125	0.298	0.91	156	0.333	0.97
1227493	1224765	900	0.28	125	0.232	1.13	156	0.259	1.2
1224765	1227497	900	0.18	125	0.252	1.04	156	0.283	1.08
1227497	1278268	1200	0.13	127	0.225	0.73	158	0.249	0.78
1278268	1281000	1200	0.15	131	0.224	0.75	160	0.248	0.8
1281000	1277995	1200	0.15	131	0.225	0.75	160	0.249	0.79
1277995	1280483	1200	0.15	131	0.233	0.73	160	0.258	0.77
1280483	1280111	1200	0.13	131	0.217	0.74	160	0.239	0.78
1280111	1280115	1200	0.32	131	0.227	0.82	160	0.251	0.86
1280115	1608413	1050	0.31	132	0.265	0.82	161	0.293	0.87
1608413	1279791	1050	0.30	132	0.255	0.87	161	0.281	0.92
1279791	1282311	1050	0.30	132	0.256	0.87	161	0.283	0.92
1282311	1279583	1050	0.30	132	0.254	0.87	161	0.28	0.92
1279583	1279371	1050	0.30	132	0.202	1.09	161	0.223	1.15
1279371	1279103	1050	0.32	133	0.279	0.81	162	0.308	0.86
1279103	1281835	1050	0.30	136	0.204	1.1	164	0.225	1.16
1281835	1279107	1500	0.15	194	0.226	0.71	243	0.253	0.75
1279107	1281839	1500	0.10	194	0.224	0.69	243	0.25	0.74
1281839	1281603	1500	0.10	194	0.224	0.69	243	0.251	0.74
1281603	1281199	1500	0.10	194	0.24	0.66	243	0.269	0.7
1281199	1278471	1050	0.13	194	0.316	0.84	243	0.353	0.9
1278471	1280983	1050	0.45	194	0.344	0.96	243	0.384	1.02
1280983	1280786	1050	0.15	215	0.284	1.17	267	0.317	1.24
1280786	1277646	1200	0.11	223	0.324	0.77	277	0.364	0.82
1277646	1280378	1200	0.09	223	0.318	0.75	277	0.356	0.79
1280378	1280086	1200	0.09	223	0.3	0.79	277	0.334	0.84
1280086	1280090	1200	0.10	223	0.267	0.93	277	0.298	0.99
1280090	1279614	1200	0.11	223	0.265	0.93	277	0.295	1
1279614	1282026	1200	0.10	236	0.265	1.12	291	0.294	1.19
1282026	1282022	1200	0.50	236	0.184	1.65	291	0.204	1.75
1282022	1279294	1200	0.50	236	0.477	0.56	291	0.516	0.59
1279294	1281374	1350	0.09	405	0.393	0.84	471	0.427	0.85
1281374	1275321	1350	0.12	403	0.368	0.9	468	0.397	0.94
1275321	1276981	1350	0.11	403	0.341	0.95	468	0.366	1
1276981	1276849	1350	0.11	404	0.303	1.26	466	0.325	1.32

U/s Node	D/s Node	Pipe Dia (mm)	Slope (%)	2020 (Runcode: SMJE)			2036 (Runcode: SMJE)		
				PDWF (l/s)	Hmax/D	Max Velocity (m/s)	PDWF (l/s)	Hmax/D	Max Velocity (m/s)
1276849	1273977	1350	0.13	411	0.366	0.99	468	0.391	1.04
1273977	1276705	1350	0.15	411	0.296	1.3	468	0.315	1.35
1276705	1404019	1350	2.36	502	0.223	2.36	542	0.236	2.36
1404019	SPS0204	1350	13.55	502	0.554	8.99	542	0.559	6.07
RMTND01	RMTND03	2000	0.20	501	0.186	1.81	542	0.196	1.78
RMTND03	OUTLET1	3000	0.20	810	0.124	1.61	904	0.131	1.66



HGL along East St. Clair Carrier Extension and downstream East St. Clair Carrier in 2020 PDWF



HGL along East St. Clair Carrier Extension and downstream East St. Clair Carrier in 2036 PDWF

Appendix E – Wet Weather (Design Event) System Performance (2036)

Appendix F – Cost Estimates

Sydney WATER Cost Estimator									
Job Name:		Oakdale Central				Estimate Date:		05/05/2016	
Estimator:		Amir Rashidi				Print Date/Time:		26/05/2016 15:36	
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	Ver 09-2015.11 TOTAL		
DIRECT COSTS									
	H1	Option 1							
1		Gravity Sewer Greenfield PVC 1.5m deep	225 dia	m	0	228		0	0
2		Gravity Sewer Greenfield PVC 1.5m deep	300 dia	m	0	275		0	0
3		Gravity Sewer Greenfield PVC 1.5m deep	375 dia	m	750	386		289,828	
4		Gravity Sewer Greenfield PP 2.0m deep	450 dia	m	0	621		0	0
5		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	0	18		0	0
6		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	0	21		0	0
7		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	750	25		18,621	
8		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10		0	0
9		EO Road Restoration Trench Std Depth	250 dia	m	0	434		0	0
10		EO Road Restoration Trench Std Depth	300 dia	m	0	485		0	0
11		EO Road Restoration Trench Std Depth	375 dia	m	188	513		96,163	
12		EO Road Restoration Trench Std Depth	450 dia	m	0	579		0	0
H1		Scope Contingency							
13		Urban Detailed Planning	75	%	404,612	0.75		303,459	
		Sub Total Direct Costs						708,072	
INDIRECT COSTS									
					%				
14		Contractor Design Costs (% of Direct Costs)			10.00%			70,807	
15		Contractor Indirect Costs (% of Direct Costs)			20.00%			141,614	
16		Contractor Margin (% of DC+Indirect Costs)			15.00%			138,074	
17		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%			370,498	
		Total Construction Cost						1,429,065	
SWC CLIENT COSTS									
					% of ConstC				
18		SWC Costs to Date							
19		SWC Design Costs (% of Construction Costs)			1.00%			14,291	
20		SWC Tender Costs (% of Construction Costs)			0.50%			Adj. to Min Limit>>	50,000

Sydney WATER										Cost ESTIMATOR	
Job Name:		Oakdale Central								Estimate Date:	
Estimator:		Amir Rashidi								Print Date/Time:	
										26/05/2016 15:36	
										Ver 09-2015.11	
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE		TOTAL			
21		SWC Planning Costs (% of Construction Costs)			5.00%				71,453		
22		SWC Project Management Costs (% of Construction Costs)			5.00%				71,453		
23		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%				7,860		
24		SWC Land Acquisition/Easement Costs									
25		SWC Risk Contingency (% of the SWC Client Future Costs only)					of Client Costs				
		TOTAL PROJECT BUDGET REQUIREMENT							1,644,122		

Sydney WATER Cost Estimator									
Job Name:						Estimate Date:		05/05/2016	
Estimator:		Amir Rashidi				Print Date/Time:		26/05/2016 15:39	
						Ver 09-2015.11			
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
DIRECT COSTS									
	H1	Option 1							
1		Gravity Sewer Greenfield PVC 1.5m deep	225 dia	m	0	228		0	0
2		Gravity Sewer Greenfield PVC 1.5m deep	300 dia	m	0	275		0	0
3		Gravity Sewer Greenfield PVC 1.5m deep	375 dia	m	1,020	386		394,166	
4		Gravity Sewer Greenfield PP 2.0m deep	450 dia	m	0	621		0	0
5		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	0	18		0	0
6		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	0	21		0	0
7		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	1,020	25		25,325	
8		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10		0	0
9		EO Road Restoration Trench Std Depth	250 dia	m	0	434		0	0
10		EO Road Restoration Trench Std Depth	300 dia	m	0	485		0	0
11		EO Road Restoration Trench Std Depth	375 dia	m	255	513		130,782	
12		EO Road Restoration Trench Std Depth	450 dia	m	0	579		0	0
H1		Scope Contingency							
13		Urban Detailed Planning	75	%	550,273	0.75		412,705	
		Sub Total Direct Costs						962,977	
INDIRECT COSTS									
					%				
14		Contractor Design Costs (% of Direct Costs)			10.00%			96,298	
15		Contractor Indirect Costs (% of Direct Costs)			20.00%			192,595	
16		Contractor Margin (% of DC+Indirect Costs)			15.00%			187,781	
17		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%			503,878	
		Total Construction Cost						1,943,529	
SWC CLIENT COSTS									
					% of ConstC				
18		SWC Costs to Date			1.00%			19,435	
19		SWC Design Costs (% of Construction Costs)			0.50%			Adj. to Min Limit>>	50,000
20		SWC Tender Costs (% of Construction Costs)							

Sydney WATER										Cost ESTIMATOR			
Job Name:		Oakdale East								Estimate Date:		05/05/2016	
Estimator:		Amir Rashidi								Print Date/Time:		26/05/2016 15:39	
										Ver 09-2015.11			
ITEM		H#	DESCRIPTION	PARAMETER		UNIT	QUANTITY		RATE		TOTAL		
21			SWC Planning Costs (% of Construction Costs)					5.00%				97,176	
22			SWC Project Management Costs (% of Construction Costs)					5.00%				97,176	
23			SWC Insurances & Financing Costs (% of Construction Costs)					0.55%				10,689	
24			SWC Land Acquisition/Easement Costs										
25			SWC Risk Contingency (% of the SWC Client Future Costs only)							of Client Costs			
			TOTAL PROJECT BUDGET REQUIREMENT									2,218,005	

Sydney: WATER Cost ESTIMATOR									
Job Name:		Oakdale West				Estimate Date: 05/05/2016			
Estimator:		Amir Rashidi				Print Date/Time: 26/05/2016 15:40			
						Ver 09-2015.11			
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
DIRECT COSTS									
	H1	Option 1							
1		Gravity Sewer Greenfield PVC 1.5m deep	225 dia	m	250	228			57,075
2		Gravity Sewer Greenfield PVC 1.5m deep	300 dia	m	1,500	275			413,142
3		Gravity Sewer Greenfield PVC 1.5m deep	375 dia	m	2,320	386			896,533
4		Gravity Sewer Greenfield PP 2.0m deep	450 dia	m	0	621			0
5		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	250	18			4,421
6		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	1,500	21			32,141
7		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	2,320	25			57,602
8		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10			0
9		EO Road Restoration Trench Std Depth	250 dia	m	63	434			27,128
10		EO Road Restoration Trench Std Depth	300 dia	m	375	485			181,800
11		EO Road Restoration Trench Std Depth	375 dia	m	580	513			297,466
12		EO Road Restoration Trench Std Depth	450 dia	m	0	579			0
	H1	Scope Contingency							
13		Urban Detailed Planning	75	%	1,967,308	0.75			1,475,481
Sub Total Direct Costs									3,442,789
INDIRECT COSTS									
					%				
14		Contractor Design Costs (% of Direct Costs)			10.00%				344,279
15		Contractor Indirect Costs (% of Direct Costs)			20.00%				688,558
16		Contractor Margin (% of DC+Indirect Costs)			15.00%				671,344
17		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%				1,801,440
Total Construction Cost									6,948,410
SWC CLIENT COSTS									
					% of ConstC				
18		SWC Costs to Date							
19		SWC Design Costs (% of Construction Costs)			1.00%				69,484
20		SWC Tender Costs (% of Construction Costs)			0.50%	Adj. to Min Limit>>			50,000

Sydney WATER										Cost ESTIMATOR	
Job Name:		Oakdale West								Estimate Date:	
Estimator:		Amir Rashidi								Print Date/Time:	
										26/05/2016 15:40	
										Ver 09-2015.11	
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE		TOTAL			
21		SWC Planning Costs (% of Construction Costs)			5.00%			347,421			
22		SWC Project Management Costs (% of Construction Costs)			5.00%			347,421			
23		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%			38,216			
24		SWC Land Acquisition/Easement Costs									
25		SWC Risk Contingency (% of the SWC Client Future Costs only)					of Client Costs				
		TOTAL PROJECT BUDGET REQUIREMENT						7,800,952			

Sydney: WATER Cost Estimator									
Job Name:		Oakdale South				Estimate Date:			
Estimator:		Amir Rashidi				Print Date/Time:			
						26/05/2016 15:39			
						Ver 09-2015.11			
						TOTAL			
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE			
DIRECT COSTS									
	H1	Option 1							
1		Gravity Sewer Greenfield PVC 1.5m deep	225 dia	m	1,280	228			292,226
2		Gravity Sewer Greenfield PVC 1.5m deep	300 dia	m	450	275			123,943
3		Gravity Sewer Greenfield PVC 1.5m deep	375 dia	m	1,250	386			483,046
4		Gravity Sewer Greenfield PP 2.0m deep	450 dia	m	720	621			447,136
5		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	1,280	18			22,638
6		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	450	21			9,642
7		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	1,250	25			31,035
8		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	720	10			7,102
9		EO Road Restoration Trench Std Depth	250 dia	m	320	434			138,896
10		EO Road Restoration Trench Std Depth	300 dia	m	113	485			54,540
11		EO Road Restoration Trench Std Depth	375 dia	m	313	513			160,272
12		EO Road Restoration Trench Std Depth	450 dia	m	180	579			104,172
	H1	Scope Contingency							
13		Urban Detailed Planning	75	%	1,874,649	0.75			1,405,986
Sub Total Direct Costs									
INDIRECT COSTS									
					%				
14		Contractor Design Costs (% of Direct Costs)			10.00%				328,063
15		Contractor Indirect Costs (% of Direct Costs)			20.00%				656,127
16		Contractor Margin (% of DC+Indirect Costs)			15.00%				639,724
17		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%				1,716,592
Total Construction Cost									
SWC CLIENT COSTS									
					% of ConstC				
18		SWC Costs to Date							
19		SWC Design Costs (% of Construction Costs)			1.00%				66,211
20		SWC Tender Costs (% of Construction Costs)			0.50%	Adj. to Min Limit>>			50,000

Sydney WATER										Cost ESTIMATOR		
Job Name:		Oakdale South								Estimate Date:		05/05/2016
Estimator:		Amir Rashidi								Print Date/Time:		26/05/2016 15:39
										Ver 09-2015.11		
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE		TOTAL				
21		SWC Planning Costs (% of Construction Costs)			5.00%					331,057		
22		SWC Project Management Costs (% of Construction Costs)			5.00%					331,057		
23		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%					36,416		
24		SWC Land Acquisition/Easement Costs										
25		SWC Risk Contingency (% of the SWC Client Future Costs only)						of Client Costs				
		TOTAL PROJECT BUDGET REQUIREMENT								7,435,882		

Sydney: WATER Cost ESTIMATOR									
Job Name: Jacfin						Estimate Date: 05/05/2016			
Estimator: Amir Rashidi						Print Date/Time: 26/05/2016 15:38			
						Ver 09-2015.11			
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
DIRECT COSTS									
	H1	Option 1							
1		Gravity Sewer Greenfield PVC 1.5m deep	225 dia	m	1,250	228		285,377	
2		Gravity Sewer Greenfield PVC 1.5m deep	300 dia	m	170	275		46,823	
3		Gravity Sewer Greenfield PVC 1.5m deep	375 dia	m	0	386		0	
4		Gravity Sewer Greenfield PP 2.0m deep	450 dia	m	0	621		0	
5		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	1,250	18		22,107	
6		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	170	21		3,643	
7		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0	25		0	
8		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10		0	
9		EO Road Restoration Trench Std Depth	250 dia	m	313	434		135,641	
10		EO Road Restoration Trench Std Depth	300 dia	m	43	485		20,604	
11		EO Road Restoration Trench Std Depth	375 dia	m	0	513		0	
12		EO Road Restoration Trench Std Depth	450 dia	m	0	579		0	
	H1	Scope Contingency							
13		Urban Detailed Planning	75	%	514,195	0.75		385,646	
Sub Total Direct Costs								899,841	
INDIRECT COSTS									
					%				
14		Contractor Design Costs (% of Direct Costs)			10.00%			89,984	
15		Contractor Indirect Costs (% of Direct Costs)			20.00%			179,968	
16		Contractor Margin (% of DC+Indirect Costs)			15.00%			175,469	
17		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%			470,842	
Total Construction Cost								1,816,104	
SWC CLIENT COSTS									
					% of ConstC				
18		SWC Costs to Date							
19		SWC Design Costs (% of Construction Costs)			1.00%			18,161	
20		SWC Tender Costs (% of Construction Costs)			0.50%			Adj. to Min Limit>>	50,000

Sydney WATER Cost ESTIMATOR									
Job Name:		Estimate Date:					05/05/2016		
Estimator:		Print Date/Time:					26/05/2016 15:38		
		Ver 09-2015.11					TOTAL		
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE			
21		SWC Planning Costs (% of Construction Costs)			5.00%			90,805	
22		SWC Project Management Costs (% of Construction Costs)			5.00%			90,805	
23		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%			9,989	
24		SWC Land Acquisition/Easement Costs							
25		SWC Risk Contingency (% of the SWC Client Future Costs only)				of Client Costs			
TOTAL PROJECT BUDGET REQUIREMENT								2,075,864	

Sydney WATER Cost ESTIMATOR									
Job Name: Jacfin		Estimate Date: 05/05/2016							
Estimator: Amir Rashidi		Print Date/Time: 26/05/2016 15:36							
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
DIRECT COSTS									
	H1	Option 1							
1		Gravity Sewer Greenfield PVC 1.5m deep	225 dia	m	1,250	228		285,377	
2		Gravity Sewer Greenfield PVC 1.5m deep	300 dia	m	170	275		46,823	
3		Gravity Sewer Greenfield PVC 1.5m deep	375 dia	m	0	386		0	
4		Gravity Sewer Greenfield PP 2.0m deep	450 dia	m	0	621		0	
5		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	1,250	18		22,107	
6		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	170	21		3,643	
7		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0	25		0	
8		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10		0	
9		EO Road Restoration Trench Std Depth	250 dia	m	313	434		135,641	
10		EO Road Restoration Trench Std Depth	300 dia	m	43	485		20,604	
11		EO Road Restoration Trench Std Depth	375 dia	m	0	513		0	
12		EO Road Restoration Trench Std Depth	450 dia	m	0	579		0	
H1		Scope Contingency							
13		Urban Detailed Planning	75	%	514,195	0.75		385,646	
		Sub Total Direct Costs						899,841	
INDIRECT COSTS									
					%				
14		Contractor Design Costs (% of Direct Costs)			10.00%			89,984	
15		Contractor Indirect Costs (% of Direct Costs)			20.00%			179,968	
16		Contractor Margin (% of DC+Indirect Costs)			15.00%			175,469	
17		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%			470,842	
		Total Construction Cost						1,816,104	
SWC CLIENT COSTS									
					% of ConstC				
18		SWC Costs to Date							
19		SWC Design Costs (% of Construction Costs)			1.00%			18,161	
20		SWC Tender Costs (% of Construction Costs)			0.50%	Adj. to Min Limit>>		50,000	

Sydney WATER										Cost ESTIMATOR			
Job Name:		Jacfin								Estimate Date:		05/05/2016	
Estimator:		Amir Rashidi								Print Date/Time:		26/05/2016 15:36	
										Ver 09-2015.11			
ITEM		H#	DESCRIPTION	PARAMETER		UNIT	QUANTITY		RATE		TOTAL		
21			SWC Planning Costs (% of Construction Costs)				5.00%				90,805		
22			SWC Project Management Costs (% of Construction Costs)				5.00%				90,805		
23			SWC Insurances & Financing Costs (% of Construction Costs)				0.55%				9,989		
24			SWC Land Acquisition/Easement Costs										
25			SWC Risk Contingency (% of the SWC Client Future Costs only)						of Client Costs				
			TOTAL PROJECT BUDGET REQUIREMENT								2,075,864		

www.ghd.com





Oakdale Industrial Development - Planning of Water Related
Services
Final Report - Water

July 2016

Commercial in Confidence

GHD Disclaimer

This report: has been prepared by GHD for Goodman Property Services (Aust) Pty Ltd (GPS) and may only be used and relied on by GPS Associates for the purpose agreed between GHD and the GPS as set out in section 1.2 of this report.

GHD otherwise disclaims responsibility to any person other than GPS arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described in Basis of Planning report (i.e. TM-01). GHD disclaims liability arising from any of the assumptions being incorrect.

GHD has prepared this report on the basis of information provided by Sydney Water and GPS who provided information to GHD (including Government authorities)], which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.

GHD has prepared preliminary Cost Estimates in this report. Actual prices, costs and other variables may be different to those used to prepare the Cost Estimate and may change. Unless as otherwise specified in this report, no detailed quotation has been obtained for actions identified in this report. GHD does not represent, warrant or guarantee that the works can or will be undertaken at a cost which is the same or less than the Cost Estimate.

GHD

133 Castlereagh St Sydney NSW 2000

-


T: +61 2 9239 7100 F: +61 2 9239 7199 E: sydmail@ghd.com.au

© GHD 2016

This document is and shall remain the property of GHD. The document may only be used for the purpose for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

G:\21\25274\WP\215513_Oakdale Industrial Water Planning Report_Ver01.docx

Document Status



Revision	Author	Reviewer		Approved for Issue		
		Name	Signature	Name	Signature	Date
Rev. 01	A Rashidi	M Healey		M Healey		15/06/16
Rev. 02	A Rashidi	M Healey		M Healey		5/07/16
Final	A Rashidi	M Healey, Sydney Water, Goodmans		M Healey		28/07/2016

Document Status

Oakdale Industrial Development - Planning of Water Related Services July 2016

This report has been prepared by GHD

Approved for issue

Signature	Date	Signature	Date	Signature	Date
	29/07/16		29/07/16	
Kym Dracopoulos Manager, Technical Goodman Property Services (AUST) Pty Ltd		Russell Hogan Project Manager AT&L Associates		Amir Rashidi Project Manager GHD	

Endorsed

I confirm that impacted parties within my business have been consulted, their inputs have been considered and the decisions have been communicated to relevant parties.

Signature	Date	Signature	Date
-----------	------	-----------	------

Suhanti Thirunavukarasu
Principal Planner
Engineering & Environmental Services
Sydney Water

Richard Schuil
Engineering & Planning Manager
Growth Centres
Sydney Water

Approved

Signature	Date
-----------	------

Jim Price
Development Services Officer
Liveable City Solutions
Sydney Water

Executive Summary

The Oakdale industrial site is part of the existing Western Sydney Employment Area (WSEA 8 – Area South of Pipeline Precinct), located approximately 40 kms west of the Sydney CBD, adjacent to the M7 and M4 intersection. The site was rezoned in September 2009 through the WSEA SEPP 2009, and Goodman is the lead developer of the precinct. An overview of study area is presented in Figure 1.

The initial water servicing plan scheme was to supply Oakdale from existing DN450 lead-in main within Cecil Park supply system.

This Local Area Servicing Plan (LASP) for potable water has been prepared at the request of Sydney Water to provide a servicing strategy for the existing WSEA Precinct No. 8–Area South of Pipeline, including Goodman’s Oakdale development. This servicing strategy identifies the Sydney Water infrastructure required to service the Oakdale Precinct, anticipated costs, sizing, preliminary alignments and trigger points (i.e. development timing and staging) for the delivery of potable water infrastructure required to service the Oakdale Precinct.

Growth and water demand projections

Oakdale Estate is an ongoing industrial development with approximately 452 nett hectares of developable area. This includes Goodman, CSR and Jacfin lands. Their lands are predominately zoned IN1 ‘General Industrial’ under the State Environmental Planning Policy (Western Sydney Employment Area) 2009. The site spans two local government areas of Penrith and Fairfield.

The growth projections listed for this study are supplied by AT&L in conjunction with Jacfin, CSR and Goodman. The list of the growth projection within the Oakdale Industrial Development is summarised in Table 1.

Table 1 Growth Projections

Development site	Nett Development (ha)	Development type	Connection ⁽¹⁾
Oakdale Central	45.2	IN1- General Industrial ⁽²⁾	2016- 2017
Jacfin	87.8	IN1- General Industrial/ Residential	2016- 2017
Oakdale South	70.2	IN1- General Industrial	2017- 2019
CSR	63.4	IN1- General Industrial	2017-2020
Oakdale West	90.5	IN1- General Industrial	2019- 2021
Oakdale East	95.0	IN1- General Industrial	2022- 2024
Total	452		

Note 1: The proposed timing of connection is subject to change

Note 2: water demand assessed based on Light industrial / warehouse

An evidence based approach to forecasting future demands in the study area, based on observed demands in an adjacent water supply system, was adopted as per the “Water System Planning Guidelines 2014”. Table 2 below summarises the projected water demands for the Oakdale Industrial Development. Total projected max day demand in the Oakdale Precinct is 7.5 ML/d.

Table 2 Summary of Water Demand - Oakdale Industrial Development

Development site	Timing	Average Day Demand (ML/d)	Max Day Demand (ML/d)
Oakdale Central	2016-2017	0.42	0.7
Jacfin	2016-2017	1.04	2.12
Oakdale South	2017-2019	0.65	1.0
CSR	2017-2020	0.58	0.93
Oakdale West	2019-2021	0.83	1.3
Oakdale East	2022-2024	0.87	1.4
Total		4.4	7.5

The key opportunities and constraints associated with water servicing of the Oakdale Industrial Development is summarised below.

Opportunities

- Based on the supplied Oakdale growth projections, Cecil Park reservoir and Prospect Creek pumping station WP0184B have sufficient capacity to supply the entire Cecil Park zone including Oakdale Development for the 2020 demand scenario.
- A DN450 lead-in water main has been constructed as part of previous site works and has sufficient capacity to supply the entire Oakdale Development.
- Minchinbury Elevated supply zone has 2.5 ML/d transferable capacity to provide supply contingency to Oakdale Industrial.
- The Growth Servicing Strategy (GSS) proposed augmentations are adequate to supply the entire Cecil Park zone including Oakdale Development for the post 2031 demand scenario.

Constraints

- Cecil Park reservoir and pumping station WP0184 has insufficient capacity to supply the entire Cecil Park zone including Oakdale Development post 2020 demand scenario, when Austral and Leppington North will be rezoned to Cecil Park supply system. Sydney Water will address growth servicing requirements in the broader region.
- Erskine Park Elevated supply system has insufficient head to supply Oakdale Industrial system.




Figure 1 Oakdale Industrial Development Overview

The Oakdale Servicing Strategy is made up of the following:

Oakdale Central

Oakdale Central is currently supplied from the existing DN250 potable water main within Millner Avenue (refer section 3-4 on figure 2) which is supplied from the Cecil Park Supply System. To improve system reliability, it is proposed to supply Oakdale Central from the Minchinbury Elevated supply system via a proposed DN300 connection (refer section 4-7 on Fig. 2) between the existing DN250 potable water main within Millner Avenue (refer section 3-4 on Fig. 2) to the proposed DN300 within Oakdale West (refer section 7-8 on Fig. 2) which ultimately connects to the existing DN300 within Erskine Park Link Road (EPLR). The proposed DN300 is proposed to be delivered at the same time as the Oakdale West development.

Oakdale South

Oakdale South will be supplied via extension (refer section 4-6 on Fig. 2) of the existing DN250 potable water main (Refer Section 3-4 on Fig. 2) within Millner Avenue which is supplied from the Cecil Park Supply System.

Oakdale West

Oakdale West will be supplied via a proposed DN300 (refer section 8-9 on Fig. 2) connection to the existing DN300 within Erskine Park Link Road (EPLR). This proposed DN300 will be supplied from the Minchinbury Elevated Supply System. As mentioned above, a DN300 cross connection (refer section 4-7 on Fig. 2) to Oakdale Central will be delivered at the same time as the Oakdale West development to supply Oakdale Central from the Minchinbury Elevated Supply System which will improve the system reliability.

Oakdale East

Oakdale East will be supplied off the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System.

CSR

CSR lands will be supplied via a proposed DN300 connected to the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System.

Jacfin

Jacfin lands will be supplied via a proposed DN300 connected to the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System. Jacfin internal reticulation will be via a proposed DN250 which will be connected to the proposed DN250 within Oakdale South to improve the system reliability.

The preliminary capital cost estimates associated with Oakdale Industrial water servicing is presented in Table 3. The Oakdale servicing plan overview is presented in Figure 2.

Table 3 Preliminary capital cost estimates

Section	Description	Delivery Date	Capital Cost (\$M)
2-4	1.2 km DN300	2016-2017	\$2.21 M
4-5	0.9 km DN250	2016-2017	\$1.34 M
5-6	0.85 km DN200	2016-2017	\$1.08 M
4-7	0.7 km DN300	2017-2018	\$ 1.31 M
7-8	1.2 km DN300	2018-2019	\$2.21 M
8-9	1.6 km DN300	2018-2019	\$2.93 M




Figure 2- Oakdale Industrial Water Servicing Plan

Table of contents

1.	Introduction.....	1
1.1	Background.....	1
1.2	Purpose of this report.....	1
2.	Growth Projections	2
2.1	Summary of Growth	2
2.2	Water Demand Projections	4
3.	Opportunities and constraints	5
3.1	Opportunities.....	5
3.2	Constraints	5
4.	Water servicing	7
4.1	Oakdale Industrial water servicing	7
4.2	Preliminary capital cost assessment.....	10
5.	Conclusions and Recommendations	11

Table index

Table 1 Growth Projections	iii
Table 2 Summary of Water Demand - Oakdale Industrial Development.....	iv
Table 3 Preliminary capital cost estimates	2
Table 3 Growth Projections	2
Table 4 Summary of revised future water demand- Cecil Park Supply System	4
Table 5 Summary of Water Demand - Oakdale Industrial Development.....	4
Table 8 Preliminary capital cost estimates	10

Figure index

Figure 1 Oakdale Industrial Development Overview.....	i
Figure 2 Oakdale Industrial Water Servicing Plan	i
Figure 3 Opportunities and constraints	6
Figure 4 Oakdale Industrial Water Servicing Plan	9

Appendices

Appendix A – Revised Basis of Water Planning

Appendix B – Detailed Cost Estimation

Appendix C – Growth Servicing Strategy (GSS) augmentations

1. Introduction

1.1 Background

The Oakdale industrial site is part of the existing Western Sydney Employment Area (WSEA 8 – Area South of Pipeline Precinct), located approximately 40 kms west of the Sydney CBD, adjacent to the M7 and M4 intersection. The site was rezoned in September 2009 through the WSEA SEPP 2009, and Goodman is the lead developer of the precinct. An overview of study area is presented in Figure 1.

The initial water servicing plan scheme was to supply Oakdale from existing DN450 lead-in main within Cecil Park supply system. Minchinbury Elevated supply system also will provide connection to Oakdale from the existing DN300 within Erskine Park Link Road (EPLR).

Assets required to service proposed Goodman, Jacfin and CSR developments within Oakdale precinct are to be staged to meet development timeframes, with lead-in infrastructure funded up front and delivered by the lead developer and to be reimbursed by Sydney Water in accordance with its policy on Funding Infrastructure to Service Growth.

1.2 Purpose of this report

The purpose of this report is to document the:

- Revised growth and water demand forecasts,
- Key opportunities and constraints,
- Outcomes of the assessment work undertaken, and
- Water servicing plan for the Oakdale Industrial Development.

This Local Area Servicing Plan (LASP) for potable water has been prepared at the request of Sydney Water to provide a servicing strategy for the existing WSEA Precinct No. 8–Area South of Pipeline, including Goodman’s Oakdale development. This servicing strategy identifies the Sydney Water infrastructure required to service the Oakdale Precinct, anticipated costs, sizing, preliminary alignments and trigger points (i.e. development timing and staging) for the delivery of potable water infrastructure required to service the Oakdale Precinct.

2. Growth Projections

This section provides details of growth and water demand projections within the study area including the expected timing, and scale of growth.

2.1 Summary of Growth

Growth forecasts are a key input into the planning process and provide an insight into future infrastructure needs as well as future capital investment needs.

Oakdale Estate is an ongoing industrial development with approximately 452 nett hectares of development area. This includes Goodman, CSR and Jacfin lands. These lands are predominately zoned IN1 'General Industrial' under the State Environmental Planning Policy (Western Sydney Employment Area) 2009. The site spans two local government areas of Penrith and Fairfield.

The growth projections listed for this study are supplied by AT&L in conjunction with Jacfin, CSR and Goodman. The list of the growth projection within the Oakdale Industrial Development is summarised in Table 4.

Table 4 Growth Projections

Development site	Precinct	Nett Development (ha)	Development type	Connection
Oakdale South	1	18.8	IN1- General Industrial ⁽⁵⁾	2017-2018
	2	4.4		2018
	3	16.5		2017-2019
	4	9.5		2019
	5	14.0		2017
	6	7.0		2019
	Total	70.2		
Oakdale East	1	95.0 ⁽³⁾	IN1- General Industrial	2022-2024 ⁽¹⁾
Oakdale West	1	21.7		2019
	2	21.6		2019-2020
	3	18.5		2020
	4	22.6		2020-2021
	5	6.1		2020
	Total	90.5		
Oakdale Central	1A	4.1	IN1- General Industrial	Built
	1B	5.9		Built
	1C	4.6		Q1-2016
	2A	7.5		Built

Development site	Precinct	Nett Development (ha)	Development type	Connection
	2B	6.0		Q1-2016
	3A	1.6		2017
	3B	5.8		Q4-2016
	3C	5.6		2017
	3D	1.9		2017
	Lot 4	2.2		2017
	Total	45.2		
Jacfin	1	3.6	IN1- General Industrial	2016
	2	17.4		2016
	3	21.6		2017
	4	25.7	Residential low density ⁽²⁾	2016
	5	19.5		2016
	Total	87.8		
CSR	1	10.1	IN1- General Industrial	2017
	2	20.8		2018
		11.5		
	3	21.0		2020 ⁽¹⁾
	Total	63.4		
Grand Total		452		

Note 1: The proposed timing of infrastructure proposed is subject to change

Note 2: Rural Residential

Note 3: Further growth listed for this study is in addition to current East Oakdale development plan

Note 4: The above growth projections have been provided by the following:

Developer	Contact(s) – Role	Received	Date received
CSR	Wayne Pasalich – CSR Senior Development Manager	Via Email	1st March 2016
Jacfin	Emma Sunderland – Calibre Consulting on behalf of Jacfin	Via Email	29th Feb 2016
Goodman	Richard Seddon – Goodman Development Manager	Via Email	29th Feb 2016

Note 5: Water demand assessed based on Light industrial / warehouse

2.2 Water Demand Projections

An evidence based approach to forecasting future demands in the study area, based on observed demands in an adjacent water supply system, was adopted as per the "Water System Planning Guidelines 2014". The Growth Servicing Strategy (GSS) demand estimation revised based on the following updated growth data:

- The proposed Oakdale Industrial demand within GSS model (i.e. 0.2 ML/d) will be replaced with evidence based industrial demand assumptions. i.e. 9.2 ML/d. the proposed demand previously calculated for this development removed from the model.
- Additional forecast growth within the Parkbridge Estate i.e. 264 dwellings
- Defer rezoning from Austral to Cecil Park supply system to post 2020 i.e. 450 dwellings. The 2020 sensitivity analysis with Austral demand will be developed.
- Potable top-up transfers into the Hoxton Park recycled water scheme reduced from 1.2 ML/d to 1.1 ML/d

The revised future demand projections for the Cecil Park supply system are presented in Table 5.

Table 5 Summary of revised future water demand- Cecil Park Supply System

Demand Category	2016 MDD ML/d	2020 MDD ML/d	2031 MDD ML/d	2036 MDD ML/d
Residential (LD)	6.2	10.2	31.7	47.7
Residential (HD)	0.03	4.9	5.3	5.4
Dual Retic Res (LD)	0.2	1.1	1.2	1.4
Dual Retic Res (HD)	0.03	0.1	0.1	0.1
Industrial	1.6	1.8	4.1	7.7
Commercial	8.6	13.8	24.7	40.6
Other	2.1	2.1	5.6	5.64
Oakdale Industrial	0.0	5.8	7.5	7.5
Total	18.8	39.8	80.3	116.0

The detailed methodology for projecting average day and maximum day demands is described in Tech Memo 1 (Appendix A).

Table 6 summarises the projected water demands for the Oakdale Industrial Development. Total projected max day demand in the Oakdale Precinct is 7.5 ML/d.

Table 6 Summary of Water Demand - Oakdale Industrial Development

Development site	Timing	Average Day Demand (ML/d)	Max Day Demand (ML/d)
Oakdale South	2017-2019	0.65	1.0
Oakdale West	2019-2021	0.83	1.3
Oakdale East	2022-2024	0.87	1.4
Oakdale Central	2016-2017	0.42	0.7
Jacfin	2016-2017	1.04	2.12
CSR	2017-2020	0.58	0.93
Total		4.4	7.5

3. Opportunities and constraints

The following is a summary of the key opportunities and constraints associated with water servicing of the Oakdale Industrial Development.

3.1 Opportunities

- Based on the supplied Oakdale growth projections, Cecil Park reservoir and Prospect Creek pumping station WP0184B have sufficient capacity to supply the entire Cecil Park zone including Oakdale Development for the 2020 demand scenario.
- A DN450 lead-in water main has been constructed as part of previous site works and has sufficient capacity to supply the entire Oakdale Development.
- Minchinbury Elevated supply zone has 2.5 ML/d transferable capacity to provide supply contingency to Oakdale Industrial. Extensions off Sydney Water's existing DN300 trunk main will need to be built. i.e. approx. 1.2 Km.
- The Growth Servicing Strategy (GSS) proposed augmentations are adequate to supply the entire Cecil Park zone including Oakdale Development for the post 2031 demand scenario. Additional augmentations as a result of the GSS study include 30 ML new reservoir will provide system reliability.
- Customers along Aldington Rd that experiencing low pressure under current maximum day demand could be rezoned to Oakdale development. i.e. 1.0 ML/d

3.2 Constraints

- Cecil Park reservoir and pumping station WP0184 has insufficient capacity to supply the entire Cecil Park zone including Oakdale Development post 2020 demand scenario, when Austral and Leppington North will be rezoned to Cecil Park supply system. The GSS system augmentations (i.e. Prospect Creek pumping station WP0184B and raising main upgrade) proposed for 2031 demand scenario will address the long term system capacity issues within Cecil Park supply system.
- Erskine Park Elevated supply system has insufficient head to supply Oakdale Industrial system.

The opportunities and constraints identified in Oakdale Industrial water servicing plan is presented in Figure 3.




Figure 3 Opportunities and constraints

4. Water servicing

4.1 Oakdale Industrial water servicing

4.1.1 Oakdale Central

Oakdale Central is currently supplied from the existing DN250 potable water main within Millner Avenue (refer section 3-4 on figure 4) which is supplied from the Cecil Park Supply System. To improve system reliability, it is proposed to supply Oakdale Central from the Minchinbury Elevated supply system via a proposed DN300 connection (refer section 4-7 on Fig. 4) between the existing DN250 potable water main within Millner Avenue (refer section 3-4 on Fig. 4) to the proposed DN300 within Oakdale West (refer section 7-8 on Fig. 4) which ultimately connects to the existing DN300 within Erskine Park Link Road (EPLR). The proposed DN300 is proposed to be delivered at the same time as the Oakdale West development.

4.1.2 Oakdale South

Oakdale South will be supplied via extension (refer section 4-6 on Fig. 4) of the existing DN250 potable water main (Refer Section 3-4 on Fig. 4) within Millner Avenue which is supplied from the Cecil Park Supply System.

4.1.3 Oakdale West

Oakdale West will be supplied via a proposed DN300 (refer section 8-9 on Fig. 2) connection to the existing DN300 within Erskine Park Link Road (EPLR). This proposed DN300 will be supplied from the Minchinbury Elevated Supply System. As mentioned above, a DN300 cross connection (refer section 4-7 on Fig. 2) to Oakdale Central will be delivered at the same time as the Oakdale West development to supply Oakdale Central from the Minchinbury Elevated Supply System which will improve the system reliability.

4.1.4 Oakdale East

Oakdale East will be supplied off the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System.

4.1.5 CSR

CSR lands will be supplied via a proposed DN300 connected to the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System.

4.1.6 Jacfin

Jacfin lands will be supplied via a proposed DN300 connected to the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System. Jacfin internal reticulation will be via a proposed DN250 which will be connected to the proposed DN250 within Oakdale South to improve the system reliability.

4.2 Short-term servicing plan (Current- 2020)

Under this short-term supply configuration, Oakdale development will be supplied from Cecil Park supply system using existing DN450 lead-in main. The proposed internal pipework within Oakdale South need to be completed. i.e. 850 m DN250 and 850 m DN200.

Cecil Park reservoirs have sufficient capacity to supply the Cecil Park zone for the current max day scenario including proposed 2020 growth in the Oakdale Development as summarised below:

- Oakdale South, (i.e. 2020 MDD: 1.0 ML/d)
- Oakdale Central, (i.e. 2020 MDD: 0.7 ML/d)
- Oakdale West, (i.e. 2020 MDD: 1.0 ML/d)
- Jacfin, (i.e. 2020 MDD: 2.1 ML/d) and
- CSR. (i.e. 2020 MDD: 0.9 ML/d)

4.3 Mid-term servicing plan (2020- 2031)

Cecil Park reservoirs and transfer system have capacity to supply Cecil Park zone for the 2020 max day scenario including proposed 2020 growth in the Oakdale Development.

Between 2020 and 2024 the following actions are proposed:

- Rezoning to occur @ 2020 of Austral onto Cecil park (MDD: 2.8 ML/d @ 2020 and through to MDD: 4.8 ML/d @ 2024-25) (South West Priority Land Release Area “SWPLRA”; May 2016)
- Further growth within the Oakdale Development 1.7 ML/d (Oakdale Industrial will be fully developed at 2024)

The above contribute to significant capacity deficiencies within the system. i.e. WP0184 and Cecil Park reservoirs cannot keep up with a max week demand. By rezoning Oakdale West and Central on to Minchinbury Elevated relieves demand of 1.6 ML/d provides sufficient capacity relief to accommodate the forecasted demand and rezoning up to 2024.

Therefore, under mid-term servicing plan, Oakdale West and Oakdale Central will be supplied from Minchinbury Elevated supply zone using existing DN300 trunk main (i.e. gravity supply from elevated reservoir). Extensions off Sydney Water’s existing DN300 trunk main will need to be built. i.e. approx. 1.2 Km. Customers along Aldington Rd (i.e. approx. 28 customers) that experiencing low pressure under current maximum day demand could also be rezoned to Minchinbury Elevated supply zone using the proposed DN300 trunk main within Oakdale West.

The Oakdale Industrial remainder including Jacfin and CSR would be supplied from Cecil Park using existing DN450 and proposed DN300 lead-in main.

From 2024 through to 2030 there is insufficient capacity within both the Minchinbury Elevated and Cecil Park supply systems to accommodate growth within the Oakdale Industrial area.

Between 2024 and 2030 the following actions are proposed:

- Further growth in the Austral rezoned area now being fed from Cecil Park
- Rezoning to occur @ 2024 of Leppington North onto Cecil Park (7.3 ML/d @ 2024) (South West Priority Land Release Area “SWPLRA”; May 2016)

Accordingly, further investigation into the proposed rezoning and or required amplification of the system prior to this date is required.

4.4 Long-term servicing plan (Post 2030)

The Oakdale Industrial development will be supplied from Cecil Park and Minchinbury Elevated supply systems. Cecil Park reservoirs (i.e. including any proposed new reservoir) and upgraded Prospect Creek pumping station WP0184B have sufficient capacity to supply the Cecil Park zone for the 2036 max day scenario including ultimate growth within the Oakdale Development. This is based on an indicative scheme included in the GSS but subject to detailed planning before finalisation of preferred option.

The Oakdale servicing plan overview is presented in Figure 4.




Figure 4- Oakdale Industrial Water Servicing Plan

4.5 Preliminary capital cost assessment

Preliminary capital cost estimates were developed for Oakdale Development. The water mains indirect and total delivery costs were estimated using the Sydney Water Cost Estimator tool (version 09-2015.11). The following assumptions were adopted for preliminary cost estimation:

- 75% scope contingency was adopted for all options as per advice from Sydney Water
- An allowance was made for rock excavation for 30% of the length of the water mains
- 25% Road restoration was allowed for all pipework

A summary of the preliminary capital cost estimates associated with Oakdale Industrial water servicing is presented in Table 7. Detailed cost estimates are provided in Appendix B.

Table 7 Preliminary capital cost estimates

Section	Description	Delivery Date	Capital Cost (\$M)
1-2	4.0 km DN450	Constructed	NA
2-3	0.35 km DN250	Constructed	NA
3-4	1.2 km DN250	Constructed	NA
2-4	1.2 km DN300	2016-17	\$2.21 M
4-5	0.9 km DN250	2016-17	\$1.34 M
5-6	0.85 km DN200	2016-2017	\$1.08 M
4-7	0.7 km DN300	2017-2018	\$ 1.31 M
7-8	1.2 km DN300	2018-2019	\$2.21 M
8-9	1.6 km DN300	2018-2019	\$2.93 M

5. Conclusions and Recommendations

This study investigated the assets required to service the proposed Goodman, Jacfin and CSR developments within the Oakdale Precinct to meet development timeframes. The water servicing plan for the Oakdale Industrial Development is made up of the following:

Oakdale Central

Oakdale Central is currently supplied from the existing DN250 potable water main within Millner Avenue which is supplied from the Cecil Park Supply System. To improve system reliability, it is proposed to supply Oakdale Central from the Minchinbury Elevated supply system via a proposed DN300 connection between the existing DN250 potable water main within Millner Avenue to the proposed DN300 within Oakdale West which ultimately connects to the existing DN300 within Erskine Park Link Road (EPLR). The proposed DN300 is proposed to be delivered at the same time as the Oakdale West development.

Oakdale South

Oakdale South will be supplied via extension of the existing DN250 potable water main within Millner Avenue which is supplied from the Cecil Park Supply System.

Oakdale West

Oakdale West will be supplied via a proposed DN300 connection to the existing DN300 within Erskine Park Link Road (EPLR). This proposed DN300 will be supplied from the Minchinbury Elevated Supply System. As mentioned above, a DN300 cross connection to Oakdale Central will be delivered at the same time as the Oakdale West development to supply Oakdale Central from the Minchinbury Elevated Supply System which will improve the system reliability.

Oakdale East

Oakdale East will be supplied off the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System.

CSR

CSR lands will be supplied via a proposed DN300 connected to the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System.

Jacfin

Jacfin lands will be supplied via a proposed DN300 connected to the existing DN450 within Burley Road which is supplied from the Cecil Park Supply System. Jacfin internal reticulation will be via a proposed DN250 which will be connected to the proposed DN250 within Oakdale South to improve the system reliability.

Appendices

Appendix A –Revised Basis of Water Planning



Memorandum

25 May 2016

To	Amir Rashidi		
Copy to	Russell Hogan, Suhanti Thirunavukarasu, Suganthini Niranjani		
From	Amir Rashidi	Tel	02 92397010
Subject	Oakdale Industrial- Revised Basis of Water Planning	Job no.	21/25274

1. Introduction

1.1 Purpose of this memorandum

The purpose of this memorandum is to document and seek endorsement from Sydney Water on the design and system performance criteria to be adopted for the investigation associated with the water system within the Oakdale Industrial development. It is important that Sydney Water agrees to these criteria prior to substantial commencement of the planning tasks.

1.2 Background

The Oakdale industrial site is part of the existing Western Sydney Employment Area (WSEA 8 – Area South of Pipeline Precinct), located approximately 40 kms west of the Sydney CBD, adjacent to the M7 and M4 intersection, adjacent south to the Eastern Creek Precinct and Warragamba Water Pipeline at Horsley Park. The site was rezoned in September 2009 through the WSEA SEPP 2009, and Goodman is the lead developer of the precinct. An overview of study area is presented in Figure 1.

Water: The initial scheme was to supply the site from Cecil Park; however, there is an alternative option to supply Oakdale through a combination of the Minchinbury and Cecil Park supply zones. Extensions off Sydney Water's existing system will need to be built to provide the full site with drinking water services.

Assets required to service proposed Goodman development at Oakdale are to be staged to meet development timeframes, with lead-in infrastructure funded up front and delivered by the lead developer and to be reimbursed by Sydney Water in accordance with its policy on Funding Infrastructure to Service Growth.




Figure 1 Oakdale Industrial Development Overview

2. Summary of Growth

This section provides details of growth projections within the study area including the expected timing, and scale of growth.

2.1 Growth

Population growth forecasts are a key input into the planning process and provide an insight into future infrastructure needs as well as future capital investment needs.

Oakdale Estate is a future industrial development with approximately 300 nett hectares of development lots anticipated in the ultimate stage. The site spans two local government areas of Penrith and Fairfield.

The growth projections listed for this study are supplied by AT&L in conjunction with Jacfin, CSR and Goodman. The list of the growth projection within the Oakdale Industrial Development is summarised in Table 1. Detailed figures for each of the developments are included in Appendix A.

Table 1 Growth projections

Development site	Precinct	Nett Development (ha)	Development type	Timing
Oakdale South	1	18.8	Light industrial/warehouse	2017-2018
	2	4.4		2018
	3	16.5		2017-2019
	4	9.5		2019
	5	14.0		2017
	6	7.0		2019
	Total	70.2		
Oakdale East	1	95.0⁽³⁾	Light industrial/warehouse	2022-2024 ⁽¹⁾
Oakdale West	1	21.7	Light industrial/warehouse	2019
	2	21.6		2019-2020
	3	18.5		2020
	4	22.6		2020-2021
	5	6.1		2020
	Total	90.5		

Development site	Precinct	Nett Development (ha)	Development type	Timing
Oakdale Central	1A	4.1	Light industrial/warehouse	Built
	1B	5.9		Built
	1C	4.6		Q1-2016
	2A	7.5		Built
	2B	6.0		Q1-2016
	3A	1.6		2017
	3B	5.8		Q4-2016
	3C	5.6		2017
	3D	1.9		2017
	Lot 4	2.2		2017
	Total	45.2		
Jacfin	1	3.6	Light industrial/warehouse	2016
	2	17.4		2016
	3	21.6		2017
	4	25.7	Residential low density ⁽²⁾	2016
	5	19.5		2016
	Total	87.8		
CSR	1	10.1	Light industrial/warehouse	2017
	2	32.3		2018
		11.5	Environmental /Open Space	
	3	21.0	Light industrial/warehouse	2020 ⁽¹⁾
	Total	74.9		
Grand Total		463.6		

Note 1: The timeframes are subject to change

Note 2: Rural Residential

Note 3: Further growth listed for this study is in addition to current East Oakdale development plan

Note 4: The above growth projections have been provided by the following:

Developer	Contact(s) - Role	Received	Date received
CSR	Wayne Pasalich – CSR Senior Development Manager	Via Email	1 st March 2016
Jacfin	Emma Sunderland – Calibre Consulting on behalf of Jacfin	Via Email	29 th Feb 2016
Goodman	Richard Seddon – Goodman Development Manager Russell Hogan – AT&L on behalf of Goodman	Via Email	29 th Feb 2016

3. Planning criteria

3.1 Water planning criteria

This section details the water planning criteria relevant to this investigation. We request Sydney Water's endorsement of the design criteria as a hold point for the project prior to commencement of the system performance assessment.

3.2 Water planning references

The following documents, referenced in Table 2, were consulted in developing the planning criteria:

1. Water and Recycled Water System Growth Servicing Strategy – Criteria and Guidelines 2012
2. Water System Planning Guideline (ver. 1- September 2014)
3. Water Supply Code of Australia (WSA 03-2011-3.1 - Sydney Water Edition 2012)
4. Recommendation – Water-main renewal program interim sizing rules to address fire-fighting needs
5. Precinct Structure Plan

Table 2 Water Planning Criteria

Item	Design Criteria	Units	Water	Reference
System Demands (existing areas)				
Max Day Demand (MDD)	Max Day Demand /Average Day Demand (MDD/ADD) Factor	NA	An analysis of the last ten consecutive financial years of IICATS data to select the day with the highest demand over 24 hours. The peaking factor will be derived from calculated MDD and ADD. (i.e. peaking factor: MDD/ADD) <ul style="list-style-type: none"> • Cecil Park Supply System peaking factor: 2.8 • Cecil Park maximum day demand : 18.75 ML/d • Minchinbury Supply System peaking factor: 1.6 • Minchinbury maximum day demand : 5.2 ML/d 	Reference 2 See Appendix C
Max Hour Demand	Max Hour Demand /Max Day Demand Factor	NA	An analysis of the last ten years of 15 minutes of IICATS data to select the maximum hour event. If the results are inconsistent then the default WMS maximum day demand diagram will be adopted	Reference 2
Performance Requirements				
Trunk Mains	Minimum Pressure	Meter	Trunk mains (no customer connections) will maintain 3 m at all times under max day demand condition	Reference 1

Item	Design Criteria	Units	Water	Reference
Reticulation Mains	Minimum Pressure	m	Maintain at the property boundary: >25 m residual pressure (desirable) ⁽²⁾	
	Maximum Pressure	m	The long-term aim is to reduce to 60 m or less where financially viable	Reference 2
	Maximum headloss	km/ hr.	Maximum headloss of 5 m/km for ≤ DN150 and 3 m/km for ≥ DN200. (secondary criteria)	Reference 3
	Maximum Velocity	m/s	>2 m/s (i.e. The optimum velocity is in the range 0.8 m/s to 1.4 m/s.)	
Critical water-mains (Fire flow criteria)	Fire-Fighting Enquiries	L/s	High density residential, major special uses and heavy commercial and industrial : Not less than 10 m residual head with assume flow of 25 L/s (at 95th percentile domestic demand)	Reference 4
Minimum Pipe Size	Flow rates & residual pressure	mm	Industrial and Commercial: Cast iron outside diameter series: 150; Steel and Polyethylene pipes: 180	Reference 3

WMS model for water planning purposes ⁽¹⁾

Minchinbury	<p><u>Current MDD:</u> > Potable Retic>04. Prospect South>4.1 Minchinbury>Minchinbury-Minchinbury Elevated>20 Projects>GSS 2013-14>HP2 System Performance>Max Day>GSS - Current Max Day Run 1.1</p> <p><u>2031 MDD Model Run:</u> >Potable Retic>04. Prospect South>4.1 Minchinbury>Minchinbury-Minchinbury Elevated>20 Projects>GSS 2013-14>HP2 System Performance>Max Day>GSS - 2031 Max Day Run 1.1</p> <p><u>2036 MDD Model Run:</u> >Potable Retic>04. Prospect South>4.1 Minchinbury>Minchinbury-Minchinbury Elevated>20 Projects>GSS 2013-14>HP2 System Performance>Max Day>GSS - 2036 Max Day Run 1.1</p>
Cecil Park	<p><u>Current MDD :</u> >Potable Retic>04. Prospect South>4.4 Cecil Park>Cecil Park>20 Projects>WSEA - Structure Plan Update>GSS Run Group>Current Max Day</p> <p><u>2031 MDD Model Run :</u> >Potable Retic>04. Prospect South>4.4 Cecil Park>Cecil Park>20 Projects>GSS>Run Group>2031 Max week GSS_Solutions</p> <p><u>2036 MDD Model Run :</u> >Potable Retic>04. Prospect South>4.4 Cecil Park>Cecil Park>20 Projects>GSS>Run Group>2036 Max week_Solutions_N</p>

Note 1: The GSS model for Minchinbury was used as this was the latest study in the local area and included an update of key assets and system demands. This will be validated and forecast demands updated as part of this project. The GSS model for Cecil Park was referenced in the recent SWPLRA / SWGC 2nd release precincts detailed planning investigation and is the latest version of the Cecil Park model available. This will be validated and forecast demands updated to reflect latest data. This has been discussed and confirmed with Sydney Water.

Note 2: The minimum pressure specified in the Operating Licence is 15 metres, however, some exceedances of this limit are permitted. Refer to Sydney Water Operating Licence. A lower minimum service pressure may be provided based on financial and risk considerations, and is subject to Sydney Water approval.

4. Water demand assessment

A baseline maximum day demand of 40 kL/Nha/day for light industrial new development was employed from Water System Planning Guideline to estimate the Oakdale Industrial water demand. During this assessment, it was observed that new development that anticipated occurring in Oakdale industrial will be typically warehouses with commercial / office land use. Consequently, Sydney Water advice to reassess the Oakdale industrial future demand based upon the Moorebank and Wetherill Park industrial areas that exhibit a similar type of development. The evidence based average day water demand summarised in Table 3. Figure 2 also shows the location of the Moorebank and Wetherill Park industrial areas in relation to the Oakdale Industrial precinct. .

Table 3 Evidence based average day water demand for comparable Industrial Areas ⁽¹⁾

Average Day Demand	Units	Moorebank	Wetherill Park	Weighted Average
Area demand (average)	kL/day	1,324	4,520	-
Area	Hectares	182	456	-
Demand per net hectare	kL/net ha/day	7.3	9.9	9.2

Note 1: The evidence based industrial demand employed from Broader WSEA Water Services Study (Nov 2013)

4.1 Summary of Oakdale Industrial water demand forecasts

The following outline of potable water demand provides predicted average day (ADD), maximum day (MDD) and maximum hour demand (MHD) based on projected development yield.

The calculations are based on the forecast development yield (i.e. Table 1) and evidence base design demands (Table 3). Detailed calculations for MDD and MHD demand are provided in Appendix B. The Oakdale Industrial demand forecast summarised in Table 4.

Table 4 Summary of revised water demand- Oakdale Industrial fully developed

Development site	Demand Scenario (ML/d)		
	ADD	MDD	MHD
Oakdale South	0.65	1.0	1.65
Oakdale West	0.83	1.3	2.13
Oakdale East	0.87	1.4	2.24
Oakdale Central	0.42	0.7	1.08
Jacfin	1.04	2.12	4.1
CSR	0.58	0.93	1.49
Total	4.4	7.5	12.7

Note 1: the maximum demand was estimated based on Industrial peaking factor of 1.6 (i.e. MDD/ADD)




Figure 2- Comparable Industrial Areas

21/25274/214076

GHD

Level 15, 133 Castlereagh Street Sydney NSW 2000 Australia

T 61 2 9239 7100 F 61 2 9239 7199 E sydney@ghd.com W www.ghd.com

4.2 Future Max Day Demand Projections

The Growth Servicing Strategy (GSS) demand estimation revised based on the following updated growth data:

- Additional forecast growth within the Parkbridge Estate i.e. 264 dwellings
- Defer rezoning from Austral to Cecil Park supply system to post 2020 i.e. 450 dwellings. The 2020 sensitivity analysis with Austral demand will be developed.
- Potable top-up transfer into the Hoxton Park recycled water scheme reduced from 1.2 ML/d to 1.1 ML/d (i.e. The Hoxton Park Recycled Water top-up water demand pattern will be employed)
- The proposed Oakdale Industrial demand within GSS model (i.e. 0.2 ML/d) will be replaced with revised demand assumptions (Table 4)

The revised future demand projections are presented in Table 5. The residential growth sites details are provided in Appendix D.

Table 5 Summary of revised future water demand- Cecil Park Supply System

Demand Category	2016 MDD ML/d	2020 MDD ML/d	2031 MDD ML/d	2036 MDD ML/d
Residential (LD)	6.2	10.2	31.7	47.7
Residential (HD)	0.03	4.9	5.3	5.4
Dual Retic Res (LD)	0.2	1.1	1.2	1.4
Dual Retic Res (HD)	0.03	0.1	0.1	0.1
Industrial	1.6	1.8	4.1	7.7
Commercial	8.6	13.8	24.7	40.6
Other	2.1	2.1	5.6	5.64
Oakdale Industrial	0.0	5.8	7.5	7.5
Total	18.8	39.8	80.3	116.0

Appendix A- Oakdale Industrial Detailed Development


CENTRAL Area Schedule

TOTAL LAND AREA		612,065 sqm
Lot	Site Area	Building Area
Lot 1A	41,368 sqm	20,220 sqm
Lot 1B	58,760 sqm	31,745 sqm*
Lot 1C	46,417 sqm	27,145 sqm*
Lot 2A	74,693 sqm	36,570 sqm
Lot 2B	60,010 sqm	31,080 sqm*
Lot 3A	16,016 sqm	7,283 sqm*
Lot 3B	58,493 sqm	36,965 sqm*
Lot 3C	55,622 sqm	33,426 sqm*
Lot 3D	18,795 sqm	8,275 sqm*
SUB TOTAL	414,158 sqm	232,709 sqm*
Lot 4	21,615 sqm	0 sqm*
CENTRAL TOTAL	435,773 sqm	232,709 sqm*
Services Lot	10,000 sqm	
Biodiversity Lot A	18,367 sqm	
Biodiversity Lot B	40,812 sqm	
Biodiversity Lot C	41,533 sqm	
Road Widening Lots	4,572 sqm	

* Areas subject to Survey.




APPENDIX 1 STAGING PLAN




2017 = 10 DATE

Site Area Schedule	
Total Site Area	117.00 ha
Less:	
Non Developable Land	35.65 ha
Easements	3.73 ha
Regional Roads	1.74 ha
Services Lot	1.66 ha
Estate Roads	5.38 ha
	48.36 ha
Development Areas	
Precinct 1	18.81 ha
Precinct 2	4.38 ha
Precinct 3	16.53 ha
Precinct 4	9.45 ha
Precinct 5	14.01 ha
Precinct 6	7.09 ha
Total Developable	70.28 ha
Total Warehouse	376,295 sqm
Total Office	19,585 sqm
Total Facility	395,880 sqm



SEE DRAWING OAK MP03 FOR CONTINUATION

OAKDALE WEST
- ESTIMATED TAKE
UP FOR SERVICING



PRELIMINARY

Russell Hogan

From: Russell Hogan
Sent: Wednesday, March 2, 2016 3:11 PM
To: Mahmood Hossain (Mahmood.Hossain@ghd.com); 'Amir Rashidi (Amir.Rashidi@ghd.com)'
Subject: RE: Oakdale LASP update
Attachments: Appendix 2 Subdivision Development Application Plans.pdf

Gents,

Please see below staging horizons for CSR land.

Goodman information to follow shortly.

Also please see attached CSR proposed staging plan.

Regards,

Russell Hogan
Civil Project Manager



Level 7, 153 Walker Street
North Sydney NSW 2060

P 02 9439 1777
M 0424 441 231
F 02 9923 1055
russell@atl.net.au
www.atl.net.au

From: Pasalich, Wayne [<mailto:WPASALICH@csr.com.au>]
Sent: Tuesday, March 1, 2016 5:52 PM
To: Russell Hogan <Russell@atl.net.au>; Claire Kollaras <Claire.Kollaras@calibreconsulting.co>
Cc: Rachel Owen <Rachel.Owen@calibreconsulting.co>; Stuart Green <Stuart.Green@calibreconsulting.co>; Inbox <inbox1@atl.net.au>
Subject: RE: Oakdale LASP update

Russell

Claire is away on leave currently so I can address any queries you have. The current anticipated deliver program is as follows;

Stage	Registration Date	Notes
1	Q2 2017	Earlier connection would be beneficial as we have sold the property and the new owners are looking to make an early start on the works
2	Q1 2018	
3	TBA	No fixed date for this stage as the business does not currently have any plans to shut down the factory in the short term

Appendix B- Detail Water Demand Calculations

Industrial- Max Day Demand	15	kL/Nha/day
Residential- Max Day Demand	2.2	kL/dwelling/day

Development site	Precinct	Area (ha)	Development type	Timing	Average Day Demand (ML/d)	Maximum Day Demand (ML/d)	Maximum Hour Demand (ML/d)
Oakdale South	1	18.8	Light industrial/warehouse	2017-2018	0.17	0.28	0.44
	2	4.4	Light industrial/warehouse	2018	0.04	0.06	0.10
	3	16.5	Light industrial/warehouse	2017-2019	0.15	0.24	0.39
	4	9.5	Light industrial/warehouse	2019	0.09	0.14	0.22
	5	14	Light industrial/warehouse	2017	0.13	0.21	0.33
	6	7	Light industrial/warehouse	2019	0.06	0.10	0.16
Oakdale East	1	95	Light industrial/warehouse	2022-2024	0.87	1.40	2.24
	1	21.7	Light industrial/warehouse	2019	0.20	0.32	0.51
Oakdale West	2	21.6	Light industrial/warehouse	2019-2020	0.20	0.32	0.51
	3	18.5	Light industrial/warehouse	2020	0.17	0.27	0.44
	4	22.6	Light industrial/warehouse	2021-2020	0.21	0.33	0.53
	5	6.1	Light industrial/warehouse	2020	0.06	0.09	0.14
Oakdale Central	1A	4.1	Light industrial/warehouse	Built	0.04	0.06	0.10
	1B	5.9	Light industrial/warehouse	Built	0.05	0.09	0.14
	1C	4.6	Light industrial/warehouse	Q1-2016	0.04	0.07	0.11
	2A	7.5	Light industrial/warehouse	Built	0.07	0.11	0.18
	2B	6.0	Light industrial/warehouse	Q1-2016	0.06	0.09	0.14
	3A	1.6	Light industrial/warehouse	2017	0.01	0.02	0.04
	3B	5.8	Light industrial/warehouse	Q4-2016	0.05	0.09	0.14
	3C	5.6	Light industrial/warehouse	2017	0.05	0.08	0.13
	3D	1.9	Light industrial/warehouse	2017	0.02	0.03	0.04
	Lot 4	2.2	Commercial/cafe /light industrial	2017	0.02	0.03	0.05
Jacfin	1	3.6	Light industrial/warehouse	2016	0.03	0.05	0.08
	2	17.4	Light industrial/warehouse	2016	0.16	0.26	0.41
	3	21.6	Light industrial/warehouse	2017	0.20	0.32	0.51
	4	25.7	Residential low density (R4 Rural Residential)	2016	0.37	0.85	1.75
CSR	5	19.5	Residential low density (R4 Rural Residential)	2016	0.28	0.64	1.33
	1	10.1	Light industrial/warehouse	2017	0.09	0.15	0.24
	2	32.34	Light industrial	2018	0.30	0.48	0.76
		11.5	Environmental conservation area (Open Space)		0.00	0.00	0.00
Grand Total	3	21	Light industrial	2020	0.19	0.31	0.49
		463.6			4.39	7.48	12.7

Note 1: Timeframes are subject to change

Note 2: No water demand assumed for environmental conservation area within the CSR

Note 3: Additional development within Oakdale East

21/25274/214076

GHD

Level 15, 133 Castlereagh Street Sydney NSW 2000 Australia

T 61 2 9239 7100 F 61 2 9239 7199 E sydmail@ghd.com W www.ghd.com

Appendix C- Existing system demands assessment

Cecil Park supply system current demand

Historical system demand in the last 10 years was assessed to calculate the average day demand and to identify a suitable maximum day demand (MDD) event. Data from flow meter WF0557 downstream of Prospect Creek Pumping Station WP0184 and the reservoir level trends of Cecil Park Reservoirs were considered for the mass balance (i.e. flow data were not available from 2006 to 2009). The mass balance carried out for the above period indicated the highest max day value in November 2015 (i.e. 21.8 MI/d).

However, this event is not acceptable due to an open DV between Cecil Park and Liverpool system. Sydney Water advice to adopt the GSS peaking factor (i.e. MDD/ADD: 2.80).

Minchinbury supply system current demand

Analysis of historical Minchinbury system demand in IICATS (i.e. past 10-year data) revealed the highest max day value in 15 January 2015. Details of selected peak demand event is provided in Table 6.

Table 6 Historical demand assessment (MI/d)


	Cecil Park Supply System	Minchinbury Supply System	Notes
Average day demand (ADD)	6.7	32.1	# Cecil Park: 20 Nov 2015
Maximum day demand (MDD)	21.8	50.2	# Minchinbury: 15 Jan 2014
MDD/ ADD ratio	2.80	1.56	

The Table 7 below outlines the calculated MDD per demand category in Cecil Park and Minchinbury models. The individual demand category max day factors were based on the guideline factors applied to the actual MDD/ADD.

Table 7 Current maximum day demand breakdown

Demand Category	Cecil Park Water Supply System			Minchinbury Water Supply System		
	ADD (MI/d)	MDD factor	MDD (MI/d)	ADD (MI/d)	MDD factor	MDD (MI/d)
Residential (LD)	2.07	3.24	6.40	19.7	1.74	34.4
Residential (HD)	0.02	3.19	0.03	1.9	1.44	2.8
Commercial	3.38	3.05	7.49	1.7	1.52	2.6
Industrial	0.51	3.70	1.58	2.4	1.21	2.9
Other	0.23	1.89	2.54	2.2	1.52	3.3
UFW	0.7	1.0	0.7	4.2	1.0	4.2
Total	6.87	2.80	18.75	32.1	1.56	50.2


Cecil Park historical system demand analysis within the last 10 years demonstrated in figure below.



IICATS	Average (ML/d)	Maximum (ML/d)	MDD/ADD
Cecil Park	7.9	19.5 ⁽¹⁾	2.46

Note 1: Include 0.7 ML/day recycled water component that is potable water and should be subtracted from IICATS data. Hence, current max day of Cecil Park = 18.8 ML/day

Minchinbury historical system demand analysis demonstrated in figure below.



Residential Growth Sites – Dwellings (Cumulative)

*** These SWGC precincts are located outside of the existing Cecil Park zone boundary however the Cecil Park zone boundary will be extended in the future to enable supply from Cecil Park Reservoirs to these precincts



Appendix B – Detailed Cost Estimation

Sydney WATER										Cost Estimator			
Job Name:		Oakdale Central -2-3-								Estimate Date:		10/06/2016	
Estimator:		Amir Rashidi								Print Date/Time:		10/06/2016 18:32	
ITEM	H#	DESCRIPTION		PARAMETER		UNIT	QUANTITY	RATE		TOTAL			
DIRECT COSTS													
	H1	Option 1											
1		Water Main Greenfield PVC		200 dia		m			191		0		
2		Water Main Greenfield PVC		250 dia		m	350		238		83,204		
3		Water Main Greenfield PVC		300 dia		m			314		0		
4		Water Main Greenfield PVC		375 dia		m			407		0		
5		Water Main Greenfield DI CL		450 dia		m			569		0		
6		EO Rock Excav Trench Std Dpth - 200 Dia (1%RK-100%RK)		30		m	0		15		0		
7		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)		30		m	350		18		6,190		
8		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)		30		m	0		21		0		
9		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)		30		m	0		25		0		
10		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)		30		m	0		10		0		
11		EO Road Restoration Trench Std Depth		250 dia		m	88		434		37,980		
12		EO Road Restoration Trench Std Depth		300 dia		m	0		485		0		
13		EO Road Restoration Trench Std Depth		375 dia		m	0		513		0		
14		EO Road Restoration Trench Std Depth		450 dia		m	0		579		0		
15		EO Road Restoration Trench Std Depth		200 dia		m	0		409		0		
	H1	Scope Contingency											
16		Urban Detailed Planning		75		%	127,374		0.75		95,530		
Sub Total Direct Costs										222,904			
INDIRECT COSTS													
								%					
17		Contractor Design Costs (% of Direct Costs)						10.00%		22,290			
18		Contractor Indirect Costs (% of Direct Costs)						20.00%		44,581			
19		Contractor Margin (% of DC+Indirect Costs)						15.00%		43,466			
20		Risk Contingency (% of (Direct Costs+ Indirect Costs+Margin))						35.00%		116,634			
Total Construction Cost										449,875			
SWC CLIENT COSTS													
								% of ConstC					
21		SWC Costs to Date											
22		SWC Design Costs (% of Construction Costs)						1.00%		4,499			
23		SWC Tender Costs (% of Construction Costs)						0.50%		Adj. to Min Limit>>			

Sydney WATER Cost ESTIMATOR									
Job Name:		Oakdale Central -2-3-					Estimate Date: 10/06/2016		
Estimator:		Amir Rashidi					Print Date/Time: 10/06/2016 18:32		
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	Ver 09-2015.11		
TOTAL									
24		SWC Planning Costs (% of Construction Costs)			5.00%				22,494
25		SWC Project Management Costs (% of Construction Costs)			5.00%				22,494
26		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%				2,474
27		SWC Land Acquisition/Easement Costs							
28		SWC Risk Contingency (% of the SWC Client Future Costs only)				of Client Costs			
TOTAL PROJECT BUDGET REQUIREMENT									551,836

Sydney WATER				Cost Estimator			
Job Name:		Oakdale Central- 2-4-			Estimate Date: 10/06/2016		
Estimator:		Amir Rashidi			Print Date/Time: 04/07/2016 11:29		
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL
DIRECT COSTS							
	H1	Option 1					
1		Water Main Greenfield PVC	200 dia	m		191	0
2		Water Main Greenfield PVC	250 dia	m		238	0
3		Water Main Greenfield PVC	300 dia	m	1,200	314	377,012
4		Water Main Greenfield PVC	375 dia	m		407	0
5		Water Main Greenfield DI CL	450 dia	m	0	569	0
6		EO Rock Excav Trench Std Dpth - 200 Dia (1%RK-100%RK)	30	m	0	15	0
7		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	0	18	0
8		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	1,200	21	25,713
9		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0	25	0
10		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10	0
11		EO Road Restoration Trench Std Depth	250 dia	m	0	434	0
12		EO Road Restoration Trench Std Depth	300 dia	m	300	485	145,440
13		EO Road Restoration Trench Std Depth	375 dia	m	0	513	0
14		EO Road Restoration Trench Std Depth	450 dia	m	0	579	0
15		EO Road Restoration Trench Std Depth	200 dia	m	0	409	0
	H1	Scope Contingency					
16		Urban Detailed Planning	75	%	548,164	0.75	411,123
Sub Total Direct Costs							959,287
INDIRECT COSTS							
					%		
17		Contractor Design Costs (% of Direct Costs)			10.00%		95,929
18		Contractor Indirect Costs (% of Direct Costs)			20.00%		191,857
19		Contractor Margin (% of DC+Indirect Costs)			15.00%		187,061
20		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%		501,947
Total Construction Cost							1,936,081
SWC CLIENT COSTS							
					% of ConstC		
21		SWC Costs to Date					
22		SWC Design Costs (% of Construction Costs)			1.00%		19,361
23		SWC Tender Costs (% of Construction Costs)			0.50%	Adj. to Min Limit>>	50,000

Sydney WATER		Cost Estimator				
Job Name:	Oakdale Central- 2-4-		Estimate Date: 10/06/2016			
Estimator:	Amir Rashidi		Print Date/Time: 04/07/2016 11:29			
		Ver 09-2015.11				
ITEM H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL
24	SWC Planning Costs (% of Construction Costs)			5.00%		96,804
25	SWC Project Management Costs (% of Construction Costs)			5.00%		96,804
26	SWC Insurances & Financing Costs (% of Construction Costs)			0.55%		10,648
27	SWC Land Acquisition/Easement Costs					
28	SWC Risk Contingency (% of the SWC Client Future Costs only)				of Client Costs	
	TOTAL PROJECT BUDGET REQUIREMENT					2,209,698

Sydney: WATER Cost ESTIMATOR									
Job Name:		Oakdale Central -4-5-				Estimate Date: 10/06/2016			
Estimator:		Amir Rashidi				Print Date/Time: 10/06/2016 18:46			
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
DIRECT COSTS									
	H1	Option 1							
1		Water Main Greenfield PVC	200 dia	m		191		0	
2		Water Main Greenfield PVC	250 dia	m	900	238		213,954	
3		Water Main Greenfield PVC	300 dia	m		314		0	
4		Water Main Greenfield PVC	375 dia	m		407		0	
5		Water Main Greenfield DI CL	450 dia	m		569		0	
6		EO Rock Excav Trench Std Dpth - 200 Dia (1%RK-100%RK)	30	m	0	15		0	
7		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	900	18		15,917	
8		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	0	21		0	
9		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0	25		0	
10		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10		0	
11		EO Road Restoration Trench Std Depth	250 dia	m	225	434		97,662	
12		EO Road Restoration Trench Std Depth	300 dia	m	0	485		0	
13		EO Road Restoration Trench Std Depth	375 dia	m	0	513		0	
14		EO Road Restoration Trench Std Depth	450 dia	m	0	579		0	
15		EO Road Restoration Trench Std Depth	200 dia	m	0	409		0	
	H1	Scope Contingency							
16		Urban Detailed Planning	75	%	327,533	0.75		245,650	
Sub Total Direct Costs								573,183	
INDIRECT COSTS									
					%				
17		Contractor Design Costs (% of Direct Costs)			10.00%			57,318	
18		Contractor Indirect Costs (% of Direct Costs)			20.00%			114,637	
19		Contractor Margin (% of DC+Indirect Costs)			15.00%			111,771	
20		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%			299,918	
Total Construction Cost								1,156,827	
SWC CLIENT COSTS									
					% of ConstC				
21		SWC Costs to Date							
22		SWC Design Costs (% of Construction Costs)			1.00%			11,568	
23		SWC Tender Costs (% of Construction Costs)			0.50%			Adj. to Min Limit>>	50,000

Sydney WATER										Cost ESTIMATOR		
Job Name:		Oakdale Central -4-5-								Estimate Date:		10/06/2016
Estimator:		Amir Rashidi								Print Date/Time:		10/06/2016 18:46
										Ver 09-2015.11		
ITEM		H#	DESCRIPTION	PARAMETER		UNIT	QUANTITY		RATE		TOTAL	
24			SWC Planning Costs (% of Construction Costs)					5.00%			57,841	
25			SWC Project Management Costs (% of Construction Costs)					5.00%			57,841	
26			SWC Insurances & Financing Costs (% of Construction Costs)					0.55%			6,363	
27			SWC Land Acquisition/Easement Costs									
28			SWC Risk Contingency (% of the SWC Client Future Costs only)						of Client Costs			
			TOTAL PROJECT BUDGET REQUIREMENT								1,340,440	

Sydney WATER				Cost Estimator			
Job Name:		Oakdale Central -4-7		Estimate Date:		10/06/2016	
Estimator:		Amir Rashidi		Print Date/Time:		04/07/2016 11:30	
						Ver 09-2015.11	
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL
DIRECT COSTS							
	H1	Option 1					
1		Water Main Greenfield PVC	200 dia	m		191	0
2		Water Main Greenfield PVC	250 dia	m		238	0
3		Water Main Greenfield PVC	300 dia	m	700	314	219,923
4		Water Main Greenfield PVC	375 dia	m	0	407	0
5		Water Main Greenfield DI CL	450 dia	m		569	0
6		EO Rock Excav Trench Std Dpth - 200 Dia (1%RK-100%RK)	30	m	0	15	0
7		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	0	18	0
8		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	700	21	14,999
9		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0	25	0
10		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10	0
11		EO Road Restoration Trench Std Depth	250 dia	m	0	434	0
12		EO Road Restoration Trench Std Depth	300 dia	m	175	485	84,840
13		EO Road Restoration Trench Std Depth	375 dia	m	0	513	0
14		EO Road Restoration Trench Std Depth	450 dia	m	0	579	0
15		EO Road Restoration Trench Std Depth	200 dia	m	0	409	0
	H1	Scope Contingency					
16		Urban Detailed Planning	75	%	319,762	0.75	239,822
Sub Total Direct Costs							559,584
INDIRECT COSTS							
					%		
17		Contractor Design Costs (% of Direct Costs)			10.00%		55,958
18		Contractor Indirect Costs (% of Direct Costs)			20.00%		111,917
19		Contractor Margin (% of DC+Indirect Costs)			15.00%		109,119
20		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%		292,802
Total Construction Cost							1,129,380
SWC CLIENT COSTS							
					% of ConstC		
21		SWC Costs to Date					
22		SWC Design Costs (% of Construction Costs)			1.00%		11,294
23		SWC Tender Costs (% of Construction Costs)			0.50%	Adj. to Min Limit>>	50,000

Sydney WATER										Cost ESTIMATOR			
Job Name:		Oakdale Central -4-7								Estimate Date:		10/06/2016	
Estimator:		Amir Rashidi								Print Date/Time:		04/07/2016 11:30	
										Ver 09-2015.11			
ITEM		H#	DESCRIPTION		PARAMETER		UNIT	QUANTITY	RATE		TOTAL		
24			SWC Planning Costs (% of Construction Costs)					5.00%				56,469	
25			SWC Project Management Costs (% of Construction Costs)					5.00%				56,469	
26			SWC Insurances & Financing Costs (% of Construction Costs)					0.55%				6,212	
27			SWC Land Acquisition/Easement Costs										
28			SWC Risk Contingency (% of the SWC Client Future Costs only)							of Client Costs			
			TOTAL PROJECT BUDGET REQUIREMENT									1,309,824	

Sydney WATER COST ESTIMATOR									
Job Name:		Oakdale Central -5-6-				Estimate Date: 10/06/2016			
Estimator:		Amir Rashidi				Print Date/Time: 10/06/2016 18:47			
						Ver 09-2015.11			
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE			
DIRECT COSTS									
	H1	Option 1							
1		Water Main Greenfield PVC	200 dia	m	850		191		162,010
2		Water Main Greenfield PVC	250 dia	m			238		0
3		Water Main Greenfield PVC	300 dia	m			314		0
4		Water Main Greenfield PVC	375 dia	m			407		0
5		Water Main Greenfield DI CL	450 dia	m			569		0
6		EO Rock Excav Trench Std Dpth - 200 Dia (1%RK-100%RK)	30	m	850		15		12,431
7		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	0		18		0
8		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	0		21		0
9		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0		25		0
10		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0		10		0
11		EO Road Restoration Trench Std Depth	250 dia	m	0		434		0
12		EO Road Restoration Trench Std Depth	300 dia	m	0		485		0
13		EO Road Restoration Trench Std Depth	375 dia	m	0		513		0
14		EO Road Restoration Trench Std Depth	450 dia	m	0		579		0
15		EO Road Restoration Trench Std Depth	200 dia	m	213		409		86,959
	H1	Scope Contingency							
16		Urban Detailed Planning	75	%	261,400		0.75		196,050
Sub Total Direct Costs									457,450
INDIRECT COSTS									
17		Contractor Design Costs (% of Direct Costs)			%				
18		Contractor Indirect Costs (% of Direct Costs)			10.00%				45,745
19		Contractor Margin (% of DC+Indirect Costs)			20.00%				91,490
20		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			15.00%				89,203
Total Construction Cost									239,361
									923,249
SWC CLIENT COSTS						% of ConstC			
21		SWC Costs to Date							
22		SWC Design Costs (% of Construction Costs)				1.00%			9,232
23		SWC Tender Costs (% of Construction Costs)				0.50%		Adj. to Min Limit>>	50,000

Sydney WATER Cost ESTIMATOR									
Job Name:		Oakdale Central -5-6-					Estimate Date: 10/06/2016		
Estimator:		Amir Rashidi					Print Date/Time: 10/06/2016 18:47		
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	Ver 09-2015.11		
							TOTAL		
24		SWC Planning Costs (% of Construction Costs)			5.00%				46,162
25		SWC Project Management Costs (% of Construction Costs)			5.00%				46,162
26		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%				5,078
27		SWC Land Acquisition/Easement Costs							
28		SWC Risk Contingency (% of the SWC Client Future Costs only)				of Client Costs			
TOTAL PROJECT BUDGET REQUIREMENT									1,079,883

Sydney WATER				Cost Estimator			
Job Name:		Oakdale Central -7-8-			Estimate Date: 10/06/2016		
Estimator:		Amir Rashidi			Print Date/Time: 10/06/2016 18:47		
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL
DIRECT COSTS							
	H1	Option 1					
1		Water Main Greenfield PVC	200 dia	m		191	0
2		Water Main Greenfield PVC	250 dia	m		238	0
3		Water Main Greenfield PVC	300 dia	m	1,200	314	377,012
4		Water Main Greenfield PVC	375 dia	m		407	0
5		Water Main Greenfield DI CL	450 dia	m		569	0
6		EO Rock Excav Trench Std Dpth - 200 Dia (1%RK-100%RK)	30	m	0	15	0
7		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	0	18	0
8		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	1,200	21	25,713
9		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0	25	0
10		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10	0
11		EO Road Restoration Trench Std Depth	250 dia	m	0	434	0
12		EO Road Restoration Trench Std Depth	300 dia	m	300	485	145,440
13		EO Road Restoration Trench Std Depth	375 dia	m	0	513	0
14		EO Road Restoration Trench Std Depth	450 dia	m	0	579	0
15		EO Road Restoration Trench Std Depth	200 dia	m	0	409	0
	H1	Scope Contingency					
16		Urban Detailed Planning	75	%	548,164	0.75	411,123
Sub Total Direct Costs							959,287
INDIRECT COSTS							
					%		
17		Contractor Design Costs (% of Direct Costs)			10.00%		95,929
18		Contractor Indirect Costs (% of Direct Costs)			20.00%		191,857
19		Contractor Margin (% of DC+Indirect Costs)			15.00%		187,061
20		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%		501,947
Total Construction Cost							1,936,081
SWC CLIENT COSTS							
					% of ConstC		
21		SWC Costs to Date					
22		SWC Design Costs (% of Construction Costs)			1.00%		19,361
23		SWC Tender Costs (% of Construction Costs)			0.50%	Adj. to Min Limit>>	50,000

Sydney WATER Cost ESTIMATOR									
Job Name:		Oakdale Central -7-8-							
Estimator:		Amir Rashidi							
		Estimate Date: 10/06/2016							
		Print Date/Time: 10/06/2016 18:47							
		Ver 09-2015.11							
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
24		SWC Planning Costs (% of Construction Costs)			5.00%		96,804		
25		SWC Project Management Costs (% of Construction Costs)			5.00%		96,804		
26		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%		10,648		
27		SWC Land Acquisition/Easement Costs							
28		SWC Risk Contingency (% of the SWC Client Future Costs only)				of Client Costs			
		TOTAL PROJECT BUDGET REQUIREMENT					2,209,698		

Sydney: WATER Cost ESTIMATOR									
Job Name:		Oakdale Central -7-9-				Estimate Date: 10/06/2016			
Estimator:		Amir Rashidi				Print Date/Time: 10/06/2016 18:48			
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
DIRECT COSTS									
	H1	Option 1							
1		Water Main Greenfield PVC	200 dia	m		191		0	
2		Water Main Greenfield PVC	250 dia	m		238		0	
3		Water Main Greenfield PVC	300 dia	m	1,600	314		502,682	
4		Water Main Greenfield PVC	375 dia	m		407		0	
5		Water Main Greenfield DI CL	450 dia	m		569		0	
6		EO Rock Excav Trench Std Dpth - 200 Dia (1%RK-100%RK)	30	m	0	15		0	
7		EO Rock Excav Trench Std Dpth - 250 Dia (1%RK-100%RK)	30	m	0	18		0	
8		EO Rock Excav Trench Std Dpth - 300 Dia (1%RK-100%RK)	30	m	1,600	21		34,284	
9		EO Rock Excav Trench Std Dpth - 375 Dia (1%RK-100%RK)	30	m	0	25		0	
10		EO Rock Excav Trench Std Dpth - 450 Dia (1%RK-100%RK)	30	m	0	10		0	
11		EO Road Restoration Trench Std Depth	250 dia	m	0	434		0	
12		EO Road Restoration Trench Std Depth	300 dia	m	400	485		193,920	
13		EO Road Restoration Trench Std Depth	375 dia	m	0	513		0	
14		EO Road Restoration Trench Std Depth	450 dia	m	0	579		0	
15		EO Road Restoration Trench Std Depth	200 dia	m	0	409		0	
	H1	Scope Contingency							
16		Urban Detailed Planning	75	%	730,885	0.75		548,164	
Sub Total Direct Costs								1,279,049	
INDIRECT COSTS									
					%				
17		Contractor Design Costs (% of Direct Costs)			10.00%			127,905	
18		Contractor Indirect Costs (% of Direct Costs)			20.00%			255,810	
19		Contractor Margin (% of DC+Indirect Costs)			15.00%			249,415	
20		Risk Contingency (% of (Direct Costs+Indirect Costs+Margin))			35.00%			669,263	
Total Construction Cost								2,581,442	
SWC CLIENT COSTS									
					% of ConstC				
21		SWC Costs to Date							
22		SWC Design Costs (% of Construction Costs)			1.00%			25,814	
23		SWC Tender Costs (% of Construction Costs)			0.50%		Adj. to Min Limit>>	50,000	

Sydney WATER Cost ESTIMATOR									
Job Name:		Oakdale Central -7-9-					Estimate Date: 10/06/2016		
Estimator:		Amir Rashidi					Print Date/Time: 10/06/2016 18:48		
ITEM	H#	DESCRIPTION	PARAMETER	UNIT	QUANTITY	RATE	TOTAL		
24		SWC Planning Costs (% of Construction Costs)			5.00%				129,072
25		SWC Project Management Costs (% of Construction Costs)			5.00%				129,072
26		SWC Insurances & Financing Costs (% of Construction Costs)			0.55%				14,198
27		SWC Land Acquisition/Easement Costs							
28		SWC Risk Contingency (% of the SWC Client Future Costs only)				of Client Costs			
TOTAL PROJECT BUDGET REQUIREMENT									2,929,598

www.ghd.com

