


6.5.5 Proposed Works to Group C Courtyard

Significance	Little
Proposed use	Outdoor space, including new covered external circulation, including walkway, stairs and ramps
Demolition	Ground floor slabs  Figures 120, 121, 122: Intrusive structures within the courtyard, and the existing concrete floor slab, to be removed. Note: Demolition of the intrusive structures within the courtyard was included in the Early Works Package. Source: Tonkin Zulaikha Greer Architects, 2016.
Conservation works	- Repairs to retained windows and doors facing courtyard (covered above). - Brick cleaning and repointing. Removal of corrosive metal inserts. - Render repairs. - Repainting of painted surfaces. Includes removal and / or encapsulation of lead paint systems. - Cleaning of stained exposed external walls. - Repairs to existing copper rainwater disposal system where required. - Clean pigeon guano and install pigeon proofing.
Alterations + additions	- New covered external circulation including walkway, stairs and ramps. - Landscape treatment to courtyard