

Secretary's Environmental Assessment Requirements

Section 78A(8A) of the *Environmental Planning and Assessment Act*
Schedule 2 of the *Environmental Planning and Assessment Regulation 2000*

Application Number	SSD 7532
Proposal Name	Hunter Sports High School Redevelopment
Location	2 Pacific Highway, Gateshead
Applicant	NSW Department of Education
Date of Issue	21 March 2016
General Requirements	<p>The Environmental Impact Statement (EIS) must be prepared in accordance with, and meet the minimum requirements of clauses 6 and 7 of Schedule 2 the <i>Environmental Planning and Assessment Regulation 2000</i> (the Regulation).</p> <p>Notwithstanding the key issues specified below, the EIS must include an environmental risk assessment to identify the potential environmental impacts associated with the development.</p> <p>Where relevant, the assessment of the key issues below, and any other significant issues identified in the risk assessment, must include:</p> <ul style="list-style-type: none"> • adequate baseline data; • consideration of potential cumulative impacts due to other development in the vicinity (completed, underway or proposed); and • measures to avoid, minimise and if necessary, offset the predicted impacts, including detailed contingency plans for managing any significant risks to the environment. <p>The EIS must be accompanied by a report from a qualified quantity surveyor providing:</p> <ul style="list-style-type: none"> • a detailed calculation of the capital investment value (CIV) (as defined in clause 3 of the Environmental Planning and Assessment Regulation 2000) of the proposal, including details of all assumptions and components from which the CIV calculation is derived; • an estimate of the jobs that will be created by the future development during the construction and operational phases of the development; and • certification that the information provided is accurate at the date of preparation.
Key issues	<p>The EIS must address the following specific matters:</p> <p>1. Statutory and Strategic Context – including: Address the statutory provisions contained in all relevant environmental planning instruments, including:</p> <ul style="list-style-type: none"> • State Environmental Planning Policy (State & Regional Development) 2011; • State Environmental Planning Policy (Infrastructure) 2007; • State Environmental Planning Policy No.55 – Remediation of Land; and • Lake Macquarie Local Environmental Plan 2014.

	<p><i>Permissibility</i> Detail the nature and extent of any prohibitions that apply to the development.</p> <p><i>Development Standards</i> Identify compliance with the development standards applying to the site and provide justification for any contravention of the development standards.</p> <p>2. Policies Address the relevant planning provisions, goals and strategic planning objectives in the following:</p> <ul style="list-style-type: none"> • NSW State Priorities; • NSW Long Term Transport Master Plan 2012; • Hunter Regional Transport Plan 2014; and • Healthy Urban Development Checklist, NSW Health. <p>3. Built Form and Urban Design</p> <ul style="list-style-type: none"> • Address the height, density, bulk and scale, setbacks of the proposal in relation to the school campus and the surrounding development, topography, streetscape and public open spaces. • Address design quality, with specific consideration of the overall site layout, streetscape, open spaces, façade, rooftop, massing, setbacks, building articulation, materials, colours and Crime Prevention Through Environmental Design Principles. • Detail how services, including but not limited to waste management, loading zones, and mechanical plant are integrated into the design of the development. <p>4. Environmental Amenity Detail amenity impacts including solar access, acoustic impacts, visual privacy, view loss, overshadowing and wind impacts. A high level of environmental amenity for any surrounding residential land uses must be demonstrated.</p> <p>5. Transport and Accessibility Include a transport and accessibility impact assessment, which details, but not limited to:</p> <ul style="list-style-type: none"> • the existing and proposed pedestrian and cycle routes and facilities within the vicinity of the site and to public transport facilities as well as measures to maintain road and personal safety in line with CPTED principles; • an estimate of the total daily and peak hour trips generated by the proposal, including vehicle, public transport, pedestrian and cycle trips; • the adequacy of public transport, pedestrian and bicycle movements to meet the likely future demand of the proposed development; • impact of the proposed development on existing and future public transport infrastructure within the vicinity of the site; • measures to promote travel choices that support sustainable travel, such as a location-specific sustainable travel plan, provision of end-of-trip facilities, green travel plans and wayfinding strategies; • the daily and peak (AM, PM and events) transport movements impact on nearby intersections, with consideration of the cumulative impacts from other approved developments in the vicinity, and the need/associated funding for upgrading or road improvement works (if required); • the proposed active transport access arrangements and
--	---

	<p>connections to public transport services;</p> <ul style="list-style-type: none"> • the proposed access arrangements, including car and bus pick-up/drop-off facilities, and measures to mitigate any associated traffic impacts and impacts on public transport, pedestrian and cycle networks; • proposed car and bicycle parking provision, including consideration of the availability of public transport and the requirements of the relevant parking codes and Australian Standards; • service vehicle access, delivery and loading arrangements and estimated service vehicle movements (including vehicle type and the likely arrival and departure times); and • traffic and transport impacts during construction and how these impacts will be mitigated for any associated traffic, pedestrian, cyclists, parking and public transport, including the preparation of a draft Construction Traffic Management Plan to demonstrate the proposed management of the impact. <p>→ <i>Relevant Policies and Guidelines:</i></p> <ul style="list-style-type: none"> • <i>Guide to Traffic Generating Developments (Roads and Maritime Services)</i> • <i>EIS Guidelines – Road and Related Facilities (DoPI)</i> • <i>Cycling Aspects of Austroads Guides</i> • <i>NSW Planning Guidelines for Walking and Cycling</i> • <i>Austroads Guide to Traffic Management Part 12: Traffic Impacts of Development</i> • <i>Standards Australia AS2890.3 (Bicycle Parking Facilities)</i> <p>6. Ecologically Sustainable Development (ESD)</p> <ul style="list-style-type: none"> • Detail how ESD principles (as defined in clause 7(4) of Schedule 2 of the Environmental Planning and Assessment Regulation 2000) will be incorporated in the design and ongoing operation phases of the development. • Demonstrate that the development has been assessed against a suitably accredited rating scheme to meet industry best practice. • Include a description of the measures that would be implemented to minimise consumption of resources, water (including water sensitive urban design) and energy. <p>7. Biodiversity</p> <p>Biodiversity impacts related to the proposed development are to be assessed and documented in accordance with the Framework for Biodiversity Assessment (FBA)(OEH 2014), unless otherwise agreed by OEH, by a person accredited in accordance with s142B(1)(c) of the <i>Threatened Species Conservation Act 1995</i>.</p> <p><u>Note:</u> In accordance with s5.1.1.3 of the FBA, areas that are not native vegetation do not require further assessment in the FBA except where it is assessed as habitat for threatened species according to Section 6.4.</p> <p>8. Aboriginal Heritage</p> <p>Where relevant, the EIS shall address Aboriginal Heritage in accordance with the Draft Guidelines for Aboriginal Cultural Heritage Impact Assessment and Community Consultation 2005 and Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010.</p> <p>9. Noise and Vibration</p> <p>Identify and provide a quantitative assessment of the main noise and vibration generating sources during construction and operation. Outline measures to minimise and mitigate the potential noise impacts on surrounding occupiers of land.</p>
--	---

	<p>→ <i>Relevant Policies and Guidelines:</i></p> <ul style="list-style-type: none"> • <i>NSW Industrial Noise Policy (EPA)</i> • <i>Interim Construction Noise Guideline (DECC)</i> • <i>Assessing Vibration: A Technical Guideline 2006</i> <p>10. Contamination Demonstrate that the site is suitable for the proposed use in accordance with SEPP 55.</p> <p>→ <i>Relevant Policies and Guidelines:</i></p> <ul style="list-style-type: none"> • <i>Managing Land Contamination: Planning Guidelines - SEPP 55 Remediation of Land (DUAP)</i> <p>11. Utilities</p> <ul style="list-style-type: none"> • Prepare an Infrastructure Management Plan in consultation with relevant agencies, detailing information on the existing capacity and any augmentation requirements of the development for the provision of utilities including staging of infrastructure. • Prepare an Integrated Water Management Plan detailing any proposed alternative water supplies, proposed end uses of potable and non-potable water, and water sensitive urban design. <p>12. Contributions Address Council's Section 94A Contribution Plan and/or details of any Voluntary Planning Agreement.</p> <p>13. Drainage Detail drainage associated with the proposal, including stormwater and drainage infrastructure.</p> <p>14. Flooding Assess any flood risk on site (detailing the most recent flood studies for the project area) and consideration of any relevant provisions of the NSW Floodplain Development Manual (2005), including the potential effects of climate change, sea level rise and an increase in rainfall intensity.</p> <p>15. Waste Identify, quantify and classify the likely waste streams to be generated during construction and operation and describe the measures to be implemented to manage, reuse, recycle and safely dispose of this waste. Identify appropriate servicing arrangements (including but not limited to, waste management, loading zones, mechanical plant) for the site.</p> <p>17. Bushfire Address bushfire hazard and prepare a report that addresses the requirements for Special Fire Protection Purpose Development as detailed in Planning for Bush Fire Protection 2006 guidelines.</p>
Plans and Documents	<p>The EIS must include all relevant plans, architectural drawings, diagrams and relevant documentation required under Schedule 1 of the Environmental Planning and Assessment Regulation 2000. Provide these as part of the EIS rather than as separate documents.</p> <p>In addition, the EIS must include the following:</p> <ul style="list-style-type: none"> • Architectural drawings (dimensioned and including RLs); • Site Survey Plan, showing existing levels, location and height of existing and adjacent structures / buildings and boundaries; • Site Analysis Plan; • Stormwater Concept Plan;

	<ul style="list-style-type: none"> • Sediment and Erosion Control Plan; • Shadow Diagrams; • View Analysis / Photomontages; • Landscape Plan (identifying any trees to be removed and trees to be retained or transplanted); • Preliminary Construction Management Plan, inclusive of a Preliminary Construction Traffic Management Plan detailing vehicle routes, number of trucks, hours of operation, access arrangements and traffic control measures; • Geotechnical and Structural Report; • Accessibility Report; • Arborist Report; • Acid Sulphate Soils Management Plan (if required); and • Schedule of materials and finishes.
Consultation	<p>During the preparation of the EIS, you must consult with the relevant local, State or Commonwealth Government authorities, service providers, community groups and affected landowners.</p> <p>In particular you must consult with:</p> <ul style="list-style-type: none"> • Lake Macquarie City Council; • Roads and Maritime Services; and • Transport for NSW <p>The EIS must describe the consultation process and the issues raised, and identify where the design of the development has been amended in response to these issues. Where amendments have not been made to address an issue, a short explanation should be provided.</p>
Further consultation after 2 years	<p>If you do not lodge a development application and EIS for the development within two years of the issue date of these SEARs, you must consult further with the Secretary in relation to the preparation of the EIS.</p>
References	<p>The assessment of the key issues listed above must take into account relevant guidelines, policies, and plans as identified.</p>