MANAGING DIRECTORS MATTHEW PALAVIDIS VICTOR FATTORETTO



DIRECTORS MATTHEW SHIELDS BEN WHITE

20160612.2/2605A/R2/HP

26/05/2017

DEXUS Property Group PO Box R1822 ROYAL EXCHANGE NSW 1225

# North Shore Private Hospital - East Tower Expansion - Response to EPA Comments

## **1** INTRODUCTION

This letter is in response to the EPA letter (EPA Ref: DOC17/207116-04) from Mark Hanemann, dated the 10<sup>th</sup> of May 2017.

## **2 RESPONSE**

Acoustic Logic Consultancy agree with the EPA that detailed acoustic design work needs to be done and that reporting should be submitted prior to construction.

#### 2.1 OPERATIONAL NOISE

The level of detail provided in the DA stage report included a breakdown of key equipment items, construction processes, likely noise impact and potential treatment options.

The level of detail included was as much as can be practically provided prior to development approval as there will not have been selection of equipment items, or appointment of a contractor/determination of construction processes. This is entirely consistent with projects of this nature.

Notwithstanding, given our experience with similar projects (coupled with preliminary input from the project team) we have presented a preliminary assessment which shows that it is feasible for the development to comply with the project noise emission goals. Further, vibration isolation of the

SYDNEY A: 9 Sarah St Mascot NSW 2020 T: (02) 8339 8000 F: (02) 8338 8399

SYDNEY MELBOURNE BRISBANE CANBERRA LONDON DUBAI SINGAPORE GREECE

ABN: 11 068 954 343

The information in this document is the property of Acoustic Logic Consultancy Pty Ltd ABN 11 068 954 343 and shall be returned on demand. It is issued on the condition that, except with our written permission, it must not be reproduced, copied or communicated to any other party nor be used for any purpose other than that stated in particular enquiry, order or contract with which it is issued.

mechanical plant and equipment will be required for it to comply within the building which will mean that compliance will be achieved in neighbouring buildings as well. A particular assessment of noise and vibration from the proposed mechanical plant and equipment will need to be prepared and submitted prior to the commencement of construction to ensure ongoing compliance with the project acoustic goals.

Compliance with the EPA noise emission goals (intrusiveness and amenity – Tables 3 and 5 our report) will be achievable.

#### 2.2 CONSTRUCTION NOISE

Regarding construction noise and vibration, the particular noise and vibration impacts from the construction works will depend on the particular methods proposed to be employed by the demolition/building contractor.

These cannot be assessed until after the contractor is appointed.

Despite this, the report identified the likely construction activities and provided predictions of the likely level of noise generation.

Once the builder has been appointed (typically following project approval and completion of primary design work), a detailed Construction Noise and Vibration Management Plan can then be prepared.

Noise levels at nearby residences was predicted to be below the Highly Noise Effected level and typically use of respite periods (which will prolong the construction period if adopted unnecessarily) should not be required. Noise and vibration impacts on other buildings within the hospital precinct would be a matter of negotiation between the various parties and cannot be done prior to the construction methods being at least identified.

### **3 CONCLUSION**

Acoustic Logic Consultancy have prepared an acoustic assessment for the proposed North Shore Hospital East Tower Expansion, in which the project noise and vibration goals have been nominated. During the detailed design process the particular treatments and/or management controls for compliance with those goals will be determined. Follow up reports (Mechanical Noise and Vibration Assessment; and Construction Noise and Vibration Management Plan) will need to be submitted prior to the commencement of construction.

We trust this information is satisfactory. Please contact us should you have any further queries.

Yours faithfully,

Montce.

Acoustic Logic Consultancy Pty Ltd Hilary Pearce