



Bulli Aged Care Centre of Excellence - 15617

EXTERNAL MATERIALS AND FINISHES SCHEDULE

Issue 1 25.11.2016

CONTENTS

03350 - CONCRETE FINISHES	1
04200 - MASONRY	1
05500 - FABRICATED METALWORK	2
07400 - CLADDING & LOUVRES	2
07600 - METAL ROOFING	3
09970 - STEEL FINISHES	4
08400 - GLAZING & WINDOWS (FACADES)	4


General Note:

This schedule shall be read in conjunction with architectural & consultant engineer's documentation.

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
------	------	---------------------	----------------------------------	-----


03350 - CONCRETE FINISHES

CF – Concrete

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
CF-01	OFF FORM CONCRETE	LIFT SHAFT – EXPOSED CONCRETE FACES TO NORTH & EAST LHD WING: SE/NW FIRE STAIR SHAFTS EXPOSED STRUCTURE	<p>* Off Form Concrete * Acceptable product: N/A * Colour: N/A * Finish: Class 2 / 3 off-form</p>  <p>NOTE: Image shows Class 2, The only difference between Classes 2 and 3 are the type, number and dimensions of permitted surface defects. A Class 3 finish will give a good visual quality when the project is viewed as a whole. (From AS3610 Concrete Finishes Classes)</p>	

04200 - MASONRY


WF – Masonry finish to walls

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
WF-01	BRICKWORK	LHD WING: FROM NATURAL GROUND SURFACE TO U/S LEVEL 1 RAC WING: FROM NATURAL GROUND SURFACE TO U/S LEVEL 2	<p>* Brick Wall * Acceptable product: PGH Bricks Velour * Colour: "Crevole" * Finish: textured face bricks * Pale grout</p> 	

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
------	------	---------------------	----------------------------------	-----




05500 - FABRICATED METALWORK

DP – External Downpipes



Code	Item	Indicative Location	Detail / Proprietary Description	Rev
DP-01	Colourbond Steel Downpipes	All Downpipes Generally	<p>* Colourbond Steel Downpipes</p> <p>* Colour: Colourbond 'Whitehaven'</p> 	

07400 - CLADDING & LOUVRES

WF – Metallic wall finishes & louvre systems


Code	Item	Indicative Location	Detail / Proprietary Description	Rev
WF-02	CORRUGATED STEEL WALL CLADDING	LHD WING: LEVEL 1, 2 & PLANT ROOM RAC WING: LEVEL 2, 3	<p>* CUSTOMORB Colourbond Steel wall cladding</p> <p>* Finish: Colourbond 'Whitehaven'</p> 	
WF-03	CORRUGATED STEEL WALL CLADDING	LHD WING: LEVEL 1, 2 CONTRAST PANELS RAC WING: LEVEL 2, 3 CONTRAST PANELS	<p>* CUSTOMORB Colourbond Steel wall cladding</p> <p>* Finish: Colourbond 'Monument'</p> 	
WF-04	CORRUGATED STEEL WALL CLADDING	LHD WING: LEVEL 2 HIGH LEVEL TO EAVES RAC WING: LEVEL 3 HIGH LEVEL TO EAVES	<p>* CUSTOMORB Colourbond Steel wall cladding</p> <p>* Finish: Colourbond 'Cosmic'</p> 	

FINISHES SCHEDULE

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
WF-05	CORRUGATED STEEL WALL CLADDING	LHD WING: PLANT ROOM TO EAVES, EAVES TO AWNINGS AT ENTRY AND AMBULANCE DROP OFF. RAC WING: LEVEL 3 HIGH LEVEL TO EAVES	* CUSTOMORB Powdercoated Steel wall cladding * Finish: Dulux Powdercoat 'Rain Forest Glow' 	
WF-06	ALUMINIUM ACOUSTIC LOUVRES	LHD WING: PLANT ROOM LOUVRES	* Powdercoated Extruded Aluminium Acoustic Louvres * Finish: Dulux Powdercoat 'Rain Forest Glow' 	


07600 - METAL ROOFING

RF – Metallic Roof Finishes



Code	Item	Indicative Location	Detail / Proprietary Description	Rev
RF-01	CORRUGATED STEEL ROOF SHEETING	ALL ROOF SURFACES ALL EAVES (EXCLUDING LHD PLANT ROOM)	* CUSTOMORB Colourbond Steel Roof Sheeting * Finish: Colourbond 'Whitehaven' 	
RF-02	CORRUGATED STEEL ROOF SHEETING	LHD PLANT ROOM EAVES	* CUSTOMORB Powdercoated Steel Roof Sheeting * Finish: Dulux Powdercoat 'Rain Forest Glow' 	

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
------	------	---------------------	----------------------------------	-----

09970 - STEEL FINISHES**SF – Steel Finishes**

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
SF-01	HOT DIP GALVANISED RHS STEEL	VERTICAL 'ROD' ELEMENTS TO LHD SE STAIR SHAFT	<p>* Hot Dip Galvanised RHS Steel sections</p> <p>* Finish: natural Zinalume finish</p> 	

08400 - GLAZING & WINDOWS (FACADES)**FR – Window & Door Frames**

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
FR-01	POWDERCOATED EXTRUDED ALUMINIUM WINDOW & DOOR FRAMES	ALL WINDOWS & DOORS	<p>* Powdercoated Extruded Aluminium Window & Door Frames</p> <p>* Material: Dulux Powdercoat 'Monument'</p> 	
FR-02	POWDERCOATED EXTRUDED ALUMINIUM WINDOW & DOOR FRAMES	RAC WING: INSET WINDOWS	<p>* Powdercoated Extruded Aluminium Window & Door Frames</p> <p>* Material: Dulux Powdercoat 'Rain Forest Glow'</p> 	

GL – Exterior Glazing

Code	Item	Indicative Location	Detail / Proprietary Description	Rev
GL-01	Windows & Doors Glazing Panels	Windows & Doors generally	<p>* DESCRIPTION</p> <p>* Product: Viridian Comfort Plus Single Laminate (Double Laminate where required)</p>	