










EXTERNAL FINISHES SCHEDULE

Project No: P19-006 Lindfield Learning Village - Stage 2

CODE	TYPE	DESCRIPTION	MANUFACTURER	LOCATION	IMAGE	COMMENTS	REV
EXTERNAL WALL FINISHES							
BR-01	BRICK WALL INFILL & REPAIR	Existing bricks from stockpile on site		External Wall Finish		Clean existing bricks of mortar & discolouration for reuse	A
SCN-02	EXTERNAL MESH SCREENS	1.5mm gauge 316 stainless steel stranded wire mesh with 25mm aperture certified to EN1263-1 for static & dynamic load capacity	JACOB	Balustrade security barriers rooftop Cola, fire stair & light void infill mesh panels		Refer to architectural elevations for extent & details.	A
CLAD-05	CLADDING	12mm Vitrapanel Fixed with wafer head screws & façade washer Colour: YELLOW WARBLER	VITRAPANEL	External Fibre Cement Cladding to COLA & Fire stair		10mm joints, sealant filled similar to james hardie joint sealant and Bostik seal and flex	A
CLAD-06	CLADDING	12mm Vitrapanel Fixed with wafer head screws & façade washer Colour: HAPPY	VITRAPANEL	External Fibre Cement Cladding to COLA & Fire stair		10mm joints, sealant filled similar to james hardie joint sealant and Bostik seal and flex	A
CLAD-07	CLADDING	12mm Vitrapanel Fixed with wafer head screws & façade washer Colour: TEMPLATE	VITRAPANEL	External Fibre Cement Cladding to COLA & Fire stair		10mm joints, sealant filled similar to james hardie joint sealant and Bostik seal and flex	A
CLAD-08	CLADDING	12mm Vitrapanel Fixed with wafer head screws & façade washer Colour: MISTY BEAD	VITRAPANEL	External Fibre Cement Cladding to COLA & Fire stair		10mm joints, sealant filled similar to james hardie joint sealant and Bostik seal and flex	A
CLAD-09	CLADDING	12mm Vitrapanel Fixed with wafer head screws & façade washer Colour: CANDIDATE	VITRAPANEL	External Fibre Cement Cladding to COLA & Fire stair		10mm joints, sealant filled similar to james hardie joint sealant and Bostik seal and flex	A
CLAD-10	CLADDING	12mm Vitrapanel Fixed with wafer head screws & façade washer Colour: BIRDSEED	VITRAPANEL	External Fibre Cement Cladding to COLA & Fire stair		10mm joints, sealant filled similar to james hardie joint sealant and Bostik seal and flex	A

EXTERNAL FINISHES SCHEDULE

Project No: P19-006 Lindfield Learning Village - Stage 2

CODE	TYPE	DESCRIPTION	MANUFACTURER	LOCATION	IMAGE	COMMENTS	REV
CLAD-11	CLADDING	12mm Vitrapanel Fixed with wafer head screws & façade washer Colour: To match colorbond SURFMIST	VITRAPANEL	External Fibre Cement Cladding to Lv 6 Zone K skylight		10mm joints, sealant filled similar to james hardie joint sealant and Bostik seal and flex	A
	RETRACTABLE AWNINGS	Shenker Retractable Awning NGM20 Fabric: Bushfire & Fungal resistant	SHENKER	External Awning level 2,3 & 4 Courtyards			A
	INSULATION	Medium Duty bulk insulation facing Thermofoil Medium Duty Wall insulation	CSR BRADFORD	External wall insulation lift bridges level 4, 5 & 6		Medium Duty bulk insulation facing	A

EXTERNAL MISCELLANEOUS

FT-01	SECURITY FENCE	2100 high x 40mm square hollow section frame • Galvabond square hollow section posts complete with permanently fitted proprietary galvabond steel caps COL: PT-15	AUSTRALIA SECURITY FENCING	External Security Perimeter Fence		Refer architectural drawings for extent and SPECIFICATION	B
HDG	GALVANIZED COATING	Finish: Hot dip galvanized		External exposed steel members roof top fence		Refer architectural drawings for extent	A
	LADDER ROOF ACCESS	LD 400/Modular ladder systems for roof access	SAYFA SYSTEMS GROUP	External Ladder Support & Attachment Point		Katt Ladder Support Bracket (LD402) - Gutter & Parapet Mount Type	A
	FALL ARRESTING EQUIPMENT	Fall arresting equipment & systems for all roofs	SAYFA SYSTEMS GROUP	External fall arresting equipment to all roofs			A
ST-01	STEEL COLUMN	Paint and corrosion protection system to exposed steel columns: DULUX DUREMAX GPE ZP. PRODICT CODE 78052033 + TOP COAT Colour: Charcoal	DULUX	ALL External Steel ColumnS		Refer arch docs for location + structural eng docs for details Follow dulux application requirements Sample to be provided	A