

## **APPENDIX G FINAL ACHAR**

# Aboriginal Cultural Heritage Assessment

BERYL SOLAR FARM



JUNE 2017



## Document Verification

|                                                                                   |                |                  |
|-----------------------------------------------------------------------------------|----------------|------------------|
|  | Project Title: | Beryl Solar Farm |
|-----------------------------------------------------------------------------------|----------------|------------------|

Project Number: 16-337

Project File Name: Beryl Solar Farm ACHA Final v1

| Revision | Date     | Prepared by (name) | Reviewed by (name)     | Approved by (name) |
|----------|----------|--------------------|------------------------|--------------------|
| Draft V1 | 23/03/17 | Kirsten Bradley    | Matthew Barber         | Matthew Barber     |
| Draft V2 | 24/03/17 | Kirsten Bradley    | Tom Best (First Solar) | Matthew Barber     |
| Final    | 06/07/17 | Kirsten Bradley    | Matthew Barber         | Matthew Barber     |
|          |          |                    |                        |                    |
|          |          |                    |                        |                    |

NGH Environmental prints all documents on environmentally sustainable paper including paper made from bagasse (a by-product of sugar production) or recycled paper.

NGH Environmental Pty Ltd (ACN: 124 444 622. ABN: 31 124 444 622) and NGH Environmental (Heritage) Pty Ltd (ACN: 603 938 549. ABN: 62 603 938 549) are part of the NGH Environmental Group of Companies.

[www.nghenvironmental.com.au](http://www.nghenvironmental.com.au) e [ngh@nghenvironmental.com.au](mailto:ngh@nghenvironmental.com.au)

### Sydney Region

18/21 mary st  
surry hills nsw 2010 (t 02 8202 8333)

### Newcastle - Hunter and North Coast

153 tudor st  
hamilton nsw 2303 (t 02 4969 4910)

### Canberra - NSW SE & ACT

unit 8/27 yallourn st (po box 62)  
fyshwick act 2609 (t 02 6280 5053)

### Bega - ACT and South East NSW

suite 1, 216 carp st (po box 470)  
bega nsw 2550 (t 02 6492 8333)

### Wagga Wagga - Riverina and Western NSW

suite 1, 39 fitzmaurice st (po box 5464)  
wagga wagga nsw 2650 (t 02 6971 9696)

### Bathurst - Central West and Orana

35 morrisset st (po box 434)  
bathurst nsw 2795 (m 0448 820 748)

# CONTENTS

|                                                       |           |
|-------------------------------------------------------|-----------|
| <b>EXECUTIVE SUMMARY .....</b>                        | <b>v</b>  |
| INTRODUCTION.....                                     | V         |
| PROJECT PROPOSAL.....                                 | V         |
| ABORIGINAL CONSULTATION .....                         | VI        |
| ARCHAEOLOGICAL CONTEXT .....                          | VI        |
| SURVEY RESULTS.....                                   | VI        |
| POTENTIAL IMPACTS.....                                | VII       |
| RECOMMENDATIONS .....                                 | VIII      |
| <b>1 INTRODUCTION.....</b>                            | <b>1</b>  |
| 1.1 DEVELOPMENT CONTEXT.....                          | 1         |
| 1.2 PROJECT PROPOSAL .....                            | 2         |
| 1.3 PROJECT PERSONNEL .....                           | 2         |
| 1.4 REPORT FORMAT .....                               | 4         |
| <b>2 ABORIGINAL CONSULTATION PROCESS .....</b>        | <b>4</b>  |
| 2.1 ABORIGINAL COMMUNITY FEEDBACK .....               | 6         |
| <b>3 BACKGROUND INFORMATION .....</b>                 | <b>7</b>  |
| 3.1 REVIEW OF LANDSCAPE CONTEXT .....                 | 7         |
| 3.1.1 Geology and Topography.....                     | 7         |
| 3.1.2 Flora and Fauna .....                           | 12        |
| 3.1.3 Historic Landuse .....                          | 12        |
| 3.1.4 Landscape Context.....                          | 13        |
| 3.2 REVIEW OF ABORIGINAL ARCHAEOLOGICAL CONTEXT ..... | 13        |
| 3.2.1 Ethnohistoric Setting .....                     | 13        |
| 3.2.2 AHIMS Search .....                              | 15        |
| 3.2.3 Regional Archaeological Models.....             | 16        |
| 3.2.4 Previous archaeological studies.....            | 19        |
| 3.2.5 Summary of Aboriginal land use.....             | 22        |
| 3.2.6 Archaeological Site Location Model .....        | 22        |
| 3.2.7 Comment on Existing Information.....            | 23        |
| <b>4 ARCHAEOLOGICAL INVESTIGATION RESULTS .....</b>   | <b>23</b> |
| 4.1 SURVEY STRATEGY .....                             | 23        |
| 4.2 SURVEY COVERAGE .....                             | 24        |

|       |                                                                     |            |
|-------|---------------------------------------------------------------------|------------|
| 4.3   | SURVEY RESULTS .....                                                | 30         |
| 4.3.1 | Surface Finds.....                                                  | 30         |
| 4.3.2 | Consideration of Potential for Subsurface material .....            | 32         |
| 4.4   | DISCUSSION.....                                                     | 35         |
| 5     | <b>CULTURAL HERITAGE VALUES AND STATEMENT OF SIGNIFICANCE .....</b> | <b>36</b>  |
| 6     | <b>PROPOSED ACTIVITY .....</b>                                      | <b>37</b>  |
| 6.1   | HISTORY AND LANDUSE .....                                           | 37         |
| 6.2   | PROPOSED DEVELOPMENT ACTIVITY.....                                  | 38         |
| 6.3   | ASSESSMENT OF HARM.....                                             | 38         |
| 6.4   | IMPACTS TO VALUES .....                                             | 39         |
| 7     | <b>AVOIDING OR MITIGATING HARM .....</b>                            | <b>40</b>  |
| 7.1   | CONSIDERATION OF ESD PRINCIPLES.....                                | 40         |
| 7.2   | CONSIDERATION OF HARM .....                                         | 40         |
| 8     | <b>LEGISLATIVE CONTEXT .....</b>                                    | <b>41</b>  |
| 9     | <b>RECOMMENDATIONS .....</b>                                        | <b>43</b>  |
| 10    | <b>REFERENCES.....</b>                                              | <b>44</b>  |
|       | <b>APPENDIX A ABORIGINAL COMMUNITY CONSULTATION.....</b>            | <b>A-1</b> |
|       | TECHNICAL SURVEY AND REPORT MATTERS .....                           | A-1        |
|       | Mapping .....                                                       | A-1        |
|       | Background information .....                                        | A-1        |
|       | Survey methodology .....                                            | A-2        |
|       | Report content .....                                                | A-2        |
|       | Recommendations .....                                               | A-3        |
|       | General considerations .....                                        | A-4        |
|       | <b>APPENDIX B AHIMS SEARCH.....</b>                                 | <b>B-1</b> |
|       | <b>APPENDIX C TRANSECT DATA.....</b>                                | <b>C-1</b> |
|       | <b>APPENDIX D SITE CARDS.....</b>                                   | <b>D-3</b> |
|       | <b>APPENDIX E HERITAGE UNEXPECTED FINDS PROTOCOL .....</b>          | <b>E-1</b> |
|       | PURPOSE .....                                                       | E-2        |
|       | WHAT IS A HERITAGE UNEXPECTED FIND? .....                           | E-2        |
|       | HISTORIC HERITAGE .....                                             | E-2        |
|       | UNEXPECTED FINDS MANAGEMENT PROCEDURE .....                         | E-2        |
|       | HUMAN SKELETAL REMAINS.....                                         | E-3        |

## TABLES

|                                                                                                                                 |    |
|---------------------------------------------------------------------------------------------------------------------------------|----|
| Table 1 Description of the Mitchell Landscape relevant to the proposal (DECC 2002).....                                         | 8  |
| Table 2 Description of the soil landscapes of the Dubbo 1:250 000 sheet relevant to the proposal (Murphy and Lawrie 1998) ..... | 9  |
| Table 3 Breakdown of previously recorded Aboriginal sites in the region.....                                                    | 15 |
| Table 4 Breakdown of landforms mapped by Purcell in the Brigalow Belt South Bioregion.....                                      | 20 |
| Table 5. Transect information.....                                                                                              | 29 |
| Table 6. Artefact characteristics .....                                                                                         | 33 |
| Table 7 Identified risk to known sites .....                                                                                    | 39 |

## FIGURES

|                                                                                                                                                               |    |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| Figure 1. General project area. ....                                                                                                                          | 1  |
| Figure 2. Project area.....                                                                                                                                   | 2  |
| Figure 3. Project area with development design.....                                                                                                           | 3  |
| Figure 4. Dubbo Geological map of project area (extracted from Colquhoun et al 1997). ....                                                                    | 7  |
| Figure 5. Location of Mitchell landscapes.....                                                                                                                | 10 |
| Figure 6. Location of soil landscapes from the Dubbo 1:250 000 sheet.....                                                                                     | 11 |
| Figure 7. Location of AHIMS sites .....                                                                                                                       | 17 |
| Figure 8. Close up of AHIMS sites near project area.....                                                                                                      | 18 |
| Figure 9. Overlay of Brayshaw (1987) and Smith (1987) survey areas in relation to the current assessment area (image modified from Smith 1987: Figure 2)..... | 19 |
| Figure 10. Survey sections within project area.....                                                                                                           | 28 |
| Figure 11. Location of recorded sites contour .....                                                                                                           | 34 |

## PLATES

|                                                                                                         |    |
|---------------------------------------------------------------------------------------------------------|----|
| Plate 1 View north towards low hill in north-eastern corner of project area. ....                       | 25 |
| Plate 2 View west along northern boundary towards location of Beryl Solar IF 1. ....                    | 25 |
| Plate 3 View north towards substation with powerlines in frame. ....                                    | 25 |
| Plate 4 View south towards hard rock quarry, note poor visibility due to dense thistle vegetation. .... | 25 |

|                                                                                                                                                          |    |
|----------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| Plate 5 View west towards far western portion of project area. ....                                                                                      | 26 |
| Plate 6 View south of area quarried for diamonds in far west of project area, note prospecting depressions and mounds. ....                              | 26 |
| Plate 7 View north of hard rock quarry pit showing piles of quarried rock.....                                                                           | 26 |
| Plate 8 View north-east of area subject to sand quarrying, note spoil mound deposits in background. ....                                                 | 26 |
| Plate 9 View east along abandoned rail corridor, noting area for rail raised above natural ground level...                                               | 26 |
| Plate 10 View south of pile of rocks collected mechanically from field in far east of project area with L. Foley inspecting for Aboriginal objects. .... | 26 |
| Plate 11 View west of farm dam, note ground visibility. ....                                                                                             | 27 |
| Plate 12 View of animal tracks, note ground visibility.....                                                                                              | 27 |
| Plate 13. View south, pole shows artefact location.....                                                                                                  | 30 |
| Plate 14. Close up of Beryl Solar Farm IF 1. ....                                                                                                        | 30 |
| Plate 15. View south, pole shows artefact location.....                                                                                                  | 30 |
| Plate 16. Close up of Beryl Solar Farm IF 2. ....                                                                                                        | 30 |
| Plate 17. View south, pole shows artefact location.....                                                                                                  | 31 |
| Plate 18. Close up of Beryl Solar Farm IF 3. ....                                                                                                        | 31 |
| Plate 19. View east, pole shows artefact location. ....                                                                                                  | 31 |
| Plate 20. Close up of Beryl Solar Farm IF 4. ....                                                                                                        | 31 |
| Plate 21. View east, poles show artefact locations. ....                                                                                                 | 32 |
| Plate 22. Close up of quartz broken flake from Beryl Solar Farm AS1.....                                                                                 | 32 |
| Plate 23. View north-west, pole shows artefact location.....                                                                                             | 32 |
| Plate 24. Close up of quartz flake from Beryl Solar Farm AS1. ....                                                                                       | 32 |

# EXECUTIVE SUMMARY

## INTRODUCTION

NGH Environmental has been contracted by First Solar Pty Ltd (First Solar) to prepare an Aboriginal Cultural Heritage Assessment Report (ACHAR) for the proposed Beryl Solar Farm, located at Beryl approximately 6 kilometres west of the township of Gulgong, NSW.

The solar farm proposal would involve ground disturbance that has the potential to impact on Aboriginal heritage sites and objects which are protected under the NSW *National Parks and Wildlife Act 1974* (NPW Act). The purpose of the Aboriginal Cultural Heritage Assessment (ACHA) is therefore to investigate the presence of any Aboriginal sites and to assess the impacts and management strategies that may mitigate any impact.

The Secretary of the DPE Environmental Assessment Requirements (SEARs) relating to Aboriginal heritage were as follows:

Include an assessment of the likely Aboriginal and historic heritage (cultural and archaeological) impacts of the development, including adequate consultation with the local Aboriginal community (SEARs for Beryl Solar Farm 25/01/17).

This ACHA Report was prepared in line with the following:

- *Guide to Investigating, Assessing and Reporting on Aboriginal Cultural Heritage in NSW* (OEH 2011);
- *Code of Practice for the Archaeological Investigation of Aboriginal Objects in New South Wales* (OEH 2010a), and
- *Aboriginal cultural heritage consultation requirements for proponents 2010* (ACHCRP) (OEH 2010b) produced by the NSW Office of Environment and Heritage (OEH)

The proposal area is within the Mid-Western Regional Council Local Government Area.

## PROJECT PROPOSAL

The Beryl Solar Farm proposal would comprise the installation of a solar plant with a capacity up to 100 MW. The power generated will be fed into the National Electricity Market (NEM) at the transmission level from the adjacent Beryl Substation. First Solar proposes to develop approximately 206 ha of the 332 ha proposal site.

The proposal would include the following elements:

- PV modules mounted on either a horizontal tracking structure (likely) or fixed structure.
- Internal inverter stations to allow conversion of DC module output to AC electricity, with associated transformers.
- Onsite solar farm substation (smaller than the existing Beryl Substation).
- Overhead electricity transmission for grid connection to the adjacent existing substation. (66kV).
- Underground electrical conduits and cabling to connect the inverters to the onsite substation.
- Underground and aboveground (mounted to module structure) DC cabling to connect the modules to the inverter stations.
- An access road off Beryl Road.
- Site office and maintenance building.

- Internal access tracks to allow for site maintenance.
- Perimeter security fencing.
- Native vegetation screening, where required to break up views of infrastructure to specific receivers.

## **ABORIGINAL CONSULTATION**

The consultation with Aboriginal stakeholders was undertaken in accordance with clause 80C of the *National Parks and Wildlife Amendment (Aboriginal Objects and Aboriginal Places) Regulation 2010* following the consultation steps outlined in the (ACHCRP) guide provided by OEH.

The full list of consultation steps, including those groups and individuals that were contacted and a consultation log is provided in Appendix A.

As a result of this process, four groups contacted the consultant to register their interest in the proposal. The groups who registered interest were Buudang, Murong Gialinga Aboriginal & Torres Strait Islander Corporation, Warrabinga Native Title Claimants Aboriginal Corporation and the Wellington Valley Wiradjuri Aboriginal Corporation. No other party registered their interest, including the entities and individuals recommended by OEH.

The fieldwork was organised and all registered parties were asked to participate in one of the two days of fieldwork. The fieldwork was carried out in late February 2017 with a representative from all four of the registered parties participating for a day of survey.

A copy of the draft report was provided to all the registered parties for comment.

## **ARCHAEOLOGICAL CONTEXT**

The assessment included a review of relevant information relating to the existing landscape of the proposal area. Included in this was a search of the OEH AHIMS database. No Aboriginal sites had previously been recorded within and adjacent to the proposal area. The closest AHIMS site to the project area was recorded as an open artefact site (AHIMS # 36-2-0016) located approximately 500m north of the assessment area.

Assessment of Aboriginal site models for the region suggest that there appears to be a pattern of site location that relates to the presence of potential resources for Aboriginal use. The most archaeologically sensitive areas are noted to occur within 100-400 m of water. Nonetheless, given that Aboriginal people have lived in the region for tens of thousands of years, there is some potential for archaeological evidence to occur across the proposal area. This would most likely be in the form of stone artefacts and scarred trees.

## **SURVEY RESULTS**

The intention for the heritage survey was to cover as much of the ground surface as possible, given that the project was going to disturb approximately 206 hectares, within the 332 hectare proposal site. Survey transects were undertaken on foot across the project area to achieve maximum coverage. All mature trees within or adjacent to the development footprint were also inspected for evidence of Aboriginal scarring. Visibility within the project area was variable with visibility ranging from 80% in exposures to less than 5%. The average effective visibility was 15% but overall was quite good.

Between the survey participants, over the course of the field survey, approximately, 100 km of transects were walked across the proposed solar farm development area. Allowing for an effective view width of 5m

each person, this equates to a surface area examined of 46ha. However, allowing for the visibility restrictions, the effective survey coverage was reduced to 6.9 ha, or 3.3% of the project area. The effective survey coverage for the area outside the development plan was lower at 1.9 ha or 1.5%.

Despite the variable visibility encountered during the survey, there were six stone artefacts found across the proposal area that were recorded as five site occurrences. The archaeological features have been recorded as an artefact scatter (Beryl Solar Farm AS1) and four isolated finds (Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3 and Beryl Solar Farm IF 4).

In terms of the current proposal therefore, extrapolating from the results of this survey, it is possible that additional stone artefacts could occur within the proposed development footprint. Based on the land use history of the proposal area, and an appraisal of the results from the field survey, there is negligible potential for the presence of intact subsurface deposits with high densities of objects or cultural material within the solar farm and powerline easement areas.

The models of site location for the area have been shown to be accurate, with the current survey confirming the predicted distribution and nature of archaeological material with the sites located within 100-400m to a water source, even in areas highly disturbed by farming activities.

The cultural significance of the sites is only determined by the local Aboriginal community.

## POTENTIAL IMPACTS

The proposal involves the construction of a solar farm and includes connection to the nearby substation with an above ground powerline on Lot 21/DP 1173059 that will extend to the existing Beryl substation on Lot 1/ DP 523876. The development will result in disturbance of almost 206 hectares of the 332-hectare property within Lot 20/DP 1173059 and Lot 1/DP 1012926. The impact is likely to be most extensive where earthworks occur and would involve the removal, breakage or displacement of artefacts. This is considered a direct impact on the Aboriginal objects by the development in its present form.

| Site name                    | Site integrity                                            | Type of harm | Degree of harm | Consequence of harm   | Recommendation                                   |
|------------------------------|-----------------------------------------------------------|--------------|----------------|-----------------------|--------------------------------------------------|
| <b>Beryl Solar Farm IF 1</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm IF 2</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm IF 3</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm IF 4</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm AS1</b>  | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage objects prior to development of project. |

The impact to the scientific values if the sites Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS 1 were to be impacted by the current proposal is considered low. The stone artefacts have little research value apart from what has already been gained from the information obtained during the present assessment. This information relates more to the

presence of the artefacts and in the development of Aboriginal site modelling, which has largely now been realised by the recording.

The Beryl Solar Farm proposal is classified as State Significant Development under the EP&A Act which have a different assessment regime. As part of this process, Section 90 harm provisions under the NPW Act are not required, that is, an AHIP is not required to impact Aboriginal objects as the Department of Planning and Environment provides development approval.

## **RECOMMENDATIONS**

It is recommended that:

1. If complete avoidance of the five recorded sites within the proposal area (Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS 1) is not possible, the artefacts must be salvaged prior to the proposed work commencing and moved to a safe area within the property that will not be subject to any ground disturbance.
2. The collection and relocation of the artefacts should be undertaken by an archaeologist with representatives of the registered Aboriginal parties. A new site card/s will need to be completed once the sites are moved to record their new location on the AHIMS database.
3. Once the sites Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS 1 are salvaged, the proposed work can proceed with caution within the development footprint.
4. The development proposal should now be able to proceed without any additional archaeological investigation.
5. First Solar should prepare a Cultural Heritage Management Plan (CHMP) to address the potential for finding additional Aboriginal artefacts during the construction of the Solar Farm and management of known sites and artefacts. The Plan should include the unexpected finds procedure to deal with construction activity. Preparation of the CHMP should be undertaken in consultation with the registered Aboriginal parties.
6. In the unlikely event that human remains are discovered during the construction, all work must cease in the immediate vicinity. OEH, the local police and the registered Aboriginal parties should be notified. Further assessment would be undertaken to determine if the remains were Aboriginal or non-Aboriginal.
7. Further archaeological assessment would be required if the proposal activity extends beyond the area of the current investigation. This would include consultation with the registered Aboriginal parties and may include further field survey.

# 1 INTRODUCTION

First Solar Pty Ltd (First Solar) proposes to develop a commercial scale solar farm at Beryl, approximately 6 kilometres west of the township of Gulgong, NSW (Figure 1 and 2). The proposal site is approximately 332 hectares in size with 206 hectares proposed for development (Figure 3). The Beryl solar farm would have a capacity of around 100 Mega Watt (MW). NGH Environmental has been contracted by First Solar to prepare an Aboriginal Cultural Heritage Assessment (ACHA) to investigate and examine the presence, extent and nature of any Aboriginal heritage for the proposal area as part of an Environmental Impact Assessment (EIS).

The solar farm proposal would involve ground disturbance that has the potential to impact on Aboriginal heritage sites and objects which are protected under the NSW *National Parks and Wildlife Act 1974* (NPW Act). The purpose of the Aboriginal Cultural Heritage Assessment (ACHA) is therefore to investigate the presence of any Aboriginal sites and to assess the impacts and management strategies that may mitigate any impact.

## 1.1 DEVELOPMENT CONTEXT

The development of renewable energy projects is one of the most effective ways to achieve the commitments of Australia and many other nations under the Kyoto Protocol to reduce greenhouse gas emissions. The Beryl Solar Farm would provide the following benefits:

- Reduction in greenhouse gas emissions.
- Provision of embedded electricity generation to supply into the Australian grid close to a main consumption centre.
- Provision of social and economic benefits through the provision of direct employment opportunities.

The establishment of a Solar Farm would therefore have both local, National and International benefits.

As part of the development impact assessment process, the proposed development application will be assessed under part 4 of the *Environmental Planning and Assessment Act 1979* (EP&A Act). The proposed solar farm at Beryl is classified as “state significant development” (SSD) under Part 4 of the EP&A Act. SSDs are major projects which require approval from the Minister for Planning and Environment. The EIS has been prepared in accordance with the requirements of the Secretary of the Department of Planning and Environment (DPE).

The Secretary of the DPE Environmental Assessment Requirements (SEARs) relating to Aboriginal heritage were as follows:

Include an assessment of the likely Aboriginal and historic heritage (cultural and archaeological) impacts of the development, including adequate consultation with the local Aboriginal community (SEARs for Beryl Solar Farm 25/01/17).

The assessment area of the proposed solar farm comprises of Lot 20/DP 1173059 and Lot 1/DP 1012926 with a transmission line on Lot 21/DP 1173059 that will extend to the existing Beryl substation on Lot 1/ DP 523876.

The Beryl Solar Farm proposal site is located between 4.5 and 7km west of the township of Gulgong, within the Mid-Western Regional Council Local Government Area (LGA).

## 1.2 PROJECT PROPOSAL

The Beryl Solar Farm proposal (Figures 1-3) would comprise of the installation of a solar plant with a capacity up to 100 MW. The power generated will be fed into the National Electricity Market (NEM) at the transmission level from the adjacent Beryl Substation.

Frist Solar proposes to develop approximately 206 ha of the 332 ha proposal site. The solar farm site would be accessed via Beryl Road, Spring Ridge Road and Perseverance Lane.

The proposal would include the following elements:

- PV modules mounted on either a horizontal tracking structure (likely) or fixed structure.
- Internal inverter stations to allow conversion of DC module output to AC electricity, with associated transformers.
- Onsite solar farm substation (smaller than the existing Beryl Substation).
- Overhead electricity transmission for grid connection to the adjacent existing substation. (66kV).
- Underground electrical conduits and cabling to connect the inverters to the onsite substation.
- Underground and aboveground (mounted to module structure) DC cabling to connect the modules to the inverter stations.
- An access road off Beryl Road.
- Site office and maintenance building.
- Internal access tracks to allow for site maintenance.
- Perimeter security fencing.
- Native vegetation screening, where required to break up views of infrastructure to specific receivers.

The Beryl Solar Farm is expected to operate for around 30 years. The construction phase of the proposal is expected to take twelve months. After the initial operating period the solar farm would either be decommissioned, removing all above ground infrastructure and returning the site to its existing land capability, or repowered with new PV equipment.

Three existing electricity transmission lines pass through the proposal site, mostly in a north-south direction and in alignment with the existing Beryl substation. The existing Beryl Substation is directly adjacent to the proposal site within the north-western section. In the centre of the site, a raised embankment indicates the location of the former railway line which passes through the proposal site in an east-west direction. Most of the railway line infrastructure has been removed though some concrete culverts are present.

## 1.3 PROJECT PERSONNEL

The assessment was undertaken by the archaeologists Matthew Barber and Kirsten Bradley of NGH Environmental, including research, Aboriginal community consultation, field survey and report preparation.

Consultation with the Aboriginal community was undertaken following the process outlined in OEH's *Aboriginal cultural heritage consultation requirements for proponents 2010*. Four Aboriginal groups registered their interest in the proposal. These groups were Buudang, Murong Gialinga Aboriginal & Torres Strait Islander Corporation, Warrabinga Native Title Claimants Aboriginal Corporation and the Wellington Valley Wiradjuri Aboriginal Corporation

Further detail and an outline of the consultation process is provided in Section 2.




Figure 1. General project area.




Figure 2. Project area.




Figure 3. Project area with development design.

## 1.4 REPORT FORMAT

For the purposes of this assessment of the Beryl Solar Farm, we have prepared the report in line with the following:

- *Guide to Investigating, Assessing and Reporting on Aboriginal Cultural Heritage in NSW* (OEH 2011);
- *Code of Practice for the Archaeological Investigation of Aboriginal Objects in New South Wales* (OEH 2010a), and
- *Aboriginal cultural heritage consultation requirements for proponents 2010* (ACHCRP) (OEH 2010b) produced by the NSW OEH.

The purpose of this ACHA Report is to provide an assessment of the Aboriginal cultural values associated with the study area and to assess the cultural and scientific significance of any Aboriginal heritage sites. This conforms to the intention of the SEARs.

The objectives of the assessment were to:

- Conduct Aboriginal consultation as specified in clause 80c of the *National Parks and Wildlife Regulation 2009*, using the consultation process outlined in the ACHCRP;
- Undertake an assessment of the archaeological and cultural values of the study area and any Aboriginal sites therein;
- Assess the cultural and scientific significance of any archaeological material;
- Assess the impacts of the development proposal on cultural sites, and
- Provide management recommendations for any objects found.

## 2 ABORIGINAL CONSULTATION PROCESS

The consultation with Aboriginal stakeholders was undertaken in accordance with clause 80C of the *National Parks and Wildlife Amendment (Aboriginal Objects and Aboriginal Places) Regulation 2010* following the consultation steps outlined in the ACHCRP guide provided by OEH. The guide outlines a four-stage process of consultation as follows:

- Stage 1 – Notification of project proposal and registration of interest.
- Stage 2 – Presentation of information about the proposed project.
- Stage 3 – Gathering information about cultural significance.
- Stage 4 – Review of draft cultural heritage assessment report.

The full list of consultation steps, including those groups and individuals that were contacted and a consultation log is provided in Appendix A. A summary of actions carried out in following these stages are as follows.

**Stage 1.** Letters outlining the development proposal and the need to carry out an ACHA were sent to the Mudgee LALC and various statutory authorities including OEH, as identified under the ACHCRP. An advertisement was placed in the local newspaper, the Mudgee Guardian on the 18<sup>th</sup> of November 2016 seeking registrations of interest from Aboriginal people and organisations. A further series of letters was sent to other organisations identified by OEH in correspondence to NGH Environmental. In each instance, the closing date for submission was 14 days from receipt of the letter.

As a result of this process, four groups contacted the consultant to register their interest in the proposal. The groups who registered interest were Buudang, Murong Gialinga Aboriginal & Torres Strait Islander

Corporation, Warrabinga Native Title Claimants Aboriginal Corporation and the Wellington Valley Wiradjuri Aboriginal Corporation.

No other party registered their interest, including the entities and individuals recommended by OEH.

**Stage 2.** On the 19<sup>th</sup> of December 2016, an Assessment Methodology document for the Beryl Solar Farm was sent to the four registered parties as noted above and the Mudgee LALC as required by OEH. This document provided details of the background to the proposal, a summary of previous archaeological surveys and the proposed heritage assessment methodology for the proposal. The document invited comments regarding the proposed methodology and sought any information regarding known Aboriginal cultural significance values associated with the subject area and/or any Aboriginal objects contained therein. A minimum of 28 days was allowed for a response to the document. Comments were received from Warrabinga Native Title Claimants Aboriginal Corporation and the Wellington Valley Wiradjuri Aboriginal Corporation.

The main points raised in the comments received from the Wellington Valley Wiradjuri Aboriginal Corporation on the methodology were in relation to:

- Survey spacing; and
- Recording techniques for sites, specifically photography and GPS co-ordinates.

The main points raised in the comments received from the Warrabinga Native Title Claimants Aboriginal Corporation on the methodology were requests for further information on:

- The proposal, specifically the proposed earthworks;
- Landforms;
- The closest site to the project area; and
- Previous surveys.

These comments were addressed by NGH in reply letters sent to the Wellington Valley Wiradjuri Aboriginal Corporation on the 30<sup>th</sup> of January 2017 and the Warrabinga Native Title Claimants Aboriginal Corporation on the 9<sup>th</sup> of February 2017. No further correspondence was received regarding the letters from NGH Environmental that addressed the comments on the methodology from either group. No response or registration of interest in the project was received from the Mudgee LALC.

The Wellington Valley Wiradjuri Aboriginal Corporation has requested that any information they provided in regards to the project area was not shared. Therefore, the letters received as noted above have not been included in this report or appendix. As a similar courtesy, we have not included the response received from the Warrabinga Native Title Claimants Aboriginal Corporation.

**Stage 3.** The *Assessment Methodology* outlined in Stage 2 included a written request to provide any information that may be relevant to the cultural heritage assessment of the study area. It was noted that sensitive information would be treated as confidential.

Cultural information about to the project area was received from the Wellington Valley Wiradjuri Aboriginal Corporation however they have requested that the information provided is not shared. Therefore, the cultural information received has not been included in this report.

No other response regarding cultural information was received.

At this stage, the fieldwork was organised and all four registered parties were asked to participate in one of the two days of fieldwork. The fieldwork was carried out in late February 2017 with a representative from all four of the registered parties participating for a day of the survey.

**Stage 4** In March 2017 a draft version of this *Aboriginal Cultural Heritage Assessment Report* for the proposal (this document) was forwarded to Buudang, Murong Gialinga Aboriginal & Torres Strait Islander Corporation, Warrabinga Native Title Claimants Aboriginal Corporation and the Wellington Valley Wiradjuri Aboriginal Corporation inviting comment on the results, the significance assessment and the recommendations. A minimum of 28 days was allowed for responses to the document.

## **2.1 ABORIGINAL COMMUNITY FEEDBACK**

Community consultation occurred throughout the project. The draft report was provided to each of the Registered Aboriginal Parties (RAPs) and feedback was sought on the recommendations, the assessment and any other issues that may have been important.

Report feedback was provided in writing by all four of the RAPs with their responses provided in full in Appendix A. Below is a summary of the main points from the consultation with each group.

Buudang and the Murong Gialinga Aboriginal & Torres Strait Islander Corporation provided verbal feedback on the report during a phone conversation as documented in the consultation log in Appendix A. This was followed up by a written response. Buudang and the Murong Gialinga Aboriginal & Torres Strait Islander Corporation agreed with the recommendations and survey methodology outlined in the report and noted that the objects identified should be moved prior to any works commencing in the area. The objects should be kept on country as close to their original locations as possible. It was requested that Aboriginal representatives be present when the artefacts are moved.

Wellington Valley Wiradjuri Aboriginal Corporation did not have any objections to the report and all the recommendations as outlined in the report were deemed to be satisfactory.

The Warrabinga Native Title Claimants Aboriginal Corporation raised a number of points in their written reply and felt that insufficient information had been presented in the draft report for them to provide comment on the proposed development in relation to Aboriginal heritage. The major points raised have been summarised as being technical relating to how the survey was conducted, the results of the survey, the terms used by NGH in our assessment and the interpretation of the results and assessment or significance and recommendations by Warrabinga. The issues raised were assessed by NGH in a reply letter and where appropriate additional information and mapping, as proposed by Warrabinga, was incorporated into the Final report. It has been noted that it is the view of the Warrabinga Native Title Claimants Aboriginal Corporation that this report should not be finalised until all comments and concerns raised have been addressed.

NGH have prepared a revised report (this Final Report) but do not believe that all of the points raised by Warrabinga need to be addressed. The reply letter that NGH sent in response to the comments on the draft report from Warrabinga is also provided in Appendix A. NGH believe that the information presented in the draft report and the reply letter is sufficient and believe that we have sufficiently characterised the nature of the Aboriginal archaeological material within the project area.

## 3 BACKGROUND INFORMATION

### 3.1 REVIEW OF LANDSCAPE CONTEXT

#### 3.1.1 Geology and Topography

The landscape context assessment is based on several classifications that have been made at national and regional level for Australia. The national IBRA system identifies the proposal area as located within the South-Western Slopes Bioregion and the Inland Slopes Subregion (IBRA v.7 2012). The dominant IBRA subregion affected by the project is the Inland Slopes Subregion.

The bioregion lies wholly in the eastern part of the Lachlan Fold Belt which consists of a complex series of north to north-westerly trending folded bodies of Cambrian to Early Carboniferous sedimentary and volcanic rocks. Granites are common and mostly located in large scale up-folded bodies of rock. Granite landscapes occur either as central basins surrounded by steep hills formed on contact metamorphic rocks, or as high blocky plateau features with rock outcrops and tors (NSW National Parks and Wildlife Services 2003).

The Dubbo Geological map (1:250,000 SI/55-4) indicates that geology underlying the project area consists of the Quaternary and Tertiary Cainozoic geological sequences as shown in Figure 4 and detailed below (Colquhoun et al 1997). The two large seams of basalt identified within the project area are indicated by the orange Tb layer in Figure 4.

- **Qa** Alluvium, gravel, sand, silt and clay.
- **Tb** Tholeiite, alkali basalts and alkali ultramafic.
- **Cza** High level alluvium, gravel, sand, silt and clay.



Figure 4. Dubbo Geological map of project area (extracted from Colquhoun et al 1997).

The proposal area is encompassed by three Mitchell Landscape, The Talbragar – Upper Macquarie Terrace Sand, Dubbo Basalts and Cope Hills Granite. Two other Mitchell Landscapes, the Gulgong Ranges and the Macquarie – Turon Gorges, are also located near the project area. The Mitchell Landscape descriptions are provided in Table 1 below and shown in Figure 5.

Table 1 Description of the Mitchell Landscape relevant to the proposal (DECC 2002)

| Mitchell Landscape                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p><b>Talbragar – Upper Macquarie Terrace Sand</b></p> <p>Sandy Quaternary alluvial sediments on the floodplains and terraces of the Talbragar River, general elevation 350 to 500m, local relief 30 to 40m. Red-brown and red-yellow earthy sands with some yellow texture-contrast soils on the valley margins. River red gum (<i>Eucalyptus camaldulensis</i>) along the channels, yellow box (<i>Eucalyptus melliodora</i>) and rough-barked apple (<i>Angophora floribunda</i>) with white cypress pine (<i>Callitris glaucophylla</i>) on the plain.</p>                                                                                                                                                                                                                                                                                                                                                    |
| <p><b>Dubbo Basalts</b></p> <p>Slightly elevated plains and low hills on flat lying Tertiary basalt and trachyte flows, roughly parallel to the present course of the Talbragar and Macquarie Rivers. General elevation 300 to 330m, local relief 10m. Shallow stony red-brown clay loam and clay, self-mulching and with moderate fertility. Open white box (<i>Eucalyptus albens</i>), yellow box (<i>Eucalyptus melliodora</i>) and rough-barked apple (<i>Angophora floribunda</i>) with diverse grasses.</p>                                                                                                                                                                                                                                                                                                                                                                                                 |
| <p><b>Gulgong Ranges</b></p> <p>Strike ridges with steep slopes and long debris aprons on complexly folded steep dipping Silurian lithic sandstone, quartzite and phyllite, Devonian sandstone, siltstone, shale, rhyolite and dacite. General elevation 550 to 980m, local relief 350m. Shallow stony red and yellow texture-contrast soils with stony uniform loams on steep slopes. Large areas of dense black cypress pine (<i>Callitris endlicheri</i>) on slopes, red stringybark (<i>Eucalyptus macrorhyncha</i>) and white gum (<i>Eucalyptus rossii</i>) on ridges. Blakely's red gum (<i>Eucalyptus blakelyi</i>), narrowleaved peppermint (<i>Eucalyptus radiata</i>) and white box (<i>Eucalyptus albens</i>) on lower slopes grading to yellow box (<i>Eucalyptus melliodora</i>).</p>                                                                                                               |
| <p><b>Cope Hills Granite</b></p> <p>Undulating and rolling hills on Carboniferous granite and granodiorite, general elevation 500 to 740m, local relief 150m. Gritty gradational red earth and red texture-contrast soils. Forest of yellow box (<i>Eucalyptus melliodora</i>), Blakely's red gum (<i>Eucalyptus blakelyi</i>), red stringybark (<i>Eucalyptus macrorhyncha</i>), apple box (<i>Eucalyptus bridgesiana</i>), mountain gum (<i>Eucalyptus dalrympleana</i>) and black cypress pine (<i>Callitris endlicheri</i>).</p>                                                                                                                                                                                                                                                                                                                                                                              |
| <p><b>Macquarie – Turon Gorges</b></p> <p>Steep sided, deep gorge tract with incised meanders of the Macquarie and Turon Rivers below extensive tablelands of the Ophir-Hargraves Plateau landscape. Incised across the structural grain of north-south trending tightly folded Devonian dacite, crystal tuff, quartzite and slates. General elevation 500 to 700m, local relief to 150m. Shallow stony soils on semi-stable scree slopes and yellow texture-contrast soils on lower angle slopes. Open woodland of yellow box (<i>Eucalyptus melliodora</i>), red box (<i>Eucalyptus polyanthemus</i>) and Blakely's red gum (<i>Eucalyptus blakelyi</i>) on lower areas, red stringybark (<i>Eucalyptus macrorhyncha</i>), broadleaved peppermint (<i>Eucalyptus dives</i>) and candlebark (<i>Eucalyptus rubida</i>), on higher slopes. River oak (<i>Casuarina cunninghamiana</i>) dominates the channel.</p> |

Cudgong River lies approximately 750m to the south of the site, and Wialdra Creek is situated approximately 150m to the north. No rivers or permanent streams are present within the site. Two small ephemeral drainage lines are located within the north-eastern and south-western portions of the site. The former is predominantly a second order stream draining north into Wialdra Creek (approx. 1.35 km north of the site boundary), and the latter is a first order stream draining west into Cudgong River (approx. 900 m

west of the site boundary). Both these drainage lines are predominantly dry. There are several man made dams occurring within the project area.

The project area has two areas of naturally occurring bedrock outcrops which may have provided a source of stone material for Aboriginal people. However, both outcrops have been subjected to various degrees of intensive quarrying since European arrival in the area. A section in the central portion of the project area was also noted to be subjected to some form of sand mining with no outcrops of bedrock observed in this section.

Soils within the proposal area are typically a reddish brown sandy loam. The 1:250,000 Dubbo Soils Landscape series sheet indicates that four soil landscapes occur within the proposal site as shown in Figure 6 and detailed below in Table 2. These include Craigmores, Home Rule, Mebul and Nanima. All these soil types have a moderate to very high erosion hazard when disturbed (Murphy and Lawrie 1998).

Table 2 Description of the soil landscapes of the Dubbo 1:250 000 sheet relevant to the proposal (Murphy and Lawrie 1998)

| Soil landscapes of the Dubbo 1:250 000 sheet                                                                                                                                                                                                                                                                                                                                                                                                                         |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Craigmores</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| <ul style="list-style-type: none"><li>• These soils are found on high terrace ranging in elevation between 460 and 475m above sea level.</li><li>• The landscape consists of non-calcareous soils and red earths.</li><li>• Erosion hazard is low unless in areas with minimal ground cover.</li></ul>                                                                                                                                                               |
| <b>Home Rule</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| <ul style="list-style-type: none"><li>• These soils are found on undulating low rises ranging in elevation between 420 and 500m above sea level.</li><li>• Slopes are gently inclined 4 – 8%.</li><li>• The landscape consists of siliceous sands, bleached sands and earthy sands overlying yellow sodic soils.</li><li>• Erosion hazard is high especially in areas with minimal ground cover and drainage depressions are susceptible to gully erosion.</li></ul> |
| <b>Mebul</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| <ul style="list-style-type: none"><li>• These soils are found on undulating low hills ranging in elevation between 400 and 540m above sea level.</li><li>• Slopes range from 2 –15%.</li><li>• The landscape consists of chocolate soils and euchozems.</li><li>• Erosion hazard is high especially in areas with minimal ground cover.</li></ul>                                                                                                                    |
| <b>Nanima</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| <ul style="list-style-type: none"><li>• These soils are found on rolling low hills ranging in elevation between 300 and 550m above sea level.</li><li>• Slopes are gently inclined 5 – 20%.</li><li>• The landscape consists of non-calcareous brown soils, red-brown earths, euchozems and Terra Rossa soils.</li><li>• Erosion hazard is low to moderate especially in areas with minimal ground cover.</li></ul>                                                  |




Figure 5. Location of Mitchell landscapes.




Figure 6. Location of soil landscapes from the Dubbo 1:250 000 sheet

### 3.1.2 Flora and Fauna

The biodiversity assessment carried out by NGH Environmental (2017) identified two distinct plant community types within the proposal area. These included:

1. White Box Yellow Box Blakely's Red Gum Grassy Woodland and Derived Native Grassland
2. Cleared areas (exotic dominated pasture)

The dominant tree species within the development area consisted of the Rough-barked Apple (*Angophora floribunda*), although this species is mixed/co-dominant with Yellow Box (*Eucalyptus melliodora*) and Blakely's Red Gum (*E. blakelyi*) in woodland patches immediately surrounding the site. This suggests the Yellow Box and Blakely's Red Gum have historically been selectively removed (for the timber/firewood) from the whole property, including the north-south laneways. The understorey vegetation included a relatively sparse midstorey vegetation layer comprised primarily of younger/regrowth Rough-barked Apple, Yellow Box and Blakely's Red Gum, with very few native shrubs observed across the site. The groundcover vegetation characteristics included patches of native perennial grasses, particularly across the western half of the site, whilst most the eastern half of the site was dominated by exotic pastures.

The vegetation in the eastern half of the project area was dominated by exotic pastures or planted non-local flora species that are typically grazed on a regular basis. The groundcover in this area is mainly exotic with common grazing species including (but not limited to) Barley Grass (*Hordeum leporinum*), Ryegrass species (*Lolium sp*), Brome species (*Bromus sp*), numerous Clover species (*Trifolium sp*), Paspalum (*Paspalum dilatatum*), Sheep Sorrel (*Acetosella vulgaris*), Delicate Hairgrass (*Aira elegantissima*), and numerous Fescue species (*Vulpia sp*). Numerous weed species are also present in these areas including (but not limited to) Capeweed (*Arctotheca calendula*), Smooth Catsear (*Hypochaeris glabra*), Flatweed (*Hypochaeris radicata*), and Stagger Weed (*Stachys arvensis*).

The wood and grass land vegetation community provides numerous habitat types for fauna. Canopy trees provide foraging and nesting/resting for birds and arboreal fauna. The mid-storey (if present) provides foraging and nesting for smaller birds, as well as refuge for small-medium sized mammals and reptiles. Ground cover plants, logs and fallen leaves provide shelter and foraging for terrestrial fauna as well. Where hollow-bearing trees are present, it may provide daytime resting habitat for bats and mammals, and roosting habitat for birds.

### 3.1.3 Historic Landuse

The proposal area has a history of intensive agricultural and pastoral use. Most the area has been utilised for grazing and crop production since European settlement in the 1820's. The location of the proposed Beryl Solar Farm is predominately within paddocks currently used to graze livestock (sheep and cattle). Areas within the proposed Beryl Solar Farm have also been subject to a range of quarrying activities by the land owners. According to the landowner, the far western portion along a basalt ridge has been subject to prospecting for diamonds following the commencement of mining by the Australia Diamond Mines Company of Melbourne close to the junction of Wyaldra Creek and the Cudgegong River. The basalt outcrop to the south has also been subject to intensive hard rock quarrying. There is also evidence of surface sand and gravel extraction in a small area in the central part of the proposal area. The exact dates of the quarry activity within the property is currently unknown. The impacts from farming and quarry activities over many decades has meant that any cultural material within the proposal area has been extensively disturbed and potentially destroyed.

The construction of the existing powerlines through the project area has also caused disturbance to the project area. There are also several man-made dams within the project area that have modified the ground. The ground has also been modified for the construction of the raised embankment of the former railway line which passes through the centre of the proposal site in an east-west direction.

Overall, the proposal area would be categorised as disturbed through consistent farming practices, quarrying practices, land clearing and development.

### 3.1.4 Landscape Context

Most archaeological surveys are conducted in a situation where there is topographic variation and this can lead to differences in the assessment of archaeological potential and site modelling for the location of Aboriginal archaeological sites. However, as already noted, the terrain is generally undulating within the Talbragar – Upper Macquarie Terrace Sand Mitchell Landscape, with a low hill in the north-eastern corner. The project area has also been significantly disturbed in three areas by quarrying activities. Electricity transmission lines and a raised east-west embankment of the former railway line have also disturbed the area.

The only other differences observed within the landscape were two drainage channels that cross the project area and the two large rock outcrops that have been subject to European quarrying activities. Areas in close proximity to a water source are likely to have been a major focus for Aboriginal people. However, prior to European land modifications, this area as a whole may have provided resources, shelter, water and food for Aboriginal people.

The different Dubbo Sheet soils and the Mitchell landscapes were not readily identifiable within the survey area and were not used as means of landscape differentiation. The landforms for the survey was therefore determined to be two units, undulating plains and the slopes of low rolling hills. This landform division is based on topographic maps of the project area and visual inspection during field survey.

## 3.2 REVIEW OF ABORIGINAL ARCHAEOLOGICAL CONTEXT

### 3.2.1 Ethnohistoric Setting

Cultural areas are difficult to define and “must encompass an area in which the inhabitants have cultural ties, that is, closely related ways of life as reflected in shared meanings, social practices and interactions” (Egloff *et al.* 2005:8). Depending on the culture defining criteria chosen - i.e. which cultural traits and the temporal context (historical or contemporary) - the definition of the spatial boundary may vary. In Australia, Aboriginal “marriage networks, ceremonial interaction and language have been central to the constitution of regional cultural groupings” with the distribution of language speakers being the main determinate of groupings larger than a foraging band (Egloff *et al.* 2005:8 & 16).

The Beryl area is within an area identified as part of the Wiradjuri language group. This is an assemblage of many small clans and bands speaking a number of similar dialects (Howitt 1996, Tindale 1974, MacDonald 1983, Horton 1994).

The Wiradjuri language group was the largest in NSW prior to European settlement. The borders were however, not static, they were most likely fluid, expanding and contracting over time to the movements of smaller family or clan groups. Boundaries ebbed and flowed through contact with neighbours, the seasons and periods of drought and abundance.

It was the small family group that was at the core of Aboriginal society and the basis for their hunting and gathering life. The immediate family camped, sourced food, made shelter and performed daily rituals together. The archaeological manifestations of these activities are likely to be small campsites, characterised by small artefact scatters and hearths across the landscape. Places that were visited more frequently would develop into larger site complexes with higher numbers of artefacts and possibly more diverse archaeological evidence.

These small family units were part of a larger band which comprised a number of families. They moved within an area defined by their particular religious sites (MacDonald 1983). Such groups might come together on special occasions such as pre-ordained times for ceremonies, rituals or simply if their paths happened to cross. They may also have joined together at particular times of the year and at certain places where resources were known to be abundant. The archaeological legacy of these gatherings would be larger sites rather than small family camps. They may include large hearth or oven complexes, contain a number of grinding implements and a larger range of stone tools and raw materials.

Identification and differentiation of such sites are difficult in the field. A family group and their antecedents and descendants occupying a particular campsite repeatedly over a long period of time may leave a similar pattern of archaeological signatures as a large group camped over a shorter period of time.

European settlers started arriving in the district in the 1820s. At this point the Aboriginal population was in decline, due to disease such as small pox and influenza as well as dispossession from traditional lands and acts of violence against the Aboriginal people meant there was great social upheaval and partial disintegration of the traditional way of life. This meant that access to traditional resource gathering and hunting areas, religious life and marriage links and access to sacred ceremonial sites were disrupted or destroyed.

However, despite these disruptions, Aboriginal people continued to maintain their connections to sites and the land in the early days of European settlement. Where Aboriginal people were moved to places like missions, people could maintain at least some form of association with country and maintain traditional stories.

Early settlers and others who wrote about the Wiradjuri people and customs differentiated between the origin of some groups, referring to people as the Lachlan or Murrumbidgee tribes, or the Levels tribe for those between the two major rivers (Woolrych 1890). The extent of the Wiradjuri group means that there were many different environments that were exploited for natural resources and food. Like everywhere in Australia, Wiradjuri people were adept at identifying and utilising resources either on a seasonal basis or all year round.

Terrestrial animals such as the possum was noted by many early observers as a prime food source and the skins were made into fine cloaks that evidently were very warm (Evans 1815, Oxley 1820, Mitchell 1839). Kangaroos were also eaten and their skins made into cloaks as well. A range of reptiles and other mammals were food sources. Fish and mussels would have been prevalent from the rivers and creeks and insects were also a common food type, in particular grubs and ants and ant eggs (Pearson 1981, Fraser 1892). Birds including emus were common as a food source, often being caught in nets made from fibres of various plants such as flax, rushes and kurrajong trees. Bird hunts were also often undertaken as group activities, with emus, ducks and other birds targeted through groups of people flushing them out and driving them into pre-arranged nets (Ramson 1983).

Plant foods were equally as important and mostly consisted of roots and tubers, such as *Typha* or Cumbungi whose tubers were eaten in late summer and the shoots in early spring. Other edible plants from the

Wiradjuri region include the Yam Daisy or *Murnong*, eaten in summer and autumn, the Kurrajong seeds and roots, Acacia seeds and other rushes (Gott 1982).

Some of the early settlers and pastoralists, surveyors, explorers, administrators and others observed traditional Aboriginal activities, including ceremonies, burial practices and general way of living, and recorded these in letters, journals and books. These early records of Aboriginal lifestyle and society within the region assist in understanding parts of the traditional Aboriginal way of life, albeit already heavily disrupted at the time of the observations and through the eyes of largely ignorant and uninformed observers.

The early observations also note that some weapons and tools were carried, some made from wood such as spears, spear throwers, clubs, shields, boomerangs, digging sticks, bark vessels and canoes. Other materials were observed in use such as stone axes, shell and stone scrapers and bone needles.

In an archaeological context, few of these items would survive, particularly in an open site context. Anything made from bark and timber and animal skins would decay quickly in an open environment. However, other items, in particular those made of stone would survive where they were made, placed or dropped. Shell material may also survive in an archaeological context. Sources of raw materials, such as the extraction of wood or bark would leave scars on the trees that are archaeologically visible, although few trees of sufficient age survive in the modern context. Outcropping stone sources also provide clues to their utilisation through flaking, although pebble beds may also provide sources of stone which leave no archaeological trace.

### 3.2.2 AHIMS Search

The Aboriginal Heritage Information Management System (AHIMS) is maintained by OEH and provides a database of previously recorded Aboriginal heritage sites. A search provides basic information about any sites previously identified within a search area. However, a register search is not conclusive evidence of the presence or absence of Aboriginal heritage sites, as it requires that an area has been inspected and details of any sites located have been provided to OEH to add to the register. As a starting point, the search will indicate whether any sites are known within or adjacent to the investigation area.

A search of the AHIMS database was conducted over an area approximately 22km east-west x 22km north-south centred on the proposal area, was undertaken on the 15<sup>th</sup> of November 2016. The AHIMS Client Service Number was: 254143. There were 79 Aboriginal sites and no declared Aboriginal Places recorded in the search area. Figure 7 and 8 show the locations of the AHIMS sites in relation to the assessment area and Table 3 shows a breakdown the of the site types.

Table 3 Breakdown of previously recorded Aboriginal sites in the region.

| Site Type                    | Number    |
|------------------------------|-----------|
| Artefact (1 or more)         | 58        |
| Artefact (1 or more) and PAD | 8         |
| Modified tree                | 6         |
| Stone Quarry and artefact    | 3         |
| PAD                          | 2         |
| Grinding Groove              | 1         |
| Art and PAD                  | 1         |
| <b>TOTAL</b>                 | <b>79</b> |

None of the sites are located within the current proposal area. The closest sites to the project area was recorded as an open artefact site (AHIMS # 36-2-0016) located approximately 500m north of the assessment area. The information provided on the site card was poor and information relating to the landform of the site and size is not detailed. However, the site was noted at the time of its recording to be a campsite and said to still be frequented. Bondi point artefacts were also noted to be present. The site card lists R. Hawkins as the informant for the site. No other information pertaining to this site is currently available.

### **3.2.3 Regional Archaeological Models**

Aboriginal people have occupied what we now know as the Australian continent for at least 40,000 years and perhaps 60,000 years and beyond (Hiscock 2007, Mulvaney and Kamminga 1999). While no regional synthesis of the archaeology has been completed for the Beryl area research studies have been undertaken in the Upper Macquarie River region by Pearson (1981) and Koettig (1985). The following is a summary of the finding from these studies.

Pearson (1981) analysed a series of sites which tended to be biased towards larger and more noticeable sites identified by local residents. During this study, he excavated three rockshelters (Botobolar 5, Granites 1 and Granites 2) which provided a record of regional Aboriginal occupation in the area to 5,000 years before present. Based on his finding Pearson categorised these sites as either occupation sites or non-occupation sites (sites that are generally for a single purpose ie. scarred trees, grinding grooves and burial sites) and built an archaeological model based on location. The model developed by Pearson is summarised below.

- Distance to water from sites varied from 10 to 500m, with larger sites found closer to a water source.
- Good soil drainage and an outlook over a water source were important to location.
- Ceremonial and stone arrangement sites were located away from campsites.
- Quarry sites were located in areas with desirable stone source qualities and reasonably accessible.

Koettig (1985) continued to build on the archaeological understanding of this region by conducting a comprehensive and systematic study of the Dubbo region, which although over 70km to the west, is relevant as one of only a few side-ranging archaeological studies. Koettig investigated all topographic landform units and creek orders through sample survey to clarify locations and site types. The study arrived at the following conclusions:

- Aboriginal sites may be expected throughout all landscapes.
- Artefact scatters, scar trees and grinding grooves are the most frequently occurring site types.
- The location and size of sites were determined by various factors; predominately environmental and social factors around the proximity to water, geological formations and the availability of food resources.

Koettig suggested that larger and constantly occupied sites are likely to occur along permanent watercourses, while more sporadic occupation would have occurred along ridge tops or temporary water courses.




Figure 7. Location of AHIMS sites




Figure 8. Close up of AHIMS sites near project area

### 3.2.4 Previous archaeological studies

The following are summaries of those archaeological survey reports that have been completed in the Beryl area and in relative proximity to the current assessment area.

Cubis (1981) surveyed a 35km proposed route for a 132 kV transmission line between the Beryl and Ulan substations. A total of ten sites were recorded during the survey. The site types included isolated finds and artefact scatters.

Brayshaw (1987) surveyed the land for a haul road and a 125mx 125m area for proposed hard rock basalt quarry on the bank of the Cudgegong River at Beryl, 9km west of Gulgong. Six open sites (CR1-CR6) and an isolated find were recorded. The dominate lithology was quartz with lesser amounts of chert, mudstone and basalt. Brayshaw noted that the minimal use of basalt at the sites was unusual given the presence of basalt outcrops within the project area. Two of the sites were located on ridge tops while the others were all located on the river flats and adjacent slopes. Sites were located up to 240m away from the river.

Smith (1987) surveyed additional land near the proposed hard rock basalt quarry on the southern bank of the Cudgegong River at Beryl, 9km west of Gulgong. Six open sites and quartz quarry site (CR7-13) were recorded. The sites recorded by Smith were all located within 5 to 500m of the Cudgegong River. While three of the sites were located amongst basalt outcrops the outcrops did not appear to be utilised. However, the two sites recorded in association with quartz outcrops appeared to be utilised. The dominant lithology recorded at the sites was quartz. Smith noted an average site density of three sites per square kilometre in the area by combining her results with Brayshaw's. The areas surveyed by Smith and Brayshaw are shown in relation to the current assessment area in Figure 8 below.




Figure 9. Overlay of Brayshaw (1987) and Smith (1987) survey areas in relation to the current assessment area (image modified from Smith 1987: Figure 2).

Purcell (2002) conducted a broad regional cultural heritage study of the Brigalow Belt South Bioregion in NSW. This bioregion extends from Dubbo north to Moree but its southern boundary is approximately 15km north of the current project area. Over the course of the study Purcell recorded 110 oral history interviews, located 1,110 Aboriginal sites, documented 60 traditionally used plant species and mapped landforms that have Aboriginal cultural heritage values. Of the 1,110 Aboriginal sites recorded during this assessment 893 existed on the site register prior to the study.

The field survey portion of Purcell's study primarily targeted government owned land such as state forests and a landform mapping project was undertaken to assist with the development of a predictive model for Aboriginal site distribution across the bioregion. Water localities were noted to be the major contributing element influencing the distribution of sites among landforms with sites expected to be concentrated near water localities. The landform types were classified into four key groups as shown in Table 4 below. The study indicated that Aboriginal sites have been recorded more frequently on high contour and alluvial landforms. The majority of the sites recorded were within 100-400 m of water.

In 2012 OzArk conducted a survey for the proposed duplication of the existing 66kv powerline from the Beryl Substation to the Dunedoo Substation. The Beryl substation is directly adjacent to the northern boundary of the current assessment area. OzArk assessed the impact footprint that was 40 km in length and 15m wide. A new substation at Beryl was also included as part of the larger project. It was also noted by OzArk that the proximity to a permanent water supply appeared to be the primary factor determining the location of Aboriginal campsites in the area. Two previously recorded sites were noted to have been legally impacted and it was determined that these sites were no longer existed and were not a constraint to the proposed development. Two new sites were also identified near the headwaters of Limestone Creek; both were artefact scatters with potential archaeological deposit.

Table 4 Breakdown of landforms mapped by Purcell in the Brigalow Belt South Bioregion.

| Landforms        | Description                                                                                                                                                                                                                                                               | Likelihood of Aboriginal sites                                                   |
|------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| Alluvial         | Low lying areas associated with a variety of water features including rivers, creeks, channels, billabongs, swamps and lakes. Landforms include alluvial fans, alluvial terrace, alluvium, channel, floodplain, flood channel, gilgai, wetland/swamp and palaeo channels. | Aboriginal sites occur frequently                                                |
| Deep stable sand | Landform types include yellow sand sheets and sand monkey. Water is scarce.                                                                                                                                                                                               | Aboriginal sites occur less frequently                                           |
| Terrace group    | Landform types consist of terrace with scalds, terrace with overland flow, terrace and clay pans. Each variety of terrace adjoins a landform associated with an alluvium landform.                                                                                        | Areas where terrace and floodplains overlap will have a high potential for sites |
| Higher contour   | Landforms that are elevated and consist of rocky ground, rocky ravines, colluvial slope, soil mantled slope, bench and talus.                                                                                                                                             | High frequency of sites when associated with alluvial landforms or creek lines   |

Since the 1980's a number of surveys have been conducted for the Moolarben, Wilpinjong and Ulan coal mines near Ulan, between 30 and 40km east of the current assessment area. The following are summaries of those archaeological survey reports that have been completed however, it should be noted that NGH Environmental have assessed the landscape of the current assessment to be different to that of the

Moolarben, Wilpinjong and Ulan coal mining areas as these latter areas are associated with sandstone escarpments and valleys associated with the Illawarra Coal Measures and the Narabeen group of sandstones, shale and conglomerate with a decidedly different topography, not the open Quaternary topography of the Beryl area. Therefore, while the models mentioned in the below summary are not generally applicable, they provide an insight into the archaeological survey and dates of Aboriginal occupation for the wider region.

The Moorlarbeen coal mine is located 25km east of Gulgong and is adjacent to the Wilpinjong and Ulan mines. A number of surveys for the project have been conducted by from 2006 till 2013 (Hamm 2008, 2009, Kuskie 2013 and Niche 2015). Hamm's 2006 assessment of the proposed mine area noted that concentrations of Aboriginal sites occurred on the alluvial flats associated with water courses. A number of sites have been recorded in the subsequent surveys including isolated artefacts, artefact scatters, rock shelters, rock shelters with art, modified trees, grinding grooves and PADs. Quartz generally dominates the artefact assemblages with lesser numbers of tuff, silcrete, quartzite, chert, mudstone, chalcedony and volcanics. Flakes and flaked pieces dominated the assemblage with cores, hammer stones and backed artefacts also recorded (Kuskie 2015).

A series of test excavations and salvage programs have also been undertaken for the Moorlarbeen coal mine Stage 1 Main infrastructure area and Open Cut 1 area with approximately 13,700m<sup>2</sup> subject to controlled mechanical exposure and 271 m<sup>2</sup> excavated by hand. The salvage and excavation programs for the Stage 1 Main infrastructure area and Open Cut 1 area resulted in the recovery of 2,643 artefacts and the identification of 35 new artefact sites (Hamm and Foley 2010).

A number of surveys for the Ulan Coal Mine have been conducted from 1980 till 2015 (as summarised in Kuskie 2013 and Niche 2015). The surveys resulted in the identification of a number of sites including isolated finds, artefact scatters, rock shelters, PADs, quarry, grinding grooves, rock shelters with art and modified trees being recorded. Quartz is the dominate lithology recorded. Kuskie (2009) noted that the archaeological evidence collected in the Ulan Coal Mine area indicates that the Aboriginal utilisation of the study area was generally of a low intensity and most likely relates to the limited presence of higher order watercourse within the analysis area.

A series of test excavations and salvage programs have been undertaken over the course of the Ulan Coal Mine project including Haglund's salvage excavation of the rock shelter site AHIMS# 36-3-177 that resulted in the recovery of 765 artefacts from 20m<sup>2</sup> of excavated deposit. The artefact density of the objects recovered was very high at 139 artefacts/m<sup>3</sup>. The rock shelter site Spring Gully 5 has also been subject to extensive salvage excavation and has returned a radiocarbon date of 4,147 ±60 years before present. A total of 10,002 artefacts were recovered from 37m<sup>3</sup> of excavated deposit. Kuskie also conducted the test excavation of three rock shelters (IS# 104, 105 and 1420) recovering a total of 2,896 artefacts from 3m<sup>3</sup> of excavated deposit. An Aboriginal fire place was also identified within the rock shelter #105 that has been radiocarbon dated to 3,200 to 3,500 year ago (Kuskie 2015:34-35).

The Wilpinjong coal mine was surveyed from 2005 to 2015. A number of Aboriginal sites have been recorded including artefact scatters, isolated finds, rock shelter with artefacts, PADs, art and modified trees. Quartz was the dominate lithology in the area followed by tuff with lesser numbers of chert, volcanic, jasper, rhyolite and quartzite artefacts. Complete and broken flakes were the dominate artefacts recorded (Kuskie 2015; Niche 2015). A number of salvage programs and excavations have occurred, including the baseline recording and monitoring of rock art sites (Kuskie 2015).

Surface collections, controlled mechanical exposure (surface scrapes) and mechanically excavated test pits have been conducted at a number of sites within the Wilpinjong coal mine project area. The test excavation of site WCP33 the southern portion pf Pit 5 excavated ten 0.5x 0.5m test pits by shovel. A total of 20 artefacts were recorded with quartz the dominate lithology. The test excavation of site WCP2016 recovered 97

artefacts and the site was noted to have a low artefact density of artefacts with 8.1 artefacts per m<sup>2</sup>. Test excavation was also conducted at site WCP92 in Pit 7 with only two artefacts recovered from eleven 1m x 1m pits. However, mechanical surface scrapes of approximately 7,950m<sup>2</sup> and the hand excavation of the site WCP1 has been noted to have recovered a number of artefacts with the report still in preparation (Kuskie 2015:26-29)

### 3.2.5 Summary of Aboriginal land use

The results of previous archaeological surveys in the Beryl region show that there are sites and artefacts present throughout the landscape. There is a dominance of artefacts either as isolated finds or in clusters as artefact scatters.

There appears to be a pattern of site location that relates to the presence of potential resources for Aboriginal use. The Aboriginal site modelling for the region to date suggests that while Aboriginal sites may be expected throughout all landscapes the most archaeologically sensitive areas occur in proximity to water. The most likely site type to be encountered within the Beryl Solar Farm project area would be stone artefacts and scarred trees where old growth trees remain.

A detailed understanding of the Aboriginal land use of the region is in reality lacking, as few in depth studies have been completed and no sites have been dated. It is possible however, to ascertain that proximity to water sources and raw materials was a key factor in the location of Aboriginal sites. It is also reasonable to expect that Aboriginal people ventured away from these resources to utilise the broader landscape but the current archaeological record of that activity is currently limited.

### 3.2.6 Archaeological Site Location Model

Based on the results of the previous archaeological investigations in the local Beryl area, and through extrapolation of Wiradjuri sites from the region it is possible to provide the following model of site location in relation to the proposed Beryl Solar Farm area.

**Stone artefact scatters** – representing camp sites can occur across the landscape, usually in association with some form of resource or landscape unit. Within the project area, there are no high order, permanent drainage channels, although the close proximity of the junction of the Wyaldra Creek and Cudgegong River is noted. However, due to the lack of permanent water in the project area large campsites are unlikely to occur.

**Burials** – are generally found in elevated sandy contexts or in association with rivers and major creeks. No such features exist with the project area and therefore such sites are unlikely to occur.

**Scarred Trees** – these require the presence of mature trees and are likely to be concentrated along major waterways and around swamps areas. There are patches of remnant vegetation across the project area. Therefore, this feature could occur.

**Hearths/Ovens** – are identified by burnt clay and stone used for heat retainers. None are recorded in the district but they could occur either independently or in association with other Aboriginal cultural features such as campsites, often in association with resource locations. Such places are not obvious within the project area and this feature is therefore unlikely to occur.

**Stone resources** – are areas where people used natural stone outcrops as a source material for flaking. This requires geologically suitable material outcropping so as to be accessible. The project area contains natural outcropping basalt therefore such sites could occur although, it has been noted that the outcropping stone

in the project area has been quarried since European arrival in the area which may have destroyed or disturbed any evidence of Aboriginal quarrying.

**Shell Middens** – are the agglomeration of shell material disposed of after consumption. Such places are found along the edges of significant waterways, swamps and billabongs. The proposal area contains no significant waterways, swamps and billabongs and this feature is therefore unlikely to occur

**Isolated Artefacts** – are present across the entire landscape, in varying densities. As Aboriginal people traversed the entire landscape for thousands of years, such finds can occur anywhere and indicate the presence of isolated activity, dropped or discarded artefacts from hunting or gathering expeditions or the ephemeral presence of short term camps.

In summary, the topography and landscape features within the proposed Beryl Solar Farm project area indicate that this area would likely have been part of the Wiradjuri landscape, particularly with the junction of Wyaldra Creek and Cudgegong River so close to the project area. Therefore, the project area could potentially be attractive to Aboriginal people to concentrate activity and therefore has a higher possibility of providing an archaeological signature. Subsequently, given that Aboriginal people have lived in the region for tens of thousands of years, there is potential for archaeological evidence to occur throughout the area, this is most likely to be in the form of stone artefacts.

### 3.2.7 Comment on Existing Information

The AHIMS database is a record of those places that have been identified and had site cards submitted to OEH. It is not a comprehensive list of all places in NSW as site identification relies on an area being surveyed and on the submission of site forms to AHIMS. There are likely to be many areas within NSW that have yet to be surveyed and therefore have no sites recorded. However, this does not mean that sites are not present.

Within the Beryl district there have only been a few archaeological investigations. The information relating to site patterns, their age and geomorphic context is little understood.

The robustness of the AHIMS survey results are therefore considered to be only moderate for the present investigation. There are likely to be sites that exist that have yet to be identified although the scale of farming and quarrying development has altered the natural landscape in some places. This activity has also greatly disturbed the archaeological record and there are unlikely to be many places that retain *in situ* archaeological material due to the scale of the quarrying activities and agricultural and pastoral development. The current study is the most comprehensive assessment of this locality and therefore the results outlined in this report are the most thorough and up to date available.

With regard to the limitations of the information available, archaeologists rely on Aboriginal parties to divulge information about places with cultural or spiritual significance in situations where non-archaeological sites may be threatened by development. To date, no such places have been identified within the archaeological reports carried out within the broader Beryl area. No such places have been identified through the consultation process for the Beryl Solar Farm proposal area.

## 4 ARCHAEOLOGICAL INVESTIGATION RESULTS

### 4.1 SURVEY STRATEGY

The heritage survey covered as much of the ground surface as possible, given that the project was going to disturb approximately 206 hectares, within the 332 hectare proposal site. Although the actual ground impact

from the construction method was likely to be low, the placement of solar arrays across the landscape has the potential to cover any cultural heritage sites.

The strategy therefore was to walk a series of transects across the landscape to achieve maximum coverage. Because landform was generally a cleared undulating plain with exotic dominated pasture used for grazing livestock, transects were spaced evenly with the survey team spread apart at 20m intervals, walking in parallel lines. The cleared nature of the paddocks made this an ideal survey strategy. The team were able to walk in parallel lines, at a similar pace, allowing for maximum survey coverage and maximum opportunity to identify any heritage features. The size of the survey team was a maximum of four people which allowed an 80m tract of the project area to be surveyed with each transect. At the end of each transect, the team would reposition along a new transect line at the same spacing and walk back on the same compass bearing.

We believe that the survey strategy was comprehensive and the most effective way to identify the presence of Aboriginal heritage sites. Discussion were held in the field during each day between the archaeologists and Aboriginal community representatives to ensure all were satisfied and agreed with the spacing and methodology.

The proposal area was divided into two sections as shown in Figure 9 and detailed below:

- The solar farm development proposal area (undulating plain) -comprising of 206 hectares which would be developed.
- Area not proposed for development within the project area –approximately 80 hectares comprising of low slopes and undulating plain.

The survey was undertaken by the team on the 21<sup>st</sup> and 22<sup>nd</sup> of February 2017. Notes were made about visibility, photos taken and any possible Aboriginal features identified were inspected, assessed and recorded if deemed to be Aboriginal in origin.

All mature trees within or adjacent to the development footprint were also inspected for evidence of Aboriginal scarring (c.f Long 2005).

The start and end points of each transect are provided in Appendix C. However, it should be noted that such points are only indicative of the transects walked by a single individual and that while there were more people present during the survey not all had GPS units

## **4.2 SURVEY COVERAGE**

The solar farm area comprised primarily of a cleared undulating plain with little topographic variation except towards to the slope of the low hill in the north-eastern corner of the project. The two drainage lines across the project area formed minor depressions and the ground near the agricultural dams and quarrying sites had been modified. The entire project area had been subject to clearing and ploughing activities. The landforms were therefore divided into two units based on the solar farm proposal; the solar farm development areas and the area outside the development plan within the project area.

Survey transects were undertaken on foot and traversed all the project area including the proposed powerline easement to the substation. Visibility within the project area was variable however the project area as a whole generally had a low grass cover. The effective visibility in the paddocks ranged from 80% in exposures to less the 5% in areas of dense thistles near the hard rock quarry to the south of the project area (Plate 4). The average effective visibility was 15% but overall was quite good.

It was noted that the stones in several the paddocks had been mechanically collected and placed in piles (Plate 10). These piles of stone were inspected for any evidence of Aboriginal objects.

Table 5 below shows the calculations of effective survey coverage and plates 1-10 show examples of the transects and disturbed area within the proposal area.

Between the survey participants, over the course of the field survey, approximately, 100 km of transects were walked across the proposed solar farm development area. Allowing for an effective view width of 5m each person, this equates to a surface area examined of 46ha. However, allowing for the visibility restrictions, the effective survey coverage is reduced to 6.9 ha, or 3.3% of the project area.

The survey coverage for the area outside the development footprint within the project area was 12.9 ha of the 126 ha area, but allowing for visibility restrictions, the effective survey coverage was 1.9 ha or 1.5% .

Overall, it is considered that the surface survey of the Beryl Solar Farm project area had sufficient and effective survey coverage. The results identified are considered a true reflection of the nature of the Aboriginal archaeological record present within the proposal area.

|                                                                                     |                                                                                                           |
|-------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------|
|   |                        |
| <p>Plate 1 View north towards low hill in north-eastern corner of project area.</p> | <p>Plate 2 View west along northern boundary towards location of Beryl Solar IF 1.</p>                    |
|  |                       |
| <p>Plate 3 View north towards substation with powerlines in frame.</p>              | <p>Plate 4 View south towards hard rock quarry, note poor visibility due to dense thistle vegetation.</p> |

|                                                                                                                 |                                                                                                                                                            |
|-----------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                |                                                                          |
| <p>Plate 5 View west towards far western portion of project area.</p>                                           | <p>Plate 6 View south of area quarried for diamonds in far west of project area, note prospecting depressions and mounds.</p>                              |
|                               |                                                                         |
| <p>Plate 7 View north of hard rock quarry pit showing piles of quarried rock.</p>                               | <p>Plate 8 View north-east of area subject to sand quarrying, note spoil mound deposits in background.</p>                                                 |
|                              |                                                                        |
| <p>Plate 9 View east along abandoned rail corridor, noting area for rail raised above natural ground level.</p> | <p>Plate 10 View south of pile of rocks collected mechanically from field in far east of project area with L. Foley inspecting for Aboriginal objects.</p> |



Plate 11 View west of farm dam, note ground visibility.



Plate 12 View of animal tracks, note ground visibility.




Figure 10. Survey sections within project area.

Table 5. Transect information.

| Survey Section                                    | Number of Survey Transects | Topography                                   | Exposure type                                                                           | Project Area ha | Surveyed area (length m x width m) | Survey Area m2 | Visibility  | Effective coverage (area x visibility) m2 | Project Area surveyed (ha) | Percentage of Project area effectively surveyed | Archaeological result                  |
|---------------------------------------------------|----------------------------|----------------------------------------------|-----------------------------------------------------------------------------------------|-----------------|------------------------------------|----------------|-------------|-------------------------------------------|----------------------------|-------------------------------------------------|----------------------------------------|
| Solar farm development area                       | 36                         | Undulating plain                             | Vehicle tracks, animal tracks, eroded and disturbed ground soil mounds, quarried areas. | 206             | 23,000 x 20                        | 460,000        | 15% average | 69,000                                    | 6.9                        | 3.3                                             | 4 isolated finds<br>1 artefact scatter |
| Area outside development plan within project area | 16                         | Undulating plain and slopes of rolling hills | Vehicle tracks, animal tracks, eroded and disturbed ground soil mounds.                 | 126             | 5,550x20<br>1,800x 10              | 129,000        | 15% average | 19,350                                    | 1.9                        | 1.5                                             | Nil                                    |

## 4.3 SURVEY RESULTS

### 4.3.1 Surface Finds

Despite the variable visibility encountered during the survey, there were six stone artefacts found across the proposal area that were recorded as five site occurrences. The archaeological features have been recorded as an artefact scatter and four isolated finds. The details of the sites are outlined below; their location is shown in Figure 10 with the artefact characteristics provided in Table 6.

#### *Beryl Solar Farm IF1*

This site consisted of a single artefact on a minor slope in a cleared paddock. The artefact was a bifacial flaked hand axe manufactured from tuff. The deposits consisted of a yellowish brown sandy silt and visibility within the area was 15%. The area has been subject to disturbance from ploughing in the past and the site was on the edge of a concentration of river pebbles associated with a first order drainage depression. The axe was noted by the Aboriginal representatives onsite to be relatively large for the area as it measured 135mm in length.



Plate 13. View south, pole shows artefact location.



Plate 14. Close up of Beryl Solar Farm IF 1.

#### *Beryl Solar Farm IF2*

This site consisted of a single artefact on the flat in a cleared paddock. The artefact was a multi-platform core of tuff. A total of four platforms and nine negative scars were recoded with step terminations noted. The artefact had been partially bifacial flaked at one end and was noted by the Aboriginal representatives onsite to be axe like in shape. The artefact had 20% terrestrial cortex and was located on a yellowish brown sandy silt deposits. Visibility within the paddock was approximately 15%.



Plate 15. View south, pole shows artefact location.



Plate 16. Close up of Beryl Solar Farm IF 2.

#### Beryl Solar Farm IF3

This site consisted of a single artefact on the gentle basal slope of a ploughed cleared paddock. The artefact was a multi-platform core of quartz. Two platforms and four negative scars were recorded with the artefact noted to have 60% pebble cortex. The artefact was located on reddish brown silty soil approximately 150m west of the Beryl substation.



Plate 17. View south, pole shows artefact location.



Plate 18. Close up of Beryl Solar Farm IF 3.

#### Beryl Solar Farm IF4

This site consisted of a single artefact on the lower basal slope of a ploughed and cleared paddock. The artefact was an edge-ground axe manufactured from a volcanic material with some anvil damage. The axe had split in half; it is unclear if this damage was the result of ploughing activities. The artefact was located on reddish brown sandy loam deposits and visibility within the area was 15%. The site was located approximately 30m south of Beryl Road.



Plate 19. View east, pole shows artefact location.



Plate 20. Close up of Beryl Solar Farm IF 4.

#### Beryl Solar Farm AS1

This site consisted of two artefacts approximately 5m apart from each other on the lower basal slope of a ploughed and cleared paddock. The area was noted to be disturbed with broken pieces of house bricks scattered nearby. The artefacts were a flake and broken flake of quartz. The artefacts were located on a reddish brown sandy loam deposits and visibility within the area was approximately 20%. The site was located approximately 30m south of Beryl Road and 40 m west of the site Beryl Solar Farm IF 4.

|                                                                                     |                                                                                      |
|-------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
|    |    |
| <p>Plate 21. View east, poles show artefact locations.</p>                          | <p>Plate 22. Close up of quartz broken flake from Beryl Solar Farm AS1.</p>          |
|  |  |
| <p>Plate 23. View north-west, pole shows artefact location.</p>                     | <p>Plate 24. Close up of quartz flake from Beryl Solar Farm AS1.</p>                 |

#### 4.3.2 Consideration of Potential for Subsurface material

Discussion were held in the field with the representatives present to assess the potential for subsurface deposits at each of the five sites identified and generally across the project area. Based on the land use history, an appraisal of the results from the field survey, and consideration of the likelihood that the artefacts identified had eroded from the landscape it was concluded that any artefacts within the project area were most likely to be surface finds and that there was negligible potential for the presence of intact subsurface deposits with high densities of objects or cultural material within the project area. It was assessed that subsurface testing was not warranted in the project area due to shallow soils and low potential for subsurface deposits within the project area.

Table 6. Artefact characteristics

| AHIMS *#  | Site Name             | Easting/Northing<br>(GDA 94 Zone 55) | Artefact Type | Raw Material | Dimensions (mm) | Comments                                                                                                                        |
|-----------|-----------------------|--------------------------------------|---------------|--------------|-----------------|---------------------------------------------------------------------------------------------------------------------------------|
| 36-2-0473 | Beryl Solar Farm IF 1 | 733453/ 6417569                      | Axe           | Tuff         | 135x 90 x 32    | Bifacial flaked axe.                                                                                                            |
| 36-2-0472 | Beryl Solar Farm IF 2 | 733005/ 6417165                      | Core          | Tuff         | 118 x 46 x 55   | Four platforms and nine negative scars with step fractures, 20% rough terrestrial cortex, partially bifacial flaked at one end. |
| 36-2-0471 | Beryl Solar Farm IF 3 | 731385/ 6418330                      | Core          | Quartz       | 35 x 91 x 60    | Two platforms and four negative scar, 60% water worn riverine cortex.                                                           |
| 36-2-0470 | Beryl Solar Farm IF 4 | 731214/ 6418411                      | Axe           | Volcanic     | 80 x 59 x 18    | Edge-ground axe with some anvil damage, artefact has split.                                                                     |
| 36-2-0469 | Beryl Solar Farm AS1  | 731174/ 6418420                      | Flake         | Quartz       | 20 x 12 x 5     | Broad platform with feather termination and tertiary stage of reduction.                                                        |
|           |                       | 731172/ 6418417                      | Broken flake  | Quartz       | 20 x 12 x 5     | Feather termination.                                                                                                            |

\* Copies of the site cards are provided in Appendix D.




Figure 11. Location of recorded sites

## 4.4 DISCUSSION

The predictions based on the modelling for the proposal area were that stone artefacts and scarred trees were the most likely manifestation of Aboriginal occupation of the area. It was noted that the areas closest to a water source were likely to contain sites given the modelling for the region. The survey results have confirmed this prediction with stone artefacts recorded. The absence of scarred trees within the project area is likely the result of clearing activities with few mature trees remaining within the assessment area.

The sites are all located within 450m of a watercourse with a noticeable cluster of artefacts (Beryl Solar Farm AS1 and Beryl Solar Farm IF 4) recorded in the north-western corner of the project area approximately 250m south-east of Wialdra Creek. These results indicate that while sites can occur throughout the landscape, even in areas highly disturbed by farming activities, there is a dominance of Aboriginal cultural material recorded near a water source.

The sites identified in this assessment are in close proximity to either permanent or ephemeral water sources and are representative of the opportunistic use and movement of people through the landscape. They are most likely representative of the use of major water course and the associated back country. The area was likely used intermittently over a period of time for camping, hunting and gathering resources. This is evident by the presence of stone artefacts in low densities. Based on this assumption, there is every chance that there are similar stone artefacts across similar landscapes in the Beryl area.

While the sites themselves and the distribution of cultural material provide an indication that the area was used more than once, artefacts manufactured from quartz, tuff and volcanic material is common for the general region. The presence of cores and flakes indicates that tool manufacture probably occurred onsite, although the presence of the bifacial axe and the edge ground axe may imply some tools were brought to the site. The presence of a large bifacial hand axe (Beryl Solar Farm IF 1) suggested a multi-staged approach to manufacturing artefacts, including the sourcing of material and then shaping and manufacture of the desired product.

The use of a volcanic material for the manufacture of the edge-grounded axe is common for the region however it should be noted that no grinding grooves have been recorded to date within the AHIMS search area. This suggests that edge-grounded axes in the Beryl area may have been shaped and sharpened elsewhere or that simply that this site type is yet to be identified and recorded in the area. Exposed sandstone bedrock near Ulan, approximately 25 km north-east of the current assessment area, has sites with grinding grooves used for the shaping and maintenance of ground- edge axes (Kuskie 2009:143; Kuskie 2015:80).

While two large basalt outcrops were located within the project area, neither showed any evidence of Aboriginal quarrying although it is possible that European quarrying activities have since destroyed or removed any evidence of the Aboriginal utilisation of these outcrops. Nevertheless, these results do support the observations previously made by Brayshaw (1987) and Smith (1987) that while sites could be located amongst the basalt outcrops, the outcrops themselves did not appear to be utilised.

In terms of the current proposal therefore, extrapolating from the results of this survey, it is possible that additional stone artefacts could occur within the proposed development footprint. However, they are likely to be small scatters or isolated artefacts and consideration must also be given to the level of disturbance of any such sites. Based on the land use history of the proposal area, and an appraisal of the results from the field survey, there is negligible potential for the presence of intact subsurface deposits with high densities of objects or cultural material within the solar farm and powerline easement areas.

## 5 CULTURAL HERITAGE VALUES AND STATEMENT OF SIGNIFICANCE

The assessment of the significance of Aboriginal archaeological sites is currently undertaken largely with reference to criteria outlined in the ICOMOS Burra Charter (Marquis-Kyle & Walker 1994). Criteria used for assessment are:

- *Social or Cultural Value*: In the context of an Aboriginal heritage assessment, this value refers to the significance placed on a site or place by the local Aboriginal community – either in a contemporary or traditional setting.
- *Scientific Value*: Scientific value is the term employed to describe the potential of a site or place to answer research questions. In making an assessment of Scientific Value issues such as representativeness, rarity and integrity are addressed. All archaeological places possess a degree of scientific value in that they contribute to understanding the distribution of evidence of past activities of people in the landscape. In the case of flaked stone artefact scatters, larger sites or those with more complex assemblages are more likely to be able to address questions about past economy and technology, giving them greater significance than smaller, less complex sites. Sites with stratified and potentially in situ sub-surface deposits, such as those found within rock shelters or depositional open environments, could address questions about the sequence and timing of past Aboriginal activity, and will be more significant than disturbed or deflated sites. Groups or complexes of sites that can be related to each other spatially or through time are generally of higher value than single sites.
- *Aesthetic Value*: Aesthetic values include those related to sensory perception, and are not commonly identified as a principal value contributing to management priorities for Aboriginal archaeological sites, except for art sites.
- *Historic Value*: Historic value refers to a site or place's ability to contribute information on an important historic event, phase or person.
- *Other Values*: The Burra Charter makes allowance for the incorporation of other values into an assessment where such values are not covered by those listed above. Such values might include Educational Value.

All sites or places have some degree of value, but of course, some have more than others. In addition, where a site is deemed to be significant, it may be so on different levels or contexts ranging from local to regional to national, or in very rare cases, international. Further, sites may either be assessed individually, or where they occur in association with other sites the value of the complex as a whole should be considered.

### Social or cultural value

While the true cultural and social value of Aboriginal sites can only be determined by local Aboriginal people, as a general concept, all sites hold cultural value to the local Aboriginal community. An opportunity to identify cultural and social value was provided to the Aboriginal representatives for this proposal through the fieldwork and draft reporting process.

Feedback about the cultural value of the sites from Larry Foley who represented both Buudang and Murong Gialinga Aboriginal & Torres Strait Islander Corporation over the course of the fieldwork indicated that all sites hold cultural value to the local Aboriginal community.

The cultural significance of the sites is only determined by the local Aboriginal community.

### Scientific (archaeological) value.

The research potential of the sites located during this assessment is considered to be low. While the presence of the sites can be used to assist in the development of site modelling for the local landscape, their scientific value for further research is limited.

While the artefacts themselves are intrinsically interesting in terms of their base technical information their current lack of temporal context and the absence of information about local resources makes further conclusions about land use difficult. Their scientific value for further research is also limited due to the sparse distribution of the artefacts, disturbed nature of the landscape and the subsequent movement of objects by clearing and ploughing activities. The stone axes are generally considered of higher value due to their relative rarity compared to typical flaking material of cores and flakes. Axes are an indicator of a different tool use and activity, being mostly for the removal of wood from trees that could have been used for a variety of purposes such as carrying dishes, shields, spears and shelter as well as extraction of food such as possums and honey from hollows. The presence of at least two definite axes in the one locality would indicate that such woodworking activities was a high priority in the area.

The only other potential area of research would be to analyse the edge-ground axe (Beryl Solar Farm IF4) and bifacial hand axe (Beryl Solar Farm IF1) to see if there are any residues present that could indicate what materials were ground or cut. However, this is likely to be difficult as the items would have been moved around by pastoral and agricultural activity and may have been compromised through contact with cereal crops and livestock. They may be useful in analyses of artefact distribution if the quarry source was ever identified.

### Aesthetic value.

There are no aesthetic values associated with the archaeological site per se, apart from the presence of Aboriginal artefacts in the landscape. The modified and heavily disturbed landscape within the solar farm development area however detracts from this aesthetic setting.

### Other Values

There are no other known heritage values associated with the project area. The area may have some educational value (not related to archaeological research) through educational material provided to the public about the Aboriginal occupation and use of the area, although the archaeological material is within private property and there is little for the public to see.

## 6 PROPOSED ACTIVITY

### 6.1 HISTORY AND LANDUSE

It has been noted above in Section 3.1.3 that historically the solar farm proposal area has been impacted through land use practices specifically quarrying, clearing, ploughing and grazing.

The implications for this activity is that the archaeological record has been compromised in terms of the potential for scarred trees to remain. The implication for stone artefacts is that they may have been damaged or moved but they are likely to be present and remain in the general area they were discarded by Aboriginal people.

Despite these impacts, Aboriginal artefacts remain in the area, indicating the presence of past Aboriginal people and providing indications of their use of this landscape.

## 6.2 PROPOSED DEVELOPMENT ACTIVITY

As noted above in section 1.2, the proposal involves the construction of a solar farm and includes a transmission line on Lot 21/DP 1173059 that will extend to the existing Beryl substation on Lot 1/ DP 523876. The development will result in disturbance of approximately 206 ha of the 332ha proposal site within Lot 20/DP 1173059 and Lot 1/DP 1012926.

Disturbances will largely be in the preparation of the ground for the solar farm. Piles would be driven or screwed into the ground to support the solar array's mounting system, which reduces the potential overall level of ground disturbance.

PV modules would be installed on single axis tracking or fixed mounting structures across the site

Trenches would be dug for the installation of a series of underground cables linking the arrays across the proposal site.

Some internal access tracks would also be required, and typically these would comprise a compacted layer of gravel laid on stripped bare natural ground.

Some ancillary facilities would also be required including parking facilities, staff amenities and offices.

A perimeter fence and a vegetation buffer would also be constructed around the solar farm.

An overhead power line would be installed to connect the solar farm to the existing Beryl substation.

The proposed construction timetable is 12 months duration and the operational life of the solar farm is estimated to be 30 years. After the initial operating period the solar farm would either be decommissioned, removing all above ground infrastructure and returning the site to its existing land capability, or repowered with new PV equipment.

The development activity will therefore involve disturbance of the ground during the construction of the solar farm and the transmission line to the adjacent substation. Once established however, there would be minimal ongoing disturbance of the ground surface.

The final details and timing of the proposed construction activity have yet to be finalised but it is anticipated that construction could commence in 2017.

## 6.3 ASSESSMENT OF HARM

As described in this report, five archaeological sites were located within the project area. The following table provides a summary of the degree of harm and the consequence of that harm upon the heritage value of each site resulting from the proposed works for the solar farm and transmission line to the Beryl substation.

There is Aboriginal archaeological material present within the solar farm and the assessment is that there are likely to be other artefacts and cultural material present as well, although in similar low densities. The proposed level of disturbance for the construction of the solar farm could impact the stone artefacts recorded during the field survey and others that may be present within other areas of the development site.

The impact is likely to be most extensive where earthworks occur such as the installation of cabling and the transmission line poles, which may involve the removal, breakage or displacement of artefacts and cultural material. This is considered a direct impact on the sites and the Aboriginal objects by the development in its present form.

The proposed construction methodology for the project will however results in only small areas of disturbance. The construction of access and maintenance tracks may involve some grading but given the relatively flat nature of the terrain, this is likely to be minimal. The installation of the solar arrays involves drilling or screwing the piles into the ground and no widespread ground disturbance work such as grading or excavation is required to accomplish this.

The assessment of harm overall for the project is therefore assessed as low.

Table 7 Identified risk to known sites

| Site name                    | Site integrity                                            | Type of harm | Degree of harm | Consequence of harm   | Recommendation                                   |
|------------------------------|-----------------------------------------------------------|--------------|----------------|-----------------------|--------------------------------------------------|
| <b>Beryl Solar Farm IF 1</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm IF 2</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm IF 3</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm IF 4</b> | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage object prior to development of project.  |
| <b>Beryl Solar Farm AS1</b>  | Poor – 100+ year history of agricultural and pastoral use | Direct       | Complete       | Minimal loss of value | Salvage objects prior to development of project. |

## 6.4 IMPACTS TO VALUES

The values potentially impacted by the development are any social and cultural values attributed to the artefacts and the sites by the local Aboriginal community. The extent to which the loss of the sites or parts of the sites would impact on the community is only something the Aboriginal community can articulate.

The impact to values for this development are summarised in Table 7 above

The impact to the scientific values if the sites Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS1 were to be impacted by the current proposal is considered low. However, the intrinsic values of the artefacts themselves may be affected by the development of the site. Any removal of the artefacts, or their breakage would reduce the low scientific value they retain.

No other values have been identified that would be affected by the development proposal.

## 7 AVOIDING OR MITIGATING HARM

### 7.1 CONSIDERATION OF ESD PRINCIPLES

Consideration of the principles of Ecologically Sustainable Development (ESD) and the use of the precautionary principle was undertaken when assessing the harm to the sites and the potential for mitigating impacts to the sites recorded within the Beryl Solar Farm proposal area. The main consideration was the cumulative effect of the proposed impact to the sites and the wider archaeological record. The precautionary principle in relation to Aboriginal heritage implies that development proposals should be carefully evaluated to identify possible impacts and assess the risk of potential consequences.

In broad terms, the archaeological material located during this investigation is similar to what has been found previously within the Beryl region. Currently there is no clear regional synthesis of the nature, number, extent and content for archaeological sites within the Mid-Western Regional Council LGA. Nevertheless, given the size of the geographical area, it is certain that there would be similar artefacts present within the region.

The result of this Aboriginal heritage assessment has confirmed the proposed model of site location and site distribution, whereby sites could be expected to occur across the landscape and in particular in proximity to a water source, even in ploughed areas.

The implications for ESD principles is that other artefacts are likely to be present in the district.

As noted above, the archaeological values of the sites, considering the scientific, representative and rarity values was deemed to be low. It is believed therefore that the proposed impacts to the sites through the development would not adversely affect the broader archaeological record for the local area or the region.

The principle of inter-generational equity requires the present generation to ensure that the sites and diversity of the archaeological record is maintained or enhanced for the benefit of future generations. We believe that the diversity of the archaeological record is not compromised by development of this particular solar farm proposal.

We therefore consider, that while the current development proposals will impact five sites, all with stone artefacts, the overall cumulative impact on the archaeological record for the region is likely to be minimal.

It is argued that the cumulative impacts of the proposal are not enough to reject outright the development proposal.

### 7.2 CONSIDERATION OF HARM

Avoiding harm to the five sites is technically possible through avoidance. However, their position, scattered across the landscape would pose serious design constraints on the solar farm proposal.

Based on the assessment of the artefacts, and in consideration of discussions with the Aboriginal representatives during the field survey, it is not considered necessary to prevent all development at this location. The sites have been shown to be highly disturbed with little remaining scientific value. Aboriginal cultural value has been determined by the local Aboriginal community to be generally low enough to not prevent the development proposal proceeding.

The sites Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS1 are situated within the development footprint area of the proposed solar arrays, tracks,

cables and office parking. The most likely cause of harm to the artefacts will be through ground preparation activities such as vegetation clearance, installation of the posts and solar arrays.

The question remains about possible occurrence of artefacts and cultural material within the balance of the solar farm site. It is possible, and considered likely that additional artefacts will be present. Without knowing their exact locations, it is difficult to manage the impacts. We do not consider that the risk of such disturbances means the development should be abandoned. The archaeological material identified in the survey, and potentially present in the balance of the development site is not of sufficient value to reject the development proposal.

Mitigation of harm to cultural heritage sites generally involves some level of detailed recording to preserve the information contained within the site. Mitigation can be in the form of minimising harm, through slight changes in the development plan or through direct management measures of the sites and Aboriginal objects.

It is argued here that mitigation in the form of alteration is not feasible or warranted within the solar farm development area in this situation for the sites Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS 1. However, the five sites are conducive to salvage as a mitigation strategy as requested by the Aboriginal community representative Larry Foley during the field survey.

As identified above, it is recommended that the five sites recorded within the proposed Beryl Solar Farm development area (Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS1) are salvaged by an archaeologist with representatives of the registered Aboriginal parties prior to the proposed development commencing. The artefacts should be collected and moved to a safe area within the property that will not be subject to any ground disturbance.

The Aboriginal community representative Larry Foley noted during the field survey his preference for the artefacts to be relocated to another surface location rather than to be buried.

## 8 LEGISLATIVE CONTEXT

Aboriginal heritage is primarily protected under the NPW Act and as subsequently amended in 2010 with the introduction of the *National Parks and Wildlife Amendment (Aboriginal Objects and Places) Regulation 2010*. The aim of the NPW Act includes:

The conservation of objects, places or features (including biological diversity) of cultural value within the landscape, including but not limited to: places, objects and features of significance to Aboriginal people.

An Aboriginal object is defined as:

Any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises New South Wales, being habitation before or concurrent with the occupation of that area by persons on non-Aboriginal extraction and includes Aboriginal remains.

Part 6 of the NPW Act concerns Aboriginal objects and places and various sections describe the offences, defences and requirements to harm an Aboriginal object or place. The main offences under section 86 of the NPW Act are:

- A person must not harm or desecrate an object that the person knows is an Aboriginal object.

- A person must not harm an Aboriginal object.
- For the purposes of this section, "circumstances of aggravation" are:
  - o that the offence was committed in the course of carrying out a commercial activity, or
  - o that the offence was the second or subsequent occasion on which the offender was convicted of an offence under this section.
- A person must not harm or desecrate an Aboriginal place.

Under section 87 of the NPW Act, there are specified defences to prosecution including authorisation through an Aboriginal Heritage Impact Permit (AHIP) or through exercising due diligence or compliance through the regulation.

Section 89A of the Act also requires that a person who is aware of an Aboriginal object, must notify the Director-General in a prescribed manner. In effect this section requires the completion of OEH AHIMS site cards for all sites located during heritage surveys.

Section 90 of the NPW Act deal with the issuing of an AHIP, including that the permit may be subject to certain conditions.

The EP&A Act is legislation for the management of development in NSW. It sets up a planning structure that requires developers (individuals or companies) to consider the environmental impacts of new projects. Under this Act, cultural heritage is considered to be a part of the environment. This Act requires that Aboriginal cultural heritage and the possible impacts to Aboriginal heritage that development may have are formally considered in land-use planning and development approval processes.

Proposals classified as State Significant Development or State Significant Infrastructure under the EP&A Act have a different assessment regime. As part of this process, Section 90 harm provisions under the NPW Act are not required, that is, an AHIP is not required to impact Aboriginal objects. However, the Department of Planning and Environment is required to ensure that Aboriginal heritage is considered in the environmental impact assessment process. The Department of Planning and Environment will consult with other departments, including OEH prior to development consent being approved.

The Beryl Solar Farm proposal is a State Significant Development and will therefore be assessed via this pathway, which does not negate the need to carry out an appropriate level of Aboriginal heritage assessment or the need to conduct Aboriginal consultation in line with the requirements outlined by the OEH *Aboriginal cultural heritage consultation requirements for proponents 2010* (OEH 2010b).

## 9 RECOMMENDATIONS

The recommendations are based on the following information and considerations:

- Results of the archaeological survey;
- Consideration of results from other local archaeological studies;
- Results of consultation with the registered Aboriginal parties;
- The assessed significance of the sites;
- Appraisal of the proposed development, and
- Legislative context for the development proposal.

It is recommended that:

1. If complete avoidance of the five recorded sites within the proposal area (Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS1) is not possible, the artefacts must be salvaged prior to the proposed work commencing and moved to a safe area within the property that will not be subject to any ground disturbance.
2. The collection and relocation of the artefacts should be undertaken by an archaeologist with representatives of the registered Aboriginal parties. A new site card/s will need to be completed once the artefacts are moved to record their new location on the AHIMS database.
3. Once the sites Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4 and Beryl Solar Farm AS1 are salvaged, the proposed work can proceed with caution within the development footprint.
4. The development proposal should now be able to proceed without any additional archaeological investigation.
5. First Solar should prepare a Cultural Heritage Management Plan (CHMP) to address the potential for finding additional Aboriginal artefacts during the construction of the Solar Farm and management of known sites and artefacts. The Plan should include the unexpected finds procedure to deal with construction activity. Preparation of the CHMP should be undertaken in consultation with the registered Aboriginal parties.
6. In the unlikely event that human remains are discovered during the construction, all work must cease in the immediate vicinity. OEH, the local police and the registered Aboriginal parties should be notified. Further assessment would be undertaken to determine if the remains were Aboriginal or non-Aboriginal.
7. Further archaeological assessment would be required if the proposal activity extends beyond the area of the current investigation. This would include consultation with the registered Aboriginal parties and may include further field survey.

## 10 REFERENCES

- Brayshaw, H. 1987 *Archaeological survey of a Hard Rock Quarry Near Gulgong, NSW*. Report prepared for Broal Limited.
- Colquhoun et al 1997 *Dubbo 1:250 000 Geological Sheet SI/55-04*, Preliminary second edition, Geological Survey of NSW, Sydney. Australian Geological Survey Organisation, Canberra,
- Cubis, L. 1981 *Archaeological survey of the proposed beryl to Ulan 132 KV Electricity Transmission Line*. Report prepared for Electricity Commission of NSW.
- DECC 2002 *Descriptions for NSW (Mitchell) Landscapes Version 2*. NSW Department of Environment and Climate Change.
- Egloff, B., Peterson, N., and Wesson, S. 2005. *Biamanga and Gulaga: Aboriginal Cultural Association with Biamanga and Gulaga National Parks*. NSW Office of the Registrar – Aboriginal Land Rights Act (1983), Surrey Hills - Sydney.
- Evans, G. 1815 in *Historical Records of Australia Series 1* Vol. 8.
- Fraser, J. 1892 *The Aborigines of New South Wales*.
- Gott, B. 1982 "Ecology of Root Use by the Aborigines of Southern Australia" in *Archaeology in Oceania* 17:59-67
- Hamm, G. 2008 *Moolarben Coal Project Aboriginal Cultural Heritage Assessment Report Stage 2*. Report prepared for Moolarben Coal Mines Pty Ltd.
- Hamm, G. 2009 *Aboriginal Cultural Heritage and Archaeological Assessment for Moolarben Coal Project Stage 1 Rail Loop Modification Project in support of a Section 75W (2) Approval*. Report prepared for Moolarben Coal Operations Pty Ltd.
- Hamm, G. and L. Foley 2010 *Cultural Heritage Management Report on Moolarben Coal Project Stage 1: Open Cut 1 and Main Infrastructure Area*. Report prepared for Moolarben Coal Operations Pty Ltd.
- Hiscock, P 2007, *The Archaeology of Ancient Australia*. Routledge, New York.
- Horton, D. (ed) 1994 *The Encyclopedia of Aboriginal Australia: Aboriginal and Torres Strait Islander History, society and culture*. Aboriginal Studies Press, Canberra.
- Howitt, A W 1996, *The Native Tribes of South-East Australia*. Aboriginal Studies Press, Canberra.
- IBRA 2012 *Department of Sustainability, Environment, Water, Population and Communities. Commonwealth of Australia* Accessed online via <http://www.environment.gov.au/land/nrs/science/ibra>
- Koettig, M. 1985 *Assessment of Aboriginal sites in the Dubbo City Area*. Report prepared for Parkes Shire Council.
- Kuskie, P. 2009 *Ulan Coal Continued Operations: Aboriginal Heritage Assessment*. Report prepared for Ulan Coal Mines Pty Ltd.
- Kuskie, P. 2013 *Moolarben Coal Project- Stage 1 Optimisation Modification, near Ulan, Central Tablelands of NSW: Aboriginal Cultural Heritage Assessment*. Report prepared for Moolarben Coal Pty Ltd.
- Kuskie, P. 2015 *Wilpinjong Coal Mine, Central Tablelands of NSW- Extension project: Aboriginal Cultural Heritage Assessment*. Report prepared for Wilpinjong Coal Pty Ltd.

- Long, A. 2005 *Aboriginal Scarred Trees in New South Wales A Field Manual*. Department of Environment and Conservation, Hurstville.
- MacDonald, G. 1983 *The Concept of Boundaries in Relation to the Wiradjuri People of Inland New South Wales: An assessment of Inter-Group Relationships at the Time of European Conquest*. Report prepared for Wiradjuri Land Council.
- Marquis, P and Walker, M. 1994 *The Illustrated Burra Charter*. Australian ICOMOS, Sydney.
- Mitchell, T. 1839 *Three Expeditions to the Interior of Eastern Australia* 2 Vols. London. Accessed online via <http://gutenberg.net.au/ebooks/e00036.html>
- Mulvaney, D. J., and Kamminga, J. 1999. *Prehistory of Australia*. Allen & Unwin, St Leonards, NSW.
- Murphy, B and J. Lawrie 1998 *Soil landscapes of the Dubbo 1:250,000 Sheet (Dubbo, Wellington, Gulgong, Mudgee)*. Dept. of Land and Water Conservation, Sydney.
- Niche 2015 *Aboriginal Cultural Heritage and Archaeological Assessment Moolarben Coal Complex OC4 South-West modification*. Report prepared for Moolarben Coal Operations Pty Ltd.
- NGH Environmental 2017 *Biodiversity Assessment Report Beryl Solar Farm*. Report prepared for First Solar Pty Ltd.
- NSW National Parks and Wildlife Services 2003 *The Bioregion of New South Wales their biodiversity, conservation and history*. NSW National Parks and Wildlife Services, Hurstville.
- OEH 2010a *Code of Practice for Archaeological Investigation of Aboriginal Objects in New South Wales*.
- OEH 2010b *Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010*.
- OEH 2011 *Guide to Investigating, Assessing and Reporting on Aboriginal Cultural Heritage in NSW*.
- Oxley, J. 1820 *Journals of Two Expeditions into the Interior of New South Wales by Order of the British Government in the Years 1817-1818*.
- Pearson, M. 1981 *Seen Through Different eyes: Changing Land Use and Settlement Patterns in the Upper Macquarie River Region of NSW from Prehistoric Times to 1860*. Unpublished PhD thesis, Department of Prehistory and Anthropology, ANU
- Purcell 2002 *Aboriginal Cultural Heritage Assessment NSW Western Regional Assessments: Brigalow Belt South Stage 2 Final Report*. Report prepared for Resource and Conservation Assessment Council NSW Western Regional Assessments and NSW National Parks and Wildlife Services.
- Ramson, M. 1983 *To Kill a Flocking Bird*. Unpublished B. Litt. Thesis, Department of Prehistory and Anthropology, ANU.
- Smith, L 1987 *Archaeological survey of land near a proposed Hard Rock Quarry, Cudgegong River, Near Gulgong, NSW*. Report prepared for Broal Limited.
- Tindale, N.B. 1974 *Aboriginal Tribes of Australia*. ANU Press, Canberra.
- Woolrych, F.B. 1890 "Native Names of some of the Runs etc. in the Lachlan District" in *Journal of the Royal Society of New South Wales* 24:63-70.

## **APPENDIX A ABORIGINAL COMMUNITY CONSULTATION**

Consultation Log of Beryl Solar Farm project.

| Organisation                                          | Contact                        | Action                                            | Date Sent  | Reply Date | Replied by       | Response                                                                                                                                                                                                                                                                                      |
|-------------------------------------------------------|--------------------------------|---------------------------------------------------|------------|------------|------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| OEH                                                   | Phil Purcell                   | Letter sent via email                             | 15/11/2016 | 16/11/2016 | letter via email | Phil provided list of additional possible Aboriginal stakeholder to contact regarding the project.                                                                                                                                                                                            |
| NTScorp                                               | information@ntscorp.com.au     | Letter sent via email                             | 15/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |
| National Native Title Tribunal                        |                                | online seach- no claim or determination over area | 15/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |
| Office of Registrar <i>Aboriginal Land Rights Act</i> | adminofficer@oralra.nsw.gov.au | Letter sent via email                             | 15/11/2016 | 18/11/2016 | letter via email | Register of Aboriginal Owners and the project area described does not appear to have Registered Aboriginal Owners pursuant to Division 3 of the Aboriginal Land Rights Act 1983 (NSW). Suggest that you contact LALC. Originally noted Broken Hill LALC in error but corrected to Mudgee LALC |
| Central Tablelands                                    | admin.ct@lls.nsw.gov.au        | Letter sent via email                             | 15/11/2016 | 16/11/2016 | via email        | Informed that key contact in area is the Mudgee LALC email: mudgeelalc@bigpond.com                                                                                                                                                                                                            |
| Mid-western shire council                             | council@midwestern.nsw.gov.au  | Letter sent via email                             | 15/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |
| Mudgee LALC                                           | mudgeelalc@bigpond.com         | Letter sent via email                             | 15/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |
|                                                       |                                |                                                   |            |            |                  |                                                                                                                                                                                                                                                                                               |
| Local Newspaper                                       |                                | The Mudgee Guardian                               | 18/11/2016 |            |                  | closing date 2nd December 2016                                                                                                                                                                                                                                                                |
|                                                       |                                |                                                   |            |            |                  |                                                                                                                                                                                                                                                                                               |
| <b>OEH list of potential stakeholders</b>             |                                |                                                   |            |            |                  |                                                                                                                                                                                                                                                                                               |
| Bill Allen                                            |                                | Letter sent via post                              | 17/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |
| Binjang Wellington Wiradjuri heritage Survey          | Dorothy Stewart                | Letter sent via post                              | 17/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |
| Darlina Verrills                                      |                                | Letter sent via post                              | 17/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |
| David Maynard                                         |                                | Letter sent via post                              | 17/11/2016 |            |                  |                                                                                                                                                                                                                                                                                               |

| Organisation                                                    | Contact                | Action               | Date Sent  | Reply Date | Replied by       | Response                                                                                                   |
|-----------------------------------------------------------------|------------------------|----------------------|------------|------------|------------------|------------------------------------------------------------------------------------------------------------|
| Buudang                                                         | Larry Foley            | Letter sent via post | 17/11/2016 | 20/11/2016 | Letter via post  | registered for project.                                                                                    |
| Dhuuluu-Yala Aboriginal Corporation                             | Chairperson            | Letter sent via post | 17/11/2016 |            |                  | return to sender                                                                                           |
| Jean Thornton                                                   |                        | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Jodie Mckinnon                                                  |                        | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Katrina Mckinnon                                                |                        | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Lyn Syme                                                        | North-East Wiraduri    | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Mingaan Aboriginal Corporation                                  | Helen Riley            | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Mooka                                                           | Neville Williams       | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Murong Gialinga Aboriginal & Torres Strait Islander Corporation | Debbie Foley           | Letter sent via post | 17/11/2016 | 20/11/2016 | Letter via post  | Registered for project                                                                                     |
| North- Eastern Wiradjuri                                        |                        | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Paul Brydon                                                     |                        | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Trevor Robinson                                                 |                        | Letter sent via post | 17/11/2016 |            |                  | letter returned to sender no longer at this address                                                        |
| Wamarr Cutural Consultants                                      | Craig Riley            | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Warrabinga Native Tittle Claimants Aboriginal Corporation       | The Board of Directors | Letter sent via post | 17/11/2016 | 25/11/2016 | letter via email | Registered for project Requests map of project location. KB sent map of general project area on 28/11/2016 |
| Wellington Valley Wiradjuri Aboriginal Corporation              | Chairperson            | Letter sent via post | 17/11/2016 | 22/11/2016 | letter via email | registered for project                                                                                     |
| Wiradjuri Council of Elders                                     | Robert Clegg           | Letter sent via post | 17/11/2016 |            |                  |                                                                                                            |
| Wiradjuri Interim Working Party                                 |                        | Letter sent via post | 17/11/2016 |            |                  | letter returned to sender no longer at this address                                                        |

| Organisation                                                           | Contact     | Action                   | Date Sent  | Reply Date | Replied by | Response                                                                                                                                                                                                                                                                                                                    |
|------------------------------------------------------------------------|-------------|--------------------------|------------|------------|------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Wiradjuri traditional Owners<br>Central West Aboriginal<br>Corporation | Chairperson | Letter sent via post     | 17/11/2016 |            |            |                                                                                                                                                                                                                                                                                                                             |
|                                                                        |             |                          |            |            |            |                                                                                                                                                                                                                                                                                                                             |
| <b>Methodology</b>                                                     |             |                          |            |            |            |                                                                                                                                                                                                                                                                                                                             |
| Mudgee LALC                                                            |             | letter via email         | 19/12/2016 |            |            | methodology sent though yet to register<br>for project                                                                                                                                                                                                                                                                      |
| Buudang                                                                |             | letter via email         | 19/12/2016 | 27/12/2016 | via email  | supplied insurances and rates, no<br>comment on the methodology received                                                                                                                                                                                                                                                    |
| Murong Gialinga Aboriginal &<br>Torres Strait Islander Corporation     |             | letter via email         | 19/12/2016 | 27/12/2016 | via email  | supplied insurances and rates, no<br>comment on the methodology received                                                                                                                                                                                                                                                    |
| Warrabinga Native Tittle<br>Claimants Aboriginal Corporation           |             | letter via email         | 19/12/2016 | 27/01/2017 | via email  | supplied rates and insurances and<br>comments on the methodology.<br>Comments to be addressed by NGH                                                                                                                                                                                                                        |
| Warrabinga Native Tittle<br>Claimants Aboriginal Corporation           |             | phone call               | 23/01/2017 |            |            | KB called to ensure received<br>methodology over Christmas period,<br>Kristen informed that email server<br>crashed over Christmas period and<br>unable to recover all emails, asked KB to<br>resend methodology for comment. KB<br>forwarded original methodology email<br>and noted closing date for comments<br>27th Jan |
| Wellington Valley Wiradjuri<br>Aboriginal Corporation                  |             | letter via email         | 19/12/2016 | 5/01/2017  | via email  | supplied rates and insurances and<br>comments on the methodology.<br>Comments to be addressed by NGH                                                                                                                                                                                                                        |
| Warrabinga Native Tittle<br>Claimants Aboriginal Corporation           |             | letter via email         | 27/01/2017 |            | email      | had a number of questions regarding the<br>methodology and the project. NGH to<br>respond.                                                                                                                                                                                                                                  |
| Wellington Valley Wiradjuri<br>Aboriginal Corporation                  | Brad Bliss  | MB sent letter via email | 30/01/2017 |            |            | NGH sent letter in response to queries<br>and providing clarification on<br>methodology.                                                                                                                                                                                                                                    |
| Warrabinga Native Tittle<br>Claimants Aboriginal Corporation           |             | email                    | 31/01/2017 |            |            | provided new insurance details                                                                                                                                                                                                                                                                                              |
| Murong Gialinga                                                        |             | email                    | 31/01/2017 |            |            | provided revised rates                                                                                                                                                                                                                                                                                                      |

| Organisation                                                    | Contact       | Action                                      | Date Sent  | Reply Date | Replied by     | Response                                                                                                                                                                                                                                                                                                                           |
|-----------------------------------------------------------------|---------------|---------------------------------------------|------------|------------|----------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Warrabinga Native Tittle Claimants Aboriginal Corporation       |               | KB sent letter via email                    | 9/02/2017  |            |                | NGH sent letter in response to queries and providing clarification on methodology.                                                                                                                                                                                                                                                 |
| <b>OEH informed of registered parties</b>                       | Phil Purcell  | via email                                   | 30/01/2017 |            |                | 4 x registered parties and 3 x return to sender letters                                                                                                                                                                                                                                                                            |
| <b>Fieldwork 21-22 Feb 2017</b>                                 |               |                                             |            |            |                |                                                                                                                                                                                                                                                                                                                                    |
| Buudang                                                         | Larry Foley   | On site 21/02/2017                          |            |            |                |                                                                                                                                                                                                                                                                                                                                    |
| Murong Gialinga Aboriginal & Torres Strait Islander Corporation | Larry Foley   | On site 22/02/2017                          |            |            |                |                                                                                                                                                                                                                                                                                                                                    |
| Warrabinga Native Tittle Claimants Aboriginal Corporation       | Tayle Pennell | On site 21/02/2017                          |            |            |                |                                                                                                                                                                                                                                                                                                                                    |
| Wellington Valley Wiradjuri Aboriginal Corporation              | Shanae Martin | On site 22/02/2017                          |            |            |                |                                                                                                                                                                                                                                                                                                                                    |
| <b>Draft report</b>                                             |               |                                             |            |            |                | <b>comments due 24 April 2017</b>                                                                                                                                                                                                                                                                                                  |
| Buudang                                                         |               | sent via email                              | 27/03/2017 |            |                |                                                                                                                                                                                                                                                                                                                                    |
| Murong Gialinga Aboriginal & Torres Strait Islander Corporation |               | sent via email                              | 27/03/2017 |            |                |                                                                                                                                                                                                                                                                                                                                    |
| Warrabinga Native Tittle Claimants Aboriginal Corporation       |               | sent via email                              | 27/03/2017 | 24/04/2017 | via email      | Asked for extension to supply comments on 26/04 KB responded that this was not a problem                                                                                                                                                                                                                                           |
| Wellington Valley Wiradjuri Aboriginal Corporation              |               | sent via email                              | 27/03/2017 | 24/04/2017 | via email      | Wellington Valley Wiradjuri Aboriginal Corporation does not have any objections to the report as published for the solar farm. All recommendations as outlined in the report are satisfactory.                                                                                                                                     |
| Buudang                                                         |               | KB sent follow up email requesting comments | 26/04/2017 | 26/04/2017 | via phone call | Agreed with the recommendations outlined in the report the only comment was that the artefacts identified should be moved prior to any works commencing and be placed back on country as close as possible to the original location as possible. Stressed importance of objects being kept on country. Enjoyed working on project. |

| Organisation                                                    | Contact | Action                                      | Date Sent  | Reply Date | Replied by     | Response                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|-----------------------------------------------------------------|---------|---------------------------------------------|------------|------------|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Murong Gialinga Aboriginal & Torres Strait Islander Corporation |         | KB sent follow up email requesting comments | 26/04/2017 | 26/04/2017 | via phone call | Agreed with the recommendations outlined in the report the only comment was that the artefacts identified should be moved prior to any works commencing and be placed back on county as close as possible to the original location as possible.                                                                                                                                                                                                                                                               |
| Warrabinga Native Tittle Claimants Aboriginal Corporation       |         | letter via email                            | 26/04/2017 |            |                | letter outlining a number of issue in report -NGH respond via letter and updated report                                                                                                                                                                                                                                                                                                                                                                                                                       |
| Buudang                                                         |         | email                                       | 29/04/2017 |            |                | Deborah Foley wrote email behalf of Buudang And Murong Gialinga for written record following earlier phone call to KB noting that they agree with the recommendations, survey methodology taken during the field work also the results as outlined in the report , Both Murong Gialinga and Buudang have agreed with our recommendation that the Artefacts should return to county as close as possible where they were originally found. Noted that a Aboriginal rep be present when the Artefacts are moved |
| Warrabinga Native Tittle Claimants Aboriginal Corporation       |         | letter and revised report via email         | 6/07/2017  |            |                | letter outlining NGH response and sent final report                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| Wellington Valley Wiradjuri Aboriginal Corporation              |         | Report via email                            | 6/07/2017  |            |                | NGH sent final report                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| Buudang                                                         |         | Report via email                            | 6/07/2017  |            |                | NGH sent final report                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| Murong Gialinga Aboriginal & Torres Strait Islander Corporation |         | Report via email                            | 6/07/2017  |            |                | NGH sent final report                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |

Public Notice placed in The Mudgee Guardian on 18 November 2016.

**Connect with Classifieds**  
SAVE UP TO 50%  
CALL US TODAY  
ON 02 6372 1455  
Fairfax Media

**QUOTES & REVIEWS**  
**DOWDY INSURANCE**  
PHONE 0427 724 744

**FOR SALE** Caravan Viscount, 1976 Higo X16706, rego till May 2017, good tyres, new spare, good condition, LED lights inside. Contact Brian 0438 323 908

Sofa Lounge, Pine Wardrobe, Desk  
Tel: 0405 289 475

**SPANLINE** Rep in area next week. Patios, Cladding, Rooms, Carports. As on TV 637 26996. BL63757C  
www.spanline.com.au

**Garage Sales**

83 Short Street, Mudgee 8-30am to 2pm.  
Household items plus Hardwood Timber, Art, Cedar Doors and Windows, Sofa-bed, King-Bed, Mattresses, Claw-foot Bath, Antique Kitchen Dresser, Wooden Chests. All must go. Ph: 0402 715 879 for enquiries on bigger items.

14 Constanilla Road, Meters, Drills, Tools, Books  
Saturday 19th November, 9.00AM  
20 Spring Road, Mudgee  
Small Furniture, Books and Bric-A-Brac

**For Rent**

1 Bedroom fully furnished flat for rent in Mudgee  
Phone 0432-749-507

**Pets and Pet Care**

NORMAN'S TLC PET BOARDING and Pet Cremation Services 24/7  
www.nammspets.com  
0447-009-037

**Produce**

ALL GRADES of produce have available 0438-226-884 business hours.

**Public Notices**

**DENTURES | RELINES | REPAIRS**  
Leon Deloraini Denture Clinic is now in attendance Mudgee Medical Centre, 145 Church Street, 8am to 12pm Wednesdays  
1399 134 486

**RESTORE SIGN FOR JUST \$25**  
DONATE SIGN  
1800 352 400

The Housing Plus Annual General Meeting will be held at 3:00pm on Thursday 24 November 2016 at  
Quality Inn Ambassador, 174 Bathurst Road, ORANGE NSW 2800  
All Welcome to attend.  
RSVP by Monday 21 November 2016 to the Executive Assistant via  
www@housingplus.com.au

**Rylstone Kandos Aged & Disabled Association Inc. Annual General Meeting**  
ADA Cottage  
ADA Community Services  
Annual General Meeting to be held at The Globe Hotel, Rylstone, on Thursday 8th December 2016, commencing at 6.30pm.  
All interested persons are invited to attend.

**Expression of Interest - Christmas Venue Host**  
Mudgee Chamber of Commerce will soon be having their Christmas Function for members.  
The Chamber would like to hear from venues in Mudgee who are interested in hosting the event.  
The criteria is:  
• **Availability:** Access to venue from 5:30pm until 9:30pm  
• **Access:** A level access or lift option is essential  
• **Space:** For a minimum 40 people  
• **Catering:** Please quote on finger food and supply a suggested menu together with a price per head.  
• **Alcohol:** A licensed venue is preferred.  
The event will be a casual get together and a chance to network between members. We would like to hold the event on Thursday 8 December.  
This EO is open to members of Mudgee Chamber of Commerce and any potential New MCC Members. Please email EO to info@mudgeechamber.com.au. EO closes on Wednesday 23 November 4:00pm. For further information, please call Kim Gribble 0403 130 899.

**Notification for registration of interest for Aboriginal stakeholders**  
NGH Environmental has been contracted by First Solar Pty Ltd to undertake an Aboriginal Cultural Heritage Assessment (ACHA) for the proposed Beryl Solar Farm. The assessment area comprises of land at the proposed location of the solar farm on Lot 2/ DP 1173059 and Lot 1/DP 1012826, with transmission lines extending to the adjacent existing Beryl substation on Lot 1/DP 523876 in the Mid-Western Regional Council, Local Government Area.  
The proponent (First Solar Pty Ltd) is proposing to construct a utility scale solar farm including panels, electrical reticulation, substation, internal access tracks, site office and perimeter fencing.  
The purpose of this consultation, particularly with Aboriginal people, is to assist the proponent in the preparation of the ACHA and to be involved in consultation should the proponent need to apply for an Aboriginal Heritage Impact Permit (AHIP), and further to assist the Director General of the Office of Environment and Heritage in consideration and determination of such an application.  
In order to fulfil the requirements set out in the OEH Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010, NGH Environmental is seeking interested Aboriginal parties who hold cultural knowledge of the assessment area to register their interest in the consultation process for the project and to assist in the determination of cultural significance of any Aboriginal objects or places located there.  
Registrations should be provided in writing to:  
NGH Environmental Pty Ltd  
PO Box 62  
FYSWICK ACT 2609  
Or via email to:  
ngh@nghenvironmental.com.au  
All correspondence must be received by the 2nd December 2016  
Those registering an interest will be contacted to discuss the project further. Those who do register are advised that their details will be provided to OEH and the Local Aboriginal Land Council, unless they specifically advise in writing that their details are not to be forwarded.

**RAIL MOTOR TRAIN RIDES**  
Gulgong to Dunedoo  
4 Ulan  
19th & 20th November  
6373 3625  
0458 555 929  
kingpeter2850@gmail.com  
MUDGEE MINAATUNE RAILWAY

**AGM of**  
Mudgee Disability Support Service Inc.  
will be held on  
Monday 21st November  
at Mudgee C.W.A Hall  
Market Street  
from 6pm  
63723948  
All Visitors welcome

**AGM, Mudgee Region Mud-  
dragons annual meeting to  
be held Wednesday 23rd  
November at 6:00pm at  
Lawson Park Hotel**

**PINGALL RECORDS &  
TROPHIES** Mr Dykes  
Mortimer Centre,  
0411 097 856

Triathlon Sunday 4th  
December, streets affected  
are Short, Lawson and  
Mortimer 8am to 11am

We are looking for a highly motivated reporter to join our news team, filing stories for the Lithgow Mercury and our website and social media platforms.  
The successful applicant will be as comfortable covering courts and council rounds as they are working on community and social news. You must have experience in digital photography and have a sound knowledge of social media. As well as photographic skills, video experience would be highly regarded.  
We are looking for a candidate who is keen to develop news-reporting skills across a range of platforms using the latest digital software. You will be able to work quickly and accurately, and be an ambassador for the Lithgow Mercury. You must also be willing to work on weekends and evenings when required.  
If you thrive in the deadline driven media world, we can offer you the chance to be part of our editorial team and one of the largest media companies in the country. Apply online at  
fairfaxmediacareers.com  
quoting position number 25068  
Disclaimer: Fairfax Media does not accept unsolicited agency resumes. Fairfax Media is not responsible for any fees related to unsolicited resumes.

**Assistant Manager (Development Role)**  
Cassilis NSW  
An exciting opportunity has arisen for a reliable, self-motivated person seeking long-term employment to assist in the management of a large beef grazing property in the Upper Hunter area of NSW, Australia. This property is close to the NSW towns of Merriwa and Colah.  
**The successful applicant will have:**  
• 5-7 years relevant experience  
• Experience in road building and maintenance including previous experience in operating a bulldozer and grader, yard building, fencing, water reticulation, machinery operation in steep country, woody weed control and renovation/maintenance of property houses.  
• Sound communication and mechanical skills.  
• Sound knowledge of pasture improvement programs.  
• Proven ability to manage staff and communicate effectively.  
• Accurate record keeping skills & computer knowledge.  
• Ability to work unsupervised, as part of a team and to manage staff with a high level of integrity and respect.  
• Ambition to take on higher managerial responsibility as your career progresses.  
An excellent remuneration package will be on offer to the right candidate including a four-bedroom home with well-developed gardens, breeze air and wood heating that will be supplied with employment. For more information, please contact our Farm Manager Trevor Nash on +61 418 459 551 or go to www.betrols.com.au To apply directly, please send your application to tre@betrols.com.au

**adzuna**

Warrabinga Native Title Claimants Aboriginal Corporation response to  
methodology and NGH response

# WARRABINGA

## Native Title Claimants Aboriginal Corporation

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4805 0615



Kirsten Bradley  
Heritage Consultant  
NGH Environmental  
Unit 17, 27 Yalourn St  
Hythwick ACT 2609

27th January 2017

Dear Kirsten,

**RE: 1st Round of Comment on Aboriginal Heritage Investigation Methodology, Beryl  
Solar Farm, December 2016**

Below you will find our comments in regards on the Aboriginal Heritage Investigation Methodology, Beryl Solar Farm, December 2016 prepared by NGH Environmental (NGH) for First Solar Pty Ltd.

Warrabinga would like to notify NGH that we are presently authorising a whole of country claim (which includes the Subject Area), and are of the expectation that this claim will pass registration. Given our acknowledged position as Traditional Owners, we expect to be the sole RAs involved in all fieldwork associated with the project.

Warrabinga has registered and been determined for upwards of 10 claims within the extent of our country. There is no reason to suggest that a determination on our whole of country claim will not be made in the near future.

NGH has not clarified as to what part of the Aboriginal Cultural Heritage Consultation Requirements for Proponents (DECCW, 2010) this document relates to. Has this document been prepared to address Stage 2 – Presentation of Information about the Proposed Project, or Stage 3 – Gathering Information about cultural significance?

In regards to Section 3.1 Project Background, no information has been provided in regards to:

- How many PV modules will be installed;
- Is demolition of existing structures required;
- The amount of land clearance required for the proposed works;
- The amount of earthworks required;
- What is the maximum depth of ground disturbance as a result of construction; and,
- Is there a civil works boundary.

Is there a design layout for the proposed solar farm? If so, please provide the layout to all RAs.

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



If there is a civil works boundary? If so, where is it? And, will it be assessed as part of this project?

What is the former land-use and disturbance of the project area? Both of these factors will impact the likely identification of surface artefacts, as well as the presence of subsurface archaeological deposits within the project area.

Please provide a copy of the site card for AHIMS #36-2-0016. Please provide a map that shows the extent of AHIMS #36-2-0016 in relation to the project area.

Please provide details in regards to the landform the AHIMS #36-2-0016 is located on, as well as the landforms present with the project area. Based on proximity, if the landform at AHIMS #36-2-0016 is present within the project area, it would not be unreasonable to predict that there is potential for a similar site to be present within the project area.

In Sections 4.2 Regional Archaeological Models and 4.3 Previous Archaeological Studies, NGH states that the presence and distance of water, as well as landform will likely have an influence on the identification of Aboriginal sites. NGH has provided no details in regards to the presence and distance of water in relation to the project area; nor, have any landforms within and around the project area been identified.

NGH has not provided sufficient information in order for Warrabinga to comment on the potential for Aboriginal heritage to be present within the project area. Please provide information in relation to the environmental context of the project area.

In Section 4.3 Previous Archaeological Studies, NGH has not clarified as to whether the project area has been previously subject to an Aboriginal heritage assessment. Please clarify.

Have there been any Aboriginal archaeological excavations been undertaken in the area? If so, what do the results indicate in relation to the presence of subsurface deposits and landforms?

NGH has provided no details in regards to the critical timeline for the project. Please include as part of the Aboriginal Heritage Investigation Methodology, as required by the *Aboriginal Cultural Heritage Consultation Requirements for Proponents* (DECCW, 2010).

We wait to receive your responses to our queries and all queries provided by RAPs in regards to the Aboriginal Heritage Investigation Methodology.

Warrabinga waits to receive an updated Aboriginal Heritage Investigation Methodology, which includes the requested information.

# WARRABINGA

*Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



It should be noted that this may not be Warrabinga's last response in regards to the documentation provided to-date by NGH Environmental; Warrabinga will provide additional responses until such time as we feel that our concerns have been satisfactorily addressed.

Should you wish to have a meeting to discuss the issues we have raised please coordinate this with our office via email ([info@warrabinga.com.au](mailto:info@warrabinga.com.au)).

Regards,

per: 

Virginia Doig  
Director



9 February 2017

Virginia Doig  
Director  
Warrabinga Native Title Claimants Aboriginal Corporation  
PO Box 282  
Mudgee NSW 2850

Dear Virginia,

**RE – #16-337 Registration of interest for Aboriginal stakeholders, Beryl Solar Farm**

I refer to your response dated 27 January 2017 to the proposed methodology for the cultural heritage assessment of the proposed Beryl solar farm. Thank you for your response. You raised a number of issues which this letter aims to address.

NGH Environmental is obliged under the OEH Consultation Requirements to consult with all Aboriginal parties who register for the project. While we understand the sentiments of your request to be the sole RAPs involved in the fieldwork for this project, we are not in a position to exclude Aboriginal people who register on this basis and the Consultation Requirements state that the proponent is able to determine who attends the field survey. While there may be active Native Title claims within the broader region, at this point there is no determined claim over the project area. However, the proponent would like to ensure that you are represented in the field survey.

Your request for NGH to clarify as to what part of the *Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010* methodology document provided refers to is noted in Section 5.2 Methodology Outline. The methodology document provides details of the project and the heritage assessment methodology to registered parties for comment (Stage 2) and seeks any information on whether there are any known places or objects of cultural significance to the Aboriginal people (Stage 3).

The project boundary provided in the methodology document Figure 2 outlines the civil work boundary for the project. The indicative development area design of the solar farm is provided below. The entire project area as identified in the methodology provided will be assessed as part of this project.

As stated in Section 3.1 Project Background, the assessment area is primarily cultivated. It is understood that the land has been used for grazing and cropping purposes in the past and is disturbed. The disturbance is most likely to have occurred in the form of clearing and ploughing activities. It has been noted recently that the quarrying of material may have previously occurred in sections of the assessment area. The exact location/s of any quarrying are currently unknown however this would be further assessed and noted during the field survey.

While the design plan has yet to be finalised the current design indicates:

- There will be approximately 950,000 PV modules (solar panels).
- There are no existing structures within the project area that have been indicated to require demolition.
- The development envelope will cover approximately 220ha of the 300ha project area.

**canberra**

unit 8, 27 yallourn st  
(po box 62)  
fyshwick act 2609  
t 61 2 6280 5053  
f 61 2 6280 9387

**bathurst**

35 morrisset st  
po box 434  
bathurst nsw 2795  
t 0448 820 748

**bega**

suite 1, 216 carp st  
(po box 470)  
bega nsw 2550  
t 61 2 6492 8333

**newcastle**

153 tudor st  
hamilton nsw 2303  
t 61 2 4969 4910

**sydney**

unit 18, level 3  
21 mary st  
surry hills nsw 2010  
t 61 2 8202 8333

**wagga wagga**

suite 1, 39 fitzmaurice st  
(po box 5464)  
wagga wagga nsw 2650  
t 61 2 6971 9696  
f 61 2 6971 9693

[ngh@nghenvironmental.com.au](mailto:ngh@nghenvironmental.com.au)  
[www.nghenvironmental.com.au](http://www.nghenvironmental.com.au)

- The installation of 45,000 piles supporting the solar panels, would be driven or screwed into the ground to a depth of approximately 1.5m.
- Trenches for underground cabling would be to a depth of approximately 1m.

You noted that if there were landforms similar to that where site AHIMS#36-2-0016 was recorded, it would not be unreasonable to predict that there is potential for similar sites to occur in the project area. NGH has also recognised the potential for Aboriginal objects and sites in the project area and field inspection will be carried out for this project as documented in the methodology.

Please note that the site card for AHIMS 36-02-0016 has been attached below for your record as requested. The information provided on the site card is poor and the information you have requested relating to the landform of the site and size is not detailed. However, the site was noted at the time of its recording to be a campsite and said to still be frequented. Bondi point artefacts were also noted. The site card list R. Hawkins as the informant for the site. No other information pertaining to this site is available.

In regards to your query regarding distance to water around the project area these can be seen in Figure 2 in the Methodology document. The project area is located just east of the convergence of the Cudgong and Wialdra Creeks. Cudgegong River lies approximately 750m to the south of the project area, and Wialdra Creek is situated approximately 150m to the north of the project area, at its closest point. The landscape is generally an undulating plain with a low hill rising adjacent to the north-eastern boundary of the project area, which while within the project boundary is not identified as part of the development footprint.

NGH also wish to clarify that the project area has not been subject to any Aboriginal Heritage assessments. The surveys undertaken in close proximity to the project area were summarised in the Methodology Section 4.3 Previous Archaeological studies. No known archaeological excavations have been undertaken in close proximity to the project area. The closest known excavations were undertaken approximately 25km to the east at Ulan as detailed in the methodology. While the excavations at Ulan provide a date of occupation for the general region the distance between the areas and difference in landscapes does not allow other comparisons to be made given the limited presence of higher order watercourse at Ulan compared to the Beryl project area.

In regards to your request for the proponent to specify critical timelines and milestones for the completion of assessment activities and the delivery of reports NGH have been advised that the current schedule for completion of the Draft Aboriginal Cultural Heritage Assessment report for inclusion in the Environmental Impact Statement Report (EIS) for public exhibition is the 1 March 2017.


We would also advise that First Solar will be holding an open public meeting on 23 February (2pm) where you may go to obtain further information and meet the proponent's representatives.

NGH Environmental and First Solar acknowledge your rates and insurances and conditions of engagement in terms of notice.

Once again thank you for your interest in the project and no doubt we will be in touch to clarify potential fieldwork dates.


If you have any questions, please do not hesitate to contact me on 6153 6320.

Yours Sincerely,



Matthew Barber

Principal Heritage Consultant  
NGH Environmental



Development area for Project.

|                                             |                                                                             |                                          |                                                                                                         |
|---------------------------------------------|-----------------------------------------------------------------------------|------------------------------------------|---------------------------------------------------------------------------------------------------------|
| N II 8733<br>COBBORA                        | DUBBO SI/55-4                                                               | Locality                                 | 36-2-16<br>OPEN                                                                                         |
| [Beryl]                                     |                                                                             |                                          |                                                                                                         |
| Military map/other reference                | 1:250,000 243999                                                            | C-1299                                   |                                                                                                         |
| Pastoral or other property, park            |                                                                             |                                          |                                                                                                         |
| Suburb, street, number                      |                                                                             |                                          |                                                                                                         |
| Description of site                         | Campsite, said to be still frequented.                                      |                                          | <br><b>36-2-0016</b> |
|                                             |                                                                             |                                          |                                                                                                         |
|                                             | Length                                                                      | Width                                    |                                                                                                         |
| Soil and vegetation on and adjacent to site |                                                                             |                                          |                                                                                                         |
|                                             |                                                                             |                                          |                                                                                                         |
| Nearest water supply                        |                                                                             |                                          |                                                                                                         |
| Erosion, cultivation or other works         |                                                                             |                                          |                                                                                                         |
| Assemblages                                 |                                                                             |                                          |                                                                                                         |
| Implement types                             | Include bondi points.                                                       |                                          | <div style="font-size: 4em; margin: 0;">+</div>                                                         |
|                                             |                                                                             |                                          |                                                                                                         |
| Site collection deposited                   |                                                                             |                                          | <div style="font-size: 2em; margin: 0;">36-2-16</div>                                                   |
| Associated with                             | rock engravings<br>stone arrangements<br>fireplaces                         | rock paintings<br>axe grooves<br>burials | carved trees<br>quarry<br>other relics                                                                  |
| Photo record by                             |                                                                             | Where deposited                          |                                                                                                         |
| Scale chart by                              |                                                                             | Where deposited                          |                                                                                                         |
| History                                     |                                                                             |                                          |                                                                                                         |
|                                             |                                                                             |                                          |                                                                                                         |
| Aberiginal meaning and name                 |                                                                             |                                          |                                                                                                         |
|                                             |                                                                             |                                          |                                                                                                         |
| Published reference                         |                                                                             |                                          |                                                                                                         |
| Remarks                                     | Information from R. Hawkins, 2 Lookerbie Rd., Thornleigh, 2120. Ph. 847101. |                                          |                                                                                                         |

25-2-76

**Correspondence from Wellington Valley Wiradjuri Aboriginal Corporation 24 April 2017**

**From:** WVVAC Contact Officer [mailto:WVVAC@hotmail.com]  
**Sent:** Monday, 24 April 2017 1:47 PM  
**To:** Kirsten Bradley <kirsten.b@nghenvironmental.com.au>  
**Subject:** Re: Beryl Solar Farm Draft Report- request for comments

Dear Kirsten

Wellington Valley Wiradjuri Aboriginal Corporation does not have any objections to the report as published for the solar farm. All recommendations as outlined in the report are satisfactory.

Regards,

Bradley R. Bliss J.P.  
WVVAC Chairman and Contact Officer  
P.O. Box 2290  
Orange NSW 2800  
Email: [WVVAC@hotmail.com](mailto:WVVAC@hotmail.com)  
Mobile: 0427321016

**Correspondence from Murong Gialinga and Buudang 29 April 2017**

**From:** Debbie Foley [mailto:dfoley2850@hotmail.com]

**Sent:** Saturday, 29 April 2017 11:22 PM

**To:** Kirsten Bradley <kirsten.b@nghenvironmental.com.au>

**Subject:** Re: Beryl Solar Farm Draft Report- request for comments

I Deborah Foley am writing this email on behalf of Buudang And Murong Gialinga that we agree with the recommendations also the survey methodology taken during the field work also the results as outlined in the report , Both Murong Gialinga and Buudang have spoken with our recommendation that the Artefacts should return to county as close as possible where they were originally found a Aboriginal rep be present when the Artefacts are removed from country and taken back to country .We would like to thank Kirsten and Matt and look forward to working with them in the future .

Kind Regards Debbie Foley

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



NGH Environmental Pty Ltd  
Attn: Kirsten Bradley,  
Heritage Consultant,  
Unit 8, 27 Yallourn St,  
Fyshwick ACT 2609

26<sup>th</sup> April 2017

Dear Kirsten,

**RE: 1st Round of Comment on DRAFT Aboriginal Cultural Heritage Assessment for Beryl Solar Farm, March 2017**

Below you will find our comments in regards on the DRAFT Aboriginal Cultural Heritage Assessment for Beryl Solar Farm, March 2017 prepared by NGH Environmental for First Solar Pty Ltd.

First off, we would like to make it clear that NGH Environmental should not finalise the DRAFT Aboriginal Cultural Heritage Assessment for Beryl Solar Farm, March 2017 until they have received confirmation from Warrabinga that we are of the opinion that all our concerns have been addressed. We would also like to clarify that all our concerns must be addressed in the Aboriginal Cultural Heritage Assessment report.

On page vi, it is stated that "the intention for the heritage survey was to cover as much of the ground surface as possible"; the use of the word "intention" implies that the heritage survey was different to that proposed in the methodology provided by NGH in December 2016. Please clarify whether the heritage survey differed from that which was proposed in the methodology, if so, how did it differ?

Warrabinga could not find copies of site cards issued to AHIMS, in relation to the newly identified sites (Beryl Solar Farm IF 1, Beryl Solar Farm IF 2, Beryl Solar Farm IF 3, Beryl Solar Farm IF 4, and Beryl Solar Farm AS 1) in the report. Please provide copies of the site cards in the report.

At no point in the report does NGH Environmental state whether any subsurface investigations have been undertaken within the region of Beryl, or whether excavations had been undertaken within similar landforms within the mines (i.e. Ulan, Moolarben, Wilpingjong). Please clarify.

In relation to point 2 of the recommendations, an Aboriginal Site Impact Recording Form (ASIR) needs to be prepared once the surface artefacts have been collected in order to document that state of their original location prior to relocation.

In relation to points 3 and 4 of the recommendations, Warrabinga believes that subsurface investigations of the landforms within the Project Area are necessary

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



before the proposed works can commence without additional archaeological investigations. NGH has provided in sufficient information in order to determine the likely extent and nature of the Aboriginal sites present within the Project Area. The *Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW* (DECCW, 2010) says that Archaeological test excavation will be necessary when (regardless of whether or not there are objects present on the ground surface)...the area cannot be substantially avoided by the proposed activity.

As NGH Environmental has not proposed a conservation management outcome (i.e. reconfiguration of development layout), and the proposed works will result in the **destruction** of the Aboriginal site (Warrabinga considers both the Aboriginal object and the land that it was located on, to constitute an Aboriginal site), it is not unreasonable that a subsurface investigation program be undertaken prior to construction works commencing. Furthermore, this point in the project will be the only opportunity for a subsurface investigation to take place, once the project has been completed; all future archaeological assessments will consider the Project Area to be highly disturbed and as such will have nil potential for Aboriginal objects to be present.

Based on the information detailed in the report it is evident that a detailed configuration plan is available. Warrabinga requests that the detailed development configuration be provided in the report.

No 1:25,000 topographic map has been included in the report; it is industry standard to include a 1:25,000 topographic map, or something similar (not an ESRI topographic map). Please include.

NGH Environmental refers to landforms within the Project Area; however, no landforms map has been included in the report. Please include.

NGH Environmental refers to disturbance present within the Project Area; however, no disturbance map has been included in the report. Please include.

Warrabinga could not find a copy of the site card for AHIMS #36-2-0016 in the report. Please provide a copy of the site card in the report.

Upon review of the AHIMS results shown in Figure 7, Warrabinga notes that the cluster of Aboriginal sites around the Project Area are important. Please provide a zoomed-in map of Aboriginal sites surrounding the Project Area, and discuss these sites in relation to the Aboriginal sites identified within the Project Area.

Warrabinga requires that the extent of the AHIMS search be produced on Figure 7, this is because we note that there a large number of sites east of Gulgong which were not evident in Figure 7, but are discussed in Section 3.2.4. Please include.

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



In regards to Section 3.2.3, there are a number of archaeological assessments that have been undertaken in the last 15 years within the mines east of Gulgong, and many of these assessments have formed and refined the archaeological models for the surrounding regions; however, none of these archaeological models has been considered in this report. Please include.

In Section 3.2.4, a number of archaeological studies have been discussed, but no map has been included to detail the location of each of the studies in relation to the Project Area. Please include a map.

On page 19, it is noted that there was an error when AHIMS uploaded an OzArk report prepared for the existing 66kV powerline from Beryl Substation to Dunedoo Substation; did NGH Environmental try to request a copy of this report from OzArk? If not, why not?

In the last paragraph on page 20, NGH Environmental references several excavations that were undertaken within Wilpingjong (WCP33, WCP2016, and WCP92); however, Warrabinga believes that WCP33 and WCP92 are in different environments compared with the Aboriginal sites identified within the Project Area. Warrabinga believes that it would be far more appropriate to discuss the results from the excavations undertaken at Wilpin Farm and WCP133, as these sites are located in more similar environmental contexts to that of the newly identified Aboriginal sites. Please amend.

Warrabinga requires clarity on how the survey was undertaken, especially when the "the intention for the heritage survey was to cover as much of the ground surface as possible"; at no point in the report does NGH Environmental provide a copy of the transects and/or GPS track logs from the survey. Please provide.

NGH Environmental has not provided details as to whether the survey was limited to the proposed project footprint or the entire Project Area. Please clarify.

If the survey was limited to the proposed project footprint, what will happen if the footprint is reconfigured to include areas that were not subject to survey?

Warrabinga questions why only 2 days were allocated for undertaking a survey of an area of approximately 332 hectares; Warrabinga is well aware that the average survey can cover approximately 40 hectares per day, on this basis, it sounds like that NGH undertook a targeted survey, and did not survey the entire Project Area.

On page 22, it is stated that "transects were spaced evenly with the survey team spread at 20m intervals"; however, in the Executive Summary (page vi) it is stated that "allow for an effective view width of 5m each person", Warrabinga is confused. Please clarify what NGH means.

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



The Code of Practice (DECCW, 2010) and standard industry practices, requires that a brief description be provided for each transect; Warrabinga was unable to locate a description of each of the transects. Please include.

In regards to Table 5, the Code of Practice (DECCW, 2010:18) states that:

*Survey results must:*

- *Be presented in the format of the example tables below or include clear justification where this format is not used, and*
- *Include a descriptive summary of the survey for each landform unit and then for the whole subject area.*

Table 5 is not present in the same format as those on page 19 of the Code of Practice (DECCW, 2010). The "survey coverage" in the Code of Practice (DECCW, 2010:19) shows that each survey unit (or transect in this case) is listed. Why has NGH differed from the format required in the Code of Practice? Please amend Table 5 to reflect the tables required by the Code of Practice (DECCW, 2010).

Table 6 is missing the datum. Please amend.

At no point in the report, does NGH hypothesise whether the artefacts had eroded out of the ground, or had been displaced. Please consider, and do not just pick the easy answer.

The location of Beryl Solar Farm AS 1, Beryl Solar Farm IF 3 and Beryl Solar Farm IF 4 in Figure 10 indicates that it is highly likely that subsurface Aboriginal objects are present. NGH Environmental only appears to be interested in Aboriginal objects if they are considered high density; at no point has NGH Environmental considered that the artefacts identified may signify a low-density artefact scatter, or a possible knapping site.

In Section 4.4, it is stated that the identified Aboriginal sites are "in close proximity to either permanent or ephemeral water sources"; please define what you mean by "close proximity".

It should also be noted that at no point has NGH Environmental provided a map that shows both permanent and ephemeral water sources. Please include.

In paragraph 3 on page 33, it is stated that "they are most likely representative of the use of major water course"; please explain who and for what purpose.

In paragraph 3 on page 33, Warrabinga does not understand the phrase "associated back country". Please explain.

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



In paragraph 4 on page 33, it is stated, "the presence of cores and flakes indicates that tool manufacture probably occurred onsite"; if this is the case, why has NGH Environmental not considered a large scale landform excavation. Please explain. If tool manufacture occurred onsite, then it is **highly** likely that additional artefacts will be present both on the surface and subsurface.

The statement above is furthered by the fact that "multi-staged approach to manufacturing artefacts, including the source of material, and then shaping and manufacturing of the desired product" is likely to have occurred onsite. If a multi-stage approach occurred onsite then all sorts of Aboriginal artefacts are likely to be present, including tools, knapping debitage, etc.

It should also be noted that ground disturbance as a result of European practices is typically limited to the upper 20cm of the soil deposit (also referred to as the plough-zone); NGH Environmental has provided no argument to say that intact artefact deposits would not be present below the plough-zone.

In paragraph 5 of page 33, it is stated that "no grinding grooves have been recorded on AHIMS within Beryl area", Warrabinga does not agree with this statement made by NGH Environmental; the statement should read, "no grinding grooves have been recorded within the AHIMS search area". This is because a large number of grinding grooves have been recorded east of the AHIMS search extent. Please amend.

In paragraph 6 on page 33, if there are two large basalt outcrops which have the potential to have been utilised by Aboriginal as part of sourcing raw material for artefact production, but evidence for this utilisation was destroyed by European quarrying practices, then the reasonable response would be to undertake a subsurface investigation of the area surrounding the outcrops in order to determine the presence and/or absence of Aboriginal objects, and therefore utilisation by Aboriginal people.

In paragraph 7 on page 33, it is stated "it is possible that additional stone artefacts could occur", if this is the case why has no subsurface investigation been proposed? Please explain. It does not matter whether an Aboriginal site has a high density of objects or a **low density** of objects, all artefacts can tell a story about how past Aboriginal people utilised a landscape.

As previously stated, this project is the only point in which it will be possible to undertake a subsurface archaeological investigation, once this project is finished in 30 years' time, all subsequent archaeological assessments will consider the Project Area to have been heavily impacted, and nil potential for Aboriginal objects to be present.

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



In addition, NGH Environmental has provided no conservation outcome for Aboriginal objects within the Project Area. Warrabing does not consider it unreasonable to expect that for a State Significant Development would at least **offer** a conservation outcome; all that has been offered is the collection of surface artefacts, and the **destruction** of any and/or all subsurface artefact bearing deposits. Please provide a conservation outcome.

All evidence of Aboriginal occupation is of high cultural significance to Warrabing.

In regards to Section 6.2, please provide a map that shows the location of the Aboriginal sites and the detailed development configuration. At this point, Warrabing is unable to provide comment on the proposed work in relation to Aboriginal heritage, as insufficient information has been presented to us.

Please clarify whether the civil works boundary will differ from the "development area" as detailed in Figure 10.

Please clarify whether it will be necessary to establish temporary access roads, as part of construction.

In relation to Section 7.1, NGH Environmental states:

*The principle of inter-generational equity requires the present generation to ensure that the sites and diversity of the archaeological record is maintained or enhanced for the benefit of future generations.*

Based on the information presented by NGH Environmental, as well as the absence of a conservation outcome, Warrabing does not agree that the diversity of the archaeological record is not compromised. NGH Environmental has at no point, undertaken and/or considers undertaking additional archaeological investigations in order to increase the known archaeological record of the Project Area to offset that, which will be potentially lost by the undertaking of the proposed development.

Warrabing would like to make it clear that if every developer/project manager were to approach the principle of inter-generational equity the same way, then the archaeological record is being eroded for future generations.

In regards to paragraph 5 on page 39, Warrabing requests that a map be provided in the ACHAR for the proposed location for the relocation of the surface artefacts. NGH Environmental requires consensus amongst the Aboriginal groups for the deposition location of the Aboriginal objects. Please provide.

If the surface artefacts were to be relocated to another surface location rather than buried, what is to stop these artefacts being collected and relocated, repeatedly in

# WARRABINGA

## *Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815



the future? What will NGH do to ensure that the Aboriginal objects remain at their new location in perpetuity?

There are references to an Unexpected Finds Protocol; however, Warrabinga could not find the Unexpected Finds Protocol in the ACHAR. Please include a copy of the Unexpected Finds Protocol in the report.

As the project is a State Significant Development, Warrabinga believes that it is appropriate for a Cultural Heritage Management Plan (CHMP) to be prepared. When can Warrabinga expect to receive a draft CHMP to comment on?

While Warrabinga appreciates the courtesy provided by NGH excluding our comments from the ACHAR, Warrabinga requires that **all** of our comments are included in the ACHAR, and that each of our queries is specifically addressed.

As all Aboriginal heritage is considered sensitive by Warrabinga, we are of the opinion that two (2) versions of the ACHAR should be prepared: one for public exhibition, which has all references to the location of Aboriginal cultural heritage and comments provided by the Aboriginal community redacted, and one version of the report for assessment by the Consent Authority.

Warrabinga is of the opinion that insufficient information has been presented in order for us to provide comment on the proposed development in relation to Aboriginal heritage, as well as the fact that NGH Environmental has not confirmed the likely nature and extent of the Aboriginal sites present within the Project Area. Once the requested information has been provided in an updated ACHAR, we will be able to provide a comment on the proposed development.

It should be noted that this may not be Warrabinga's last response in regards to the documentation provided to-date by NGH Environmental and First Solar; Warrabinga will provide additional responses until such time as we feel that our concerns have been satisfactorily addressed.

Warrabinga would like to remind both NGH Environmental and the Proponent that the DRAFT Aboriginal Cultural Heritage Assessment should not be finalised until **all** comments and concerns raised by the RAPs have been **addressed**.

Should you wish to have a meeting to discuss the issues we have raised please coordinate this with our office via email ([info@warrabinga.com.au](mailto:info@warrabinga.com.au)).

Regards,

7

# WARRABINGA

*Native Title Claimants Aboriginal Corporation*

PO Box 282  
Mudgee NSW 2850  
Office: 02 4627 8622  
Fax: 02 4605 0815

*per Virginia Doig*

Virginia Doig  
Director





6 July 2017

Virginia Doig  
Director  
Warrabinga Native Title  
Claimants Aboriginal Corporation  
PO Box 282  
Mudgee NSW 2850

Email: [info@warrabinga.com.au](mailto:info@warrabinga.com.au)

**canberra**  
unit 8, 27 yallourn st  
(po box 62)  
fyshwick act 2609  
t 02 6280 5053

**bathurst**  
35 morrisset st  
(po box 434)  
bathurst nsw 2795  
t 02 6331 4541

**bega**  
suite 1, 216 carp st  
(po box 470)  
bega nsw 2550  
t 02 6492 8333

**brisbane**  
level 7, 320 adelaide st  
brisbane qld 4000  
t 07 3511 0238

**newcastle**  
7/11 union st  
newcastle west nsw 2302  
t 02 4929 2301

**sydney**  
unit 18, level 3  
21 mary st  
surry hills nsw 2010  
t 02 8202 8333

**wagga wagga**  
suite 1, 39 fitzmaurice st  
(po box 5464)  
wagga wagga nsw 2650  
t 02 6971 9696  
f 02 6971 9693

[nggh@nghenvironmental.com.au](mailto:nggh@nghenvironmental.com.au)  
[www.nghenvironment.com.au](http://www.nghenvironment.com.au)



Dear Virginia,

**RE – 16-337 Beryl Solar Farm Heritage Assessment**

I refer to your letter dated 26 April 2017 regarding the Warrabinga Native Title Claimants Aboriginal Corporation (Warrabinga) response to the draft Aboriginal cultural heritage assessment report for the Beryl Solar Farm. We appreciate the comprehensive nature of your response. This letter responds to your comments.

You raised a large number of points in your correspondence, some of which were technical relating to the conduct of the survey and results, some relating to the terms used by NGH and our assessment and some relating to the Warrabinga interpretation of the results and assessment or significance and recommendations.

We do not intend to address each point in turn but have grouped our response to the key points you raised based on our interpretation of your comments. Some of the issues you raise will be addressed in the revised report but there are a number of points that we don't believe need to be addressed in the report and are therefore providing this letter as a way of answering your comments.

Our response is provided below.

Yours sincerely,

Matthew Barber  
Principal Heritage Consultant  
NGH Environmental

## TECHNICAL SURVEY AND REPORT MATTERS

### *Mapping*

- The project configuration of the project that was supplied with the report was up to date at the time of the report. There has been a very minor change to the internal layout since the report but this does not affect the overall assessment or the survey results. The change relates to a reduction in possible impact area at the very western end of the project area, which was surveyed but removed from the development footprint. The final version of the report shows the detail of proposed layout in Figure 3.
- 1:25,000 topographic maps are not the best standard of map available, GIS based maps with aeriels are now generally included as acceptable and best practice. Our maps (figure 8, 10, 11) include contours that are the same as the 1:25,000 maps and therefore shows the appropriate level of detail.
- We did include soil and landscape maps in the report which are sufficient (Figures 5 and 6).
- Figure 10 does show disturbance areas.
- The site card for AHIMS #36-2-0016 was provided to the RAPs with the project methodology. It was not included in the report due to its lack of information. We do not consider it worthwhile to include in the ACHA.
- In relation to Figure 7 showing the AHIMS sites, a zoomed in map of surrounding sites has now been included (Figure 8) however, it should be noted that some information is provided in the text.
- The extent of the AHIMS search area has now been added to Figure 7 as requested.
- Figure 10 in the draft ACHA report (and now Figure 11) shows the area with water courses, a separate figure with defined ephemeral or permanent water courses is not required.
- Figure 10 in the draft ACHA report (now Figure 11) also shows the location of the sites in relation to the proposed development footprint, which was the best available at the time of report writing. To our knowledge the only change was a reduction in the overall footprint, as noted in point one above. The maps detail the project area and the actual development area. The proposed works for the project will occur within the development area as mapped.
- It is not possible at this stage to identify the exact location where the collected artefacts would be relocated. This would need to be done in consultation with the developer and site construction contractor as well as with agreement from the Aboriginal parties. This wouldn't be possible until the project has been approved and a suitable location identified.

### *Background information*

- Our background section addresses the issue of subsurface testing. No subsurface testing programs have been undertaken within the Beryl area and those from the mining areas to the east are noted and discussed. We don't believe that any further information in relation to the project area is available or warranted.
- The background section (3.2.4) does report on previous archaeological investigations that have occurred east of Gulgong (the mining related projects). We believe that the models mentioned are not generally applicable due to a different landscape.
- Other project archaeological studies have been discussed (3.2.4) but we don't believe a map showing their location is necessary.
- NGH Environmental had been seeking the OzArk report for some time but it was only recently provided to NGH (May 2017) by OzArk. This information has now been included in the background section of the revised report (page 20).
- The references to previous archaeological excavations and landscapes was noted. We examined the locations of the sites suggested (Wilpin Farm and WCP133) and found they related to a surveyor's scar tree (non Aboriginal) and no information on Wilpin Farm was found in AHIMS.

## Survey methodology

- There was no difference in the survey strategy outlined in the methodology to that undertaken in the field with the survey methodology discussed in the field with the participants who all agreed on the approach.
- The survey did cover as much ground as possible. We do not normally include transect data in our reports but have included GPS start and end points in a table in Appendix C of the revised report. It should be noted however, that such points are only indicative as there were more people present during the survey than GPS units.
- The survey concentrated on the area of proposed footprint but included areas outside of this. The maximum area of disturbance was assessed by the fieldwork.
- If any areas not assessed are proposed to be used for the project, further survey and assessment would be undertaken.
- The figure quoted by Warrabinga of an average of 40ha per day survey coverage is well below normal survey coverage. NGH covered approximately 150ha each full day of survey, with all Aboriginal representatives present and in agreement with the transect spacing and coverage pace.
- In relation to the discussion on transects, we noted in the report that the spacing of people along each transect was approximately 20m, as was identified in the methodology, and discussed with people in the field. When we refer to the 5m effective viewing width of each person, we acknowledge that to find stone artefacts, the effective view of a person is 5m either side of them. This assists in our calculation of effective survey coverage, as per standard archaeological practice, we do not suggest that each transect had 100% ground surface viewed. There is no suggestion that the survey coverage was 100% but a realistic figure is provided. This is in line with standard archaeological practice, we do not subscribe to the view of some that such a methodology provides 100% view of the ground. Nor is it feasible for survey participants to be closer together (eg 10m) apart. Nonetheless, the survey coverage was comprehensive and suitable for the project.
- The Code of Practice (OEH 2010) does not require a description of each transect. It does require that transects be identified either by their start and end points or through a tracklog function in a GPS. Our transects were recorded with the latter. We do not generally include this information in our reports but have provided a table of start and end GPS points in Appendix C. Transects were determined by the development footprint, although notes were made about various landform elements.

## Report content

- Table 5 relating to transect coverage in our report provides all of the relevant and necessary data required under the code. The intention of the code is to provide a summary of information and a calculation of effective survey coverage, which table 5 and the supplied information, we would argue does.
- We have now included the datum in Table 6.
- Consideration of erosion relating to the artefact locations. We did consider the issue of subsurface deposits in the field and indeed discussed the potential with the representatives present. We concluded that the artefacts are most likely to be surface finds. We have added this information to the report.
- The sites AS1, IF3 and IF4 are not in locations that are “highly likely” to contain subsurface deposits. We had considered the possible alternatives (low density scatter or knapping site) and suggest that the artefacts represent low density use of the area (see discussion). While low density artefacts can assist in telling the story of Aboriginal occupation and land use, they are not in themselves useful for targeting with subsurface testing (even if there were suitable depth of deposit available).
- Section 4.4 relating to close proximity- we identify the sites as being within 450m of a watercourse.
- Page 33, the discussion on water courses and back country are self-evident. The discussion identifies that the movement of people was most likely concentrated along major water courses but that people also moved across the landscape away from the major waterways, that we call back country.
- Tool manufacture probably did occur on site, evident by the presence of a core and the suggestion is made in the report that other artefacts are likely to occur within the project area. However, this does not mean that an archaeological survey will, or needs to, identify all of those artefacts, this is impossible. There is no

evidence to suggest that subsurface testing would identify cultural material that in essence is likely to be low density and ephemeral. Subsurface testing is used to identify or assess areas where the deposits are able to reveal evidence that can assist in the explanation of Aboriginal occupation. In the instance of the Beryl project area, the archaeological evidence does not support the presence of subsurface deposits to be identified by subsurface testing. Testing is generally only used in locations where concentrations of archaeological material are likely to occur, otherwise digging is unlikely to reveal cultural material owing to the sparse nature of low density sites. The expense and effort involved in subsurface testing needs to be warranted based on the evidence or the impacts to the archaeological record. We don't believe that testing in this area would find either the density or the character of archaeological material that would warrant testing.

- We note that manufacturing of artefacts may have occurred, evidenced by the presence of cores and finished products such as the ground edge axes. This should be tempered by the further observation that even where visibility was good, further artefactual material was not identified, leading to the conclusion that the locality was not a place of highly concentrated activity and flaking events.
- We agree that plough zones are typically the upper 20cm, as a general rule. The soils within the project area were noted as being generally shallow but more importantly there were no landforms with high archaeological potential in combination with subsurface deposits that warranted subsurface testing.
- Statement in relation to grinding grooves in the discussion section has been amended.
- In relation to the basalt outcrops that were identified, the disturbance around these areas was extensive. There is no suggestion that subsurface material would be found around the outcrops for two reasons:
  - o a). there are no subsurface deposits to excavate at the outcrops; and
  - o b). there was no defined topographic or archaeological context in which to test the surrounding areas.
- As mentioned above, subsurface testing is undertaken at locations where topographic or archaeological features suggest there are subsurface deposits. While we agree that artefacts can tell a story, digging in areas of predicted (and surface evidence would suggest proven) low density scatters is unlikely to locate enough archaeological evidence to further the understanding of Aboriginal use of the area. In our experience, there is no justification for undertaking subsurface testing in areas of low density as it is unlikely that artefacts would be found, unless it is undertaken in conjunction with a broader assessment of high density sites, which in this case don't occur within the project area.
- The assessment of the development is that there are a few isolated or small low density artefact scatters present across the project area. It is difficult with such a finding to identify a conservation outcome as Warrabinga have suggested. There were no large sites and no areas of subsurface potential, we believe that the results are a real reflection of the ephemeral and opportunistic Aboriginal use of the area. The conservation outcome that was discussed in the field with the representatives was to collect those artefacts that were recorded (especially the rarer types) so they were preserved. We believe, in light of the findings, this is the most appropriate measure and this was agreed with the Aboriginal representatives during the survey.
- We note that all evidence of Aboriginal occupation is significant to Warrabinga, thank you for the assessment.
- Insertion of a new Figure 3 clarifies the boundaries of the solar arrays works area and the project area.
- In relation to temporary access roads, we have identified that some temporary access road would be required for construction along with a temporary construction office and parking. These are within the footprint of the development area.
- We will include the correspondence from Warrabinga in our final report as requested.

## Recommendations

- An ASIR form will be submitted once the artefacts are collected and placed in a safe location.

- Subsurface testing is not warranted in this area due to shallow soils and low potential for subsurface deposits. We believe that the area, while acknowledging has some potential for additional artefacts to occur (no one ever finds 100% of artefacts), the low-density nature of the finds and the soils would make any subsurface testing program unlikely to find any meaningful archaeological data.
- We also reiterate that the construction method for the solar farm is generally of low impact to the landscape. The activity of driving poles into the ground means there is minimal ground disturbance, no topsoil stripping is required, therefore any archaeological material that may be present would have limited disturbance, mostly limited to the trenching for cables, which in themselves are a narrow trench.
- Relocating the artefacts would be done in consultation with the proponent, their contractor and the Aboriginal groups. It may be preferred to either leave the artefacts on the ground surface or to bury them. Their final location would be identified to the proponent and fencing would be erected to ensure no disturbance during construction and operation. New site cards would also be submitted to OEH.
- A Cultural Heritage Management Plan and would be prepared in consultation with the Aboriginal parties. This has not yet been undertaken as the development approval has not been granted.
- An Unexpected Finds Protocol has been included in the report.

### *General considerations*

- It is noted that Warrabinga have asked that two versions of the report be produced, one for public display with comments by the Aboriginal community and site location details redacted and a second copy for the consent authority with all information. The draft copy that was provided to Warrabinga and the other Aboriginal groups was also included as a draft to the proponent and has gone on public display, as the request from Warrabinga was not received before the public exhibition. The draft did not contain comments from the Aboriginal groups and the sites are unlikely to be disturbed as the land is private property.
- We note that Warrabinga requires the further information and clarification in an updated draft before being able to comment further. We have prepared a revised report but do not believe that all of the points raised need to be addressed in the report. This letter outlines our response to the Warrabinga comments and will be included in the updated report.
- It should also be noted that the other three registered Aboriginal parties for the project had no objections to the survey methodology, the report findings and recommendations, indeed they have advised they were satisfied with the outcome and the results. We would also like to point out that the Warrabinga representative during the survey was satisfied with the survey strategy and recording and made no mention of the subsequent points raised in the letter.
- We believe that the information presented in the draft report, this letter and the revised report is sufficient to make comment on the development proposal and we believe that we have sufficiently characterised the nature of the Aboriginal archaeological material within the project area and likely impacts from the development.

## APPENDIX B AHIMS SEARCH



## AHIMS Web Services (AWS)

Extensive search - Site list report

Your Ref/PO Number : Beryl Solar Farm

Client Service ID : 254143

| SiteID    | SiteName                | Datum                     | Zone                    | Easting | Northing | Context   | Site Status | SiteFeatures                           | SiteTypes      | Reports |
|-----------|-------------------------|---------------------------|-------------------------|---------|----------|-----------|-------------|----------------------------------------|----------------|---------|
| 36-2-0075 | Gooree Vneyards GV1     | AGD                       | 55                      | 734420  | 6409890  | Open site | Valid       | Modified Tree<br>(Carved or Scarred) : | Scarred Tree   | 4434    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Mr.David Maynard        |         |          |           |             |                                        |                |         |
| 36-2-0040 | DM/OC1 - "Pugoon"       | AGD                       | 55                      | 731150  | 6423350  | Open site | Valid       | Artefact : -                           | Open Camp Site |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Stephanie Garling       |         |          |           |             |                                        |                |         |
| 36-3-0135 | CR10;                   | AGD                       | 55                      | 729950  | 6416750  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1236    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Laura-Jane Smith        |         |          |           |             |                                        |                |         |
| 36-3-0136 | CR11;                   | AGD                       | 55                      | 728670  | 6416050  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1236    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Laura-Jane Smith        |         |          |           |             |                                        |                |         |
| 36-3-0137 | CR12;                   | AGD                       | 55                      | 729700  | 6416370  | Open site | Valid       | Stone Quarry : -,<br>Artefact : -      | Quarry         | 1236    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Laura-Jane Smith        |         |          |           |             |                                        |                |         |
| 36-3-0138 | CR13;                   | AGD                       | 55                      | 729920  | 6416610  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1236    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Laura-Jane Smith        |         |          |           |             |                                        |                |         |
| 36-3-0139 | CR8;                    | AGD                       | 55                      | 729950  | 6417050  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1236    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Laura-Jane Smith        |         |          |           |             |                                        |                |         |
| 36-3-0028 | Gulgong;                | AGD                       | 55                      | 741820  | 6411318  | Open site | Valid       | Stone Quarry : -,<br>Artefact : -      | Quarry         | 1299    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Isabel McBryde          |         |          |           |             |                                        |                |         |
| 36-3-0047 | Stubbo Creek 3;         | AGD                       | 55                      | 739276  | 6424042  | Open site | Valid       | Artefact : -                           | Open Camp Site | 234     |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | L Cubis                 |         |          |           |             |                                        |                |         |
| 36-3-0048 | Slapdash Creek 1;       | AGD                       | 55                      | 737542  | 6421727  | Open site | Valid       | Artefact : -                           | Open Camp Site | 234     |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | L Cubis                 |         |          |           |             |                                        |                |         |
| 36-3-0140 | CR9;                    | AGD                       | 55                      | 729800  | 6417100  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1236    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Laura-Jane Smith        |         |          |           |             |                                        |                |         |
| 36-3-0141 | CR7;                    | AGD                       | 55                      | 730150  | 6417050  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1236    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Laura-Jane Smith        |         |          |           |             |                                        |                |         |
| 36-2-0013 | Spring Ridge;           | AGD                       | 55                      | 724971  | 6425674  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1299    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | R Hawkins.Hawkins       |         |          |           |             |                                        |                |         |
| 36-2-0014 | Two Mile Flat;          | AGD                       | 55                      | 725544  | 6416502  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1299    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Moore,R Hawkins.Hawkins |         |          |           |             |                                        |                |         |
| 36-2-0015 | Pugoon;                 | AGD                       | 55                      | 731367  | 6425435  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1299    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | R Hawkins,Hawkins       |         |          |           |             |                                        |                |         |
| 36-2-0016 | Beryl;                  | AGD                       | 55                      | 732922  | 6418057  | Open site | Valid       | Artefact : -                           | Open Camp Site | 1299    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | R Hawkins,Hawkins       |         |          |           |             |                                        |                |         |

Report generated by AHIMS Web Service on 15/11/2016 for Kirsten Bradley for the following area at Lat, Long From : -32.422, 149.3336 - Lat, Long To : -32.2713, 149.5725 with a Buffer of 50 meters. Additional Info : Background for assessment. Number of Aboriginal sites and Aboriginal objects found is 79

This information is not guaranteed to be free from error omission. Office of Environment and Heritage (NSW) and its employees disclaim liability for any act done or omission made on the information and consequences of such acts or omission.



## AHIMS Web Services (AWS)

### Extensive search - Site list report

Your Ref/PO Number : Beryl Solar Farm

Client Service ID : 254143

| SiteID    | SiteName             | Datum | Zone | Easting | Northing | Context   | Site Status | SiteFeatures                                | SiteTypes      | Reports              |
|-----------|----------------------|-------|------|---------|----------|-----------|-------------|---------------------------------------------|----------------|----------------------|
| 36-3-0090 | CR 1                 | AGD   | 55   | 730350  | 6416693  | Open site | Valid       | Artefact : -                                | Open Camp Site | 1125,1504,102<br>800 |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0091 | CR 2                 | AGD   | 55   | 730458  | 6416531  | Open site | Valid       | Artefact : -                                | Open Camp Site | 1125,1504,102<br>800 |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0092 | CR 3;                | AGD   | 55   | 730586  | 6416108  | Open site | Valid       | Artefact : -                                | Open Camp Site | 1125,102800          |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0093 | CR 4;                | AGD   | 55   | 730637  | 6416306  | Open site | Valid       | Artefact : -                                | Open Camp Site | 1125,1504,102<br>800 |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0094 | CR 5;                | AGD   | 55   | 730133  | 6416731  | Open site | Valid       | Artefact : -                                | Open Camp Site | 1125,1504,102<br>800 |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0095 | CR 6;                | AGD   | 55   | 730128  | 6417026  | Open site | Valid       | Artefact : -                                | Open Camp Site | 1125                 |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0145 | Potts Hill site;     | AGD   | 55   | 741570  | 6411650  | Open site | Valid       | Stone Quarry : -,<br>Artefact : -           | Quarry         |                      |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0155 | JOS DAVIS BRIDGE;    | AGD   | 55   | 741590  | 6419720  | Open site | Valid       | Modified Tree<br>(Carved or Scarred) :<br>- | Scarred Tree   | 1333                 |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-3-0233 | WILINDA 1 W1         | AGD   | 55   | 740680  | 6412780  | Open site | Valid       | Modified Tree<br>(Carved or Scarred) :<br>- |                |                      |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-2-0097 | Stony Creek 5 SC5    | AGD   | 55   | 726540  | 6413650  | Open site | Valid       | Artefact : -                                |                |                      |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-2-0098 | Stony Creek 4 SC4    | AGD   | 55   | 726580  | 6414080  | Open site | Valid       | Artefact : -                                |                |                      |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-2-0099 | Stony Creek 3 SC3    | AGD   | 55   | 726480  | 6417070  | Open site | Valid       | Artefact : -                                |                |                      |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-2-0101 | Wialdra Creek 1. WC1 | AGD   | 55   | 731990  | 6419720  | Open site | Valid       | Artefact : -                                |                |                      |
|           | <u>Contact</u>       |       |      |         |          |           |             |                                             |                |                      |
|           | <u>Recorders</u>     |       |      |         |          |           |             |                                             |                |                      |
| 36-2-0104 | YBCR-ST1             | AGD   | 55   | 719670  | 6411642  | Open site | Valid       | Modified Tree<br>(Carved or Scarred) :<br>2 |                | 98915                |

Report generated by AHIMS Web Service on 15/11/2016 for Kirsten Bradley for the following area at Lat, Long From : -32.422, 149.3336 - Lat, Long To : -32.2713, 149.5725 with a Buffer of 50 meters. Additional Info : Background for assessment. Number of Aboriginal sites and Aboriginal objects found is 79

This information is not guaranteed to be free from error omission. Office of Environment and Heritage (NSW) and its employees disclaim liability for any act done or omission made on the information and consequences of such acts or omission.



## AHIMS Web Services (AWS)

### Extensive search - Site list report

Your Ref/PO Number : Beryl Solar Farm

Client Service ID : 254143

| SiteID    | SiteName                                     | Datum            | Zone | Easting                 | Northing | Context   | Site Status | SiteFeatures                                                      | SiteTypes      | Reports                      |
|-----------|----------------------------------------------|------------------|------|-------------------------|----------|-----------|-------------|-------------------------------------------------------------------|----------------|------------------------------|
|           | <u>Contact</u> Murong Gialinga Aboriginal an | <u>Recorders</u> |      | Doctor,Jodie Benton     |          |           |             | <u>Permits</u>                                                    |                |                              |
| 36-2-0105 | YBCR-PAD1                                    | AGD              | 55   | 719560                  | 6412130  | Open site | Valid       | Potential<br>Archaeological<br>Deposit (PAD) : 1                  |                | 98915,99037,9<br>9042,102443 |
|           | <u>Contact</u> Murong Gialinga Aboriginal an | <u>Recorders</u> |      | Doctor,Jodie Benton     |          |           |             | <u>Permits</u>                                                    | 1920,2060,2061 |                              |
| 36-2-0106 | YBCR-OS2 with PAD                            | AGD              | 55   | 719669                  | 6411920  | Open site | Valid       | Potential<br>Archaeological<br>Deposit (PAD) : 1                  |                | 98915,99037,9<br>9042,102443 |
|           | <u>Contact</u> Murong Gialinga Aboriginal an | <u>Recorders</u> |      | Doctor,Jodie Benton     |          |           |             | <u>Permits</u>                                                    | 1920,2060,2061 |                              |
| 36-2-0107 | YBCR-OS1 with Pad                            | AGD              | 55   | 719449                  | 6411791  | Open site | Valid       | Potential<br>Archaeological<br>Deposit (PAD) : -.<br>Artefact : 1 |                | 98915                        |
|           | <u>Contact</u> Murong Gialinga Aboriginal an | <u>Recorders</u> |      | Doctor,Jodie Benton     |          |           |             | <u>Permits</u>                                                    |                |                              |
| 36-2-0102 | Stoney Creek 1                               | AGD              | 55   | 725840                  | 6413200  | Open site | Valid       | Artefact : -                                                      |                |                              |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Mr.David Maynard        |          |           |             | <u>Permits</u>                                                    | 1845           |                              |
| 36-2-0103 | Stoney Creek 2                               | AGD              | 55   | 725840                  | 6413200  | Open site | Valid       | Artefact : -                                                      |                |                              |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Mr.David Maynard        |          |           |             | <u>Permits</u>                                                    |                |                              |
| 36-2-0108 | YBCR-OS3                                     | AGD              | 55   | 719329                  | 6412034  | Open site | Valid       | Artefact : 2                                                      |                | 99038                        |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Doctor,Jodie Benton     |          |           |             | <u>Permits</u>                                                    | 2060,2061      |                              |
| 36-2-0109 | YBCR-OS4                                     | AGD              | 55   | 719355                  | 6412267  | Open site | Valid       | Artefact : 4                                                      |                | 99038                        |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Doctor,Jodie Benton     |          |           |             | <u>Permits</u>                                                    | 2060,2061      |                              |
| 36-2-0119 | BBS; Dubbo LALC; "Makuba Shukran"            | AGD              | 55   | 725433                  | 6425487  | Open site | Valid       | Artefact : 30                                                     |                | 99169                        |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Phil Purcell,Dubbo LALC |          |           |             | <u>Permits</u>                                                    |                |                              |
| 36-2-0112 | BBS; Dubbo LALC; property                    | AGD              | 55   | 724850                  | 6425437  | Open site | Valid       | Artefact : 30                                                     |                | 99169                        |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Leila McAdam,Dubbo LALC |          |           |             | <u>Permits</u>                                                    |                |                              |
| 36-2-0116 | BBS; Dubbo LALC; property 1                  | AGD              | 55   | 725331                  | 6425711  | Open site | Valid       | Artefact : 20                                                     |                | 99169                        |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Phil Purcell,Dubbo LALC |          |           |             | <u>Permits</u>                                                    |                |                              |
| 36-2-0111 | BBS; Dubbo LALC; " Makuba Shuka"             | AGD              | 55   | 725180                  | 6425960  | Open site | Valid       | Artefact : 22                                                     |                | 99169                        |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Phil Purcell,Dubbo LALC |          |           |             | <u>Permits</u>                                                    |                |                              |
| 36-2-0137 | Pig and Wistle Creek 3 (PWC3)                | AGD              | 55   | 733420                  | 6411946  | Open site | Valid       | Artefact : 2                                                      |                |                              |
|           | <u>Contact</u> T Russell                     | <u>Recorders</u> |      | Mr.David Maynard        |          |           |             | <u>Permits</u>                                                    | 3546           |                              |
| 36-2-0138 | Pig and Wistle Creek 2 (PWC2)                | AGD              | 55   | 732820                  | 6411883  | Open site | Valid       | Artefact : -                                                      |                |                              |
|           | <u>Contact</u> T Russell                     | <u>Recorders</u> |      | Mr.David Maynard        |          |           |             | <u>Permits</u>                                                    | 3546           |                              |
| 36-3-0676 | Thornbury AS1                                | AGD              | 55   | 735930                  | 6413490  | Open site | Valid       | Artefact : 2500                                                   |                |                              |
|           | <u>Contact</u>                               | <u>Recorders</u> |      | Mr.John Appleton        |          |           |             | <u>Permits</u>                                                    |                |                              |

Report generated by AHIMS Web Service on 15/11/2016 for Kirsten Bradley for the following area at Lat, Long From : -32.422, 149.3336 - Lat, Long To : -32.2713, 149.5725 with a Buffer of 50 meters. Additional Info : Background for assessment. Number of Aboriginal sites and Aboriginal objects found is 79  
This information is not guaranteed to be free from error omission. Office of Environment and Heritage (NSW) and its employees disclaim liability for any act done or omission made on the information and consequences of such acts or omission.



## AHIMS Web Services (AWS)

### Extensive search - Site list report

Your Ref/PO Number : Beryl Solar Farm

Client Service ID : 254143

| SiteID    | SiteName                | Datum                     | Zone                                                                            | Easting | Northing | Context   | Site Status | SiteFeatures                                                                          | SiteTypes    | Reports |
|-----------|-------------------------|---------------------------|---------------------------------------------------------------------------------|---------|----------|-----------|-------------|---------------------------------------------------------------------------------------|--------------|---------|
| 36-2-0140 | WC IF 1                 | AGD                       | 55                                                                              | 730960  | 6419061  | Open site | Valid       | Artefact : 1                                                                          |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Mr.David Maynard,Murong Gialinga Aboriginal and Torres Strait Islander Corporat |         |          |           |             |                                                                                       |              |         |
| 36-3-0674 | Magpie AS1              | AGD                       | 55                                                                              | 738200  | 6410120  | Open site | Valid       | Artefact : 50                                                                         |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Mr.John Appleton                                                                |         |          |           |             |                                                                                       |              |         |
| 36-3-0675 | Magpie AS2              | AGD                       | 55                                                                              | 738180  | 6409980  | Open site | Valid       | Artefact : 20                                                                         |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Fred Appleton                                                                   |         |          |           |             |                                                                                       |              |         |
| 36-2-0076 | Goore Vineyards GV2     | AGD                       | 55                                                                              | 734330  | 6409840  | Open site | Valid       | Modified Tree<br>(Carved or Scarred) :<br>-                                           | Scarred Tree | 4434    |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Mr.David Maynard                                                                |         |          |           |             |                                                                                       |              |         |
| 36-2-0288 | SAC 48                  | GDA                       | 55                                                                              | 721529  | 6415418  | Open site | Valid       | Artefact : 1                                                                          |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0272 | Grinding Groove 16      | GDA                       | 55                                                                              | 721073  | 6416624  | Open site | Valid       | Grinding Groove : 1                                                                   |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0274 | IF 14                   | GDA                       | 55                                                                              | 720886  | 6425987  | Open site | Valid       | Artefact : 1                                                                          |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0275 | IF 15                   | GDA                       | 55                                                                              | 720319  | 6425539  | Open site | Valid       | Artefact : 1                                                                          |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0276 | IF 16                   | GDA                       | 55                                                                              | 720412  | 6424701  | Open site | Valid       | Artefact : 1                                                                          |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0277 | IF 17                   | GDA                       | 55                                                                              | 720013  | 6423366  | Open site | Valid       | Artefact : 1                                                                          |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0278 | IF 18                   | GDA                       | 55                                                                              | 720129  | 6422149  | Open site | Valid       | Artefact : 1                                                                          |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0279 | SAC 39                  | GDA                       | 55                                                                              | 720289  | 6424996  | Open site | Valid       | Art (Pigment or<br>Engraved) : 1,<br>Potential<br>Archaeological<br>Deposit (PAD) : - |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0280 | SAC 40                  | GDA                       | 55                                                                              | 720242  | 6424682  | Open site | Valid       | Artefact : 1, Potential<br>Archaeological<br>Deposit (PAD) : -                        |              |         |
|           | <a href="#">Contact</a> | <a href="#">Recorders</a> | Doctor.Tim Owen                                                                 |         |          |           |             |                                                                                       |              |         |
| 36-2-0281 | SAC 41                  | GDA                       | 55                                                                              | 720045  | 6423564  | Open site | Valid       | Artefact : 1, Potential<br>Archaeological<br>Deposit (PAD) : -                        |              |         |

Report generated by AHIMS Web Service on 15/11/2016 for Kirsten Bradley for the following area at Lat, Long From : -32.422, 149.3336 - Lat, Long To : -32.2713, 149.5725 with a Buffer of 50 meters. Additional Info : Background for assessment. Number of Aboriginal sites and Aboriginal objects found is 79

This information is not guaranteed to be free from error omission. Office of Environment and Heritage (NSW) and its employees disclaim liability for any act done or omission made on the information and consequences of such acts or omission.



| SiteID    | SiteName                           | Datum            | Zone           | Easting | Northing | Context   | Site Status | SiteFeatures                                                | SiteTypes | Reports |
|-----------|------------------------------------|------------------|----------------|---------|----------|-----------|-------------|-------------------------------------------------------------|-----------|---------|
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0282 | SAC 42                             | GDA              | 55             | 720023  | 6423137  | Open site | Valid       | Artefact : 1, Potential Archaeological<br>Deposit (PAD) : - |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0284 | SAC 44                             | GDA              | 55             | 720151  | 6418448  | Open site | Valid       | Artefact : 1, Potential Archaeological<br>Deposit (PAD) : - |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0285 | SAC 45                             | GDA              | 55             | 721039  | 6416749  | Open site | Valid       | Artefact : 1, Potential Archaeological<br>Deposit (PAD) : - |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0286 | SAC 46                             | GDA              | 55             | 721034  | 6416565  | Open site | Valid       | Artefact : 1, Potential Archaeological<br>Deposit (PAD) : - |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0287 | SAC 47                             | GDA              | 55             | 721362  | 6415584  | Open site | Valid       | Artefact : 1, Potential Archaeological<br>Deposit (PAD) : - |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0312 | Lower Piambong Rd ( LP39)          | GDA              | 55             | 723357  | 6410334  | Open site | Valid       | Artefact : 27                                               |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0313 | Lower Piambong Rd ( LP40)          | GDA              | 55             | 723482  | 6410757  | Open site | Valid       | Artefact : 77                                               |           | 3336    |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0314 | Lower Piambong Rd ( LP41)          | GDA              | 55             | 723304  | 6411232  | Open site | Valid       | Artefact : 11                                               |           | 3336    |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0320 | Hughes Road Lower Piambong Road IA | AGD              | 55             | 723738  | 6410500  | Open site | Valid       | Artefact : 2                                                |           | 102331  |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-3-2582 | Castlereagh Hwy Scarred Tree 1     | GDA              | 55             | 737405  | 6410456  | Open site | Valid       | Modified Tree<br>(Carved or Scarred) :<br>-                 |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-3-2595 | Magpie Lane IFML1                  | GDA              | 55             | 737462  | 6410892  | Open site | Valid       | Artefact : 1                                                |           | 102441  |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0370 | CBR - OS - 32                      | GDA              | 55             | 720461  | 6426794  | Open site | Valid       | Artefact : 1                                                |           |         |
|           | <u>Contact</u>                     | <u>Recorders</u> | <u>Permits</u> |         |          |           |             |                                                             |           |         |
| 36-2-0389 | CBR - OS - 25                      | GDA              | 55             | 721554  | 6415264  | Open site | Valid       | Artefact : 1                                                |           |         |

Report generated by AHIMS Web Service on 15/11/2016 for Kirsten Bradley for the following area at Lat, Long From : -32.422, 149.3336 - Lat, Long To : -32.2713, 149.5725 with a Buffer of 50 meters. Additional Info : Background for assessment. Number of Aboriginal sites and Aboriginal objects found is 79

This information is not guaranteed to be free from error omission. Office of Environment and Heritage (NSW) and its employees disclaim liability for any act done or omission made on the information and consequences of such acts or omission.



## AHIMS Web Services (AWS)

### Extensive search - Site list report

Your Ref/PO Number : Beryl Solar Farm

Client Service ID : 254143

| SiteID    | SiteName                                                             | Datum                     | Zone | Easting                                          | Northing | Context   | Site Status | SiteFeatures            | SiteTypes | Reports |
|-----------|----------------------------------------------------------------------|---------------------------|------|--------------------------------------------------|----------|-----------|-------------|-------------------------|-----------|---------|
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Mr.Neville Baker                                 |          |           |             | <a href="#">Permits</a> |           |         |
| 36-2-0390 | CBR - OS - 24                                                        | GDA                       | 55   | 721400                                           | 6414920  | Open site | Valid       | Artefact : 1            |           |         |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Mr.Neville Baker                                 |          |           |             | <a href="#">Permits</a> |           |         |
| 36-2-0391 | CBR - OS - 23                                                        | GDA                       | 55   | 721220                                           | 6414610  | Open site | Valid       | Artefact : 1            |           |         |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Mr.Neville Baker                                 |          |           |             | <a href="#">Permits</a> |           |         |
| 36-2-0392 | CBR - OS - 22                                                        | GDA                       | 55   | 721134                                           | 6414455  | Open site | Valid       | Artefact : 1            |           |         |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Mr.Neville Baker                                 |          |           |             | <a href="#">Permits</a> |           |         |
| 36-2-0331 | Restriction applied. Please contact<br>ahims@environment.nsw.gov.au. |                           |      |                                                  |          | Open site | Valid       |                         |           | 102448  |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Miss.Christine Maynard                           |          |           |             | <a href="#">Permits</a> | 3478      |         |
| 36-2-0332 | GRG-2                                                                | GDA                       | 55   | 724088                                           | 6412963  | Open site | Valid       | Artefact : -            |           | 102448  |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Miss.Christine Maynard                           |          |           |             | <a href="#">Permits</a> | 3478      |         |
| 36-2-0333 | GRG-3                                                                | GDA                       | 55   | 724296                                           | 6413664  | Open site | Valid       | Artefact : -            |           | 102448  |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Miss.Christine Maynard                           |          |           |             | <a href="#">Permits</a> | 3478      |         |
| 36-2-0334 | GRG-4                                                                | GDA                       | 55   | 725154                                           | 6413927  | Open site | Valid       | Artefact : 1            |           | 102448  |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Miss.Christine Maynard                           |          |           |             | <a href="#">Permits</a> | 3478      |         |
| 36-3-3091 | Old Barney's AFT 1                                                   | GDA                       | 55   | 738486                                           | 6420460  | Open site | Valid       | Artefact : -            |           |         |
|           | <a href="#">Contact</a>                                              | <a href="#">Recorders</a> |      | Niche Environment and Heritage,Ms.Clare Anderson |          |           |             | <a href="#">Permits</a> |           |         |

Report generated by AHIMS Web Service on 15/11/2016 for Kirsten Bradley for the following area at Lat, Long From : -32.422, 149.3336 - Lat, Long To : -32.2713, 149.5725 with a Buffer of 50 meters. Additional Info : Background for assessment. Number of Aboriginal sites and Aboriginal objects found is 79

This information is not guaranteed to be free from error omission. Office of Environment and Heritage (NSW) and its employees disclaim liability for any act done or omission made on the information and consequences of such acts or omission.

## APPENDIX C   TRANSECT DATA

| <b>Transect #</b> | <b>Start Location<br/>Easting/Northing<br/>(GDA 94 Zone 55)</b> | <b>Finish Location<br/>Easting/Northing<br/>(GDA 94 Zone 55)</b> | <b>Transect #</b> | <b>Start Location<br/>Easting/Northing<br/>(GDA 94 Zone 55)</b> | <b>Finish Location<br/>Easting/Northing<br/>(GDA 94 Zone 55)</b> |
|-------------------|-----------------------------------------------------------------|------------------------------------------------------------------|-------------------|-----------------------------------------------------------------|------------------------------------------------------------------|
| <b>1</b>          | 734319<br>6417232                                               | 734406<br>6417855                                                | <b>26</b>         | 731526<br>6417641                                               | 731630<br>6417891                                                |
| <b>2</b>          | 734240<br>6417898                                               | 734237<br>6417222                                                | <b>27</b>         | 731630<br>6417891                                               | 732211<br>6417556                                                |
| <b>3</b>          | 734140<br>6417218                                               | 734135<br>6417912                                                | <b>27</b>         | 732204<br>6417504                                               | 731670<br>6417715                                                |
| <b>4</b>          | 734040<br>6417934                                               | 734037<br>6417218                                                | <b>28</b>         | 731496<br>6418375                                               | 731139<br>6418420                                                |
| <b>5</b>          | 733937<br>6417216                                               | 733988<br>6417943                                                | <b>29</b>         | 731132<br>6418342                                               | 731448<br>6418276                                                |
| <b>6</b>          | 733881<br>6417487                                               | 732918<br>6417675                                                | <b>30</b>         | 731658<br>6418101                                               | 731091<br>6418255                                                |
| <b>7</b>          | 732874<br>6417587                                               | 733863<br>6417390                                                | <b>31</b>         | 731074<br>6418143                                               | 731640<br>6418006                                                |
| <b>8</b>          | 733863<br>6417301                                               | 732849<br>6417503                                                | <b>32</b>         | 731633<br>6417917                                               | 731043<br>6417992                                                |
| <b>9</b>          | 732828<br>6417418                                               | 733844<br>6417216                                                | <b>33</b>         | 731345<br>6417909                                               | 730407<br>6418099                                                |
| <b>10</b>         | 732770<br>6417352                                               | 734128<br>6417183                                                | <b>34</b>         | 730355<br>6418065                                               | 731335<br>6417787                                                |
| <b>11</b>         | 734174<br>6417106                                               | 732756<br>6417274                                                | <b>35</b>         | 731463<br>6417570                                               | 730989<br>6417662                                                |
| <b>12</b>         | 732742<br>6417195                                               | 734228<br>6416976                                                | <b>36</b>         | 730978<br>6417623                                               | 731291<br>6417486                                                |
| <b>13</b>         | 734263<br>6416850                                               | 732727<br>6417105                                                | <b>37</b>         | 731463<br>6417570                                               | 731343<br>6417331                                                |
| <b>14</b>         | 732709<br>6417010                                               | 734259<br>6416733                                                | <b>38</b>         | 731454<br>6417262                                               | 731581<br>6417591                                                |
| <b>15</b>         | 734239<br>6416627                                               | 732685<br>6416876                                                | <b>39</b>         | 731652<br>6417557                                               | 732221<br>6417445                                                |
| <b>16</b>         | 732811<br>6417414                                               | 732860<br>6417674                                                | <b>40</b>         | 732221<br>6417445                                               | 732171<br>6416977                                                |
| <b>17</b>         | 732860<br>6417674                                               | 732351<br>6417769                                                | <b>41</b>         | 732171<br>6416977                                               | 731821<br>6417119                                                |
| <b>18</b>         | 732318<br>6417663                                               | 732771<br>6417603                                                | <b>42</b>         | 731821<br>6417119                                               | 732106<br>6417081                                                |
| <b>19</b>         | 732749<br>6417516                                               | 732303<br>6417570                                                | <b>43</b>         | 732106<br>6417081                                               | 732136<br>6417313                                                |
| <b>20</b>         | 732286<br>6417488                                               | 732735<br>6417432                                                | <b>44</b>         | 732136<br>6417313                                               | 732000<br>6417327                                                |
| <b>21</b>         | 732750<br>6417426                                               | 732720<br>6417229                                                | <b>45</b>         | 732000<br>6417327                                               | 731939<br>6417154                                                |
| <b>22</b>         | 732602<br>6417233                                               | 732628<br>6417391                                                | <b>46</b>         | 731939<br>6417154                                               | 731838<br>6417169                                                |
| <b>23</b>         | 732501<br>6417420                                               | 732445<br>6416999                                                | <b>47</b>         | 731838<br>6417169                                               | 731864<br>6417383                                                |
| <b>24</b>         | 732351<br>6417017                                               | 732398<br>6417439                                                | <b>48</b>         | 731864<br>6417383                                               | 731836<br>6417295                                                |
| <b>25</b>         | 732295<br>6417481                                               | 732245<br>6416963                                                | <b>49</b>         | 731836<br>6417295                                               | 731666<br>6417376                                                |

| Transect # | Start Location Easting/Northing (GDA 94 Zone 55) | Finish Location Easting/Northing (GDA 94 Zone 55) | Transect # | Start Location Easting/Northing (GDA 94 Zone 55) | Finish Location Easting/Northing (GDA 94 Zone 55) |
|------------|--------------------------------------------------|---------------------------------------------------|------------|--------------------------------------------------|---------------------------------------------------|
| 50         | 731666<br>6417376                                | 731648<br>6417584                                 | 52         | 730643<br>6417927                                | 730844<br>6418011                                 |
| 51         | 732560<br>6417095                                | 732482<br>6416998                                 |            |                                                  |                                                   |

## APPENDIX D SITE CARDS



## Aboriginal Site Recording Form

AHIMS Registrar  
PO Box 1967, Hurstville 2220 NSW

AHIMS site ID: 36-Z-0469

Date recorded: 15-03-2017

### Site Location Information

Site name: Beryl Solar Farm AS1

Easting: 731174 Northing: 6418420 Coordinates must be in GDA (MGA)

Horizontal Accuracy (m): 5

Zone: 55 Location method: Non-Differential GPS

### Recorder Information

(The person responsible for the completion and submission of this form)

Title Surname First name

Mr Barber Matthew

Organisation: 75

Address: Po Box 62 Fyshwick ACT 2609

Phone: 0407485018 E-mail: matthew.b@ngHENvironmental.com.au

### Site Context Information

Land Form Pattern: Undulating Plain

Land Form Unit: Flat

Vegetation: Cleared

Distance to Water (m): 230

Primary Report: NGH Environmental 2017 Aboriginal Cultural Heritage Assessment- Beryl Solar Farm

How to get to the site: on private property at Beryl accessed off either Beryl Road or Perseverance Lane

open/closed site:

|                        |           |
|------------------------|-----------|
| <b>Site condition:</b> | Disturbed |
|------------------------|-----------|

1. Artefact

Number of features

Length of  
feature(s)  
extent (n

Width of  
feature (s)  
extent (m)

This site consisted of two artefacts approximately 5m apart from each other on the lower basal slope of a ploughed and cleared paddock. The artefacts were a flake and broken flake of quartz. 1 flake quartz. Dimensions (mm) 20 x 12 x 5. 1 broken flake quartz. Dimensions (mm) 20 x 12 x 5.

2. \_\_\_\_\_

Number of features

Length of  
feature(s)  
extent (m)

Width of  
feature (s)  
extent (m)

\_\_\_\_\_

| Scar Depth<br>(cm)                                                                    | Regrowth<br>(cm)                                                                      | Scar Length<br>(cm)                                                                   | Scar Width<br>(cm)                                                                    |
|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
|  |  |  |  |
| Scar shape                                                                            | Tree Species                                                                          |                                                                                       |                                                                                       |

| Scar Depth<br>(cm)                                                                    | Regrowth<br>(cm)                                                                      | Scar Length<br>(cm)                                                                   | Scar Width<br>(cm)                                                                    |
|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
|  |  |  |  |
| Scar shape                                                                            | Tree Species                                                                          |                                                                                       |                                                                                       |

|                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|------------------|---------------------|--------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|---------------|-----------------|--|--|
| <b>Features:</b>                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                          | Number of<br>features                                                   | Length of<br>feature(s)<br>extent (m)                                   | Width of<br>feature (s)<br>extent (m)                                   | <div style="text-align: center; font-weight: bold; font-size: small;">Scarred Trees</div> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Depth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Regrowth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Length<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> </tr> <tr> <td style="text-align: center; font-size: x-small;">Scar<br/>shape</td> <td colspan="2" style="text-align: center; font-size: x-small;">Tree<br/>Species</td> <td></td> </tr> </table> | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | Scar<br>shape | Tree<br>Species |  |  |
| Scar Depth<br>(cm)                                                                                                                                                                                                                                                                                                                                                                                               | Regrowth<br>(cm)                                                         | Scar Length<br>(cm)                                                     | Scar Width<br>(cm)                                                      |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| <div style="border: 1px solid black; width: 30px; height: 30px;"></div>                                                                                                                                                                                                                                                                                                                                          | <div style="border: 1px solid black; width: 30px; height: 30px;"></div>  | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| Scar<br>shape                                                                                                                                                                                                                                                                                                                                                                                                    | Tree<br>Species                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| 3.                                                                                                                                                                                                                                                                                                                                                                                                               | <div style="border: 1px solid black; width: 250px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| Description:                                                                                                                                                                                                                                                                                                                                                                                                     |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
|                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| <b>Features:</b>                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                          | Number of<br>features                                                   | Length of<br>feature(s)<br>extent (m)                                   | Width of<br>feature (s)<br>extent (m)                                   | <div style="text-align: center; font-weight: bold; font-size: small;">Scarred Trees</div> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Depth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Regrowth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Length<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> </tr> <tr> <td style="text-align: center; font-size: x-small;">Scar<br/>shape</td> <td colspan="2" style="text-align: center; font-size: x-small;">Tree<br/>Species</td> <td></td> </tr> </table> | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | Scar<br>shape | Tree<br>Species |  |  |
| Scar Depth<br>(cm)                                                                                                                                                                                                                                                                                                                                                                                               | Regrowth<br>(cm)                                                         | Scar Length<br>(cm)                                                     | Scar Width<br>(cm)                                                      |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| <div style="border: 1px solid black; width: 30px; height: 30px;"></div>                                                                                                                                                                                                                                                                                                                                          | <div style="border: 1px solid black; width: 30px; height: 30px;"></div>  | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| Scar<br>shape                                                                                                                                                                                                                                                                                                                                                                                                    | Tree<br>Species                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| 4.                                                                                                                                                                                                                                                                                                                                                                                                               | <div style="border: 1px solid black; width: 250px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| Description:                                                                                                                                                                                                                                                                                                                                                                                                     |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
|                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| <b>Features:</b>                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                          | Number of<br>features                                                   | Length of<br>feature(s)<br>extent (m)                                   | Width of<br>feature (s)<br>extent (m)                                   | <div style="text-align: center; font-weight: bold; font-size: small;">Scarred Trees</div> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Depth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Regrowth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Length<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> <td style="text-align: center;"><div style="border: 1px solid black; width: 30px; height: 30px;"></div></td> </tr> <tr> <td style="text-align: center; font-size: x-small;">Scar<br/>shape</td> <td colspan="2" style="text-align: center; font-size: x-small;">Tree<br/>Species</td> <td></td> </tr> </table> | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | Scar<br>shape | Tree<br>Species |  |  |
| Scar Depth<br>(cm)                                                                                                                                                                                                                                                                                                                                                                                               | Regrowth<br>(cm)                                                         | Scar Length<br>(cm)                                                     | Scar Width<br>(cm)                                                      |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| <div style="border: 1px solid black; width: 30px; height: 30px;"></div>                                                                                                                                                                                                                                                                                                                                          | <div style="border: 1px solid black; width: 30px; height: 30px;"></div>  | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> | <div style="border: 1px solid black; width: 30px; height: 30px;"></div> |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| Scar<br>shape                                                                                                                                                                                                                                                                                                                                                                                                    | Tree<br>Species                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| 5.                                                                                                                                                                                                                                                                                                                                                                                                               | <div style="border: 1px solid black; width: 250px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> | <div style="border: 1px solid black; width: 20px; height: 20px;"></div> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| Description:                                                                                                                                                                                                                                                                                                                                                                                                     |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
|                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |
| <div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="width: 15%;">Other Site Info:</div> <div style="width: 85%; border: 1px solid black; padding: 5px; font-size: x-small;">             Location of artefacts T31112/0415411 and T31114/0415420. The area was noted to be disturbed with broken pieces of house bottles scattered nearby.           </div> </div> |                                                                          |                                                                         |                                                                         |                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |                  |                     |                    |                                                                         |                                                                         |                                                                         |                                                                         |               |                 |  |  |

**Site plan**

3

## Site photographs



Description: View east, poles show artefact locations



Description: Close up of quartz broken flake from Beryl Solar Farm AS1



Description: View west, pole shows artefact location



Description: Close up of quartz flake from Beryl Solar Farm AS1

## Site restrictions

Do you want to Restrict this site?:

Restriction type: Gender  General  Location

Why is this site restricted?:

## Further information contact

Title  Surname  First name   
 Organisation:   
 Address:   
 Phone:  E-mail:



## Aboriginal Site Recording Form

AHIMS Registrar  
PO Box 1967, Hurstville 2220 NSW

AHIMS site ID: 36-2-0470

Date recorded: 15-03-2017

### Site Location Information

Site name: Beryl Solar Farm (F 4)

Easting: 731214 Northing: 6418411 Coordinates must be in GDA (MGA)

Horizontal Accuracy (m): 5

Zone: 56 Location method: Non-Differential GPS

### Recorder Information

(The person responsible for the completion and submission of this form)

Title Surname First name

Mr. Barber Matthew

Organisation: 75

Address: Po Box 62 Fyshwick ACT 2609

Phone: 0407485018 E-mail: matthew.b@ngHENvironmental.com.au

### Site Context Information

Land Form Pattern: Undulating Plain

Land Form Unit: Flat


Vegetation: Cleared

Distance to Water (m): 250

Primary Report: NGH Environmental 2017 Aboriginal Cultural Heritage Assessment: Beryl Solar Farm

How to get to the site: on private property at Beryl accessed off either Beryl Road or Perseverance Lane

## Site location map



## Site contents information

open/closed site:

Site condition:

### Features:

| Number of features | Length of feature(s) extent (m) | Width of feature (s) extent (m) |
|--------------------|---------------------------------|---------------------------------|
| 1.                 |                                 |                                 |

### Description:

This site consisted of a single artefact on the lower basal slope of a ploughed and cleared paddock. The artefact was an edge-ground axe manufactured from a volcanic material with some anvil damage. The axe had split in half. Dimensions (mm) 80 x 58 x 18

### Scarred Trees

| Scar Depth (cm) | Regrowth (cm) | Scar Length (cm) | Scar Width (cm) |
|-----------------|---------------|------------------|-----------------|
|                 |               |                  |                 |

Scar shape  Tree Species

### Features:

| Number of features | Length of feature(s) extent (m) | Width of feature (s) extent (m) |
|--------------------|---------------------------------|---------------------------------|
| 2.                 |                                 |                                 |

### Description:

|                  |  |                                                                         |                                                                         |                                                                         |                    |                                                                         |                     |                                                                         |
|------------------|--|-------------------------------------------------------------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|--------------------|-------------------------------------------------------------------------|---------------------|-------------------------------------------------------------------------|
| <b>Features:</b> |  | Number of<br>features                                                   | Length of<br>feature(s)<br>extent (m)                                   | Width of<br>feature (s)<br>extent (m)                                   | Scarred Trees      |                                                                         |                     |                                                                         |
| 3.               |  | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | Scar Depth<br>(cm) | Regrowth<br>(cm)                                                        | Scar Length<br>(cm) | Scar Width<br>(cm)                                                      |
| Description:     |  |                                                                         |                                                                         |                                                                         | Scar<br>shape      | <div style="width: 40px; height: 20px; border: 1px solid black;"></div> | Tree<br>Species     | <div style="width: 40px; height: 20px; border: 1px solid black;"></div> |
|                  |  |                                                                         |                                                                         |                                                                         |                    |                                                                         |                     |                                                                         |

|                  |  |                                                                         |                                                                         |                                                                         |                    |                                                                         |                     |                                                                         |
|------------------|--|-------------------------------------------------------------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|--------------------|-------------------------------------------------------------------------|---------------------|-------------------------------------------------------------------------|
| <b>Features:</b> |  | Number of<br>features                                                   | Length of<br>feature(s)<br>extent (m)                                   | Width of<br>feature (s)<br>extent (m)                                   | Scarred Trees      |                                                                         |                     |                                                                         |
| 4.               |  | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | Scar Depth<br>(cm) | Regrowth<br>(cm)                                                        | Scar Length<br>(cm) | Scar Width<br>(cm)                                                      |
| Description:     |  |                                                                         |                                                                         |                                                                         | Scar<br>shape      | <div style="width: 40px; height: 20px; border: 1px solid black;"></div> | Tree<br>Species     | <div style="width: 40px; height: 20px; border: 1px solid black;"></div> |
|                  |  |                                                                         |                                                                         |                                                                         |                    |                                                                         |                     |                                                                         |

|                  |  |                                                                         |                                                                         |                                                                         |                    |                                                                         |                     |                                                                         |
|------------------|--|-------------------------------------------------------------------------|-------------------------------------------------------------------------|-------------------------------------------------------------------------|--------------------|-------------------------------------------------------------------------|---------------------|-------------------------------------------------------------------------|
| <b>Features:</b> |  | Number of<br>features                                                   | Length of<br>feature(s)<br>extent (m)                                   | Width of<br>feature (s)<br>extent (m)                                   | Scarred Trees      |                                                                         |                     |                                                                         |
| 5.               |  | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | <div style="width: 20px; height: 20px; border: 1px solid black;"></div> | Scar Depth<br>(cm) | Regrowth<br>(cm)                                                        | Scar Length<br>(cm) | Scar Width<br>(cm)                                                      |
| Description:     |  |                                                                         |                                                                         |                                                                         | Scar<br>shape      | <div style="width: 40px; height: 20px; border: 1px solid black;"></div> | Tree<br>Species     | <div style="width: 40px; height: 20px; border: 1px solid black;"></div> |
|                  |  |                                                                         |                                                                         |                                                                         |                    |                                                                         |                     |                                                                         |

Other Site Info:

**Site plan**

3

## Site photographs



Description: View east, pole shows artefact location.

|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |

Description:



Description: Close up of Beryl Solar Farm IF 4.

|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |

Description:

## Site restrictions

Do you want to  
Restrict this site?:

Restriction type:

Why is this site restricted?:

## Further information contact

|                      |                      |                              |
|----------------------|----------------------|------------------------------|
| Title                | Surname              | First name                   |
| <input type="text"/> | <input type="text"/> | <input type="text"/>         |
| Organisation:        | <input type="text"/> |                              |
| Address:             | <input type="text"/> |                              |
| Phone:               | <input type="text"/> | E-mail: <input type="text"/> |

4



## Aboriginal Site Recording Form

AHIMS Registrar  
PO Box 1967, Hurstville 2220 NSW

AHIMS site ID: 36-2-0471

Date recorded: 15-03-2017

### Site Location Information

Site name: Beryl Solar Farm IF 3

Easting: 731385 Northing: 6418330 Coordinates must be in GDA (MGA)

Horizontal Accuracy (m): 5

Zone: 55 Location method: Non-Differential GPS

### Recorder Information

(The person responsible for the completion and submission of this form)

Title Surname First name

Mr Barber Matthew

Organisation: 75

Address: Po Box 62 Fyshwick ACT 2609

Phone: 0407485018 E-mail: matthew.b@ngHENvironmental.com.au

### Site Context Information

Land Form Pattern: Undulating Plain

Land Form Unit: Flat

Vegetation: Cleared

Distance to Water (m): 350

Primary Report: NGH Environmental 2017 Aboriginal Cultural Heritage Assessment: Beryl Solar Farm

How to get to the site: on private property at Beryl accessed off either Beryl Road or Perseverance Lane

**Location of recorded sites**

**Beryl Solar Farm**

- Artefact Scatter
- Stone Artefacts
- Project\_area
- Development\_area
- Solar\_arrays\_and\_cables

**Notes:**

- Data collected by rgh environmental (2016)
- Ordnance Survey of Great Britain, copyright 2014
- Aerial map Copyright © Esri and DeLorme Australia
- License: OSM, SA, CC-BY

**Scale:**

0 100 200 300 400 500 600 700 800 900 1000

**Map Information:**

- A4 © 1:25000
- Ref: Beryl Solar Farm
- Author: K. Bradley
- Date Created: 14/03/2017

**Logos:**

- rgh environmental
- North Arrow

|                 |           |
|-----------------|-----------|
| Site condition: | Disturbed |
|-----------------|-----------|

|    |          |
|----|----------|
| 1. | Artefact |
|----|----------|



|   |  |
|---|--|
| 1 |  |
|---|--|



This site consisted of a single artefact on the gentle basal slope of a ploughed cleared paddock. The artefact was a multi-platform core of quartz. Two platforms and four negative scars were recorded with the artefact noted to have 80% riverine cortex. Dimensions (mm) 35 x 81 x 60

| Scar Depth<br>(cm)                                                                    | Regrowth<br>(cm)                                                                      | Scar Length<br>(cm)                                                                   | Scar Width<br>(cm)                                                                    |
|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
|  |  |  |  |
| Scar shape                                                                            | Tree Species                                                                          |                                                                                       |                                                                                       |

Scar  
shapeTree  
Species

2.



|  |  |
|--|--|
|  |  |
|--|--|

\_\_\_\_\_


| Scar Depth<br>(cm)                                                                               | Regrowth<br>(cm)                                                                                   | Scar Length<br>(cm)                                                                   | Scar Width<br>(cm)                                                                    |
|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
|             |               |  |  |
| Scar shape  | Tree Species  |                                                                                       |                                                                                       |

Scar  
shape

Tree Species

| <b>Features:</b>                                            |                                            | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="4" style="text-align: center;">Scarred Trees</th> </tr> <tr> <td style="text-align: center;">Scar Depth<br/>(cm)</td> <td style="text-align: center;">Regrowth<br/>(cm)</td> <td style="text-align: center;">Scar Length<br/>(cm)</td> <td style="text-align: center;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> </tr> <tr> <td style="text-align: center;">Scar<br/>shape</td> <td colspan="2" style="text-align: center;">Tree<br/>Species</td> <td style="text-align: center;"><input type="text"/></td> </tr> </table> | Scarred Trees |  |  |  | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | Scar<br>shape | Tree<br>Species |  | <input type="text"/> |
|-------------------------------------------------------------|--------------------------------------------|-------------------------------------------|-------------------------------------------|-------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|--|--|--|--------------------|------------------|---------------------|--------------------|----------------------|----------------------|----------------------|----------------------|---------------|-----------------|--|----------------------|
| Scarred Trees                                               |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar Depth<br>(cm)                                          | Regrowth<br>(cm)                           | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <input type="text"/>                                        | <input type="text"/>                       | <input type="text"/>                      | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar<br>shape                                               | Tree<br>Species                            |                                           | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| 3.                                                          | <input style="width: 150px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Description:                                                |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
|                                                             |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <b>Features:</b>                                            |                                            | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="4" style="text-align: center;">Scarred Trees</th> </tr> <tr> <td style="text-align: center;">Scar Depth<br/>(cm)</td> <td style="text-align: center;">Regrowth<br/>(cm)</td> <td style="text-align: center;">Scar Length<br/>(cm)</td> <td style="text-align: center;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> </tr> <tr> <td style="text-align: center;">Scar<br/>shape</td> <td colspan="2" style="text-align: center;">Tree<br/>Species</td> <td style="text-align: center;"><input type="text"/></td> </tr> </table> | Scarred Trees |  |  |  | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | Scar<br>shape | Tree<br>Species |  | <input type="text"/> |
| Scarred Trees                                               |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar Depth<br>(cm)                                          | Regrowth<br>(cm)                           | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <input type="text"/>                                        | <input type="text"/>                       | <input type="text"/>                      | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar<br>shape                                               | Tree<br>Species                            |                                           | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| 4.                                                          | <input style="width: 150px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Description:                                                |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
|                                                             |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <b>Features:</b>                                            |                                            | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="4" style="text-align: center;">Scarred Trees</th> </tr> <tr> <td style="text-align: center;">Scar Depth<br/>(cm)</td> <td style="text-align: center;">Regrowth<br/>(cm)</td> <td style="text-align: center;">Scar Length<br/>(cm)</td> <td style="text-align: center;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> </tr> <tr> <td style="text-align: center;">Scar<br/>shape</td> <td colspan="2" style="text-align: center;">Tree<br/>Species</td> <td style="text-align: center;"><input type="text"/></td> </tr> </table> | Scarred Trees |  |  |  | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | Scar<br>shape | Tree<br>Species |  | <input type="text"/> |
| Scarred Trees                                               |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar Depth<br>(cm)                                          | Regrowth<br>(cm)                           | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <input type="text"/>                                        | <input type="text"/>                       | <input type="text"/>                      | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar<br>shape                                               | Tree<br>Species                            |                                           | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| 5.                                                          | <input style="width: 150px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Description:                                                |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
|                                                             |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Other Site Info: <input style="width: 500px;" type="text"/> |                                            |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |

### Site plan




## Site photographs




Description: View south, pole shows artefact location



Description: Close up of Beryl Solar Farm IF 3.



Description:



Description:

## Site restrictions

Do you want to  
Restrict this site?: ☐

Restriction type: ☐ Gender ☐ General ☐ Location

Why is this site restricted?:

## Further information contact

Title  Surname  First name   
 Organisation:   
 Address:   
 Phone:  E-mail:



## Aboriginal Site Recording Form

AHIMS Registrar  
PO Box 1967, Hurstville 2220 NSW

AHIMS site ID: 36-2-0472

Date recorded: 15-03-2017

### Site Location Information

Site name: Beryl Solar Farm IF 2

Easting: 733005

Northing: 6417165

Coordinates must be in GDA (MGA)

Horizontal Accuracy (m):

5

Zone: 55

Location method:

Non-Differential GPS

### Recorder Information

(The person responsible for the completion and submission of this form)

Title

Surname

First name

Mr.

Barber

Matthew

Organisation:

75

Address:

Po Box 62 Fyshwick ACT 2609

Phone:

0407485018

E-mail:

matthew.b@ngHENvironmental.com.au

### Site Context Information

Land Form  
Pattern:

Undulating Plain

Land Form  
Unit:

Flat

Vegetation:

Cleared

Distance to  
Water (m):

450


Primary  
Report:

NGH Environmental 2017 Aboriginal Cultural Heritage Assessment- Beryl Solar Farm

How to get  
to the site:

on private property at Beryl accessed off either Beryl Road or Perseverance Lane

## Site location map



## Site contents information

open/closed site:

Site condition:

### Features:

1.

Artefact

Number of  
features

Length of  
feature(s)  
extent (m)

Width of  
feature (s)  
extent (m)

1

1

1

### Description:

This site consisted of a single artefact on the flat in a cleared paddock. The artefact was a multi-platform core of tuff. A total of 4 platforms and 9 negative scars were recorded with step reduction noted. Dimensions (mm) 118 x 48 x 55. The artefact had been partially bifacial flaked at one end.

### Scarred Trees

| Scar Depth<br>(cm)   | Regrowth<br>(cm)     | Scar Length<br>(cm)  | Scar Width<br>(cm)   |
|----------------------|----------------------|----------------------|----------------------|
| <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |
| Scar shape           | Tree Species         |                      | <input type="text"/> |

### Features:

2.

Number of  
features

Length of  
feature(s)  
extent (m)

Width of  
feature (s)  
extent (m)

### Description:

### Scarred Trees

| Scar Depth<br>(cm)   | Regrowth<br>(cm)     | Scar Length<br>(cm)  | Scar Width<br>(cm)   |
|----------------------|----------------------|----------------------|----------------------|
| <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |
| Scar shape           | Tree Species         |                      | <input type="text"/> |

|                                                                                                                                                           |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|-------------------------------------------|-------------------------------------------|-------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|------------------|---------------------|--------------------|-------------------------------------------|-------------------------------------------|-------------------------------------------|-------------------------------------------|---------------|-----------------|--|--------------------|-------------------------------------------|-------------------------------------------|--|-------------------------------------------|
| <b>Features:</b>                                                                                                                                          |                                           | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <div style="text-align: center; font-weight: bold; font-size: small;">Scarred Trees</div> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Depth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Regrowth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Length<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> </tr> <tr> <td style="text-align: center; font-size: x-small;">Scar<br/>shape</td> <td colspan="2" style="text-align: center; font-size: x-small;">Tree<br/>Species</td> <td style="text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td colspan="2" style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> </tr> </table> | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | Scar<br>shape | Tree<br>Species |  | Scar Width<br>(cm) | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |  | <input style="width: 100%;" type="text"/> |
| Scar Depth<br>(cm)                                                                                                                                        | Regrowth<br>(cm)                          | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <input style="width: 100%;" type="text"/>                                                                                                                 | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| Scar<br>shape                                                                                                                                             | Tree<br>Species                           |                                           | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <input style="width: 100%;" type="text"/>                                                                                                                 | <input style="width: 100%;" type="text"/> |                                           | <input style="width: 100%;" type="text"/> |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| 3.                                                                                                                                                        | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| Description:                                                                                                                                              |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
|                                                                                                                                                           |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <b>Features:</b>                                                                                                                                          |                                           | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <div style="text-align: center; font-weight: bold; font-size: small;">Scarred Trees</div> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Depth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Regrowth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Length<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> </tr> <tr> <td style="text-align: center; font-size: x-small;">Scar<br/>shape</td> <td colspan="2" style="text-align: center; font-size: x-small;">Tree<br/>Species</td> <td style="text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td colspan="2" style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> </tr> </table> | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | Scar<br>shape | Tree<br>Species |  | Scar Width<br>(cm) | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |  | <input style="width: 100%;" type="text"/> |
| Scar Depth<br>(cm)                                                                                                                                        | Regrowth<br>(cm)                          | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <input style="width: 100%;" type="text"/>                                                                                                                 | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| Scar<br>shape                                                                                                                                             | Tree<br>Species                           |                                           | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <input style="width: 100%;" type="text"/>                                                                                                                 | <input style="width: 100%;" type="text"/> |                                           | <input style="width: 100%;" type="text"/> |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| 4.                                                                                                                                                        | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| Description:                                                                                                                                              |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
|                                                                                                                                                           |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <b>Features:</b>                                                                                                                                          |                                           | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <div style="text-align: center; font-weight: bold; font-size: small;">Scarred Trees</div> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Depth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Regrowth<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Length<br/>(cm)</td> <td style="width: 25%; text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> </tr> <tr> <td style="text-align: center; font-size: x-small;">Scar<br/>shape</td> <td colspan="2" style="text-align: center; font-size: x-small;">Tree<br/>Species</td> <td style="text-align: center; font-size: x-small;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td colspan="2" style="text-align: center;"><input style="width: 100%;" type="text"/></td> <td style="text-align: center;"><input style="width: 100%;" type="text"/></td> </tr> </table> | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | Scar<br>shape | Tree<br>Species |  | Scar Width<br>(cm) | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |  | <input style="width: 100%;" type="text"/> |
| Scar Depth<br>(cm)                                                                                                                                        | Regrowth<br>(cm)                          | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <input style="width: 100%;" type="text"/>                                                                                                                 | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| Scar<br>shape                                                                                                                                             | Tree<br>Species                           |                                           | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| <input style="width: 100%;" type="text"/>                                                                                                                 | <input style="width: 100%;" type="text"/> |                                           | <input style="width: 100%;" type="text"/> |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| 5.                                                                                                                                                        | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> | <input style="width: 100%;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| Description:                                                                                                                                              |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
|                                                                                                                                                           |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |
| Other Site Info: <span style="border: 1px solid black; padding: 2px; display: inline-block; width: 600px; height: 1.2em; vertical-align: middle;"></span> |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                  |                     |                    |                                           |                                           |                                           |                                           |               |                 |  |                    |                                           |                                           |  |                                           |

**Site plan**

3


## Site photographs




Description: View south, pole shows artefact location.



Description: Close up of Beryl Solar Farm IF 2



Description:



Description:

## Site restrictions

Do you want to  
Restrict this site?: ☐

Restriction type: ☐ Gender ☐ General ☐ Location

Why is this site restricted?:

## Further information contact

Title  Surname  First name   
 Organisation:   
 Address:   
 Phone:  E-mail:

## Aboriginal Site Recording Form

AHIMS Registrar  
PO Box 1967, Hurstville 2220 NSW

AHIMS site ID: 36-2-0473

Date recorded: 15-03-2017

### Site Location Information

Site name: Beryl Solar Farm IF 1

Easting: 733453

Northing: 6417569

Coordinates must be in GDA (MGA)

Horizontal Accuracy (m):

5

Zone: 55

Location method:

Non-Differential GPS

### Recorder Information

(The person responsible for the completion and submission of this form)

Title

Surname

First name

Mr

Barber

Matthew

Organisation:

75

Address:

Po Box 62 Fyshwick ACT 2609

Phone:

0407485019

E-mail:

matthew.b@ngHENvironmental.com.au

### Site Context Information

Land Form  
Pattern:

Undulating Plain

Land Form  
Unit:

Flat

Vegetation:

Cleared

Distance to  
Water (m):

150


Primary  
Report:

NGH Environmental 2017 Aboriginal Cultural Heritage Assessment- Beryl Solar Farm

How to get  
to the site:

on private property at Beryl accessed off either Beryl Road or Perseverance Lane

## Site location map



## Site contents information

open/closed site:

Site condition:

### Features:

1.

Artefact

Number of features  
Length of feature(s) extent (m)  
Width of feature(s) extent (m)

### Description:

This site consisted of a single artefact on a minor slope in a cleared paddock. The artefact was a bifacial flaked hand axe manufactured from tuff. Dimensions (mm) 135 x 90 x 32

### Scared Trees

Scar Depth (cm)  
Regrowth (cm)  
Scar Length (cm)  
Scar Width (cm)  
Scar shape  
Tree Species

### Features:

2.

Number of features  
Length of feature(s) extent (m)  
Width of feature(s) extent (m)

### Description:

### Scared Trees

Scar Depth (cm)  
Regrowth (cm)  
Scar Length (cm)  
Scar Width (cm)  
Scar shape  
Tree Species

| <b>Features:</b>                                                                            |                                           | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="4" style="text-align: center;">Scarred Trees</th> </tr> <tr> <td style="text-align: center;">Scar Depth<br/>(cm)</td> <td style="text-align: center;">Regrowth<br/>(cm)</td> <td style="text-align: center;">Scar Length<br/>(cm)</td> <td style="text-align: center;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> </tr> <tr> <td style="text-align: center;">Scar<br/>shape</td> <td colspan="2" style="text-align: center;">Tree<br/>Species</td> <td style="text-align: center;"><input type="text"/></td> </tr> </table> | Scarred Trees |  |  |  | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | Scar<br>shape | Tree<br>Species |  | <input type="text"/> |
|---------------------------------------------------------------------------------------------|-------------------------------------------|-------------------------------------------|-------------------------------------------|-------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|--|--|--|--------------------|------------------|---------------------|--------------------|----------------------|----------------------|----------------------|----------------------|---------------|-----------------|--|----------------------|
| Scarred Trees                                                                               |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar Depth<br>(cm)                                                                          | Regrowth<br>(cm)                          | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <input type="text"/>                                                                        | <input type="text"/>                      | <input type="text"/>                      | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar<br>shape                                                                               | Tree<br>Species                           |                                           | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| 3.                                                                                          | <input style="width: 100%;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Description:<br><div style="border: 1px solid black; height: 40px; width: 100%;"></div>     |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <b>Features:</b>                                                                            |                                           | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="4" style="text-align: center;">Scarred Trees</th> </tr> <tr> <td style="text-align: center;">Scar Depth<br/>(cm)</td> <td style="text-align: center;">Regrowth<br/>(cm)</td> <td style="text-align: center;">Scar Length<br/>(cm)</td> <td style="text-align: center;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> </tr> <tr> <td style="text-align: center;">Scar<br/>shape</td> <td colspan="2" style="text-align: center;">Tree<br/>Species</td> <td style="text-align: center;"><input type="text"/></td> </tr> </table> | Scarred Trees |  |  |  | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | Scar<br>shape | Tree<br>Species |  | <input type="text"/> |
| Scarred Trees                                                                               |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar Depth<br>(cm)                                                                          | Regrowth<br>(cm)                          | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <input type="text"/>                                                                        | <input type="text"/>                      | <input type="text"/>                      | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar<br>shape                                                                               | Tree<br>Species                           |                                           | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| 4.                                                                                          | <input style="width: 100%;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Description:<br><div style="border: 1px solid black; height: 40px; width: 100%;"></div>     |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <b>Features:</b>                                                                            |                                           | Number of<br>features                     | Length of<br>feature(s)<br>extent (m)     | Width of<br>feature (s)<br>extent (m)     | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="4" style="text-align: center;">Scarred Trees</th> </tr> <tr> <td style="text-align: center;">Scar Depth<br/>(cm)</td> <td style="text-align: center;">Regrowth<br/>(cm)</td> <td style="text-align: center;">Scar Length<br/>(cm)</td> <td style="text-align: center;">Scar Width<br/>(cm)</td> </tr> <tr> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> <td style="text-align: center;"><input type="text"/></td> </tr> <tr> <td style="text-align: center;">Scar<br/>shape</td> <td colspan="2" style="text-align: center;">Tree<br/>Species</td> <td style="text-align: center;"><input type="text"/></td> </tr> </table> | Scarred Trees |  |  |  | Scar Depth<br>(cm) | Regrowth<br>(cm) | Scar Length<br>(cm) | Scar Width<br>(cm) | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | Scar<br>shape | Tree<br>Species |  | <input type="text"/> |
| Scarred Trees                                                                               |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar Depth<br>(cm)                                                                          | Regrowth<br>(cm)                          | Scar Length<br>(cm)                       | Scar Width<br>(cm)                        |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| <input type="text"/>                                                                        | <input type="text"/>                      | <input type="text"/>                      | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Scar<br>shape                                                                               | Tree<br>Species                           |                                           | <input type="text"/>                      |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| 5.                                                                                          | <input style="width: 100%;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> | <input style="width: 30px;" type="text"/> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Description:<br><div style="border: 1px solid black; height: 40px; width: 100%;"></div>     |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |
| Other Site Info:<br><div style="border: 1px solid black; height: 20px; width: 100%;"></div> |                                           |                                           |                                           |                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |               |  |  |  |                    |                  |                     |                    |                      |                      |                      |                      |               |                 |  |                      |

**Site plan**

3


## Site photographs




Description: View south, pole shows anefact location



Description: Close up of Beryl Solar Farm IF 1



Description:



Description:

## Site restrictions

Do you want to Restrict this site?:

Restriction type:  Gender  General  Location

Why is this site restricted?:

## Further information contact

Title  Surname  First name   
 Organisation:   
 Address:   
 Phone:  E-mail:

4

# APPENDIX E HERITAGE UNEXPECTED FINDS PROTOCOL

# HERITAGE UNEXPECTED FINDS PROTOCOL

## PURPOSE

This unexpected finds protocol has been developed to provide a method for managing unexpected non-Aboriginal and Aboriginal heritage items identified during the construction and maintenance of the Project. The unexpected finds protocol has been developed to ensure the successful delivery of the Project while adhering to the NSW *National Parks and Wildlife Act 1974* (NPW Act) and the *Heritage Act 1977* (Heritage Act).

Despite undertaking appropriate heritage assessment prior to the commencement of the Project, unexpected heritage items may still be identified during construction, operation and maintenance works. If this happens the following unexpected finds protocol plan should be implemented.

## WHAT IS A HERITAGE UNEXPECTED FIND?

An unexpected heritage find is defined as any possible Aboriginal or non-Aboriginal heritage object or place, that was not identified or predicted by the project's heritage assessment and is not covered by appropriate permits or development consent conditions. Such finds have potential to be culturally significant and may need to be assessed prior to development impact.

Unexpected heritage finds may include:

- Aboriginal stone artefacts, shell middens, modified trees, hearths and rock art;
- Human skeletal remains; and
- Remains of historic infrastructure and relics.

## ABORIGINAL HERITAGE PLACES OR OBJECTS

All Aboriginal objects are protected under the NSW *National Parks and Wildlife Act 1974* (NPW Act).

An Aboriginal object is defined as:

Any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises New South Wales, being habitation before or concurrent with the occupation of that area by persons on non-Aboriginal extraction and includes Aboriginal remains.

All Aboriginal objects are protected and it is an offence to harm or desecrate an Aboriginal object or place.

## HISTORIC HERITAGE

The *Heritage Act 1977* protects relics which are defined as:

Any deposit, artefact, object or material evidence that relates to the settlement of the area that comprises NSW, not being Aboriginal settlement; and is of State or local heritage significance.

## UNEXPECTED FINDS MANAGEMENT PROCEDURE

In the event that any unexpected Aboriginal heritage places or objects or any substantial intact historic archaeological relics of State or local significance are unexpectedly discovered during the Project, the following management protocols will be implemented:

1. Works at that identified heritage location will cease with an appropriate buffer zone of at least 20 metres to allow for the assessment and management of the find. All site personal will be informed about the buffer zone with no further works to occur within the buffer zone.
2. Heritage specialist will be engaged to assess the Aboriginal place or object encountered, Representatives from the registered the Aboriginal Stakeholders for the Project may also be engaged to assess the cultural significance of the place or object.
3. The Project approvals will be reviewed to assess consistency with the approvals to impact Aboriginal heritage within the Project area.
4. The discovery of an Aboriginal place or object will be reported to the local office of the Office of Environment and Heritage (OEH).
5. If the Aboriginal heritage places or objects are found to be covered under the existing approvals to impact Aboriginal heritage within the Project area, works may continue to be conducted in accordance with mitigation measures and approval requirements.
6. If the Aboriginal heritage places or objects are found to not be covered under the existing approvals to impact Aboriginal heritage within the Project area, works will not recommence at the heritage place or object until advised to do so by OEH.
7. If the heritage place or object can be managed *in situ*, works at the heritage location will not recommence until appropriate heritage management controls have been implemented, such as protective fencing.
8. For historic relics, work must cease in the affected area and the Heritage Council must be notified in writing. This is in accordance with section 146 of the *Heritage Act 1977*.
9. Depending on the nature of the discovery, additional assessment may be required prior to the recommencement of work in the area. At a minimum, any find should be recorded by an archaeologist.

## HUMAN SKELETAL REMAINS

Where human skeletal remains are unexpectedly found during works for the Project the following protocol would be adopted:

1. Works at that location will cease, and an appropriate buffer zone of at least 50 metres will be established;
2. The human remains will not be moved;
3. The NSW police will be notified, and if the human remains are deemed a crime scene, the place will be managed by the police;
4. Should the human remains be deemed Aboriginal or historical by the police, OEH must be notified immediately to assess the remains; and
5. Should the human remains be deemed Aboriginal in origin all registered Aboriginal parties for the Project are to be notified in writing.

The above process functions only to appropriately identify the human remains and secure the site, from which time the management of the remains is to be determined through liaison with the NSW police, OEH and the relevant Aboriginal stakeholders.