# Gunnedah Solar Project – Phase 2
# Water Management Plan

September 14, 2020

Prepared for:

PCL Constructors Pacific Rim Pty Ltd.
Level 11
485 Bourke Street
Melbourne, VIC 3000

Prepared by:

Stantec Australia Pty Ltd.
Level 4, 99 Walker Street
North Sydney, NSW 2061

| Revision | Description | Author | | Quality Check | | Independent Review | |
|---|---|---|---|---|---|---|---|
| 0 | Preliminary WMP | 2020/07/22 | DW | 2020/07/27 | BW | 2020/07/27 | PB |
| 1 | Preliminary WMP – Response to NSW DPIE Comments | 2020/09/10 | DW | 2020/09/14 | BW | 2020/09/14 | PB |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

This document entitled Gunnedah Solar Project – Phase 2 Water Management Plan was prepared by Stantec Consulting International Ltd. ("Stantec") for the account of PCL Constructors Pacific Rim Pty Ltd. (the "Client"). Any reliance on this document by any third party is strictly prohibited. The material in it reflects Stantec's professional judgment in light of the scope, schedule and other limitations stated in the document and in the contract between Stantec and the Client. The opinions in the document are based on conditions and information existing at the time the document was published and do not take into account any subsequent changes. In preparing the document, Stantec did not verify information supplied to it by others. Any use which a third party makes of this document is the responsibility of such third party. Such third party agrees that Stantec shall not be responsible for costs or damages of any kind, if any, suffered by it or any other third party as a result of decisions made or actions taken based on this document.

David Williams – 2020/09/14

Prepared by _____
(signature)
**David Williams, P.Eng. (Ontario, Canada)**

Bedilu Wolelo – 2020/09/14

Reviewed by _____
(signature)
**Bedilu Wolelo, Bsc(Civil), GradCert, MSc, MEngsc, MIEAust, CPEng, RPEQ, NER**

Peter Bright – 2020/09/14

Approved by _____
(signature)
**Peter Bright, Project Manager**

# Table of Contents

**1.0 INTRODUCTION ..... 1.1**
1.1 BACKGROUND INFORMATION ..... 1.1

**2.0 EXISTING CONDITIONS ..... 2.1**
2.1 TOPOGRAPHY ..... 2.1
2.2 HYDROLOGY ..... 2.1
2.2.1 Flood Risk Assessment ..... 2.1
2.3 SOILS AND HYDROGEOLOGY ..... 2.1

**3.0 PROPOSED CONDITIONS ..... 3.1**
3.1 GRADING AND DRAINAGE STRATEGY ..... 3.1

**4.0 STORMWATER MANAGEMENT DESIGN ..... 4.1**
4.1 WATER QUANTITY CONTROLS ..... 4.1
4.1.1 Water Quantity Monitoring Requirements ..... **Error! Bookmark not defined.**
4.2 WATER QUALITY CONTROLS ..... 4.2

**5.0 SEDIMENT AND EROSION CONTROL (SEC) MEASURES ..... 5.4**
5.1 CONSTRUCTION DEWATERING ..... 5.5
5.2 CONTINGENCY PLAN ..... 5.6
5.2.1 Contingency Measures in Case of Failure ..... 5.6
5.2.2 Contingency Measures where there is a High Risk of Failure ..... 5.7
5.3 EROSION AND SEDIMENT CONTROL MONITORING PROGRAM ..... 5.7
5.4 LONG TERM EROSION AND SEDIMENT CONTROL ..... 5.8

**6.0 FLOODPLAIN MAPPING ..... 6.1**
6.1 SITE FLOODPLAIN CHARACTERISTICS ..... 6.1
6.2 FLOODPLAIN MANAGEMENT ..... 6.1
6.2.1 Fish passage requirement ..... 6.1
6.2.2 Flood characteristics ..... 6.2
6.2.3 Overall ..... 6.2

**7.0 CONCLUSION ..... 7.1**

**LIST OF APPENDICES**

DRAWINGS
INSPECTION FORMS
GUNNEDAH SOLAR FARM HYDROLOGY REPORT

# 1.0 INTRODUCTION

Stantec Australia Pty Ltd (Stantec) has been retained by PCL Constructors Pacific Rim Pty Ltd. (PCL) to provide engineering services for the 147 MW Gunnedah Solar Project located at 765 Orange Grove Road, Gunnedah, New South Wales (NSW) (Site). The Site is located approximately 10 km north east of Gunnedah Township, 430 km north west of Sydney.

The approved Phase 1 of the Water Management Plan (Stantec, June 2020) documented stormwater management and erosion and sediment controls for the construction of the main access road, stretching from Orange Grove Road to the location of the substation.

This report documents Phase 2 of the Water Management Plan encompassing the remainder of the proposed works 3.24 and 4.24 of the project's Development Consent (Application Number SSD 8658). It is noted that Phase 2 of the Water Management Plan reflects the current grading design for the site with minor design changes anticipated for the site, however significant changes to flooding characteristics of the site and water management are not anticipated.

## 1.1 BACKGROUND INFORMATION

A list of resources referenced when completing this preliminary water management plan has been provided below for reference:

- *Gunnedah Solar Project – Early Works – Phase 1 Water Management Plan*, Stantec Consulting Ltd., June 2020
- *Gunnedah Solar Farm – Flood Risk Assessment*, Stantec Consulting Ltd, March 2020
- *Gunnedah Solar Farm Development Consent* – Independent Planning Commission of NSW, March 12, 2019
- *Australia Rainfall and Runoff (ARR)*, Geoscience Australia, 2019
- *Gunnedah Solar Farm Environmental Impact Statement*, Pitt & Sherry Pty Ltd., April 17, 2018
- *Guidelines for watercourse crossings on waterfront land*, NSW Department of Primary Industries – Office of Water, July 2012
- *Managing Urban Stormwater: Soils and Construction* – Landcom, 2004

In addition to the above noted reference documentation various communications with project team members from Stantec, PCL and Canadian Solar (CS) were considered.

# 2.0 EXISTING CONDITIONS

Under existing conditions the current land use of the site is primarily agricultural being used for row crops.

## 2.1 TOPOGRAPHY

The project area is relatively flat with ground slopes in the 0.1 to 0.5% range. Ground surface elevations range from 256 to 280 metres above sea level (masl).

## 2.2 EXISTING SITE HYDROLOGY

In general, runoff from the site drains as shallow overland flow towards the west. There are no significant natural drainage features across the site. The entire site is bound by irrigation channels which are approximately 5 m wide, 2-3 metres deep with a negligible longitudinal slope. During runoff events water is stored within these channels until they are pumped for irrigation or water infiltrates/evaporates. Anecdotal evidence from PCL suggests that irrigation channels infiltrate/evaporate within 3 days to a week of a rainfall event.

### 2.2.1 Flood Risk Assessment

An existing conditions flood risk assessment was completed by Pitt & Sherry Pty Ltd. (2018) and Stantec (2020) addressing requirements for regional and local flood modeling, respectively. These reports are available under separate cover. A summary of the local flood modeling is included in Section 6 of this report.

## 2.3 SOILS AND HYDROGEOLOGY

Site soils are described in the Environmental Impact Statement (EIS) as “deep alluvial brown clays, typically comprising clay loam toposoil’s (sic) over clay loam to medium clay soils” (pitt&sherry, 2018). The EIS suggests the erosion potential of the site as low to moderate hazard for rill and gully erosion

Groundwater depths range from 6.7 to 7.6 m below ground surface (bgs) in the area. The Site is not designated as groundwater vulnerable under the Gunnedah Local Environment Plan (LEP).

# 3.0 PROPOSED CONDITIONS

The Gunnedah Solar Project includes approximately 14 km of 4.5 to 6.5 m wide access roads, 45 inverter stations located on granular pads, one substation, a switching yard, laydown areas for construction and the ground mounted solar panels.

The design of the Gunnedah Solar Project employs a low-impact approach to site development. The grading plans appended, show that the proposed grades will match existing grades wherever possible; existing drainage patterns are preserved wherever possible; roads will typically be constructed at grade to maintain existing drainage patterns; and site excavation will be kept to a minimum in order to retain as much existing ground cover as possible.

Once panels and racking are in place, all accessible disturbed areas will be scarified to alleviate soil compaction prior to restoration seeding. The post-development hydrology will mimic a permanently grassed pasture, which represents an improved hydrologic condition over the existing agricultural land use.

It is understood that site inverter stations, switching station and other site infrastructure will be installed on piles such that the bottom floor elevation of the infrastructure is above the 1% AEP regional flood event.

Design of the substation pad in the southern portion of the site was completed by TransGrid. This area consists of substation infrastructure installed on a granular pad designed to raise floor elevations above the 1% AEP regional flood event.

## 3.1 GRADING AND DRAINAGE STRATEGY

The proposed grade of the access road generally matches existing conditions elevations on site. In areas where the access road crosses a topographical low the access road has been designed to meet the existing low point. Armouring will be provided in the form of a hardened surface and/or road sealer at road crossings where erosive velocities are exceeded for the proposed granular surface. Hardened surface / road sealer locations and extents will be confirmed prior to issuing drawings for construction.

Equalisation culverts have been provided in the existing site irrigation channels.to provide a connection under the proposed access road. Culverts have been sized to fit within the base of the channel, without requiring over excavation of the side slopes. As the irrigation channels are used for storage of runoff and managed by a pump, conveyance of specific storm events is not required.

## 3.2 DROP-DOWN / FLOW THROUGH FENCING

Per the regional flood risk assessment, approximately 50% of the site perimeter fencing is required to be drop down fencing. A drawing of the proposed perimeter fence has been appended for reference, in which a flow through fence design has been selected instead of a drop-down fence. The flow through fence consists of a standard fence panel, with a pivot pin halfway up the fence. The bottom of the fence

is secured using a 4 mm low tensile wire (designed by others) which will release following buildup of debris along the fence, allowing debris to flow under the fence during a high flow event. Following the event, the fence will fall back into place providing temporary security until a low tensile wire can be installed.



# 4.0 STORMWATER MANAGEMENT DESIGN

## 4.1 WATER QUANTITY CONTROLS

Grading design has been completed to mimic existing site drainage conditions. The increase in impervious coverage to downstream areas as a result of the installation of the proposed access road and substation infrastructure is minimal compared to the upstream drainage catchments. Therefore any increase in flows, and impact to downstream areas as a result of the access road construction is expected to be negligible (outlined in section 6.2.2).

It is noted that the site is bounded by existing irrigation channels, including a 5+ m wide irrigation channel on the adjacent property to the west running parallel to the main access road. It is anticipated that overland flows leaving the site will enter adjacent irrigation channels and redistribute throughout the channel prior to spilling and continuing downstream, similar to existing conditions.

### 4.1.1 Flow Through Fencing Monitoring Requirements

The primary concern for flooding impacts relate to the perimeter fencing and potential of increase in flooding due to blockage from flood debris. Following a significant rainfall event (> 25 mm in depth) or a Namoi River flood event (overtopping of Orange Grove Road in the vicinity of the site), the perimeter fence will be inspected (within 24-72 hours of the event) for damage, evidence of flow and debris along the fence and flow through fence activation (broken connectors). High water marks will be identified on interior solar panel racking and adjacent perimeter fence posts in locations identified on the attached figures. High water marks are to be measured as depth from ground surface. If it is noted that high water marks are different (> 200 mm) between external and adjacent internal features, further investigation into the performance of the drop-down/flow through fencing will be required.

Inspections shall be recorded within a log-book (including, date/depth of rainfall event, date of inspection, inspector name and high water mark measurements) and kept in the site operation and maintenance building. Log-books will be made available to local regulatory agencies upon request.

If regular monitoring concludes that the current fencing configuration requires improvement, the following mitigation measures may be considered:

- Install lower strength shear pins / connections (if debris build-up is identified on drop-down fencing panels and little evidence of flow through is identified)
- Increase percentage of flow though fencing panels along west and east edges of site
- Revise drop-down/flow fencing configuration

In addition to monitoring following significant rainfall events, regular monitoring of perimeter fencing should be completed to ensure shear pins / low-tensile wire connections are still intact and site security is maintained.

## 4.2 WATER QUALITY CONTROLS

As mentioned above the increase in impervious coverage to downstream areas as a result of the installation of the proposed access road is minimal compared to the upstream drainage catchments. In addition the remainder of the site will be converted from agricultural land with repeated disturbance to a permanently vegetated pasture improving the sites ability to prevent erosion and retain site soils in-situ.

Hardened surfaces and/or road sealing are proposed at access road low points / surface water crossings in order to mitigate erosion and transport of sediments downstream, while irrigation channels will have permanent rock check dams at regular intervals to promote sediment deposition.

No additional formal stormwater management water quality controls are recommended for the site.

## 4.3 LONG-TERM STORMWATER MANAGEMENT MONITORING PROGRAM

Implementation of a post-construction monitoring program provides the data necessary to assess that the stormwater management system is functioning as designed. The following objectives of the post-construction monitoring program should be assessed on a routine basis:

- Ensuring site vegetative cover is maintained and areas of exposed soil remediated
- Routine observations as to the presence of retained trash/debris that could be conveyed downstream and/or affect the conveyance capacity of the system and removal of same as needed
- Ensuring all surface water crossings are free of flow obstruction with armoring on access roads suitable for conveyance at low points
- Ensuring functioning condition of the on-site culverts
- Ensuring that the perimeter fence is functioning to allow the passage of floodwaters through the site
- Maintaining both the use and integrity of surrounding irrigation channels for stormwater storage

### 4.3.1 Visual Inspections

Site Vegetation

Regular inspections should be completed to identify areas of bare soil and/or the formation of erosive gullies. Remediative efforts would typically involve re-grading the area and/or re-vegetating with sod or appropriate seed mix, with fertilizer and water applied as necessary to ensure germination and stabilization

Vegetation management is not a strict requirement in that excess growth will serve to improve water quality treatment benefits. If the density of vegetation reaches a level where conveyance capacity is

impacted, a cutting operation should be undertaken. A minimum vegetation height of 0.15 m should be maintained.

Drainage Swale Conveyance System

Routine observations of ditches for erosion and/or presence of trash/debris within the swale that could be conveyed downstream and/or effect the conveyance capacity of the system should be conducted.

Access Road Low-Points

Regular inspections of the low points should be conducted to assess the low point for erosion and/or potential flow blockages inhibiting smooth passage of water across the low point.

On-site Infrastructure

On-site culverts are used to convey stormwater under the site access roads. Routine inspections of the culverts should be conducted to ensure that the culverts can pass water per their design capacity. The inspector should be looking for flow obstructions and culvert damage which could impede the conveyance capacity of the culvert.

Site Perimeter Fencing

The perimeter fencing is designed to maintain existing floodwater drainage. Per Section 4.1.1 the perimeter fencing should be inspected to ensure the fence is capable of maintaining flow passage through the fence.

# 5.0 SEDIMENT AND EROSION CONTROL (SEC) MEASURES

The various construction activities required for construction include topsoil removal, minor area grading, placement of granular material, installation of piles, racking and panels and general construction traffic. If left unmitigated, these activities will result in impacts ranging form disturbance of at-surface soils to potential erosion and sediment transport to downstream locations.

Erosion control will be achieved primarily by:

- Managing disturbed soils using soil conservation practices to reduce runoff and sediment transport during construction;
- Constructing barriers to filter runoff

Erosion and sediment control measures (detailed on Drawing C-600) will be implemented prior to any grading or servicing works commencing, and include, but are not necessarily limited to, the following measures:

- Perimeter sediment fencing will be installed at the downstream side of the work limits
    - Where shallow topsoil depths prevent trenching in the filter fabric, 150 mm of clear stone or pea gravel will be used to provide contact between the fabric and ground surface.
- A construction entrance feature (“shaker”) will be provided at the site entrance to minimize the offsite transport of sediment via construction vehicles.
- Orange Grove Road will be inspected for and cleaned daily of any sediment (if necessary) deposited by site construction traffic.
- Sediment and erosion control berms provided downstream of disturbed areas (as shown on drawings) to promote settling of any solids entrained in stormwater runoff
- Stabilise topsoil stockpiles expected to be left in place longer than 10 days with vegetative cover (i.e., hydroseeding) or a rolled erosion control product in the event of unfavourable growing conditions. Topsoil stockpiles are to be surrounded by sediment fence.
- No equipment will be permitted to enter any area beyond the proposed work limits during construction.
- Water or synthetic dust suppressants will be employed to manage wind erosion and reduce dust generated from unsealed roads, stockpiles or areas of disturbed soil.
    - Dust generating activities shall be limited during periods of high velocity wind, as determined by the Construction Manager
- Re-vegetate all disturbed areas where construction is not expected for 20 days with sufficient topsoil to support re-vegetation and hydro-seeding or other stabilising vegetation / erosion protection. If, given seasonal restriction or other revegetation limiting factors, the disturbed area should be stabilised against erosion impacts by non-vegetated means such as erosion control blankets.

- All materials and equipment used for site preparation and project construction should be operated and stored in a manner that prevents any deleterious substance (e.g., petroleum products, silt, etc.) from migrating to offsite receivers.
    - Refueling and maintenance of construction equipment should occur in designated areas, a minimum of 100 m from a water body.
- All spills must be reported to the appropriate regulatory authority(ies).
- In the event of inclement weather or unfavourable terrain for construction, construction best practices, such as temporary rig-mats may be used to prevent disruption of surface soils and vegetative cover by construction vehicles and equipment.
- Sediment and erosion control measures are to be cleaned out when sediment reaches 1/3 of the available storage capacity.
- In the event of large or back-to-back storm events where on-site irrigation channels begin to exceed 80% capacity, irrigation channels may be pumped to provide additional containment volume. Pumped water will be discharged through a filter sock a sediment trap located on a gently sloped, vegetated area (when possible) greater than 50 m from any waterbody or downstream property.
- Silt-soxx (or approved equivalent) will be installed downstream of all proposed culvert crossings to minimise transport of sediment downstream.
- Culvert crossings will be installed with a rip-rip apron upstream and downstream of culvert entrances and exits to mitigate erosion as a result of flow concentration.

## 5.1 CONSTRUCTION DEWATERING

Since no significant excavation is anticipated for the construction of the Gunnedah Solar Farm, construction activities are not expected to intercept the groundwater table. However, if necessary, any required dewatering operations will be completed such that discharge rates will not adversely impact flooding or erosion conditions upstream or downstream of the Site. To mitigate the risk of sediment migration to downstream areas, dewatering discharges may be treated with a variety of measures including, but not limited to, filter socks or sediment traps at the discretion of the contractor in consultation with the owner's engineer. Dewatering measures will be directed through the sediment control measures to a gently sloped, vegetated area (when possible) greater than 50 m from any waterbody or downstream property.

Although an exceedance isn't expected, should anticipated pumping rates exceed 3,000,000 L/water year (July 1 to June 30) a Water Access License will need to be obtained with sufficient entitlement to account for the total water take prior to the taking occurring.

## 5.2 PROJECT CONSTRUCTION WATER SUPPLY

Construction water requirements anticipated for the project include dust suppression and compaction. Water supply will be provided using on-site bores currently under agreement from the existing landowner.

The anticipated water consumption for the construction phase of the project is 240,000 L/day for a total of 30,240,000 L over the six (6) month construction timeline.

## 5.3 CONTINGENCY PLAN

The purpose of the contingency plan is to help minimize the risk or consequence of failure of the erosion and sediment control works. Failure could result from insufficient measures, lack of maintenance, or severe weather conditions. The contingency plan includes two areas of consideration: the procedures that will be followed where a failure has occurred; and the contingency measures that will be implemented where there is potential for failure.

The Contractor shall be responsible for following the contingency plan, and will prepare the following items:

- Workers shall be on call for emergency situations for all aspects of the emergency from design to construction of emergency sediment and erosion control measures. Any associated health and safety issues are the responsibility of the Contractor.
- Heavy duty silt fence, erosion control blankets, straw bales and stakes or silt-soxx, sandbags, appropriate sized rip-rap, and clean gravel fill shall be available on-site for emergency installation.
- Heavy equipment shall be on standby for emergency works.
- Fuel spill containment supplies and equipment shall be available on-site for emergency spills of deleterious substances.
- A contact list for any further required equipment or materials shall be prepared and made available for emergency use.

### 5.3.1 Contingency Measures in Case of Failure

In the event of a failure, the Contractor will cease all construction related work and focus on erosion and sediment control as required to effectively stabilise the site where a failure has occurred or is imminent.

If significant long-term damage to downstream fish habitat or property is suspected, the Environmental Monitor will immediately assess and document the situation and report the incident to the appropriate regulatory agencies The Contractor will develop a restoration plan in consultation with regulatory authorities. Development of the initial restoration plan will begin within 24 hours of the discovery of sediment discharge, and will be implemented as soon as possible, following consultation and approval. The plan will address:

- Removal and disposal of sediment from outside the work limits;
- Restoration of the affected area; and
- Restoration of any areas disturbed through deposition or removal.

### 5.3.2 Contingency Measures where there is a High Risk of Failure

Conditions that may potentially cause failures can be identified through two methods: monitoring of the erosion and sediment control measures, and weather forecasts that anticipate severe weather conditions.

#### 5.3.2.1 High Risk Identified Through Monitoring

Where monitoring has identified a high potential for failure, steps shall be immediately taken to reduce the risk. These measures may include repair to existing measures, modification of existing measures, and the addition of new measures.

#### 5.3.2.2 Severe Weather Anticipated

In cases where the weather forecast indicates that significant rainfall is expected within a 24-hour period, the Contractor shall immediately complete the following:

- Verify that all erosion and sediment control measures are secure and that there is no exposed soil that could erode and be deposited downstream;
- Verify that all other measures are in good working order;
- Monitor all measures during the rainfall event, and where a potential for failure is identified, take corrective measures.

If unforeseen events cause the strategies set out in the contingency plan to be insufficient or inappropriate to meet the objective of containing sediment within the work limits, the Contractor will respond in a timely manner with all reasonable measures consistent with safety, to prevent, counteract or remedy any negative effects on the natural environment or adjacent properties.

## 5.4 EROSION AND SEDIMENT CONTROL MONITORING PROGRAM

To ensure the effectiveness of the various erosion and sediment control measures, a routine program should be implemented which includes the inspection of the erosion and sediment controls weekly and after each rainfall event generating runoff, and immediate repair of any deficiencies. Non-urgent repairs (i.e., no immediate risk of sediment discharges to the downstream environment) will be completed within 48 hours of identifying the deficiency, or prior to the next anticipated rainfall event, whichever is less. This program will consist of the following activities:

- Visual inspection of the SEC measures to ensure discharged flows are generally free of sediment and turbidity;
- Inspection of vegetation protection, erosion control blankets and silt fencing to ensure that they are maintained in good repair;
- Removal of construction debris that may accumulate; and



- Implementation of remedial measures including erosion stabilization, repair of damaged measures and any other remediation where required.

If the monitoring program outlined above indicates a persistent problem, then the following steps should be undertaken to determine appropriate mitigative measures (if step 1 does not resolve the issue, proceed to step 2):

1. Analysis of the monitoring information and field visits as required, to determine the cause of the problem and develop a mitigation plan to address the issue in consultation with a qualified Environmental Monitor.

    a. Implement additional mitigation measures and monitor the results.

2. Convene a meeting with the appropriate review agencies.

    a. Develop a consensus on a proposed plan of action to resolve the problem in consultation with agency staff.

    b. Implement additional mitigation measures and monitor the results.

## 5.5 LONG TERM EROSION AND SEDIMENT CONTROL

Approximately one (1) year after completion of construction, a site inspection will be completed to ensure that long-term erosion control measures have been effective. Seeded or replanted areas will be inspected to ensure that vegetation measures were successful and reseeding or replanting will occur where necessary.

If erosion control measures are found to be less than fully effective during this survey, reseeding or replanting of problem areas will take place. Should there be residual effects noted during post-construction monitoring, advice on contingency measures will be sought and applied.

# 6.0 FLOODPLAIN MAPPING

Floodplain mapping was complete to address requirements outlined in the *Floodplain Management Plan for the Upper Namoi Valley Floodplain 2019* (New South Wales, 2019) and the *Carroll to Boggabri Floodplain Management Plan* (NSW Department of Natural Resources, 2006). A detailed floodplain assessment is included in the *Gunnedah Solar Farm Hydrology Report* (Stantec, 2020).

## 6.1 SITE FLOODPLAIN CHARACTERISTICS

During major storm events Namoi River breaks bank and drains in a westerly direction across the access road. The site design was completed taking into account the requirements of the *Floodplain Management Plan for the Upper Namoi Valley Floodplain 2019* to maintain flow characteristics during local and regional flood events. The vertical alignment was designed to blend with the existing ground form.

The vertical geometric alignments of the access roads follow the existing ground level. Cut was required at sections of the alignment and slight fill, not exceeding 0.5m was provided at sections of the road to maintain geometric design requirements.

Hardened surface is provided at sag points to allow runoff to drain across the road.

Equalisation culverts are provided at road crossings of existing irrigation channels, maintain connectivity.

## 6.2 FLOODPLAIN MANAGEMENT

The project site is located in the Upper Namoi Management Zone BL. The Zone BL management zone is important for the conveyance of floodwaters during large flood events. The *Floodplain Management Plan for the Upper Namoi Valley Floodplain 2019* designates access road construction inside Zones BL and AID as flood works. Division 5 of the flood management plan provides rules for granting or amending flood works approvals in Upper Namoi Management Zones BL and AID. Floodplain modeling for the subject works was documented in the *Gunnedah Solar Farm Hydrology Report* (Stantec, 2020), attached.

### 6.2.1 Fish passage requirement

Inundation of the site occurs during the 10% AEP storm event. There is no defined watercourse along the road alignment and hence there is no permanent water feature along the access road alignment. Fish may cross the proposed road during this rare storm event. The hard pavement provided at the sag points and the road design will meet fish passage requirement as:

- The road is designed to follow the natural ground and minimises barrier to fish crossing
- The site a prime agricultural land that has a flat regular gradient of less than 0.5%, this has resulted in flow velocities less than 0.5m/sec during major regional storm events

- There is less turbulence created at downstream end of the access road as the difference in height above natural ground surface is limited. Turbulence to flow is limited and fish passage will be maintained

### 6.2.2 Flood characteristics

The proposed works vertical geometry undulates following the existing ground topography. Fill height is limited along the project to limit increase in flood level upstream and redistribution of flow on adjacent landholdings.

A flood model was completed to determine the impact of the proposed road on flow characteristics during the 1% AEP storm event generated from local catchments. The study has indicated that:

- The maximum reduction in depth of flow downstream of the site was 2 mm
    - This minor reduction, within the limits of accuracy of the hydraulic model
- The maximum increase in flood level downstream of the access road was 0.05m and the increase occurs at a ford crossing inside the project site limits
- The maximum increase in flood level upstream of the project was 90mm
    - The increase in flood level occurs inside project boundary.
- The difference in maximum flow velocity under proposed conditions 0.25m/sec.
    - The increase is within the limits acceptable by the upper Namoi Valley Flood Plain Management Plan.

The flood level difference maps were provided as appendix to the *Gunnedah Solar Farm Hydrology Report* (Stantec, 2020), attached. The flood study has indicated that the impacts are minor and that the impacts occur within the project limits. The study has indicated that there is no impact on adjacent landholding due to the construction of the proposed project.

### 6.2.3 Overall

The proposed site is designed taking into consideration the requirements of the *Floodplain Management Plan for the Upper Namoi Valley Floodplain 2019*. There are no defined watercourses within the site. Runoff occurs as a sheet flow. With the site being flat (i.e., a grade less than 0.5%) maximum flow velocity across the site is less than 0.5m/sec. With the main access road, internal access road and minor grading design blending into the existing natural terrain, there was limited increase in flood levels upstream and limited/no increase in flow redistribution for downstream property.

The proposed site design was assessed against the requirements of the floodplain management plan for the upper Namoi River and it meets all the requirements.

# 7.0 CONCLUSION

Based on the findings of this report, the following recommendations are provided.

- The proposed stormwater management measures in this report shall be constructed as designed;
- The SEC measures documented herein shall be implemented during construction; and
- The monitoring and maintenance program (for both fencing and SEC) shall be carried out during and following construction;




# DRAWINGS

Stantec

PCL

CONSTRUCTION LEADERS




## DRAWING LIST

CIVIL


C010 SITE PLAN 1 TO 6
C050 EXISTING CONDITIONS, CLEARING, GRUBBING AND FENCING PLAN 1 TO 6
C200 PLAN & PROFILE, ENTRANCE & ACCESS ROAD 1 TO 16
C400 GRADING PLAN 1 TO 19
C500 NOTES AND DETAILS
C600 EROSION AND SEDIMENT CONTROL PLAN 1 TO 19

# CANADIAN SOLAR AUSTRALIA
# GUNNEDAH SOLAR PROJECT
# 147MW GROUND MOUNTED SOLAR FARM
## GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

APRIL, 2020
CIVIL PACKAGE
ISSUED FOR 30% REVIEW
Project Number: 3600727160

NOT FOR CONSTRUCTION

ORIGINAL SHEET - ISO A1
C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-CV.dwg
2020/07/28 11:37 PM By: Childs, Jason




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SOLAR PANEL TABLE
- SOLAR ARRAY BLOCK DELINEATOR
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-SP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
SITE PLAN

| Project No. | Scale | Revision |
|---|---|---|
| 3600727160 | 1:2000 (0, 20, 60, 100m) | |
| Drawing No. | Sheet | |
| C-010 | 1 of 6 | 3 |

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-SP.dwg
2020/07/28 1:41 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PCS2

4.0m WIDE ACCESS ROAD

PCS3

ACCESS ROAD B

PCS4

PCS5

4.0m WIDE ACCESS ROAD

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PCS7

4.0m WIDE ACCESS ROAD

PCS8

ACCESS ROAD B

PCS9

PCS10

4.0m WIDE ACCESS ROAD

PCS11

PROPOSED CULVERT X2

PROPOSED CULVERT

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

SEE DRAWING C-010-SHEET 1

PCS15

PCS16

ACCESS ROAD A

PCS17

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

4.0m WIDE ACCESS ROAD

ACCESS ROAD C

PCS18

PCS19

4.0m WIDE ACCESS ROAD

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PCS20

PROPOSED CULVERT

PROPOSED CULVERT X2

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

4.0m WIDE ACCESS ROAD

PCS21


ACCESS ROAD D

PROPOSED CULVERT


4.0m WIDE ACCESS ROAD

SEE DRAWING C-010-SHEET 3

SEE DRAWING C-010-SHEET 4




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

## Legend

PROPOSED

- SWALE
- 184.5 EXISTING TOPOGRAPHIC SURVEY CONTOUR
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SOLAR PANEL TABLE
- SOLAR ARRAY BLOCK DELINEATOR
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-SP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

SITE PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:2000 (0 20 60 100m) | C-010 | 2 of 6 | 3 |


Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-SP.dwg
2020/07/28, 11:42 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION




## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SOLAR PANEL TABLE
- SOLAR ARRAY BLOCK DELINEATOR
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-SP.dwg | | DR | IH | DR | 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

SITE PLAN

| Project No. | Scale |
|---|---|
| 3600727160 | 1:2000 (0 20 60 100m) |
| Drawing No. | Sheet / Revision |
| C-010 | 3 of 6 / 3 |

Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

C:\Users\jchiba\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet files\3600727160_C-SP.dwg
2020/07/28, 11:43 PM By: Chiba, Jason
ORIGINAL SHEET - ARCH D

SEE DRAWING
C-010-SHEET 3

PROPOSED DROP DOWN GATE (DESIGNED BY OTHERS)

PROPOSED CULVERT X2

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED CULVERT

4.0m WIDE ACCESS ROAD

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PROPOSED CULVERT

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED DROP DOWN GATE (DESIGNED BY OTHERS)

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)


ACCESS ROAD A

ACCESS ROAD E


ACCESS ROAD F

PCS28 PCS29 PCS30 PCS31 PCS32 PCS33 PCS34 PCS35 PCS36 PCS37 PCS38 PCS39 PCS40 PCS41 PCS42

SEE DRAWING
C-010-SHEET 5




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- SWALE
- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SOLAR PANEL TABLE
- SOLAR ARRAY BLOCK DELINEATOR
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-SP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

SITE PLAN

Project No. 3600727160

Scale 1:2000 (0 20 60 100m)

Drawing No. C-010

Sheet 4 of 6

Revision 3

Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

NOT FOR CONSTRUCTION

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-SP.dwg
2020/07/28, 11:44 PM By: C.Hesh, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING
C-010-SHEET 4




SEE DRAWING
C-010-SHEET 6





Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS



Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.


## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SOLAR PANEL TABLE
- SOLAR ARRAY BLOCK DELINEATOR
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C-SP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

SITE PLAN

Project No. 3600727160

Scale 1:2000 (0, 20, 60, 100m)

Drawing No. C-010

Sheet 5 of 6


Revision 3


NOT FOR CONSTRUCTION



C:\Users\Childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-SP.dwg
2020/07/28 11:43 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SOLAR PANEL TABLE
- SOLAR ARRAY BLOCK DELINEATOR
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C-SP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
SITE PLAN

Project No. 3600727160

Scale 1:2000 (0 20 60 100m)

Drawing No. C-010

Sheet 6 of 6

Revision 3

C:\Users\jchiba\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-SP.dwg
2020/07/28 11:46 PM By: Chiba, Jason

ORIGINAL SHEET - ARCH D

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PCS1

PCS2

4.0m WIDE ACCESS ROAD

PCS3

ACCESS ROAD B

PCS4

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

4.0m WIDE ACCESS ROAD

PCS6

PROPOSED DROP DOWN GATE (DESIGNED BY OTHERS)

PCS7

4.0m WIDE ACCESS ROAD

PCS8

ACCESS ROAD B

PCS9

PCS12

4.0m WIDE ACCESS ROAD

PCS13

PCS14

ACCESS ROAD C

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PCS15

PCS16

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)


PCS17

4.0m WIDE ACCESS ROAD


PCS18

SEE DRAWING C-050-SHEET 2

NOTE:
CLEAR/TRIM ANY OVER GROWN WILD GRASS ON WORKING AREAS




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- LIMIT OF TOPSOIL REMOVAL
- EXISTING TREE LINE
- PROPOSED TREE LINE
- EXISTING TREES TO BE CLEARED
- OVERLAND FLOW DIRECTION
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-DP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EXISTING CONDITIONS, CLEARING, GRUBBING AND FENCING PLAN

Project No. 3600727160

Scale 1:2000 (0, 20, 60, 100m)

Drawing No. C-050

Sheet 1 of 6

Revision 3

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DP.dwg
2020/07/28 11:42 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- LIMIT OF TOPSOIL REMOVAL
- EXISTING TREE LINE
- PROPOSED TREE LINE
- EXISTING TREES TO BE CLEARED
- OVERLAND FLOW DIRECTION
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-DP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

EXISTING CONDITIONS, CLEARING, GRUBBING AND FENCING PLAN

| Project No. | Scale | | | | |
|---|---|---|---|---|---|
| 3600727160 | 1:2000 | 0 | 20 | 50 | 100m |
| Drawing No. | Sheet | | | Revision | |
| C-050 | 2 of 6 | | | 3 | |

C:\Users\childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DP.dwg
2020/07/28 11:43 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D

ACCESS ROAD B

4.0m WIDE ACCESS ROAD

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

4.0m WIDE ACCESS ROAD

PCS11

ACCESS ROAD B

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

ACCESS ROAD A

4.0m WIDE ACCESS ROAD

PCS21

PCS22

4.0m WIDE ACCESS ROAD

ACCESS ROAD D

4.0m WIDE ACCESS ROAD

PCS20

ACCESS ROAD C

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PCS23

4.0m WIDE ACCESS ROAD

PCS24

PCS25

4.0m WIDE ACCESS ROAD

PCS26

PCS27

ACCESS ROAD D

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

ACCESS ROAD A

PROPOSED DROP DOWN GATE (DESIGNED BY OTHERS)

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PCS28

4.0m WIDE ACCESS ROAD

PCS29

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

NOTE:
CLEAR/TRIM ANY OVER GROWN WILD GRASS ON WORKING AREAS

SEE DRAWING C-050-SHEET 2

SEE DRAWING C-050-SHEET 4

N

ORANGE GROVE RD.

LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- LIMIT OF TOPSOIL REMOVAL
- EXISTING TREE LINE
- PROPOSED TREE LINE
- EXISTING TREES TO BE CLEARED
- OVERLAND FLOW DIRECTION
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-DP.dwg | | DR | IH | DR | 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

EXISTING CONDITIONS, CLEARING, GRUBBING AND FENCING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:2000 (0, 20, 60, 100m) | C-050 | 3 of 6 | 3 |

C:\Users\chlids\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DP.dwg
2020/07/28 11:44 PM By: CHlds, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING
C-050-SHEET 3

PROPOSED DROP DOWN GATE (DESIGNED BY OTHERS)

ACCESS ROAD A

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PCS30

4.0m WIDE ACCESS ROAD

PCS31

ACCESS ROAD E

PCS32

PCS33

PCS34

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PCS35

PCS36

ACCESS ROAD A

ACCESS ROAD E

PCS37

4.0m WIDE ACCESS ROAD

PCS38

PCS39

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PCS40

ACCESS ROAD F

4.0m WIDE ACCESS ROAD

PCS42

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)


PCS29

4.0m WIDE ACCESS ROAD


PROPOSED DROP DOWN GATE (DESIGNED BY OTHERS)

NOTE:
CLEAR/TRIM ANY OVER GROWN WILD GRASS ON WORKING AREAS

SEE DRAWING
C-050-SHEET 5




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- LIMIT OF TOPSOIL REMOVAL
- EXISTING TREE LINE
- PROPOSED TREE LINE
- EXISTING TREES TO BE CLEARED
- OVERLAND FLOW DIRECTION
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C-DP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EXISTING CONDITIONS, CLEARING, GRUBBING AND FENCING PLAN

Project No. 3600727160

Scale 1:2000 (0, 20, 60, 100m)

Drawing No. C-050

Sheet 4 of 6

Revision 3

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DP.dwg
2020/07/28, 11:45 PM By: C.Hetts, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING
C-050-SHEET 4

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PCS40

ACCESS ROAD E

4.0m WIDE ACCESS ROAD

PCS42

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

ACCESS ROAD A

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PCS43

ACCESS ROAD F

4.0m WIDE ACCESS ROAD

PCS44

4.0m WIDE ACCESS ROAD

PCS45

PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)


PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

PROPOSED DROP DOWN GATE (DESIGNED BY OTHERS)


PROPOSED EXTENT OF SITE FENCE (SEE SHEET C-500 FOR DETAILS)

MAIN ACCESS ROAD

SEE DRAWING
C-050-SHEET 6




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
CLEAR/TRIM ANY OVER GROWN WILD GRASS ON WORKING AREAS

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- LIMIT OF TOPSOIL REMOVAL
- EXISTING TREE LINE
- PROPOSED TREE LINE
- EXISTING TREES TO BE CLEARED
- OVERLAND FLOW DIRECTION
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C-DP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EXISTING CONDITIONS, CLEARING, GRUBBING AND FENCING PLAN

Project No. 3600727160

Scale 1:2000 (0, 20, 60, 100m)


Drawing No. C-050

Sheet 5 of 6

Revision 3

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DP.dwg
2020/07/28 11:48 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D







LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
CLEAR/TRIM ANY OVER GROWN WILD GRASS ON WORKING AREAS

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- LIMIT OF TOPSOIL REMOVAL
- EXISTING TREE LINE
- PROPOSED TREE LINE
- EXISTING TREES TO BE CLEARED
- OVERLAND FLOW DIRECTION
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED EXTENT OF SITE FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C-DP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

EXISTING CONDITIONS, CLEARING, GRUBBING AND FENCING PLAN

Project No. 3600727160

Scale 1:2000 (0, 20, 50, 100m)


Drawing No. C-050


Sheet 6 of 6

Revision 3

C:\Users\cchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DP.dwg
2020/07/28 11:44 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

## GENERAL NOTES

1. ALL DIMENSIONS ARE IN METRES UNLESS NOTED OTHERWISE.
2. COORDINATE CONTROL IS TO MAP GRID OF AUSTRALIA (MGA) ZONE 56. REDUCED LEVELS ARE TO AUSTRALIAN HEIGHT DATUM (AHD).
3. ALL SURVEY CONTROL MARKS, PERMANENT MARKS AND STATE SURVEY MARKS SHALL BE PRESERVED. WHERE DISTURBANCE OF A SURVEY MARK OCCURS OR IS UNAVOIDABLE, ADVICE MUST BE SOUGHT FROM A SURVEYOR AUTHORIZED BY THE SURVEYOR-GENERAL OR A SURVEYOR ENGAGED BY A NSW PUBLIC AUTHORITY NOTING THAT A REPLACEMENT MARK OR MARKS MAY NEED TO BE INSTALLED.
4. UTILITY ARE NOT SHOWN ON THE PLANS, THEREFORE THE PRESENCE OF A SERVICE HAS NOT BEEN ASSESSED.
5. UTITILITY INVESTIGATIONS SHALL BE UNDERTAKEN TO DETERMINE THE PRESENCE OF A SERVICE BY DIALLING PH 1100 OR FAX 1300 652 077 (DIAL BEFORE YOU DIG). CAUTION SHALL BE EXERCISED WHEN WORKING IN THE VICINITY OF ALL UTILITY SERVICES. THE PRESENCE OF A UTILITY SERVICE, ITS SIZE AND LOCATION SHALL BE CONFIRMED BY CONDUCTING DIAL BEFORE YOU DIG, FIELD INSPECTION AND ASSOCIATED INVESTIGATIONS IF WARRANTED PRIOR TO THE COMMENCEMENT OF WORKS.
5. ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE RELEVANT PROJECT RMS &/ OR THE LOCAL COUNCIL SPECIFICATIONS FOR THE WORK.
6. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH OTHER PROVIDED REPORTS, RMS SPECIFICATIONS, MODEL DRAWINGS AND WRITTEN INSTRUCTIONS. ALWAYS REFER TO TECHNICAL SPECIFICATIONS FOR FURTHER CLARIFICATION AND DETAILS.
7. ALL LOCATIONS, ORIENTATION AND LEVELS SHALL BE VERIFIED ON SITE BEFORE COMMENCING ANY CONSTRUCTION OR FABRICATION WORK. REFER DISCREPANCIES TO THE PRINCIPAL FOR CLARIFICATION BEFORE PROCEEDING WITH WORK. DO NOT OBTAIN DIMENSIONS FROM SCALING.
8. ROAD OCCUPANCY LICENSES (ROLS) SHALL BE OBTAINED FROM RMS PRIOR TO IMPLEMENTATION OF ANY CLOSURE OF CURRENT LIVE TRAFFIC LANE OR ROAD REGARDLESS OF DETAILS SHOWN WITHIN THESE DRAWINGS.

DRAINAGE
9. ALL BATTERS SHALL BE TRAVERSIBLE DURING OPERATION I.E. LESS THAN OR EQUAL TO 1:4
10. THE CONTROL AND MANAGEMENT OF EXISTING STORMWATER FLOWS THROUGH AND AROUND ALL WORK SITES DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

EXISTING DRAINGE PITS AND PIPES (IF ANY)
1. THE EXISTING STORMWATER DRAINAGE PIT AND PIPE LAYOUT SHOWN ON THE DRAWINGS ARE INDICATIVE ONLY. WHERE A NEW CONNECTION OR EXTENSION IS TO BE MADE TO ANY EXISTING PIT OR PIPE, ALL LOCATIONS, ORIENTATIONS AND REDUCED LEVELS AT THE PROPOSED CONNECTION POINT SHALL BE VERIFIED ON SITE BEFORE COMMENCING ANY WORK.

GEOTECHNICAL
1. ALL EARTHWORKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE REQUIREMENTS OF RMS SPECIFICATION R44 AND ASSOCIATED COUNCIL SPECIFICATIONS.
2. GEOTECHNICAL INSPECTIONS SHALL BE CARRIED OUT BY GEOTECHNICAL ENGINEER IN ACCORDANCE WITH RMS SPECIFICATION R44 REQUIREMENTS. WHERE RECTIFICATIONS ARE REQUIRED, RE-INSPECTION SHALL BE CARRIED OUT.

TEMPORARY TRAFFIC CONTROL
1. TEMPORARY TRAFFIC CONTROL AT PUBLIC ROAD INTERFACES ETC. SHALL BE IN ACCORDANCE WITH TRAFFIC CONTROL AT WORK SITE TECHNICAL MANUAL ROADS AND MARITIME SERVICES 27 JULY, 2018


TEMPORARY DRAINAGE STRUCTURES
1. STRUCTURES HAVE BEEN DESIGNED FOR OPERATIONAL LOADS (SM1600 WHERE UNDER OR ADJACENT TO ROADWAYS) ACTING ON COMPLETED STRUCTURES. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND PROVISION OF ANY TEMPORARY BRACING, PROPPING, ETC. REQUIRED DURING CONSTRUCTION. STRUCTURES SHALL BE MAINTAINED IN A STABLE CONDITION AND NO PART SHALL BE OVERSTRESSED.
2. INADEQUATE FOUNDATION MATERIAL FOR PIPES AND STRUCTURES SHALL BE REMOVED OR IMPROVED IN ACCORDANCE WITH COUNCIL SPECIFICATIONS.
3. ALL SETOUT POINTS QUOTED FOR DRAINAGE STRUCTURES REFER RELEVANT DESIGN DRAWING, RMS MODEL DRAWING OR PRODUCT SPECIFICATION.

JOINT AT EXISTING ROAD
1. EXCAVATION INTO THE EXISTING ORANGE GROVE ROAD SHALL BE MINIMIZED AS FAR AS PRACTICABLE BUT STILL ENSURE THAT ANY LOOSE OR DEGRADED SHOULDER MATERIAL HAS BEEN REMOVED PRIOR TO PLACEMENT OF THE NEW MATERIAL
2. PLACEMENT OF THE CONSTRUCTION JOINT NOT OCCUR IN THE WHEELPATHS OF TRAFFIC USING ORANGE GROVE ROAD AS THIS WILL LIKELY RESULT IN ACCELERATED FAILURE OF THE PAVEMENT AND SURFACING. IT SHALL BE SITUATED ON OR AS CLOSE TO THE SHOULDER OF THE ROAD AS PRACTICABLE.
3. PARTICULAR ATTENTION SHALL BE MADE TO ACHIEVING SUFFICIENT COMPACTION AT THE CONSTRUCTION JOINT. IT IS RECOMMENDED TO TREAT THE JOINT AS A SEPARATE WORK LOT WITH AN INCREASED AMOUNT OF COMPACTION TESTING REQUIRED AS PART OF THE CONTRACTOR'S QUALITY MANAGEMENT PLAN.
4. SEE JOINT DETAIL ON THIS SHEET.

GEOTEXTILE
1. ALL GEOTEXTILE FABRIC TO BE BIDIM A64 (OR APPROVED EQUIVALENT) UNLESS NOTED OTHERWISE.

DRAINAGE PIPES
1. ALL DRAINAGE PIPES ARE TO BE PRECAST REINFORCED CLASS 4 CONCRETE PIPES TO AS/NZS 4058 AND RUBBER RING JOINTED SPIGOT AND SOCKET TYPE UNLESS NOTED OTHERWISE.
2. CONCRETE PIPE INSTALLATION TO BE TYPE HS3 SUPPORT IN ACCORDANCE WITH RMS MD.R11.A01.B OR COUNCIL APPROVED EQUIVELANT.
3. CONCRETE PIPE CLASSES HAVE BEEN DETERMINED FOR OPERATIONAL TRAFFIC LOADING ONLY (SM1600 AND HLP400 WHERE UNDER OR ADJACENT TO ROADWAYS). PIPE CLASSES ASSUME TYPE HS3 SUPPORT AND A 0.3 x O.D. POSITIVE PROJECTION TO AS/NZS 3725 AND RMS SPECIFICATION UNLESS NOTED OTHERWISE.
5. CONNECTION BETWEEN PIPES AND STRUCTURES TO BE UNDERTAKEN IN ACCORDANCE WITH RMS SPECIFICATION R11 RMS MODEL DRAWINGS UNLESS NOTED OTHERWISE.
6. CONTRACTOR IS RESPONSIBLE FOR DETERMINING OR CONFIRMING WITH THE DESIGNER THE MINIMUM COVER IS ACCORDANCE WITH THE PIPE CLASS DURING CONSTRUCTION, TO SUIT CONSTRUCTION METHODOLOGY UTILISED.

LINEMARKING
1. RAISED RETRO REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED ON ALL LANE, EDGE & BARRIER LINES.
2. LINEMARKING AND SIGN POSTING TO BE IN ACCORDANCE WITH RMS DELINEATION GUIDELINES, THE RELEVANT RMS TECHNICAL DIRECTIONS, COMPLEMENTARY GUIDELINES, RMS AUSTROAD & AUSTRALIAN STANDARDS SUPPLEMENTS, AUSTRALIAN STANDARD 1742 AND RMS SPECIFICATIONS.
3. EXISTING PAVEMENT MARKS AND RRPMS CONFLICTING WITH CURRENT AND PROPOSED LINEMARKING AND PAVEMENT MARKS TO BE REMOVED USING AN RMS APPROVED METHOD.
4. WHERE BARRIERS ARE LOCATED LESS THAN OR EQUAL TO 4m FROM THE EDGE LINE, REFLECTORS ARE TO BE MOUNTED ON THE BARRIER. RED CORNER CUBE REFLECTORS TO BE PLACED ON TOP OF EVERY OTHER BARRIER UNIT (ON LEFT HAND SIDE OF THE CARRIAGEWAY) STARTING THE FIRST BARRIER.
5. LINE MARKINGS TO BE APPLIED IN ACCORDANCE WITH RMS SPECIFICATION R141 USING WATER BORNE PAINT UNO.
6. EXTENTS OF TEMPORARY LINEMARKING THAT ARE TO BE REMOVED AT THE END OF THE PROJECT WILL NEED TO BE REMOVED AND REPLACED BY MILLING AND RESHEETING WITH A 50mm AC14 (A15E) WEARING COURSE.




JOINT AT EXISTING ROAD

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_MAIN.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ORANGE GROVE ROAD
PLAN VIEW

Project No. 3600727160
Scale 1:1000 (0, 10, 30, 50m)
Drawing No. C-200
Sheet 1 of 14
Revision 3

C:\Users\childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_MAIN.dwg
2020/07/27 1:12 AM By: Childs, Josh

ORIGINAL SHEET - ARCH D






R4-1 (20)




TYPICAL CROSS–SECTION OF ROAD SIDE DRAINAGE SWALE




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.00% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C–500
- SILT SOXX SEE DETAIL ON SHEET C–500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C–500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

File Name: 3600727160_C_PP_MAIN.dwg — Dwn. DR — Chkd. IH — Dsgn. DR — 19.12.16 (YY.MM.DD)

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

MAIN ACCESS ROAD
PLAN & PROFILE
STA. 0+000 TO 0+525

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)

Drawing No. C-200

Sheet 2 of 14

Revision 3

Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS


Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing – any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

C:\Users\chilish\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_MAIN.dwg
2020/07/27 12:02 AM By: C.Hish, Jason


ORIGINAL SHEET - ARCH D





R4-1 (20)





TYPICAL CROSS-SECTION OF ROAD SIDE DRAINAGE SWALE





TYPICAL CROSS-SECTION IRRIGATION CHANNEL SECTION A





LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_MAIN.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
MAIN ACCESS ROAD
PLAN & PROFILE
STA. 0+525 TO 0+1150


| Project No. | Scale | Revision |
|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | |
| Drawing No. | Sheet | |
| C-200 | 3 of 14 | 3 |


C:\Users\chitkin\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_MAIN.dwg
2020/07/27 12:01 AM By: Chitkin, Jason


ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing – any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_A.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD A
PLAN & PROFILE
STA. 0+000 TO 1+175


| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-200 | 4 of 14 | 3 |


C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_A.dwg
2020/07/27 11:16 AM By: Childs, Jason


ORIGINAL SHEET - ARCH D









NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.00% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_A.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD A
PLAN & PROFILE
STA. 1+165 TO 2+100


| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-200 | 5 of 14 | 3 |


C:\Users\chikb\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_A.dwg
2020/07/27 1:18 AM By: Chikb, Jason


ORIGINAL SHEET - ARCH D




## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | |
|---|---|---|---|
| File Name: 3600727160_C_PP_ACCESS_B.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD B
PLAN & PROFILE
STA. 0+000 TO 1+170


| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-200 | 6 of 14 | 3 |


C:\Users\chlab\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_B.dwg
2020/07/27 1:17 AM By: Chlab, Jason


ORIGINAL SHEET - ARCH D









NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_B.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD B
PLAN & PROFILE
STA. 1+170 TO 2+225


| Project No. | Scale | |
|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | |
| Drawing No. | Sheet | Revision |
| C-200 | 7 of 14 | 3 |


C:\Users\chiltds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_B.dwg
2020/07/27 1:18 AM By: Childs, Jason


ORIGINAL SHEET - ARCH D

















NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_PP_ACCESS_B.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title


ACCESS ROAD B
PLAN & PROFILE
STA. 2+225 TO 3+225


| Project No. | Scale | |
|---|---|---|
| 3600727160 | 1:1000 | 0 10 30 50m |
| Drawing No. | Sheet | Revision |
| C-200 | 8 of 14 | 3 |


C:\Users\jhhbs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_B.dwg
2020/07/27 1:22 AM By: O'Neill, Jason


ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.00% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_C.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD C
PLAN & PROFILE
STA. 0+000 TO 1+200

| Project No. | Scale |
|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) |

| Drawing No. | Sheet | Revision |
|---|---|---|
| C-200 | 9 of 14 | 3 |

C:\Users\jchilton\Desktop\working Folder\3600727140 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727140_C_PP_ACCESS_C.dwg
2020/07/27 12:1 AM By: CHilds, Jason

ORIGINAL SHEET - ARCH D






KEY MAP
N.T.S.

LOCALITY MAP
N.T.S.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.




## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_PP_ACCESS_C.dwg | | DR | IH | DR 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

ACCESS ROAD C
PLAN & PROFILE
STA. 1+200 TO 1+735

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-200 | 10 of 14 | 3 |

NOT FOR CONSTRUCTION


Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.


Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

C:\Users\jchitsi\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_C.dwg
2020/07/27 12:21 AM By: Chitsi, Jason


ORIGINAL SHEET - ARCH D










LOCALITY MAP
N.T.S.


KEY MAP
N.T.S.




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_D.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD D
PLAN & PROFILE
STA. 0+000 TO 1+135


| Project No. | Scale | Sheet | Revision |
|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | 11 of 14 | 3 |


Drawing No.
C-200


C:\Users\chlich\Desktop\working Folder\3600727140 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727140_C_PP_ACCESS_D.dwg
2020/07/27 1:23 AM By: Chlich, Jason


ORIGINAL SHEET - ARCH D


















NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_D.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD D
PLAN & PROFILE
STA. 1+135 TO 2+320


| Project No. | Scale |
|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) |


| Drawing No. | Sheet | Revision |
|---|---|---|
| C-200 | 12 of 14 | 3 |


C:\Users\jchiba\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_D.dwg
2020/07/27 12:24 AM By: Chiba, Jason


ORIGINAL SHEET - ARCH D









## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_E.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT
765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD E
PLAN & PROFILE
STA. 0+000 TO 1+150


Project No. 3600727160
Scale 1:1000 (0 10 30 50m)
Drawing No. C-200
Sheet 13 of 14
Revision 3


NOT FOR CONSTRUCTION


C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_E.dwg
2020/07/27 1:24 AM By: Childs, Jason


ORIGINAL SHEET - ARCH D









NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_PP_ACCESS_E.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD E
PLAN & PROFILE
STA. 1+150 TO 2+235


Project No. 3600727160
Scale 1:1000 (0, 10, 30, 50m)
Drawing No. C-200
Sheet 14 of 14
Revision 3


C:\Users\childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_E.dwg
2020/07/27 7:23 AM By: Childs, Jason


ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_PP_ACCESS_F.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
ACCESS ROAD F
PLAN & PROFILE
STA. 0+000 TO 0+850

Project No. 3600727160
Scale 1:1000 (0, 10, 30, 50m)
Drawing No. C-200
Sheet 15 of 14
Revision 3

C:\Users\chlds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_file\3600727160_C_PP_ACCESS_F.dwg
2020/07/27 1:29 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D





LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.




NOT FOR CONSTRUCTION

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)

| | | | | |
|---|---|---|---|---|
| 3 | REVISED PER UPDATED SITE PLAN | DR/JC | IH | 20.07.20 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

File Name: 3600727160_C_PP_ACCESS_F.dwg — Dwn. DR — Chkd. IH — Dsgn. DR — 19.12.16 YY.MM.DD

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

ACCESS ROAD F
PLAN & PROFILE
STA. 0+850 TO 1+375

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)

Drawing No. C-200

Sheet 16 of 14

Revision 3


Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

C:\Users\chlds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_PP_ACCESS_F.dwg
2020/07/27 1:30 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D




Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- PROPOSED ELEVATION
- MATCH TO EXISTING ELEVATION
- SWALE
- EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

Project No. 3600727160
Scale 1:1000 (0, 10, 30, 50m)
Drawing No. C-400
Sheet 1 of 19
Revision 3

C:\Users\cfields\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/28 11:58 PM By: Cfields, Jason

ORIGINAL SHEET - ARCH D







LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA
  PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title

GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-400 | 2 of 19 | 3 |

C:\Users\chtds\Desktop\working Folder\3600727160 - Gunnedah SolarV\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/28, 11:51 PM By: Chtds, Jdsm

ORIGINAL SHEET - ARCH D




NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- PROPOSED ELEVATION
- MATCH TO EXISTING ELEVATION
- SWALE
- EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_GP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

| Project No. | Scale | | | | |
|---|---|---|---|---|---|
| 3600727160 | 1:1000 | 0 | 10 | 30 | 50m |
| Drawing No. | Sheet | | Revision | | |
| C-400 | 3 of 19 | | 3 | | |


Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com


PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah SolarDesign\Drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/28, 11:52 PM By: Childs, Jason
ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 2




NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA
- PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-400 | 4 of 19 | 3 |

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah SolarV\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/28, 11:54 PM By: Childs, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 5




SEE DRAWING C-400-SHEET 4

SEE DRAWING C-400-SHEET 6

SEE DRAWING C-400-SHEET 7




## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- x 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA
- PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | | DR | IH | DR | 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-400 | 5 of 19 | 3 |


NOT FOR CONSTRUCTION

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

C:\Users\Childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/28 11:53 PM By: Childs, Jason
ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

| | |
|---|---|
| 185.19 | PROPOSED ELEVATION |
| 185.19(EX) | MATCH TO EXISTING ELEVATION |
| | SWALE |
| 184.5 | EXISTING TOPOGRAPHIC SURVEY CONTOUR |
| | OVERLAND FLOW DIRECTION |
| 2.0% | GRADE |
| | SLOPE (4:1 UNLESS NOTED OTHERWISE) |
| | HARDENED SURFACE |
| | CULVERT |
| | TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE) |
| | TREE LINE |
| | PROPOSED CUT AREA<br>PROPOSED FILL AREA |
| | PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS) |
| | PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS) |
| | APPROXIMATE LOCATION OF PROPERTY LINES |

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-400 | 6 of 19 | 3 |


C:\Users\cfields\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:52 AM By: CFields, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 5

SEE DRAWING C-400-SHEET 4

SEE DRAWING C-400-SHEET 8







LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA
  PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_GP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-400 | 7 of 19 | 3 |

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:53 AM By: CHilds, Jason

ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED




## Legend

PROPOSED

- ×185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

| Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|
| 3 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_GP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

Project No. 3600727160
Scale 1:1000 (0, 10, 30, 50m)
Drawing No. C-400
Sheet 8 of 19
Revision 3

C:\Users\childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:53 AM By: CHilds, Jason

ORIGINAL SHEET - ARCH D







NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA
  PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-400 | 9 of 19 | 3 |

C:\Users\chibbs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:54 AM By: CHibbs, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 9




SEE DRAWING C-400-SHEET 8

SEE DRAWING C-400-SHEET 12

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED




LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_GP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
GRADING PLAN

Project No. 3600727160
Scale 1:1000 (0, 10, 30, 50m)
Drawing No. C-400
Sheet 10 of 19
Revision 3

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:53 AM By: CHilds, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 8




NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTAITVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- x 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-400 | 11 of 19 | 3 |

Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

C:\Users\chilton\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:51 AM By: Chilton, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 10

SEE DRAWING C-400-SHEET 11

SEE DRAWING C-400-SHEET 14




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

| | |
|---|---|
| PROPOSED | |
| x 185.19 | PROPOSED ELEVATION |
| 185.19(EX) | MATCH TO EXISTING ELEVATION |
| | SWALE |
| 184.5 | EXISTING TOPOGRAPHIC SURVEY CONTOUR |
| | OVERLAND FLOW DIRECTION |
| 2.0% | GRADE |
| | SLOPE (4:1 UNLESS NOTED OTHERWISE) |
| | HARDENED SURFACE |
| | CULVERT |
| | TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE) |
| | TREE LINE |
| | PROPOSED CUT AREA<br>PROPOSED FILL AREA |
| | PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS) |
| | PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS) |
| | APPROXIMATE LOCATION OF PROPERTY LINES |

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_GP.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-400 | 12 of 19 | 3 |

C:\Users\chlds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:58 AM By: CHlds, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 11




NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

SEE DRAWING C-400-SHEET 14

SEE DRAWING C-400-SHEET 15

NOT FOR CONSTRUCTION




LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

| | |
|---|---|
| PROPOSED | |
| x 185.19 | PROPOSED ELEVATION |
| 185.19(EX) | MATCH TO EXISTING ELEVATION |
| | SWALE |
| 184.5 | EXISTING TOPOGRAPHIC SURVEY CONTOUR |
| | OVERLAND FLOW DIRECTION |
| 2.0% | GRADE |
| | SLOPE (4:1 UNLESS NOTED OTHERWISE) |
| | HARDENED SURFACE |
| | CULVERT |
| | TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE) |
| | TREE LINE |
| | PROPOSED CUT AREA<br>PROPOSED FILL AREA |
| | PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS) |
| | PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS) |
| | APPROXIMATE LOCATION OF PROPERTY LINES |

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

| | Revision | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN


| Project No. | Scale | |
|---|---|---|
| 3600727160 | 1:1000 | 0 10 30 50m |
| Drawing No. | Sheet | Revision |
| C-400 | 13 of 19 | 3 |

C:\Users\childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 1:12 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D


SEE DRAWING C-400-SHEET 12

SEE DRAWING C-400-SHEET 13




SEE DRAWING C-400-SHEET 14

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

| | |
|---|---|
| PROPOSED | |
| x 185.19 | PROPOSED ELEVATION |
| 185.19(EX) | MATCH TO EXISTING ELEVATION |
| | SWALE |
| 184.5 | EXISTING TOPOGRAPHIC SURVEY CONTOUR |
| | OVERLAND FLOW DIRECTION |
| 2.0% | GRADE |
| | SLOPE (4:1 UNLESS NOTED OTHERWISE) |
| | HARDENED SURFACE |
| | CULVERT |
| | TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE) |
| | TREE LINE |
| | PROPOSED CUT AREA<br>PROPOSED FILL AREA |
| | PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS) |
| | PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS) |
| | APPROXIMATE LOCATION OF PROPERTY LINES |

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)


Drawing No. C-400


Sheet 14 of 19

Revision 3

C:\Users\jchilds\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 11:11 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D


SEE DRAWING C-400-SHEET 13
SEE DRAWING C-400-SHEET 16
SEE DRAWING C-400-SHEET 17
ACCESS ROAD A
ACCESS ROAD F
PVI=287.72
PVI=287.95
PVI=287.68
PVI=288.10
PVI=287.89
PVI=288.18
PVI=288.04
PVI=288.29
PVI=288.14
PVI=288.30
PVI=288.17
PVI=287.95
PVI=287.85
PVI=288.31
EVC=287.74
BVC=288.24
EVC=288.61
BVC=288.12
INVERT=267.39
INVERT=267.45
INVERT=267.50
68.20
68.46
68.51
67.86
68.10
67.22
67.37
67.45
67.61
67.56
68.18
68.50
68.28
67.51
67.50
69.70
69.97
68.03
68.00
68.08
68.08
67.94
67.99
68.00
67.99
68.00
67.99
68.00







NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

| | |
|---|---|
| 185.19 | PROPOSED ELEVATION |
| 185.19(EX) | MATCH TO EXISTING ELEVATION |
| | SWALE |
| 184.5 | EXISTING TOPOGRAPHIC SURVEY CONTOUR |
| | OVERLAND FLOW DIRECTION |
| 2.0% | GRADE |
| | SLOPE (4:1 UNLESS NOTED OTHERWISE) |
| | HARDENED SURFACE |
| | CULVERT |
| | TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE) |
| | TREE LINE |
| | PROPOSED CUT AREA<br>PROPOSED FILL AREA |
| | PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS) |
| | PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS) |
| | APPROXIMATE LOCATION OF PROPERTY LINES |

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | | DR | IH | DR | 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)

Drawing No. C-400

Sheet 16 of 19


Revision 3

C:\Users\childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 1:09 AM By: Childs, Josh

ORIGINAL SHEET - ARCH D

SEE DRAWING C-400-SHEET 15




NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | | DR | IH | DR | 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-400 | 17 of 19 | 3 |

C:\Users\jchibb\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 1:03 AM By: CHibb, Jason

ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED
- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
# GRADING PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)


Drawing No. C-400

Sheet 18 of 19

Revision 3

C:\Users\childs\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 1:00 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D




NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 185.19 — PROPOSED ELEVATION
- 185.19(EX) — MATCH TO EXISTING ELEVATION
- SWALE
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- 2.0% — GRADE
- SLOPE (4:1 UNLESS NOTED OTHERWISE)
- HARDENED SURFACE
- CULVERT
- TEMPORARY LAYDOWN AREA (MATERIAL TO BE DETERMINED ON SITE)
- TREE LINE
- PROPOSED CUT AREA
  PROPOSED FILL AREA
- PROPOSED ACCESS FENCE SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_GP.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
GRADING PLAN


| Project No. | Scale | Revision |
|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | |
| Drawing No. | Sheet | |
| C-400 | 19 of 19 | 3 |

C:\Users\jchiba\Desktop\working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_GP.dwg
2020/07/27 12:39 AM By: CHiba, Jason


ORIGINAL SHEET - ARCH D

## ROAD CONSTRUCTION NOTES

1. THE FOREGOING DESIGN ASSUMES THAT CONSTRUCTION IS CARRIED OUT DURING DRY PERIODS AND THE SUB-GRADE IS STABLE UNDER THE LOAD OF CONSTRUCTION EQUIPMENT. IF CONSTRUCTION IS CARRIED OUT DURING WET WEATHER AND HEAVING OR ROLLING OF THE SUB-GRADE IS EXPERIENCED, ADDITIONAL THICKNESS OF GRANULAR ROAD BASE MAY BE REQUIRED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER.
2. THE LONG-TERM PERFORMANCE OF THE ROAD BASE STRUCTURE IS DEPENDENT UPON THE SUB-GRADE SUPPORT CONDITIONS. STRINGENT CONSTRUCTION CONTROL PROCEDURES SHALL BE MAINTAINED TO ENSURE THAT UNIFORM SUB-GRADE MOISTURE AND DENSITY CONDITIONS ARE ACHIEVED. IF, DURING THE EXCAVATION PROCESS, NATIVE MATERIAL APPEARS SUITABLE TO BE USED AS ROAD SUB-BASE A GRAIN SIZE ANALYSIS MUST BE COMPLETED TO DETERMINE IF THE MATERIAL CAN BE LEFT IN PLACE AND WHETHER A REDUCTION IN DEPTH OF THE GRANULAR ROAD STRUCTURE IS WARRANTED. THE UNDERLYING SUB-GRADE SHALL BE FREE OF DEPRESSIONS AND IS TO BE SLOPED TO PROVIDE POSITIVE SURFACE DRAINAGE. SURFACE WATER SHALL NOT BE PERMITTED TO POND ADJACENT TO THE OUTSIDE EDGES.
3. AS PART OF THE SUB-GRADE PREPARATION, PROPOSED ROADWAYS SHALL BE STRIPPED OF TOPSOIL AND UNSUITABLE MATERIAL. FILL REQUIRED TO RAISE THE SUB-GRADE TO DESIGN ELEVATIONS SHALL BE ORGANIC-FREE AND SHALL HAVE A MOISTURE CONTENT WHICH WILL PERMIT COMPACTION TO THE DENSITIES INDICATED. THE SUB-GRADE SHALL BE SHAPED AND THEN PROOF-ROLLED IN THE PRESENCE OF A GEOTECHNICAL CONSULTANT. SOFT OR SPONGY SUB-GRADE AREAS SHALL BE SUB-EXCAVATED AND REPLACED WITH SUITABLE APPROVED BACKFILL COMPACTED TO 98 PERCENT SPMDD.





FILTREXX SILTSOXX DETAIL
OR APPROVED EQUIVALENT
NTS





NOTE:
CONTRACTOR MAY PROVIDE METAL ENTRANCE MAT UPON ACCEPTANCE OF THE ENGINEER

CONSTRUCTION ENTRANCE MAT





| PIPE SIZE DN (NOMINAL INTERNAL DIAMETER) | MINIMUM DEPTH* (mm) | | | MINIMUM DISTANCE (mm) | | | |
|---|---|---|---|---|---|---|---|
| | BED | HAUNCH | SIDE | SELECT FILL | | CLSM | |
| | A | B | C | $I_1$ | $I_2$ | $I_1$ | $I_2$ |
| 375 | 100 | 175 | 110 | 400 | 400 | 100 | 100 |
| 450 | 100 | 200 | 130 | 400 | 400 | 100 | 100 |
| 525 | 100 | 225 | 150 | 400 | 400 | 100 | 170 |
| 600 | 100 | 250 | 170 | 400 | 500 | 140 | 180 |
| 675 | 100 | 280 | 190 | 400 | 500 | 150 | 190 |
| 750 | 100 | 310 | 210 | 400 | 500 | 150 | 200 |
| 825 | 100 | 330 | 230 | 400 | 500 | 150 | 200 |
| 900 | 100 | 360 | 240 | 400 | 500 | 160 | 210 |
| 1 050 | 100 | 420 | 280 | 400 | 500 | 160 | 220 |
| 1 200 | 100 | 475 | 310 | 400 | 500 | 170 | 230 |
| 1 350 | 100 | 530 | 350 | 400 | 500 | 170 | 240 |
| 1 500 | 100 | 585 | 390 | 400 | 500 | 180 | 260 |
| 1 650 | 100 | 630 | 420 | 400 | 500 | 190 | 280 |
| 1 800 | 100 | 680 | 370 | 400 | 600 | 200 | 290 |
| 2 100 | 100 | 790 | 470 | 400 | 600 | 200 | 290 |





HARDENED SURFACE ACCESS ROAD DETAIL
NTS




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
BASE-COURSE DRY-BACK REQUIREMENTS: THE FIELD MOISTURE CONTENT OF BASE-COURSE MATERIAL TO RECEIVE A BITMINOUS SEAL MUST NOT EXCEED 70% OF THE BASE MATERIAL'S OPTIMUM MOISTURE CONTENT AT THE TIME THAT THE BITUMINOUS SEAL IS APPLIED.


TYPICAL CROSS-SECTION 5.5m/6.5m WIDE UNSEALED ACCESS ROAD FROM ORANGE GROVE ROAD TO SUBSTATION DETAIL (FILL)
NTS




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 14/7mm DOUBLE/DOUBLE SEAL WITH A CLASS 170 OR HIGHER BINDER TYPE.
4 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
BASE-COURSE DRY-BACK REQUIREMENTS: THE FIELD MOISTURE CONTENT OF BASE-COURSE MATERIAL TO RECEIVE A BITMINOUS SEAL MUST NOT EXCEED 70% OF THE BASE MATERIAL'S OPTIMUM MOISTURE CONTENT AT THE TIME THAT THE BITUMINOUS SEAL IS APPLIED.


TYPICAL CROSS-SECTION 5.5m/6.5m WIDE SEALED ACCESS ROAD FROM ORANGE GROVE ROAD TO SUBSTATION DETAIL (FILL)
NTS




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
BASE-COURSE DRY-BACK REQUIREMENTS: THE FIELD MOISTURE CONTENT OF BASE-COURSE MATERIAL TO RECEIVE A BITMINOUS SEAL MUST NOT EXCEED 70% OF THE BASE MATERIAL'S OPTIMUM MOISTURE CONTENT AT THE TIME THAT THE BITUMINOUS SEAL IS APPLIED.

TYPICAL CROSS-SECTION 5.5m/6.5m WIDE UNSEALED ACCESS ROAD FROM ORANGE GROVE ROAD TO SUBSTATION DETAIL (CUT)
NTS




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 14/7mm DOUBLE/DOUBLE SEAL WITH A CLASS 170 OR HIGHER BINDER TYPE.
4 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
BASE-COURSE DRY-BACK REQUIREMENTS: THE FIELD MOISTURE CONTENT OF BASE-COURSE MATERIAL TO RECEIVE A BITMINOUS SEAL MUST NOT EXCEED 70% OF THE BASE MATERIAL'S OPTIMUM MOISTURE CONTENT AT THE TIME THAT THE BITUMINOUS SEAL IS APPLIED.

TYPICAL CROSS-SECTION 5.5m/6.5m WIDE SEALED ACCESS ROAD FROM ORANGE GROVE ROAD TO SUBSTATION DETAIL (CUT)
NTS

## EROSION AND SEDIMENT CONTROL NOTES:
## (SEE DETAILS THIS SHEET)


1. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES TO PROVIDE FOR PROTECTION OF THE AREA DRAINAGE SYSTEM DURING CONSTRUCTION ACTIVITIES. THIS INCLUDES LIMITING THE AMOUNT AND DURATION OF EXPOSED SOIL AND INSTALLING SILT FENCES AND OTHER SEDIMENT TRAPS/FILTERS SIMILAR TO THOSE ILLUSTRATED HEREIN.
2. EROSION AND SEDIMENT CONTROL WORKS SHALL BE INSTALLED AND IN WORKING CONDITION PRIOR TO COMMENCEMENT OF CONSTRUCTION RELATED ACTIVITIES.
3. SEDIMENT CONTROL MEASURES ADJACENT TO CONSTRUCTION AREAS MAY REQUIRE REMOVAL / RELOCATION IN ORDER TO COMPLETE SPECIFIC CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL ENSURE THAT ADEQUATE SEDIMENT CONTROL MEASURES ARE IN PLACE AT ALL TIMES.
4. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN AND BOLSTER EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY TO KEEP THEM EFFECTIVE AND MINIMIZE THE POTENTIAL FOR EROSION AND MIGRATION OF SEDIMENT TO THE DOWNSTREAM NATURAL ENVIRONMENT
5. AT THE DISCRETION OF THE OWNER OR OWNER'S CONSULTANT, ADDITIONAL SILT CONTROL DEVICES SHALL BE INSTALLED AT DESIGNATED LOCATIONS.
6. STOCKPILED MATERIAL IS TO BE STORED AWAY FROM WATER BODIES, WETLANDS AND OTHER SENSITIVE RECEIVERS IN A MANNER THAT PREVENTS ANY DELETERIOUS SUBSTANCE FROM ENTERING THAT FEATURE AND BE SURROUNDED BY EROSION CONTROL MEASURE WHERE MATERIAL IS TO BE LEFT IN PLACE IN EXCESS OF 10 DAYS OR PRIOR TO A RAIN EVENT, WHICHEVER OCCURS SOONER.
7. SEDIMENT THAT IS ACCUMULATED BY THE TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES SHALL BE REMOVED IN A MANNER THAT AVOIDS ESCAPE OF THE SEDIMENT TO THE DOWNSTREAM SIDE OF THE CONTROL MEASURE AND AVOIDS DAMAGE TO THE CONTROL MEASURE. ALL SEDIMENT SHALL BE REMOVED AND TOPSOIL WITH SEED TO BE ADDED IF NECESSARY.
8. SILT FENCE AND EROSION CONTROL STRUCTURES TO BE CHECKED DAILY AND AFTER EACH RAINFALL (>10mm) BY A QUALIFIED INSPECTOR FOR DEFICIENCIES. SEDIMENT SHALL BE REMOVED WHEN THE LEVEL OF SEDIMENT DEPOSITION REACHES ONE THIRD OF THE WAY TO THE TOP OF THE BARRIER.
9. STOCKPILED MATERIAL IS TO BE STORED A SUFFICIENT DISTANCE FROM WATERCOURSES, TO PRECLUDE SEDIMENT INPUTS DUE TO EROSION OF STORED SOIL MATERIALS. WHERE STOCKPILED EXCAVATED NATIVE MATERIALS AND IMPORTED MATERIALS WITH A D50 LESS THAN 4.75mm ARE TO BE LEFT IN PLACE UNDISTURBED IN EXCESS OF 30 DAYS, STOCKPILES ARE TO BE COVERED WITH A ROLLED EROSION CONTROL PRODUCT (RECP) SUCH AS A TARP, SINGLE NET STRAW MAT OR DOUBLE NET STRAW MAT. IMPORTED MATERIALS WITH A D50 OF 4.75mm OR GREATER CAN REMAIN UNCOVERED. EROSION AND SEDIMENT CONTROL MONITORING PROCESS SHALL BE KEPT AND MADE AVAILABLE TO THE MINISTRY OF ENVIRONMENT AND CLIMATE CHANGE UPON REQUEST.
10. IN THE EVENT OF INCLEMENT WEATHER OR UNFAVOURABLE TERRAIN FOR CONSTRUCTION, CONSTRUCTION BEST PRACTICES, SUCH AS TEMPORARY RIG-MATS MAY BE USED TO PREVENT DISRUPTION OF SURFACE SOILS AND VEGETATIVE COVER BY CONSTRUCTION VEHICLES AND EQUIPMENT.
11. EQUIPMENT AND CONSTRUCTION MATERIAL SHALL BE STORED AWAY FROM WATER BODIES IN A MANNER THAT PREVENTS ANY DELETERIOUS SUBSTANCE FROM ENTERING THE WATER, REFUELLING OF MACHINERY AND GENERATORS SHALL NOT BE CONDUCTED WITHIN 30m OF A WATER BODY OR WETLAND AND SHALL BE COMPLETED IN A CONTROLLED MANNER WITH ADEQUATE SPILL PROTECTION ON SITE
12. PUBLIC ROADS TO BE CLEANED OF ACCUMULATED SEDIMENT CAUSED BY CONSTRUCTION AS REQUIRED.
13. IN ADDITION TO BEING RESPONSIBLE FOR ENSURING THAT THE PRESCRIBED MEASURES ARE INSTITUTED AND FUNCTIONING AS INTENDED, THE CONTRACTOR IS ALSO RESPONSIBLE FOR IMPLEMENTING ANY INTERIM OR EMERGENCY MEASURES REQUIRED, TO ENSURE THAT NO SEDIMENT IS DISCHARGED TO THE NATURAL ENVIRONMENT. THE FOLLOWING EXTRA EQUIPMENT/MATERIALS ARE TO BE KEPT ON SITE AS A CONTINGENCY, IN CASE THE PROPOSED CONTROL MEASURES ARE BREACHED.
    - SILT FENCE
    - FILTER CLOTH
    - PUMPS
    - CLEAN RIP-RAP (FREE OF FINES) FOR ROCK CHECK DAMS
    - SAND BAGS
    - ANY ADDITIONAL MATERIAL DEEMED NECESSARY TO REPAIR/ CONSTRUCT PROPOSED MEASURES OR TO ADEQUATELY DEAL WITH UNEXPECTED HIGH FLOWS

## DURING AREA GRADING :

1. TOPSOIL IS TO BE STRIPPED ONLY IN AREAS REQUIRING EARTHWORKS AND PLACED IN STOCKPILES AT THE LOCATIONS SHOWN ON THE PLANS OR AS APPROVED BY THE QUALIFIED ENVIRONMENTAL SITE INSPECTOR.
2. ROADWAYS AND LAY DOWN YARDS ARE TO BE PLACED ON NATIVE GROUND AFTER TOPSOIL HAS BEEN STRIPPED
3. ALL TOPSOIL IS TO BE RE-SPREAD THROUGHOUT THE PROJECT EXTENTS.
4. NO TOPSOIL MAY BE EXPORTED FROM THE SITE.

## PAVEMENT:

1. PROPOSED NEW PAVEMENTS HAVE BEEN DESIGNED BASED ON A DESIGN SUBGRADE AS SHOWN ON THE PROFILES ON DRAWING NUMBER C-500. WHERE THE EXISTING SUBGRADE IS LESS THAN DESIGN SUBGRADE, THE GEOTECHNICAL AND PAVEMENT ENGINEER SHALL BE CONSULTED
2. IF REQUIRED TRENCH AND EDGE DRAINS ARE TO BE PLACED AS INDICATED ON THE DRAWINGS AND IN ACCORDANCE WITH RMS PAVEMENT SUBSURFACE DRAINAGE DETAILS, VOLUMES 1 TO 6 (AS APPLICABLE).
3. PAVEMENT INTERFACE DRAINS TO BE PROVIDED FOR ALL INTERFACES BETWEEN DIFFERENT PERMANENT PAVEMENT TYPES, INCLUDING AT INTERFACES WITH EXISTING PAVEMENTS.




### Construction Notes

1. Construct sediment fences as close as possible to being parallel to the contours of the site, but with small returns as shown in the drawing to limit the catchment area of any one section. The catchment area should be small enough to limit water flow if concentrated at one point to 50 litres per second in the design storm event, usually the 10-year event.
2. Cut a 150-mm deep trench along the upslope line of the fence for the bottom of the fabric to be entrenched.
3. Drive 1.5 metre long star pickets into ground at 2.5 metre intervals (max) at the downslope edge of the trench. Ensure any star pickets are fitted with safety caps.
4. Fix self-supporting geotextile to the upslope side of the posts ensuring it goes to the base of the trench. Fix the geotextile with wire ties or as recommended by the manufacturer. Only use geotextile specifically produced for sediment fencing. The use of shade cloth for this purpose is not satisfactory.
5. Join sections of fabric at a support post with a 150-mm overlap.
6. Backfill the trench over the base of the fabric and compact it thoroughly over the geotextile.

**SEDIMENT FENCE** **SD 6-8**

NOT FOR CONSTRUCTION

Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com
PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR MUST CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR HIS/HER REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, HE/SHE MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS TO BE RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C-DT.dwg | DR | JK/SW | DR | 19.08.13 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

GUNNEDAH SOLAR PROJECT
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title

NOTES & DETAILS

| Project No. | Scale | |
|---|---|---|
| 3600727160 | | |
| Drawing No. | Sheet | Revision |
| C-500 | 1 of 2 | 3 |

V:\01614\active\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DT.dwg
2020/07/28 1:15 PM By: Rick.Dietrick


ORIGINAL SHEET - ARCH D




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL.
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.


TYPICAL CROSS-SECTION 4.0m WIDE UNSEALED INTERNAL ACCESS ROAD DETAIL (FILL)
NTS




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL.
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.


TYPICAL CROSS-SECTION 4.0m WIDE UNSEALED INTERNAL ACCESS ROAD DETAIL WITH ROADSIDE DITCH (FILL)
NTS




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL.
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.


TYPICAL CROSS-SECTION 4.0m WIDE UNSEALED INTERNAL ACCESS ROAD DETAIL (CUT)
NTS




NOTE:
1 ALL TOPSOIL AND ORGANIC SOILS TO BE REMOVED FROM BELOW ANY PROPOSED STRUCTURES, ACCESS ROADS, AND PARKING AREAS. THE EXPOSED SUBGRADE TO BE PROOF-ROLLED AND INSPECTED BY A QUALIFIED GEOTECHNICAL ENGINEER. ANY LOOSE/SOFT OR WET AREAS IDENTIFIED AT THE TIME OF PROOF-ROLLING TO BE SUB-EXCAVATED AND REMOVED AND REPLACED BY COMPACTED, LOW-PLASTICITY GRANULAR FILL.
2 CHANGES TO THICKNESS AND BASE MATERIAL SPECIFICATIONS TO BE MADE AT THE DISCRETION OF A QUALIFIED GEOTECHNICAL ENGINEER.
3 EXPOSED SUBGRADE MUST HAVE A MINIMUM CBR OF 4 AS PER GEOTECHNICAL REPORT COMPLETED BY CROZIER GEOTECHNICAL CONSULTANTS DATED APRIL, 2018.

COMPACTION REQUIREMENTS:
SUB-GRADE: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE R44, RIP AND RECOMPACT FOUNDATION TO A MINIMUM OF 98% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.
SUB-BASE AND BASE-COURSE LAYERS: IN ACCORDANCE WITH RMS SPECIFICATION GUIDE 71, COMPACT TO A MINIMUM OF 102% OF THE SOIL'S DRY DENSITY RATIO, USING THE STANDARD COMPACTION METHOD.

TYPICAL CROSS-SECTION 4.0m WIDE UNSEALED INTERNAL ACCESS ROAD DETAIL WITH ROADSIDE DITCH (CUT)
NTS




NOTE: Only to be used as temporary bank where maximum upslope length is 80 metres.

**Construction Notes**

Avoid removing trees and shrubs if possible - work around them.


Ensure the structures are free of projections or other irregularities that could impede water flow.

Build the drains with circular, parabolic or trapezoidal cross sections, not V shaped.

Ensure the banks are properly compacted to prevent failure.

Complete permanent or temporary stabilisation within 10 days of construction.

EROSION & SEDIMENT CONTROL BERM DETAIL




NOTES:
1. THIS DESIGN IS CONCEPTUAL, THE FINAL DESIGN TO BE FINALIZED BY OTHERS
2. DIMENSIONS TO BE PER NSW GOVERNMENT| TRANSPORTATION – ROAD & MARITIME SERVICES STANDARD DRAWINGS R0800-09

DROP DOWN FENCE DETAIL
NTS

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR MUST CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR HIS/HER REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, HE/SHE MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS TO BE RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | |
|---|---|---|---|
| File Name: 3600727160_C-DT.dwg | DR | JK/SW | DR | 19.08.13 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

GUNNEDAH SOLAR PROJECT
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title


NOTES & DETAILS

| Project No. | Scale | |
|---|---|---|
| 3600727160 | | |
| Drawing No. | Sheet | Revision |
| C-500 | 2 of 2 | 3 |

V:\101614\active\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C-DT.dwg
2020/07/28, 11:10 PM By: Rice, Derrick

ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 2




LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

ACCESS ROAD B

ACCESS ROAD C

SEE DRAWING C-600-SHEET 4

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

NOT FOR CONSTRUCTION

C:\Users\childs\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 7:03 AM By: Childs, Jaden

ORIGINAL SHEET - ARCH D

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)


Drawing No. C-600

Sheet 1 of 19

Revision 3

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.







LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-600 | 2 of 19 | 3 |

C:\Users\jchiles\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:55 AM By: CHiles, Jason

ORIGINAL SHEET - ARCH D







LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Notes
1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

Legend

PROPOSED
- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| Revision | | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160
Scale 1:1000 (0 10 30 50m)
Drawing No. C-600
Sheet 3 of 19
Revision 3

C:\Users\chlds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:06 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D







NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.26 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-600 | 4 of 19 | 3 |

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:07 AM By: CHilds, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 5

SEE DRAWING C-600-SHEET 4


SEE DRAWING C-600-SHEET 6

SEE DRAWING C-600-SHEET 7

ACCESS ROAD B

ACCESS ROAD B

ACCESS ROAD C




LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)


Drawing No. C-600

Sheet 5 of 19

Revision 3

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:58 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION




LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Notes
1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)

Drawing No. C-600

Sheet 6 of 19

Revision 3

C:\Users\childs\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:58 AM By: Childs, Josh


ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 5


SEE DRAWING C-600-SHEET 4

SEE DRAWING C-600-SHEET 8

ACCESS ROAD C




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-600 | 7 of 19 | 3 |

C:\Users\jchibb\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:55 AM By: CHibb, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 6

SEE DRAWING C-600-SHEET 7

SEE DRAWING C-400-SHEET 9

SEE DRAWING C-600-SHEET 10

SEE DRAWING C-600-SHEET 11


ACCESS ROAD A

ACCESS ROAD C

ACCESS ROAD D

ACCESS ROAD A

ACCESS ROAD D




LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)


Drawing No. C-600

Sheet 8 of 19


Revision 3

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:03 AM By: CHilds, Jaton


ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | | | | |
|---|---|---|---|---|---|
| 3600727160 | 1:1000 | 0 | 10 | 30 | 50m |

| Drawing No. | Sheet | Revision |
|---|---|---|
| C-600 | 9 of 19 | 3 |

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:02 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 9


SEE DRAWING C-600-SHEET 8

SEE DRAWING C-600-SHEET 12


ACCESS ROAD D

ACCESS ROAD D

ACCESS ROAD D




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-600 | 10 of 19 | 3 |

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 9:01 AM By: Childs, Jason


ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 8





SEE DRAWING C-600-SHEET 12

SEE DRAWING C-600-SHEET 13




LOCALITY MAP
N.T.S.




KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.



NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-600 | 11 of 19 | 3 |

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:45 AM By: Childs, Jason


ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 10

SEE DRAWING C-600-SHEET 11

SEE DRAWING C-600-SHEET 14

ACCESS ROAD E




LOCALITY MAP
N.T.S.

KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)

Drawing No. C-600

Sheet 12 of 19

Revision 3

C:\Users\childs\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:44 AM By: Childs, Josh

ORIGINAL SHEET - ARCH D




NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTAITVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project

CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title

# EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)

Drawing No. C-600

Sheet 13 of 19

Revision 3

C:\Users\childs.\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:44 AM By: Childs, Josh

ORIGINAL SHEET - ARCH D


SEE DRAWING C-600-SHEET 12

SEE DRAWING C-600-SHEET 13


ACCESS ROAD E

ACCESS ROAD E

ACCESS ROAD F




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURNG SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

Project No.
3600727160

Scale
1:1000 0 10 30 50m

Drawing No.
C-600

Sheet
14 of 19

Revision
3

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:43 AM By: Childs, Jason


ORIGINAL SHEET - ARCH D

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

SEE DRAWING C-600-SHEET 13




SEE DRAWING C-600-SHEET 16

SEE DRAWING C-600-SHEET 17




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| Revision | | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT


765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-600 | 15 of 19 | 3 |

C:\Users\jchibi\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:42 AM By: CHIBI, Jason

ORIGINAL SHEET - ARCH D







NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- 184.5 — EXISTING TOPOGRAPHIC SURVEY CONTOUR
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | | DR | IH | DR | 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA


Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | |
|---|---|---|
| 3600727160 | 1:1000 | 0 10 30 50m |
| Drawing No. | Sheet | Revision |
| C-600 | 16 of 19 | 3 |


C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:41 AM By: Childs, Jason

ORIGINAL SHEET - ARCH D


SEE DRAWING C-600-SHEET 15




SEE DRAWING C-600-SHEET 18




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

| | Revision | By | Appd. | YY.MM.DD |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |

| File Name: 3600727160_C_EC.dwg | Dwn. | Chkd. | Dsgn. | YY.MM.DD |
|---|---|---|---|---|
| | DR | IH | DR | 19.12.16 |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0, 10, 30, 50m) | C-600 | 17 of 19 | 3 |

Stantec
Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL CONSTRUCTION LEADERS

Copyright Reserved
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.


C:\Users\jchibb\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:41 AM By: CHibb, Jason

ORIGINAL SHEET - ARCH D


SEE DRAWING C-600-SHEET 17




SEE DRAWING C-600-SHEET 19




LOCALITY MAP
N.T.S.



KEY MAP
N.T.S.

NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

NOT FOR CONSTRUCTION

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | | DR | IH | DR | 19.12.16 |
| | | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

| Project No. | Scale | Drawing No. | Sheet | Revision |
|---|---|---|---|---|
| 3600727160 | 1:1000 (0 10 30 50m) | C-600 | 18 of 19 | 3 |

C:\Users\jchibi\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:46 AM By: Chibi, Jason

ORIGINAL SHEET - ARCH D

SEE DRAWING C-600-SHEET 18




NOT FOR CONSTRUCTION




NOTE:
- FOR ACCESS ROAD TYPICAL CROSS SECTION PLEASE REFER TO DRAWING C-500
- IF TOPSOIL IS ENCOUNTERED DURING SOFT SURFACE GRADING STRIP AS REQUIRED

THIS PLAN TO BE USED TO STAGE EROSION AND SEDIMENT CONTROLS PRIOR TO AND DURING CONSTRUCTION. IN ADDITION TO THE MEASURES SHOWN, THE CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC EROSION AND SEDIMENT CONTROLS AS REQUIRED TO RESPOND TO CHANGING SITE CONDITIONS DURING CONSTRUCTION.

GROUND SURFACE TO BE RESTORED WITH SUFFICIENT TOPSOIL AND RESTORATION VEGETATION SEED MIX PER DRAWING C-650 AND DETAILED IN THE LANDSCAPING PLAN.

Stantec

Stantec Consulting Ltd.
300 Hagey Boulevard
Waterloo ON Canada
Tel. 519.579.4410
www.stantec.com

PCL
CONSTRUCTION LEADERS

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

## Notes

1. EXISTING VEGETATION INFORMATION IS APPROXIMATE, PROVIDED FROM AERIAL IMAGERY. CONTRACTOR TO CONFIRM ALL TREE & SHRUB LOCATION ON SITE.
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS IN THIS SET PREPARED BY STANTEC CONSULTING LTD.
3. THE CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS; OBTAIN ALL UTILITY LOCATES AND OBTAIN ALL REQUIRED PERMITS/LICENSES AND VERIFY ELEVATIONS OF EXISTING SERVICES BEFORE PROCEEDING WITH ANY WORK.
4. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
5. IF, FOR UNFORESEEN REASONS, THE OWNER AND/OR IT'S REPRESENTATIVE MUST ENCROACH ONTO PRIVATE LANDS TO UNDERTAKE ANY WORKS, THEY MUST OBTAIN WRITTEN PERMISSION FROM THE ADJACENT PROPERTY OWNERS PRIOR TO ENTERING UPON THE PRIVATE PROPERTY TO PERFORM ANY WORKS. COPIES OF THESE LETTERS OF CONSENT MUST BE SUBMITTED TO THE OWNER AND CONTRACTOR AND A COPY IS TO BE KEPT ON FILE ON SITE PRIOR TO ANY WORK BEING PERFORMED. FAILURE TO COMPLY WITH THE ABOVE IS AT THE PROPERTY OWNERS OWN RISK.
6. THE CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ALL DAMAGED AND/OR DISTURBED PROPERTY WITHIN THE MUNICIPAL RIGHT-OF-WAY.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL DRAINAGE AND MEASURES TO CONTROL WATER. THE SITE IS TO BE FINE GRADED/LEVELED LEAVING THE SITE IN A NEAT APPEARANCE SUCH THAT POSITIVE DRAINAGE IS ACHIEVED EVERYWHERE PRIOR TO THE INSTALLATION OF SOLAR PANELS.
8. CONSTRUCTION TURNING RADIUS LIMITS IDENTIFY AREAS WHERE ADDITIONAL ROAD WIDTH IS REQUIRED TO ALLOW FOR ADEQUATE CLEARANCE FOR CONSTRUCTION VEHICLES.
9. THESE DRAWINGS ARE TOO BE READ IN CONJUNCTION WITH THE Gunn_Earlyworks_WaterManagementPlan AND THE GUNNEDAH EARLY WORKS DESIGN MEMO.

## Legend

PROPOSED

- EXISTING TOPOGRAPHIC SURVEY CONTOUR (184.5)
- OVERLAND FLOW DIRECTION
- SWALE
- SLOPE (3:1 UNLESS NOTED OTHERWISE)
- CULVERT
- EROSION AND SEDIMENT CONTROL BERM (C-500 SHEET 2)
- PROPOSED CUT AREA / PROPOSED FILL AREA
- PROPOSED ACCESS FENCE (SEE SHEET C-500 FOR DETAILS)
- PROPOSED DROP DOWN FENCE (DESIGNED BY OTHERS)
- APPROXIMATE LOCATION OF PROPERTY LINES
- PROPOSED ROCK CHECK DAM (SEE SHEET C-650 FOR DETAILS)
- SILT FENCE SEE DETAIL ON SHEET C-500
- SILT SOXX SEE DETAIL ON SHEET C-500
- PROPOSED RIP RAP SPILLWAY (SEE SHEET C-650 FOR DETAILS)

| | | | | |
|---|---|---|---|---|
| 3 | 30% DESIGN | DR/JC | BW | 20.07.27 |
| 2 | REVISED PER UPDATED SURVEY | DR | IH | 20.06.09 |
| 1 | REVISED AND ADDED DETAILS | DR | JK | 20.05.27 |
| 0 | ISSUED FOR CONSTRUCTION | DR | JK | 20.03.26 |
| Revision | | By | Appd. | YY.MM.DD |

| | | | | |
|---|---|---|---|---|
| File Name: 3600727160_C_EC.dwg | DR | IH | DR | 19.12.16 |
| | Dwn. | Chkd. | Dsgn. | YY.MM.DD |

Permit-Seal

Client/Project
CANADIAN SOLAR AUSTRALIA
GUNNEDAH SOLAR PROJECT

765 ORANGE GROVE ROAD
147MV GROUND MOUNT SOLAR FARM
GUNNEDAH, NEW SOUTH WALES, AUSTRALIA

Title
EROSION AND SEDIMENT CONTROL PLAN

Project No. 3600727160

Scale 1:1000 (0, 10, 30, 50m)

Drawing No. C-600

Sheet 19 of 19

Revision 3

C:\Users\cfields\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_C_EC.dwg
2020/07/27 8:39 AM By: CFields, Jason

ORIGINAL SHEET - ARCH D

# INSPECTION FORMS

Stantec

# RAINFALL EVENT MONITORING INSPECTION FORM

Project: GUNNEDAH SOLAR PROJECT

Project #: 3600727160

Inspection Date (m/d/y) _____

Location: 765 Orange Grove Road, Gunnedah, NSW

Date of Rainfall Event (m/d/y) _____

Depth of Rainfall Event _____

## HIGH WATER MARK OBSERVATIONS

| Monitoring Location | External Measurement | Internal Measurement | High Water Difference | Monitoring Location | External Measurement | Internal Measurement | High Water Difference |
|---|---|---|---|---|---|---|---|
| 1 | | | | 17 | | | |
| 2 | | | | 18 | | | |
| 3 | | | | 19 | | | |
| 4 | | | | 20 | | | |
| 5 | | | | 21 | | | |
| 6 | | | | 22 | | | |
| 7 | | | | 23 | | | |
| 8 | | | | 24 | | | |
| 9 | | | | 25 | | | |
| 10 | | | | 26 | | | |
| 11 | | | | 27 | | | |
| 12 | | | | 28 | | | |
| 13 | | | | 29 | | | |
| 14 | | | | 30 | | | |
| 15 | | | | 31 | | | |
| 16 | | | | | | | |

*Measurements taken as depth from ground surface at panel racking or perimeter fence post, per monitoring location figure

*Concerns/Comments:*

_____

_____

_____

_____

## PERIMETER FENCE OBSERVATIONS

*Fence Condition (comment on evidence of flow and accumulated debris – markup attached map as necessary):*

_____

_____

_____

_____

*Fence connections (comment on location and condition of damaged or broken connectors – markup attached map as necessary):*


_____

_____

_____

_____ _____ _____

Print Name | Signature (Inspector) | Date




Stantec

Stantec Consulting Ltd.
100-300 Hagey Boulevard
Waterloo ON N2L 0A4
Tel: (519) 579-4410
www.stantec.com

LEGEND

EXT-24 MONITORING LOCATION

Client/Project
PCL CONSTRUCTION

GUNNEDAH SOLAR PROJECT

Project No.
3600727160

Title
HIGH WATER MARK MONITORING LOCATIONS

| Revision | Date |
|---|---|
| 0 | 2020.08.04 |
| Reference Sheet | Figure No. |
| 1 | 1 |

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_MONITOR_HWM_FIG.dwg
8/5/2020 9:49:15 AM By: Childs, Jason




Stantec

Stantec Consulting Ltd.
100-300 Hagey Boulevard
Waterloo ON N2L 0A4
Tel: (519) 579-4410
www.stantec.com

LEGEND

EXT-24 MONITORING LOCATION

Client/Project
PCL CONSTRUCTION

GUNNEDAH SOLAR PROJECT

Project No.
3600727160

Title
HIGH WATER MARK MONITORING LOCATIONS

Revision
0

Date
2020.08.04

Reference Sheet
2

Figure No.
2

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_MONITOR_HWM_FIG.dwg
8/5/2020 9:51:54 AM By: Childs, Jason

Stantec

## GUNNEDAH SOLAR PROJECT – SEC Inspection and Monitoring Checklist

Project: GUNNEDAH SOLAR PROJECT  Project #: 3600727160

Inspection Date (m/d/y) _____  Location: 765 Orange Grove Road, Gunnedah, NSW

### STORMWATER MANAGEMENT

| | |
|---|---|
| Any obstructions or pieces of debris in the graded drainage swales? | Y / N |
| Is there on-site water ponding? | Y / N |
| Anticipated conveyance issues at surface water crossings on access road low points? | Y / N |
| Obstructions to or damage of on-site culverts inhibiting conveyance capacity? | Y / N |
| Evidence of poor flow passage through the perimeter fence? | Y / N |
| Missing or inoperable connections at locations of the flow through fence? | Y / N |
| Any drainage intrusions mitigating overland flow to surrounding irrigation channel? | Y / N |
| Any indication of downstream conveyance capacity issues? | Y / N |

*Concerns/Comments (use site map to identify specific areas of concern):*

_____
_____
_____
_____

### EROSION AND SEDIMENT CONTROL


| | |
|---|---|
| Are there areas of exposed soil (no vegetation)? | Y / N |
| Are there significant shaded areas lacking vegetation growth under the panels? | Y / N |
| Are there signs of overland erosion/rilling? | Y / N |
| Evidence of erosion on granular pad and road infrastructure? | Y / N |
| Erosion in the on-site diversion swales? | Y / N |
| Scour and erosion at the culverts located on-site? | Y / N |
| Evidence of erosion or sediment build-up at entrances and exits of culverts? | Y / N |
| Access road low point armoring showing signs of sour/erosion? | Y / N |
| Evidence of silt fence damage / repairs required? | Y / N |
| Evidence of sediment deposition downstream of the site? | Y / N |
| Do sediment accumulations exceed 1/3 of the capacity of any sediment storage areas? | Y / N |

*Concerns/Comments (use site map to identify specific areas of concern):*

_____
_____
_____
_____

_____  _____  _____

Print Name  Signature (Inspector)  Date




Stantec

Stantec Consulting Ltd.
100-300 Hagey Boulevard
Waterloo ON N2L 0A4
Tel: (519) 579-4410
www.stantec.com

LEGEND

EXT-24 MONITORING LOCATION

Client/Project
PCL CONSTRUCTION

GUNNEDAH SOLAR PROJECT

Project No.
3600727160

Title
HIGH WATER MARK MONITORING LOCATIONS

| Revision | Date |
|---|---|
| 0 | 2020.08.04 |
| Reference Sheet | Figure No. |
| 1 | 1 |

C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_MONITOR_HWM_FIG.dwg
8/5/2020 9:49:15 AM By: Childs, Jason




Stantec

Stantec Consulting Ltd.
100-300 Hagey Boulevard
Waterloo ON N2L 0A4
Tel: (519) 579-4410
www.stantec.com

LEGEND

EXT-24 MONITORING LOCATION

Client/Project
PCL CONSTRUCTION

GUNNEDAH SOLAR PROJECT

Project No.
3600727160

Title
HIGH WATER MARK MONITORING LOCATIONS

Revision
0

Date
2020.08.04

Reference Sheet
2

Figure No.
2


C:\Users\jchilds\Desktop\Working Folder\3600727160 - Gunnedah Solar\design\drawing\civil\sheet_files\3600727160_MONITOR_HWM_FIG.dwg
8/5/2020 9:51:54 AM By: Childs, Jason

# GUNNEDAH SOLAR FARM HYDROLOGY REPORT

# GUNNEDAH SOLAR FARM HYDROLOGY REPORT

**PREPARED FOR PCL**

27/07/2020



This document has been prepared for the benefit of PCL. No liability is accepted by this company or any employee or sub-consultant of this company with respect to its use by any other person.

This disclaimer shall apply notwithstanding that the report may be made available to other persons for an application for permission or approval to fulfil a legal requirement.

# QUALITY STATEMENT

| PROJECT MANAGER | | PROJECT TECHNICAL LEAD | |
|---|---|---|---|
| Darren Schreiber | | Dave Williams | |
| **PREPARED BY** | | | |
| Bedilu Wolelo | ..... | ...../...../..... | |
| **CHECKED BY** | | | |
| | ..... | ...../...../..... | |
| **REVIEWED BY** | | | |
| Darren Schreiber | ..... | ...../...../..... | |
| **APPROVED FOR ISSUE BY** | | | |
| Peter Bright | ..... | ...../...../..... | |

**SYDNEY**
Level 4, 99 Walker Street, NORTH SYDNEY, NSW 2060
TEL +61 2 9493 9700, FAX +61 2 9493 9799

# REVISION SCHEDULE

| Rev No. | Date | Description | Signature or Typed Name (documentation on file) | | | |
|---|---|---|---|---|---|---|
| | | | Prepared by | Checked by | Reviewed by | Approved by |
| 01 | 06/03/2020 | Issued for Review | B. Wolelo | N. Keenan | D. Schreiber | P. Bright |
| 02 | 18/03/2020 | Issued for Client Review | B. Wolelo | D. Williams | D. Schreiber | P. Bright |
| 03 | 25/05/2020 | reissued to support water management plan for access road construction | B. Wolelo | D. Williams | D. Schreiber | P. Bright |
| 04 | 27/07/2020 | Re issued to support water management plan for conceptual grading | B. Wolelo | D. Williams | D. Schreiber | P. Bright |
| | | | | | | |

# Abbreviations

| Terms, abbreviations and acronyms | Meaning |
|---|---|
| 12d | 12d Model Civil Engineering Design and Surveying software package |
| AEP | Annual Exceedance Probability |
| AHD | Australian Height Datum |
| AGRD | Austroads Guide to Road Design |
| ALS | Aerial laser survey |
| ARR | Australian Rainfall and Runoff |
| BoM | Bureau of Meteorology |
| CBFMP | Carroll to Boggabri Floodplain Management Plan |
| DTM | Digital Terrain Model |
| GIS | Geographic Information System |
| IFD | Intensity Frequency Duration |
| Lidar | Light Detection and Ranging |
| LOF | Local Overland Flow |
| NSW | New South Wales |
| RFFE | Regional Flood Frequency Estimation Model |
| Tuflow | Tuflow Software Package |
| UNVFMP | Upper Namoi Valley Flood Management Plan |
| XpRafts | Xprafts software package |

# CONTENTS

Abbreviations ..... ii
1. Introduction ..... 1
1.1 Purpose ..... 1
1.2 References ..... 1
2. Project Definition ..... 2
2.1 Location ..... 2
3. Flooding & Drainage design Criteria ..... 4
4. Hydrology ..... 5
4.1 Data Collection ..... 5
4.2 Terrain ..... 5
4.3 Rainfall Data ..... 5
4.4 Temperature ..... 6
4.5 IFD and Temporal Pattern ..... 7
4.6 Hydrological and Hydraulic Modelling in Tuflow ..... 9
5. Access Road Model ..... 14
6. Regional Flooding ..... 14

# LIST OF TABLES

Table 3-1 Site initial and continuing loss figures (Obtained from ARR Data hub) ..... 7
Table 3-2 Site Probability Neutral Burst Initial Loss (Obtained from ARR Data Hub) ..... 8
Table 3-3 Adopted Manning's n values ..... 11

# LIST OF FIGURES

Figure 2-1: Location ..... 3
Figure 4-1: Mean Monthly Rainfall at Gunnedah Pool Station ..... 6
Figure 4-2: Mean Monthly Temperature at Gunnedah Pool ..... 6
Figure 4-3: IFD Depth and Intensity data ..... 7
Figure 4-4: Hydraulic Model Domain ..... 10
Figure 4-5: Land Use Map ..... 12

# APPENDICES


Appendix A Depth of Flooding ..... 1
Appendix B Flow velocity ..... 6
Appendix C Flood Hazard ..... 9
Appendix D Regional Flooding ..... 13
Appendix E Depth of Flooding Difference Post Construction of Access Road ..... 15
Appendix F Design Rainfall Depth and Site IFD ..... 19

# 1. Introduction

## 1.1 Purpose

This Hydrology report is prepared to document depth of inundation, flood levels, hazard and flow velocity generated while design storm occurs in the locality of the proposed Gunnedah Solar Farm (GSF) project site. A separate report that documents flow behaviour across the project site during regional flooding has been prepared by Pitt & Sherry Group. The report will inform the panel block layout plan, proposed landform design and risk of flooding during the construction and operation sitewide. The hydraulic modelling was conducted using Tuflow 1d/2d software package applying rainfall on grid hydrology. The modelling was undertaken in accordance with ARR2019. This report was updated to include finding from the post access construction modelling conducted to support water management plan during the construction of the access road and in accordance with the internal road and panel block provided during preliminary design development.

This hydrology Report summarises the processes and procedures followed, and assumptions taken while conducting the hydrological and hydraulic assessment during the following scenarios:

- Existing catchments in a pre-development condition and
- Post the construction of the access road connecting the project site with Orange Grove Road, internal roads and panel block layout provided during the preliminary design development stage.

## 1.2 References

This item lists the reference documents including reports on previous investigations, studies, consultations and data gathering processes. This includes data utilised for hydrological and hydraulic modelling.

1. A300 – Civil Engineering and construction requirements - Australia
2. Aerial Imagery, obtained from Bing Maps
3. Topographical Terrain Model Survey, undertaken by Land Survey
4. Topographical Digital Terrain Model, obtained from Airbus Website
5. 1987 & 2016 IFD data obtained from the Bureau of Meteorology Web Site
6. 2016 Ensemble temporal pattern data from Bureau of Meteorology Web Site
7. ARR Datahub, publications and guidelines
8. Australian Rainfall and Runoff (ARR), Geoscience Australia, 2019
9. Drains Utility Spreadsheet
10. Gunnedah Solar Farm – Flood impact Assessment Rev 5 by Pitt & Sherry Group
11. Aerial laser survey (ALS) data, Obtained from Pitt & Sherry Hydraulic model file
12. Gunnedah Solar Farm Development Consent – Independent Planning Commission of NSW,
13. Flood Management Plan for the Upper Namoi Valley Floodplain, NSW Government, June 2019
14. Upper Namoi Valley Floodplain Management Plan – Management Zone BL – rules and assessment criteria, NSW Government, June 2019 (UNVFMP)
15. *Carroll to Boggabri Floodplain Management Plan*, NSW Government, September 2006 (CBFMP)

# 2. Project Definition

## 2.1 Location

The GSF will be installed at 765 Orange Grove Road Gunnedah, approximately 10km north east of Gunnedah township. Gunnedah township is located 430km north west of Sydney. It is proposed to provide site access road from Orange Grove Road located east of the site. There were recorded incidences of flood waters overtopping Namoi River banks located east of Orange Grove Road and inundating the project site. The site is currently used for agriculture. Irrigation channels traverse the project site. The terrain of the site is flat. There are no distinct gullies inside the project site. Site location is shown in  Figure 2-1.





Figure 2-1: Location

# 3. Flooding & Drainage design Criteria

A generic civil design specification A300 was provided at an earlier stage of design development. The project site is located at the banks of Namoi River. The Namoi River Breaks banks during storm events including and larger than the 10% AEP storm event. It was required to amend the design criteria to take into consideration the impacts of:

- Site flat topography and flood affectation of the site by local and regional flooding;
- Existing regional flood extent and AEP of the Namoi River Breaking bank,
- conditions set in the Gunnedah Solar Farm Development Consent;
- conditions set in the floodplain management plan for the Upper Namoi Valley floodplain; 2019 and
- the solar farm operational requirements.

The revised flooding and drainage design criteria for various project infrastructure requirements are set in Table 3-1.

Table 3-1 GSF Civil Design Criteria

| Asset | Criteria | Limit | Reference | Storm type governing Design Element |
|---|---|---|---|---|
| Road Side Swale | minimum Vertical gradient | 0.10% | A300 | Local Overland Flooding |
| Culverts | minimum culvert diameter | 450mm | A300 & Standard Pipe Size in Australia | Local Overland Flooding |
| Ditches | Design AEP | 10%AEP Freeboard:150mm | A300 | Local Overland Flooding |
| Ditches | Design AEP | 1% AEP no overtopping | A300 | Local Overland Flooding |
| | Flooding Risk | Minimize Risk to life and property | EIS section 4.5.7 | Local Overland Flooding & Regional Fluvial Flooding |
| | Maximum flood depth difference post construction | 100mm | CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| | Maximum height of civil/structural works arresting floodwaters | only 10% of the length of proposed sctructure could exeed 0.5m above existing ground level | UNVFMP / CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| Floodways | capacity | no reduction | UNVFMP / CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| | Flow Velocity | < 50% increase | UNVFMP / CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| | Flow Velocity | < 0.5m/sec | UNVFMP / CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| Adjacent Land holding | drainage pattern | No change | UNVFMP / CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| Access Road | Floodway | allowed to overtop through floodway | UNVFMP / CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| Internal Roads | Floodway | allowed to overtop through floodway | UNVFMP / CBFMP | Local Overland Flooding & Regional Fluvial Flooding |
| Invertor Station | Design AEP | 1% AEP + 300 Freeboard | GSF Operational Requirement | Regional Fluvial Flooding |
| Switch Yard | Design AEP | 1% AEP + 300 Freeboard | GSF Operational Requirement | Regional Fluvial Flooding |

# 4. Hydrology

Rainfall on grid hydrology was utilised to determine flow behaviour across the project site. The hydrological model development process involved collecting rainfall depth and temporal pattern data from the Bureau of Meteorology website and collecting loss parameters from ARR Datahub. The temporal patterns that resulted in maximum intensity following initial losses were selected to be routed through the hydraulic model.

## 4.1 Data Collection

Data utilised for the hydrological modelling purposes was collected from the following sources:

- Areal Imagery by Bing Maps
- Digital Terrain model from Airbus website
- Areal Laser Survey data utilised in Pitt & Sherry Regional flood model
- Unmanned Aerial vehicle (UAV) survey undertaken by Land Survey
- 2016 IFD data from the Bureau of Meteorology website
- 2016 Ensemble temporal pattern data for the Bureau of Meteorology website
- Catchment loss parameters obtained from ARR Datahub website

## 4.2 Terrain

A digital terrain model of the existing scenario model was developed from ground survey data utilised in the Pitt & Sherry hydraulic model, data obtained from Airbus website and UAV survey data undertaken across the project site by Land survey and follow up update of the site survey. During the proposed scenario modelling the preliminary design layout and earthworks were superimposed on top of the existing scenario ground model. Runoff collected from the hills located north of the project site are collected in farm dams provided at the bottom of the hills. The locality downstream of the dams is uniformly graded flat terrain. The elevation of the project site varies from 256m AHD to 279.7m AHD. Majority of the project site has a longitudinal less than 0.5%. Runoff in the flat section drains as sheet flow across the project site. Irrigation channels traverse the site. The Irrigation channels are up to 1m deep. A berm is provided upstream of the irrigation channels.

## 4.3 Rainfall Data

Rainfall data was collected from the Bureau of Meteorology (BoM) website for Station number 055023 Gunnedah (Pool) Station. The data indicates that the mean annual rainfall for the locality is 615.7mm. Precipitation occurs at the site throughout the year. However, majority of the rainfall occurs between the months of October and March. The data could assist in selecting suitable period to undertake the construction works on site. Statistical summary of rainfall at the locality is provided in Figure 4-1.

| Statistic | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Annual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Mean | 70.6 | 66.1 | 48.9 | 36.6 | 42 | 44 | 41.5 | 40.9 | 40.2 | 54.2 | 61.4 | 69.6 | 615.7 |





Figure 4-1: Mean Monthly Rainfall at Gunnedah Pool Station

## 4.4 Temperature

Temperature data collected at station number 056037 (Gunnedah Pool) in Gunnedah indicates that the mean maximum temperature varies between 21 and 41$^0$c. The mean minimum temperature varies between 11 and 29$^0$c.

The minimum temperature occurs in the winter month of July and the maximum temperature occurs in the summer month of January. Mean, lowest and highest monthly temperature data is shown in Figure 4-2.





Figure 4-2: Mean Monthly Temperature at Gunnedah Pool

## 4.5 IFD and Temporal Pattern

The 2016 IFD data was obtained from the Bureau of Meteorology site. The IFD depth and intensity for the project site is shown in Figure 4-3. Tabular form of the data is provided in Appendix F. The 2016 ensemble temporal data for the site was obtained from ARR Datahub website. Datahub prescribes that the east coast south temporal pattern be applied for the site.





Figure 4-3: IFD Depth and Intensity data

### 4.5.1 Loss Parameters

Initial and continuing loss parameters were selected in accordance with the approaches prescribed in ARR 2019. Literature review has not identified a study conducted in the catchment that determined calibrated initial loss in the locality of the catchment. Where good initial loss figures are not available OEH has prescribed that hierarchical approach be utilised to determine preferred loss parameter. The catchments fits in hierarchy number five where it is preferred to utilise probability neutral initial loss figures provided in ARR Datahub. Accordingly, probability neutral burst initial figures shown in Table 4-2 where utilised while conducting the hydrological modelling.

Table 4-1 Site initial and continuing loss figures (Obtained from ARR Data hub)

| | |
|---|---|
| **ID** | 2264.0 |
| **Storm Initial Losses (mm)** | 53.0 |
| **Storm Continuing Losses (mm/h)** | 0.2 |

Table 4-2 Site Probability Neutral Burst Initial Loss (Obtained from ARR Data Hub)

| min (h)\AEP(%) | 50 | 20 | 10 | 5 | 2 | 1 |
|---|---|---|---|---|---|---|
| **60 (1.0)** | 22.8 | 26.0 | 21.2 | 21.0 | 21.0 | 20.7 |
| **90 (1.5)** | 25.8 | 27.3 | 22.8 | 22.9 | 22.2 | 21.2 |
| **120 (2.0)** | 28.1 | 24.5 | 21.1 | 21.2 | 21.9 | 21.0 |
| **180 (3.0)** | 31.6 | 24.7 | 21.7 | 21.6 | 21.6 | 19.8 |
| **360 (6.0)** | 39.0 | 25.9 | 22.8 | 21.9 | 20.0 | 16.9 |
| **720 (12.0)** | 47.0 | 31.6 | 28.2 | 27.6 | 21.8 | 15.9 |
| **1080 (18.0)** | 49.0 | 35.0 | 31.2 | 29.5 | 21.9 | 13.5 |
| **1440 (24.0)** | 50.3 | 37.5 | 35.0 | 34.2 | 26.3 | 17.4 |
| **2160 (36.0)** | 49.5 | 37.7 | 35.6 | 36.0 | 31.6 | 23.7 |
| **2880 (48.0)** | 53.5 | 43.4 | 42.3 | 43.2 | 40.2 | 32.2 |
| **4320 (72.0)** | 54.0 | 45.5 | 46.3 | 47.8 | 45.2 | 36.0 |

### 4.5.2 Storm Events and Temporal Patterns and Loss parameters

The initial loss for the site as obtained from ARR Data Hub is 53mm. If we use this in the study no runoff will be generated for design storms ranging from 5 minutes to 1hr. The 1hr storm depth is 59mm. FFA conducted for a site inside the Namoi River Catchment and far from the site under consideration indicates that the initial loss figure of 49mm.

As there is no source of good initial loss data, for the locality, which makes it fall in category 5 of the ARR NSW specific guide. The NSW guide specifies that a probability neutral burst initial loss values available on ARR datahub be utilised in all instances. Accordingly, the probability neutral burst initial loss figures shown in Table 4-2 were utilised in the study.

Storm events with durations less than and including 1hr duration would not provide significant flooding as a significant part of the rainfall will be lost as an initial loss. Storm events with durations of 90, 120, 180, 270 and 360 minutes were run through the hydraulic model to determine flood characteristics across the project site.

The temporal patterns that generate worst scenario flooding at the site were tested. The test has indicated that the depth of flooding across the project site during local storm events was less than 100mm for the 75% of the site and is less than 0.5m near the bunds provided on the upstream side of the irrigation channels. The site is flat agricultural land. Flow across the site occurs as a sheet flow. The depth of water in these areas is controlled only by the bunds provided upstream of the irrigation channels. The median storm as directed by ARR will produce much less inundation than the worst case scenarios. Storms that generated worst inundation at the site for each storm duration were considered for hydraulic run.

Selection of storms that generate worst scenario flood characteristics was selected based on the following rational:

- Intensity of rainfall is directly correlated to generation of runoff
- No runoff being generated from site prior to rainfall depth in excess of initial loss occurs
- Back loaded storms with intense rainfall occurring at a duration following rainfall in excess of initial loss

Based on the analysis provided above, the following storm durations, associated temporal patterns and loss figures were run through the hydraulic model

Table 4-3 AEP, Storm Duration, Temporal Patterns and initial loss figures

| AEP | Storm duration | Temporal pattern | loss (mm) |
|---|---|---|---|
| 1%AEP | 90 | TP10 | 21.2 |
| 1%AEP | 120 | TP07 | 21 |
| 1%AEP | 120 | TP09 | 21 |
| 1%AEP | 180 | TP02 | 19.8 |
| 1%AEP | 270 | TP10 | 18.3 |
| 1%AEP | 360 | TP05 | 16.9 |

## 4.6 Hydrological and Hydraulic Modelling in Tuflow

A 2d–hydrodynamic model was developed using Tuflow software package to determine flood level, flow depth, flow velocity and hazard mapping across the project during the existing scenario. Tuflow solves depth averaged free surface flow in 1d channels or over a 2d regular grid with square cells. A hydrograph generated in other hydrological modelling packages could be applied as a boundary conduction or Tuflow can route rainfall excess across the 1d/2d model domain.

There are no significant drainage features obstructing flow at the project site. 2d hydrodynamic model could provide sufficient information on flooding across the site. Accordingly, rainfall on grid methodology was used while undertaking the flood modelling. The flood modelling process included developing existing surface digital terrain model, determining rainfall and outlet boundary conditions, determining the manning's roughness of the existing ground, preparing the Tuflow control files, debugging the model, preparing the result files and preparing the flood characteristics maps.

### 4.6.1 2d Model Bathymetry

Accuracy of the 2d hydraulic model result is influenced by the accuracy of model bathymetry. Model bathymetry was developed from unmanned Aerial vehicle (UAV) survey undertaken by Land Survey in the locality of the project and merged aerial survey data utilised in the Pitt & Sherry model to develop a regional flood model. Airbus DTM data was utilised in localities that were not covered by both survey data discussed. A model cell size of 2m is adopted for the study. This resolution is sufficient to determine flood characteristic across the site for the modelled events. Model domain and DTM data utilised in the study is shown in Figure 4-4.





Figure 4-4: Hydraulic Model Domain

### 4.6.2 2d model boundary Conditions

Rainfall in excess of initial and continued loss in each cell is routed through the hydraulic model towards catchment outlet. Storm events that generate intense rainfall, post the initial losses, cause maximum flood depth, flow velocity and hazard. As the initial losses for the locality are high, an insignificant amount of runoff is generated during short duration storms including the 1% AEP, 20minute storm. The study has reduced the number of hydraulic model runs by systematically reviewing the temporal patterns and selecting storm durations and temporal patterns that have the potential to generate maximum flood characteristics. Temporal distribution patterns and storm durations that generated maximum flood characteristics during the 1% AEP storm events for storm durations ranging from 30 minutes to 270 minutes are provided in Appendix E. The temporal patterns that were selected to be routed through the hydraulic model are highlighted in yellow. The rainfall depth data is stored in the boundary condition database file and was applied across the 2d rainfall boundary layer. 2d downstream condition layers were digitised in GIS and normal depth boundary condition was applied at local catchment downstream outlet locations.

### 4.6.3 Model data

2d model extent, 2d rainfall layer, 2d boundary and 2d land use (material type) was digitised using the ArcGIS software package. Aerial imagery obtained from Bing Maps was utilised to digitise ground cover that exists within the model domain. The hydraulic roughness figures utilised for the respective ground cover inside the model domain is provided in Table 4-4. The land use map is

Table 4-4 Adopted Manning's n values

| Land use (Ground Cover) | Manning's n |
|---|---|
| Dense Vegetation | 0.1 |
| Farm/Pasture | 0.045 |





Figure 4-5: Land Use Map

### 4.6.4 Existing Scenario Tuflow Model Results

Existing scenario Tuflow model run was conducted to determine extent of flooding, flood level, depth of flow, flow velocity and flooding hazard across the project site. Flow hydrographs were also extracted at key locations to assist with sizing of drainage structures at road crossings.

#### 4.6.4.1 Flood Depth

The gradient of the site is flat. There are no natural drainage features that direct runoff through the site. runoff from external catchment enters the project site as a sheet flow. Runoff at the site occurs as a sheet flow and runoff from the site and upstream catchments drains away from the site as a sheet flow.

Irrigation channels traverse the project site. Bunds are provided upstream of the irrigation channels. These bunds block the sheet flow from entering the Irrigation Channels. During major storm events, runoff ponds upstream of the bunds and overtops these bunds to eventually drain towards the irrigation channels. Runoff draining towards the irrigation channel ponds in these channels and once the capacity is exceeded, it overtops the channels and drains towards downstream project boundary. Sheet flow depth is minor. Flow depth in excess of 50mm is observed only behind the bunds and inside the irrigation channels during major storm events in the local catchment. Map Showing depth of flooding generated from the 1% AEP storm event occurring across the model boundary from local catchments is shown in Appendix A.1. The map in Appendix A.2 Shows data presented in Appendix A.1 in the project locality.

#### 4.6.4.2 Velocity

Map showing maximum flow velocity across the project site is provided in Appendix B.1. The mapping shows that maximum velocity across the site is less than 0.5m/sec.

#### 4.6.4.3 Hazard

Depth of flow, velocity of flow or product of velocity and depth of flow could provide flooding hazard across a floodplain. MBRC hazard category pallets are utilised to generate hazard category at the project site. MBRC hazard category description is provided in Appendix C.2. Depth of flow at the site is less than 0.5m and velocity of flow is less than 0.5m/sec. Majority of the site is covered under category H1. The irrigation channels and localities abutting the irrigation channel are categorised as H2. This indicates that there is no significant hazard across the project site during major storm event in the local catchment.

### 4.6.5 Proposed Scenario Tuflow Model Results

Proposed Scenario Tuflow model run was conducted to determine extent of flooding, flood level, depth of flow, flow velocity and flooding hazard across the project site post installation of the solar farm.

#### 4.6.5.1 Flood Depth

The installation of the proposed solar farm involved minimal amount of regrading works. it is proposed to drive piles and install the solar arrays. It is also proposed to install the invertor stations on piles to ensure that the infrastructure is above the regional flood level. The vertical geometry of the proposed access road and internal roads follows the existing terrain pattern and is provided to not to interfere with flow behaviour in the floodplain.

The existing irrigation channels were maintained post construction and the bunds placed upstream of the irrigation channel were not altered. The proposed scenario digital terrain model was superimposed on the existing ground DTM and has been utilised as bathymetry for the proposed scenario flood model.

The model of the proposed scenario has indicated that ponding not exceeding 0.5m was observed upstream of the existing bunds provided upstream of the irrigation channels. Runoff through the project site occurs as a sheet flow. Depth of inundation during the 1% AEP storm event is less than 50mm at approximately more than 50% of the project site area.

#### 4.6.5.2 Velocity

Map showing maximum flow velocity across the project site is provided in Appendix B. The mapping shows that maximum velocity across the site post the installation of the solar farm is less than 0.5m/sec.

#### 4.6.5.3 Hazard

Depth of flow, velocity of flow or product of velocity and depth of flow could provide flooding hazard across a floodplain. MBRC hazard category pallets are utilised to generate hazard category at the project site. MBRC hazard category description is provided in Appendix C.2. Depth of flow at the site is less than 0.5m and velocity of flow is less than 0.5m/sec. Majority of the site is covered under category H1. In category H1 area parked cars could not be buoyed by flood waters and moving cars could easily

navigate through during local storm events. Localities abutting the irrigation channel which could pond up to a depth of 0.5m are categorised as H2. Category H2 covers less than 10% of the site area. Heavy vehicles could be parked or would be able to navigate through these areas.

### 4.6.6 Impacts of the proposed works

The proposed installation of the solar farm will minimise works that would interfere with the natural floodwater movement in the vicinity of the project area. This is inline with the requirements of the UNVFMP. The Development consent requires that impacts to adjacent land holdings be minimised. The modelling of the hydraulic modelling, post processing and mapping of flood characteristics has indicated that the proposed works have minimal impact on adjacent land holdings.

The modelling, post processing and mapping has indicated that:

- Maximum afflux of 2mm was observed outside the project boundary. This is within the limits of accuracy of the hydraulic modelling software package
- The modelling has indicated that a maximum flow velocity of 0.5m/sec could be observed inside and outside the project boundary. In some localities a maximum flow velocity increase of 0.25m/sec is predicted. Maximum flow of 0.5m/sec estimate included 0.25m/sec increase inside the model boundary. The UNVFRM allows an increase of velocity by up to 50% and the increase is within the limits acceptable by the UNVFRM.
- Difference mapping of hazard category has indicated that there is no change for this parameter post installation of the solar farm

# 5. Access Road Model

As part of the access road water management plan, it was required to identify impacts of the proposed road on flood characteristics in the locality of the project.

A proposed scenario modelling was conducted to determine the flood levels, flow velocity, depth of flow and flow hazard post construction of the road. It was also required to understand the impacts of the proposed works.

The proposed road terrain model was included in the Tuflow model geometry control file and model run was conducted for the 1% AEP storm event. Post processing was conducted in ArcGIS to determine the flood level and maximum velocity difference across the model domain.

The modelling has indicated that:

- The increase in flood level upstream and downstream of the proposed road was minor and it occurred inside the project boundary. The maximum level increase was estimated at 100mm.
- The increase in velocity was minor. The maximum change in velocity post the construction of the proposed road was 0.05m/sec and this increase occurs inside the proposed road corridor.

The road design blends well with the existing terrain and has minor to no impact on holding downstream of the proposed road.

# 6. Regional Flooding

The project site is located adjacent the Namoi River. Data obtained from New South Wales Water website indicates that the catchment of Namoi River at Gunnedah (stream gauging station # 419001) is approximately 17. 100 sq.km. This station is located approximately 10km downstream of the project site. The river breaks banks and flows through the site during major storm events. Flooding occurring at the project site due to major storms occurring in the entire 17,100 sq. km is referred as the regional flooding. The regional flood modelling was conducted by Pitt & Sherry Group. Depth of flooding during the 1% AEP regional flooding event is shown in Appendix B.

The regional flooding produces worst case flow characteristics at the project site and should be utilised to determine finished floor level for essential services site wide. The impact of constructing access road and earthworks on the regional flood characteristics should be tested in the regional model.


Fencing arrangements were tested in the regional model and to ensure EIS requirements are met. Pitt & Sherry Group has proposed a preferred fencing arrangements. It is proposed that the recommendation made by the group be utilised while installing perimeter fence around the site.

# Appendices




# Appendix A Depth of Flooding

Figure Appendix A. 1 Existing scenario Local overland Flow depth model wide during the 1% AEP Storm event




Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of that information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure Appendix A 2 Existing scenario Local overland Flow depth across project site during the 1% AEP Storm event




Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure Appendix A. 3  Proposed scenario Local overland Flow depth model wide during the 1% AEP Storm event






Figure Appendix A 4 Proposed scenario Local overland Flow depth across project site during the 1% AEP Storm event




Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.


# Appendix B Flow velocity

Figure Appendix B 1 Existing Scenario Local overland Flow Velocity project site wide during the 1% AEP Storm event




Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.


Figure Appendix B 2 Proposed Scenario Local overland Flow Velocity project site wide during the 1% AEP Storm event




Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.


# Appendix C Flood Hazard

Figure Appendix C 1 Existing Scenario Local overland Flow project site wide Hazard during the 1% AEP Storm event





Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure Appendix C 2  Proposed Scenario Local overland Flow project site wide Hazard during the 1% AEP Storm event





Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure Appendix C 3  MBRC Hazard Category (adopted from BMTWBM 2018)

| Flag | Map Output Hazard Type | Supported Formats | Description |
|---|---|---|---|
| ZMBRC | ZMBRC | All formats | Flood hazard output used by Moreton Bay Regional Council.<br>Where:<br>V > 2.5 or D > 2.5 or V*D > 2.5: Category 5 (H5 )<br>V > 2.0 or D > 2.0 or V*D > 1.0: Category 4 (H4)<br>V > 3.2 - 4D: Category 3 (H3)<br>V > 0.5 or D > 0.3: Category 2 (H2)<br>Otherwise Category 1 (H1 )<br>Dry points are assigned Category 0<br><br><br>H1: Hydraulically suitable for parked or moving cars.<br>H2: Hydraulically suitable for parked or moving heavy vehicles and wading by able-bodied adults.<br>H3: Hydraulically suitable for light construction (e.g. Timber frame and brick veneer).<br>H4: Hydraulically suitable for heavy construction (e.g. steel frame and reinforced concrete).<br>H5: Generally unsuitable |

# Appendix D Regional Flooding

Figure Appendix D 1 Depth of Flooding during the 1% AEP Regional Storm Event




Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

# Appendix E Depth of Flooding Difference Post Construction of Access Road

Figure Appendix E 1 Afflux project site wide during the 1% AEP Storm event





Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure Appendix E 2 Velocity Difference project site wide during the 1% AEP Storm event




Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure Appendix E 3 Afflux project site wide during the 1% AEP Storm event




Disclaimer. This document has been prepared based on information provided by others as cited in the Notes section. Stantec has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. Stantec assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

# Appendix F Design Rainfall Depth and Site IFD

Appendix F Table 1 1% AEP 30minute rainfall Patterns

| 1% AEP, 90 Minute (1.5 Hour) Rainfall Patterns | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | Duration (minutes) | | 90 | | | Original Depth (mm) | 66.30 | | | |
| | | | | | | Climate Adjusted Depth (mm) | 66.30 | | Intensity (mm/h) | 44.20 |
| **Time** | **Depth (mm) for Pattern:** | | | | | | | | | |
| (minutes) | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| 0 | | | | | | | | | | |
| 5 | 2.82 | 4.79 | 2.96 | 1.72 | 6.68 | 5.68 | 2.19 | 3.45 | 1.28 | 2.43 |
| 10 | 5.66 | 2.51 | 5.14 | 2.86 | 3.73 | 14.22 | 2.65 | 3.45 | 5.54 | 4.12 |
| 15 | 8.33 | 1.14 | 7.57 | 2.19 | 4.16 | 5.64 | 1.47 | 4.61 | 4.63 | 3.56 |
| 20 | 7.23 | 1.37 | 9.02 | 2.25 | 2.78 | 7.04 | 0.86 | 2.88 | 3.95 | 1.31 |
| 25 | 6.76 | 4.55 | 5.52 | 6.24 | 3.14 | 5.34 | 1.37 | 3.46 | 0.69 | 2.43 |
| 30 | 3.77 | 6.84 | 3.95 | 9.64 | 8.08 | 2.77 | 4.00 | 4.04 | 0.27 | 1.50 |
| 35 | 5.81 | 8.66 | 3.27 | 5.68 | 6.16 | 1.23 | 5.84 | 4.04 | 1.49 | 3.18 |
| 40 | 3.45 | 6.84 | 2.18 | 9.47 | 2.13 | 0.21 | 4.16 | 2.31 | 4.89 | 2.06 |
| 45 | 2.67 | 2.73 | 0.67 | 2.52 | 2.13 | 0.06 | 3.38 | 2.88 | 1.44 | 0.75 |
| 50 | 3.61 | 3.19 | 0.62 | 5.53 | 5.26 | 0.06 | 3.98 | 4.04 | 0.25 | 0.75 |
| 55 | 4.40 | 5.01 | 1.44 | 5.53 | 3.20 | 0.50 | 6.29 | 5.77 | 0.25 | 0.75 |
| 60 | 2.35 | 3.19 | 3.74 | 3.10 | 4.83 | 1.06 | 5.73 | 4.61 | 6.29 | 0.93 |
| 65 | 1.88 | 3.19 | 4.55 | 2.23 | 3.21 | 1.17 | 6.84 | 5.19 | 7.58 | 0.56 |
| 70 | 2.20 | 4.55 | 3.80 | 2.23 | 3.24 | 3.60 | 5.04 | 4.04 | 2.83 | 7.86 |
| 75 | 1.73 | 3.65 | 3.26 | 1.61 | 2.99 | 3.60 | 2.39 | 3.46 | 4.52 | 11.05 |
| 80 | 1.41 | 2.05 | 3.74 | 1.19 | 2.68 | 3.60 | 4.69 | 3.75 | 3.53 | 9.74 |
| 85 | 0.63 | 0.68 | 2.29 | 1.45 | 0.48 | 6.44 | 3.30 | 1.44 | 10.26 | 7.31 |
| 90 | 1.57 | 1.37 | 2.57 | 0.84 | 1.43 | 4.08 | 2.11 | 2.88 | 6.64 | 5.99 |
| | | | | | | | | | | |
| Check | 66.30 | 66.30 | 66.30 | 66.30 | 66.30 | 66.30 | 66.30 | 66.30 | 66.30 | 66.30 |

Appendix F Table 2 Adopted 1% AEP 3 hour rainfall Pattern

| 1% AEP, 180 Minute (3 Hour) Rainfall Patterns | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | Duration (minutes) | | 180 | | | Original Depth (mm) | 79.50 | | | |
| | | | | | | Climate Adjusted Depth (mm) | 79.50 | | Intensity (mm/h) | 26.50 |
| **Time** | **Depth (mm) for Pattern:** | | | | | | | | | |
| (minutes) | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| 0 | | | | | | | | | | |
| 15 | 3.92 | 16.77 | 2.27 | 2.02 | 11.68 | 6.34 | 9.51 | 13.87 | 2.92 | 3.02 |
| 30 | 13.75 | 3.59 | 2.21 | 9.29 | 10.02 | 5.28 | 7.36 | 12.00 | 9.60 | 4.68 |
| 45 | 4.71 | 1.91 | 6.65 | 7.47 | 16.28 | 7.39 | 9.09 | 12.51 | 5.26 | 4.34 |
| 60 | 7.26 | 0.02 | 1.26 | 8.07 | 10.53 | 5.72 | 11.50 | 11.30 | 7.78 | 5.76 |
| 75 | 14.25 | 0.02 | 1.50 | 8.47 | 11.21 | 2.02 | 9.46 | 7.37 | 7.76 | 4.79 |
| 90 | 6.03 | 0.02 | 3.82 | 18.36 | 6.11 | 6.33 | 5.41 | 3.60 | 2.78 | 7.04 |
| 105 | 4.89 | 0.02 | 12.09 | 10.29 | 2.38 | 14.07 | 9.91 | 1.03 | 10.14 | 13.00 |
| 120 | 5.75 | 6.82 | 14.64 | 3.83 | 0.08 | 13.72 | 5.41 | 0.52 | 10.81 | 4.45 |
| 135 | 5.80 | 10.29 | 10.96 | 0.20 | 1.26 | 1.58 | 4.51 | 6.17 | 5.63 | 9.99 |
| 150 | 3.66 | 8.09 | 10.20 | 1.42 | 2.08 | 5.10 | 4.21 | 3.77 | 5.90 | 4.52 |
| 165 | 4.74 | 15.82 | 8.23 | 4.04 | 7.47 | 7.39 | 2.10 | 1.72 | 2.40 | 4.80 |
| 180 | 4.76 | 16.11 | 5.66 | 6.05 | 0.41 | 4.57 | 1.05 | 5.65 | 8.52 | 13.11 |
| | | | | | | | | | | |
| Check | 79.50 | 79.50 | 79.50 | 79.50 | 79.50 | 79.50 | 79.50 | 79.50 | 79.50 | 79.50 |
| Sum | | | | | | | | | | |

Appendix F Table 3 Adopted 1% AEP 4.5 hour rainfall Pattern

| 1% AEP, 270 Minute (4.5 Hour) Rainfall Patterns | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | Duration (minutes) | | 270 | | | Original Depth (mm) | 88.50 | | | |
| | | | | | | Climate Adjusted Depth (mm) | 88.50 | | Intensity (mm/h) | 19.67 |
| **Time** | **Depth (mm) for Pattern:** | | | | | | | | | |
| (minutes) | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| 0 | | | | | | | | | | |
| 15 | 5.51 | 1.50 | 4.88 | 1.65 | 18.30 | 11.55 | 0.05 | 6.88 | 2.54 | 2.14 |
| 30 | 1.33 | 1.78 | 8.87 | 2.82 | 14.18 | 13.56 | 0.05 | 8.83 | 10.02 | 6.50 |
| 45 | 3.09 | 5.66 | 16.39 | 3.11 | 3.91 | 8.17 | 8.19 | 3.30 | 4.73 | 1.73 |
| 60 | 4.03 | 5.24 | 2.51 | 3.46 | 8.97 | 2.79 | 13.44 | 6.80 | 3.31 | 13.70 |
| 75 | 4.52 | 6.48 | 2.18 | 3.28 | 1.50 | 5.58 | 7.20 | 1.42 | 6.37 | 6.05 |
| 90 | 11.30 | 3.00 | 3.03 | 4.24 | 2.96 | 4.19 | 17.29 | 2.08 | 5.58 | 2.52 |
| 105 | 8.82 | 7.13 | 7.13 | 2.66 | 0.61 | 6.38 | 7.68 | 4.06 | 3.61 | 0.36 |
| 120 | 3.58 | 10.31 | 4.71 | 4.12 | 0.00 | 7.18 | 4.81 | 5.89 | 4.04 | 0.58 |
| 135 | 2.35 | 11.63 | 5.57 | 3.82 | 0.23 | 4.19 | 0.48 | 6.96 | 3.01 | 0.09 |
| 150 | 4.55 | 5.33 | 3.94 | 5.06 | 0.00 | 2.99 | 0.70 | 6.50 | 2.93 | 0.03 |
| 165 | 1.51 | 4.36 | 1.50 | 4.22 | 0.00 | 2.59 | 0.26 | 5.61 | 7.09 | 2.14 |
| 180 | 6.48 | 4.04 | 5.96 | 6.19 | 5.15 | 3.19 | 0.96 | 6.02 | 15.90 | 5.43 |
| 195 | 2.48 | 7.85 | 7.65 | 11.43 | 7.41 | 2.19 | 3.36 | 6.55 | 6.93 | 3.81 |
| 210 | 0.68 | 4.48 | 0.93 | 3.91 | 11.05 | 1.80 | 9.12 | 6.60 | 1.78 | 10.82 |
| 225 | 0.45 | 4.90 | 4.85 | 8.79 | 9.12 | 2.59 | 1.92 | 2.87 | 0.91 | 9.80 |
| 240 | 13.20 | 2.42 | 4.24 | 3.98 | 1.12 | 3.39 | 0.96 | 2.60 | 0.73 | 13.97 |
| 255 | 10.75 | 1.33 | 2.42 | 4.22 | 1.49 | 2.99 | 7.20 | 2.51 | 0.72 | 8.30 |
| 270 | 3.86 | 1.06 | 1.76 | 11.53 | 2.50 | 3.19 | 4.81 | 3.01 | 8.29 | 0.51 |
| | | | | | | | | | | |
| Check Sum | 88.50 | 88.50 | 88.50 | 88.50 | 88.50 | 88.50 | 88.50 | 88.50 | 88.50 | 88.50 |

Appendix F Table 4 Gunnedah Site IFD Data

| | Annual Exceedance Probability (AEP) | | | | | | |
|---|---|---|---|---|---|---|---|
| Duration | 63.20% | 50% | 20% | 10% | 5% | 2% | 1% |
| 1 min | 104 | 118 | 163 | 194 | 225 | 268 | 302 |
| 2 min | 88.5 | 99.8 | 137 | 165 | 193 | 232 | 261 |
| 3 min | 81.9 | 92.5 | 127 | 152 | 178 | 213 | 240 |
| 4 min | 76.9 | 86.9 | 119 | 143 | 166 | 198 | 223 |
| 5 min | 72.6 | 82.1 | 113 | 135 | 157 | 187 | 210 |
| 10 min | 56.9 | 64.4 | 88.7 | 106 | 123 | 146 | 164 |
| 15 min | 47.1 | 53.3 | 73.5 | 87.7 | 102 | 121 | 137 |
| 20 min | 40.4 | 45.7 | 63.1 | 75.3 | 87.5 | 104 | 118 |
| 25 min | 35.5 | 40.2 | 55.4 | 66.2 | 77 | 91.9 | 104 |
| 30 min | 31.8 | 36 | 49.6 | 59.2 | 69 | 82.4 | 93.1 |
| 45 min | 24.5 | 27.7 | 38.1 | 45.6 | 53.1 | 63.5 | 71.8 |
| 1 hour | 20.2 | 22.8 | 31.3 | 37.4 | 43.6 | 52.2 | 59 |
| 1.5 hour | 15.3 | 17.2 | 23.6 | 28.1 | 32.7 | 39.1 | 44.2 |
| 2 hour | 12.5 | 14.1 | 19.2 | 22.8 | 26.6 | 31.7 | 35.8 |
| 3 hour | 9.42 | 10.6 | 14.4 | 17 | 19.8 | 23.5 | 26.5 |
| 4.5 hour | 7.11 | 7.97 | 10.8 | 12.8 | 14.7 | 17.5 | 19.7 |
| 6 hour | 5.83 | 6.54 | 8.81 | 10.4 | 12 | 14.2 | 16 |
| 9 hour | 4.41 | 4.95 | 6.66 | 7.85 | 9.05 | 10.7 | 12 |
| 12 hour | 3.62 | 4.06 | 5.47 | 6.45 | 7.43 | 8.78 | 9.86 |
| 18 hour | 2.73 | 3.06 | 4.14 | 4.9 | 5.66 | 6.71 | 7.55 |
| 24 hour | 2.22 | 2.5 | 3.4 | 4.03 | 4.67 | 5.56 | 6.28 |
| 30 hour | 1.89 | 2.13 | 2.9 | 3.46 | 4.02 | 4.81 | 5.45 |
| 36 hour | 1.65 | 1.86 | 2.55 | 3.05 | 3.55 | 4.27 | 4.86 |
| 48 hour | 1.33 | 1.5 | 2.07 | 2.48 | 2.91 | 3.53 | 4.04 |
| 72 hour | 0.96 | 1.09 | 1.52 | 1.83 | 2.17 | 2.66 | 3.06 |
| 96 hour | 0.757 | 0.859 | 1.2 | 1.46 | 1.73 | 2.13 | 2.47 |
| 120 hour | 0.627 | 0.712 | 0.998 | 1.21 | 1.43 | 1.77 | 2.05 |
| 144 hour | 0.537 | 0.61 | 0.854 | 1.03 | 1.22 | 1.49 | 1.73 |
| 168 hour | 0.471 | 0.535 | 0.746 | 0.897 | 1.05 | 1.28 | 1.49 |

**Sydney**
Level 4, 99 Walker Street,
NORTH SYDNEY, NSW 2060
Tel +61 2 9493 9700
Fax +61 2 9493 9799

Please visit **www.stantec.com** to learn more about how Stantec design with community in mind.

Stantec